

NFPA

72[®]

National Fire Alarm and Signaling Code[®]

2022



IMPORTANT NOTICES AND DISCLAIMERS CONCERNING NFPA® STANDARDS

NFPA® codes, standards, recommended practices, and guides (“NFPA Standards”), of which the document contained herein is one, are developed through a consensus standards development process approved by the American National Standards Institute. This process brings together volunteers representing varied viewpoints and interests to achieve consensus on fire and other safety issues. While the NFPA administers the process and establishes rules to promote fairness in the development of consensus, it does not independently test, evaluate, or verify the accuracy of any information or the soundness of any judgments contained in NFPA Standards.

The NFPA disclaims liability for any personal injury, property, or other damages of any nature whatsoever, whether special, indirect, consequential or compensatory, directly or indirectly resulting from the publication, use of, or reliance on NFPA Standards. The NFPA also makes no guaranty or warranty as to the accuracy or completeness of any information published herein.

In issuing and making NFPA Standards available, the NFPA is not undertaking to render professional or other services for or on behalf of any person or entity. Nor is the NFPA undertaking to perform any duty owed by any person or entity to someone else. Anyone using this document should rely on his or her own independent judgment or, as appropriate, seek the advice of a competent professional in determining the exercise of reasonable care in any given circumstances.

The NFPA has no power, nor does it undertake, to police or enforce compliance with the contents of NFPA Standards. Nor does the NFPA list, certify, test, or inspect products, designs, or installations for compliance with this document. Any certification or other statement of compliance with the requirements of this document shall not be attributable to the NFPA and is solely the responsibility of the certifier or maker of the statement.



ALERT: THIS STANDARD HAS BEEN MODIFIED BY A TIA OR ERRATA

Users of NFPA codes, standards, recommended practices, and guides (“NFPA Standards”) should be aware that NFPA Standards may be amended from time to time through the issuance of a Tentative Interim Amendment (TIA) or corrected by Errata. An official NFPA Standard at any point in time consists of the current edition of the document together with any TIAs and Errata then in effect.

To determine whether an NFPA Standard has been amended through the issuance of TIAs or corrected by Errata, go to www.nfpa.org/docinfo to choose from the list of NFPA Standards or use the search feature to select the NFPA Standard number (e.g., NFPA 13). The document information page provides up-to-date document-specific information as well as postings of all existing TIAs and Errata. It also includes the option to register for an “Alert” feature to receive an automatic email notification when new updates and other information are posted regarding the document.

ADDITIONAL IMPORTANT NOTICES AND DISCLAIMERS CONCERNING NFPA® STANDARDS

Updating of NFPA Standards

Users of NFPA codes, standards, recommended practices, and guides (“NFPA Standards”) should be aware that these documents may be superseded at any time by the issuance of a new edition, may be amended with the issuance of Tentative Interim Amendments (TIAs), or be corrected by Errata. It is intended that through regular revisions and amendments, participants in the NFPA standards development process consider the then-current and available information on incidents, materials, technologies, innovations, and methods as these develop over time and that NFPA Standards reflect this consideration. Therefore, any previous edition of this document no longer represents the current NFPA Standard on the subject matter addressed. NFPA encourages the use of the most current edition of any NFPA Standard [as it may be amended by TIA(s) or Errata] to take advantage of current experience and understanding. An official NFPA Standard at any point in time consists of the current edition of the document, including any issued TIAs and Errata then in effect.

To determine whether an NFPA Standard has been amended through the issuance of TIAs or corrected by Errata, visit the “Codes & Standards” section at www.nfpa.org.

Interpretations of NFPA Standards

A statement, written or oral, that is not processed in accordance with Section 6 of the Regulations Governing the Development of NFPA Standards shall not be considered the official position of NFPA or any of its Committees and shall not be considered to be, nor be relied upon as, a Formal Interpretation.

Patents

The NFPA does not take any position with respect to the validity of any patent rights referenced in, related to, or asserted in connection with an NFPA Standard. The users of NFPA Standards bear the sole responsibility for determining the validity of any such patent rights, as well as the risk of infringement of such rights, and the NFPA disclaims liability for the infringement of any patent resulting from the use of or reliance on NFPA Standards.

NFPA adheres to the policy of the American National Standards Institute (ANSI) regarding the inclusion of patents in American National Standards (“the ANSI Patent Policy”), and hereby gives the following notice pursuant to that policy:

NOTICE: The user’s attention is called to the possibility that compliance with an NFPA Standard may require use of an invention covered by patent rights. NFPA takes no position as to the validity of any such patent rights or as to whether such patent rights constitute or include essential patent claims under the ANSI Patent Policy. If, in connection with the ANSI Patent Policy, a patent holder has filed a statement of willingness to grant licenses under these rights on reasonable and nondiscriminatory terms and conditions to applicants desiring to obtain such a license, copies of such filed statements can be obtained, on request, from NFPA. For further information, contact the NFPA at the address listed below.

Law and Regulations

Users of NFPA Standards should consult applicable federal, state, and local laws and regulations. NFPA does not, by the publication of its codes, standards, recommended practices, and guides, intend to urge action that is not in compliance with applicable laws, and these documents may not be construed as doing so.

Copyrights

NFPA Standards are copyrighted. They are made available for a wide variety of both public and private uses. These include both use, by reference, in laws and regulations, and use in private self-regulation, standardization, and the promotion of safe practices and methods. By making these documents available for use and adoption by public authorities and private users, the NFPA does not waive any rights in copyright to these documents.

Use of NFPA Standards for regulatory purposes should be accomplished through adoption by reference. The term “adoption by reference” means the citing of title, edition, and publishing information only. Any deletions, additions, and changes desired by the adopting authority should be noted separately in the adopting instrument. In order to assist NFPA in following the uses made of its documents, adopting authorities are requested to notify the NFPA (Attention: Secretary, Standards Council) in writing of such use. For technical assistance and questions concerning adoption of NFPA Standards, contact NFPA at the address below.

For Further Information

All questions or other communications relating to NFPA Standards and all requests for information on NFPA procedures governing its codes and standards development process, including information on the procedures for requesting Formal Interpretations, for proposing Tentative Interim Amendments, and for proposing revisions to NFPA standards during regular revision cycles, should be sent to NFPA headquarters, addressed to the attention of the Secretary, Standards Council, NFPA, 1 Batterymarch Park, P.O. Box 9101, Quincy, MA 02269-9101; email: stds_admin@nfpa.org.

For more information about NFPA, visit the NFPA website at www.nfpa.org. All NFPA codes and standards can be viewed at no cost at www.nfpa.org/docinfo.

Copyright © 2021 National Fire Protection Association®. All Rights Reserved.

NFPA 72®

National Fire Alarm and Signaling Code®

2022 Edition

This edition of *NFPA 72, National Fire Alarm and Signaling Code*, was prepared by the Technical Committees on Emergency Communication Systems, Fundamentals of Fire Alarm and Signaling Systems, Single- and Multiple-Station Alarms and Household Signaling Systems, Initiating Devices for Fire Alarm and Signaling Systems, Notification Appliances for Fire Alarm and Signaling Systems, Protected Premises Fire Alarm and Signaling Systems, Public Emergency Reporting Systems, Supervising Station Fire Alarm and Signaling Systems, and Testing and Maintenance of Fire Alarm and Signaling Systems, released by the Correlating Committee on Signaling Systems for the Protection of Life and Property, and acted on by the NFPA membership during the 2021 NFPA Technical Meeting held June 14–July 2. It was issued by the Standards Council on August 26, 2021, with an effective date of September 15, 2021, and supersedes all previous editions.

This document has been amended by one or more Tentative Interim Amendments (TIAs) and/or Errata. See "Codes & Standards" at www.nfpa.org for more information.

This edition of *NFPA 72* was approved as an American National Standard on September 15, 2021.

Origin and Development of NFPA 72

The development of NFPA's signaling standards dates back to 1898 with the appointment of the Committee on Thermo-Electric Fire Alarms. The 1905 edition of NBFU 71A, *Rules and Requirements of the National Board of Fire Underwriters for the Construction, Installation, and Use of Signaling Systems Used for the Transmission of Signals Affecting the Fire Hazard as Recommended by the National Fire Protection Association*, and related documents dating back to 1903 were among the first of numerous signaling standards published in conjunction with the National Fire Protection Association. The descendants of these earlier standards were consolidated into the *National Fire Alarm Code, NFPA 72*.

The first edition of the *National Fire Alarm Code*, published in 1993, was a consolidation of the 1989 edition of NFPA 71, *Standard for the Installation, Maintenance, and Use of Signaling Systems for Central Station Service*; the 1990 edition of NFPA 72, *Standard for the Installation, Maintenance, and Use of Protective Signaling Systems*; the 1990 edition of NFPA 72E, *Standard on Automatic Fire Detectors*; the 1989 edition of NFPA 72G, *Guide for the Installation, Maintenance, and Use of Notification Appliances for Protective Signaling Systems*; the 1988 edition of NFPA 72H, *Guide for Testing Procedures for Local, Auxiliary, Remote Station, and Proprietary Protective Signaling Systems*; and the 1989 edition of NFPA 74, *Standard for the Installation, Maintenance, and Use of Household Fire Warning Equipment*. Many of the requirements of these standards were identical or very similar. The recommendations that were taken from the guides (NFPA 72G and NFPA 72H) were changed to mandatory requirements.

The 1996 edition of *NFPA 72* incorporated many changes of a technical nature. These changes related to the Americans with Disabilities Act, software testing, fire modeling, and communications.

The 1999 edition represented a major change in code content and organization. The chapters were arranged to facilitate user friendliness and provide a logical structure. A new chapter on public fire reporting was added, and many technical revisions were made. Annex B (formerly Appendix B) was streamlined to facilitate ease of use, many unenforceable terms were removed, and Chapter 3 was reorganized to facilitate a more logical approach.

The 2002 edition reflected an extensive editorial revision of the Code to comply with the latest edition of the *Manual of Style for NFPA Technical Committee Documents*. These revisions included the addition of three administrative chapters at the beginning of the Code: Administration, Referenced Publications, and Definitions. Eight technical chapters followed the administrative chapters in the same sequence as in the 1999 edition. Other editorial revisions included the breakout of paragraphs with multiple requirements into individually numbered paragraphs for each requirement, the minimization of use of exceptions, the use of consistent headings for sections and section subdivisions, and reorganization to limit paragraph numbering to six digits.

The 2002 edition contained a number of technical revisions throughout the Code, including the following:

- (1) A major revision of the power supply requirements
- (2) A new requirement addressing impairments to fire alarm systems
- (3) Additional requirements concerning the review and approval of performance-based detection system designs
- (4) Revision of the rules for system survivability from attack by fire
- (5) The introduction of rules for an alternate approach for audible signaling
- (6) The addition of requirements to address performance-based designs for visible signaling
- (7) The relocation of testing and maintenance requirements for single- and multiple-station alarms and household fire alarm systems to the testing and maintenance chapter
- (8) Revisions to re-establish the prescriptive rules for household fire-warning equipment from the 1996 edition of the Code

The 2007 edition contained several technical revisions including many to accommodate new technology and to take advantage of new research. Changes were made to better address the integration of mass notification systems and other systems with fire alarm systems. Revisions were also made in several areas of the Code for clarity and to enhance its usability.

Some of the more significant revisions in the 2007 edition addressed protection of fire alarm control units, personnel qualifications, heat detector response time, smoke detector spacing, smoke detection in ducts, detectors that use multiple sensing inputs, video image smoke and flame detection, synchronization of visible notification appliances, exit marking audible notification appliances, tactile notification appliances, different types of protected premises fire alarm systems, and in-building enhancement systems for fire fighter radio communications. The 2007 edition also included significant changes to the requirements for smoke alarms in residential applications, revisions to require the interconnection of smoke alarms for existing occupancies, revisions to require additional smoke alarms for larger dwelling units, and revisions to allow voice messages to be included as a part of the smoke alarm notification signal.

Revisions in the 2007 edition to enhance and clarify the Code included those that address suppression system inputs to the fire alarm system, emergency/voice alarm communications systems, fire alarm system interface with elevator systems, and the means to indicate central station service. In addition, a complete revision of the Record of Completion Form along with examples of filled-out forms were provided.

The 2007 edition also included the addition of two new annexes — one to provide guidance for the design of mass notification systems and one to replace previous annex material for the design of fire service interfaces with a separate industry standard.

The 2010 edition of the Code presented a major change in the scope and organization of the document. This was reflected in the new title, *National Fire Alarm and Signaling Code*. The broader scope of the Code included emergency communications systems in addition to the traditional scope of fire alarm systems. A new chapter on emergency communications systems (ECS) was added to provide requirements for a variety of systems used for communication of information in various emergency situations. The ECS chapter included new systems such as in-building mass notification systems, wide area mass notification systems, distributed recipient mass notifications systems, two-way radio communications enhancement systems, and area of refuge emergency communications systems. The ECS chapter also included two systems formerly in the chapter on protected premises fire alarm systems: (in-building fire) emergency voice/alarm communications systems and two-way in-building wired (telephone) emergency services communication systems.

Two other new chapters were added in the 2010 edition. The new chapter on circuits and pathways included requirements and information formerly from the chapters on fundamentals of fire alarm systems and from the chapter on protected premises fire alarm systems. This new chapter provided circuit and pathway performance (class) designations and pathway survivability level designations as well as general wiring requirements presented in a format that allowed use by any type of system covered in the Code. The new chapter on emergency control functions and interfaces included requirements and information formerly contained in the chapter of protected premises fire alarm systems. In this chapter the term *fire safety function* generally was replaced with the term *emergency control function* to reflect the potentially broader application beyond just fire alarm systems. This new chapter also included new provisions for first-responder-use elevators and elevators for occupant-controlled evacuation.

The 2010 edition was reorganized substantially to accommodate the new chapters in a logical order with reserved chapter numbers included to minimize the potential for further renumbering in the future. The overall organization included administrative chapters, support chapters, and system chapters as well as numerous annexes for usability.

Significant revisions were also made throughout the 2010 edition to reflect the broader application of the Code to emergency communication systems. These included revisions in the chapter on fundamentals to address power supply requirements, signal priorities, signal distinction and documentation requirements; revisions to the protected premises chapter to better accommodate non-fire alarm systems in combination systems; revisions to the supervising station chapter and public emergency reporting system chapter to allow their use for emergency communications systems; and revisions to the testing and maintenance chapter to incorporate requirements for the inspection, testing, and maintenance of mass notification systems and two-way radio communications enhancement systems.

In addition to the content of the new chapters, the 2010 edition included significant technical changes. These included new requirements for signaling to the deaf and hard of hearing, new requirements and guidance for the design, installation, and testing of voice communications systems to ensure voice intelligibility, and extensive revision of requirements for the installation of smoke detectors in both level and sloped joist and beam ceiling applications.

Revisions to the supervising station chapter in the 2010 edition included the retirement of four legacy transmission technologies no longer being installed: active multiplex transmission systems, McCulloh systems, directly connected noncoded systems, and private microwave systems. The subsection on Other Transmission Technologies was relocated to become the default subsection for supervising stations communications methods.

Modifications in the 2010 edition to the chapter on single- and multiple-station alarms and household fire alarms systems included new provisions to address the interconnection of smoke alarms using wireless technology, new provisions for signaling to those with hearing loss, and new requirements and guidance for the placement of smoke alarms and smoke detectors.

The 2010 edition included two new guidance annexes, Annex C on system performance and design and Annex D on speech intelligibility.

The 2013 edition of the Code was built on the organizational changes made in the 2010 edition. A new Chapter 7, Documentation, was added to improve the usability of the document and provided a central location for all the documentation requirements of the Code. In some cases, the documentation provisions were contained directly in the new chapter. In other cases, references were provided to the locations of documentation requirements contained in other chapters. As an example, the new chapter contained the minimum documentation requirements that applied to any system covered by the Code, while additional document requirements that might apply from other parts of the Code or from other governing laws, codes, or standards were listed with an appropriate reference. The Record of Completion and Record of Inspection, Testing, and Maintenance forms were included at the end of the chapter and were completely revised to be easier to use with a basic form for straightforward systems and supplemental forms for more complex systems.

Chapter 10, Fundamentals, was reorganized for the 2013 edition to provide a more user-friendly flow of requirements. In addition, requirements for circuit monitoring found in the previous edition of Chapter 10 were relocated to Chapter 12, Circuits and Pathways, a more logical location.

Extensive usability changes also were made in the inspection and testing tables of Chapter 14, Inspection, Testing, and Maintenance. The visual inspection table was updated, adding new inspection methods for each component along with the inspection frequency. The test methods and test frequency tables were combined into a single table so that the test method appeared along with the test frequency for each component. The component listings in both tables were reorganized and coordinated so that components and equipment were easier to find.

The 2013 edition of the Code also included many technical updates. Among those updates were changes in Chapter 10 requiring supervising station operators and fire alarm system service providers to report to the authority having jurisdiction certain conditions of system impairment. Requirements for inspection, testing, and service personnel qualifications were updated to better reflect the level of qualification needed for each type of activity.

Changes were also made in Chapter 18, Notification Appliances, requiring documentation of the locations that require audible notification appliances as well as documentation of the audibility levels that must be produced. Area of coverage requirements were added for visible notification appliances. Changes were made in Chapter 21, Emergency Control Function Interfaces, to address requirements for elevator recall when sprinklers are installed in elevator pits. The requirements for occupant evacuation elevators were completely revised to coordinate with changes made in ASME A17.1/B44, *Safety Code for Elevators and Escalators*. Changes were made in Chapter 24, Emergency Communications Systems, to address the use of microphones and of textual and graphical visible notification appliances for primary or supplemental notification, and to update the requirements for emergency command centers. Changes were made in Chapter 26, Supervising Station Alarm Systems, to address alarm signal verification, alarm signal content, and restoration of signals. Those changes were made in part to help emergency responders better manage issues related to unwanted alarms. In addition, new definitions for unwanted alarms were added to more precisely identify the sources of those alarms. Changes were also made to update the communications methods addressed in Chapter 26. Among them were changes to the supervision interval requirements for communications paths and changes to the types of transmission means that can be used for the second channel of a digital alarm communicator transmitter (DACT). Changes were made in Chapter 29, Single- and Multiple-Station Alarms and Household Fire Alarm Systems, to address the connection of sprinkler waterflow switches to multiple-station alarms and to add new requirements addressing the smoke alarm resistance to common nuisance sources.

The 2016 edition made many changes relative to documentation. Chapter 7 revised and added items to the minimum documentation, documentation for new emergency communications systems, and software documentation requirements; and addressed review of electronic documentation media formats. Requirements for documentation of qualifications for the system designer and personnel who program systems were more clearly addressed while providing for the allowance for system design trainees. New criteria were added for plans examiners and inspectors.

Perhaps the most significant changes to the Code pertained to wiring. The 2016 edition added Class N, which addressed Ethernet infrastructures for alarm and signaling systems, and pathway performance and installation criteria were provided. Class A and Class X pathway separation requirements were revised to address emergency control function interface devices controlled by the fire alarm system on those circuits. Level 2 and Level 3 pathway survivability requirements were revised, which provided flexibility of use and addressed other fire-resistive methods.

The 2016 edition of the Code added language relative to recalled equipment observed during inspection and testing and clarified the intent of periodic visual inspections relative to building or other changes that could affect the performance of the system. With the exception of reference and requirements pertaining to survivability, requirements for the design, installation, testing, and maintenance of in-building emergency radio communications enhancement systems were relocated to NFPA 1221, *Standard for the Installation, Maintenance, and Use of Emergency Services Communications Systems*.

Chapter 17 revised the requirements for total coverage and expanded its annex language to address general consideration for elevator shafts and enclosed stairways. The requirements for placement of smoke detectors used for door release were also revised to provide additional flexibility in locating detectors.

Chapter 24 was restructured, providing greater user friendliness while expanding the section on risk analysis. Emphasis was placed on the importance of effective message development. Annex G, Guidelines for Emergency Communication Strategies for Buildings and Campuses, based on the National Institute of Standards and Technology and Fire Protection Research Foundation research, was added to the 2016 edition.

Language was changed in Chapter 26 to require that when multiple communication paths are used for performance-based technologies or the two transmission means for a digital alarm communicator transmitter they be arranged to avoid a single point of failure.

Chapter 29 added requirements pertaining to remote resetting and silencing of a fire alarm control unit from other than the protected premises for a minimum of 4 minutes from the initial activation of the fire alarm signal. Smart phones and Internet access to almost any device made remote access to residential equipment possible. The ability to establish remote access to a fire alarm system was addressed. Also, a new requirement established that, where a communication or transmission means other than DACT is used, all equipment necessary to transmit an alarm signal must be provided with a minimum of 24 hours of secondary power capacity.

The 2019 edition reflected a number of changes. The requirements for fire service access elevators and occupant evacuation elevators (OEE) were completely revised to coordinate with changes made in ASME A17.1/CSA B44. The requirements for occupant evacuation operation (OEO) were revised extensively. Annex text was added for clarification, as was Figure A.21.6, Simplified Occupant Evacuation Operation (OEO) (elevator system interface with the building fire alarm system based on ASME A17.1, Section 2.27.11; and NFPA 72, Section 21.6). In addition to the requirements for area of refuge (area of rescue assistance), Chapter 24 was revised to include requirements for stairway communications systems, elevator landing communications systems, and occupant evacuation elevator lobby communications systems. A review was accomplished and revisions made to ensure alignment of NFPA 72 with the *Manual of Style for NFPA Technical Committee Documents*. These editorial revisions included the breakout of paragraphs with multiple requirements into individually numbered paragraphs for each requirement and the minimization of use of exceptions. For many years, when codes required visual (or visible) notification in addition to audible notification, strobe lights meeting the requirements of Chapter 18 were used. With newer LED products that can be used for fire alarm, the terms *strobe*, *light*, and *visible* were essentially changed to *visual notification appliance*. The terms *speaker* and *high power speaker array (HPSA)* were changed to *loudspeaker* and *high power loudspeaker array (HPLA)* for consistency.

Perhaps the most significant change to the Code pertained to carbon monoxide. In August 2015, the Standards Council voted to relocate material that is in NFPA 720, *Standard for the Installation of Carbon Monoxide (CO) Detection and Warning Equipment*, to various chapters of NFPA 72. These requirements were incorporated into Chapter 17 for carbon monoxide detectors; Chapter 14 for installation, testing, and maintenance; Chapter 29 for carbon monoxide alarms; and new Annex H. Chapter 29 was greatly expanded, and a significant amount of annex text was added for explanation. NFPA 720 was withdrawn as the requirements were moved to NFPA 72.

Chapter 14, Inspection, Testing, and Maintenance, was greatly modified to incorporate valve-regulated lead-acid (VRLA) batteries. The inspection and testing requirements were revised in Tables 14.3.1 and 14.4.3.2. This also expanded the annex language to address use and testing of these batteries. Several new terms were introduced and defined in Chapter 3.

The changes to the 2022 edition of the Code primarily focus on a number of key areas.

The 2022 edition provides a new Chapter 11 on Cybersecurity and Annex J, Guidelines for Cybersecurity. These provide criteria and guidance for protection of fire alarm and signaling systems from cyberattacks.

New Annex I introduces a green, yellow, red color-coded tagging program that can provide “at a glance” details of the apparent condition of the fire alarm and signaling system. Tagging is a common visual system in place in many states and jurisdictions.

Another area of focus pertains to pathway survivability, defined as “the ability of any conductor, optical fiber, radio carrier, or other means for transmitting system information to remain operational during fire conditions.” For many applications, pathway survivability is required to ensure that the conducting means between point A (e.g., fire alarm control unit) and point B (i.e., the notification area) is not compromised by a fire somewhere along that path such that notification is impaired. The Code defines four levels of survivability and establishes which level is required for a given application. One level might require interconnecting conductors, cables, or other physical pathways to be protected by metal raceways or metal armored cables, while another level might require a 2-hour fire-rated circuit integrity (CI) or fire-resistive cable, fire-rated cable system [electrical circuit protective system(s)], fire-rated enclosure or protected area, or other performance alternative. The 2022 edition of the Code provides a fifth option that reduces the 2-hour rated application criteria to 1-hour rated application criteria; Chapter 24 provides specific requirements that must be followed to enable use of the 1-hour application.

A major addition to the Code pertains to remote access to fire alarm and signaling systems for operations that could include resetting, silencing, or operation of emergency control functions. Remote access is permitted to be enabled remotely to perform diagnostics and update software.

Numerous changes to several areas within the Code affect detector technology and methods. Photoelectric and ionization detectors will likely be relegated to history and replaced with newer technology single- or multiple-criteria detectors. These detectors will lead to a paradigm shift in vocabulary and operation and will provide greater resistance to false triggers.

Correlating Committee on Signaling Systems for the Protection of Life and Property

Merton W. Bunker, Jr., Chair
Merton Bunker & Associates, LLC., VA [SE]

Richard J. Roux, Secretary
National Fire Protection Association, MA

Douglas M. Aiken, Lakes Region Mutual Fire Aid, NH [U]
Rep. IMSA Educational Foundation

Andrew G. Berezowski, Honeywell Inc., CT [M]
Rep. National Electrical Manufacturers Association

Art Black, Carmel Fire Protection Associates, CA [E]

Shane M. Clary, Bay Alarm Company, CA [IM]
Rep. The Monitoring Association

Raymond A. Grill, Arup, DC [SE]

Peter A. Larrimer, US Department of Veterans Affairs, PA [U]

James Ludden, Battlefield Fire Protection District, MO [E]
Rep. International Association of Fire Chiefs

Wayne D. Moore, JENSEN HUGHES, RI [SE]
Rep. JENSEN HUGHES

James M. Mundy, Jr., Asset Protection Associates, Ltd., NY [M]
Rep. Automatic Fire Alarm Association, Inc.

Lynn Nielson, City of Henderson, NV [E]

Thomas F. Norton, Norel Service Company, Inc., MA [IM]

Thomas J. Parrish, Telgian Corporation, MI [U]

Rodger Reiswig, Johnson Controls, FL [M]

Robert P. Schifiliti, R. P. Schifiliti Associates, Inc., MA [SE]

Lawrence J. Shudak, UL LLC, IL [RT]

Jeffery G. Van Keuren, Carrier, FL [M]

Alternates

Cristina Aragon Vandenbent, Telgian, GA [U]
(Alt. to Thomas J. Parrish)

Daniel Besson, Leland Township Fire & Rescue, MI [E]
(Alt. to James Ludden)

Louis Chavez, UL LLC, IL [RT]
(Alt. to Lawrence J. Shudak)

Daniel J. Gauvin, Johnson Controls, MA [M]
(Alt. to Rodger Reiswig)

Rick Heffernan, SDi, NJ [M]
(Alt. to James M. Mundy, Jr.)

Fred Leber, AML Encore Corporation, Canada [SE]
(Alt. to Raymond A. Grill)

David J. LeBlanc, JENSEN HUGHES, MA [SE]
(Alt. to Wayne D. Moore)

Maria B. Marks, Siemens Industry, Inc., MD [M]
(Alt. to Andrew G. Berezowski)

Martin C. Smith, ADT Commercial, MD [IM]
(Alt. to Shane M. Clary)

Morris L. Stoops, Carrier, KS [M]
(Alt. to Jeffery G. Van Keuren)

Nonvoting

Laurence J. Dallaire, Architect of the Capitol, DC [E]
Rep. TC on Initiating Devices for Fire Alarm Systems

Manuelita E. David, JENSEN HUGHES, CA [SE]
Rep. TC on Fundamentals of Fire Alarm Systems

William E. Koffel, Koffel Associates, Inc., MD [SE]
Rep. TC on Emergency Communication Systems

David O. Lowrey, City of Boulder Fire Rescue, CO [E]
Rep. TC on Notification Appliances for Fire Alarm Systems

Leo F. Martin, Jr., Martin Electrical Code Consultants, MA [SE]
Rep. TC on Public Fire Reporting Systems

Daniel J. O'Connor, JENSEN HUGHES, IL [SE]
Rep. TC on Supervising Station Fire Alarm Systems

Cory Ogle, Code Consultants, Inc., MO [SE]
Rep. TC on Household Fire Alarm Systems

Jack Poole, Poole Fire Protection, Inc., KS [SE]
Rep. TC on Protected Premises Fire Alarm Systems

Martin H. Reiss, Retired-JENSEN HUGHES, MA [SE]
(Member Emeritus)

Dean K. Wilson, JENSEN HUGHES, PA [O]
(Member Emeritus)

Richard J. Roux, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on the installation, performance, maintenance, testing, and use of signaling components and signaling systems for the protection of life, property and mission continuity.

Technical Committee on Emergency Communication Systems (SIG-ECS) (Chapter 24 and Annex G)

William E. Koffel, *Chair*
Koffel Associates, Inc., MD [SE]

Daniel P. Finnegan, *Secretary*
Siemens Smart Infrastructure, IL [M]
Rep. National Electrical Manufacturers Association

Oded Aron, Port Authority of New York & New Jersey, NY [U]
Thomas M. Chambers, Vector Security Inc., PA [IM]
Rep. The Monitoring Association
Joseph Dafin, US General Services Administration, DC [U]
Charles E. Hahl, GHD, NC [SE]
Raymond N. Hansen, US Department of the Air Force, FL [U]
Bryan Lawrence Hoskins, Oklahoma State University, OK [SE]
Waymon Jackson, University of Texas at Austin, TX [U]
Scott Lacey, Lacey Fire Protection Engineering, AR [SE]
Minfei M. Leng, TX RX Systems Inc., NY [M]
Ted Leventhal, Marktek Inc., PA [M]
Derek D. Mathews, UL LLC, IL [RT]
James Mongeau, Space Age Electronics, Inc., MA [M]
Rep. Automatic Fire Alarm Association, Inc.
Wayne D. Moore, JENSEN HUGHES, RI [SE]
Rep. JENSEN HUGHES

Michael Pallett, Telcor Inc., Canada [M]
Thomas J. Parrish, Telgian Corporation, MI [SE]
Joseph Ranaudo, AFA Protective Systems, Inc., NY [IM]
Rodger Reiswig, Johnson Controls, FL [M]
Jeffrey A. Scott, FP&C Consultants KC LLC, MO [SE]
Andrew J. Shear, Diversified Electronic Technologies, Inc./United Life Safety Systems, NC [IM]
James P. Simpson, Electrical Training Alliance, MN [L]
Rep. International Brotherhood of Electrical Workers
Morris L. Stoops, Carrier, KS [M]
Richard B. Wagoner, DFW International Airport, TX [U]
Andrew B. Woodward, Arup, MA [SE]
Jake Zlomie, Montana State University, MT [E]

Alternates

Cristina Aragon Vandenbent, Telgian, GA [SE]
(Alt. to Thomas J. Parrish)
Matthew Batbouta, GHD, VA [SE]
(Alt. to Charles E. Hahl)
Laura E. Doyle, US General Services Administration, DC [U]
(Alt. to Joseph Dafin)
Aleksandr Frenkel, Port Authority of New York & New Jersey, NJ [U]
(Alt. to Oded Aron)
Carlos Gomez, UL LLC, IL [RT]
(Alt. to Derek D. Mathews)
Raymond A. Grill, Arup, DC [SE]
(Alt. to Andrew B. Woodward)
David Madole, University of Texas at Austin, TX [U]
(Alt. to Waymon Jackson)

Denise L. Pappas, Valcom, Inc., VA [M]
(Alt. to Daniel P. Finnegan)
Larry D. Rietz, JENSEN HUGHES, CO [SE]
(Alt. to Wayne D. Moore)
Joseph Ripp, Interface Engineering, OR [M]
(Alt. to James Mongeau)
Jason D. Rolf, Minnesota Statewide JATC, MN [L]
(Alt. to James P. Simpson)
Peter D. Ryan, Johnson Controls, MA [M]
(Alt. to Rodger Reiswig)
Jim Surber, United States Air Force, OK [U]
(Alt. to Raymond N. Hansen)
Larry D. Watson, American Professional Services, Inc., OK [IM]
(Alt. to Thomas M. Chambers)

Richard J. Roux, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This committee shall have primary responsibility for documents on the risk analysis, design, application, installation, and performance of emergency communications systems and their components. Public emergency services communications systems covered by NFPA 1221 are outside the scope of this committee except where they interface with in-building bi-directional amplifiers and where trouble and supervisory signals are intended to be monitored by the building fire alarm system.

Technical Committee on Fundamentals of Fire Alarm and Signaling Systems (SIG-FUN)
(Chapters 1, 7, 10 and 11, and Annexes E and J)

Manuelita E. David, Chair
 JENSEN HUGHES, CA [SE]

Kimberly A. Gruner, Secretary
 Fike Corporation, MO [M]
 Rep. Fire Suppression Systems Association

Ed Vaillancourt, Secretary (Alternate)
 E & M International, Inc., NM [M]
 Rep. Fire Suppression Systems Association
 (Alt. to Kimberly A. Gruner)

Zainul Abedeen, WSP Middle East, United Arab Emirates [SE]
Laura Bennett-Hourigan, Walt Disney World Parks & Resorts, FL [U]
Andrew G. Berezowski, Honeywell Inc., CT [M]
 Rep. National Electrical Manufacturers Association
Brian Boeglin, Comcast Xfinity Home, CA [IM]
 Rep. Electronic Security Association
Robert A. Bonifas, Alarm Detection Systems, Inc., IL [IM]
 Rep. The Monitoring Association
Shane M. Clary, Bay Alarm Company, CA [IM]
Daniel G. Decker, Safety Systems, Inc., MI [IM]
James DiTaranto, Commercial Electrical Systems, FL [IM]
Tommy L. Farr, JATC of Southern Nevada, NV [L]
 Rep. International Brotherhood of Electrical Workers
David W. Frable, US General Services Administration, IL [U]
Daniel J. Gauvin, Johnson Controls, MA [M]
Kevin M. Green, Pyro-Comm Systems, Inc., CA [IM]
Paul Hail, Saudi Aramco, AK [U]
Jeffrey S. Hancock, Valero, TX [U]
Scott Jacobs, ISC Electronic Systems, Inc., CA [IM]
Bill Johns, P.E., Los Angeles City Fire Department, CA [E]
Jon Kapis, Coffman Engineers, CA [SE]
Walter J. Kessler, Jr., FM Approvals, MA [I]

Fred Leber, AML Encore Corporation, Canada [SE]
Richard A. Malady, Fire Fighter Sales & Service Company, PA [IM]
 Rep. National Association of Fire Equipment Distributors
Charlie McDaniel, AXA XL Risk Consultants/Global Asset Protection Services, LLC, WV [I]
 Rep. Global Asset Protection Services, LLC
Jack McNamara, Bosch Security Systems, NY [M]
Nicholas Moriarty, NV5/JBA Consulting Engineers, NV [SE]
Christopher Moseley, Power Design, FL [SE]
James M. Mundy, Jr., Asset Protection Associates, Ltd., NY [M]
 Rep. Automatic Fire Alarm Association, Inc.
Louis Nash, US Coast Guard, DC [E]
Thomas F. Norton, Norel Service Company, Inc., MA [IM]
 Rep. US Naval Historical Center
James R. Richardson, Lisle Woodridge Fire District, IL [E]
Allan Sanedrin, UL LLC, IL [RT]
Justin A. Schwartz, U.S. Army Corps Of Engineers, VA [U]
Jim Surber, United States Air Force, OK [U]
Emily Troyanski, Intertek Testing Services, NJ [RT]
Todd W. Warner, Brooks Equipment Company, Inc., MT [M]
 Rep. Fire Equipment Manufacturers' Association
Daniel R. Wilkerson, City Of Huntsville, AL [E]

Alternates

Bruce L. Abell, US Army Corps of Engineers, VA [U]
 (Alt. to Justin A. Schwartz)
Erinc Eslik, Intertek Testing Services, CT [RT]
 (Alt. to Emily Troyanski)
Timothy C. Fritz, UL LLC, IL [RT]
 (Alt. to Allan Sanedrin)
John Houlihan, Fire Command Systems, Inc., MA [M]
 (Alt. to James M. Mundy, Jr.)
Scott Kincaid, Brooks Equipment Company, NC [M]
 (Alt. to Todd W. Warner)
William E. Koffel, Koffel Associates, Inc., MD [SE]
 (Voting Alt.)
Maria B. Marks, Siemens Industry, Inc., MD [M]
 (Alt. to Andrew G. Berezowski)

John McCamish, NECA IBEW Electrical Training Center, OR [L]
 (Alt. to Tommy L. Farr)
Rich Neves, Pyro-Comm Systems, Inc., CA [IM]
 (Alt. to Kevin M. Green)
Timothy R. Oates, Johnson Controls, DE [M]
 (Alt. to Daniel J. Gauvin)
Sean Ramsey, US Coast Guard, DC [E]
 (Alt. to Louis Nash)
Rick D. Sheets, AT&T Digital Life, TX [IM]
 (Alt. to Brian Boeglin)
William F. Wayman, Jr., JENSEN HUGHES, MD [SE]
 (Alt. to Manuelita E. David)
Albert R. Wickham, Alarm Detection Systems Inc., IL [IM]
 (Alt. to Robert A. Bonifas)

Richard J. Roux, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on common system fundamentals for fire alarm and signaling systems, requirements for approvals, power supplies, equipment performance, system documentation, and compatibility.

Technical Committee on Single- and Multiple-Station Alarms and Household Signaling Systems (SIG-HOU) (Chapter 29 and Annex H)

Cory Ogle, Chair
Code Consultants, Inc., MO [SE]

Jeffrey P. McBride, Secretary (Alternate)
EBL Engineers, LLC, MD [SE]

George Bish, Amazon/Ring Protect Inc., NC [M]

David E. Christian, Gentex Corporation, MI [M]
Rep. Automatic Fire Alarm Association, Inc.

Thomas G. Cleary, National Institute of Standards & Technology (NIST), MD [RT]

Timothy K. Dedear, City of Farmers Branch Fire Department, TX [E]

Wendy B. Gifford, Consultant, IL [SE]

Daniel T. Gottuk, JENSEN HUGHES, MD [SE]

Greg L. Hansen, Vivint Inc., UT [M]

David E. Mills, UL LLC, IL [RT]

Kim R. Mniszewski, FX Engineering, Inc., IL [SE]

Paul Murphy, Borough Of Atlantic Highlands, NJ [E]

Jeffrey L. Okun, Nuko Security, Inc., LA [IM]

Stephen M. Olenick, Combustion Science & Engineering, Inc., MD [SE]

Timothy A. Rader, ADT Security Services, Inc., FL [M]

Larry Ratzlaff, Carrier/UTC/Kidde Safety, IL [M]

Eric Sacco, Siemens Building Technologies Division, NJ [M]
Rep. National Electrical Manufacturers Association

Robert A. Schmidt, Marriott International, Inc., MD [U]

Richard M. Simpson, Vector Security Inc., PA [IM]
Rep. The Monitoring Association

John D. Sorrell, Defenders Inc., TN [IM]
Rep. Electronic Security Association

Alternates

Oded Aron, Port Authority of New York & New Jersey, NY [U]
(Voting Alt.)

Brian Cohen, Marriott, MD [U]
(Alt. to Robert A. Schmidt)

Gil Lind Hays, ADT Security Services, Inc., FL [M]
(Alt. to Timothy A. Rader)

Rick Heffernan, SDi, NJ [M]
(Alt. to Eric Sacco)

Nasir Hussain, Combustion Science & Engineering, Inc., MD [SE]
(Alt. to Stephen M. Olenick)

Paul T. Kahle, Code Consultants, Inc., MO [SE]
(Alt. to Cory Ogle)

Thomas H. Miller, Hansen Engineering Services, IL [SE]
(Alt. to Kim R. Mniszewski)

Keith Mirra, Vector Security Inc., MD [IM]
(Alt. to Richard M. Simpson)

Ken Mott, Carrier/UTC/Kidde Safety, CO [M]
(Alt. to Larry Ratzlaff)

John L. Parssinen, UL LLC, IL [RT]
(Alt. to David E. Mills)

Roy Pollack, Comcast Xfinity Home, FL [IM]
(Alt. to John D. Sorrell)

Richard Jay Roberts, Honeywell Fire Safety, IL [M]
Rep. Automatic Fire Alarm Association, Inc.
(Alt. to David E. Christian)

Jason A. Sutula, JENSEN HUGHES, MD [SE]
(Alt. to Daniel T. Gottuk)

Steven Wardle, Vivint Inc., UT [M]
(Alt. to Greg L. Hansen)

Nonvoting

Arthur S. Lee, US Consumer Product Safety Commission, MD [C]
Rep. US Consumer Product Safety Commission (CPSC)

Maurice M. Pilette, Mechanical Designs Ltd., MA [SE]
Rep. TC on Residential Sprinkler Systems

Richard J. Roux, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on the performance, installation, operation, inspection, testing, maintenance, and use of single- and multiple-station alarms and household signaling systems.

Technical Committee on Initiating Devices for Fire Alarm and Signaling Systems (SIG-IDS) (Chapter 17 and Annex B)

Laurence J. Dallaire, Chair
Architect of the Capitol, DC [E]

Wayne J. Aho, Jr., Siemens, Industry Inc., NJ [M]
John M. Cholin, J. M. Cholin Consultants Inc., NJ [SE]
Donald Wayne Duplechian, Wilson Fire Equipment, TX [IM]
Scott A. Frazer, Performance Design Technologies, TN [SE]
James W. Gaut, Marriott Vacations Worldwide, FL [U]
Jim Goggin, Protectowire Company, Inc., MA [M]
Scott M. Golly, JENSEN HUGHES, MD [SE]
Todd Gustafson, Mircom Group Of Companies, IL [M]
 Rep. Automatic Fire Alarm Association, Inc.
Marty Heller, Shambaugh and Son, IN [M]
 Rep. National Fire Sprinkler Association
Noel Hernberger, Electrical JATC for Soouthern Nevada, NV [L]
 Rep. International Brotherhood of Electrical Workers
Mark Hopkins, TerpConsulting, MD [SE]
Scott R. Lang, Honeywell International, IL [M]
Norbert W. Makowka, National Association of Fire Equipment Distributors, IL [IM]
 Rep. National Association of Fire Equipment Distributors
Larry W. Mann, Central Station, Inc., AL [IM]
 Rep. Electronic Security Association

Chris Marrion, Marrion Fire & Risk Consulting PE, LLC, NY [SE]
Justin D. Merrick, S&S Sprinkler Company, LLC, AL [IM]
Samuel M. Miller, BP, TX [U]
Ovid E. Morphew, Jr., Design/Systems Group, TX [IM]
 Rep. National Independent Fire Alarm Distributors Assn.
James W. Mottorn, II, Bosch Security Systems, NY [M]
Abhay Nadgir, Carrier/Kidde-Fenwal, Inc., MA [M]
 Rep. Fire Suppression Systems Association
Lynn Nielson, City of Henderson, NV [E]
John L. Parssinen, UL LLC, IL [RT]
Samuel Rokowski, Reedy Creek Improvement District, FL [E]
John R. Schertel, Jr., Apollo America Inc., MI [M]
Kenneth R. Schneider, UA - ITF, MO [L]
 Rep. United Assn. of Journeymen & Apprentices of the Plumbing & Pipe Fitting Industry
Michael D. Sides, Global Asset Protection Services, LLC, FL [I]
Mark Swerdin, Zurich Services Corporation, NY [I]
David Waite, FM Approvals, MA [I]
Jason E. Webb, Potter Electric Signal Company, MO [M]

Alternates

Mark E. Agar, Fire Equipment Company Inc., MI [IM]
 (Alt. to Norbert W. Makowka)
Scott Bailey, Koorsen Fire & Security, IN [M]
 (Alt. to Abhay Nadgir)
Charles Berra, Sprinkler Fitters LU 268 JAC, MO [L]
 (Alt. to Kenneth R. Schneider)
Cecil Bilbo, Jr., Academy of Fire Sprinkler Technology, Inc., IL [M]
 (Alt. to Marty Heller)
Charles E. Brockett, AXA XL Risk Consultancy/ Global Asset Protection Services, LLC, TX [I]
 (Alt. to Michael D. Sides)
Tommy L. Farr, JATC of Southern Nevada, NV [L]
 (Alt. to Noel Hernberger)
Michael A. Henke, Potter Electric Signal Company, MO [M]
 (Alt. to Jason E. Webb)
Robert Kasiski, FM Global, RI [I]
 (Alt. to David Waite)

Henry J. Kozlowski, Zurich Services Corporation, RI [I]
 (Alt. to Mark Swerdin)
Jack McNamara, Bosch Security Systems, NY [M]
 (Alt. to James W. Mottorn, II)
Grady Medcalf, Spectrum Security, LLC., CO [IM]
 (Alt. to Larry W. Mann)
David E. Mills, UL LLC, IL [RT]
 (Alt. to John L. Parssinen)
David M. Nelson, Volunteer Technology Systems, TN [IM]
 (Alt. to Ovid E. Morphew, Jr.)
Brian E. Swanick, Siemens Industry, Inc., NJ [M]
 (Alt. to Wayne J. Aho, Jr.)
Jerry Trotter, City of Henderson, NV [E]
 (Alt. to Lynn Nielson)

Richard J. Roux, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on the installation and operation of initiating devices for fire alarm and signaling systems.

Technical Committee on Notification Appliances for Fire Alarm and Signaling Systems (SIG-NAS) (Chapter 18 and Annex D)

David O. Lowrey, Chair
City of Boulder Fire Rescue, CO [E]

Cory Blair, Genesis Building Systems, OH [IM]

Jan Braam, Carrier, FL [M]
Rep. Carrier/UTC

Matthew Buehrer, Buehrer Alarm Systems Consulting LLC, AZ [IM]
Rep. Electronic Security Association

David Dressler, Minnesota Statewide Limited Energy JATC, MN [L]
Rep. International Brotherhood of Electrical Workers

Michael L. Edwards, US Architect of the Capitol, DC [U]

Raymond A. Grill, Arup, DC [SE]

Daniel M. Grosch, UL LLC, IL [RT]

Douglas Hoeferle, Honeywell Fire Safety, IL [M]
Rep. Automatic Fire Alarm Association, Inc.

Paul Jennison, Forsyth County Georgia, GA [U]

Doug Kline, Nowak Supply Fire Systems, IN [M]
Rep. Fire Suppression Systems Association

Neal W. Krantz, Sr., Krantz Systems & Associates, LLC, MI [IM]
Rep. NFPA Industrial Fire Protection Section

Steven P. Lewis, RFI Enterprises, CA [IM]

David Madole, University of Texas at Austin, TX [U]

Bob D. Morgan, Fort Worth Fire Department, TX [E]

David Newhouse, Gentex Corporation, MI [M]
Rep. National Electrical Manufacturers Association

Isaac I. Papier, Papier Consulting Group LLC, IL [SE]

Maurice M. Pilette, Mechanical Designs Ltd., MA [SE]

Andrew W. Poole, Poole Fire Protection, Inc., KS [SE]

Robert P. Schifiliti, R. P. Schifiliti Associates, Inc., MA [SE]

Daniel L. Seibel, Wolverine Fire Protection Company, MI [IM]

Paul R. Strelecki, Siemens Building Technologies, Inc., NJ [M]

John R. Swanson, Minnesota State Fire Marshal Division, MN [E]

Alternates

Robert F. Accosta, Jr., Arup, NY [SE]
(Alt. to Raymond A. Grill)

Maxwell French, Code Red Consultants, MA [SE]
(Alt. to Maurice M. Pilette)

Mark C. Hamilton, Siemens, Inc., NJ [M]
(Alt. to Paul R. Strelecki)

Michael Sebastian Hamrah, RFI Enterprises, CA [IM]
(Alt. to Steven P. Lewis)

Neal W. Krantz, Jr., Krantz Systems & Associates, LLC., MI [IM]
(Alt. Neal W. Krantz, Sr.)

James Mongeau, Space Age Electronics, Inc., MA [M]
(Alt. to Douglas Hoeferle)

Richard J. Roux, NFPA Staff Liaison

Leon Newsome, Eaton Corporation, FL [M]
(Alt. to David Newhouse)

Warren E. Olsen, Fire Safety Consultants, Inc., IL [E]
(Voting Alt.)

Scott E. Panowitz, BFPE International, MD [M]
(Alt. to Doug Kline)

Jack Poole, Poole Fire Protection, Inc., KS [SE]
(Alt. to Andrew W. Poole)

Brian Robertson, Comcast, FL [IM]
(Alt. to Matthew Buehrer)

Morris L. Stoops, Carrier, KS [M]
(Alt. to Jan Braam)

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on the installation and operation of notification appliances for fire alarm and signaling systems.

Technical Committee on Protected Premises Fire Alarm and Signaling Systems (SIG-PRO)
(Chapters 12, 21, and 23 and Annex C)

Jack Poole, Chair
 Poole Fire Protection, Inc., KS [SE]

Leonard Belliveau, Jr., JENSEN HUGHES, MA [SE]
 Rep. JENSEN HUGHES
Robert Bourke, Wayne Alarm Systems, MA [IM]
 Rep. The Monitoring Association
Merton W. Bunker, Jr., Merton Bunker & Associates, LLC., VA [SE]
Robert Cole, Intertek Testing Services, GA [RT]
 Rep. Intertek Testing Services
David Correia, Honeywell International, CT [M]
 Rep. National Electrical Manufacturers Association
Paul F. Crowley, FM Approvals, MA [I]
Laura E. Doyle, US General Services Administration, DC [U]
Scott D. Harris, AFA Protective Systems, Inc., NY [IM]
William K. Hopple, Hopple & Company, CA [IM]
Daniel J. Horon, CADgraphics, Incorporated, FL [M]
Vic Humm, Vic Humm & Associates, TN [SE]
Brian Jarvis, US Department of Defense, AE [U]
Paul T. Kahle, Code Consultants, Inc., MO [SE]

Peter Leszczak, US Department of Veterans Affairs, CT [U]
Gregg Lupaczky, Johnson Controls, MA [M]
Scott T. Martorano, The Viking Corporation, MI [M]
 Rep. National Fire Sprinkler Association
Jebediah J. Novak, Cedar Rapids Electrical JATC, IA [L]
 Rep. International Brotherhood of Electrical Workers
Christopher Russell, Security Solutions NW, WA [IM]
 Rep. Electronic Security Association
Frank Savino, United Fire Protection Corporation, NJ [M]
 Rep. Fire Suppression Systems Association
Lawrence J. Shudak, UL LLC, IL [RT]
Donald Struck, Siemens Fire Safety, NJ [M]
Jeffery G. Van Keuren, Carrier, FL [M]
 Rep. Automatic Fire Alarm Association, Inc.
Sagiv Weiss-Ishai, San Francisco Fire Department, CA [E]
Carl F. Willms, Fire Safety Consultants, Inc., NJ [SE]
Brian Woodward, Fire Safety Engineers Inc., NV [SE]

Alternates

Vincent Baroncini, Siemens, Inc., NJ [M]
 (Alt. to Donald Struck)
Donald C. Birchler, FP&C Consultants KC, LLC., MO [SE]
 (Alt. to Vic Humm)
Martin Chiarizio, Johnson Controls, MA [M]
 (Alt. to Gregg Lupaczky)
Joseph Dafin, US General Services Administration, DC [U]
 (Alt. to Laura E. Doyle)
Joshua W. Elvove, Self, CO [SE]
 (Alt. to Carl F. Willms)
Dwayne Griffith, Walmart Security Services, AR [IM]
 (Alt. to Robert Bourke)
Jacob P. Hemke, Code Consultants, Inc., MO [SE]
 (Alt. to Paul T. Kahle)
Theodore Ivers, UL LLC, NY [RT]
 (Alt. to Lawrence J. Shudak)
Walter J. Kessler, Jr., FM Approvals, MA [I]
 (Alt. to Paul F. Crowley)

Tim Knisely, Automatic Fire Alarm Association, Inc. (AFAA), PA [M]
 (Alt. to Jeffery G. Van Keuren)
Mark LaBua, AFA Protective Systems Inc., NY [IM]
 (Alt. to Scott D. Harris)
Peter A. Larrimer, US Department of Veterans Affairs, PA [U]
 (Alt. to Peter Leszczak)
Andre Lickefett, Minimax GmbH & Co. KG, Germany [M]
 (Alt. to Scott T. Martorano)
Todd Marc Pearson, Jensen Hughes Inc., MA [SE]
 (Alt. to Leonard Belliveau, Jr.)
Christian Pierson, US Department of State, MD [U]
 (Alt. to Brian Jarvis)
Lou Richard, Comcast, TN [IM]
 (Alt. to Christopher Russell)
Sean P. Titus, Fike Corporation, MO [M]
 (Alt. to Frank Savino)

Richard J. Roux, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on the installation and operation of protected premises fire alarm and signaling systems, including their interconnection with initiating devices, notification appliances, and other related building control equipment, within the protected premises.

Technical Committee on Public Emergency Reporting Systems (SIG-PRS) (Chapter 27)

Leo F. Martin, Jr., Chair

Martin Electrical Code Consultants, MA [SE]

Douglas M. Aiken, Lakes Region Mutual Fire Aid, NH [E]
Anthony W. Cole, Wal-Mart Stores, Inc., CA [U]
Michael Scott Custer, Fort Detrick Fire Department, MD [E]
Daniel R. Dinwiddie, L W Bills Company, MA [M]
Romeo G. Dupuis, Manchester VA Hospital, NH [U]
Donald Gottfried, New York City Department of Buildings, NY [E]
Samuel Iannucci, Chubb Group of Insurance Companies, PA [I]
Brian Patrick Kirtley, Comcast Xfinity Home, TX [IM]
 Rep. Electronic Security Association
Jeffrey G. Knight, City of Newton Fire Department, MA [U]
 Rep. International Municipal Signal Association

Robert E. Lapham, Signal Communications Corporation, MA [M]
Gregory D. Lapin, Digital Design Laboratories, IL [SE]
Robert Malanga, Fire and Risk Engineering, NJ [SE]
 Rep. Fairmount Fire Company No. 1
Max McLeod, Siemens Industry, Inc., AL [M]
Robert E. Myers, MC Dean, VA [IM]
Isa Y. Saah, GHD, VA [SE]
Deborah L. Shaner, Shaner Life Safety, CO [SE]
Stephen Smith, Advanced Signal Corporation, MA [IM]
Thomas R. Waldron, Coffman Engineers, CA [SE]
Christopher Willms, Sea Girt Fire Company #1, NJ [E]

Alternates

Robert J. Allen, R. B. Allen Company, Inc., NH [IM]
 (Voting Alt.)
Dwayne Griffith, Walmart Security Services, AR [U]
 (Alt. to Anthony W. Cole)
Charles E. Hahl, GHD, NC [SE]
 (Alt. to Isa Y. Saah)
Hans Kristensen, Woodstock Fire/Rescue Department, IL [U]
 (Alt. to Jeffrey G. Knight)
Richard J. Roux, NFPA Staff Liaison

Rodger Reiswig, Johnson Controls, FL [IM]
 (Alt. to Brian Patrick Kirtley)
Leo J. Watts, Signal Communications Corporation, MA [M]
 (Alt. to Robert E. Lapham)
Michael S. White, Siemens Building Technologies, NC [M]
 (Alt. to Max McLeod)

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on the proper configuration, performance, installation, and operation of public emergency alarm reporting systems and auxiliary alarm systems. The Committee scope shall include systems that use a communication infrastructure that is publicly owned, operated, and controlled. Reporting of alarms by voice over the public switched telephone network utilizing the Universal Emergency Number 9-1-1, or any other telephone number that can be dialed, is outside the scope of this committee.

Technical Committee on Supervising Station Fire Alarm and Signaling Systems (SIG-SSS) (Chapter 26)

Daniel J. O'Connor, *Chair*
JENSEN HUGHES, IL [SE]

Raymond E. Bigelow, Natick, MA [U]
Rep. International Municipal Signal Association
Art Black, Carmel Fire Protection Associates, CA [E]
David A. Blanken, Keltron Corporation, MA [M]
Robert F. Buckley, Signal Communications Corporation, MA [M]
Lawrence E. Coveny, CPSI Fire And Security (Cross Point Sales Inc.), IL [IM]
Christopher Creamer, DynaFire, FL [IM]
James S. Crews, Allianz, GA [I]
Robert Deardorff, FM Approvals, MA [I]
Lee Dube, AES Corporation, MA [M]
Jason Dupuis, Cintas Fire Protection F19, CA [M]
Rep. Automatic Fire Alarm Association, Inc.
William J. (Jody) Dwyer, Germantown Fire Department, TN [E]
Donald Fess, Harvard University, MA [U]
Joseph (Jay) Hauhn, Hauhn and Associates, LLC, MD [IM]
Rep. The Monitoring Association
Richard G. Kluge, Ericsson, NJ [U]
Rep. Alliance for Telecommunications Industry Solutions

Scott M. May, Bosch Security Systems, NY [M]
Rep. National Electrical Manufacturers Association
Matthew J. Mertens, North Shore Fire Department, WI [E]
Scott Newman, Walgreens, IL [U]
Warren E. Olsen, Fire Safety Consultants, Inc., IL [E]
Rep. Illinois Fire Inspectors Association
Donald C. Pannell, City of Memphis, TN [E]
Roy Pollack, Comcast Xfinity Home, FL [U]
Rep. Electronic Security Association
Richard Jay Roberts, Honeywell Fire Safety, IL [M]
Steven A. Schmit, UL LLC, IL [RT]
Rep. UL LLC
Glenn Schroeder, NetOne Inc., NC [IM]
Sean P. Titus, Fike Corporation, MO [M]
Rep. Fire Suppression Systems Association
Daniel S. Vandergriff, Telgian Corporation, GA [U]
Rep. The Home Depot
Iman Yavari, Crosslinx Transit Solution, Canada [SE]

Alternates

Shane M. Clary, Bay Alarm Company, CA [M]
(Alt. to Jason Dupuis)
Pamela DeMeo, North Collier Fire, FL [E]
(Alt. to William J. (Jody) Dwyer)
Martin J. Farraher, Siemens Industry, Inc., IL [M]
(Alt. to Sean P. Titus)
Scott D. Henderson, Allianz, MA [I]
(Alt. to James S. Crews)
Charles Mason, JENSEN HUGHES, RI [SE]
(Alt. to Daniel J. O'Connor)
Anthony Mucci, Johnson Controls, FL [IM]
(Alt. to Joseph (Jay) Hauhn)
Paul J. Olson, UL LLC, MN [RT]
(Alt. to Steven A. Schmit)

Thomas J. Parrish, Telgian Corporation, MI [U]
(Alt. to Daniel S. Vandergriff)
Steven P. Sargent, Keltron Corporation, MA [M]
(Alt. to David A. Blanken)
Randy H. Schubert, Ericsson, NJ [U]
(Alt. to Richard G. Kluge)
Michael Sherman, AES Corporation, MA [M]
(Alt. to Lee Dube)
Michael G. Slossar, [U], AT&T Digital Life, NJ [U]
(Alt. to Roy Pollack)
Deane E. Walker, Grayslake Fire Protection District, IL [E]
(Alt. to Warren E. Olsen)
Leo J. Watts, Signal Communications Corporation, MA [M]
(Alt. to Robert F. Buckley)

Richard J. Roux, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on the installation and operation of equipment for the transmission and receipt of signals from a protected premises to a supervising station, including the supervising station facilities.

Technical Committee on Testing and Maintenance of Fire Alarm and Signaling Systems (SIG-TMS) (Chapter 14 and Annexes F and I)

Frank L. Van Overmeiren, Chair
Fire Protection & Code Consultants, LLC, IN [SE]

Timothy E. Adams, American Society for Healthcare Engineering, IN [U]

John CC Biggs, Intrepid, CA [IM]

Rep. California Automatic Fire Alarm Association Inc.

Anthony Bloodworth, Siemens Industries, Inc., IL [M]

Charles E. Brockett, AXA XL Risk Consultancy/ Global Asset Protection Services, LLC, TX [I]

Louis Chavez, UL LLC, IL [RT]

Franklin Chenoweth, Fireline Corporation, MD [M]

Rep. Fire Suppression Systems Association

Scott D. Corrin, C T Services, CA [SE]

Rick Heffernan, SDi, NJ [M]

Rep. National Electrical Manufacturers Association

Herbert B. Hurst, Jr., Savannah River Nuclear Solutions, LLC, SC [U]

John Kelly, Washington DC Fire & EMS Department, MD [E]

Robert H. Kelly, Fire Defense Equipment Company, Inc., MI [IM]

J David Kerr, Melissa Fire Department, TX [E]

E. J. Kleintop, Johnson Controls, PA [M]

Peter A. Larrimer, US Department of Veterans Affairs, PA [U]

James R. Lugar, JENSEN HUGHES, MD [SE]

Grady Medcalf, Spectrum Security, LLC, CO [IM]

Rep. Electronic Security Association

James Murphy, Vector Security Inc., PA [IM]

Rep. The Monitoring Association

Top Myers, Myers Risk Services, Inc., FL [M]

Rep. National Fire Sprinkler Association

Katherine A. Pothier, Fisher Engineering, Inc., GA [SE]

Christopher Rawson, International Brotherhood of Electrical Workers- Technical Institute (IBEW), IL [L]

Rep. International Brotherhood of Electrical Workers

Joe Scibetta, BuildingReports, GA [M]

George E. Seymour, Montgomery, TX [IM]

Rep. National Association of Fire Equipment Distributors

Derek Shackley, Pacific Auxiliary Fire Alarm, CA [M]

Rep. Automatic Fire Alarm Association, Inc.

Michael J. Slattery, AFA Protective Systems, Inc., MA [IM]

Timothy M. Soverino, Nantucket, MA [U]

Rep. International Municipal Signal Association

Charles K. Stormer, US General Services Administration, IL [U]

Rep. US General Services Administration

Alternates

Scott Bailey, Koorsen Fire & Security, IN [M]

(Alt. to Franklin Chenoweth)

Joshua Brackett, Baptist Health, AR [U]

(Alt. to Timothy E. Adams)

Scott D. Carlson, Fire Defense Equipment Company, Inc., MI [IM]

(Alt. to Robert H. Kelly)

Shane Courbier, Gentex Corporation, MI [M]

(Alt. to Rick Heffernan)

Charles Harkness, Telgian, NV [M]

(Alt. to Daniel Morrin, Jr.)

Vic Humm, Vic Humm & Associates, TN [SE]

(Alt. to Frank L. Van Overmeiren)

Bill Isemann, Guardian Fire Protection Services LLC, MD [IM]

(Alt. to George E. Seymour)

Matthew Jackson, AFA Protective Systems Inc., NJ [IM]

(Alt. to Michael J. Slattery)

David E. Kipley, JENSEN HUGHES, IL [SE]

(Alt. to James R. Lugar)

Brian Patrick Kirtley, Comcast Xfinity Home, TX [IM]

(Alt. to Grady Medcalf)

Ariana Kistner, City of Rockwall Fire Department, TX [E]

(Voting Alt.)

Peter Leszczak, US Department of Veterans Affairs, CT [U]

(Alt. to Peter A. Larrimer)

Troy O'Neal, Siemens, TX [M]

(Alt. to Anthony Bloodworth)

Vincent Powers, National Fire Sprinkler Association (NFSA), MD [M]

(Alt. to Top Myers)

Thomas Presnak, UL LLC, IL [RT]

(Alt. to Louis Chavez)

Steven Crieg Schwartz, Consolidated Fire Protection, CA [IM]

(Alt. to John CC Biggs)

Michael D. Sides, Global Asset Protection Services, LLC, FL [I]

(Alt. to Charles E. Brockett)

Je Weon Sung, U.S. General Services Administration, WA [U]

(Alt. to Charles K. Stormer)

Terry L. Victor, Johnson Controls, MD [M]

(Alt. to E. J. Kleintop)

Richard J. Roux, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents and requirements for the inspection, testing, and maintenance of fire alarm and signaling systems and associated components, for both new and existing systems. This Committee shall

not have responsibility for inspection, testing, and maintenance of single- and multiple-station alarms and household signaling systems.

Contents

Chapter 1 Administration	72- 20	10.21 Impairments.	72- 83
1.1 Scope.	72- 20	10.22 Unwanted Alarms.	72- 83
1.2 Purpose.	72- 20	Chapter 11 Cybersecurity	72- 83
1.3 Application.	72- 20	11.1 Cybersecurity.	72- 83
1.4 Retroactivity.	72- 20	Chapter 12 Circuits and Pathways	72- 83
1.5 Equivalency.	72- 21	12.1 Application.	72- 83
1.6 Units and Formulas.	72- 21	12.2 General.	72- 83
1.7 Code Adoption Requirements.	72- 21	12.3 Pathway Class Designations.	72- 84
Chapter 2 Referenced Publications	72- 21	12.4 Pathway Survivability.	72- 85
2.1 General.	72- 21	12.5 Shared Pathway Designations.	72- 85
2.2 NFPA Publications.	72- 21	12.6 Monitoring Integrity and Circuit Performance of Installation Conductors and Other Signaling Channels.	72- 85
2.3 Other Publications.	72- 21	12.7 Nomenclature.	72- 86
2.4 References for Extracts in Mandatory Sections.	72- 22	Chapter 13 Reserved	72- 86
Chapter 3 Definitions	72- 22	Chapter 14 Inspection, Testing, and Maintenance	72- 86
3.1 General.	72- 22	14.1 Application.	72- 86
3.2 NFPA Official Definitions.	72- 22	14.2 General.	72- 86
3.3 General Definitions.	72- 23	14.3 Inspection.	72- 87
Chapter 4 Reserved	72- 38	14.4 Testing.	72- 87
Chapter 5 Reserved	72- 38	14.5 Maintenance.	72- 103
Chapter 6 Reserved	72- 38	14.6 Records.	72- 103
Chapter 7 Documentation	72- 39	Chapter 15 Reserved	72- 103
7.1 Application.	72- 39	Chapter 16 Reserved	72- 103
7.2 Minimum Required Documentation.	72- 39	Chapter 17 Initiating Devices	72- 103
7.3 Design (Layout) Documentation.	72- 39	17.1 Application.	72- 103
7.4 Shop Drawings (Installation Documentation).	72- 40	17.2 Purpose.	72- 103
7.5 Completion Documentation.	72- 41	17.3 Performance-Based Design.	72- 103
7.6 Inspection, Testing, and Maintenance Documentation.	72- 42	17.4 General Requirements.	72- 104
7.7 Records, Record Retention, and Record Maintenance.	72- 43	17.5 Requirements for Smoke and Heat Detectors.	72- 104
7.8 Forms.	72- 43	17.6 Heat-Sensing Fire Detectors.	72- 105
Chapter 8 Reserved	72- 74	17.7 Smoke-Sensing Fire Detectors.	72- 106
Chapter 9 Reserved	72- 74	17.8 Radiant Energy-Sensing Fire Detectors.	72- 114
Chapter 10 Fundamentals	72- 74	17.9 Combination, Multi-Criteria, and Multi-Sensor Detectors.	72- 115
10.1 Application.	72- 74	17.10 Gas Detection.	72- 115
10.2 Purpose.	72- 74	17.11 Other Fire Detectors.	72- 115
10.3 Equipment.	72- 74	17.12 Carbon Monoxide Detectors.	72- 116
10.4 Design and Installation.	72- 74	17.13 Sprinkler Waterflow Alarm-Initiating Devices.	72- 116
10.5 Personnel Qualifications.	72- 74	17.14 Detection of Operation of Other Automatic Extinguishing Systems.	72- 116
10.6 Power Supplies.	72- 76	17.15 Manually Actuated Alarm-Initiating Devices.	72- 116
10.7 Signal Priority.	72- 79	17.16 Fire Extinguisher Electronic Monitoring Device. .	72- 117
10.8 Detection and Signaling of Conditions.	72- 80	17.17 Supervisory Signal-Initiating Devices.	72- 117
10.9 Responses.	72- 80	Chapter 18 Notification Appliances	72- 117
10.10 Distinctive Signals.	72- 80	18.1 Application.	72- 117
10.11 Alarm Signals.	72- 80	18.2 Purpose.	72- 118
10.12 Fire Alarm Notification Appliance Deactivation. .	72- 81	18.3 General.	72- 118
10.13 Carbon Monoxide Notification Appliance Deactivation.	72- 81	18.4 Audible Characteristics.	72- 118
10.14 Supervisory Signals.	72- 81	18.5 Visual Characteristics — Public Mode.	72- 121
10.15 Trouble Signals.	72- 81	18.6 Visual Characteristics — Private Mode.	72- 125
10.16 Emergency Control Function Status Indicators. ...	72- 82	18.7 Supplementary Visual Signaling Method.	72- 125
10.17 Notification Appliance Circuits and Supervised Notification Appliance Control Circuits.	72- 82	18.8 Textual Audible Appliances.	72- 125
10.18 Annunciation and Annunciation Zoning.	72- 82	18.9 Textual and Graphical Visual Appliances.	72- 125
10.19 Monitoring Integrity of In-Building Fire Emergency Voice/Alarm Communications Systems.	72- 83	18.10 Tactile Appliances.	72- 125
10.20 Documentation and Notification.	72- 83	Chapter 19 Reserved	72- 126
		Chapter 20 Reserved	72- 126

Chapter 21 Emergency Control Function Interfaces	72– 126	Chapter 26 Supervising Station Alarm Systems	72– 156
21.1 Application.	72– 126	26.1 Application.	72– 156
21.2 General.	72– 126	26.2 General.	72– 156
21.3 Elevator Phase I Emergency Recall Operation.	72– 127	26.3 Central Station Service Alarm Systems.	72– 157
21.4 Elevator Power Shutdown.	72– 128	26.4 Proprietary Supervising Station Alarm Systems. ...	72– 160
21.5 Fire Service Access Elevators.	72– 128	26.5 Remote Supervising Station Alarm Systems.	72– 162
21.6 Occupant Evacuation Elevators (OEE).	72– 128	26.6 Communications Methods for Supervising Station Alarm Systems.	72– 164
21.7 Heating, Ventilating and Air-Conditioning (HVAC) Systems.	72– 130	Chapter 27 Public Emergency Alarm Reporting Systems	72– 171
21.8 High Volume Low Speed (HVLS) Fans.	72– 130	27.1 Application.	72– 171
21.9 Door and Shutter Release.	72– 130	27.2 General.	72– 171
21.10 Electrically Locked Doors.	72– 130	27.3 Management and Maintenance.	72– 171
21.11 Exit Marking Audible Notification Systems.	72– 130	27.4 Communications Methods.	72– 172
Chapter 22 Reserved	72– 131	27.5 Alarm Processing Equipment.	72– 172
Chapter 23 Protected Premises Alarm and Signaling Systems	72– 131	27.6 Alarm Boxes.	72– 177
23.1 Application.	72– 131	27.7 Public Cable Plant.	72– 180
23.2 General.	72– 131	27.8 Emergency Communications Systems (ECS).	72– 183
23.3 System Features.	72– 131	Chapter 28 Reserved	72– 183
23.4 System Performance and Integrity.	72– 131	Chapter 29 Single- and Multiple-Station Alarms and Household Signaling Systems	72– 183
23.5 Performance of Initiating Device Circuits (IDCs).	72– 132	29.1 Application.	72– 183
23.6 Performance of Signaling Line Circuits (SLCs). ..	72– 132	29.2 Purpose.	72– 183
23.7 Performance of Notification Appliance Circuits (NACs).	72– 133	29.3 Basic Requirements.	72– 183
23.8 System Requirements.	72– 134	29.4 Remote Annunciation.	72– 184
23.9 In-Building Emergency Voice/Alarm Communications.	72– 139	29.5 Notification.	72– 184
23.10 Fire Alarm Systems Using Tone.	72– 139	29.6 Assumptions.	72– 184
23.11 Suppression System Actuation.	72– 139	29.7 Carbon Monoxide Detection.	72– 185
23.12 Off-Premises Signals.	72– 140	29.8 Detection and Notification.	72– 185
23.13 Guard's Tour Supervisory Service.	72– 140	29.9 Power Supplies.	72– 185
23.14 Suppressed (Exception Reporting) Signal System.	72– 140	29.10 Equipment Performance.	72– 187
23.15 Protected Premises Emergency Control Functions.	72– 140	29.11 Installation.	72– 190
23.16 Special Requirements for Low-Power Radio (Wireless) Systems.	72– 140	29.12 Optional Functions.	72– 191
Chapter 24 Emergency Communications Systems (ECS)	72– 142	29.13 Inspection, Testing, and Maintenance.	72– 192
24.1 Application.	72– 142	29.14 Markings and Instructions.	72– 192
24.2 Purpose.	72– 142	Annex A Explanatory Material	72– 192
24.3 General.	72– 142	Annex B Engineering Guide for Automatic Fire Detector Spacing	72– 328
24.4 In-Building Fire Emergency Voice/Alarm Communications Systems (EVACS).	72– 145	Annex C System Performance and Design Guide	72– 370
24.5 In-Building Mass Notification Systems.	72– 147	Annex D Speech Intelligibility	72– 371
24.6 Wide-Area Mass Notification Systems.	72– 151	Annex E Sample Ordinance Adopting NFPA 72	72– 381
24.7 Distributed Recipient Mass Notification Systems (DRMNS).	72– 152	Annex F Wiring Diagrams and Guide for Testing Fire Alarm Circuits	72– 382
24.8 Two-Way, In-Building Wired Emergency Services Communications Systems.	72– 152	Annex G Guidelines for Emergency Communication Strategies for Buildings and Campuses	72– 390
24.9 Two-Way Radio Communications Enhancement Systems.	72– 153	Annex H Carbon Monoxide	72– 395
24.10 Two-Way Emergency Communications Systems for Rescue Assistance.	72– 153	Annex I Color-Coded Tagging Program	72– 396
24.11 Information, Command, and Control.	72– 154	Annex J Guidelines for Cybersecurity	72– 399
24.12 Performance-Based Design of Mass Notification Systems.	72– 155	Annex K Informational References	72– 400
24.13 Documentation for Emergency Communications Systems.	72– 156	Index	72– 408
Chapter 25 Reserved	72– 156		

NFPA 72

National Fire Alarm and Signaling Code®

2022 Edition

IMPORTANT NOTE: This NFPA document is made available for use subject to important notices and legal disclaimers. These notices and disclaimers appear in all publications containing this document and may be found under the heading “Important Notices and Disclaimers Concerning NFPA Standards.” They can also be viewed at www.nfpa.org/disclaimers or obtained on request from NFPA.

UPDATES, ALERTS, AND FUTURE EDITIONS: New editions of NFPA codes, standards, recommended practices, and guides (i.e., NFPA Standards) are released on scheduled revision cycles. This edition may be superseded by a later one, or it may be amended outside of its scheduled revision cycle through the issuance of Tentative Interim Amendments (TIAs). An official NFPA Standard at any point in time consists of the current edition of the document, together with all TIAs and Errata in effect. To verify that this document is the current edition or to determine if it has been amended by TIAs or Errata, please consult the National Fire Codes® Subscription Service or the “List of NFPA Codes & Standards” at www.nfpa.org/docinfo. In addition to TIAs and Errata, the document information pages also include the option to sign up for alerts for individual documents and to be involved in the development of the next edition.

NOTICE: An asterisk (*) following the number or letter designating a paragraph indicates that explanatory material on the paragraph can be found in Annex A.

A reference in brackets [] following a section or paragraph indicates material that has been extracted from another NFPA document. Extracted text may be edited for consistency and style and may include the revision of internal paragraph references and other references as appropriate. Requests for interpretations or revisions of extracted text shall be sent to the technical committee responsible for the source document.

Information on referenced and extracted publications can be found in Chapter 2 and Annex K.

Chapter 1 Administration

1.1 Scope.

1.1.1 NFPA 72 covers the application, installation, location, performance, inspection, testing, and maintenance of fire alarm systems, supervising station alarm systems, public emergency alarm reporting systems, fire and carbon monoxide detection and warning equipment, and emergency communications systems (ECS), and their components.

1.1.2 The provisions of this chapter apply throughout the Code unless otherwise noted.

1.1.3 For the purposes of carbon monoxide detection, this standard is primarily concerned with life safety, not property protection.

1.2* Purpose.

1.2.1 The purpose of this Code shall be to define the means of signal initiation, transmission, notification, and annunciation; the levels of performance; and the reliability of the various types of fire alarm systems, supervising station alarm systems, public emergency alarm reporting systems, fire and carbon

monoxide detection and warning equipment, emergency communications systems, and their components.

1.2.2 This Code defines the features associated with these systems and also provides information necessary to modify or upgrade an existing system to meet the requirements of a particular system classification.

1.2.3 This Code establishes minimum required levels of performance, extent of redundancy, and quality of installation but does not establish the only methods by which these requirements are to be achieved.

1.2.4* This Code shall not be interpreted to require a level of protection that is greater than that which would otherwise be required by the applicable building or fire code.

1.3 Application.

1.3.1 Alarm systems shall be classified as follows:

- (1) Fire alarm systems
 - (a) Household fire alarm systems
 - (b) Protected premises (local) fire alarm systems
- (2) Carbon monoxide detection equipment and systems
 - (a) Single and multiple station carbon monoxide alarms
 - (b) Carbon monoxide detectors and their related systems and components
- (3) Supervising station alarm systems
 - (a) Central station (service) alarm systems
 - (b) Remote supervising station alarm systems
 - (c) Proprietary supervising station alarm systems
- (4) Public emergency alarm reporting systems

1.3.2 Emergency communications systems shall be classified as follows:

- (1) One-way emergency communications systems
 - (a) Distributed recipient mass notification systems
 - (b) In-building fire emergency voice/alarm communications systems
 - (c) In-building mass notification systems
 - (d) Wide-area mass notification systems
- (2) Two-way emergency communications systems
 - (a) In-building emergency communications systems

1.3.3 Any reference or implied reference to a particular type of hardware shall be for the purpose of clarity and shall not be interpreted as an endorsement.

1.3.4 The intent and meaning of the terms used in this Code shall be, unless otherwise defined herein, the same as those of NFPA 70.

1.3.5 The requirements of Chapters 7, 10, 12, 14, 17, 18, 21, 23, 24, 26, and 27 shall apply unless otherwise noted in the specific chapter. Chapter 29 is designed to stand alone unless it specifically references an earlier chapter.

1.4 Retroactivity.

1.4.1 Unless otherwise noted, it is not intended that the provisions of this document be applied to facilities, equipment, structures, or installations that were existing or approved for construction or installation prior to the effective date of the document.

1.4.2 In those cases where it is determined by the authority having jurisdiction that the existing situation involves a distinct hazard to life or property, retroactive application of the provisions of this document shall be permitted.

1.5 Equivalency.

1.5.1 Nothing in this Code shall prevent the use of systems, methods, devices, or appliances of equivalent or superior quality, strength, fire resistance, effectiveness, durability, and safety over those prescribed by this Code.

1.5.2 Technical documentation shall be submitted to the authority having jurisdiction to demonstrate equivalency.

1.5.3 The systems, methods, devices, or appliances that are found equivalent shall be approved.

1.6 Units and Formulas.

1.6.1 The units of measure in this Code are presented in U.S. Customary Units (inch-pound units).

1.6.2 Where presented, the International System (SI) of Units follow the inch-pound units in parentheses.

1.6.3 Where both systems of units are presented, either system shall be acceptable for satisfying the requirements in this Code.

1.6.4 Where both systems of units are presented, users of this Code shall apply one set of units consistently and shall not alternate between units.

1.6.5* The values presented for measurements in this Code are expressed with a degree of precision appropriate for practical application and enforcement. It is not intended that the application or enforcement of these values be more precise than the precision expressed.

1.6.6 Where extracted text contains values expressed in only one system of units, the values in the extracted text have been retained without conversion to preserve the values established by the responsible technical committee in the source document.

1.7 Code Adoption Requirements. This Code shall be administered and enforced by the authority having jurisdiction designated by the governing authority. (See Annex E for sample wording for enabling legislation.)

Chapter 2 Referenced Publications

2.1 General. The documents or portions thereof listed in this chapter are referenced within this Code and shall be considered part of the requirements of this document.

2.2 NFPA Publications. National Fire Protection Association, 1 Batterymarch Park, Quincy, MA 02169-7471.

NFPA 10, *Standard for Portable Fire Extinguishers*, 2022 edition.

NFPA 13, *Standard for the Installation of Sprinkler Systems*, 2022 edition.

NFPA 25, *Standard for the Inspection, Testing, and Maintenance of Water-Based Fire Protection Systems*, 2020 edition.

NFPA 37, *Standard for the Installation and Use of Stationary Combustion Engines and Gas Turbines*, 2021 edition.

NFPA 70®, *National Electrical Code®*, 2020 edition.

NFPA 75, *Standard for the Fire Protection of Information Technology Equipment*, 2020 edition.

NFPA 90A, *Standard for the Installation of Air-Conditioning and Ventilating Systems*, 2021 edition.

NFPA 101®, *Life Safety Code®*, 2021 edition.

NFPA 110, *Standard for Emergency and Standby Power Systems*, 2022 edition.

NFPA 111, *Standard on Stored Electrical Energy Emergency and Standby Power Systems*, 2022 edition.

NFPA 170, *Standard for Fire Safety and Emergency Symbols*, 2021 edition.

NFPA 601, *Standard for Security Services in Fire Loss Prevention*, 2020 edition.

NFPA 855, *Standard for the Installation of Stationary Energy Storage Systems*, 2020 edition.

NFPA 1031, *Standard for Professional Qualifications for Fire Inspector and Plan Examiner*, 2014 edition.

NFPA 1221, *Standard for the Installation, Maintenance, and Use of Emergency Services Communications Systems*, 2019 edition.

NFPA 1600®, *Standard on Continuity, Emergency, and Crisis Management*, 2019 edition.

NFPA 1620, *Standard for Pre-Incident Planning*, 2020 edition.

2.3 Other Publications.

2.3.1 ASA Publications. Acoustical Society of America, 35 Pinelawn Road, Suite 114 E, Melville, NY 11747-3177.

ANSI/ASA S1.4/Part 1, *Electroacoustics — Sound Level Meters — Part 1: Specifications*, 2014.

ANSI/ASA S3.41, *Audible Emergency Evacuation (E2) and Evacuation Signals with Relocation Instructions (ESRI)*, 2015.

2.3.2 ASCE Publications. American Society of Civil Engineers, 1801 Alexander Bell Drive, Reston, VA 20191.

ASCE/SEI 7, *Minimum Design Loads and Associated Criteria for Buildings and Other Structures*, 2016.

2.3.3 ASME Publications. American Society of Mechanical Engineers, Two Park Avenue, New York, NY 10016-5990.

ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*, 2019.

2.3.4 ICC Publications. International Code Council, 500 New Jersey Avenue, NW, 6th Floor, Washington, DC 20001.

ICC/ANSI A117.1, *Accessible and Usable Buildings and Facilities*, 2017.

2.3.5 IEEE Publications. IEEE, 3 Park Avenue, 17th Floor, New York, NY 10016-5997.

IEEE 450, *Recommended Practice for Maintenance, Testing, and Replacement of Vented Lead-Acid Batteries for Stationary Applications*, 2010.

IEEE 1106, *Recommended Practice for Installation, Maintenance, Testing, and Replacement of Vented Nickel-Cadmium Batteries for Stationary Applications*, 2015.

ANSI/IEEE C2, *National Electrical Safety Code*, 2017.

2.3.6 ISO Publications. International Organization for Standardization, ISO Central Secretariat, BIBC II, Chemin de Blandinnet 8, CP 401, 1214 Vernier, Geneva, Switzerland.

ISO 7731, *Ergonomics — Danger signals for public and work areas — Auditory danger signals*, 2003 (reconfirmed 2015).

2.3.7 Telcordia Publications. Telcordia Technologies, One Telcordia Drive, Piscataway, NJ 08854.

GR-506-CORE, LATA Switching Systems Generic Requirements: Signaling for Analog Interface, 2011.

GR-909-CORE, Fiber in the Loop Systems Generic Requirements, 2004.

2.3.8 TIA Publications. Telecommunications Industry Association, 1320 North Courthouse Road, Suite 200, Arlington, VA 22201.

ANSI/TIA-568.3, Optical Fiber Cabling and Components Standard, 2016.

2.3.9 UL Publications. Underwriters Laboratories Inc., 333 Pfingsten Road, Northbrook, IL 60062-2096.

UL 38, *Manual Signaling Boxes for Fire Alarm Systems*, 2008, revised 2018.

UL 217, *Smoke Alarms*, 8th edition, 2015, revised 2016.

UL 268, *Smoke Detectors for Fire Alarm Systems*, 7th edition, 2016.

UL 521, *Heat Detectors for Fire Protective Signaling Systems*, 1999, revised 2017.

UL 827, *Central-Station Alarm Services*, 2014, revised 2019.

UL 864, *Control Units and Accessories for Fire Alarm Systems*, 2014, revised 2018.

UL 985, *Household Fire Warning System Units*, 2015, revised 2018.

UL 1484, *Residential Gas Detectors*, 2016, revised 2017.

UL 1638, *Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories*, 2016.

UL 1730, *Smoke Detector Monitors and Accessories for Individual Living Units of Multifamily Residences and Hotel/Motel Rooms*, 2006, revised 2017.

UL 1971, *Signaling Devices for the Hearing Impaired*, 2002, revised 2018.

UL 1981, *Central Station Automation Systems*, 2014, revised 2015.

UL 2017, *General-Purpose Signaling Devices and Systems*, 2008, revised 2018.

UL 2034, *Single and Multiple Station Carbon Monoxide Alarms*, 2017, revised 2018.

UL 2075, *Gas and Vapor Detectors and Sensors*, 2013, revised 2017.

UL 2525, *Two-way Emergency Communications Systems for Rescue Assistance*, 2020.

UL 2572, *Mass Notification Systems*, 2016, revised 2018.

UL 60950-1, *Information Technology Equipment — Safety — Part 1: General Requirements*, 2019.

UL 62368-1, *Audio/Video, Information and Communication Technology Equipment — Part 1: Safety Requirements*, 2019.

2.3.10 Other Publications.

Merriam-Webster's Collegiate Dictionary, 11th edition, Merriam-Webster, Inc., Springfield, MA, 2003.

2.4 References for Extracts in Mandatory Sections.

NFPA 13, *Standard for the Installation of Sprinkler Systems*, 2022 edition.

NFPA 70®, *National Electrical Code*®, 2020 edition.

NFPA 101®, *Life Safety Code*®, 2021 edition.

NFPA 654, *Standard for the Prevention of Fire and Dust Explosions from the Manufacturing, Processing, and Handling of Combustible Particulate Solids*, 2020 edition.

NFPA 1221, *Standard for the Installation, Maintenance, and Use of Emergency Services Communications Systems*, 2019 edition.

NFPA 5000®, *Building Construction and Safety Code*®, 2021 edition.

Chapter 3 Definitions

3.1 General. The definitions contained in this chapter shall apply to the terms used in this Code. Where terms are not defined in this chapter or within another chapter, they shall be defined using their ordinarily accepted meanings within the context in which they are used. *Merriam-Webster's Collegiate Dictionary*, 11th edition, shall be the source for the ordinarily accepted meaning.

3.2 NFPA Official Definitions.

3.2.1* Approved. Acceptable to the authority having jurisdiction.

3.2.2* Authority Having Jurisdiction (AHJ). An organization, office, or individual responsible for enforcing the requirements of a code or standard, or for approving equipment, materials, an installation, or a procedure.

3.2.3* Code. A standard that is an extensive compilation of provisions covering broad subject matter or that is suitable for adoption into law independently of other codes and standards.

3.2.4 Labeled. Equipment or materials to which has been attached a label, symbol, or other identifying mark of an organization that is acceptable to the authority having jurisdiction and concerned with product evaluation, that maintains periodic inspection of production of labeled equipment or materials, and by whose labeling the manufacturer indicates compliance with appropriate standards or performance in a specified manner.

3.2.5* Listed. Equipment, materials, or services included in a list published by an organization that is acceptable to the authority having jurisdiction and concerned with evaluation of products or services, that maintains periodic inspection of production of listed equipment or materials or periodic evaluation of services, and whose listing states that either the equipment, material, or service meets appropriate designated standards or has been tested and found suitable for a specified purpose.

3.2.6 Shall. Indicates a mandatory requirement.

3.2.7 Should. Indicates a recommendation or that which is advised but not required.

3.3 General Definitions.

3.3.1 Accessible (as applied to equipment). Capable of being reached for operation, renewal, and inspection. [70:100] (SIG-FUN)

3.3.2 Accessible (as applied to wiring methods). Capable of being removed or exposed without damaging the building structure or finish or not permanently closed in by the structure or finish of the building. [70:100] (SIG-FUN)

3.3.3 Accessible, Readily (Readily Accessible). Capable of being reached quickly for operation, renewal, or inspections without requiring those to whom ready access is requisite to take actions such as to use tools (other than keys), to climb over or under, to remove obstacles, or to resort to portable ladders, and so forth. [70:100] (SIG-FUN)

3.3.4 Accessible Spaces (as applied to detection coverage in Chapter 17). Spaces or concealed areas of construction that can be entered via openable panels, doors, hatches, or other readily movable construction elements. (SIG-IDS)

3.3.5 Acknowledge. An action performed by a person to confirm that a message or signal has been received. (SIG-SSS)

3.3.6* Acoustically Distinguishable Space (ADS). An emergency communications system notification zone, or subdivision thereof, that might be an enclosed or otherwise physically defined space, or that might be distinguished from other spaces because of different acoustical, environmental, or use characteristics, such as reverberation time and ambient sound pressure level. (SIG-NAS)

3.3.7 Active Multiplex System. A multiplexing system in which signaling devices such as transponders are employed to transmit status signals of each initiating device or initiating device circuit within a prescribed time interval so that the lack of receipt of such a signal can be interpreted as a trouble signal. (SIG-SSS)

3.3.8 Addressable Device. A fire alarm system component, with an input, output, or combination function, that is discretely identified by a unique address. (SIG-FUN)

3.3.9 Adverse Condition. Any condition occurring in a communications or transmission channel that interferes with the proper transmission or interpretation, or both, of status change signals at the supervising station. (See also 3.3.272.10, *Trouble Signal*.) (SIG-SSS)

3.3.10 Air Sampling-Type Detector. See 3.3.77, Detector.

3.3.11 Alarm. An indication of the existence of a condition that requires immediate response. (SIG-FUN)

3.3.11.1 Carbon Monoxide Alarm. A single or multiple-station alarm responsive to carbon monoxide (CO). (SIG-HOU)

3.3.12 Alarm Box.

3.3.12.1 Auxiliary Alarm Box. An alarm box that can only be operated from one or more remote initiating devices or an auxiliary alarm system used to send an alarm to the communications center. (SIG-PRS)

3.3.12.2 Combination Fire Alarm and Guard's Tour Box. A manually operated box capable of transmitting a fire alarm signal and a separate guard patrol tour supervisory signal. (SIG-IDS)

3.3.12.3* Manual Fire Alarm Box. A manually operated device used to initiate a fire alarm signal. (SIG-IDS)

3.3.12.4 Master Alarm Box. A publicly accessible alarm box that can also be operated by one or more remote initiating devices or an auxiliary alarm system used to send an alarm to the communications center. (SIG-PRS)

3.3.12.5 Publicly Accessible Alarm Box. An enclosure, accessible to the public, housing a manually operated transmitter used to send an alarm to the communications center. (SIG-PRS)

3.3.13 Alarm Repeater System. A device or system for the purpose of automatically retransmitting alarm information received by the alarm processing equipment. (SIG-PRS)

3.3.14 Alarm Service. The service required following the receipt of an alarm signal. (SIG-SSS)

3.3.15 Alarm Signal. See 3.3.272, Signal.

3.3.16 Alarm System. See 3.3.118, Fire Alarm System; 3.3.302, Supervising Station Alarm Systems; 3.3.229, Public Emergency Alarm Reporting System; 3.3.97.1.2, In-Building Fire Emergency Voice/Alarm Communication System; and 3.3.97.1.3, In-Building Mass Notification System.

3.3.17 Alarm Verification Feature. A feature of automatic fire detection and alarm systems to reduce unwanted alarms wherein smoke detectors report alarm conditions for a minimum period of time, or confirm alarm conditions within a given time period after being reset, in order to be accepted as a valid alarm initiation signal. (SIG-PRO)

3.3.18 Alert Tone. An attention-getting signal to alert occupants of the pending transmission of a voice message. (SIG-PRO)

3.3.19 Analog Initiating Device (Sensor). See 3.3.148, Initiating Device.

3.3.20* Ancillary Functions. Non-emergency activations of the fire alarm or mass notification audible, visual, and textual output circuits. (SIG-ECS)

3.3.21 Annunciator. A unit containing one or more indicator lamps, alphanumeric displays, or other equivalent means in which each indication provides status information about a circuit, condition, or location. (SIG-FUN)

3.3.22 Apartment Building. A building or portion thereof containing three or more dwelling units with independent cooking and bathroom facilities. (SIG-HOU) [5000, 2021]

3.3.23 Audible Notification Appliance. See 3.3.189, Notification Appliance.

3.3.24 Authorized Personnel. The property owner, or designated representative appointed or selected by the property owner, who performs certain duties. (SIG-FUN)

3.3.25 Automatic Extinguishing System Supervisory Device. See 3.3.148, Initiating Device.

3.3.26 Automatic Fire Detector. See 3.3.77, Detector.

3.3.27 Automatic Fire Extinguishing or Suppression System Operation Detector. See 3.3.77, Detector.

3.3.28 Autonomous Control Unit (ACU). See 3.3.69, Control Unit.

3.3.29 Auxiliary Alarm System. See 3.3.229, Public Emergency Alarm Reporting System.

3.3.30 Auxiliary Box. See 3.3.12, Alarm Box.

3.3.31* Average Ambient Sound Level. The root mean square, A-weighted, sound pressure level measured over the period of time that any person is present, or a 24-hour period, whichever time period is the lesser. (SIG-NAS)

3.3.32* Backbone. A part of a network that acts as a common infrastructure to which the branch parts are connected. (SIG-PRO)

3.3.33* Battery. Two or more cells connected together electrically. (SIG-TMS)

3.3.33.1 Battery Capacity. The electrical energy available from a fully charged battery expressed in ampere-hours. (SIG-TMS)

3.3.33.2 Battery Charger. A device used to restore and maintain the charge of a secondary battery in which electrical energy is converted to chemical energy. (SIG-TMS)

3.3.33.2.1 Float Charge. A constant-voltage charge applied to a battery to maintain it in a fully charged condition. (SIG-TMS)

3.3.33.2.2 Fully Charged. A condition synonymous with 100 percent state of charge. (See also 3.3.33.2.3, *State of Charge*.) (SIG-TMS)

3.3.33.2.3 State of Charge (SOC). The stored or remaining capacity of a battery at a given time expressed as a percentage of its rated capacity. (SIG-TMS)

3.3.33.2.4 Trickle Charge. A continuous, low-rate, constant-current charge given to a cell or battery to keep the unit fully charged. (See also 3.3.33.2.1, *Float Charge*.) (SIG-TMS)

3.3.33.3 Battery Load Test. A controlled discharge of a battery at a specified rate for a given period of time until a final voltage is achieved to determine battery capacity. (SIG-TMS)

3.3.33.4 Battery Unit. See 3.3.43.3, Unit (Multi-Cell). (SIG-TMS)

3.3.33.5 Rechargeable Battery. An electrochemical cell capable of being discharged and then recharged. (SIG-TMS)

3.3.34 Beam Construction. See 3.3.42, Ceiling Surfaces.

3.3.35 Building Fire Alarm System. See 3.3.118, Fire Alarm System.

3.3.36 Building System Information Unit (BSIU). A computer-based electronic device that is intended to display building information and execute system control functions, including fire system information display and control. (SIG-PRO)

3.3.37 Carbon Monoxide Detection System. A system or portion of a combination system that consists of a control unit, components, and circuits arranged to monitor and annunciate the status of carbon monoxide alarm initiating devices and to initiate the appropriate response to those signals. (SIG-PRO)

3.3.37.1 Combination Carbon Monoxide Detection System. A carbon monoxide detection system in which components are used, in whole or in part, in common with a non-carbon

monoxide signaling system, and in which components are not used as part of a fire alarm system. (SIG-PRO)

3.3.37.2 Household Carbon Monoxide Detection System. A system of devices that uses a control unit to produce an alarm signal in the household for the purpose of notifying the occupants of the presence of concentrations of carbon monoxide that could pose a life safety risk. (SIG-HOU)

3.3.38 Carrier. High-frequency energy that can be modulated by voice or signaling impulses. (SIG-SSS)

3.3.39 Carrier System. A means of conveying a number of channels over a single path by modulating each channel on a different carrier frequency and demodulating at the receiving point to restore the signals to their original form. (SIG-SSS)

3.3.40* Ceiling. The upper surface of a space, regardless of height. (SIG-IDS)

3.3.40.1 Level Ceilings. Ceilings that have a slope of less than or equal to 1 in 8. (SIG-IDS)

3.3.40.2 Sloping Ceiling. A ceiling that has a slope of more than 1 in 8. (SIG-IDS)

3.3.40.3* Sloping Peaked-Type Ceiling. A ceiling in which the ceiling slopes in two directions from the highest point. (SIG-IDS)

3.3.40.4* Sloping Shed-Type Ceiling. A ceiling in which the high point is at one side with the slope extending toward the opposite side. (SIG-IDS)

3.3.41 Ceiling Height. The height from the continuous floor of a room to the continuous ceiling of a room or space. (SIG-IDS)

3.3.42 Ceiling Surfaces.

3.3.42.1 Beam Construction. Ceilings that have solid structural or solid nonstructural members projecting down from the ceiling surface more than 4 in. (100 mm) and spaced more than 36 in. (910 mm), center to center. (SIG-IDS)

3.3.42.2 Girder. A support for beams or joists that runs at right angles to the beams or joists. If the top of the girder is within 4 in. (100 mm) of the ceiling, the girder is a factor in determining the number of detectors and is to be considered a beam. If the top of the girder is more than 4 in. (100 mm) from the ceiling, the girder is not a factor in detector location. (SIG-IDS)

3.3.42.3* Smooth Ceiling. A ceiling surface uninterrupted by continuous projections, such as solid joists, beams, or ducts, extending more than 4 in. (100 mm) below the ceiling surface. (SIG-IDS)

3.3.42.4 Solid Joist Construction. Ceilings that have solid structural or solid nonstructural members projecting down from the ceiling surface for a distance of more than 4 in. (100 mm) and spaced at intervals of 36 in. (910 mm) or less, center to center. (SIG-IDS)

3.3.43 Cell. The basic electrochemical unit, characterized by an anode and a cathode, used to receive, store, and deliver electrical energy. [70:480] (SIG-TMS)

3.3.43.1 Primary (Dry) Cell. A nonrechargeable electrochemical cell requiring periodic replacement, such as a 9-volt alkaline cell. (SIG-FUN)

- 3.3.43.2 Starved Electrolyte Cell.** A cell in which liquid electrolyte is immobilized, also known as an absorbed glass mat (AGM) cell or a gelled electrolyte cell (gel cell). (SIG-TMS)
- 3.3.43.2.1 Absorbed Glass Mat (AGM) Cell.** A cell in which the liquid electrolyte is immobilized in fiberglass or polymeric fiber separators. (SIG-TMS)
- 3.3.43.2.2 Gelled Electrolyte Cell (Gel Cell).** A cell in which the electrolyte is immobilized by addition of a gelling agent. (SIG-TMS)
- 3.3.43.3 Unit (Multi-Cell).** Multiple cells in a single container, such as a 12-volt unit composed of six 2-volt cells. (SIG-TMS)
- 3.3.43.4* Valve-Regulated Lead-Acid (VRLA) Cell.** A sealed lead-acid cell with a valve that opens to the atmosphere when the internal pressure in the cell exceeds atmospheric pressure by a preselected amount. (SIG-TMS)
- 3.3.44 Central Station.** See 3.3.301.1, Central Supervising Station.
- 3.3.45 Central Station Alarm System.** See 3.3.302.1, Central Station Service Alarm System.
- 3.3.46 Central Station Service.** See 3.3.303, Supervising Station Service.
- 3.3.47 Central Station Service Alarm System.** See 3.3.302, Supervising Station Alarm Systems.
- 3.3.48 Central Supervising Station.** See 3.3.301, Supervising Station.
- 3.3.49 Certified.** See 3.2.5, Listed, for certified equipment.
- 3.3.50 Channel.** A path for voice or signal transmission that uses modulation of light or alternating current within a frequency band. (SIG-SSS)
- 3.3.50.1 Communications Channel.** A circuit or path connecting a subsidiary station(s) to a supervising station(s) over which signals are carried. (SIG-SSS)
- 3.3.50.2* Radio Channel.** A band of frequencies of a width sufficient to allow its use for radio communications. (SIG-SSS)
- 3.3.50.3 Transmission Channel.** A circuit or path connecting transmitters to supervising stations or subsidiary stations on which signals are carried. (SIG-SSS)
- 3.3.51 Circuit.** Either a means of providing power or a connection path between locations [see 3.3.205, *Path (Paths)*]. (SIG-PRO)
- 3.3.52 Circuit Interface.** See 3.3.153, Interface.
- 3.3.53 Cloud Chamber Smoke Detection.** See 3.3.285, Smoke Detection.
- 3.3.54* Coded.** An audible or visual signal that conveys several discrete bits or units of information. (SIG-NAS)
- 3.3.55 Combination Detector.** See 3.3.77, Detector.
- 3.3.56 Combination Emergency Communications Systems.** See 3.3.98, Emergency Communications Systems — Combination.
- 3.3.57 Combination Fire Alarm and Guard's Tour Box.** See 3.3.12, Alarm Box.
- 3.3.58 Combination System.** See 3.3.118, Fire Alarm System.
- 3.3.59 Common Talk Mode.** See 3.3.313, Talk Mode.
- 3.3.60* Communications Center.** A building or portion of a building that is specifically configured for the primary purpose of providing emergency communications services or public safety answering point (PSAP) services to one or more public safety agencies under the authority or authorities having jurisdiction. [1221, 2019] (SIG-PRS)
- 3.3.61 Communications Channel.** See 3.3.50, Channel.
- 3.3.62 Communications Circuit.** Any signaling path of an emergency communications system that carries voice, audio, data, or other signals. (SIG-ECS)
- 3.3.63 Communications Cloud.** The area in the communications path that is supported by providers of communications services not governed under the scope of *NFPA 72* in which signals travel between a protected property and a monitoring station. Depending on the type of transmission that is used, signals can travel on a single defined route or through various routes depending on what is available when the signal is initiated. (SIG-SSS)
- 3.3.64 Communications, Radio (as applied to Chapter 27).**
- 3.3.64.1 One-Way Radio Communications.** A communications channel on which alarm boxes only transmit signals and are incapable of receiving responses. (SIG-PRS)
- 3.3.64.2 Two-Way Radio Communications.** A communications channel on which alarm boxes and the communications center both transmit and receive signals. (SIG-PRS)
- 3.3.65* Condition.** A situation, environmental state, or equipment state of a fire alarm or signaling system. (SIG-FUN)
- 3.3.65.1 Abnormal (Off-Normal) Condition.** A situation, environmental state, or equipment state that warrants some type of signal, notification, communication, response, action, or service. (SIG-FUN)
- 3.3.65.1.1* Alarm Condition.** An abnormal condition that poses an immediate threat to life, property, or mission. (SIG-FUN)
- 3.3.65.1.2* Pre-Alarm Condition.** An abnormal condition that poses a potential threat to life, property, or mission, and time is available for investigation. (SIG-FUN)
- 3.3.65.1.3* Supervisory Condition.** An abnormal condition in connection with the supervision of other systems, processes, or equipment. (SIG-FUN)
- 3.3.65.1.4* Trouble Condition.** An abnormal condition in a system due to a fault. (SIG-FUN)
- 3.3.65.2 Normal Condition.** Circuits, systems, and components are functioning as designed and no abnormal condition exists. (SIG-FUN)
- 3.3.66 Constantly Attended.** Attended 24 hours a day and 365 days a year. (SIG-PRO)
- 3.3.67 Contiguous Property.** See 3.3.221, Property.

3.3.68 Control Equipment. Equipment listed as either a control unit or control unit accessory. (SIG-FUN)

3.3.69 Control Unit. A system component that monitors inputs and controls outputs through various types of circuits. (SIG-PRO)

3.3.69.1* Autonomous Control Unit (ACU). The primary control unit for an in-building mass notification system. (SIG-ECS)

3.3.69.2 Emergency Communications Control Unit (ECCU). A system capable of sending mass notification messages to individual buildings, zones of buildings, individual outdoor loudspeaker arrays, or zones of outdoor loudspeaker arrays; or a building, multiple buildings, outside areas, or a combination of these. (SIG-ECS)

3.3.69.3 Fire Alarm Control Unit (FACU). See 3.3.115, Fire Alarm Control Unit (FACU).

3.3.69.4 Wireless Control Unit. A component that transmits/ receives and processes wireless signals. (SIG-PRO)

3.3.70 Cybersecurity. The protection of systems from theft or damage of data, or damage to hardware or software, as well as from unauthorized command or control or access to any information of any services the systems provide. (SIG-FUN)

3.3.71 Day-Care Home. A building or portion of a building in which more than 3 but not more than 12 clients receive care, maintenance, and supervision, by other than their relative(s) or legal guardian(s), for less than 24 hours per day. [101, 2021] (SIG-HOU)

3.3.72 Dedicated Function Fire Alarm Control Unit. See 3.3.115, Fire Alarm Control Unit (FACU).

3.3.73 Dedicated Function Fire Alarm System. See 3.3.118, Fire Alarm System.

3.3.74 Deficiency. A condition that interferes with the service or reliability for which the part, system, or equipment was intended. (SIG-TMS)

3.3.75 Delinquency Signal. See 3.3.272, Signal.

3.3.76* Design Professional. An individual who is registered or licensed to practice their respective design profession as defined by the statutory requirements of the professional registration laws of the jurisdiction in which the project is to be constructed, or other professional with qualifications or credentials acceptable to the jurisdiction in which the project is to be constructed. (SIG-ECS)

3.3.77 Detector. A device suitable for connection to a circuit that has a sensor that responds to a physical stimulus such as gas, heat, or smoke. (SIG-IDS)

3.3.77.1 Air Sampling-Type Detector. A detector that draws air and particulate from the protected area into a sampling network that runs to the detector. An aspiration fan in the detector housing draws air from the protected area back to the detector through air sampling ports, piping, or tubing. At the detector, the air is analyzed for fire products. (SIG-IDS)

3.3.77.2* Automatic Fire Detector. A device designed to detect the presence of a fire signature and to initiate action. (SIG-IDS)

3.3.77.3 Automatic Fire Extinguishing or Suppression System Operation Detector. A device that automatically detects the operation of a fire extinguishing or suppression system by means appropriate to the system employed. (SIG-IDS)

3.3.77.4 Carbon Monoxide Detector. A device that responds to carbon monoxide. (SIG-IDS)

3.3.77.5* Combination Detector. A device that either responds to more than one of the fire phenomena or employs more than one operating principle to sense one of these phenomena. This device has listings for each sensing method employed. (SIG-IDS)

3.3.77.6 Electrical Conductivity Heat Detector. A line-type or spot-type sensing element in which resistance varies as a function of temperature. (SIG-IDS)

3.3.77.7 Fire-Gas Detector. A device that detects gases produced by a fire. (SIG-IDS)

3.3.77.8* Fixed-Temperature Detector. A device that responds when its operating element becomes heated to a predetermined level. (SIG-IDS)

3.3.77.9* Flame Detector. A radiant energy-sensing fire detector that detects the radiant energy emitted by a flame. (Refer to A.17.8.2.) (SIG-IDS)

3.3.77.10 Gas Detector. A device that detects the presence of a specified gas concentration. (SIG-IDS)

3.3.77.11 Heat Detector. A fire detector that detects either abnormally high temperature or rate-of-temperature rise, or both. (SIG-IDS)

3.3.77.12* Line-Type Detector. A device in which detection is continuous along a path. (SIG-IDS)

3.3.77.13* Multi-Criteria Detector. A device that contains multiple sensors that separately respond to physical stimulus such as heat, smoke, or fire gases, or employs more than one sensor to sense the same stimulus. This sensor is capable of generating only one alarm signal from the sensors employed in the design either independently or in combination. The sensor output signal is mathematically evaluated to determine when an alarm signal is warranted. The evaluation can be performed either at the detector or at the control unit. This detector has a single listing that establishes the primary function of the detector. (SIG-IDS)

3.3.77.14* Multi-Sensor Detector. A device that contains multiple sensors that separately respond to physical stimulus such as heat, smoke, or fire gases, or employs more than one sensor to sense the same stimulus. A device capable of generating multiple alarm signals from any one of the sensors employed in the design, independently or in combination. The sensor output signals are mathematically evaluated to determine when an alarm signal is warranted. The evaluation can be performed either at the detector or at the control unit. This device has listings for each sensing method employed. (SIG-IDS)

3.3.77.15 Other Fire Detectors. Devices that detect a phenomenon other than heat, smoke, flame, or gases produced by a fire. (SIG-IDS)

3.3.77.16 Pneumatic Rate-of-Rise Tubing Heat Detector. A line-type detector comprising small-diameter tubing, usually copper, that is installed on the ceiling or high on the walls

throughout the protected area. The tubing is terminated in a detector unit containing diaphragms and associated contacts set to actuate at a predetermined pressure. The system is sealed except for calibrated vents that compensate for normal changes in temperature. (SIG-IDS)

3.3.77.17 Projected Beam-Type Detector. A type of photoelectric light obscuration smoke detector wherein the beam spans the protected area. (SIG-IDS)

3.3.77.18 Radiant Energy-Sensing Fire Detector. A device that detects radiant energy, such as ultraviolet, visible, or infrared, that is emitted as a product of combustion reaction and obeys the laws of optics. (SIG-IDS)

3.3.77.19* Rate Compensation Detector. A device that responds when the temperature of the air surrounding the device reaches a predetermined level, regardless of the rate-of-temperature rise. (SIG-IDS)

3.3.77.20* Rate-of-Rise Detector. A device that responds when the temperature rises at a rate exceeding a predetermined value. (SIG-IDS)

3.3.77.21 Smoke Detector. A device that detects visible or invisible particles of combustion. (SIG-IDS)

3.3.77.22* Spark/Ember Detector. A radiant energy-sensing fire detector that is designed to detect sparks or embers. (SIG-IDS)

3.3.77.23* Spot-Type Detector. A device in which the detecting element is concentrated at a particular location. (SIG-IDS)

3.3.78* Device (Class N). A supervised component of a life safety system that communicates with other components of life safety systems and that collects environmental data or performs specific input or output functions necessary to the operation of the life safety system. (SIG-PRO)

3.3.79 Digital Alarm Communicator Receiver (DACR). A system component that accepts and displays signals from digital alarm communicator transmitters (DACTs) sent over a managed facilities-based voice network. (SIG-SSS)

3.3.80 Digital Alarm Communicator System (DACS). A system in which signals are transmitted from a digital alarm communicator transmitter (DACT) located at the protected premises through a managed facilities-based voice network to a digital alarm communicator receiver (DACR). (SIG-SSS)

3.3.81 Digital Alarm Communicator Transmitter (DACT). A system component at the protected premises to which initiating devices or groups of devices are connected. The DACT seizes the connected telephone line, dials a preselected number to connect to a DACR, and transmits signals indicating a status change of the initiating device. (SIG-SSS)

3.3.82 Digital Alarm Radio Receiver (DARR). A system component composed of two subcomponents: one that receives and decodes radio signals, the other that annunciates the decoded data. These two subcomponents can be coresident at the central station or separated by means of a data transmission channel. (SIG-SSS)

3.3.83 Digital Alarm Radio System (DARS). A system in which signals are transmitted from a digital alarm radio transmitter (DART) located at a protected premises through a radio channel to a digital alarm radio receiver (DARR). (SIG-SSS)

3.3.84 Digital Alarm Radio Transmitter (DART). A system component that is connected to or an integral part of a digital alarm communicator transmitter (DACT) that is used to provide an alternate radio transmission channel. (SIG-SSS)

3.3.85 Display. The visible representation of output data, other than printed copy. (SIG-NAS)

3.3.86 Distributed Recipient Mass Notification System (DRMNS). See 3.3.97, Emergency Communications System.

3.3.87 Dormitory. A building or a space in a building in which group sleeping accommodations are provided for more than 16 persons who are not members of the same family in one room, or a series of closely associated rooms, under joint occupancy and single management, with or without meals, but without individual cooking facilities. [101, 2021] (SIG-HOU)

3.3.88* Double Doorway. A single opening that has no intervening wall space or door trim separating the two doors. (SIG-IDS)

3.3.89 Downlink. The radio signal from the base station transmitter to the portable public safety subscriber receiver. (SIG-ECS)

3.3.90 Dwelling Unit. One or more rooms arranged for complete, independent housekeeping purposes with space for eating, living, and sleeping; facilities for cooking; and provisions for sanitation. [5000, 2021] (SIG-HOU)

3.3.91 Effective Masked Threshold. The minimum sound level at which the tone signal is audible in ambient noise. (SIG-NAS)

3.3.92 Electrical Conductivity Heat Detector. See 3.3.77, Detector.

3.3.93 Electromechanical Releasing Device. Mechanical devices, including fusible links, electrically monitored for contact closure to initiate a signal to the FACU. (SIG-TMS)

3.3.94* Ember. A particle of solid material that emits radiant energy due either to its temperature or the process of combustion on its surface. (See also 3.3.291, Spark.) (SIG-IDS)

3.3.95 Emergency Command Center. See 3.3.99, Emergency Communications System — Emergency Command Center.

3.3.96 Emergency Communications Control Unit (ECCU). See 3.3.69, Control Unit.

3.3.97* Emergency Communications System. A system for the protection of life by indicating the existence of an emergency situation and communicating information necessary to facilitate an appropriate response and action. (SIG-ECS)

3.3.97.1 One-Way Emergency Communications System. One-way emergency communications systems are intended to broadcast information, in an emergency, to people in one or more specified indoor or outdoor areas. It is intended that emergency messages be conveyed either by audible, visual, or textual means, or any combination thereof. (SIG-ECS)

3.3.97.1.1 Distributed Recipient Mass Notification System (DRMNS). A distributed recipient mass notification system is a system meant to communicate directly to targeted individuals and groups that might not be in a contiguous area. (SIG-ECS)

3.3.97.1.2 In-Building Fire Emergency Voice/Alarm Communications System. Dedicated manual or automatic equipment for originating and distributing voice instructions, as well as alert and evacuation signals pertaining to a fire emergency, to the occupants of a building. (SIG-ECS)

3.3.97.1.3 In-Building Mass Notification System. A system used to provide information and instructions to people in a building(s) or other space using intelligible voice communications and including visual signals, text, graphics, tactile, or other communication methods. (SIG-ECS)

3.3.97.1.4 Wide-Area Mass Notification System. Wide-area mass notification systems are generally installed to provide real-time information to outdoor areas and could have the capability to communicate with other notification systems provided for a campus, military base, municipality, or similar single or multiple contiguous areas. (SIG-ECS)

3.3.97.2 Two-Way Emergency Communications System. Two-way emergency communications systems are divided into two categories, those systems that are anticipated to be used by building occupants (area of refuge two-way emergency communications systems, elevator landing two-way emergency communications systems, occupant evacuation elevator lobby two-way emergency communications systems, and stairway communications systems) and those systems that are to be used by fire fighters, police, and other emergency services personnel. Two-way emergency communications systems are used to both exchange information and to communicate information such as, but not limited to, instructions, acknowledgement of receipt of messages, condition of local environment, and condition of persons, and to give assurance that help is on the way. (SIG-ECS)

3.3.98 Emergency Communications Systems — Combination. Various emergency communications systems such as fire alarm, mass notification, fire fighter communications, area of refuge communications, elevator communications, or others that can be served through a single control system or through an interconnection of several control systems. (SIG-ECS)

3.3.99* Emergency Communications System — Emergency Command Center. The room(s) or area(s) staffed during any emergency event by assigned emergency management staff. The room or area contains system communications and control equipment serving one or more buildings where responsible authorities receive information from premises sources or systems or from (higher level) regional or national sources or systems and then disseminate appropriate information to individuals, a building, multiple buildings, outside campus areas, or a combination of these in accordance with the emergency response plan established for the premises. The room or area contains the controls and indicators from which the emergency communications systems located in the room or area can be manually controlled as required by the emergency response plan and the emergency management coordinator. (SIG-ECS)

3.3.100* Emergency Control Function Interface Device. A listed fire alarm or signaling system component that directly interfaces with the system that operates the emergency control function. (SIG-PRO)

3.3.101* Emergency Control Functions. Building, fire, and emergency control elements or systems that are initiated by the fire alarm or signaling system and either increase the level of

life safety for occupants or control the spread of the harmful effects of fire or other dangerous products. (SIG-PRO)

3.3.102 Emergency Personnel. Person(s) who have been trained in emergency response. (SIG-FUN)

3.3.103* Emergency Response Agency (ERA). Organizations providing law enforcement, emergency medical, fire, rescue, communications, and related support services. [1221, 2019] (SIG-SSS)

3.3.104* Emergency Response Facility (ERF). A structure or a portion of a structure that houses emergency response agency equipment or personnel for response to events. [1221, 2019] (SIG-PRS)

3.3.105 Emergency Response Plan. A documented set of actions to address the planning for, management of, and response to natural, technological, and man-made disasters and other emergencies. (SIG-ECS)

3.3.106* Endpoint (Class N). The end of a pathway where a single addressable device or a control unit is connected. (SIG-PRO)

3.3.107* Evacuation. The withdrawal of occupants from a building. (SIG-PRO)

3.3.108 Evacuation Signal. See 3.3.272, Signal.

3.3.109 Executive Software. See 3.3.288, Software.

3.3.110 Exit Marking Audible Notification Appliance. See 3.3.189, Notification Appliance.

3.3.111 FACP. Fire Alarm Control Panel. See 3.3.115, Fire Alarm Control Unit (FACU).

3.3.112 False Alarm. See 3.3.326, Unwanted Alarm.

3.3.113 Field of View. The virtual cone that extends out from the detector within which the effective sensitivity of the detector is at least 50 percent of its on-axis, listed, or approved sensitivity. (SIG-IDS)

3.3.114 Fire Alarm Control Interface (FACI). See 3.3.153, Interface.

3.3.115* Fire Alarm Control Unit (FACU). A component of the fire alarm system that receives signals from initiating devices or other fire alarm control units and processes these signals to determine part or all of the required fire alarm system output function(s). (SIG-PRO)

3.3.115.1 Master Fire Alarm Control Unit. A fire alarm control unit that serves the protected premises or portion of the protected premises as a local fire alarm control unit and accepts inputs from other fire alarm control units. (SIG-PRO)

3.3.115.2 Protected Premises (Local) Control Unit. A fire alarm control unit that serves the protected premises or a portion of the protected premises. (SIG-PRO)

3.3.115.2.1* Dedicated Function Fire Alarm Control Unit. A protected premises fire alarm control unit that is intended to operate specifically identified emergency control function(s). (SIG-PRO)

3.3.115.2.2 Releasing Service Fire Alarm Control Unit. A protected premises fire alarm control unit specifically listed for releasing service that is part of a fire suppression system

and which provides control outputs to release a fire suppression agent based on either automatic or manual input. (SIG-PRO)

3.3.116 Fire Alarm/Evacuation Signal Tone Generator. A device that produces a fire alarm/evacuation tone upon command. (SIG-PRO)

3.3.117 Fire Alarm Signal. See 3.3.272, Signal.

3.3.118 Fire Alarm System. A system or portion of a combination system that consists of components and circuits arranged to monitor and annunciate the status of fire alarm or supervisory signal-initiating devices and to initiate the appropriate response to those signals. (SIG-FUN)

3.3.118.1* Combination System. A fire alarm system in which components are used, in whole or in part, in common with a non-fire signaling system. (SIG-PRO)

3.3.118.2 Household Fire Alarm System. A system of devices that uses a fire alarm control unit to produce an alarm signal in the household for the purpose of notifying the occupants of the presence of a fire so that they will evacuate the premises. (SIG-HOU)

3.3.118.3 Municipal Fire Alarm System. A public emergency alarm reporting system. (SIG-PRS)

3.3.118.4* Protected Premises (Local) Fire Alarm System. A fire alarm system located at the protected premises. (SIG-PRO)

3.3.118.4.1 Building Fire Alarm System. A protected premises fire alarm system that includes any of the features identified in 23.3.3.1 and that serves the general fire alarm needs of a building or buildings and provides notification. (SIG-PRO)

3.3.118.4.2 Dedicated Function Fire Alarm System. A protected premises fire alarm system installed specifically to perform emergency control function(s) where a building fire alarm system is not required. (SIG-PRO)

3.3.118.4.3 Releasing Fire Alarm System. A protected premises fire alarm system that is part of a fire suppression system and/or that provides control inputs to a fire suppression system related to the fire suppression system's sequence of operations and outputs for other signaling and notification. (SIG-PRO)

3.3.119* Fire Command Center. The principal attended or unattended room or area where the status of the detection, alarm communications, control systems, and other emergency systems is displayed and from which the system(s) can be manually controlled. (SIG-ECS)

3.3.120 Fire Extinguisher Electronic Monitoring Device. A device connected to a control unit that monitors the fire extinguisher in accordance with the requirements of NFPA 10. (SIG-IDS)

3.3.121 Fire Warden. A building staff member or a tenant trained to perform assigned duties in the event of a fire emergency. (SIG-PRO)

3.3.122 Fire Warning Equipment. Any detector, alarm, device, or material related to single- and multiple-station alarms or household fire alarm systems. (SIG-HOU)

3.3.123 Fire-Gas Detector. See 3.3.77, Detector.

3.3.124 Fixed-Temperature Detector. See 3.3.77, Detector.

3.3.125 Flame. A body or stream of gaseous material involved in the combustion process and emitting radiant energy at specific wavelength bands determined by the combustion chemistry of the fuel. (SIG-IDS)

3.3.126 Flame Detector. See 3.3.77, Detector.

3.3.127 Flame Detector Sensitivity. The distance along the optical axis of the detector at which the detector can detect a fire of specified size and fuel within a given time frame. (SIG-IDS)

3.3.128 Frequency. Minimum and maximum time between events. (SIG-TMS)

3.3.128.1 Weekly Frequency. Fifty-two times per year, once per calendar week. (SIG-TMS)

3.3.128.2 Monthly Frequency. Twelve times per year, once per calendar month. (SIG-TMS)

3.3.128.3 Quarterly Frequency. Four times per year with a minimum of 2 months, maximum of 4 months. (SIG-TMS)

3.3.128.4 Semiannual Frequency. Twice per year with a minimum of 4 months, maximum of 8 months. (SIG-TMS)

3.3.128.5 Annual Frequency. Once per year with a minimum of 9 months, maximum 15 months. (SIG-TMS)

3.3.129 Gateway. A device that is used in the transmission of serial data (digital or analog) from the fire alarm control unit to other building system control units, equipment, or networks and/or from other building system control units to the fire alarm control unit. (SIG-PRO)

3.3.130 Girder. See 3.3.42, Ceiling Surfaces.

3.3.131 Guard's Tour Reporting Station. A device that is manually or automatically initiated to indicate the route being followed and the timing of a guard's tour. (SIG-IDS)

3.3.132 Guard's Tour Supervisory Signal. See 3.3.272, Signal.

3.3.133 Guest Room. An accommodation combining living, sleeping, sanitary, and storage facilities within a compartment. [101, 2021] (SIG-HOU)

3.3.134 Guest Suite. An accommodation with two or more contiguous rooms comprising a compartment, with or without doors between such rooms, that provides living, sleeping, sanitary, and storage facilities. [101, 2021] (SIG-HOU)

3.3.135* Hearing Loss. A full or partial decrease in the ability to detect or comprehend sounds. (SIG-HOU)

3.3.135.1 Profound Hearing Loss. A hearing threshold of greater than 90 dB. (SIG-HOU)

3.3.136 Heat Alarm. A single- or multiple-station alarm responsive to heat. (SIG-HOU)

3.3.136.1 Mechanically Powered, Single-Station Heat Alarm. A single-station heat alarm employing a mechanical power source. (SIG-HOU)

3.3.137 Heat Detector. See 3.3.77, Detector.

3.3.138 High Power Loudspeaker Array (HPLA). High power loudspeaker arrays provide capability for voice and tone communications to large outdoor areas. (SIG-ECS)

3.3.139 High Volume Low Speed (HVLS) Fan. A ceiling fan that is approximately 6 ft (1.8 m) to 24 ft (7.3 m) in diameter with a rotational speed of approximately 30 to 70 revolutions per minute. [13, 2022] (SIG-PRO)

3.3.140 Hotel. A building or groups of buildings under the same management in which there are sleeping accommodations for more than 16 persons and primarily used by transients for lodging with or without meals. [101, 2021] (SIG-HOU)

3.3.141 Household Fire Alarm System. See 3.3.118, Fire Alarm System.

3.3.142 Hunt Group. A group of associated telephone lines within which an incoming call is automatically routed to an idle (not busy) telephone line for completion. (SIG-SSS)

3.3.143* Identified (as applied to equipment). Recognizable as suitable for the specific purpose, function, use, environment, application, and so forth, where described in a particular *Code* requirement. [70:100] (SIG-PRS)

3.3.144* Immediately (as used in Chapter 26). Performed without unreasonable delay. (SIG-SSS)

3.3.145* Impairment. An abnormal condition, during either a planned or emergency event, where a system, component, or function is inoperable. (SIG-FUN)

3.3.146* In Writing. A form of correspondence formatted as a letter or document that can be verified upon request. (SIG-FUN)

3.3.147 In-Building Mass Notification System. See 3.3.97, Emergency Communications System.

3.3.148 Initiating Device. A system component that originates transmission of a signal indicating a change-of-state condition. (SIG-IDS)

3.3.148.1 Analog Initiating Device (Sensor). An initiating device that transmits a signal indicating varying degrees of condition as contrasted with a conventional initiating device, which can only indicate an on-off condition. (SIG-IDS)

3.3.148.2* Automatic Extinguishing System Supervisory Device. A device that responds to abnormal conditions that could affect the proper operation of an automatic sprinkler system, other fire-extinguishing system(s) or fire-suppression system(s). (SIG-IDS)

3.3.148.3 Nonrestorable Initiating Device. A device in which the sensing element is designed to be destroyed in the process of operation. (SIG-IDS)

3.3.148.4 Restorable Initiating Device. A device in which the sensing element is not ordinarily destroyed in the process of operation, whose restoration can be manual or automatic. (SIG-IDS)

3.3.148.5 Supervisory Signal Initiating Device. An initiating device in which the change of state signals an off-normal condition that requires action in connection with guard tours or maintenance of related systems. (SIG-IDS)

3.3.149 Initiating Device Circuit. A circuit to which automatic or manual initiating devices are connected where the signal received does not identify the individual device operated. (SIG-PRO)

3.3.150 Inspection Personnel. See 3.3.208, Personnel.

3.3.151 Intelligibility. The quality or condition of being intelligible. (SIG-NAS)

3.3.152* Intelligible. Capable of being understood; comprehensible; clear. (SIG-NAS)

3.3.153 Interface.

3.3.153.1 Circuit Interface. A circuit component that interfaces initiating devices or control circuits, or both; notification appliances or circuits, or both; system control outputs; and other signaling line circuits to a signaling line circuit. (SIG-PRO)

3.3.153.1.1* Emergency Control Function Interface. The interface between the fire alarm system emergency control function interface device and the component controlling the emergency control function. (SIG-PRO)

3.3.153.1.2 Signaling Line Circuit Interface. A system component that connects a signaling line circuit to any combination of initiating devices, initiating device circuits, notification appliances, notification appliance circuits, system control outputs, and other signaling line circuits. (SIG-PRO)

3.3.153.2* Fire Alarm Control Interface. The fire alarm control interface coordinates signals to and from the fire alarm system and other systems. (SIG-ECS)

3.3.154 Ionization Smoke Detection. See 3.3.285, Smoke Detection.

3.3.155 Leg Facility. The portion of a communications channel that connects not more than one protected premises to a primary or secondary trunk facility. The leg facility includes the portion of the signal transmission circuit from its point of connection with a trunk facility to the point where it is terminated within the protected premises at one or more transponders. (SIG-SSS)

3.3.156 Level Ceilings. See 3.3.40, Ceiling.

3.3.157 Life Safety Network. A type of combination system that transmits fire and emergency communications system data to at least one other life safety system. (SIG-PRO)

3.3.158 Line-Type Detector. See 3.3.77, Detector.

3.3.159 Living Area. Any normally occupiable space in a residential occupancy, other than sleeping rooms or rooms that are intended for combination sleeping/living, bathrooms, toilet compartments, kitchens, closets, halls, storage or utility spaces, and similar areas. [101, 2021] (SIG-HOU)

3.3.160 Loading Capacity. The maximum number of discrete elements of fire alarm systems permitted to be used in a particular configuration. (SIG-SSS)

3.3.161 Local Energy-Type Auxiliary Alarm System. See 3.3.229, Public Emergency Alarm Reporting System.

3.3.162* Local Operating Console (LOC). Equipment used by authorized personnel and emergency responders to activate and operate an in-building mass notification system. (SIG-ECS)

3.3.163 Lodging or Rooming House. A building or portion thereof that does not qualify as a one- or two-family dwelling, that provides sleeping accommodations for a total of 16 or

fewer people on a transient or permanent basis, without personal care services, with or without meals, but without separate cooking facilities for individual occupants. [101, 2021] (SIG-HOU)

3.3.164 Loss of Power. The reduction of available voltage at the load below the point at which equipment can function as designed. (SIG-FUN)

3.3.165 Low-Power Radio Transmitter/Transceiver. Any device that communicates with associated control/receiving equipment or other transceivers by low-power radio signals. (SIG-PRO)

3.3.166 Maintenance. Work, including, but not limited to, repair, replacement, and service, performed to ensure that equipment operates properly. (SIG-TMS)

3.3.167 Malicious Alarm. See 3.3.326.1, Malicious Alarm.

3.3.168* Managed Facilities-Based Voice Network (MFVN). A physical facilities-based network capable of transmitting real-time signals with formats unchanged that is managed, operated, and maintained by the service provider to ensure service quality and reliability from the subscriber location to the interconnection point with other MFVN peer networks or the supervising station. (SIG-SSS)

3.3.169 Manual Fire Alarm Box. See 3.3.12, Alarm Box.

3.3.170* Manufacturer's Published Instructions. Published installation and operating documentation provided for each product or component. The documentation includes directions and necessary information for the intended installation, maintenance, and operation of the product or component. (SIG-TMS)

3.3.171* Mass Notification Priority Mode. The mode of operation whereby all fire alarm occupant notification is superseded by emergency mass notification action. (SIG-ECS)

3.3.172* Mass Notification System. See 3.3.97.1.3, In-Building Mass Notification System. (SIG-PRO)

3.3.173 Master Box. See 3.3.12, Alarm Box.

3.3.174 Master Control Station (Two-Way Emergency Communications Systems for Rescue Assistance). A system component providing an operator interface to receive and view calls from remote call stations and initiate two-way communications between the master control station operator and persons at the call station location. (SIG-ECS)

3.3.175 Master Fire Alarm Control Unit. See 3.3.115, Fire Alarm Control Unit (FACU).

3.3.176* Minimum Hearing Distance. The closest distance that an occupant's ear can be to an audible appliance. (SIG-NAS)

3.3.177 Multi-Criteria Detector. See 3.3.77, Detector.

3.3.178 Multiple-Station Alarm. A single-station alarm capable of being interconnected to one or more additional alarms so that the actuation of one causes the appropriate alarm signal to operate in all interconnected alarms. (SIG-HOU)

3.3.179 Multiplexing. A signaling method characterized by simultaneous or sequential transmission, or both, and reception of multiple signals on a signaling line circuit, a transmis-

sion channel, or a communications channel, including means for positively identifying each signal. (SIG-SSS)

3.3.180 Multi-Sensor Detector. See 3.3.77, Detector.

3.3.181 Municipal Fire Alarm Box (Street Box). A publicly accessible alarm box. (See 3.3.12, Alarm Box.)

3.3.182 Municipal Fire Alarm System. See 3.3.118, Fire Alarm System.

3.3.183 Net-Centric Alerting System (NCAS). A net-centric alerting system incorporates web-based management and alert activation application through which all operators and administrators could gain access to the system's capabilities based on the users' permissions and the defined access policy. (SIG-ECS)

3.3.184 Network.

3.3.184.1 Wired Network (Public Emergency Alarm Reporting Systems). The method of communications used in a public emergency alarm reporting system that consists of two or more points that are connected by physical conductors. (SIG-PRS)

3.3.184.2 Wireless Network (Public Emergency Alarm Reporting Systems). The method of communications used in a public emergency alarm reporting system that consists of two or more points that are not connected by physical conductors. (SIG-PRS)

3.3.185 Network Architecture. The physical and logical design of a network, and the inherent ability of the design to carry data from one point to another. (SIG-ECS)

3.3.186 Noncontiguous Property. See 3.3.221, Property.

3.3.187* Nonrequired. A system component or group of components that is installed at the option of the owner, and is not installed due to a building or fire code requirement. (SIG-FUN)

3.3.188 Nonrestorable Initiating Device. See 3.3.148, Initiating Device.

3.3.189 Notification Appliance. A fire alarm system component such as a bell, horn, loudspeaker, visual notification appliance, or text display that provides audible, tactile, or visual outputs, or any combination thereof. (SIG-NAS)

3.3.189.1 Audible Notification Appliance. A notification appliance that alerts by the sense of hearing. (SIG-NAS)

3.3.189.1.1 Exit Marking Audible Notification Appliance. An audible notification appliance that marks building exits and areas of refuge by the sense of hearing for the purpose of evacuation or relocation. (SIG-NAS)

3.3.189.1.2* Textual Audible Notification Appliance. A notification appliance that conveys a stream of audible information. (SIG-NAS)

3.3.189.2 Tactile Notification Appliance. A notification appliance that alerts by the sense of touch or vibration. (SIG-NAS)

3.3.189.3 Visual Notification Appliance. A notification appliance that alerts by the sense of sight. (SIG-NAS)

3.3.189.3.1* Textual Visual Notification Appliance. A notification appliance that conveys a stream of visual information

that displays an alphanumeric or pictorial message. (SIG-NAS)

3.3.190 Notification Appliance Circuit. A circuit or path directly connected to a notification appliance(s). (SIG-PRO)

3.3.191 Notification Zone. See 3.3.339, Zone.

3.3.192 Nuisance Alarm. See 3.3.326.2, Nuisance Alarm.

3.3.193* Observation. A suggested correction, improvement, or enhancement to the fire alarm or signaling system that is not considered to be an impairment or deficiency. (SIG-TMS)

3.3.194* Occupiable. A room or enclosed space designed for human occupancy. (SIG-FUN)

3.3.195 Occupiable Area. An area of a facility occupied by people on a regular basis. (SIG-FUN)

3.3.196* Octave Band. The bandwidth of a filter that comprises a frequency range of a factor of 2. (SIG-NAS)

3.3.196.1 One-Third Octave Band. The bandwidth of a filter that comprises a frequency range of a factor of $2^{1/3}$. (SIG-NAS)

3.3.197 Off-Hook. To access a communications network in preparation for connecting a telephone. (SIG-SSS)

3.3.198 One-Third Octave Band. See 3.3.196, Octave Band.

3.3.199 One-Way Emergency Communications System. See 3.3.97, Emergency Communications System.

3.3.200 On-Hook. To disconnect from a managed facilities-based voice network. (SIG-SSS)

3.3.201 Operating Mode.

3.3.201.1 Private Operating Mode. Audible or visual signaling only to those persons directly concerned with the implementation and direction of emergency action initiation and procedure in the area protected by the fire alarm system. (SIG-NAS)

3.3.201.2 Public Operating Mode. Audible or visual signaling to occupants or inhabitants of the area protected by the fire alarm system. (SIG-NAS)

3.3.202 Other Fire Detectors. See 3.3.77, Detector.

3.3.203* Ownership. Any property or building or its contents under legal control by the occupant, by contract, or by holding of a title or deed. (SIG-SSS)

3.3.204 Paging System. A system intended to page one or more persons by such means as voice over loudspeaker, coded audible signals or visual signals, or lamp annunciators. (SIG-PRO)

3.3.205 Path (Pathways). Any circuit, conductor, optical fiber, radio carrier, or other means connecting two or more locations. (SIG-PRO)

3.3.206 Pathway Survivability. The ability of any conductor, optical fiber, radio carrier, or other means for transmitting system information to remain operational during fire conditions. (SIG-ECS)

3.3.207 Permanent Visual Record (Recording). An immediately readable, not easily alterable, print, slash, or punch record of all occurrences of status change. (SIG-SSS)

3.3.208 Personnel.

3.3.208.1 Inspection Personnel. Individuals who conduct a visual examination of a system or portion thereof to verify that it appears to be in operating condition, in proper location, and is free of physical damage or conditions that impair operation. (SIG-TMS)

3.3.208.2 Service Personnel. Individuals who perform those procedures, adjustments, replacement of components, system programming, and maintenance as described in the manufacturer's service instructions that can affect any aspect of the performance of the system. (SIG-TMS)

3.3.208.3 System Designer. Individual responsible for the development of fire alarm or signaling system plans and specifications in accordance with this Code. (SIG-FUN)

3.3.208.4 System Installer. Individual responsible for the proper installation of fire alarm or signaling systems in accordance with plans, specifications, and manufacturer's requirements. (SIG-FUN)

3.3.208.5 Testing Personnel. Individuals who perform procedures used to determine the status of a system as intended by conducting acceptance, reacceptance, or periodic physical checks on systems. (SIG-TMS)

3.3.209 Photoelectric Light Obscuration Smoke Detection. See 3.3.285, Smoke Detection.

3.3.210 Photoelectric Light-Scattering Smoke Detection. See 3.3.285, Smoke Detection.

3.3.211 Plant. One or more buildings under the same ownership or control on a single property. (SIG-SSS)

3.3.212 Pneumatic Rate-of-Rise Tubing Heat Detector. See 3.3.77, Detector.

3.3.213 Positive Alarm Sequence. An automatic sequence that results in an alarm signal, even when manually delayed for investigation, unless the system is reset. (SIG-PRO)

3.3.214 Power Supply. A source of electrical operating power, including the circuits and terminations connecting it to the dependent system components. (SIG-FUN)

3.3.215 Primary Battery (Dry Cell). A nonrechargeable battery requiring periodic replacement. (SIG-FUN)

3.3.216 Primary Trunk Facility. That part of a transmission channel connecting all leg facilities to a supervising or subsidiary station. (SIG-SSS)

3.3.217 Prime Contractor. The listed central station or listed alarm service local company that is contractually responsible for providing central station services to a subscriber as required by this Code. (SIG-SSS)

3.3.218 Private Operating Mode. See 3.3.201, Operating Mode.

3.3.219 Profound Hearing Loss. See 3.3.135, Hearing Loss.

3.3.220 Projected Beam-Type Detector. See 3.3.77, Detector.

3.3.221 Property.

3.3.221.1 Contiguous Property. A single-owner or single-user protected premises on a continuous plot of ground, including any buildings thereon, that is not separated by a public

thoroughfare, transportation right-of-way, property owned or used by others, or body of water not under the same ownership. (SIG-SSS)

3.3.221.2 Noncontiguous Property. An owner- or user-protected premises where two or more protected premises, controlled by the same owner or user, are separated by a public thoroughfare, body of water, transportation right-of-way, or property owned or used by others. (SIG-SSS)

3.3.222 Proprietary Supervising Station. See 3.3.301, Supervising Station.

3.3.223 Proprietary Supervising Station Alarm System. See 3.3.302, Supervising Station Alarm Systems.

3.3.224 Proprietary Supervising Station Service. See 3.3.303, Supervising Station Service.

3.3.225 Protected Premises. The physical location protected by a fire alarm system. (SIG-PRO)

3.3.226 Protected Premises (Local) Control Unit. See 3.3.115, Fire Alarm Control Unit (FACU).

3.3.227 Protected Premises (Local) Fire Alarm System. See 3.3.118, Fire Alarm System.

3.3.228 Public Address System. An electronic amplification system with a mixer, amplifier, and loudspeakers, used to reinforce a given sound and distributing the “sound” to the general public around a building. (SIG-ECS)

3.3.229 Public Emergency Alarm Reporting System. A system of alarm-initiating devices, transmitting and receiving equipment, and communications infrastructure — other than a public telephone network — used to communicate with the communications center to provide any combination of manual or auxiliary alarm service. (SIG-PRS)

3.3.229.1* Auxiliary Alarm System. A protected premises fire alarm system or other emergency system at the protected premises and the system used to connect the protected premises system to a public emergency alarm reporting system for transmitting an alarm to the communications center. (SIG-PRS)

3.3.229.1.1 Local Energy-Type Auxiliary Alarm System. An auxiliary system that employs a locally complete arrangement of parts, initiating devices, relays, power supply, and associated components to automatically activate a master box or auxiliary box over circuits that are electrically isolated from the public emergency alarm reporting system circuits. (SIG-PRS)

3.3.229.2 Type A Public Emergency Alarm Reporting System. A system in which an alarm from an alarm box is received and is retransmitted to an emergency response facility either manually or automatically. (SIG-PRS)

3.3.229.3 Type B Public Emergency Alarm Reporting System. A system in which an alarm from an alarm box is automatically transmitted to an emergency response facility and, if used, is transmitted to supplementary alerting devices. (SIG-PRS)

3.3.230 Public Operating Mode. See 3.3.201, Operating Mode.

3.3.231 Public Safety Agency. A fire, emergency medical services, or law enforcement agency. (SIG-ECS)

3.3.232 Public Safety Radio Enhancement System. A system installed to assure the effective operation of radio communication systems used by fire, emergency medical services, or law enforcement agencies. (SIG-ECS)

3.3.233 Public Safety Radio System. A radio communication system used by fire, emergency medical services, or law enforcement agencies. (SIG-ECS)

3.3.234 Public Switched Telephone Network. See 3.3.309, Switched Telephone Network.

3.3.235 Publicly Accessible Alarm Box. See 3.3.12, Alarm Box.

3.3.236* Qualified. A competent and capable person or company that has met the requirements and training for a given field acceptable to the authority having jurisdiction. (SIG-TMS)

3.3.237 Radiant Energy-Sensing Fire Detector. See 3.3.77, Detector.

3.3.238 Radio Alarm Repeater Station Receiver (RARSR). A system component that receives radio signals and resides at a repeater station that is located at a remote receiving location. (SIG-SSS)

3.3.239 Radio Alarm Supervising Station Receiver (RASSR). A system component that receives data and annunciates that data at the supervising station. (SIG-SSS)

3.3.240 Radio Alarm System (RAS). A system in which signals are transmitted from a radio alarm transmitter (RAT) located at a protected premises through a radio channel to two or more radio alarm repeater station receivers (RARSR) and that are annunciated by a radio alarm supervising station receiver (RASSR) located at the supervising station. (SIG-SSS)

3.3.241 Radio Alarm Transmitter (RAT). A system component at the protected premises to which initiating devices or groups of devices are connected that transmits signals indicating a status change of the initiating devices. (SIG-SSS)

3.3.242 Radio Channel. See 3.3.50, Channel.

3.3.243 Radio Communications. See 3.3.64, Communications, Radio.

3.3.244* Radio Frequency. The number of electromagnetic wave frequency cycles transmitted by a radio in 1 second. [1221, 2019] (SIG-PRS)

3.3.245 Rate Compensation Detector. See 3.3.77, Detector.

3.3.246 Rate-of-Rise Detector. See 3.3.77, Detector.

3.3.247 Record Drawings. Drawings (as-built) that document the location of all devices, appliances, wiring sequences, wiring methods, and connections of the components of the system as installed. (SIG-FUN)

3.3.248 Record of Completion. A document that acknowledges the features of installation, operation (performance), service, and equipment with representation by the property owner, system installer, system supplier, service organization, and the authority having jurisdiction. (SIG-FUN)

3.3.249 Releasing Fire Alarm System. See 3.3.118, Fire Alarm System.

3.3.250 Releasing Service Fire Alarm Control Unit. See 3.3.115, Fire Alarm Control Unit (FACU).

3.3.251 Relocation. The directed movement of occupants from one area to another area within the same building. (SIG-PRO)

3.3.252* Remote Access. Communications between a remote device and a component of a fire alarm or signaling system. (SIG-PRO)

3.3.253 Remote Call Station (Two-Way Emergency Communications Systems for Rescue Assistance). A system component providing a call button used to alert a master control station operator of a person requiring assistance, capabilities providing hands-free two-way communications between the person and operator, and visual indication of both call activation and active two-way communications. (SIG-ECS)

3.3.254 Remote Supervising Station. See 3.3.301, Supervising Station.

3.3.255 Remote Supervising Station Alarm System. See 3.3.302, Supervising Station Alarm Systems.

3.3.256 Remote Supervising Station Service. See 3.3.303, Supervising Station Service.

3.3.257 Repeater Station. The location of the equipment needed to relay signals between supervising stations, subsidiary stations, and protected premises. (SIG-SSS)

3.3.258 Reset. A control function that attempts to return a system or device to its normal, nonalarm state. (SIG-FUN)

3.3.259 Residential Board and Care Occupancy. An occupancy used for lodging and boarding of four or more residents, not related by blood or marriage to the owners or operators, for the purpose of providing personal care services. [101, 2021] (SIG-HOU)

3.3.260 Residential Occupancy. An occupancy that provides sleeping accommodations for purposes other than health care or detention and correctional. [101, 2021] (SIG-HOU)

3.3.261* Response. Actions performed upon the receipt of a signal. (SIG-FUN)

3.3.261.1* Alarm Response. The response to the receipt of an alarm signal. (SIG-FUN)

3.3.261.2* Pre-Alarm Response. The response to the receipt of a pre-alarm signal. (SIG-FUN)

3.3.261.3* Supervisory Response. The response to the receipt of a supervisory signal. (SIG-FUN)

3.3.261.4* Trouble Response. The response to the receipt of a trouble signal. (SIG-FUN)

3.3.262 Response Time Index (RTI). A numerical value that represents the thermal response sensitivity of the sensing element in a heat detector, sprinkler, or other heat-sensing fire detection device to the fire environment in terms of gas temperature and velocity versus time. (See B.3.3.3.7.) (SIG-IDS)

3.3.263 Restorable Initiating Device. See 3.3.148, Initiating Device.

3.3.264 Risk Analysis. A process to characterize the likelihood, vulnerability, and magnitude of incidents associated with natural, technological, and manmade disasters and other emer-

gencies that address scenarios of concern, their probability, and their potential consequences. (SIG-ECS)

3.3.265 Runner. A person other than the required number of operators on duty at central, supervising, or runner stations (or otherwise in contact with these stations) available for prompt dispatching, when necessary, to the protected premises. (SIG-SSS)

3.3.266 Runner Service. The service provided by a runner at the protected premises, including restoration, resetting, and silencing of all equipment transmitting fire alarm or supervisory or trouble signals to an off-premises location. (SIG-SSS)

3.3.267 Secondary Trunk Facility. That part of a transmission channel connecting two or more, but fewer than all, leg facilities to a primary trunk facility. (SIG-SSS)

3.3.268 Selective Talk Mode. See 3.3.313, Talk Mode.

3.3.269 Service Personnel. See 3.3.208, Personnel.

3.3.270 Shapes of Ceilings. The shapes of ceilings can be classified as sloping or smooth. (SIG-IDS)

3.3.271* Shop Drawings. Documents that provide information pertaining to the system necessary for installation of a fire alarm and/or signaling system. (SIG-FUN)

3.3.272* Signal. An indication of a condition communicated by electrical, visible, visual, audible, wireless, or other means. (SIG-FUN)

3.3.272.1* Alarm Signal. A signal that results from the manual or automatic detection of an alarm condition. (SIG-FUN)

3.3.272.2 Carbon Monoxide Alarm Signal. A signal indicating a concentration of carbon monoxide at or above the alarm threshold that could pose a risk to the life safety of the occupants and that requires immediate action. (SIG-FUN)

3.3.272.3 Delinquency Signal. A signal indicating a supervisory condition and the need for action in connection with the supervision of guards or system attendants. (SIG-PRO)

3.3.272.4 Evacuation Signal. A distinctive alarm signal intended to be recognized by the occupants as requiring evacuation of the building. (SIG-PRO)

3.3.272.5* Fire Alarm Signal. A signal that results from the manual or automatic detection of a fire alarm condition. (SIG-FUN)

3.3.272.6* Guard's Tour Supervisory Signal. A signal generated when a guard on patrol has actuated a guard's tour reporting station. (SIG-PRO)

3.3.272.7* Pre-Alarm Signal. A signal that results from the detection of a pre-alarm condition. (SIG-FUN)

3.3.272.8 Restoration Signal. A signal that results from the return to normal condition of an initiating device, system element, or system. (SIG-FUN)

3.3.272.9* Supervisory Signal. A signal that results from the detection of a supervisory condition. (SIG-FUN)

3.3.272.10* Trouble Signal. A signal that results from the detection of a trouble condition. (SIG-FUN)

3.3.273 Signal Transmission Sequence. A DACT that obtains dial tone, dials the number(s) of the DACR, obtains verification that the DACR is ready to receive signals, transmits the signals, and receives acknowledgment that the DACR has accepted that signal before disconnecting (going on-hook). (SIG-SSS)

3.3.274 Signaling Line Circuit. A circuit path between any combination of addressable appliances or devices, circuit interfaces, control units, or transmitters over which multiple system input signals or output signals or both are carried. (SIG-PRO)

3.3.275 Signaling Line Circuit Interface. See 3.3.153, Interface.

3.3.276 Signaling System. A system consisting of one or more of the following: carbon monoxide detection equipment and system, supervising station alarm system, public emergency alarm reporting system, or emergency communications system. (SIG-PRO)

3.3.277 Signaling Zone. See 3.3.339, Zone.

3.3.278 Single-Station Alarm. A detector comprising an assembly that incorporates a sensor, control components, and an alarm notification appliance in one unit operated from a power source either located in the unit or obtained at the point of installation. (SIG-HOU)

3.3.279 Site-Specific Software. See 3.3.288, Software.

3.3.280* Sleeping Area. The area of a dwelling unit where the bedrooms or sleeping rooms are located. (SIG-HOU)

3.3.281 Sloping Ceiling. See 3.3.40, Ceiling.

3.3.282 Sloping Peaked-Type Ceiling. See 3.3.40, Ceiling.

3.3.283 Sloping Shed-Type Ceiling. See 3.3.40, Ceiling.

3.3.284 Smoke Alarm. A single or multiple-station alarm responsive to smoke. (SIG-HOU)

3.3.285 Smoke Detection.

3.3.285.1 Cloud Chamber Smoke Detection. The principle of using an air sample drawn from the protected area into a high-humidity chamber combined with a lowering of chamber pressure to create an environment in which the resultant moisture in the air condenses on any smoke particles present, forming a cloud. The cloud density is measured by a photoelectric principle. The density signal is processed and used to convey an alarm condition when it meets preset criteria. (SIG-IDS)

3.3.285.2* Ionization Smoke Detection. The principle of using a small amount of radioactive material to ionize the air between two differentially charged electrodes to sense the presence of smoke particles. The presence of smoke particles decreases the conductance of the air by reducing ion mobility, which will produce an alarm condition when it meets preset criteria. (SIG-IDS)

3.3.285.3* Photoelectric Light Obscuration Smoke Detection. The principle of using a light source and a photosensitive sensor onto which the principal portion of the source emissions is focused. When smoke particles enter the light path, some of the light is scattered and some is absorbed, thereby reducing the light reaching the receiving sensor. The light reduction signal is processed and used to convey an alarm condition when it meets preset criteria. (SIG-IDS)

3.3.285.4* Photoelectric Light-Scattering Smoke Detection. The principle of using a light source and a photosensitive sensor arranged so that the rays from the light source do not normally fall onto the photosensitive sensor. When smoke particles enter the light path, some of the light is scattered by reflection and refraction onto the sensor. The light signal is processed and used to convey an alarm condition when it meets preset criteria. (SIG-IDS)

3.3.285.5* Video Image Smoke Detection (VISD). The principle of using automatic analysis of real-time video images to detect the presence of smoke. (SIG-IDS)

3.3.286 Smoke Detector. See 3.3.77, Detector.

3.3.287 Smooth Ceiling. See 3.3.42, Ceiling Surfaces.

3.3.288 Software. Programs, instruments, procedures, data, and the like that are executed by a central processing unit of a product and that influences the functional performance of that product. For the purpose of this Code, software is one of two types: executive software and site-specific software. (SIG-TMS)

3.3.288.1 Executive Software. Control and supervisory program that manages the execution of all other programs and directly or indirectly causes the required functions of the product to be performed. Executive software is sometimes referred to as firmware, BIOS, or executive program. (SIG-TMS)

3.3.288.2 Site-Specific Software. Program that is separate from, but controlled by, the executive software that allows inputs, outputs, and system configuration to be selectively defined to meet the needs of a specific installation. Typically it defines the type and quantity of hardware, customized labels, and the specific operating features of a system. (SIG-TMS)

3.3.289 Solid Joist Construction. See 3.3.42, Ceiling Surfaces.

3.3.290 Spacing. A horizontally measured dimension used as a criterion in determining the allowable coverage of devices. (SIG-FUN)

3.3.291* Spark. A moving particle of solid material that emits radiant energy due to either its temperature or the process of combustion on its surface. [654, 2020] (SIG-IDS)

3.3.292 Spark/Ember Detector. See 3.3.77, Detector.

3.3.293 Spark/Ember Detector Sensitivity. The number of watts (or the fraction of a watt) of radiant power from a point source radiator, applied as a unit step signal at the wavelength of maximum detector sensitivity, necessary to produce an alarm signal from the detector within the specified response time. (SIG-IDS)

3.3.294 Spot-Type Detector. See 3.3.77, Detector.

3.3.295 Stakeholder. Any individual, group, or organization that might affect, be affected by, or perceive itself to be affected by the risk. (SIG-ECS)

3.3.296 Stored-Energy Emergency Power Supply Systems (SEPPS). Equipment that receives electrical energy and then provides a means to store that energy in some form for later use in order to supply electrical energy when needed. (SIG-FUN)

3.3.297 Stratification. The phenomenon where the upward movement of smoke and gases ceases due to the loss of buoyancy. (SIG-IDS)

3.3.298 Subscriber. The recipient of a contractual supervising station signal service(s). In case of multiple, noncontiguous properties having single ownership, the term refers to each protected premises or its local management. (SIG-SSS)

3.3.299 Subsidiary Station. A subsidiary station is a normally unattended location that is remote from the supervising station and is linked by a communications channel(s) to the supervising station. Interconnection of signals on one or more transmission channels from protected premises with a communications channel(s) to the supervising station is performed at this location. (SIG-SSS)

3.3.300 Supervised Notification Appliance Control Circuit. An output circuit that is monitored for integrity and used exclusively to activate control equipment for notification appliance circuits. (SIG-FUN)

3.3.301 Supervising Station. A facility that receives signals from alarm systems and at which personnel are in attendance at all times to respond to these signals. (SIG-SSS)

3.3.301.1 Central Supervising Station. A supervising station that is listed for central station service and that also commonly provides less stringent supervising station services such as remote supervising services. (SIG-SSS)

3.3.301.2 Proprietary Supervising Station. A supervising station under the same ownership as the protected premises fire alarm system(s) that it supervises (monitors) and to which alarm, supervisory, or trouble signals are received and where personnel are in attendance at all times to supervise operation and investigate signals. (SIG-SSS)

3.3.301.3 Remote Supervising Station. A supervising station to which alarm, supervisory, or trouble signals or any combination of those signals emanating from protected premises fire alarm systems are received and where personnel are in attendance at all times to respond. (SIG-SSS)

3.3.302 Supervising Station Alarm Systems.

3.3.302.1 Central Station Service Alarm System. A system or group of systems in which the operations of circuits and devices are transmitted automatically to, recorded in, maintained by, and supervised from a listed central station that has competent and experienced servers and operators who, upon receipt of a signal, take such action as required by this Code. Such service is to be controlled and operated by a person, firm, or corporation whose business is the furnishing, maintaining, or monitoring of supervised alarm systems. (SIG-SSS)

3.3.302.2 Proprietary Supervising Station Alarm System. An installation of an alarm system that serves contiguous and noncontiguous properties, under one ownership, from a proprietary supervising station located at the protected premises, or at one of multiple noncontiguous protected premises, at which trained, competent personnel are in constant attendance. This includes the protected premises fire alarm system(s); proprietary supervising station; power supplies; signal-initiating devices; initiating device circuits; signal notification appliances; equipment for the automatic, permanent visual recording of signals; and equipment for

initiating the operation of emergency building control services. (SIG-SSS)

3.3.302.3 Remote Supervising Station Alarm System. A protected premises fire alarm system (exclusive of any connected to a public emergency reporting system) in which alarm, supervisory, or trouble signals are transmitted automatically to, recorded in, and supervised from a remote supervising station that has competent and experienced servers and operators who, upon receipt of a signal, take such action as required by this Code. (SIG-SSS)

3.3.303 Supervising Station Service.

3.3.303.1 Central Station Service. The use of a system or a group of systems including the protected premises fire alarm system(s) in which the operations of circuits and devices are signaled to, recorded in, and supervised from a listed central station that has competent and experienced operators who, upon receipt of a signal, take such action as required by this Code. Related activities at the protected premises, such as equipment installation, inspection, testing, maintenance, and runner service, are the responsibility of the central station or a listed alarm service local company. Central station service is controlled and operated by a person, firm, or corporation whose business is the furnishing of such contracted services or whose properties are the protected premises. (SIG-SSS)

3.3.303.2 Proprietary Supervising Station Service. The use of a system or a group of systems including the protected premises fire alarm system(s) in which the operations of circuits and devices are signaled to, recorded in, and supervised from a supervising station under the same ownership as the protected premises that has competent and experienced operators who, upon receipt of a signal, take such action as required by this Code. Related activities at the protected premises, such as equipment installation, inspection, testing, maintenance, and runner service, are the responsibility of the owner. Proprietary supervising station service is controlled and operated by the entity whose properties are the protected premises. (SIG-SSS)

3.3.303.3 Remote Supervising Station Service. The use of a system including the protected premises fire alarm system(s) in which the operations of circuits and devices are signaled to, recorded in, and supervised from a supervising station that has competent and experienced operators who, upon receipt of a signal, take such action as required by this Code. Related activities at the protected premises, such as equipment installation, inspection, testing, and maintenance, are the responsibility of the owner. (SIG-SSS)

3.3.304 Supervisory Service. The service required to monitor performance of guard tours and the operative condition of fixed suppression systems or other systems for the protection of life and property. (SIG-PRO)

3.3.305 Supervisory Signal. See 3.3.272, Signal.

3.3.306 Supervisory Signal Initiating Device. See 3.3.148, Initiating Device.

3.3.307 Supplementary. As used in this Code, *supplementary* refers to equipment or operations not required by this Code and designated as such by the authority having jurisdiction. (SIG-FUN)

3.3.308 Surge Protective Device (SPD). A protective device for limiting transient voltages by diverting or limiting surge current. (SIG-PRS)

3.3.309 Switched Telephone Network.

3.3.309.1 Loop Start Telephone Circuit. A loop start telephone circuit is an analog telephone circuit that supports loop start signaling as specified in either Telcordia *GR-506-CORE*, *LATA Switching Systems Generic Requirements: Signaling for Analog Interface*, or Telcordia *GR-909-CORE*, *Fiber in the Loop Systems Generic Requirements*. (SIG-SSS)

3.3.309.2 Public Switched Telephone Network. An assembly of communications equipment and telephone service providers that utilize managed facilities-based voice networks (MFVN) to provide the general public with the ability to establish communications channels via discrete dialing codes. (SIG-SSS)

3.3.310 System Operator. An individual trained to operate and/or initiate a mass notification system. (SIG-ECS)

3.3.311 System Unit. The active subassemblies at the supervising station used for signal receiving, processing, display, or recording of status change signals; a failure of one of these subassemblies causes the loss of a number of alarm signals by that unit. (SIG-SSS)

3.3.312 Tactile Notification Appliance. See 3.3.189, Notification Appliance.

3.3.313 Talk Mode. A means of communications within a building normally dedicated to emergency functions. Commonly referred to as fire fighters' phones, but can also be used for communications with fire fighters and/or fire wardens, including occupants, during an emergency, such as between a fire command center and a designated location, such as a stair, stairwell, or location of emergency equipment. (SIG-ECS)

3.3.313.1 Common Talk Mode. The ability to conference multiple telephones in a single conversation. This is similar to what was referred to as a party line. (SIG-ECS)

3.3.313.2 Selective Talk Mode. The ability for personnel at the fire command center to receive indication of incoming calls and choose which call to answer. This includes the ability to transfer between incoming calls and conference multiple phone locations. Selective calling can include the ability to initiate calls to emergency phone locations. (SIG-ECS)

3.3.314 Testing Personnel. See 3.3.208, Personnel.

3.3.315 Textual Audible Notification Appliance. See 3.3.189, Notification Appliance.

3.3.316 Textual Visual Notification Appliance. See 3.3.189, Notification Appliance.

3.3.317 Transmission Channel. See 3.3.50, Channel.

3.3.318 Transmitter. A system component that provides an interface between signaling line circuits, initiating device circuits, or control units and the transmission channel. (SIG-SSS)

3.3.319 Transponder. A multiplex alarm transmission system functional assembly located at the protected premises. (SIG-SSS)

3.3.320 Trouble Signal. See 3.3.272, Signal.

3.3.321 Two-Way Emergency Communications System. See 3.3.97, Emergency Communications System.

3.3.322 Type A Public Emergency Alarm Reporting System. See 3.3.229, Public Emergency Alarm Reporting System.

3.3.323 Type B Public Emergency Alarm Reporting System. See 3.3.229, Public Emergency Alarm Reporting System.

3.3.324 Unintentional Alarm. See 3.3.326.3, Unintentional Alarm.

3.3.325 Unknown Alarm. See 3.3.326.4, Unknown Alarm.

3.3.326* Unwanted Alarm. Any alarm that occurs that is not the result of a potentially hazardous condition. (SIG-FUN)

3.3.326.1 Malicious Alarm. An unwanted activation of an alarm initiating device caused by a person acting with malice. (SIG-FUN)

3.3.326.2* Nuisance Alarm. An unwanted activation of a signaling system or an alarm initiating device in response to a stimulus or condition that is not the result of a potentially hazardous condition. (SIG-FUN)

3.3.326.3 Unintentional Alarm. An unwanted activation of an alarm initiating device caused by a person acting without malice. (SIG-FUN)

3.3.326.4 Unknown Alarm. An unwanted activation of an alarm initiating device or system output function where the cause has not been identified. (SIG-FUN)

3.3.327 Uplink. The radio signal from the portable public safety subscriber transmitter to the base station receiver. (SIG-ECS)

3.3.328* Video Image Flame Detection (VIFD). The principle of using automatic analysis of real-time video images to detect the presence of flame. (SIG-IDS)

3.3.329 Video Image Smoke Detection (VISD). See 3.3.285, Smoke Detection.

3.3.330 Visual Notification Appliance. See 3.3.189, Notification Appliance.

3.3.331 Voice Message Priority. A scheme for prioritizing mass notification messages. (SIG-ECS)

3.3.332 WATS (Wide Area Telephone Service). Telephone company service allowing reduced costs for certain telephone call arrangements. In-WATS or 800-number service calls can be placed from anywhere in the continental United States to the called party at no cost to the calling party. Out-WATS is a service whereby, for a flat-rate charge, dependent on the total duration of all such calls, a subscriber can make an unlimited number of calls within a prescribed area from a particular telephone terminal without the registration of individual call charges. (SIG-SSS)

3.3.333 Wide-Area Mass Notification System. See 3.3.97, Emergency Communications System.

3.3.334 Wide-Area Signaling. Signaling intended to provide alerting or information to exterior open spaces, such as campuses, neighborhood streets, a city, a town, or a community. (SIG-NAS)

3.3.335 Wireless Control Unit. See 3.3.69, Control Unit.

3.3.336* Wireless Mesh Network (WMN) (as used in Chapter 26). A decentralized communications network made up of radio nodes organized in a mesh topology that does not rely on a pre-existing infrastructure. (SIG-SSS)

3.3.337 Wireless Protection System. A system or a part of a system that can transmit and receive signals without the aid of interconnection wiring. It can consist of either a wireless control unit or a wireless repeater. (SIG-PRO)

3.3.338 Wireless Repeater. A component used to relay signals among wireless devices, appliances, and control units. (SIG-PRO)

3.3.339 Zone. A defined area within the protected premises. A zone can define an area from which a signal can be received, an area to which a signal can be sent, or an area in which a form of control can be executed. (SIG-FUN)

3.3.339.1 Notification Zone. A discrete area of a building, or defined area outside a building, in which people are intended to receive common notification. (SIG-PRO)

3.3.339.2* Signaling Zone. An area consisting of one or more notification zones where identical signals are activated simultaneously. (SIG-ECS)

Chapter 4 Reserved

Chapter 5 Reserved

Chapter 6 Reserved

Chapter 7 Documentation

7.1 Application.

7.1.1 The documentation of the design, acceptance, and completion of new systems required under this Code shall comply with the minimum requirements of this chapter.

7.1.2 The documentation of the alteration, maintenance, and testing of existing systems shall comply with the minimum requirements of this chapter.

7.1.3* Where required by governing laws, codes, or standards, or other parts of this Code, the requirements of this chapter, or portions thereof, shall apply.

7.1.4 Unless noted in Chapter 29 or required by other governing laws, codes, or standards, the documentation requirements of this chapter shall not apply to Chapter 29.

7.1.5 This chapter outlines documentation requirements but does not prohibit additional documentation from being provided.

7.1.6 The requirements of Chapters 10, 11, 12, 14, 17, 18, 21, 23, 24, 26, and 27 shall apply unless otherwise noted in this chapter.

7.2* Minimum Required Documentation.

7.2.1* Where documentation is required by the authority having jurisdiction, the following list shall represent the minimum documentation required for new systems and additions or alterations to existing systems:

- (1)* Written narrative providing intent and system description
- (2) Riser diagram
- (3) Floor plan layout showing locations of all devices, control equipment, and supervising station and shared communications equipment with each sheet showing the following:
 - (a) Point of compass (north arrow)
 - (b) A graphic representation of the scale used
 - (c) Room use identification
 - (d) Building features that will affect the placement of initiating devices and notification appliances
- (4) Sequence of operation in either an input/output matrix or narrative form
- (5) Equipment technical data sheets
- (6) Manufacturers' published instructions, including operation and maintenance instructions
- (7) Battery capacity and safety margin calculations (where batteries are provided)
- (8) Voltage drop calculations for notification appliance circuits
- (9) Mounting height elevation for wall-mounted devices and appliances
- (10) Where occupant notification is required, minimum sound pressure levels that must be produced by the audible notification appliances in applicable covered areas
- (11) Locations of alarm notification appliances, including candela ratings for visual alarm notification appliances
- (12)* Pathway diagrams between the control unit and shared communications equipment within the protected premises
- (13) Completed record of completion in accordance with 7.5.6

- (14) For software-based systems, a copy of site-specific software, including specific instructions on how to obtain the means of system and software access (password)
- (15) Record (as-built) drawings
- (16) Records, record retention, and record maintenance in accordance with Section 7.7
- (17) Completed record of inspection and testing in accordance with 7.6.6

7.2.2 System design documents shall identify the name and contact information of the system designer.

7.2.3 All fire alarm drawings shall use symbols described in NFPA 170 or other symbols acceptable to the authority having jurisdiction.

7.3 Design (Layout) Documentation.

7.3.1* The requirements of Section 7.3 shall apply only where required by other governing laws, codes, or standards; by other parts of this Code; or by project specifications or drawings.

7.3.2* Where required by governing laws, codes, or standards, or other parts of this Code, design (layout) documents shall be prepared prior to installing new systems and additions or alterations to existing systems.

7.3.3* Where required by governing laws, codes, or standards, or other parts of this Code, preliminary plans shall be created.

7.3.3.1 When a design professional is preparing design documents for a new fire alarm or emergency communications system, or modifying an existing system covered by this Code, preliminary bid documents shall be prepared in accordance with Section 7.3.

7.3.3.2 The design professional shall be qualified to prepare fire alarm design documents in accordance with 10.5.1.

7.3.3.3 Design documents shall incorporate performance criteria to ensure that the system will provide a beneficial component to the fire and life safety needs of the owner, occupants, and authority having jurisdiction.

7.3.3.4 Design documents shall clearly communicate the intended performance and functionality expected by all installing contractors.

7.3.3.5 For spaces designated as acoustically distinguishable spaces (ADS) in accordance with 18.4.11, the design professional shall coordinate with other design disciplines so that intelligibility of messages can be achieved utilizing the emergency communications equipment as specified in the design documents and available to contractors/installers.

7.3.3.6 Design documents shall indicate the pathway class designations in accordance with Section 12.3.

7.3.3.7 Design documents shall indicate the pathway survivability level designations in accordance with Section 12.4.

7.3.4 Notification.

7.3.4.1* The requirements of 7.3.4 shall apply only where required by other governing laws, codes, or standards, or by other parts of this Code.

7.3.4.2 Design documents shall include ambient sound pressure levels and audible design sound pressure levels in accordance with 18.4.1.5.4.

7.3.4.3 Analysis and design documentation for narrow band tone signaling shall be in accordance with 18.4.7.4.

7.3.4.4 The documentation of acoustically distinguishable spaces (ADS) shall be in accordance with 18.4.11.

7.3.4.5 Design documents shall specify the rooms and spaces that will have visual notification and those where visual notification will not be provided in accordance with 18.5.2.1.

7.3.4.6 Performance-based design alternatives for visual notification appliance design shall be in accordance with 18.5.5.9.2.

7.3.5 Detection.

7.3.5.1 Heat-Sensing Fire Detectors. Heat detection design documentation shall be provided in accordance with Section 17.6.

7.3.5.2 Smoke-Sensing Fire Detectors. Smoke detection design documentation shall be provided in accordance with Section 17.7.

7.3.5.3 Radiant Energy-Sensing Fire Detectors. Radiant energy detection design documentation shall be provided in accordance with Section 17.8.

7.3.5.4 Gas Detectors. Gas detection design documentation shall be provided in accordance with Section 17.10.

7.3.5.5 Carbon Monoxide Detectors. Carbon monoxide detector design documentation shall be provided in accordance with Section 17.12.

7.3.6* Risk Analysis Documentation.

7.3.6.1 When a risk analysis is required to be prepared, findings and considerations of the risk analysis shall be documented.

7.3.6.2 When determined by the stakeholders, security and protection of the risk analysis documentation shall be in accordance with 7.3.7 and Section 7.7.

7.3.6.3 The risk analysis documentation shall list the various scenarios evaluated and the anticipated outcomes.

7.3.6.4 Risk analyses for mass notification systems shall be documented in accordance with 7.3.6 and 24.3.12.

7.3.7* Performance-Based Design Documentation.

7.3.7.1 Performance-based design documentation for fire detection shall be in accordance with Section 17.3.

7.3.7.2 Performance-based design documentation for visual notification appliances shall be in accordance with 18.5.5.9.2.

7.3.7.3 A copy of approval documentation resulting from performance-based designs shall be included with the completion documentation in accordance with Section 7.5.

7.3.7.4 Performance-based design documentation for mass notification systems shall be in accordance with Section 24.12.

7.3.7.5 Performance-based design documentation for signaling line circuit zoning shall be in accordance with 23.6.1.4 and 23.6.1.5.

7.3.8 Emergency Response Plan Documentation.

7.3.8.1 When an emergency response plan is required to be prepared, such as for a mass notification system, findings of the plan shall be documented.

7.3.8.2 When identified by the stakeholders, security and protection of the emergency response plan documentation shall be in accordance with 7.7.3.

7.3.8.3 The emergency response plan shall document the various scenarios evaluated and the anticipated outcomes.

7.3.9 Evaluation Documentation.

7.3.9.1* Evaluation documentation shall include a signed statement(s) by the person responsible for the design attesting to the evaluation and the resultant technical decision and deeming it reliable and acceptable for the particular application.

7.3.9.2 A copy of the evaluation documentation shall be retained for the life of the system and be maintained with the documents required by 7.7.1.6.

7.4 Shop Drawings (Installation Documentation).

7.4.1* The requirements of Section 7.4 shall apply only where required by other governing laws, codes, or standards; by other parts of this Code; or by project specifications or drawings.

7.4.2* Shop drawings shall be drawn to an indicated scale, on sheets of uniform size, with a plan of each floor.

7.4.3 Shop drawings for fire alarm or emergency communications systems shall provide basic information and shall provide the basis for the record (as-built) drawings required in accordance with 7.5.2.

7.4.4 Shop drawings shall include the following information:

- (1) Name of protected premises, owner, and occupant (where applicable)
- (2) Name of installer or contractor
- (3) Location of protected premises
- (4) Device legend and symbols in accordance with NFPA 170, or other symbols acceptable to the authority having jurisdiction
- (5) Date of issue and any revision dates

7.4.5 Floor plan drawings shall comply with both of the following:

- (1) Be drawn to an indicated scale
- (2) Include the following information, where applicable for the particular system:
 - (a) Floor or level identification
 - (b) Point of compass (indication of north)
 - (c) Graphic scale
 - (d) All walls and doors
 - (e) All partitions extending to within 15 percent of the ceiling height (where applicable and when known)
 - (f) Room and area descriptions
 - (g) System devices/component locations
 - (h) Locations of the system's primary power disconnecting means
 - (i) Locations of monitor/control interfaces to other systems
 - (j) System riser locations

- (k) Type and number of system components/devices on each circuit, on each floor or level
- (l) Type and quantity of conductors and conduit (if used) for each circuit
- (m) Identification of any ceiling over 10 ft (3.0 m) in height where automatic fire detection is being proposed
- (n) Details of ceiling geometries, including beams and solid joists, where automatic fire detection is being proposed
- (o) Where known, acoustic properties of spaces
- (p) Pathway class designations in accordance with Section 12.3, including the location of any end-of-line supervisory or power devices that are required by the pathway class
- (q) Pathway survivability level designations in accordance with Section 12.4

7.4.6 System riser diagrams shall comply with both of the following:

- (1) Be coordinated with the floor plans
- (2) Include the following information, where applicable for the particular system:
 - (a) General arrangement of the system in building cross-section
 - (b) Number of risers
 - (c) Type and number of circuits in each riser
 - (d) Type and number of system components/devices on each circuit, on each floor or level
 - (e) Number of conductors for each circuit
 - (f) Pathway class designation in accordance with Section 12.3, including the location of any end-of-line supervisory or power devices that are required by the pathway class
 - (g)* Pathway survivability level designations in accordance with Section 12.4

7.4.7 Control unit diagrams shall be provided for all control equipment (i.e., equipment listed as either a control unit or control unit accessory), power supplies, battery chargers, and annunciators and shall include the following information:

- (1) Identification of the control equipment depicted
- (2) Location(s) of control equipment
- (3) All field wiring terminals and terminal identifications
- (4) All circuits connected to field wiring terminals and circuit identifications
- (5) All indicators and manual controls
- (6) Field connections to supervising station signaling equipment, releasing equipment, or emergency safety control interfaces, where provided

7.4.8 Typical wiring diagrams shall be provided for all initiating devices, notification appliances, remote indicators, annunciators, remote test stations, and end-of-line and power supervisory devices.

7.4.9* A narrative description or input/output matrix of operation shall be provided to describe the sequence of operation.

7.4.10 System calculations shall be included as follows:

- (1) Battery calculations
- (2) Notification appliance circuit voltage drop calculations
- (3) Other required calculations, such as line resistance calculations, where required

7.5 Completion Documentation.

7.5.1* The requirements of Section 7.5 shall apply only where required by other governing laws, codes, or standards; by other parts of this Code; or by project specifications or drawings.

7.5.2 Before requesting final approval of the installation, if required by the authority having jurisdiction, the installing contractor shall furnish a written statement stating that the system has been installed in accordance with approved plans and tested in accordance with the manufacturer's published instructions and the appropriate NFPA requirements.

7.5.3 Delivery.

7.5.3.1 All systems, including new systems and additions or alterations to existing systems, shall include the following documentation:

- (1)* An owner's manual and manufacturer's published instructions covering all system equipment
- (2) Record (as-built) drawings in accordance with 7.5.5
- (3) A completed record of completion form in accordance with 7.5.6
- (4) For software-based systems, record copy of the site-specific software in accordance with 7.5.7

7.5.3.2 The documentation as stated in 7.5.3.1 shall be delivered to the owner or the owner's representative upon final acceptance of the system.

7.5.4 For new emergency communications systems, an owner's manual shall be provided and shall contain the following documentation:

- (1) Detailed narrative description of the system inputs, evacuation signaling, ancillary functions, annunciation, intended sequence of operations, expansion capability, application considerations, and limitations
- (2) Written sequence of operation for the system including an operational input/output matrix
- (3) Operator instructions for basic system operations, including alarm acknowledgment, system reset, interpretation of system output (LEDs, CRT display, and printout), operation of manual evacuation signaling and ancillary function controls, and change of printer paper
- (4) Detailed description of routine maintenance and testing as required and recommended and as would be provided under a maintenance contract, including testing and maintenance instructions for each type of device installed, which includes the following:
 - (a) Listing of the individual system components that require periodic testing and maintenance
 - (b) Step-by-step instructions detailing the requisite testing and maintenance procedures, and the intervals at which those procedures shall be performed, for each type of device installed
 - (c) Schedule that correlates the testing and maintenance procedures that are required by this section
- (5) Service directory, including a list of names and telephone numbers of those who provide service for the system
- (6) Product data sheets for all system equipment

7.5.5 Record Drawings (As-Built).

7.5.5.1 Record drawings shall consist of current updated shop drawings reflecting the actual installation of all system equipment, components, and wiring.

7.5.5.2* A sequence of operations in input/output matrix or narrative form shall be provided with the record drawings to reflect actual programming at the time of completion.

7.5.5.3 Where necessary, revised calculations in accordance with 7.4.10 shall be provided depicting any changes due to installation conditions.

7.5.5.4 Record drawings shall be turned over to the owner with a copy placed inside the documentation cabinet in accordance with Section 7.7.

7.5.5.5* Record drawings shall include approval documentation resulting from variances, performance-based designs, risk analyses, and other system evaluations or variations.

7.5.6 Record of Completion.

7.5.6.1* The record of completion shall be documented in accordance with 7.5.6 using either the record of completion forms, Figure 7.8.2(a) through Figure 7.8.2(f), or an alternative document that contains only the elements of Figure 7.8.2(a) through Figure 7.8.2(f) applicable to the installed system.

7.5.6.2* The record of completion documentation shall be completed by the installing contractor and submitted to the authority having jurisdiction and the owner at the conclusion of the job. The record of completion documentation shall be permitted to be part of the written statement required in 7.5.2 and part of the documents that support the requirements of 7.5.8. When more than one contractor has been responsible for the installation, each contractor shall complete the portions of the documentation for which that contractor has responsibility.

7.5.6.3* The preparation of the record of completion documentation shall be the responsibility of the qualified and experienced person in accordance with 10.5.2.

7.5.6.4 The record of completion documentation shall be updated in accordance with 7.5.6.6 to reflect all system additions or modifications.

7.5.6.5 The updated copy of the record of completion documents shall be maintained in a documentation cabinet in accordance with 7.7.2.

7.5.6.6 Revisions.

7.5.6.6.1 All modifications made after the initial installation shall be recorded on a revised version of the original completion documents, which shall serve as a supplement to the original, unaltered completion documents.

7.5.6.6.2 The revised record of completion document shall include a revision date.

7.5.6.6.3* Where the original or the latest overall system record of completion cannot be obtained, a new system record of completion shall be provided that documents the system configuration as discovered during the current project's scope of work.

7.5.6.7 Electronic Record of Completion.

7.5.6.7.1 Where approved by the authority having jurisdiction, the record of completion shall be permitted to be filed electronically instead of on paper.

7.5.6.7.2 If filed electronically, the record of completion document shall be accessible with standard software and shall be backed up.

7.5.7 Site-Specific Software.

7.5.7.1 For software-based systems, a copy of the site-specific software shall be provided to the system owner or owner's designated representative.

7.5.7.1.1 For all software that connects to and is part of the building life safety network components, the software security access or the means of obtaining the software security access shall be provided to the owner or the owner's designated representative.

7.5.7.1.2 The site-specific software documentation shall include both the user passcode and either the system programming password or specific instructions on how to obtain the programming password from the system manufacturer.

7.5.7.1.3 The passwords provided shall enable currently certified qualified programming personnel to access, edit, modify, and add to the existing system's site-specific software.

7.5.7.2 A copy of the site-specific software shall be stored on-site in nonvolatile memory.

7.5.8* Verification of Compliant Installation.

7.5.8.1 Where required by the authority having jurisdiction, compliance of the completed installation with the requirements of this Code shall be certified by a qualified and impartial third-party organization acceptable to the authority having jurisdiction.

7.5.8.2 Verification of compliant installation shall be performed according to testing requirements and procedures specified in 14.4.1 and 14.4.2.

7.5.8.3 Verification shall ensure that:

- (1) All components and functions are installed and operate per the approved plans and sequence of operation.
- (2) All required system documentation is complete and is archived on site.
- (3) For new supervising station systems, the verification shall also ascertain proper arrangement, transmission, and receipt of all signals required to be transmitted off-premises and shall meet the requirements of 14.4.1 and 14.4.2.
- (4) For existing supervising station systems that are extended, modified, or reconfigured, the verification shall be required for the new work only, and reacceptance testing in accordance with Chapter 14 shall be acceptable.
- (5) Written confirmation has been provided that any required corrective actions have been completed.

7.5.9 Documentation of central station service shall be in accordance with 26.3.4.

7.5.10 Documentation of remote station service shall be in accordance with 26.5.2.

7.6 Inspection, Testing, and Maintenance Documentation.

7.6.1 Test plan documentation shall be provided in accordance with 14.2.10.

7.6.2 Acceptance testing documentation shall be provided in accordance with 14.6.1.

7.6.3 Reacceptance test documentation shall be provided in accordance with 14.6.1.

7.6.4 Periodic inspection and testing documentation shall be provided in accordance with 14.6.2 through 14.6.4.

7.6.5 Impairment documentation shall be provided in accordance with Section 10.21.

7.6.6 Record of Inspection and Testing. The record of all inspections, testing, and maintenance as required by 14.6.2.4 shall be documented using either the record of inspection and testing forms, Figure 7.8.2(g) through Figure 7.8.2(l), or an alternative record that includes all the applicable information shown in Figure 7.8.2(g) through Figure 7.8.2(l).

7.7 Records, Record Retention, and Record Maintenance.

7.7.1 Records.

7.7.1.1 A complete record of the tests and operations of each system shall be kept until the next test and for 1 year thereafter unless more stringent requirements are required elsewhere in this Code.

7.7.1.2* The records shall be available for examination and, if required, reported to the authority having jurisdiction. Archiving of records by any means shall be permitted if hard copies of the records can be provided promptly when requested.

7.7.1.3 If off-premises monitoring is provided, records of all signals, tests, and operations recorded at the supervising station, including the public emergency alarm reporting system, shall be maintained by the off-premise monitoring service provider for not less than 1 year unless more stringent requirements are required elsewhere in this Code.

7.7.1.4 Required documents regarding system design and function shall be maintained for the life of the system.

7.7.1.5 The emergency communications system and fire alarm system as-built plans and other related documentation shall be permitted to be maintained together, including the appearance of both systems on the same drawings.

7.7.1.6 Revisions and alterations to systems shall be recorded and records maintained with the original system design documents.

7.7.2 Document Accessibility.

7.7.2.1 With every new system, a documentation cabinet shall be installed at the system control unit or at another approved location at the protected premises.

7.7.2.2 The documentation cabinet shall be sized so that it can contain all necessary documentation.

7.7.2.3* All record documentation shall be stored in the documentation cabinet. No record documentation shall be stored in the control unit.

7.7.2.4 Where the documentation cabinet is not in the same location as the system control unit, its location shall be identified at the system control unit.

7.7.2.5 The documentation cabinet shall be prominently labeled SYSTEM RECORD DOCUMENTS.

7.7.2.6* The building owner or the building owner's representative shall, on an annual basis, review any electronic documentation media formats and associated interfacing hardware for compatibility and update, if necessary.

7.7.2.7 The contents of the cabinet shall be accessible by authorized personnel only.

7.7.2.8 Emergency communications system and fire alarm system record documentation shall be permitted to be maintained together in the same documentation cabinet.

7.7.3 Document Security.

7.7.3.1 Security for system's documentation shall be determined by the stakeholders.

7.7.3.2* Where such documents cannot be protected from public access, it shall be permitted to remove sensitive information from record documents provided the owner retains complete documentation that will be made accessible to the authority having jurisdiction at an owner designated location.

7.8 Forms.

7.8.1 General.

7.8.1.1* The requirements of Section 7.8 shall apply only where required by other governing laws, codes, or standards; by other parts of this Code; or by project specifications or drawings.

7.8.1.2 Where specific forms are required by other governing laws, codes, or standards; by other parts of this Code; or by project specifications or drawings, form layouts and content that differ from those in Section 7.8 shall be permitted provided that the minimum required content is included.

7.8.2 Forms for Documentation. Forms for documentation shall be as follows:

- (1)* Unless otherwise permitted or required in 7.5.6 or 7.8.1.2, Figure 7.8.2(a) through Figure 7.8.2(f) shall be used to document the record of completion and inspection.
- (2)* Unless otherwise permitted or required in 7.6.6 or 7.8.1.2, Figure 7.8.2(g) through Figure 7.8.2(l) shall be used to document the record of inspection and testing.
- (3) Where a form is required by the AHJ to document the installation and inspection of a household fire alarm system or single- or multiple-station alarms, Figure 7.8.2(m) shall be permitted to be used to document the record of completion and inspection.

SYSTEM RECORD OF COMPLETION

This form is to be completed by the system installation contractor at the time of system acceptance and approval.

It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

Attach additional sheets, data, or calculations as necessary to provide a complete record.

Form Completion Date: _____ Supplemental Pages Attached: _____

1. PROPERTY INFORMATION

Name of property: _____

Address: _____

Description of property: _____

Name of property representative: _____

Address: _____

Phone: _____ Fax: _____ E-mail: _____

2. INSTALLATION, SERVICE, TESTING, AND MONITORING INFORMATION

Installation contractor: _____

Address: _____

Phone: _____ Fax: _____ E-mail: _____

Service organization: _____

Address: _____

Phone: _____ Fax: _____ E-mail: _____

Testing organization: _____

Address: _____

Phone: _____ Fax: _____ E-mail: _____

Effective date for test and inspection contract: _____

Monitoring organization: _____

Address: _____

Phone: _____ Fax: _____ E-mail: _____

Account number: _____ Phone line 1: _____ Phone line 2: _____

Means of transmission: _____

Entity to which alarms are retransmitted: _____ Phone: _____

3. DOCUMENTATION

On-site location of the required record documents and site-specific software: _____

4. DESCRIPTION OF SYSTEM OR SERVICE

This is a: ☐ New system ☐ Modification to existing system Permit number: _____

NFPA 72 edition: _____

4.1 Control Unit

Manufacturer: _____ Model number: _____

4.2 Software and Firmware

Firmware revision number: _____

4.3 Alarm Verification

☐ This system does not incorporate alarm verification.

Number of devices subject to alarm verification: _____ Alarm verification set for _____ seconds

FIGURE 7.8.2(a) System Record of Completion.

SYSTEM RECORD OF COMPLETION (continued)**5. SYSTEM POWER****5.1 Control Unit****5.1.1 Primary Power**

Input voltage of control panel: _____ Control panel amps: _____

Overcurrent protection: Type: _____ Amps: _____

Branch circuit disconnecting means location: _____ Number: _____

5.1.2 Secondary Power

Type of secondary power: _____

Location, if remote from the plant: _____

Calculated capacity of secondary power to drive the system: _____

In standby mode (hours): _____ In alarm mode (minutes): _____

5.2 Control Unit☐ This system does not have power extender panels☐ Power extender panels are listed on supplementary sheet A**6. CIRCUITS AND PATHWAYS**

Pathway Type	Dual Pathway	Separate Pathway	Class	Survivability Level
Signaling Line				
Device Power				
Initiating Device				
Notification Appliance				
Other (specify):				

7. REMOTE ANNUNCIATORS

Type	Location

8. INITIATING DEVICES

Type	Quantity	Addressable or Conventional	Alarm or Supervisory	Sensing Technology
Manual Pull Stations				
Smoke Detectors				
Duct Smoke Detectors				
Heat Detectors				
Gas Detectors				
Carbon Monoxide Detectors				
Waterflow Switches				
Tamper Switches				

FIGURE 7.8.2(a) *Continued*

SYSTEM RECORD OF COMPLETION (continued)**9. NOTIFICATION APPLIANCES**

Type	Quantity	Description	Connected to a Notification Appliance Circuit (NAC)	Connected to a Signaling Line Circuit (SLC)
Audible				
Visual				
Combination Audible and Visual				

10. SYSTEM CONTROL FUNCTIONS

Type	Quantity
Hold-Open Door Releasing Devices	
HVAC Shutdown	
Fire/Smoke Dampers	
Door Unlocking	
Elevator Recall	
Elevator Shunt Trip	

11. INTERCONNECTED SYSTEMS

- ☐ This system does not have interconnected systems.
- ☐ Interconnected systems are listed on supplementary sheet _____.

12. CERTIFICATION AND APPROVALS**12.1 System Installation Contractor**

This system as specified herein has been installed according to all NFPA standards cited herein.

Signed: _____ Printed name: _____ Date: _____
 Organization: _____ Title: _____ Phone: _____

12.2 System Operational Test

This system as specified herein has tested according to all NFPA standards cited herein.

Signed: _____ Printed name: _____ Date: _____
 Organization: _____ Title: _____ Phone: _____

12.3 Acceptance Test

Date and time of acceptance test: _____
 Installing contractor representative: _____
 Testing contractor representative: _____
 Property representative: _____
 AHJ representative: _____

FIGURE 7.8.2(a) Continued

EMERGENCY COMMUNICATIONS SYSTEMS SUPPLEMENTARY RECORD OF COMPLETION

This form is a supplement to the System Record of Completion. It includes systems and components specific to emergency communications systems.

This form is to be completed by the system installation contractor at the time of system acceptance and approval.

It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

Form Completion Date: _____ Number of Supplemental Pages Attached: _____

1. PROPERTY INFORMATION

Name of property: _____

Address: _____

2. DESCRIPTION OF SYSTEM OR SERVICE

☐ Fire alarm with in-building fire emergency voice alarm communications system (EVAC)

☐ Mass notification system

☐ Combination system, with the following components:

☐ Fire alarm ☐ EVACS ☐ MNS ☐ Two-way, in-building, emergency communications system

☐ Other (specify): _____

NFPA 72 edition: _____ Additional description of system(s): _____

2.1 In-Building Fire Emergency Voice Alarm Communications System

Manufacturer: _____ Model number: _____

Number of single voice alarm channels: _____ Number of multiple voice alarm channels: _____

Number of loudspeakers: _____ Number of loudspeaker circuits: _____

Location of amplification and sound processing equipment: _____

Location of paging microphone stations:

Location 1: _____

Location 2: _____

Location 3: _____

2.2 Mass Notification System

2.2.1 System Type:

☐ In-building MNS-combination

☐ In-building MNS ☐ Wide-area MNS ☐ Distributed recipient MNS

☐ Other (specify): _____

FIGURE 7.8.2(b) Emergency Communications System Supplementary Record of Completion.

EMERGENCY COMMUNICATIONS SYSTEMS SUPPLEMENTARY RECORD OF COMPLETION *(continued)*

2. DESCRIPTION OF SYSTEM OR SERVICE *(continued)*

2.2.2 System Features:

- ☐ Combination fire alarm/MNS ☐ MNS autonomous control unit ☐ Wide-area MNS to regional national alerting interface
☐ Local operating console (LOC) ☐ Distributed-recipient MNS (DRMNS) ☐ Wide-area MNS to DRMNS interface
☐ Wide-area MNS to high power loudspeaker array (HPLA) interface ☐ In-building MNS to wide-area MNS interface
☐ Other (specify): _____

2.2.3 MNS Local Operating Consoles

Location 1: _____

Location 2: _____

Location 3: _____

2.2.4 High Power Loudspeaker Arrays

Number of HPLA loudspeaker initiation zones: _____

Location 1: _____

Location 2: _____

Location 3: _____

2.2.5 Mass Notification Devices

Combination fire alarm/MNS visual devices: _____ MNS-only visual devices: _____

Textual signs: _____ Other (describe): _____

Supervision class: _____

2.2.6 Special Hazard Notification

- ☐ This system does not have special suppression predischARGE notification.
☐ MNS systems DO NOT override notification appliances required to provide special suppression predischARGE notification.

3. TWO-WAY EMERGENCY COMMUNICATIONS SYSTEMS

3.1 Telephone System

Number of telephone jacks installed: _____ Number of warden stations installed: _____

Number of telephone handsets stored on site: _____

Type of telephone system installed: ☐ Electrically powered ☐ Sound powered

3.2 Area of Refuge Emergency Communications Systems

Number of stations: _____ Location of central control point: _____

Days and hours when central control point is attended: _____

Location of alternate control point: _____

Days and hours when alternate control point is attended: _____

FIGURE 7.8.2(b) *Continued*

**EMERGENCY COMMUNICATIONS SYSTEMS
SUPPLEMENTARY RECORD OF COMPLETION *(continued)***

3. TWO-WAY EMERGENCY COMMUNICATIONS SYSTEMS *(continued)*

3.3 Elevator Emergency Communications Systems

Number of elevators with stations: _____ Location of central control point: _____

Days and hours when central control point is attended: _____

Location of alternate control point: _____

Days and hours when alternate control point is attended: _____

3.4 Other Two-Way Communications System

Describe: _____

4. CONTROL FUNCTIONS

This system activates the following control functions specific to emergency communications systems:

Type	Quantity
Mass Notification Override of Alarm Signaling Systems or Appliances	

See Main System Record of Completion for additional information, certifications, and approvals.

FIGURE 7.8.2(b) *Continued*

POWER SYSTEMS SUPPLEMENTARY RECORD OF COMPLETION

This form is a supplement to the System Record of Completion. It includes systems and components specific to power systems that incorporate generators, SEPSS systems, remote battery systems, or other complex power systems.

This form is to be completed by the system installation contractor at the time of system acceptance and approval.

It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

Form Completion Date: _____ Number of Supplemental Pages Attached: _____

1. PROPERTY INFORMATION

Name of property: _____

Address: _____

2. SYSTEM POWER

2.1 Control Unit

2.1.1 Primary Power

Input voltage of control panel: _____ Control panel amps: _____

Overcurrent protection: Type: _____ Amps: _____

Location (of primary supply panelboard): _____

Disconnecting means location: _____

2.1.2 Engine-Driven Generator

Location of generator: _____

Location of fuel storage: _____ Type of fuel: _____

2.1.3 Stored-Energy Emergency Power Supply Systems

Equipment powered by SEPSS system: _____

Location of SEPSS system: _____

Calculated capacity of SEPSS batteries to drive the system components connected to it:

In standby mode (hours): _____ In alarm mode (minutes): _____

2.1.4 Batteries

Location: _____ Type: _____ Nominal voltage: _____ Amp/hour rating: _____

Calculated capacity of batteries to drive the system:

In standby mode (hours): _____ In alarm mode (minutes): _____

2.2 In-Building Fire Emergency Voice Alarm Communications System or Mass Notification System

2.2.1 Primary Power

Input voltage of EVACS or MNS panel: _____ EVACS or MNS panel amps: _____

Overcurrent protection: Type: _____ Amps: _____

Location (of primary supply panelboard): _____

Disconnecting means location: _____

FIGURE 7.8.2(c) Power Systems Supplementary Record of Completion.

POWER SYSTEMS
SUPPLEMENTARY RECORD OF COMPLETION (continued)

2. SYSTEM POWER (continued)

2.2.2 Engine-Driven Generator

Location of generator: _____

Location of fuel storage: _____ Type of fuel: _____

2.2.3 Stored-Energy Emergency Power Supply Systems

Equipment powered by SEPSS system: _____

Location of SEPSS system: _____

Calculated capacity of SEPSS batteries to drive the system components connected to it:

In standby mode (hours): _____ In alarm mode (minutes): _____

2.2.4 Batteries

Location: _____ Type: _____ Nominal voltage: _____ Amp/hour rating: _____

Calculated capacity of batteries to drive the system:

In standby mode (hours): _____ In alarm mode (minutes): _____

2.3 Notification Appliance Power Extender Panels

☐ This system does not have power extender panels.

2.3.1 Primary Power

Input voltage of power extender panel(s): _____ Power extender panel amps: _____

Overcurrent protection: Type: _____ Amps: _____

Location (of primary supply panelboard): _____

Disconnecting means location: _____

2.3.2 Engine Driven Generator

Location of generator: _____

Location of fuel storage: _____ Type of fuel: _____

2.3.3 Stored-Energy Emergency Power Supply Systems

Equipment powered by SEPSS system: _____

Location of SEPSS system: _____

Calculated capacity of SEPSS batteries to drive the system components connected to it:

In standby mode (hours): _____ In alarm mode (minutes): _____

2.3.4 Batteries

Location: _____ Type: _____ Nominal voltage: _____ Amp/hour rating: _____

Calculated capacity of batteries to drive the system:

In standby mode (hours): _____ In alarm mode (minutes): _____

FIGURE 7.8.2(c) *Continued*

POWER SYSTEMS SUPPLEMENTARY RECORD OF COMPLETION *(continued)*

2. SYSTEM POWER *(continued)*

2.4 Supervising Station Transmission Equipment

☐ This system does not use transmission equipment within the building powered by any other source than the alarm system control unit.

2.4.1 Primary Power

Input voltage of shared transmission equipment: _____

Shared transmission equipment panel amps: _____

Overcurrent protection: Type: _____ Amps: _____

Location (of primary supply panelboard): _____

Disconnecting means location: _____

2.4.2 Engine Driven Generator

Location of generator: _____

Location of fuel storage: _____ Type of fuel: _____

2.4.3 Energy Storage Systems

Equipment powered by ESS system: _____

Calculated capacity of ESS batteries to drive the system components connected to it:

In standby mode (hours): _____ In alarm mode (minutes): _____

2.4.4 Batteries

Location: _____ Type: _____ Nominal voltage: _____ Amp/hour rating: _____

Calculated capacity of batteries to drive the system:

In standby mode (hours): _____ In alarm mode (minutes): _____

See Main System Record of Completion for additional information, certifications, and approvals.

FIGURE 7.8.2(c) *Continued*

This form is a supplement to the System Record of Completion. It includes a list of types and locations of notification appliance power extender panels.

This form is to be completed by the system installation contractor at the time of system acceptance and approval. It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

1. PROPERTY INFORMATION

Address: _____

[illegible]

NFPA 72

2022 Edition

DEVIATIONS FROM ADOPTED CODES AND STANDARDS SUPPLEMENTARY RECORD OF COMPLETION

This form is a supplement to the System Record of Completion. It enables the designer and/or installer to document and justify deviations from accepted codes or standards.

This form is to be completed by the system installation contractor at the time of system acceptance and approval.

It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

Form Completion Date: _____ Number of Supplemental Pages Attached: _____

1. PROPERTY INFORMATION

Name of property: _____

Address: _____

2. DEVIATIONS FROM ADOPTED CODES OR STANDARDS

Description	Purpose

See Main System Record of Completion for additional information, certifications, and approvals.

FIGURE 7.8.2(f) Deviations from Adopted Codes and Standards Supplementary Record of Completion.

SYSTEM RECORD OF INSPECTION AND TESTING

This form is to be completed by the system inspection and testing contractor at the time of a system test.

It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

Attach additional sheets, data, or calculations as necessary to provide a complete record.

Inspection/Test Start Date/Time: _____ Inspection/Test Completion Date/Time: _____

Supplemental Form(s) Attached: _____ (yes/no)

1. PROPERTY INFORMATION

Name of property: _____

Address: _____

Description of property: _____

Name of property representative: _____

Address: _____

Phone: _____ Fax: _____ E-mail: _____

2. TESTING AND MONITORING INFORMATION

Testing organization: _____

Address: _____

Phone: _____ Fax: _____ E-mail: _____

Monitoring organization: _____

Address: _____

Phone: _____ Fax: _____ E-mail: _____

Account number: _____ Phone line 1: _____ Phone line 2: _____

Means of transmission: _____

Entity to which alarms are retransmitted: _____ Phone: _____

3. DOCUMENTATION

Onsite location of the required record documents and site-specific software: _____

4. DESCRIPTION OF SYSTEM OR SERVICE

4.1 Control Unit

Manufacturer: _____ Model number: _____

4.2 Software Firmware

Firmware revision number: _____

4.3 System Power

4.3.1 Primary (Main) Power

Nominal voltage: _____ Amps: _____ Location: _____

Overcurrent protection type: _____ Amps: _____ Disconnecting means location: _____

FIGURE 7.8.2(g) System Record of Inspection and Testing.

SYSTEM RECORD OF INSPECTION AND TESTING (continued)**4. DESCRIPTION OF SYSTEM OR SERVICE (continued)****4.3.2 Secondary Power**

Type: _____ Location: _____

Battery type (if applicable): _____

Calculated capacity of batteries to drive the system: _____

In standby mode (hours): _____ In alarm mode (minutes): _____

5. NOTIFICATIONS MADE PRIOR TO TESTING

Monitoring organization Contact: _____ Time: _____

Building management Contact: _____ Time: _____

Building occupants Contact: _____ Time: _____

Authority having jurisdiction Contact: _____ Time: _____

Other, if required Contact: _____ Time: _____

6. TESTING RESULTS**6.1 Control Unit and Related Equipment**

Description	Visual Inspection	Functional Test	Comments
Control unit	☐	☐	
Lamps/LEDs/LCDs	☐	☐	
Fuses	☐	☐	
Trouble signals	☐	☐	
Disconnect switches	☐	☐	
Ground-fault monitoring	☐	☐	
Supervision	☐	☐	
Local annunciator	☐	☐	
Remote annunciators	☐	☐	
Remote power panels	☐	☐	

6.2 Secondary Power

Description	Visual Inspection	Functional Test	Comments
Battery condition	☐	☐	
Load voltage	☐	☐	
Discharge test	☐	☐	
Charger test	☐	☐	
Remote panel batteries	☐	☐	
Batteries marked with date of manufacture	☐	☐	

FIGURE 7.8.2(g) Continued

SYSTEM RECORD OF INSPECTION AND TESTING *(continued)*

6. TESTING RESULTS *(continued)*

6.3 Alarm and Supervisory Alarm Initiating Device

Attach supplementary device test sheets for all initiating devices.

6.4 Notification Appliances

Attach supplementary appliance test sheets for all notification appliances.

6.5 Interface Equipment

Attach supplementary interface component test sheets for all interface components.

Circuit Interface / Signaling Line Circuit Interface / Fire Alarm Control Interface

6.6 Supervising Station Monitoring

Description	Yes	No	Time	Comments
Alarm signal	☐	☐		
Alarm restoration	☐	☐		
Trouble signal	☐	☐		
Trouble restoration	☐	☐		
Supervisory signal	☐	☐		
Supervisory restoration	☐	☐		

6.7 Public Emergency Alarm Reporting System

Description	Yes	No	Time	Comments
Alarm signal	☐	☐		
Alarm restoration	☐	☐		
Trouble signal	☐	☐		
Trouble restoration	☐	☐		
Supervisory signal	☐	☐		
Supervisory restoration	☐	☐		

FIGURE 7.8.2(g) *Continued*

*This form is to be completed by the system inspection and testing contractor at the time of the inspection and/or test.
It shall be permitted to modify this form as needed to provide a more complete and/or clear record.
Insert N/A in all unused lines.*

Number of Supplemental Pages Attached: _____

Address: _____

[illegible]

2022 Edition

MASS NOTIFICATION SYSTEM SUPPLEMENTARY RECORD OF INSPECTION AND TESTING

This form is a supplement to the System Record of Inspection and Testing.

It includes a mass notification system test record.

This form is to be completed by the system inspection and testing contractor at the time of the inspection and/or test.

It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

Inspection/Test Start Date/Time: _____ Inspection/Test Completion Date/Time: _____

Number of Supplemental Pages Attached: _____

1. PROPERTY INFORMATION

Name of property: _____

Address: _____

2. MASS NOTIFICATION SYSTEM

2.1 System Type

☐ In-building MNS—combination

☐ In-building MNS—stand alone ☐ Wide-area MNS ☐ Distributed recipient MNS

☐ Other (specify): _____

2.2 System Features

☐ Combination fire alarm/MNS ☐ MNS ACU only ☐ Wide-area MNS to regional national alerting interface

☐ Local operating console (LOC) ☐ Direct recipient MNS (DRMNS) ☐ Wide-area MNS to DRMNS interface

☐ Wide-area MNS to high-power loudspeaker array (HPLA) interface ☐ In-building MNS to wide-area MNS interface

☐ Other (specify): _____

3. IN-BUILDING MASS NOTIFICATION SYSTEM

3.1 Primary Power

Input voltage of MNS panel: _____ MNS panel amps: _____

3.2 Engine-Driven Generator ☐ This system does not have a generator.

Location of generator: _____

Location of fuel storage: _____ Type of fuel: _____

3.3 Stored-Energy Emergency Power Supply Systems ☐ This system does not have an SEPSS.

Equipment powered by an SEPSS: _____

Location of SEPSS: _____

Calculated capacity of SEPSS batteries to drive the system components connected to it:

In standby mode (hours): _____ In alarm mode (minutes): _____

3.4 Batteries

Location: _____ Type: _____ Nominal voltage: _____ Amp/hour rating: _____

Calculated capacity of batteries to drive the system:

In standby mode (hours): _____ In alarm mode (minutes): _____

☐ Batteries are marked with date of manufacture.

FIGURE 7.8.2(j) Mass Notification System Supplementary Record of Inspection and Testing.

**MASS NOTIFICATION SYSTEM
SUPPLEMENTARY RECORD OF INSPECTION AND TESTING (continued)**

4. MASS NOTIFICATION EQUIPMENT TEST RESULTS

Description	Visual Inspection	Functional Test	Comments
Functional test			
Reset/power down test			
Fuses			
Primary power supply			
SEPSS power test			
Trouble signals			
Disconnect switches			
Ground-fault monitoring			
CCU security mechanism			
Prerecorded message content			
Prerecorded message activation			
Software backup performed			
Test backup software			
Fire alarm to MNS interface			
MNS to fire alarm interface			
In-building MNS to wide-area MNS			
MNS to direct recipient MNS			
Sound pressure levels Occupied ☐ Yes ☐ No Ambient dBA: _____ Alarm dBA: _____ (attach supplementary notification appliance form(s) with locations, values, and weather conditions)			
System intelligibility Test method: _____ Score: _____ CIS value: _____ (attach supplementary notification appliance form(s) with locations, values, and weather conditions)			
Other (specify):			

See main System Record of Inspection and Testing for additional information, certifications, and approvals.

FIGURE 7.8.2(j) *Continued*

EMERGENCY COMMUNICATIONS SYSTEMS SUPPLEMENTARY RECORD OF INSPECTION AND TESTING

This form is a supplement to the System Record of Inspection and Testing.

It includes systems and components specific to emergency communication systems.

This form is to be completed by the system inspection and testing contractor at the time of the inspection and/or test.

It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

Inspection/Test Start Date/Time: _____ Inspection/Test Completion Date/Time: _____

Number of Supplemental Pages Attached: _____

1. PROPERTY INFORMATION

Name of property: _____

Address: _____

2. DESCRIPTION OF SYSTEM OR SERVICE

☐ Fire alarm with in-building fire emergency voice alarm communications system (EVAC)

☐ Mass notification system

☐ Combination system, with the following components:

☐ Fire alarm ☐ EVACS ☐ MNS ☐ Two-way, in-building, emergency communications system

☐ Other (specify): _____

Additional description of system(s): _____

2.1 In-Building Fire Emergency Voice Alarm Communications System

Manufacturer: _____ Model number: _____

Number of single voice alarm channels: _____ Number of multiple voice alarm channels: _____

Number of loudspeakers: _____ Number of loudspeaker circuits: _____

Location of amplification and sound processing equipment: _____

Location of paging microphone stations:

Location 1: _____

Location 2: _____

Location 3: _____

2.2 Mass Notification System

2.2.1 System Type:

☐ In-building MNS—combination

☐ In-building MNS ☐ Wide-area MNS ☐ Distributed recipient MNS

☐ Other (specify): _____

FIGURE 7.8.2(k) Emergency Communications Systems Supplementary Record of Inspection and Testing.

EMERGENCY COMMUNICATIONS SYSTEMS SUPPLEMENTARY RECORD OF INSPECTION AND TESTING *(continued)*

2. DESCRIPTION OF SYSTEM OR SERVICE *(continued)*

2.2.2 System Features:

- ☐ Combination fire alarm/MNS ☐ MNS autonomous control unit ☐ Wide-area MNS to regional national alerting interface
☐ Local operating console (LOC) ☐ Distributed-recipient MNS (DRMNS) ☐ Wide-area MNS to DRMNS interface
☐ Wide-area MNS to high-power loudspeaker array (HPLA) interface ☐ In-building MNS to wide-area MNS interface
☐ Other (specify): _____

2.2.3 MNS Local Operating Consoles

Location 1: _____

Location 2: _____

Location 3: _____

2.2.4 High-Power Loudspeaker Arrays

Number of HPLA loudspeaker initiation zones: _____

Location 1: _____

Location 2: _____

Location 3: _____

2.2.5 Mass Notification Devices

Combination fire alarm/MNS visual devices: _____ MNS-only visual devices: _____

Textual signs: _____ Other (describe): _____

Supervision class: _____

2.2.6 Special Hazard Notification

- ☐ This system does not have special suppression pre-discharge notification
☐ MNS systems DO NOT override notification appliances required to provide special suppression pre-discharge notification

3. TWO-WAY EMERGENCY COMMUNICATION SYSTEMS

3.1 Telephone System

Number of telephone jacks installed: _____ Number of warden stations installed: _____

Number of telephone handsets stored on site: _____

Type of telephone system installed: ☐ Electrically powered ☐ Sound powered

3.2 Area of Refuge Emergency Communications Systems

Number of stations: _____ Location of central control point: _____

Days and hours when central control point is attended: _____

Location of alternate control point: _____

Days and hours when alternate control point is attended: _____

FIGURE 7.8.2(k) *Continued*

EMERGENCY COMMUNICATIONS SYSTEMS SUPPLEMENTARY RECORD OF INSPECTION AND TESTING *(continued)*

3. TWO-WAY EMERGENCY COMMUNICATIONS SYSTEMS *(continued)*

3.3 Elevator Emergency Communications Systems

Number of elevators with stations: _____ Location of central control point: _____

Days and hours when central control point is attended: _____

Location of alternate control point: _____

Days and hours when alternate control point is attended: _____

3.4 Other Two-Way Communications System

Describe: _____

4. TESTING RESULTS

4.1 Control Unit and Related Equipment

Description	Visual Inspection	Functional Test	Comments
Control unit	☐	☐	
Lamps/LEDs/LCDs	☐	☐	
Fuses	☐	☐	
Trouble signals	☐	☐	
Disconnect switches	☐	☐	
Ground fault monitoring	☐	☐	
Supervision	☐	☐	
Local annunciator	☐	☐	
Remote annunciators	☐	☐	
Remote power panels	☐	☐	
Other:	☐	☐	

4.2 Secondary Power

Description	Visual Inspection	Functional Test	Comments
Battery condition	☐	☐	
Load voltage	☐	☐	
Discharge test	☐	☐	
Charger test	☐	☐	
Remote panel batteries	☐	☐	

FIGURE 7.8.2(k) *Continued*

EMERGENCY COMMUNICATIONS SYSTEMS
SUPPLEMENTARY RECORD OF INSPECTION AND TESTING *(continued)*

4. TESTING RESULTS *(continued)*

4.3 Emergency Communications Equipment

Description	Visual Inspection	Functional Test	Comments
Control unit	☐	☐	
Lamps/LEDs/LCDs	☐	☐	
Fuses	☐	☐	
Secondary power supply	☐	☐	
Trouble signals	☐	☐	
Disconnect switches	☐	☐	
Ground fault monitoring	☐	☐	
Panel supervision	☐	☐	
System performance	☐	☐	
System audibility	☐	☐	
System intelligibility	☐	☐	
Other:	☐	☐	

4.4 Mass Notification Equipment

Description	Visual Inspection	Functional Test	Comments
Functional test	☐	☐	
Reset/Power down test	☐	☐	
Fuses	☐	☐	
Primary power supply	☐	☐	
SEPSS power test	☐	☐	
Trouble signals	☐	☐	
Disconnect switches	☐	☐	
Ground fault monitoring	☐	☐	
CCU security mechanism	☐	☐	
Prerecorded message content	☐	☐	
Prerecorded message activation	☐	☐	
Software backup performed	☐	☐	
Test backup software	☐	☐	
Fire alarm to MNS Interface	☐	☐	
MNS to fire alarm interface	☐	☐	
In-building MNS to wide-area MNS	☐	☐	
MNS to direct recipient MNS	☐	☐	

FIGURE 7.8.2(k) *Continued*

**EMERGENCY COMMUNICATIONS SYSTEMS
SUPPLEMENTARY RECORD OF INSPECTION AND TESTING (continued)**

4. TESTING RESULTS (continued)

4.4 Mass Notification Equipment (continued)

Description	Visual Inspection	Functional Test	Comments
Sound pressure levels (attach report with locations, values, and weather conditions)	☐	☐	
System intelligibility ☐ CSI ☐ STI (attach report with locations, values, and weather conditions)	☐	☐	
Other:	☐	☐	

4.5 Two-Way Communication Equipment

Description	Visual Inspection	Functional Test	Comments
Phone handsets	☐	☐	
Phone jacks	☐	☐	
Off-hook indicator	☐	☐	
Call-in signal	☐	☐	
System performance	☐	☐	
System audibility	☐	☐	
System intelligibility	☐	☐	
Other:	☐	☐	

See main System Record of Inspection and Testing for additional information, certifications, and approvals.

FIGURE 7.8.2(k) Continued

2. INTERFACE COMPONENT TEST RESULTS (continued)

[illegible]

NFPA 72 (p. 2 of 2)

2022 Edition

INSTALLATION AND INSPECTION FORM SINGLE- AND MULTIPLE-STATION ALARMS AND HOUSEHOLD FIRE ALARM SYSTEMS

This form is to be completed at the time of installation/final inspection of any household fire alarm system and single- or multiple-station alarms. It shall be permitted to modify this form as required to provide a more complete and/or clear record. Insert N/A in all unused lines.

Attach additional sheets, data, or calculations as necessary to complete form.

Form Completion Date: _____ Supplemental Pages Attached: _____

1. PROPERTY INFORMATION

Property Owner: _____

Address: _____

Phone: _____ E-Mail: _____ Other: _____

2. INSTALLATION, CONTRACTOR, AND MONITORING INFORMATION

Installation Contractor: _____

Address: _____

Phone: _____ E-Mail: _____ Other: _____

2.1 Type of Off-Premises Notification

Monitoring Organization: _____

Address: _____

Phone: _____ E-Mail: _____ Other: _____

Account Number: _____ Means of Transmission: _____

3. DESCRIPTION OF SYSTEM OR SERVICE

NFPA 72 Edition: _____

3.1 Type of System

☐ Single-Station ☐ Multiple-Station ☐ Household Fire Alarm System ☐ Carbon Monoxide Alarm System

3.2 Number of Devices

Single-Station Smoke Alarms: _____ Multiple-Station Smoke Alarms: _____

Single-Station Heat Alarms: _____ Multiple-Station Heat Alarms: _____

Single-Station Carbon Monoxide Alarms: _____ Multiple-Station Carbon Monoxide Alarms: _____

System Smoke Detectors: _____ System Heat Detectors: _____

Waterflow Switches: _____

Notification Appliances: _____ Type: _____

Interfaced/Other Equipment: _____

3.3 Location (L) and Date (D) of Devices

Device type, location and manufacture date of devices (date shown on back of devices)

_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Electrical Panel (L): _____ Breaker Number: _____

Alarm Control Unit (L): _____ Battery Back-up (D): _____

Plug in Transformer (L): _____

Relay for Interconnection (L): _____

4. PREPARED BY

Signed: _____ Printed Name: _____ Date: _____

Title: _____ Organization: _____

FIGURE 7.8.2(m) Installation and Inspection Form Single- and Multiple-Station Alarms and Household Fire Alarm Systems.

Chapter 8 Reserved**Chapter 9 Reserved****Chapter 10 Fundamentals****10.1 Application.**

10.1.1 The basic functions of a complete fire alarm and/or signaling system shall comply with the requirements of this chapter.

10.1.2 The requirements of this chapter shall apply to systems, equipment, and components addressed in Chapters 11, 12, 14, 17, 18, 21, 23, 24, 26, and 27.

10.1.3 The requirements of Chapter 7 shall apply where referenced in Chapter 10.

10.2 Purpose. The purpose of fire alarm and signaling systems shall be primarily to provide notification of alarm, supervisory, and trouble conditions; to alert the occupants; to summon aid; and to control emergency control functions.

10.3 Equipment.

10.3.1* Equipment constructed and installed in conformity with this Code shall be listed for the purpose for which it is used.

10.3.2 System components shall be installed, tested, inspected, and maintained in accordance with the manufacturer's published instructions and this Code.

10.3.3* All devices and appliances that receive their operating power from an initiating device circuit (IDC) or from a signaling line circuit (SLC) of a control unit shall be listed for use with the control unit.

10.3.4 All apparatus requiring rewinding or resetting to maintain normal operation shall be restored to normal after each abnormal condition.

10.3.5 Equipment shall be designed so that it is capable of performing its intended functions under the following conditions:

- (1)* At 85 percent and at 110 percent of the nameplate primary (main) and secondary (standby) input voltage(s)
- (2) At ambient temperatures of 32°F (0°C) and 120°F (49°C)
- (3) At a relative humidity of 85 percent and an ambient temperature of 86°F (30°C)

10.4 Design and Installation.

10.4.1* All systems shall be installed in accordance with the plans, specifications, and standards approved by the authority having jurisdiction.

10.4.2 Devices and appliances shall be located and mounted so that accidental operation or failure is not caused by vibration or jarring.

10.4.3 Equipment shall be installed in locations where conditions do not exceed the voltage, temperature, and humidity limits specified in the manufacturer's published instructions.

10.4.4* Unless otherwise permitted by the authority having jurisdiction, control unit displays, visible indicators, or controls

shall be mounted such that the distance to the highest switch, lamp, or textual display does not exceed 6 ft (1.8 m) above the finished floor, and the lowest switch, lamp, or textual display shall not be less than 15 in. (375 mm) above the finished floor.

10.4.5* Unless otherwise permitted by 10.4.5.1 or 10.4.5.2, in areas that are not continuously occupied, early warning fire detection shall be at the location of each control unit(s), notification appliance circuit power extender(s), and supervising station transmitting equipment to provide notification of fire at that location by one of the following means:

- (1) An automatic smoke detector at the location of each control unit(s), notification appliance circuit power extender(s), and supervising station transmitting equipment
- (2) An automatic heat detector where ambient conditions prohibit installation of an automatic smoke detector

10.4.5.1* Smoke or heat detector(s) shall not be required to be installed at the location of dedicated function(s) fire alarm control unit(s) that are not required to provide local or supervising station notification signals.

10.4.5.2 Where a risk analysis shows that early warning fire detection is not required and where acceptable to the authority having jurisdiction, the requirements of 10.4.5 shall not apply.

10.4.6 Initiating Devices.

10.4.6.1 Initiating devices of the manual or automatic type shall be selected and installed to minimize unwanted alarms.

10.4.6.2 Initiating devices shall comply with the requirements of Chapter 17 and Chapter 23.

10.4.6.3 Manual alarms shall be initiated by one of the following ways:

- (1) A listed manual fire alarm box
- (2) A key operated means
- (3) A means contained within a locked cabinet or arranged to provide equivalent protection against unauthorized use

10.4.7 Abandoned Fire Alarm Equipment.

10.4.7.1 Abandoned fire alarm equipment shall be removed.

10.4.7.2 Abandoned fire alarm equipment shall be marked "not in service" until removed.

10.5 Personnel Qualifications.**10.5.1 System Designer.**

10.5.1.1 Plans and specifications shall be developed in accordance with this Code by persons who are experienced in the design, application, installation, and testing of the systems.

10.5.1.2 State or local licensure regulations shall be followed to determine qualified personnel.

10.5.1.3 Personnel shall provide documentation of their qualification by one or more of the following:

- (1) Registration, licensing, or certification by a state or local authority
- (2) Certification by an organization acceptable to the authority having jurisdiction
- (3) Manufacturer's certification for the specific type and brand of system provided

10.5.1.4 The system designer shall be identified on the system design documents.

10.5.1.5 System design trainees shall be under the supervision of a qualified system designer.

10.5.1.6 The system designer shall provide evidence of their qualifications and/or certifications when required by the authority having jurisdiction.

10.5.2 System Installer.

10.5.2.1 Installation personnel shall be qualified or shall be supervised by persons who are qualified in the installation, inspection, and testing of the systems.

10.5.2.2 State or local licensure regulations shall be followed to determine qualified personnel.

10.5.2.3 Personnel shall provide documentation of their qualification by one or more of the following:

- (1) Registration, licensing, or certification by a state or local authority
- (2) Certification by an organization acceptable to the authority having jurisdiction
- (3) Manufacturer's certification for the specific type and brand of system provided

10.5.2.4 System installation trainees shall be under the supervision of a qualified system installer.

10.5.2.5 The system installer shall provide evidence of their qualifications and/or certifications when requested by the authority having jurisdiction.

10.5.3* Inspection, Testing, and Service Personnel. (SIG-TMS)

10.5.3.1* Inspection Personnel. Inspections shall be performed by personnel who have developed competence through training and experience that are acceptable to the authority having jurisdiction or meet the requirement of 10.5.3.4.

10.5.3.2* Testing Personnel. Testing personnel shall have knowledge and experience of the testing requirements contained in this Code, of the equipment being tested, and of the test methods. That knowledge and experience shall be acceptable to the authority having jurisdiction or meet the requirement of 10.5.3.4.

10.5.3.3 Service Personnel. Service personnel shall have knowledge and experience of the maintenance and servicing requirements contained in this Code, of the equipment being serviced or maintained, and of the servicing or maintenance methods. That knowledge and experience shall be acceptable to the authority having jurisdiction or meet the requirement of 10.5.3.4.

10.5.3.4 Means of Qualification. Qualified personnel shall include, but not be limited to, one or more of the following:

- (1)* Personnel who are factory trained and certified for the specific type and brand of system being serviced
- (2)* Personnel who are certified by a nationally recognized certification organization acceptable to the authority having jurisdiction
- (3)* Personnel who are registered, licensed, or certified by a state or local authority to perform service on systems addressed within the scope of this Code, either individually or through their affiliation with an organization

- (4) Personnel who are employed and qualified by an organization listed by a nationally recognized testing laboratory for the servicing of systems within the scope of this Code

10.5.3.5* Programming Personnel.

10.5.3.5.1 Personnel programming a system shall be certified by the system manufacturer.

10.5.3.5.2 System installation personnel shall be permitted to configure systems in the field per manufacturers' published instructions.

10.5.3.5.3 System end users shall be permitted to manage system operation per manufacturers' published instructions or training.

10.5.3.6 Evidence of Qualification. Evidence of qualifications shall be provided to the authority having jurisdiction upon request.

10.5.4 Plans Examiners and Inspectors.

10.5.4.1 Plans and specifications submitted for review and approval shall be reviewed by personnel who are qualified to review such plans and specifications.

10.5.4.2 System installations shall be inspected by personnel who are qualified to perform such inspections.

10.5.4.3 State or local licensure regulations shall be followed to determine qualified personnel.

10.5.4.4 Personnel shall provide documentation of their qualifications by one or more of the following:

- (1) Registration, licensing, or certification by a state or local authority
- (2) Meeting the requirements of NFPA 1031
- (3) Assignment by the authority having jurisdiction to personnel having equivalent competency with 10.5.4.4(1) or 10.5.4.4(2)

10.5.5 Supervising Station Operators. (SIG-SSS)

10.5.5.1 All operators in the supervising station shall demonstrate competence in all tasks required of them in Chapter 26 by one or more of the following:

- (1) Certified by the manufacturer of the receiving system or equipment or the alarm-monitoring automation system
- (2)* Certified by an organization acceptable to the authority having jurisdiction
- (3) Licensed or certified by a state or local authority
- (4) Other training or certification approved by the authority having jurisdiction

10.5.5.2 Evidence of qualifications and/or certification shall be provided when requested by the authority having jurisdiction. A license or qualification listing shall be current in accordance with the requirements of the issuing authority or organization.

10.5.5.3 Operator trainees shall be under the direct supervision of a qualified operator until qualified as required by 10.5.5.1.

10.5.6 Public Emergency Alarm Reporting System Personnel Qualification. (SIG-PRS)

10.5.6.1 System Designer.

10.5.6.1.1 Public emergency alarm reporting system plans and specifications shall be developed in accordance with this Code by persons who are qualified in the proper design, application, installation, and testing of public emergency alarm reporting systems.

10.5.6.1.2 The system design documents shall include the name and contact information of the system designer.

10.5.6.2 System Installer. Installation personnel shall be qualified in the installation, inspection, and testing of public emergency alarm reporting systems.

10.5.6.3 Service Personnel. Service personnel shall be qualified in the service, inspection, maintenance, and testing of public emergency alarm reporting systems.

10.5.6.4 Qualification.

10.5.6.4.1 Personnel shall demonstrate qualification by being trained and certified in public emergency alarm reporting system design, installation, or service (as appropriate).

10.5.6.4.2 Personnel who are trained and certified for the specific type of public emergency alarm reporting system and comply with one of the following shall be considered qualified:

- (1) Personnel who are licensed or certified by a state or local authority, if applicable
- (2)* Personnel who are certified by a nationally recognized certification organization acceptable to the authority having jurisdiction
- (3) Personnel who are employed and qualified by an organization listed by a nationally recognized testing laboratory for the design, installation, or servicing of systems within the scope of this chapter
- (4)* Personnel who are employed and certified by an equipment manufacturer for the specific type of system

10.5.6.4.3 Evidence of qualifications and/or certification shall be provided when requested by the authority having jurisdiction. A license or qualification listing shall be current in accordance with the requirements of the issuing authority or organization.

10.6 Power Supplies.

10.6.1* Scope. The provisions of this section shall apply to power supplies.

10.6.2 Code Conformance. All power supplies shall be installed in accordance with applicable requirements of *NFPA 70*.

10.6.3 Power Supply Sources.

10.6.3.1* Power shall be supplied in accordance with either 10.6.3.2 or 10.6.4.

10.6.3.2 Unless configured in compliance with 10.6.4, at least two independent and reliable power supplies shall be provided, one primary and one secondary.

10.6.3.3 Each power supply shall be of adequate capacity for the application.

10.6.3.4 Monitoring the integrity of power supplies shall be in accordance with 10.6.9.

10.6.4* Stored-Energy Emergency Power Supply Systems (SEPSS).

10.6.4.1 An SEPSS that is not arranged in accordance with 10.6.4.2 shall comply with all of the following:

- (1) An SEPSS shall be configured in compliance with NFPA 111 for a Type O or U, Level 1 system.
- (2) The SEPSS shall be capable of powering the maximum required system load.
- (3) The SEPSS shall have capacity in accordance with 10.6.7.2.

10.6.4.2 Where connected to an engine-driven generator arranged in accordance with 10.6.11.3.1, an SEPSS that complies with all of the following shall be permitted:

- (1) An SEPSS shall be configured in compliance with NFPA 111 for a Type O or U, Class 4, Level 1 system.
- (2) The SEPSS shall be capable of powering the maximum required system load.

10.6.4.3 An SEPSS shall comply with the requirements of 10.6.5.

10.6.4.4* SEPSS equipment shall be installed in the manner and location recommended by the manufacturer and in accordance with NFPA 855 for SEPSS equipment whose rated energy capacity is within the scope of NFPA 855.

10.6.4.5 Failure of an SEPSS shall result in the initiation of a trouble signal in accordance with Section 10.15.

10.6.5 Primary Power Supply.

10.6.5.1 Branch Circuit.

10.6.5.1.1 The branch circuit supplying the equipment shall be supplied by one of the following:

- (1) Electric utility
- (2) An engine-driven generator or equivalent in accordance with 10.6.11.2, where a person trained in its operation is on duty at all times
- (3) An engine-driven generator or equivalent arranged for cogeneration with an electric utility in accordance with 10.6.11.2, where a person trained in its operation is on duty at all times

10.6.5.1.2* The branch circuit supplying the equipment shall supply no other loads.

10.6.5.2 Circuit Identification and Accessibility.

10.6.5.2.1 The location of the branch circuit disconnecting means shall be permanently identified at the control unit.

10.6.5.2.2* The system circuit disconnecting means shall be marked to identify the system or equipment that it serves.

10.6.5.2.3 For fire alarm and/or signaling systems, the circuit disconnecting means shall have a red marking.

10.6.5.2.4 The red marking shall not damage the overcurrent protective devices or obscure the manufacturer's markings.

10.6.5.2.5 The circuit disconnecting means shall be accessible only to authorized personnel.

10.6.5.3 Mechanical Protection. The branch circuit(s) and connections shall be protected against physical damage.

10.6.5.4 Circuit Breaker Lock. Where a circuit breaker is the disconnecting means, an approved breaker locking device shall be installed.

10.6.5.5 Overcurrent Protection. An overcurrent protective device shall be provided in accordance with *NFPA 70*.

10.6.6* Continuity of Power Supplies.

10.6.6.1 The secondary power supply shall automatically provide power to the protected premises system within 10 seconds whenever the primary power supply voltage is insufficient for required system operation.

10.6.6.2 The secondary power supply shall automatically provide power to the supervising station facility and equipment within 60 seconds whenever the primary power supply voltage is insufficient for required system operation.

10.6.6.3 Required signals shall not be lost, interrupted, or delayed by more than 10 seconds as a result of the primary power failure.

10.6.6.3.1 Storage batteries dedicated to the system or ESS arranged in accordance with the provisions of *NFPA 111* shall be permitted to supplement the secondary power supply to ensure required operation during the transfer period.

10.6.6.3.2 Where an ESS is employed in 10.6.6.3.1, a positive means for disconnecting the input and output of the ESS system while maintaining continuity of power supply to the load shall be provided.

10.6.7 Secondary Power Supply.

10.6.7.1 Secondary Power Operation.

10.6.7.1.1 Operation on secondary power shall not affect the required performance of a system or supervising station facility, including alarm, supervisory, and trouble signals and indications.

Exception: While operating on secondary power, audio amplifier monitoring shall be required only when an alarm is present.

10.6.7.2* Capacity.

10.6.7.2.1 The secondary power supply for the protected premises system shall have sufficient capacity to operate the system under quiescent load (system operating in a nonalarm condition) for a minimum of 24 hours.

10.6.7.2.2 At the end of the period in 10.6.7.2.1, the secondary power supply shall be capable of operating all alarm notification appliances used for evacuation or to direct aid to the location of an emergency for 5 minutes, unless otherwise permitted or required by 10.6.7.2.4.

10.6.7.2.3 The secondary power supply for in-building fire emergency voice/alarm communications service shall be capable of operating the system under quiescent load for a minimum of 24 hours.

10.6.7.2.4 At the end of the period in 10.6.7.2.3, the secondary power supply shall be capable of operating the system during a fire or other emergency condition for a period of 15 minutes at maximum connected load.

10.6.7.2.5 The secondary power supply capacity for supervising station facilities and equipment shall be capable of supporting operations for a minimum of 24 hours.

10.6.7.2.6 The secondary power supply for high-power loud-speaker arrays used for wide-area mass notification systems shall be in accordance with 24.6.5.2.

10.6.7.2.7 The secondary power supply for textual visual notification appliances shall be in accordance with 24.6.10.1.

10.6.7.2.8 The secondary power supply capacity for emergency command centers of wide-area mass notification systems shall be capable of supporting operations for a minimum of 24 hours.

10.6.7.2.9 The secondary power supply for in-building mass notification systems shall be capable of operating the system under quiescent load for a minimum of 24 hours.

10.6.7.2.10 The secondary power supply for in-building mass notification systems shall be capable of operating the system during emergency conditions for a period of 15 minutes at maximum connected load.

10.6.7.2.11 The secondary power supply for communications equipment at the protected premises that is used to transmit signals to a supervising station shall have sufficient capacity to operate the system under quiescent load (system operating in a nonalarm condition) for a minimum of 24 hours.

10.6.7.2.12 At the end of the period in 10.6.7.2.11, the secondary power supply for communications equipment shall be capable of transmitting signals for a period of 5 minutes.

10.6.7.2.13 The secondary power supply capacity required shall include all power supply loads that are not automatically disconnected upon the transfer to secondary power supply.

10.6.7.2.14* As a minimum, battery calculations shall apply a correction factor of 1.25 for aging to ensure the battery can meet its current demand at the end of service life.

10.6.7.2.15* Where carbon monoxide detection is not monitored by a supervising station, the secondary power supply shall have sufficient capacity to operate the carbon monoxide detection system under quiescent load (system operating in a nonalarm condition) for a minimum of 24 hours.

10.6.7.2.16 At the end of the period in 10.6.7.2.15, the secondary power supply shall be capable of operating the carbon monoxide detection system and all carbon monoxide notification appliances for 12 hours.

10.6.7.2.17 Where carbon monoxide detection is monitored by a supervising station, the secondary power supply shall have sufficient capacity to operate the carbon monoxide detection system under quiescent load (system operating in a nonalarm condition) for a minimum of 24 hours and, at the end of that period, shall be capable of operating the carbon monoxide detection system and all notification appliances for 5 minutes.

10.6.7.3* Secondary Power Supply for Protected Premises Fire Alarm Systems and Emergency Communications Systems.

10.6.7.3.1 The secondary power supply shall consist of one of the following:

- (1) A storage battery dedicated to the system arranged in accordance with 10.6.10.
- (2) An automatic-starting, engine-driven generator serving the branch circuit specified in 10.6.5.1 and arranged in accordance with 10.6.11.3.1, and storage batteries dedica-

ted to the system with 4 hours of capacity arranged in accordance with 10.6.10

10.6.7.3.2 Secondary circuits that provide power to the control unit and are not integral to the unit shall be protected against physical damage.

10.6.7.4 Secondary Power Supply for Supervising Station Facilities.

10.6.7.4.1 The secondary power supply shall consist of one of the following:

- (1) Storage batteries dedicated to the supervising station equipment arranged in accordance with 10.6.10
- (2) A branch circuit of an automatic-starting, engine-driven generator arranged in accordance with 10.6.11.3.2.1 and 10.6.11.3.2.2, and storage batteries dedicated to the supervising station equipment with 4 hours of capacity arranged in accordance with 10.6.10
- (3) A branch circuit of multiple engine-driven generators, at least one of which is arranged for automatic starting in accordance with 10.6.11.3.2.1 and 10.6.11.3.2.2

10.6.7.4.2 Where a secondary power supply for supervising station facilities in accordance with 10.6.7.4.1(3) is used, the following shall apply:

- (1) Each generator shall be capable of supplying the energy required.
- (2) Generators that are started manually shall be arranged in accordance with 10.6.11.3.2.3 and 10.6.11.3.2.4.
- (3) When manual-start generators are employed, a person trained in the procedure of starting the generator shall be on duty at all times.

10.6.8 Power Supply for Remotely Located Control Equipment.

10.6.8.1* Additional power supplies required for system operation shall comply with 10.6.1 through 10.6.6 and with 10.6.9.

10.6.8.2 The location of remotely located power supplies shall be identified at the master control unit.

10.6.8.3 The master control unit display shall be permitted to satisfy the requirement of 10.6.8.2.

10.6.8.4 The location of remotely located power supplies shall be identified on the record drawings.

10.6.8.5 An uninterruptible power supply (UPS) listed to the requirements of an applicable standard such as UL 864, *Control Units and Accessories for Fire Alarm Systems*, shall be permitted to supply power to remotely located control equipment.

10.6.9 Monitoring Integrity of Power Supplies.

10.6.9.1 Unless otherwise permitted or required by 10.6.9.1.3 and 10.6.9.1.6, all primary and secondary power supplies shall be monitored for the presence of voltage at the point of connection to the system.

10.6.9.1.1 Failure of either the primary or secondary power supply shall result in a trouble signal in accordance with Section 10.15.

10.6.9.1.2 Power failure indication for a digital alarm communicator transmitter (DACT) powered from a protected premises fire alarm system control unit shall be in accordance with 10.6.9.1.

10.6.9.1.3 Monitoring shall not be required for a power supply for supplementary equipment.

10.6.9.1.4 Monitoring shall not be required for the neutral of a three-, four-, or five-wire ac or dc supply source.

10.6.9.1.5 Monitoring shall not be required for the main power supply in a supervising station if its failure is otherwise indicated and obvious to the operator on duty.

10.6.9.1.6 Monitoring shall not be required for the output of an engine-driven generator that is part of the secondary power supply, provided the generator is tested weekly in accordance with Chapter 14.

10.6.9.2* Power supply sources and electrical supervision for digital alarm communications systems shall be in accordance with Section 10.6, 10.6.9, Section 10.19, and Section 12.6.

10.6.9.3* Supervising station alarm systems shall be arranged to delay transmission of primary power failure signals for 60 minutes to 180 minutes unless a delay is not permitted by the authority having jurisdiction.

10.6.9.4 Power supervisory devices used to monitor the integrity of power supplies shall not impair the receipt of fire alarm or supervisory signals.

10.6.10* Storage Batteries.

10.6.10.1 Marking.

10.6.10.1.1 Batteries shall be marked with the month and year of manufacture using the month/year format.

10.6.10.1.2 Where the battery is not marked with the month/year by the manufacturer, the installer shall obtain the date-code and mark the battery with the month/year of battery manufacture.

10.6.10.1.3* Effective January 1, 2024, rechargeable batteries for the secondary power supply used in control units, devices, and accessories shall be listed or component recognized by a nationally recognized testing laboratory.

10.6.10.2 Arrangement.

10.6.10.2.1 Storage batteries shall comply with the requirements of Article 480 of *NFPA 70*.

10.6.10.2.2 Storage batteries shall be located so that the equipment, including overcurrent devices, is not adversely affected by battery gases.

10.6.10.2.3 Batteries shall be insulated against ground faults.

10.6.10.2.4 Batteries shall be insulated to prevent short circuits between multiple cells.

10.6.10.2.5 Batteries shall be protected from physical damage.

10.6.10.2.6 Battery racks shall be protected against corrosion.

10.6.10.2.7 If not located in or adjacent to the control unit, the batteries and their charger location shall be permanently identified at the control unit.

10.6.10.3 Battery Charging.

10.6.10.3.1 Battery charging equipment shall be provided to keep the battery fully charged under normal conditions.

10.6.10.3.2 Battery charging equipment shall be provided to recharge batteries within 48 hours after fully charged batteries have been subject to a single discharge cycle as specified in 10.6.7.2.

10.6.10.3.3 The battery charging equipment operation shall not damage the battery.

10.6.10.3.4* Batteries shall be charged by listed means.

10.6.10.3.5 Provisions for repair or replacement of failed battery charger equipment shall be maintained at supervising stations and used to restore operation prior to depletion of one-half of the battery capacity.

10.6.10.4 Overcurrent Protection. Overcurrent devices shall be provided to protect the batteries from excessive load current.

10.6.10.5 Metering. The battery charging equipment shall include integral meters or readily accessible terminals so that portable meters can be used to determine battery voltage and charging current.

10.6.10.6* Monitoring Integrity of Battery Charging Equipment.

10.6.10.6.1 Means shall be provided to detect the failure of a battery charger.

10.6.10.6.2 Failure of the battery charger shall result in a trouble signal in accordance with Section 10.15.

10.6.11 Engine-Driven Generators.

10.6.11.1 Application and Installation. The application and installation of engine-driven generators shall be as specified in 10.6.11.2 through 10.6.11.7.

10.6.11.2 Primary Power Supply.

10.6.11.2.1 Engine-driven generators arranged as the primary supply shall be designed in an approved manner.

10.6.11.2.2 Engine-driven generators arranged as the primary supply shall be installed in an approved manner.

10.6.11.3 Secondary Power Supplies.

10.6.11.3.1 Protected Premises.

10.6.11.3.1.1 Engine-driven generators used to provide secondary power for a protected premises fire alarm system or an emergency communications system shall comply with NFPA 110 Chapter 4, requirements for a Type 10, Class 24, Level 1 system.

10.6.11.3.1.2 Installation of engine-driven generators used to provide secondary power for a protected premises fire alarm system or an emergency communications system shall be in accordance with NFPA 70, Article 700.

10.6.11.3.1.3 Where pathway survivability is required by another section of the Code, equal protection shall be provided for power supply circuits.

10.6.11.3.2 Supervising Station.

10.6.11.3.2.1 Automatic-starting, engine-driven generators used to provide secondary power for a supervising station shall comply with NFPA 110 Chapter 4, requirements for a Type 60, Class 24, Level 2 system.

10.6.11.3.2.2 Installation of automatic-starting, engine-driven generators used to provide secondary power for a supervising station shall be in accordance with NFPA 70 Article 701.

10.6.11.3.2.3 Manual-starting, engine-driven generators used to provide secondary power for a supervising station shall comply with NFPA 110 Chapter 10, requirements for a Type M, Class 24, Level 2 system.

10.6.11.3.2.4 Installation of manual-starting, engine-driven generators used to provide secondary power for a supervising station shall be in accordance with NFPA 70, Article 702.

10.6.11.4 Performance, Operation, Testing, and Maintenance. The requirements for performance, operation, testing, and maintenance of engine-driven generators shall conform to the applicable provisions of NFPA 110.

10.6.11.5 Capacity. The unit shall be of a capacity that is sufficient to operate the system under the maximum normal load conditions in addition to all other demands placed upon the unit.

10.6.11.6 Fuel. Unless otherwise required or permitted in 10.6.11.6.1 through 10.6.11.6.3, fuel shall be available in storage sufficient for 6 months of testing plus the capacity specified in 10.6.7.

10.6.11.6.1 For public emergency alarm reporting systems, the requirements of Chapter 27 shall apply.

10.6.11.6.2 If a reliable source of supply is available at any time on a 2-hour notice, it shall be permitted to have fuel in storage sufficient for 12 hours of operation at full load.

10.6.11.6.3 Fuel systems using natural or manufactured gas supplied through reliable utility mains shall not be required to have fuel storage tanks unless the structure is a seismic design category C, D, E, or F as defined in ASCE/SEI 7, *Minimum Design Loads and Associated Criteria for Buildings and Other Structures*.

10.6.11.7 Battery and Charger.

10.6.11.7.1 A separate storage battery and separate automatic charger shall be provided for starting the engine-driven generator and shall not be used for any other purpose.

10.6.11.7.2 The battery shall be sized in accordance with 5.6.4 of NFPA 110.

10.7 Signal Priority. The priority of signals shall be in accordance with this section.

10.7.1 ECS priority signals when evaluated by stakeholders through a risk analysis in accordance with 24.3.12 shall be permitted to take precedence over all other signals.

10.7.2 Fire alarm signals shall take precedence over all other signals, except as permitted by 10.7.1 or 10.7.3.

10.7.3* Emergency mass notification signals and messages shall be permitted to have priority over fire alarm notification signals in accordance with the requirements of Chapter 24.

10.7.4 Emergency mass notification signals and messages shall have priority over supervisory and trouble signals in accordance with the requirements of Chapter 24.

10.7.5 Carbon monoxide signals shall be permitted to take precedence over supervisory and trouble signals.

10.7.6 Pre-alarm signals shall take precedence over supervisory and trouble signals.

10.7.7 Supervisory signals shall take precedence over trouble signals.

10.7.8 Hold-up alarms or other life-threatening signals shall be permitted to take precedence over supervisory and trouble signals where acceptable to the authority having jurisdiction.

10.7.9* Where separate systems are installed, they shall be permitted to achieve the priority of signals in accordance with Section 10.7.

10.7.10 Combination systems shall comply with 23.8.4.7.

10.8 Detection and Signaling of Conditions.

10.8.1 Abnormal Condition Detection. Where required by this Code, the system shall be provided with means to detect and signal abnormal conditions.

10.8.2 Alarm Condition Detection. Where required by this Code, the system shall be provided with means to detect and signal alarm conditions.

10.8.2.1 Pre-Alarm Condition Detection. Where required by this Code, the system shall be provided with means to detect and signal pre-alarm conditions.

10.8.2.2 Supervisory Condition Detection. Where required by this Code, the system shall be provided with means to detect and signal supervisory conditions.

10.8.2.3 Trouble Condition Detection. Where required by this Code, the system shall be provided with means to detect and signal trouble conditions.

10.8.2.4 Normal Condition Detection. Where required by this Code, the system shall generate a restoration signal when the device or signaling system returns to normal.

10.9 Responses.

10.9.1 Alarm. The response to an alarm signal shall be in accordance with this Code.

10.9.2 Pre-Alarm. The response to a pre-alarm signal shall be in accordance with this Code.

10.9.3 Supervisory. The response to a supervisory signal shall be in accordance with this Code.

10.9.4 Trouble. The response to trouble signal shall be in accordance with this Code.

10.10 Distinctive Signals.

10.10.1 Priority alarm signals, fire alarm signals, carbon monoxide alarm signals, supervisory signals, pre-alarm signals, and trouble signals shall be distinctively and descriptively annunciated.

10.10.2 Audible alarm notification appliances for a fire alarm system shall produce signals that are distinctive from other similar appliances used for other purposes in the same area that are not part of the fire alarm or emergency communications system.

10.10.3 Audible alarm notification appliances for a carbon monoxide alarm system shall produce signals that are distinctive from other similar appliances used for other purposes in

the same area that are not part of the carbon monoxide, fire alarm, or emergency communications system.

10.10.4* An audible notification appliance on a control unit, on multiple control units that are interconnected to form a system, or at a remote location, shall be permitted to have the same audible characteristics for all alerting functions including, but not limited to, alarm, trouble, and supervisory, provided that the distinction between signals shall be by other means.

10.10.5* Supervisory signals shall be distinctive in sound from other signals, and their sound shall not be used for any other purpose except as permitted in 10.10.4.

10.10.6 Trouble signals required to indicate at the protected premises shall be indicated by distinctive audible signals, which shall be distinctive from alarm signals except as permitted in 10.10.4.

10.10.7 Alarm evacuation signals shall be distinctive in sound from other signals, shall comply with the requirements of 18.4.2, and their sound shall not be used for any other purpose.

10.10.8 Pre-alarm signals shall be distinctive in sound from other signals, and their sound shall not be used for any other purpose except as permitted in 10.10.4.

10.10.9 Carbon monoxide alarm signals shall comply with 18.4.3.

10.11 Alarm Signals.

10.11.1* Actuation of alarm notification appliances or emergency voice communications, emergency control function interface devices, and annunciation at the protected premises shall occur within 10 seconds after the activation of an initiating device.

10.11.2* Visual notification appliances, textual visual notification appliances, and loudspeaker notification appliances located in the same area shall be activated and deactivated as a group unless otherwise required by an ECS emergency response plan. (SIG-ECS)

10.11.3 Visual alarm notification appliances shall not be activated when loudspeaker notification appliances are used as permitted by 24.3.5 for non-emergency paging. (SIG-ECS)

10.11.4* A coded alarm signal shall consist of not less than three complete rounds of the number transmitted.

10.11.5 Each round of a coded alarm signal shall consist of not less than three impulses.

10.11.6* Resetting of alarm signals shall comply with 23.8.2.2.

10.11.7 The subsequent occurrence of a fault on an initiating device circuit or a signaling line circuit used for other than the interconnection of control units shall not affect previously transmitted unacknowledged alarm signals.

10.11.8 An alarm signal that has been deactivated at the protected premises shall comply with 10.11.8.1 and 10.11.8.2.

10.11.8.1 The audible and visible alarm signal at the control unit only shall automatically reactivate every 24 hours or less until alarm signal conditions are restored to normal.

10.11.8.2 The audible and visible alarm signal shall operate until it is manually silenced or acknowledged.

10.12* Fire Alarm Notification Appliance Deactivation.

10.12.1 A means for turning off activated alarm notification appliance(s) shall be permitted.

10.12.2* When an occupant notification alarm signal deactivation means is actuated, both audible and visual notification appliances shall be simultaneously deactivated.

10.12.3 The fire alarm notification deactivation means shall be key-operated or located within a locked cabinet, or arranged to provide equivalent protection against unauthorized use.

10.12.4 The means shall comply with the requirements of 10.18.1.

10.12.5 Subsequent Activation of Initiating Devices.

10.12.5.1 Subsequent activation of nonaddressable initiating devices on other initiating device circuits shall cause the notification appliances to reactivate.

10.12.5.2 Subsequent activation of addressable alarm initiating devices of a different type in the same room or addressable alarm initiating devices in a different room on signaling line circuits shall cause the notification appliances to reactivate.

10.12.6 A fire alarm notification deactivation means that remains in the deactivated position when there is no alarm condition shall operate an audible trouble notification appliance until the means is restored to normal.

10.13 Carbon Monoxide Notification Appliance Deactivation. A carbon monoxide initiating device with an integral sounder shall be permitted to be silenced locally if the carbon monoxide alarm or supervisory status continues to be displayed at the control unit.

10.14 Supervisory Signals.

10.14.1 Self-Restoring Supervisory Signal Indication. Visible and audible indication of self-restoring supervisory signals and visible indication of their restoration to normal shall be automatically indicated within 90 seconds at the following locations:

- (1) Fire alarm control unit for local fire alarm systems
- (2) Building fire command center for in-building fire emergency voice/alarm communications systems
- (3) Emergency command center for one or more buildings where responsible authorities receive and disseminate information
- (4) Supervising station location for systems installed in compliance with Chapter 26

10.14.2 Latching Supervisory Signal Indication.

10.14.2.1 Visible and audible indication of latching supervisory signals shall be indicated within 90 seconds at the locations specified in 10.14.1.

10.14.2.2 Restoration of latching supervisory signals shall be indicated within 90 seconds at the locations specified in 10.14.1.

10.14.3 Coded Supervisory Signal.

10.14.3.1 A coded supervisory signal shall be permitted to consist of two rounds of the number transmitted to indicate a supervisory off-normal condition.

10.14.3.2 A coded supervisory signal shall be permitted to consist of one round of the number transmitted to indicate the restoration of the supervisory condition to normal.

10.14.4 Combined Coded Alarm and Supervisory Signal Circuits. Where both coded sprinkler supervisory signals and coded fire or waterflow alarm signals are transmitted over the same signaling line circuit, provision shall be made to obtain either alarm signal precedence or sufficient repetition of the alarm signal to prevent the loss of an alarm signal.

10.14.5 Supervisory Notification Appliance Location. The audible supervisory notification appliances shall be located in an area where they are to be heard.

10.14.6 Supervisory Signal Reactivation. A supervisory signal that has been deactivated at the protected premises shall comply with 10.14.6.1 and 10.14.6.2.

10.14.6.1 The audible and visible supervisory signal at the control unit only shall automatically reactivate every 24 hours or less until supervisory signal conditions are restored to normal.

10.14.6.2 The audible and visible supervisory signal shall operate until it is manually silenced or acknowledged.

10.14.7 Supervisory Notification Appliance Deactivation.

10.14.7.1 A means for deactivating supervisory notification appliances shall be permitted.

10.14.7.2 The means shall be key-operated or located within a locked cabinet, or arranged to provide equivalent protection against unauthorized use.

10.14.7.3 The means for deactivating supervisory notification appliances shall comply with the requirements of 10.18.2.

10.14.7.4 Subsequent activation of supervisory initiating devices in other building zones shall cause supervisory notification appliances to activate as required by the system input/output matrix.

10.14.7.5 A means for deactivating supervisory notification appliances that remains in the deactivated position when there is no supervisory condition shall operate an audible trouble notification appliance until the means is restored to normal.

10.15 Trouble Signals.

10.15.1 Trouble signals and their restoration to normal shall be indicated within 200 seconds at the locations identified in 10.15.7 and 10.15.8.

10.15.2 Indication of primary power failure trouble signals transmitted to a supervising station shall be in accordance with 10.6.9.3.

10.15.3 An audible trouble signal shall be permitted to be intermittent provided it sounds at least once every 10 seconds, with a minimum duration of ½ second.

10.15.4 A single audible trouble signal shall be permitted to annunciate multiple fault conditions.

10.15.5 The audible trouble notification appliances shall be located in an area where they are to be heard.

10.15.6 Activated notification appliances at the protected premises shall continue to operate unless they are manually silenced as permitted by 10.15.10.1.

10.15.7 Visible and audible trouble signals and visible indication of their restoration to normal shall be indicated at the following locations:

- (1) Fire alarm control unit for protected premises alarm systems
- (2) Building fire command center for in-building fire emergency voice/alarm communications systems
- (3) Emergency command center for one or more buildings where responsible authorities receive and disseminate information
- (4) Central station or remote station location for systems installed in compliance with Chapter 26

10.15.8 Trouble signals and their restoration to normal shall be visibly and audibly indicated at the proprietary supervising station for systems installed in compliance with Chapter 26.

10.15.9* A trouble signal that has been deactivated at the protected premises shall comply with 10.15.9.1 and 10.15.9.2.

10.15.9.1 The audible and visible trouble signal shall automatically reactivate at the control unit every 24 hours or less until trouble signal conditions are restored to normal.

10.15.9.2 The audible and visible trouble signal associated with signaling the depletion or failure of the primary battery of a wireless system as required by 23.16.2.1 and 23.16.2.2 shall automatically resound every 4 hours or less until the depletion signal is restored to normal.

10.15.10 Trouble Notification Appliance Deactivation.

10.15.10.1 A means for deactivating trouble notification appliances shall be permitted.

10.15.10.2 The means shall be key-operated or located within a locked cabinet, or arranged to provide equivalent protection against unauthorized use.

10.15.10.3 The means for deactivating trouble notification appliances shall comply with the requirements of 10.18.2.

10.15.10.4 If an audible trouble notification appliance is also used to indicate a supervisory condition, as permitted by 10.10.4, a trouble notification appliance deactivation means shall not prevent subsequent actuation of supervisory notification appliances.

10.15.10.5 Subsequent trouble signals shall cause trouble notification appliances to activate as required by the system input/output matrix.

10.15.10.6 A means for deactivating trouble notification appliances that remains in the deactivated position when there is no trouble condition shall operate an audible trouble notification appliance until the means is restored to normal.

10.15.10.7* Unless otherwise permitted by the authority having jurisdiction, trouble notification appliances at the protected premises of a supervising station fire alarm system arranged in accordance with Chapter 26, that have been silenced at the protected premises shall automatically reactivate every 24 hours or less until fault conditions are restored to normal.

10.16 Emergency Control Function Status Indicators.

10.16.1 All controls provided specifically for the purpose of manually overriding any automatic emergency control function

shall provide visible indication of the status of the associated control circuits.

10.16.2* Where status indicators are provided for emergency equipment or control functions, they shall be arranged to reflect the actual status of the associated equipment or function.

10.17 Notification Appliance Circuits and Supervised Notification Appliance Control Circuits.

10.17.1 An open, ground-fault, or short-circuit fault on the installation conductors of one alarm notification appliance circuit shall not affect the operation of any other alarm notification appliance circuit for more than 200 seconds regardless of whether the short-circuit fault is present during the normal or activated circuit state.

10.17.2 Supervised notification appliance control circuits shall comply with all of the following:

- (1) A supervised notification appliance control circuit shall not serve more than one notification zone.
- (2) The supervised notification appliance control circuit shall be monitored for integrity in accordance with Section 12.6.
- (3) A fault in the supervised notification appliance control circuit installation conductors shall result in a trouble signal in accordance with Section 10.15.

10.18 Annunciation and Annunciation Zoning.

10.18.1 Alarm Annunciation. Where required by other governing laws, codes, or standards, the location of an operated initiating device shall be annunciated by visible means.

10.18.1.1 Visible annunciation of the location of an operated initiating device shall be by an indicator lamp, alphanumeric display, printout, or other approved means.

10.18.1.2* The visible annunciation of the location of operated initiating devices shall not be canceled by the means used to deactivate alarm notification appliances.

10.18.2 Supervisory and Trouble Annunciation. Where required by other governing laws, codes, or standards, supervisory or trouble conditions shall be annunciated by visible means.

10.18.2.1 Visible annunciation shall be by an indicator lamp, an alphanumeric display, a printout, or other means.

10.18.2.2 The visible annunciation of supervisory or trouble conditions shall not be canceled by the means used to deactivate supervisory or trouble notification appliances.

10.18.3* Annunciator Access and Location.

10.18.3.1 All required annunciation means shall be readily accessible to responding personnel.

10.18.3.2 All required annunciation means shall be located as required by the authority having jurisdiction to facilitate an efficient response to the situation.

10.18.4 Alarm Annunciation Display. Visible annunciators shall be capable of displaying all zones in alarm.

10.18.4.1 If all zones in alarm are not displayed simultaneously, the zone of origin shall be displayed.

10.18.4.2 If all zones in alarm are not displayed simultaneously, there shall be an indication that other zones are in alarm.

10.18.5* Annunciation Zoning.

10.18.5.1 For the purpose of alarm annunciation, each floor of the building shall be considered as a separate zone.

10.18.5.2 For the purposes of alarm annunciation, if a floor of the building is subdivided into multiple zones by fire or smoke barriers and the fire plan for the protected premises allows relocation of occupants from the zone of origin to another zone on the same floor, each zone on the floor shall be annunciated separately.

10.18.5.3 Where the system serves more than one building, each building shall be annunciated separately.

10.18.6* Emergency Services Interfaces. Where required by the enforcing authority; governing laws, codes, or standards; or other parts of this Code, annunciators, information display systems, and controls for portions of a system provided for use by emergency service personnel shall be designed, arranged, and located in accordance with the requirements of the organizations intended to use the equipment.

10.19 Monitoring Integrity of In-Building Fire Emergency Voice/Alarm Communications Systems.

10.19.1* Audio Amplifier and Tone-Generating Equipment. If loudspeakers are used to produce audible fire alarm signals, the required trouble signal for 10.19.1.1 through 10.19.1.3 shall be in accordance with Section 10.15.

10.19.1.1 When primary power is available, failure of any audio amplifier shall result in a trouble signal.

10.19.1.2 When an alarm is present and primary power is not available (i.e., system is operating from the secondary power source), failure of any audio amplifier shall result in a trouble signal.

10.19.1.3* Failure of any tone-generating equipment shall result in a trouble signal, unless the tone-generating and amplifying equipment are enclosed as integral parts and serve only a single, listed loudspeaker.

10.19.2 Two-Way Telephone Communications Circuits.

10.19.2.1 Two-way telephone communications circuit installation conductors shall be monitored for open circuit fault conditions that would cause the telephone communications circuit to become fully or partially inoperative.

10.19.2.2 Two-way telephone communications circuit installation conductors shall be monitored for short circuit fault conditions that would cause the telephone communications circuit to become fully or partially inoperative.

10.19.2.3 Two-way telephone communications circuit fault conditions shall result in a trouble signal in accordance with Section 10.15.

10.20 Documentation and Notification.

10.20.1 Documentation shall be in accordance with Chapter 7.

10.20.2 The authority having jurisdiction shall be notified prior to installation or alteration of equipment or wiring.

10.21* Impairments.

10.21.1 The system owner or the owner's designated representative shall be notified when a system or part thereof is impaired. Impairments to systems shall include out-of-service events.

10.21.2 A record of the impairments shall be maintained by the system owner or the owner's designated representative for a period of 1 year from the date the impairment is corrected.

10.21.3 The supervising station shall report to the authority having jurisdiction any system for which required monitoring has been terminated.

10.21.4* The service provider shall report to the authority having jurisdiction any system that is out of service for more than 8 hours.

10.21.5* Where required by the authority having jurisdiction, mitigating measures shall be implemented for the period that the system is impaired.

10.21.6 The system owner or the owner's designated representative and the authority having jurisdiction shall be notified when an impairment period ends.

10.22* Unwanted Alarms. For the purpose of reporting, alarm signals that are not the result of hazardous conditions shall be classified as Unwanted and subclassified as one of the following:

- (1) Malicious alarm
- (2) Nuisance alarm
- (3) Unintentional alarm
- (4) Unknown alarm

Chapter 11 Cybersecurity

11.1* Cybersecurity. Where required by governing laws, codes, or standards, or other parts of this Code, cybersecurity shall be provided for equipment, software, firmware, tools, installation methods, physical security of and access to equipment, data pathways, testing, and maintenance.

Chapter 12 Circuits and Pathways

12.1 Application.

12.1.1 Pathways (interconnections) shall be designated based on the performance characteristics defined in this chapter.

12.1.2 The requirements of Chapters 11 and 14 shall apply.

12.2 General.

12.2.1* Performance and survivability of signaling pathways (interconnections) shall comply with the defined designations of this chapter.

12.2.2 A pathway (interconnection) class designation shall be dependent on the pathway (interconnection) capability to continue to operate during abnormal conditions.

12.2.3 The installation of all pathway wiring, cable, and equipment shall be in accordance with *NFPA 70* and the applicable requirements of 12.2.3.1 through 12.2.3.4.

12.2.3.1 Optical fiber cables installed as part of the fire alarm system shall meet the requirements of *NFPA 70* Article 770, and

be protected against physical damage in accordance with *NFPA 70* Article 760.

12.2.3.2 Optical fiber cables entering from outside the building or structure shall also comply with *NFPA 70* Article 840.

12.2.3.3* Fire alarm system wiring and equipment, including all circuits controlled and powered by the fire alarm system, shall be installed in accordance with the requirements of this Code and of *NFPA 70* Article 760.

12.2.3.4* Wiring methods permitted by other sections of this Code to resist attack by fire shall be installed in accordance with manufacturer's published instructions and the requirements of *NFPA 70* Article 760 and Article 728.

12.2.3.5* Where operational capability is required to be maintained or continued during the application of a fault, the operational capability required in 10.11.1 shall be restored within 200 seconds from the time the fault is introduced.

12.2.4 Ground Connections.

12.2.4.1 Unless otherwise permitted by 12.2.4.2, all fire alarm systems shall test free of grounds.

12.2.4.2 The requirements of 12.2.4.1 shall not be required where parts of circuits or equipment are intentionally and permanently grounded in order to provide ground fault detection, noise suppression, emergency ground signals, and circuit protection grounding.

12.2.4.3* On conductive pathways, operational capability shall be maintained during the application of a single ground connection.

12.3* Pathway Class Designations. Pathways shall be designated as Class A, Class B, Class C, Class D, Class E, Class N, or Class X, depending on their performance.

12.3.1* Class A. A pathway shall be designated as Class A when it performs as follows:

- (1) It includes a redundant path.
- (2) Operational capability continues past a single open, and the single open fault results in the annunciation of a trouble signal.
- (3) Conditions that affect the intended operation of the path are annunciated as a trouble signal.
- (4) Operational capability on metallic conductors is maintained during the application of a single ground fault.
- (5) A single ground condition on metallic conductors results in the annunciation of a trouble signal.

12.3.2 Class B. A pathway shall be designated as Class B when it performs as follows:

- (1) It does not include a redundant path.
- (2) Operational capability stops at a single open.
- (3) Conditions that affect the intended operation of the path are annunciated as a trouble signal.
- (4) Operational capability on metallic conductors is maintained during the application of a single ground fault.
- (5) A single ground condition on metallic conductors results in the annunciation of a trouble signal.

12.3.3* Class C. A pathway shall be designated as Class C when it performs as follows:

- (1) It includes one or more pathways where operational capability is verified via end-to-end communication, but the integrity of individual paths is not monitored.
- (2) A loss of end-to-end communication is annunciated as a trouble signal.

12.3.4* Class D. A pathway shall be designated as Class D when it has fail-safe operation, where no fault is annunciated, but the intended operation is performed in the event of a pathway failure.

12.3.5* Class E. A pathway shall be designated as Class E when it is not monitored for integrity.

12.3.6 Class N. A pathway shall be designated as Class N when it performs as follows:

- (1)* It includes two or more pathways where operational capability of the primary pathway and a redundant pathway to each device shall be verified through end-to-end communication.

Exception: When only one device is served, only one pathway shall be required.

- (2) A loss of intended communications between endpoints shall be annunciated as a trouble signal.
- (3) A single open, ground, short, or combination of faults on one pathway shall not affect any other pathway.
- (4)* Conditions that affect the operation of the primary pathway(s) and redundant pathway(s) shall be annunciated as a trouble signal when the system's minimal operational requirements cannot be met.
- (5)* Primary and redundant pathways shall not be permitted to share traffic over the same physical segment.

12.3.7 Class X. A pathway shall be designated as Class X when it performs as follows:

- (1) It includes a redundant path.
- (2) Operational capability continues past a single open, and the single open fault results in the annunciation of a trouble signal.
- (3) Operational capability on metallic conductors continues past a single short-circuit, and the single short-circuit fault results in the annunciation of a trouble signal.
- (4) Operational capability on metallic conductors continues past a combination open fault and ground fault.
- (5) Conditions that affect the intended operation of the path are annunciated as a trouble signal.
- (6) Operational capability on metallic conductors is maintained during the application of a single ground fault.
- (7) A single ground condition on metallic conductors results in the annunciation of a trouble signal.

12.3.8* Class A, Class N, and Class X Pathway Separation. Class A, Class N, and Class X circuits using physical pathways shall be installed so that the primary and redundant, or outgoing and return, conductors exiting from and returning to the control unit, respectively, are routed separately.

12.3.8.1 The outgoing and return (redundant) circuit conductors shall be permitted in the same cable assembly (i.e., multiconductor cable), enclosure, or raceway only under the following conditions:

- (1) For a distance not to exceed 10 ft (3.0 m) where the outgoing and return conductors enter or exit the initiating device, notification appliance, or control unit enclosures

- (2) Single drops installed in the raceway to individual devices or appliances
- (3)* In a single room not exceeding 1000 ft² (93 m²) in area, a drop installed in the raceway to multiple devices or appliances that does not include any emergency control function devices

12.4* Pathway Survivability. All pathways shall comply with NFPA 70.

12.4.1 Pathway Survivability Level 0. Level 0 pathways shall not be required to have any provisions for pathway survivability.

12.4.2 Pathway Survivability Level 1. Pathway survivability Level 1 shall consist of pathways in buildings that are fully protected by an automatic sprinkler system in accordance with NFPA 13 with any interconnecting conductors, cables, or other physical pathways protected by metal raceways or metal armored cables.

12.4.3* Pathway Survivability Level 2. Pathway survivability Level 2 shall consist of one or more of the following:

- (1) 2-hour fire-rated circuit integrity (CI) or fire-resistive cable
- (2) 2-hour fire-rated cable system [electrical circuit protective system(s)]
- (3) 2-hour fire-rated enclosure or protected area
- (4)* Performance alternatives approved by the authority having jurisdiction

12.4.4* Pathway Survivability Level 3. Pathway survivability Level 3 shall consist of pathways in buildings that are fully protected by an automatic sprinkler system in accordance with NFPA 13 and one or more of the following:

- (1) 2-hour fire-rated circuit integrity (CI) or fire-resistive cable
- (2) 2-hour fire-rated cable system [electrical circuit protective system(s)]
- (3) 2-hour fire-rated enclosure or protected area
- (4)* Performance alternatives approved by the authority having jurisdiction

12.4.5* Pathway Survivability Level 4. Pathway survivability Level 4 shall consist of one or more of the following:

- (1) 1-hour fire-rated circuit integrity (CI) or fire-resistive cable
- (2) 1-hour fire-rated cable system [electrical circuit protective system(s)]
- (3) 1-hour fire-rated enclosure or protected area
- (4) Performance alternatives approved by the authority having jurisdiction

12.5* Shared Pathway Designations. Shared pathways shall be designated as Level 0, Level 1, Level 2, or Level 3, depending on their performance.

12.5.1* Shared Pathway Level 0. Level 0 pathways shall not be required to segregate or prioritize life safety data from non-life safety data.

12.5.2* Shared Pathway Level 1. Level 1 pathways shall not be required to segregate life safety data from non-life safety data, but shall prioritize all life safety data over non-life safety data.

12.5.3* Shared Pathway Level 2. Level 2 pathways shall segregate all life safety data from non-life safety data.

12.5.4* Shared Pathway Level 3. Level 3 pathways shall use equipment that is dedicated to the life safety system.

12.6* Monitoring Integrity and Circuit Performance of Installation Conductors and Other Signaling Channels.

12.6.1 Unless otherwise permitted or required by 12.3.1 through 12.3.7 and 12.6.3 through 12.6.13, all means of interconnecting equipment, devices, and appliances and wiring connections shall be monitored for the integrity of the interconnecting conductors or equivalent path so that the occurrence of a single open or a single ground-fault condition in the installation conductors or other signaling channels is automatically indicated within 200 seconds.

12.6.2 Unless otherwise permitted or required by 12.3.1 through 12.3.7 and 12.6.3 through 12.6.13, all means of interconnecting equipment, devices, and appliances and wiring connections shall be monitored for the integrity of the interconnecting conductors or equivalent path so that the restoration to normal of a single open or a single ground-fault condition in the installation conductors or other signaling channels is automatically indicated within 200 seconds.

12.6.3 Shorts between conductors shall not be required to be monitored for integrity, unless required by 12.6.15, 12.6.16, and 10.19.2.

12.6.4 Monitoring for integrity shall not be required for a noninterfering shunt circuit, provided that a fault circuit condition on the shunt circuit wiring results only in the loss of the noninterfering feature of operation.

12.6.5 Monitoring for integrity shall not be required for connections to and between supplementary system components, provided that a single open, ground-fault, or short-circuit conditions of the supplementary equipment or interconnecting means, or both, do not affect the required operation of the fire alarm and/or signaling system.

12.6.6 Monitoring for integrity shall not be required for the circuit of an alarm notification appliance installed in the same room with the control equipment, provided that the notification appliance circuit conductors are installed in conduit or are equivalently protected against mechanical injury.

12.6.7 Monitoring for integrity shall not be required for a trouble notification appliance circuit.

12.6.8* Monitoring for integrity shall not be required for the interconnection between listed equipment within a common enclosure.

12.6.9 Monitoring for integrity shall not be required for the interconnection between enclosures containing control equipment located within 20 ft (6 m) of each other where the conductors are installed in conduit or equivalently protected against mechanical injury.

12.6.10 Monitoring for integrity shall not be required for the conductors for ground-fault detection where a single ground-fault does not prevent the required normal operation of the system.

12.6.11 Monitoring for integrity shall not be required for pneumatic rate-of-rise systems of the continuous line type in which the wiring terminals of such devices are connected in multiple across electrically supervised circuits.

12.6.12 Monitoring for integrity shall not be required for the interconnecting wiring of a stationary computer and the computer's keyboard, video monitor, mouse-type device, or touch screen, as long as the interconnecting wiring does not exceed 8 ft (2.4 m) in length; is a listed computer/data processing cable as permitted by *NFPA 70*; and failure of cable does not cause the failure of the required system functions not initiated from the keyboard, mouse, or touch screen.

12.6.13 Monitoring for integrity of the installation conductors for a ground-fault condition shall not be required for the communications and transmission channels extending from a supervising station to a subsidiary station(s) or protected premises, or both, that comply with the requirements of Chapter 26 and are electrically isolated from the fire alarm system (or circuits) by a transmitter(s).

12.6.14 Interconnection means shall be arranged so that a single break or single ground-fault does not cause an alarm signal.

12.6.15 A wire-to-wire short-circuit fault on any alarm notification appliance circuit shall result in a trouble signal in accordance with Section 10.15, except as permitted by 12.6.5, 12.6.6, or 12.6.11.

12.6.16 Where two or more systems are interconnected, the systems shall be connected using Class A, B, N, or X circuits as described in Section 12.3.

12.7* Nomenclature. The following nomenclature shall be used to identify the required properties of the system(s) interconnections and pathway survivability:

- (1) System(s) interconnections
- (2) Pathway survivability levels (not required if Level 0)
- (3) Shared pathway levels (not required if Level 0)
- (4) Pathway class designation

Chapter 13 Reserved

Chapter 14 Inspection, Testing, and Maintenance

14.1 Application.

14.1.1 The inspection, testing, and maintenance of systems, their initiating devices, and notification appliances shall comply with the requirements of this chapter.

14.1.2 The inspection, testing, and maintenance of single- and multiple-station alarms and household alarm systems shall comply with 14.4.5 and 14.4.6. (SIG-HOU)

14.1.3 Procedures that are required by other parties and that exceed the requirements of this chapter shall be permitted.

14.1.4 The requirements of this chapter shall apply to both new and existing systems.

14.1.5 The requirements of Chapter 7 shall apply where referenced in Chapter 14.

14.2 General.

14.2.1 Purpose.

14.2.1.1* The purpose for initial and reacceptance inspections shall be to ensure compliance with approved design docu-

ments and to ensure installation in accordance with this Code and other required installation standards.

14.2.1.2* The purpose for initial and reacceptance tests of fire alarm and signaling systems shall be to ensure system operation in accordance with the design documents.

14.2.1.3* The purpose for periodic inspections shall be to assure that obvious damages or changes that might affect the system operability are visually identified.

14.2.1.4* The purpose for periodic testing shall be to statistically assure operational reliability.

14.2.2 Performance.

14.2.2.1 Performance Verification. To ensure operational integrity, the system shall have an inspection, testing, and maintenance program.

14.2.2.1.1 Inspection, testing, and maintenance programs shall satisfy the requirements of this Code and conform to the equipment manufacturer's published instructions.

14.2.2.1.2* Inspection, testing, and maintenance programs shall verify correct operation of the system.

14.2.2.2 Impairments. Where an automatic function of a fire alarm or signaling system is taken out of service for testing and a manual means or other compensatory measures are unavailable, the system or portion thereof is impaired and shall comply with the requirements of Section 10.21 until the automatic function is restored.

14.2.2.3 Deficiencies.

14.2.2.3.1 System deficiencies shall be corrected.

14.2.2.3.2 If a deficiency is not corrected at the conclusion of system inspection, testing, or maintenance, the system owner or the owner's designated representative shall be informed of the deficiency in writing within 24 hours.

14.2.2.3.3 In the event that any equipment is observed to be part of a recall program, the system owner or the system owner's designated representative shall be notified in writing.

14.2.2.4 Observations.

14.2.2.4.1 If observations are noted, they shall be permitted to be communicated to the system owner.

14.2.2.4.2 The system owner shall not be required to address such observations unless the observations become an impairment or deficiency.

14.2.3 Responsibilities.

14.2.3.1* The property or building or system owner or the owner's designated representative shall be responsible for inspection, testing, and maintenance of the system and for alterations or additions to this system.

14.2.3.2 Where the property owner is not the occupant, the property owner shall be permitted to delegate the authority and responsibility for inspecting, testing, and maintaining the fire protection systems to the occupant, management firm, or managing individual through specific provisions in the lease, written use agreement, or management contract.

14.2.3.3 Inspection, testing, or maintenance shall be permitted to be done by the building or system owner or a person or

organization other than the building or system owner if conducted under a written contract.

14.2.3.4 Where the building or system owner has delegated any responsibilities for inspection, testing, or maintenance, a copy of the written delegation required by 14.2.3.3 shall be provided to the authority having jurisdiction upon request.

14.2.3.5 Testing and maintenance of central station service systems shall be performed under the contractual arrangements specified in 26.3.3.

14.2.3.6* Service Personnel Qualifications and Experience. Service personnel shall be qualified and experienced in accordance with the requirements of 10.5.3.

14.2.4* Notification.

14.2.4.1 Before proceeding with any testing, all persons and facilities receiving alarm, supervisory, or trouble signals and all building occupants shall be notified of the testing to prevent unnecessary response.

14.2.4.2 At the conclusion of testing, those previously notified (and others, as necessary) shall be notified that testing has been concluded.

14.2.4.3 The owner or the owner's designated representative and service personnel shall coordinate system testing to prevent interruption of critical building systems or equipment.

14.2.5 System Documentation. Prior to system maintenance or testing, the record of completion and any information required by Chapter 7 regarding the system and system alterations, including specifications, wiring diagrams, and floor plans, shall be provided by the owner or a designated representative to the service personnel upon request.

14.2.5.1 The provided documentation shall include the current revisions of all fire alarm software and the revisions of software of any systems with which the fire alarm software interfaces.

14.2.5.2 The revisions of fire alarm software, and the revisions of the software in the systems with which the fire alarm software interfaces, shall be verified for compatibility in accordance with the requirements of 23.2.2.1.1.

14.2.6 Releasing Systems. Requirements pertinent to testing the fire alarm systems initiating fire suppression system releasing functions shall be covered by 14.2.6.1 through 14.2.6.6.

14.2.6.1 Testing personnel shall be qualified and experienced in the specific arrangement and operation of a suppression system(s) and a releasing function(s) and shall be cognizant of the hazards associated with inadvertent system discharge.

14.2.6.2 Occupant notification shall be required whenever a fire alarm system configured for releasing service is being serviced or tested.

14.2.6.3 Discharge testing of suppression systems shall not be required by this Code.

14.2.6.4 Suppression systems shall be secured from inadvertent actuation, including disconnection of releasing solenoids or electric actuators, closing of valves, other actions, or combinations thereof, for the specific system, for the duration of the fire alarm system testing.

14.2.6.5 Testing shall include verification that the releasing circuits and components energized or actuated by the fire alarm system are electrically monitored for integrity and operate as intended on alarm.

14.2.6.6 Suppression systems and releasing components shall be returned to their functional operating condition upon completion of system testing.

14.2.7 Interface Equipment and Emergency Control Functions.

14.2.7.1* Testing personnel shall be qualified and experienced in the arrangement and operation of interface equipment and emergency control functions.

14.2.7.2 Testing shall be accomplished in accordance with Table 14.4.3.2.

14.2.8 Automated Testing.

14.2.8.1 Automated testing arrangements that provide equivalent means of testing devices to those specified in Table 14.4.3.2 at a frequency at least equivalent to those specified in Table 14.4.3.2 shall be permitted to be used to comply with the requirements of this chapter.

14.2.8.2 Failure of a device on an automated test shall result in an audible and visual trouble signal.

14.2.9* Performance-Based Inspection and Testing. As an alternate means of compliance, subject to the authority having jurisdiction, components and systems shall be permitted to be inspected and tested under a performance-based program.

14.2.10* Test Plan.

14.2.10.1 A test plan shall be developed to clearly establish the scope of the testing for the fire alarm or signaling system.

14.2.10.2 The test plan and results shall be documented with the testing records.

14.3 Inspection.

14.3.1* Unless otherwise permitted by 14.3.2, visual inspections shall be performed in accordance with the schedules in Table 14.3.1 or more often if required by the authority having jurisdiction.

14.3.2* Devices or equipment that is inaccessible for safety considerations (e.g., continuous process operations, energized electrical equipment, radiation, and excessive height) shall be permitted to be inspected during scheduled shutdowns if approved by the authority having jurisdiction.

14.3.3 Extended intervals shall not exceed 18 months.

14.3.4 Initial and reacceptance inspections shall be made to ensure compliance with approved design documents and to ensure installation in accordance with this Code and other required installation standards.

14.3.5 Periodic visual inspections in accordance with Table 14.3.1 shall be made to assure that there are no changes that affect equipment performance.

14.4 Testing.

14.4.1 Initial Acceptance Testing.

14.4.1.1 All new systems shall be inspected and tested in accordance with the requirements of Chapter 14.

Table 14.3.1 Visual Inspection

Component		Initial Acceptance	Periodic Frequency	Method	Reference
1.	All equipment	X	Annual	Ensure there are no changes that affect equipment performance. Inspect for building modifications, occupancy changes, changes in environmental conditions, device location, physical obstructions, device orientation, physical damage, and degree of cleanliness.	14.3.4; 14.3.5
2.	Control equipment:				
	(1) Fire alarm systems monitored for alarm, supervisory, and trouble signals			Verify a system normal condition.	
	(a) Fuses	X	Annual		
	(b) Interfaced equipment	X	Annual		
	(c) Lamps and LEDs	X	Annual		
	(d) Primary (main) power supply	X	Annual		
	(e) Trouble signals	X	Semiannual		
	(2) Fire alarm systems unmonitored for alarm, supervisory, and trouble signals			Verify a system normal condition.	
	(a) Fuses	X	Weekly		
	(b) Interfaced equipment	X	Weekly		
	(c) Lamps and LEDs	X	Weekly		
	(d) Primary (main) power supply	X	Weekly		
	(e) Trouble signals	X	Weekly		
3.	Reserved				
4.	Supervising station alarm systems — transmitters			Verify location, physical condition, and a system normal condition.	
	(1) Digital alarm communicator transmitter (DACT)	X	Annual		
	(2) Digital alarm radio transmitter (DART)	X	Annual		
	(3) McCulloh	X	Annual		
	(4) Radio alarm transmitter (RAT)	X	Annual		
	(5) All other types of communicators	X	Annual		
5.	In-building fire emergency voice/alarm communications equipment	X	Semiannual	Verify location and condition.	
6.	Reserved				
7.	Reserved				
8.	Reserved				
9.*	Batteries				10.6.10
	(1) Valve-regulated lead-acid (VRLA) batteries				
	(a) General	X	N/A	Ensure month and year of manufacture is marked in the month/year format on each battery cell/unit. Verify tightness of battery connections. Inspect terminals for corrosion, excessive container/cover distortion, cracks in cell/unit or leakage of electrolyte. Replace any battery cell/unit if corrosion, distortion, or leakage is observed.	
	(b) Marking	N/A	Semiannual	Verify marking of the month/year of manufacture on each battery cell/unit. Replace any cell/unit if alarm equipment manufacturer's replacement date has been exceeded.	
	(2) Primary (dry cell) other than those used in low-power radio (wireless) systems in accordance with Chapter 23	X	Semiannual	Verify marking of the month/year of manufacture. Replace if alarm equipment/battery manufacturer's replacement date has been exceeded. Replacement date not to exceed 12 months. Verify tightness of connections. Inspect for corrosion or leakage. Replace any battery cell/unit if corrosion or leakage is observed.	

(continues)

Table 14.3.1 *Continued*

Component		Initial Acceptance	Periodic Frequency	Method	Reference
10.	Reserved				
11.	Remote annunciators	X	Semiannual	Verify location and condition.	
12.	Notification appliance circuit power extenders	X	Annual	Verify proper fuse ratings, if any. Verify that lamps and LEDs indicate normal operating status of the equipment.	10.6
13.	Remote power supplies	X	Annual	Verify proper fuse ratings, if any. Verify that lamps and LEDs indicate normal operating status of the equipment.	10.6
14.	Surge protective devices	X	Semiannual	Verify location and condition.	
15.	Reserved				
16.	Optical fiber cable connections	X	Annual	Verify location and condition.	
17.	Initiating devices			Verify location and condition (all devices).	
	(1) Air sampling				
	(a) General	X	Semiannual	Verify that in-line filters, if any, are clean.	17.7.4.6
	(b) Sampling system piping and sampling ports	X	N/A	Verify that sampling system piping and fittings are installed properly, appear airtight, and are permanently fixed. Confirm that sampling pipe is conspicuously identified. Verify that sample ports or points are not obstructed.	17.7.4.6
	(2) Duct detectors				
	(a) General	X	Semiannual	Verify that detector is rigidly mounted. Confirm that no penetrations in a return air duct exist in the vicinity of the detector. Confirm the detector is installed so as to sample the airstream at the proper location in the duct.	17.7.6.5
	(b) Sampling tube	X	Annual	Verify proper orientation. Confirm the sampling tube protrudes into the duct in accordance with system design.	17.7.6.5
	(3) Electromechanical releasing devices	X	Semiannual		
	(4) Fire extinguishing system(s) or suppression system(s) switches	X	Semiannual		
	(5) Manual fire alarm boxes	X	Semiannual		
	(6) Heat detectors	X	Semiannual		
	(7) Radiant energy fire detectors	X	Quarterly	Verify no point requiring detection is obstructed or outside the detector's field of view.	17.8
	(8) Video image smoke and fire detectors	X	Quarterly	Verify no point requiring detection is obstructed or outside the detector's field of view.	17.7.8; 17.8.5
	(9) Smoke detectors (excluding one- and two-family dwellings)	X	Semiannual		
	(10) Projected beam smoke detectors	X	Semiannual	Verify beam path is unobstructed.	
	(11) Supervisory signal devices	X	Semiannual		
	(12) Waterflow devices	X	Semiannual		
18.	Reserved				
19.	Combination systems			Verify location and condition (all types).	
	(1) Fire extinguisher electronic monitoring devices/systems	X	Semiannual		
	(2) Carbon monoxide detectors/systems	X	Semiannual		
20.	Alarm control interface and emergency control function interface	X	Semiannual	Verify location and condition.	
21.	Guard's tour equipment	X	Semiannual	Verify location and condition.	
22.	Notification appliances			Verify location and condition (all appliances).	
	(1) Audible appliances	X	Semiannual		

(continues)

Table 14.3.1 *Continued*

Component		Initial Acceptance	Periodic Frequency	Method	Reference
(2) Loudspeakers		X	Semiannual		
(3) Visual appliances					
(a) General		X	Semiannual		18.5.5
(b) Candela rating		X	N/A	Verify the appliance candela rating marking or the FACU controlled candela rating agrees with the approved drawings.	18.5.5
23.	Exit marking audible notification appliances	X	Semiannual	Verify location and condition.	
24.	Reserved				
25.	Two-way emergency communications systems	X	Annual	Verify location and condition.	
26.	Reserved				
27.	Supervising station alarm systems — receivers				
(1) Signal receipt		X	Daily	Verify receipt of signal.	
(2) Receivers		X	Annual	Verify location and normal condition.	
28.	Public emergency alarm reporting system transmission equipment			Verify location and condition.	
(1) Publicly accessible alarm box		X	Semiannual		
(2) Auxiliary box		X	Annual		
(3) Master box					
(a) Manual operation		X	Semiannual		
(b) Auxiliary operation		X	Annual		
29.	Reserved				
30.	Mass notification system				
(1) Monitored for integrity				Verify a system normal condition.	
(a) Control equipment					
(i) Fuses		X	Annual		
(ii) Interfaces		X	Annual		
(iii) Lamps/LED		X	Annual		
(iv) Primary (main) power supply		X	Annual		
(b) Secondary power batteries		X	Annual		
(c) Initiating devices		X	Annual		
(d) Notification appliances		X	Annual		
(2) Not monitored for integrity; installed prior to adoption of the 2010 edition				Verify a system normal condition.	
(a) Control equipment					
(i) Fuses		X	Semiannual		
(ii) Interfaces		X	Semiannual		
(iii) Lamps/LED		X	Semiannual		
(iv) Primary (main) power supply		X	Semiannual		
(b) Secondary power batteries		X	Semiannual		
(c) Initiating devices		X	Semiannual		
(d) Notification appliances		X	Semiannual		
(3) Antenna		X	Annual	Verify location and condition.	
(4) Transceivers		X	Annual	Verify location and condition.	

Note: N/A = not applicable, no minimum requirement established.

*For other than VRLA or primary (dry) cell batteries, refer to the battery manufacturer's published instructions or IEEE 450, *Recommended Practice for Maintenance, Testing, and Replacement of Vented Lead-Acid Batteries for Stationary Applications*, for vented lead-acid batteries, and IEEE 1106, *Recommended Practice for Installation, Maintenance, Testing, and Replacement of Vented Nickel-Cadmium Batteries for Stationary Applications*, for nickel-cadmium batteries.

14.4.1.2 The authority having jurisdiction shall be notified prior to the initial acceptance test.

14.4.2* Reacceptance Testing.

14.4.2.1 When an initiating device, notification appliance, or control relay is added, it shall be functionally tested.

14.4.2.2 When an initiating device, notification appliance, or control relay is deleted, another device, appliance, or control relay on the circuit shall be operated.

14.4.2.3 When modifications or repairs to control unit hardware are made, the control unit shall be tested in accordance with Table 14.4.3.2, items 2(1) and 2(4).

14.4.2.4 When changes are made to site-specific software, the following shall apply:

- (1) All functions known to be affected by the change, or identified by a means that indicates changes, shall be 100 percent tested.
- (2) In addition, 10 percent of initiating devices that are not directly affected by the change, up to a maximum of 50 devices, also shall be tested and correct system operation shall be verified.
- (3) A revised record of completion in accordance with 7.5.6 shall be prepared to reflect these changes.

14.4.2.5 Changes to the system executive software shall require a 10 percent functional test of the system, including a test of at least one device on each input and output circuit to verify critical system functions such as notification appliances, control functions, and off-premises reporting.

14.4.2.6 Where changes are made to system executive software or site-specific software for control equipment or transmitting equipment from a remote location not on the protected premises, such changes shall not be made without an individual, meeting the qualifications of 10.5.3.2, 10.5.3.3, or 10.5.3.5, being at the protected premises to verify that testing is accomplished in accordance with 14.4.2.

14.4.3* Test Methods.

14.4.3.1* At the request of the authority having jurisdiction, the central station facility installation shall be inspected for complete information regarding the central station system, including specifications, wiring diagrams, and floor plans that have been submitted for approval prior to installation of equipment and wiring.

14.4.3.2* Systems and associated equipment shall be tested according to Table 14.4.3.2.

14.4.3.3 Video image smoke and flame detectors shall be inspected, tested, and maintained in accordance with the manufacturer's published instructions.

14.4.3.4 Gas detectors shall be inspected, tested, and maintained in accordance with manufacturers' published instructions.

14.4.3.5 Testing of Carbon Monoxide System Detectors. For all carbon monoxide system detectors carbon monoxide tests shall be performed at initial acceptance and annually by the introduction of carbon monoxide into the sensing chamber or element.

14.4.4* Testing Frequency. Unless otherwise permitted by other sections of this Code, testing shall be performed in

accordance with the schedules in Table 14.4.3.2 or more often if required by the authority having jurisdiction.

14.4.4.1* Devices or equipment that are inaccessible for safety considerations (e.g., continuous process operations, energized electrical equipment, radiation, and excessive height) shall be permitted to be tested during scheduled shutdowns if approved by the authority having jurisdiction. Extended intervals shall not exceed 18 months.

14.4.4.2 If automatic testing is performed at least weekly by a remotely monitored fire alarm control unit specifically listed for the application, the manual testing frequency shall be permitted to be extended to annually. Table 14.4.3.2 shall apply.

14.4.4.3* In other than one- and two-family dwellings, sensitivity of smoke detectors shall be tested in accordance with 14.4.4.3.1 through 14.4.4.3.6.

14.4.4.3.1 Sensitivity shall be checked within 1 year after installation.

14.4.4.3.2 Sensitivity shall be checked every alternate year thereafter unless otherwise permitted by compliance with 14.4.4.3.3.

14.4.4.3.3 After the second required calibration test, if sensitivity tests indicate that the device has remained within its listed and marked sensitivity range, the length of time between calibration tests shall be permitted to be extended to a maximum of 5 years.

14.4.4.3.3.1 If the frequency is extended, records of nuisance alarms and subsequent trends of these alarms shall be maintained.

14.4.4.3.3.2 In zones or in areas where nuisance alarms show any increase over the previous year, calibration tests shall be performed.

14.4.4.3.4 Unless otherwise permitted by 14.4.4.3.5, smoke detectors found to have a sensitivity outside the listed and marked sensitivity range shall be cleaned and recalibrated or be replaced.

14.4.4.3.5 Smoke detectors listed as field adjustable shall be permitted to either be adjusted within the listed and marked sensitivity range, cleaned, and recalibrated, or be replaced.

14.4.4.3.6 The detector sensitivity shall not be tested or measured using any device that administers an unmeasured concentration of smoke or other aerosol into the detector or smoke alarm.

14.4.4.4 Test frequency of interfaced equipment shall be the same as specified by the applicable NFPA standards for the equipment being supervised.

14.4.4.5 Restorable fixed-temperature, spot-type heat detectors shall be tested in accordance with 14.4.4.5.1 through 14.4.4.5.4.

14.4.4.5.1 Two or more detectors shall be tested on each initiating circuit annually.

14.4.4.5.2 Different detectors shall be tested each year.

14.4.4.5.3 Test records shall be kept by the building owner specifying which detectors have been tested.

Table 14.4.3.2 Testing

Component		Initial Acceptance	Periodic Frequency	Method
1.	All equipment	X		See Table 14.3.1.
2.	Control unit			
	(1) Functions	X	Annually	Verify correct receipt of alarm, supervisory, and trouble signals (inputs); operation of evacuation signals and auxiliary functions (outputs); circuit supervision, including detection of open circuits and ground faults; and power supply supervision for detection of loss of ac power and disconnection of secondary batteries.
	(2) Fuses	X	Annually	Verify rating and supervision.
	(3) Interfaced equipment	X	Annually	Verify integrity of single or multiple circuits providing interface between two or more control units. Test interfaced equipment connections by operating or simulating operation of the equipment being supervised. Verify signals required to be transmitted at the control unit.
	(4) Lamps and LEDs	X	Annually	Illuminate lamps and LEDs.
	(5) Primary (main) power supply	X	Annually	Disconnect all secondary (standby) power and test under maximum load, including all alarm appliances requiring simultaneous operation. Reconnect all secondary (standby) power at end of test. Test redundant power supplies separately.
3.	Alarm control unit trouble signals			
	(1) Audible and visual	X	Annually	Verify operation of control unit trouble signals. Verify ring-back feature for systems using a trouble-silencing switch that requires resetting.
	(2) Disconnect switches	X	Annually	If control unit has disconnect or isolating switches, verify performance of intended function of each switch. Verify receipt of trouble signal when a supervised function is disconnected.
	(3) Ground-fault monitoring circuit	X	Annually	If the system has a ground detection feature, verify the occurrence of ground-fault indication whenever any installation conductor is grounded.
	(4) Transmission of signals to off-premises location	X	Annually	Actuate an initiating device and verify receipt of alarm signal at the off-premises location. Create a trouble condition and verify receipt of a trouble signal at the off-premises location. Actuate a supervisory device and verify receipt of a supervisory signal at the off-premises location. If a transmission carrier is capable of operation under a single- or multiple-fault condition, actuate an initiating device during such fault condition and verify receipt of an alarm signal and a trouble signal at the off-premises location.
4.	Supervising station alarm systems — transmission equipment			
	(1) All equipment	X	Annually	^a Test all system functions and features in accordance with the equipment manufacturer's published instructions for correct operation in conformance with the applicable sections of Chapter 26. Except for DACT, actuate initiating device and verify receipt of the correct initiating device signal at the supervising station within 90 seconds. Upon completion of the test, restore the system to its functional operating condition.
	(2) Digital alarm communicator transmitter (DACT)	X	Annually	If test jacks are used, conduct the first and last tests without the use of the test jack. Except for DACTs installed prior to adoption of the 2013 edition of NFPA 72 that are connected to a telephone line (number) that is also supervised for adverse conditions by a derived local channel, ensure connection of the DACT to two separate means of transmission. Test DACT for line seizure capability by initiating a signal while using the telephone line (primary line for DACTs using two telephone lines) for a telephone call. Ensure that the call is interrupted and that the communicator connects to the digital alarm receiver. Verify receipt of the correct signal at the supervising station. Verify each transmission attempt is completed within 90 seconds from going off-hook to on-hook. Disconnect the telephone line (primary line for DACTs using two telephone lines) from the DACT. Verify indication of the DACT trouble signal occurs at the premises fire alarm control unit within 4 minutes of detection of the fault. Verify receipt of the telephone line trouble signal at the supervising station. Restore the telephone line (primary line for DACTs using two telephone lines), reset the fire alarm control unit, and verify that the telephone line fault trouble signal returns to normal. Verify that the supervising station receives the restoral signal from the DACT. Disconnect the secondary means of transmission from the DACT. Verify indication of the DACT trouble signal occurs at the premises fire alarm control unit within 4 minutes of detection of the fault. Verify receipt of the secondary means trouble signal at the supervising station. Restore the secondary means of transmission, reset the fire alarm control unit, and verify that the trouble signal returns to normal. Verify that the supervising station receives the restoral signal from the secondary transmitter.

(continues)

Table 14.4.3.2 *Continued*

Component	Initial Acceptance	Periodic Frequency	Method
(3) Digital alarm radio transmitter (DART)	X	Annually	Cause the DACT to transmit a signal to the DACR while a fault in the telephone line (number) (primary line for DACTs using two telephone lines) is simulated. Verify utilization of the secondary communications path by the DACT to complete the transmission to the DACR.
(4) McCulloh transmitter	X	Annually	Disconnect the primary telephone line. Verify transmission of a trouble signal to the supervising station by the DART occurs within 4 minutes. Actuate initiating device. Verify production of not less than three complete rounds of not less than three signal impulses each by the McCulloh transmitter. If end-to-end metallic continuity is present and with a balanced circuit, cause each of the following four transmission channel fault conditions in turn, and verify receipt of correct signals at the supervising station: (1) Open (2) Ground (3) Wire-to-wire short (4) Open and ground If end-to-end metallic continuity is not present and with a properly balanced circuit, cause each of the following three transmission channel fault conditions in turn, and verify receipt of correct signals at the supervising station: (1) Open (2) Ground (3) Wire-to-wire short
(5) Radio alarm transmitter (RAT)	X	Annually	Cause a fault between elements of the transmitting equipment. Verify indication of the fault at the protected premises, or transmission of trouble signal to the supervising station.
(6) Performance-based technologies	X	Annually	Perform tests to ensure the monitoring of integrity of the transmission technology and technology path. Where shared communications equipment is used as permitted by 26.6.3.12, provided secondary (standby) power sources shall be tested in accordance with Table 14.4.3.2, item 7, 8, or 9, as applicable. Where a single communications path is used, disconnect the communication path. Manually initiate an alarm signal transmission or allow the check-in (handshake) signal to be transmitted automatically. Verify the premises unit annunciates the failure within 200 seconds of the transmission failure. Restore the communication path. Where multiple communication paths are used, disconnect both communication paths. Manually initiate an alarm signal transmission. Verify the premises control unit annunciates the failure within 200 seconds of the transmission failure. Restore both communication paths.
5. Emergency communications equipment			
(1) Amplifier/tone generators	X	Annually	Verify correct switching and operation of backup equipment.
(2) Call-in signal silence	X	Annually	Operate/function and verify receipt of correct visual and audible signals at control unit.
(3) Off-hook indicator (ring down)	X	Annually	Install phone set or remove phone from hook and verify receipt of signal at control unit.
(4) Phone jacks	X	Annually	Visually inspect phone jack and initiate communications path through jack.
(5) Phone set	X	Annually	Actuate each phone set and verify correct operation.
(6) System performance	X	Annually	Operate the system with a minimum of any five handsets simultaneously. Verify voice quality and clarity.
6. Engine-driven generator	X	Monthly	If an engine-driven generator dedicated to the system is used as a required power source, verify operation of the generator and transfer switch in accordance with NFPA 110 by the building owner.
7. Emergency power supply system/stored-emergency power supply system (EPSS/SEPSS)	X	Annually	If an EPSS/SEPSS dedicated to the system is used as a required power source, verify by the building owner operation of the EPSS/SEPSS in accordance with NFPA 111.
8. Secondary (standby) power supply ^c	X	Annually	Disconnect all primary (main) power supplies and verify the occurrence of required trouble indication for loss of primary power. Measure or verify the system's standby and alarm current demand using the equipment manufacturer's data and verify the battery's rated capacity exceeds the system's power demand, including the safety margin. Operate general alarm systems a minimum of 5 minutes and emergency voice communications systems for a minimum of 15 minutes. Reconnect primary (main) power supply at end of test.
9. VRLA battery and charger ^d			Prior to conducting any battery testing, verify by the person conducting the test, that all system software stored in volatile memory is protected from loss.

(continues)

Table 14.4.3.2 *Continued*

Component	Initial Acceptance	Periodic Frequency	Method
(1) Temperature test	X	Semiannually	Upon initially opening the cabinet door, measure the internal ambient temperature of the enclosure. Measure the temperature of each battery cell/unit at the negative terminal with an infrared thermometer. Replace any battery cell/unit if its temperature is greater than 18°F (10°C) above the measured internal ambient temperature of the enclosure.
(2) Charger test ^c	X	Semiannually	With the battery fully charged and connected to the charger, measure the voltage across the battery with a voltmeter. Verify the voltage is within the battery/alarm equipment manufacturer's recommendations. If the voltage is outside of the specified limits, either adjust the charger to within limits or replace the charger.
(3) Cell/Unit voltage test	X	Semiannually	With the battery fully charged and connected to the charger, measure the voltage of each cell/unit with a voltmeter. Replace the battery when any cell/unit measures a voltage less than 13.26 volts.
(4) Ohmic test ^f	X	N/A	When the battery is installed, establish a baseline ohmic value for each battery cell/unit or where available use baseline ohmic values provided by the battery or test equipment manufacturer. In either case record the base line ohmic value on each battery cell/unit.
		Semiannually	With the battery fully charged, measure the internal ohmic value of each battery cell/unit. Record the test date and ohmic value on each cell/unit. Replace the battery when the ohmic measurement of any cell/unit deviates from the established baseline by 30% or more for conductance, or 40% or more for resistance or impedance. Where the battery or test equipment manufacturer's baseline ohmic values are used, replace the battery when any cell/unit has an internal ohmic value outside of the acceptable range.
(5) Replacement/Load test ^g		3 years	Replace the battery or conduct a load test of the battery capacity. Load test the battery based on the manufacturer's specifications for a discharge rate of 3 hours or more by applying the current indicated for the selected hourly discharge rate continuously, until the terminal voltage decreases to the end voltage specified by the manufacturer. Record the test duration and calculate the battery capacity including adjustment for ambient temperature. Replace the battery if capacity is less than or equal to 80% or at the next scheduled test interval if battery capacity is less than 85%.
10. Public emergency alarm reporting system — wired system	X	Daily	Manual tests of the power supply for public reporting circuits shall be made and recorded at least once during each 24-hour period. Such tests shall include the following: (1) Current strength of each circuit. Changes in current of any circuit exceeding 10 percent shall be investigated immediately. (2) Voltage across terminals of each circuit inside of terminals of protective devices. Changes in voltage of any circuit exceeding 10 percent shall be investigated immediately. (3) ^h Voltage between ground and circuits. If this test shows a reading in excess of 50 percent of that shown in the test specified in (2), the trouble shall be immediately located and cleared. Readings in excess of 25 percent shall be given early attention. These readings shall be taken with a calibrated voltmeter of not more than 100 ohms resistance per volt. Systems in which each circuit is supplied by an independent current source (Forms 3 and 4) require tests between ground and each side of each circuit. Common current source systems (Form 2) require voltage tests between ground and each terminal of each battery and other current source. (4) Ground current reading shall be permitted in lieu of (3). If this method of testing is used, all grounds showing a current reading in excess of 5 percent of the supplied line current shall be given immediate attention. (5) Voltage across terminals of common battery on switchboard side of fuses. (6) Voltage between common battery terminals and ground. Abnormal ground readings shall be investigated immediately. Tests specified in (5) and (6) shall apply only to those systems using a common battery. If more than one common battery is used, each common battery shall be tested.
11. Remote annunciators	X	Annually	Verify the correct operation and identification of annunciators. If provided, verify the correct operation of annunciator under a fault condition.
12. Reserved			
13. Reserved			
14. Wireless communications	X	Annually	Test per the manufacturer's published instructions.
15. Conductors — metallic			

(continues)

Table 14.4.3.2 *Continued*

Component		Initial Acceptance	Periodic Frequency	Method
(1) Stray voltage		X	N/A	Test all installation conductors with a volt/ohmmeter to verify that there are no stray (unwanted) voltages between installation conductors or between installation conductors and ground. Verify the maximum allowable stray voltage does not exceed 1 volt ac/dc, unless a different threshold is specified in the manufacturer's published instructions for the installed equipment.
(2) Ground faults		X	N/A	Test all installation conductors, other than those intentionally and permanently grounded, for isolation from ground per the installed equipment manufacturer's published instructions.
(3) Short-circuit faults		X	N/A	Test all installation conductors, other than those intentionally connected together, for conductor-to-conductor isolation per the manufacturer's published instructions for the installed equipment. Also test these same circuits conductor-to-ground.
(4) Loop resistance		X	N/A	With each initiating and indicating circuit installation conductor pair short-circuited at the far end, measure and record the resistance of each circuit. Verify that the loop resistance does not exceed the limits specified in the manufacturer's published instructions for the installed equipment.
(5) Circuit integrity		X	N/A	For initial and reacceptance testing, confirm the introduction of a fault in any circuit monitored for integrity results in a trouble indication at the fire alarm control unit. Open one connection at not less than 10 percent of the initiating devices, notification appliances and controlled devices on every initiating device circuit, notification appliance circuit, and signaling line circuit. Confirm all circuits perform as indicated in Sections 23.5, 23.6, and 23.7.
		N/A	Annually	For periodic testing, test each initiating device circuit, notification appliance circuit, and signaling line circuit for correct indication at the control unit. Confirm all circuits perform as indicated in Sections 23.5, 23.6, and 23.7.
16. Nonmetallic pathways				
(1) Optical fiber cables		X	N/A	Test the transmission characteristics of optical fibers by the use of an optical power meter or by an optical time domain reflectometer used to measure the relative power loss of the line. Test result data must meet or exceed ANSI/TIA 568.3, <i>Optical Fiber Cabling and Components Standard</i> , related to fiber-optic lines and connection/splice losses and the control unit manufacturer's published specifications.
(2) Circuit integrity		X	N/A	For initial and reacceptance testing, confirm the introduction of a fault in any circuit monitored for integrity results in a trouble indication at the fire alarm control unit. Open one connection at not less than 10 percent of the initiating devices, notification appliances, and controlled devices on every initiating device circuit, notification appliance circuit, and signaling line circuit. Confirm all circuits perform as indicated in Sections 23.5, 23.6, and 23.7.
		N/A	Annually	For periodic testing, test each initiating device circuit, notification appliance circuit, and signaling line circuit for correct indication at the control unit. Confirm all circuits perform as indicated in Sections 23.5, 23.6, and 23.7.
17. Initiating devices ^d				
(1) Electromechanical releasing device				
(a) Nonrestorable-type link		X	Annually	Verify correct operation by removal of the fusible link and operation of the associated device.
(b) Restorable-type link ^e		X	Annually	Verify correct operation by removal of the fusible link and operation of the associated device.
(2) Fire extinguishing system(s) or suppression system(s) alarm switch		X	Annually	Operate the switch mechanically or electrically and verify receipt of signal by the fire alarm control unit.
(3) Fire-gas and other detectors		X	Annually	Test fire-gas detectors and other fire detectors as prescribed by the manufacturer and as necessary for the application.
(4) Heat detectors				
(a) Fixed-temperature, rate-of-rise, rate of compensation, restorable line, spot type (excluding pneumatic tube type)		X	Annually (see 14.4.4.5)	Perform heat test with a listed and labeled heat source or in accordance with the manufacturer's published instructions. Assume that the test method for the installed equipment does not damage the nonrestorable fixed-temperature element of a combination rate-of-rise/fixed-temperature element detector.
(b) Fixed-temperature, nonrestorable line type		X	Annually	Do not perform heat test. Test functionality mechanically and electrically. Measure and record loop resistance. Investigate changes from acceptance test.
(c) Fixed-temperature, nonrestorable spot type		X	See Method	After 15 years from initial installation, replace all devices or have 2 detectors per 100 laboratory tested. Replace the 2 detectors with new devices. If a failure occurs on any of the detectors removed, remove and test additional detectors to determine either a general problem involving faulty detectors or a localized problem involving 1 or 2 defective detectors.
				If detectors are tested instead of replaced, repeat tests at intervals of 5 years.
(d) Restorable line type, pneumatic tube only		X	Annually	Do not perform heat tests. Test functionality mechanically and electrically. Perform heat tests (where test chambers are in circuit), with a listed and labeled heat source or in accordance with the manufacturer's published instructions of the detector or conduct a test with pressure pump.

(continues)

Table 14.4.3.2 *Continued*

Component	Initial Acceptance	Periodic Frequency	Method
(e) Single- and multiple-station heat alarms	X	Annually	Conduct functional tests according to manufacturer's published instructions. Do not test nonrestorable heat detectors with heat.
(5) Manual fire alarm boxes	X	Annually	Operate manual fire alarm boxes per the manufacturer's published instructions. Test both key-operated presignal and general alarm manual fire alarm boxes.
(6) Radiant energy fire detectors	X	Semiannually	Test flame detectors and spark/ember detectors in accordance with the manufacturer's published instructions to determine that each detector is operative. Determine flame detector and spark/ember detector sensitivity using any of the following: (1) Calibrated test method (2) Manufacturer's calibrated sensitivity test instrument (3) Listed control unit arranged for the purpose (4) Other approved calibrated sensitivity test method that is directly proportional to the input signal from a fire, consistent with the detector listing or approval If designed to be field adjustable, replace detectors found to be outside of the approved range of sensitivity or adjust to bring them into the approved range. Do not determine flame detector and spark/ember detector sensitivity using a light source that administers an unmeasured quantity of radiation at an undefined distance from the detector.
(7) Smoke detectors — functional test			
(a) In other than one- and two-family dwellings, system detectors	X	Annually	¹ Test smoke detectors in place to ensure smoke entry into the sensing chamber and an alarm response. Use smoke or a listed and labeled product acceptable to the manufacturer or in accordance with their published instructions. Other methods listed in the manufacturer's published instructions that ensure smoke entry from the protected area, through the vents, into the sensing chamber can be used.
(b) Single- and multiple-station smoke alarms connected to protected premises systems	X	Annually	Perform a functional test on all single- and multiple-station smoke alarms connected to a protected premises fire alarm system by putting the smoke alarm into an alarm condition.
(c) System smoke detectors used in one- and two-family dwellings	X	Annually	Conduct functional tests according to manufacturer's published instructions.
(d) Air sampling	X	Annually	Test with smoke or a listed and labeled product acceptable to the manufacturer or in accordance with their published instructions. In the absence of an automatic, listed airflow supervision feature, test from the end sampling port or point on each pipe run and verify airflow through all other ports or points.
(e) Duct type	X	Annually	In addition to the testing required in Table 14.4.3.2(17)(7)(a) and Table 14.4.3.2(17)(8), test duct smoke detectors that use sampling tubes to ensure that they will properly sample the airstream in the duct using a method acceptable to the manufacturer or in accordance with their published instructions.
(f) Projected beam type	X	Annually	Test the detector by introducing smoke, other aerosol, or an optical filter into the beam path.
(g) Smoke detector with built-in thermal element	X	Annually	Operate both portions of the detector independently as described for the respective devices.
(h) Smoke detectors with control output functions	X	Annually	Verify that the control capability remains operable even if all of the initiating devices connected to the same initiating device circuit or signaling line circuit are in an alarm state.
(8) Smoke detectors — sensitivity testing			
In other than one- and two-family dwellings, system detectors	N/A	See 14.4.4.3	¹ Perform any of the following tests to ensure that each smoke detector is within its listed and marked sensitivity range: (1) Calibrated test method (2) Manufacturer's calibrated sensitivity test instrument (3) Listed control equipment arranged for the purpose (4) Smoke detector/control unit arrangement whereby the detector causes a signal at the control unit when its sensitivity is outside its listed sensitivity range (5) Other calibrated sensitivity test method approved by the authority having jurisdiction
(9) Carbon monoxide detectors/ carbon monoxide alarms connected to protected premises systems			
(a) CO entry test	X	Annually	Test the devices in place to ensure CO entry to the sensing chamber by introduction through the vents, to the sensing chamber of listed and labeled product acceptable to the manufacturer or in accordance with manufacturer's published instructions
(b) Air sampling	X	Annually	Per test methods documented in the manufacturer's published instructions, verify detector alarm response through the end sampling port on each pipe run; verify airflow through all other ports as well.
(c) Duct type	X	Annually	Test or inspect air duct detectors to ensure that the device will sample the airstream in accordance with the manufacturer's published instructions.

(continues)

Table 14.4.3.2 *Continued*

Component	Initial Acceptance	Periodic Frequency	Method
(d) CO detector with control output functions	X	Annually	Within each protected space, verify that the control capability remains operable even if all of the initiating devices connected to the same initiating device circuit or signaling line circuit are in an alarm state.
(10) Initiating devices, supervisory			
(a) Control valve switch	X	Semiannual	Operate valve and verify signal receipt to be within the first two revolutions of the handwheel or within one-fifth of the travel distance, or per the manufacturer's published instructions. Continue to cycle outside stem and yoke valves and verify switch does not reset during full travel of the valve stem.
(b) High- or low-air pressure switch	X	Annually	Operate switch and verify receipt of signal is obtained where the required pressure is increased or decreased a maximum 10 psi (70 kPa) from the required pressure level or in accordance with manufacturer's published instructions.
(c) Steam pressure	X	Annually	Operate switch and verify receipt of signal is obtained before pressure decreases to 110 percent of the minimum operating pressure of the steam-operated equipment.
(d) Pressure supervisory devices for other sources	X	Annually	Operate switch and verify receipt of signal is obtained where the required pressure is increased or decreased from the normal operating pressure by an amount specified in approved design documents.
(e) Room temperature switch	X	Annually	Operate switch and verify receipt of signal to indicate the decrease in room temperature to 40°F (4.4°C) and its restoration to above 40°F (4.4°C).
(f) Water level switch	X	Annually	Operate switch and verify receipt of signal indicating the water level raised or lowered a maximum 3 in. (70 mm) from the required level within a pressure tank, or a maximum 12 in. (300 mm) from the required level of a nonpressure tank. Also verify its restoral to required level.
(g) Water temperature switch	X	Annually	Operate switch and verify receipt of signal to indicate the decrease in water temperature to 40°F (4.4°C) and its restoration to above 40°F (4.4°C).
(11) Mechanical, electrosonic, or pressure-type waterflow device	X	Semiannually	Water shall be flowed through an inspector's test connection indicating the flow of water equal to that from a single sprinkler of the smallest orifice size installed in the system or other listed and approved waterflow switch test methods for wet-pipe systems, or an alarm test bypass connection for dry-pipe, pre-action, or deluge systems in accordance with NFPA 25.
(12) Multi-sensor fire detector or multi-criteria fire detector or combination fire detector	X	Annually	1. Test each detector in accordance with the manufacturer's published instructions. Test each of the sensors present within the detector (e.g., smoke/heat/CO, etc.) independently for the specific detection principle, regardless of the configuration status at the time of testing, or individual sensors together if the technology allows individual sensor responses to be verified, or where sensors cannot be tested individually, test the primary sensor.^m 2. Perform tests as described for the respective sensors by introduction of the physical phenomena to the sensing element. An electronic check (magnets, analog values, etc.) is not sufficient to comply with this requirement. 3. Verify by using the detector manufacturer's published instructions that the test gas used will not impair the operation of any sensing chamber of a multi-sensor, multi-criteria, or combination fire detector. 4. Confirm the result of the sensor(s) test(s) through indication at the detector or control unit. 5. Record all tests and results.
18. Special hazard equipment			
(1) Abort switch (dead-man type)	X	Annually	Operate abort switch and verify correct sequence and operation.
(2) Abort switch (recycle type)	X	Annually	Operate abort switch and verify development of correct matrix with each sensor operated.
(3) Abort switch (special type)	X	Annually	Operate abort switch and verify correct sequence and operation in accordance with authority having jurisdiction. Observe sequencing as specified on as-built drawings or in system owner's manual.
(4) Cross-zone detection circuit	X	Annually	Operate one sensor or detector on each zone. Verify occurrence of correct sequence with operation of first zone and then with operation of second zone.
(5) Matrix-type circuit	X	Annually	Operate all sensors in system. Verify development of correct matrix with each sensor operated.
(6) Release solenoid circuit ⁿ	X	Annually	Verify operation of solenoid.
(7) Squibb release circuit	X	Annually	Use AGI flashbulb or other test light approved by the manufacturer. Verify operation of flashbulb or light.
(8) Verified, sequential, or counting zone circuit	X	Annually	Operate required sensors at a minimum of four locations in circuit. Verify correct sequence with both the first and second detector in alarm.
(9) All above devices or circuits or combinations thereof	X	Annually	Verify supervision of circuits by creating an open circuit.
19. Combination systems			
(1) Fire extinguisher electronic monitoring device/system	X	Annually	Test communication between the device connecting the fire extinguisher electronic monitoring device/system and the fire alarm control unit to ensure proper signals are received at the fire alarm control unit and remote annunciator(s) if applicable.

(continues)

Table 14.4.3.2 *Continued*

Component	Initial Acceptance	Periodic Frequency	Method
(d) CO detector with control output functions	X	Annually	Within each protected space, verify that the control capability remains operable even if all of the initiating devices connected to the same initiating device circuit or signaling line circuit are in an alarm state.
(10) Initiating devices, supervisory			
(a) Control valve switch	X	Semiannual	Operate valve and verify signal receipt to be within the first two revolutions of the handwheel or within one-fifth of the travel distance, or per the manufacturer's published instructions. Continue to cycle outside stem and yoke valves and verify switch does not reset during full travel of the valve stem.
(b) High- or low-air pressure switch	X	Annually	Operate switch and verify receipt of signal is obtained where the required pressure is increased or decreased a maximum 10 psi (70 kPa) from the required pressure level or in accordance with manufacturer's published instructions.
(c) Steam pressure	X	Annually	Operate switch and verify receipt of signal is obtained before pressure decreases to 110 percent of the minimum operating pressure of the steam-operated equipment.
(d) Pressure supervisory devices for other sources	X	Annually	Operate switch and verify receipt of signal is obtained where the required pressure is increased or decreased from the normal operating pressure by an amount specified in approved design documents.
(e) Room temperature switch	X	Annually	Operate switch and verify receipt of signal to indicate the decrease in room temperature to 40°F (4.4°C) and its restoration to above 40°F (4.4°C).
(f) Water level switch	X	Annually	Operate switch and verify receipt of signal indicating the water level raised or lowered a maximum 3 in. (70 mm) from the required level within a pressure tank, or a maximum 12 in. (300 mm) from the required level of a nonpressure tank. Also verify its restoral to required level.
(g) Water temperature switch	X	Annually	Operate switch and verify receipt of signal to indicate the decrease in water temperature to 40°F (4.4°C) and its restoration to above 40°F (4.4°C).
(11) Mechanical, electrosonic, or pressure-type waterflow device	X	Semiannually	Water shall be flowed through an inspector's test connection indicating the flow of water equal to that from a single sprinkler of the smallest orifice size installed in the system or other listed and approved waterflow switch test methods for wet-pipe systems, or an alarm test bypass connection for dry-pipe, pre-action, or deluge systems in accordance with NFPA 25.
(12) Multi-sensor fire detector or multi-criteria fire detector or combination fire detector	X	Annually	1. Test each detector in accordance with the manufacturer's published instructions. Test each of the sensors present within the detector (e.g., smoke/heat/CO, etc.) independently for the specific detection principle, regardless of the configuration status at the time of testing, or individual sensors together if the technology allows individual sensor responses to be verified, or where sensors cannot be tested individually, test the primary sensor.^m 2. Perform tests as described for the respective sensors by introduction of the physical phenomena to the sensing element. An electronic check (magnets, analog values, etc.) is not sufficient to comply with this requirement. 3. Verify by using the detector manufacturer's published instructions that the test gas used will not impair the operation of any sensing chamber of a multi-sensor, multi-criteria, or combination fire detector. 4. Confirm the result of the sensor(s) test(s) through indication at the detector or control unit. 5. Record all tests and results.
18. Special hazard equipment			
(1) Abort switch (dead-man type)	X	Annually	Operate abort switch and verify correct sequence and operation.
(2) Abort switch (recycle type)	X	Annually	Operate abort switch and verify development of correct matrix with each sensor operated.
(3) Abort switch (special type)	X	Annually	Operate abort switch and verify correct sequence and operation in accordance with authority having jurisdiction. Observe sequencing as specified on as-built drawings or in system owner's manual.
(4) Cross-zone detection circuit	X	Annually	Operate one sensor or detector on each zone. Verify occurrence of correct sequence with operation of first zone and then with operation of second zone.
(5) Matrix-type circuit	X	Annually	Operate all sensors in system. Verify development of correct matrix with each sensor operated.
(6) Release solenoid circuit ⁿ	X	Annually	Verify operation of solenoid.
(7) Squibb release circuit	X	Annually	Use AGI flashbulb or other test light approved by the manufacturer. Verify operation of flashbulb or light.
(8) Verified, sequential, or counting zone circuit	X	Annually	Operate required sensors at a minimum of four locations in circuit. Verify correct sequence with both the first and second detector in alarm.
(9) All above devices or circuits or combinations thereof	X	Annually	Verify supervision of circuits by creating an open circuit.
19. Combination systems			
(1) Fire extinguisher electronic monitoring device/system	X	Annually	Test communication between the device connecting the fire extinguisher electronic monitoring device/system and the fire alarm control unit to ensure proper signals are received at the fire alarm control unit and remote annunciator(s) if applicable.

(continues)

Table 14.4.3.2 *Continued*

Component		Initial Acceptance	Periodic Frequency	Method
(2) Carbon monoxide device/system		X	Annually	Test communication between the device connecting the carbon monoxide device/system and the fire alarm control unit to ensure proper signals are received at the fire alarm control unit and remote annunciator(s) if applicable.
20.	Interface equipment ^d	X	See 14.4.4.4	Test interface equipment connections by operating or simulating the equipment being supervised. Verify signals required to be transmitted are received at the control unit. Test frequency for interface equipment is the same as the frequency required by the applicable NFPA standard(s) for the equipment being supervised.
21.	Guard's tour equipment	X	Annually	Test the device in accordance with the manufacturer's published instructions.
22.	Alarm notification appliances (1) Audible ^e	X	N/A	For initial and reacceptance testing, measure sound pressure levels for alert tone signals and evacuation signal tones with a sound level meter meeting ANSI/ASA S1.4/Part 1, <i>Electroacoustics — Sound Level Meters — Part 1: Specifications</i> , Type 2 requirements. Measure sound pressure levels to determine if they are in compliance with Chapter 18 and the required performance, as documented per 7.3.4. Set the sound level meter in accordance with ANSI/ASA S3.41, <i>Audible Emergency Evacuation (E2) and Evacuation Signals with Relocation Instructions (ESRI)</i> , using the time-weighted characteristic F (FAST).
	(2) Audible textual notification appliances (loudspeakers and other appliances to convey voice messages)	N/A X	Annually N/A	^f For periodic testing, verify the operation of the notification appliances. For initial and reacceptance testing, measure sound pressure levels for signals with a sound level meter meeting ANSI/ASA S1.4/Part 1, <i>Electroacoustics — Sound Level Meters — Part 1: Specifications</i> , Type 2 requirements. Measure sound pressure levels throughout the protected area to determine if they are in compliance with Chapter 18 and the required performance, as documented per 7.3.4. Set the sound level meter in accordance with ANSI/ASA S3.41, <i>Audible Emergency Evacuation (E2) and Evacuation Signals with Relocation Instructions (ESRI)</i> , using the time-weighted characteristic F (FAST).
	(3) Visual	N/A X	Annually N/A	Verify audible information to be intelligible and in compliance with 14.4.11. ^g For periodic testing, verify the operation of the notification appliances. Perform initial and reacceptance testing in accordance with the manufacturer's published instructions. Verify appliance locations to be per approved layout and confirm that no floor plan changes affect the approved layout. Verify the candela rating or method of candela control marking on each visual appliance and rating when reported by the FACU agrees with the approved drawings. Confirm that each appliance flashes.
		N/A	Annually	For periodic testing, verify that each appliance flashes.
		X	Annually	Perform tests in accordance with manufacturer's published instructions.
23.	Exit marking audible notification appliance	X	Annually	Perform tests in accordance with manufacturer's published instructions.
24.	Emergency control functions ^f	X	Annually	For initial, reacceptance, and periodic testing, verify emergency control function interface device activation. Where an emergency control function interface device is disabled or disconnected during initiating device testing, verify that the disabled or disconnected emergency control function interface device has been properly restored, including electromagnetic devices used for door releasing services as part of a fire alarm system.
25.	Two-way emergency communications systems	X	Annually	Use the manufacturer's published instructions and the as-built drawings provided by the system supplier to verify correct operation after the initial testing phase has been performed by the supplier or by the supplier's designated representative. Test the two-way communication system to verify operation and receipt of visual and audible signals at the transmitting unit and the receiving unit, respectively. Operate systems with more than five stations with a minimum of five stations operating simultaneously. Verify voice quality and clarity. Verify directions for the use of the two-way communication system, instructions for summoning assistance via the two-way communication system, and written identification of the location is posted adjacent to the two-way communication system. Verify that all remote stations are readily accessible. Verify the timed automatic communications capability to connect with a constantly attended monitoring location per 24.10.6.
26.	Special procedures (1) Alarm verification	X	Annually	Verify time delay and alarm response for smoke detector circuits identified as having alarm verification.
	(2) Multiplex systems	X	Annually	Verify communications between sending and receiving units under both primary and secondary power. Verify communications between sending and receiving units under open-circuit and short-circuit trouble conditions.

(continues)

Table 14.4.3.2 *Continued*

Component	Initial Acceptance	Periodic Frequency	Method
			Verify communications between sending and receiving units in all directions where multiple communications pathways are provided. If a redundant control unit is provided, verify switchover of all required functions and operations of the secondary control unit. Verify all system functions and features in accordance with manufacturer's published instructions.
27. Supervising station alarm systems — receiving equipment			
(1) All equipment	X	Monthly	Perform tests on all system functions and features in accordance with the equipment manufacturer's published instructions for correct operation in conformance with the applicable sections of Chapter 26. Actuate initiating device and verify receipt of the correct initiating device signal at the supervising station within 90 seconds. Upon completion of the test, restore the system to its functional operating condition.
(2) Digital alarm communicator receiver (DACR)	X	Monthly	If test jacks are used, perform the first and last tests without the use of the test jack. Disconnect each transmission means in turn from the DACR, and verify audible and visual annunciation of a trouble signal in the supervising station. Cause a signal to be transmitted on each individual incoming DACR line (path) at least once every 6 hours (24 hours for DACTs installed prior to adoption of the 2013 edition of <i>NFPA 72</i>). Verify receipt of these signals.
(3) Digital alarm radio receiver (DARR)	X	Monthly	Cause the following conditions of all DARRs on all subsidiary and repeater station receiving equipment. Verify receipt at the supervising station of correct signals for each of the following conditions: (1) AC power failure of the radio equipment (2) Receiver malfunction (3) Antenna and interconnecting cable failure (4) Indication of automatic switchover of the DARR (5) Data transmission line failure between the DARR and the supervising or subsidiary station
(4) McCulloh systems	X	Monthly	Test and record the current on each circuit at each supervising and subsidiary station under the following conditions: (1) During functional operation (2) On each side of the circuit with the receiving equipment conditioned for an open circuit Cause a single break or ground condition on each transmission channel. If such a fault prevents the functioning of the circuit, verify receipt of a trouble signal. Cause each of the following conditions at each of the supervising or subsidiary stations and all repeater station radio transmitting and receiving equipment; verify receipt of correct signals at the supervising station: (1) RF transmitter in use (radiating) (2) AC power failure supplying the radio equipment (3) RF receiver malfunction (4) Indication of automatic switchover
(5) Radio alarm supervising station receiver (RASSR) and radio alarm repeater station receiver (RARSR)	X	Monthly	Cause each of the following conditions at each of the supervising or subsidiary stations and all repeater station radio transmitting and receiving equipment; verify receipt of correct signals at the supervising station: (1) AC power failure supplying the radio equipment (2) RF receiver malfunction (3) Indication of automatic switchover, if applicable
(6) Private microwave radio systems	X	Monthly	Cause each of the following conditions at each of the supervising or subsidiary stations and all repeater station radio transmitting and receiving equipment; verify receipt of correct signals at the supervising station: (1) RF transmitter in use (radiating) (2) AC power failure supplying the radio equipment (3) RF receiver malfunction (4) Indication of automatic switchover
(7) Performance-based technologies	X	Monthly	Perform tests to ensure the monitoring of integrity of the transmission technology and technology path. Where a single communications path is used, disconnect the communication path. Verify that failure of the path is annunciated at the supervising station within 60 minutes of the failure (within 5 minutes for communication equipment installed prior to adoption of the 2013 edition of <i>NFPA 72</i>). Restore the communication path. Where multiple communication paths are used, disconnect both communication paths and confirm that failure of the path is annunciated at the supervising station within not more than 6 hours of the failure (within 24 hours for communication equipment installed prior to adoption of the 2013 edition of <i>NFPA 72</i>). Restore both communication paths.
28. Public emergency alarm reporting system transmission equipment			

(continues)

Table 14.4.3.2 *Continued*

Component		Initial Acceptance	Periodic Frequency	Method
(1) Publicly accessible alarm box		X	Semiannually	Actuate publicly accessible initiating device(s) and verify receipt of not less than three complete rounds of signal impulses. Perform this test under normal circuit conditions. If the device is equipped for open circuit operation (ground return), test it in this condition as one of the semiannual tests.
(2) Auxiliary box		X	Annually	Test each initiating circuit of the auxiliary box by actuation of a protected premises initiating device connected to that circuit. Verify receipt of not less than three complete rounds of signal impulses.
(3) Master box				
(a) Manual operation		X	Semiannually	Perform the tests prescribed for 28(1).
(b) Auxiliary operation		X	Annually	Perform the tests prescribed for 28(2).
29. Low-power radio (wireless systems)		X	N/A	The following procedures describe additional acceptance and reacceptance test methods to verify wireless protection system operation: (1) Use the manufacturer's published instructions and the as-built drawings provided by the system supplier to verify correct operation after the initial testing phase has been performed by the supplier or by the supplier's designated representative. (2) Starting from the functional operating condition, initialize the system in accordance with the manufacturer's published instructions, including the following: (a) Confirm the alternative communications path exists between the wireless control unit and peripheral devices used to establish initiation, indication, control, and annunciation. Test the system for both alarm and trouble conditions. (b) For initial and reacceptance testing, confirm the introduction of a fault in any Class A or B radio-frequency-specified pathway results in a trouble indication at fire alarm control unit. Disconnect the power (i.e., remove primary batteries) from a radio transceiver initiating device, notification appliance, or controlled device and confirm the pathway performs as indicated in 23.16.4.8 and 23.16.4.9. Restore the system to normal and repeat the fault on not less than 10 percent of the radio frequency initiating devices, notification appliances, and controlled devices on every initiating device circuit radio pathway, notification appliance circuit radio pathway, and signaling line circuit radio pathway. Confirm all radio pathways perform as indicated in 23.16.4.8 and 23.16.4.9. (c) For periodic testing, test each Class A and B radio frequency initiating device circuit radio pathway, notification appliance circuit radio pathway, and signaling line circuit radio pathway for correct indication at the control unit. Confirm all radio pathways perform as indicated in 23.16.4.8 and 23.16.4.9. (3) Check batteries for all components in the system monthly unless the control unit checks all batteries and all components daily.
30. Mass notification systems				
(1) Functions		X	Annually	At a minimum, test control unit to verify correct receipt of alarm, supervisory, and trouble signals (inputs); operation of evacuation signals and auxiliary functions (outputs); circuit supervision, including detection of open circuits and ground faults; and power supply supervision for detection of loss of ac power and disconnection of secondary batteries.
(2) Fuses		X	Annually	Verify the rating and supervision.
(3) Interfaced equipment		X	Annually	Verify integrity of single or multiple circuits providing interface between two or more control units. Test interfaced equipment connections by operating or simulating operation of the equipment being supervised. Verify signals required to be transmitted at the control unit.
(4) Lamps and LEDs		X	Annually	Illuminate lamps and LEDs.
(5) Primary (main) power supply		X	Annually	Disconnect all secondary (standby) power and test under maximum load, including all alarm appliances requiring simultaneous operation. Reconnect all secondary (standby) power at end of test. For redundant power supplies, test each separately.
(6) Audible textual notification appliances (loudspeakers and other appliances to convey voice messages)		X	Annually	Measure sound pressure level with a sound level meter meeting ANSI/ASA S1.4/Part 1, <i>Electroacoustics — Sound Level Meters — Part 1: Specifications</i> , Type 2 requirements. Measure and record levels throughout protected area. Set the sound level meter in accordance with ANSI/ASA S3.41, <i>Audible Emergency Evacuation (E2) and Evacuation Signals with Relocation Instructions (ESRI)</i> , using the time-weighted characteristic F (FAST). Record the maximum output when the audible emergency evacuation signal is on.
(7) Visual		X	Annually	Verify audible information to be distinguishable and understandable. Perform test in accordance with manufacturer's published instructions. Verify appliance locations to be per approved layout and confirm that no floor plan changes affect the approved layout. Verify the candela rating or method of candela control marking on each visual appliance and rating when reported by the FACU agrees with the approved drawings. Confirm that each appliance flashes.

(continues)

Table 14.4.3.2 *Continued*

Component	Initial Acceptance	Periodic Frequency	Method
(8) Control unit functions and no diagnostic failures are indicated	X	Annually	Review event log file and verify that the correct events were logged. Review system diagnostic log file; correct deficiencies noted in file. Delete unneeded log files. Delete unneeded error files. Verify that sufficient free disk space is available. Verify unobstructed flow of cooling air is available. Change/clean filters, cooling fans, and intake vents.
(9) Control unit reset	X	Annually	Power down the central control unit computer and restart it.
(10) Control unit security	X	Annually	If remote control software is loaded onto the system, verify that it is disabled to prevent unauthorized system access.
(11) Audible/visual functional test	X	Annually	Send out an alert to a diverse set of predesignated receiving devices and confirm receipt. Include at least one of each type of receiving device.
(12) Software backup	X	Annually	Make full system software backup. Rotate backups based on accepted practice at site.
(13) Secondary power test	X	Annually	Disconnect ac power. Verify the ac power failure alarm status on central control unit. With ac power disconnected, verify battery voltage under load.
(14) Wireless signals	X	Annually	Check forward/reflected radio power is within specifications.
(15) Antenna	X	Annually	Check forward/reflected radio power is within specifications. Verify solid electrical connections with no observable corrosion.
(16) Transceivers	X	Annually	Verify proper operation and mounting is not compromised.

^aSome transmission equipment (such as, but not limited to, cable modems, fiber-optic interface nodes, and VoIP interfaces) are typically powered by the building's electrical system using a secondary (standby) power supply that does not meet the requirements of this Code. This is intended to ensure that the testing authority verifies full secondary (standby) power as required by Chapter 10. Additionally, refer to Table 14.4.3.2, items 7 through 9, for secondary (standby) power supply testing.

^bThe automatic transmission of the check-in (handshake) signal can take up to 60 minutes to occur.

^cSee Table 14.4.3.2, Item 4(1) for the testing of transmission equipment.

^dThe battery tests in Table 14.4.3.2, Item 9, are based on VRLA batteries and it is the intent that the tests specified in (1) through (4) be performed in order. FACU automated load testing of VRLA batteries in accordance with Table 14.4.3.2, Item 9(5), with record of ambient temperature is an acceptable alternative to prescriptive manual methods using test equipment. For other secondary battery types, refer to the battery manufacturer's published instructions or IEEE 450, *Recommended Practice for Maintenance, Testing, and Replacement of Vented Lead-Acid Batteries for Stationary Applications*, for vented lead-acid batteries, and IEEE 1106, *Recommended Practice for Installation, Maintenance, Testing, and Replacement of Vented Nickel-Cadmium Batteries for Stationary Applications*, for nickel-cadmium batteries.

^eIf the charger is adjustable, adjust the output voltage to 2.265 volts per cell ± 0.015 volts at 77°F (25°C) or as specified by the alarm equipment manufacturer.

^fSee A.14.4.3.2 Item 9(4). A load test per Item 9(5) is permitted in lieu of an ohmic test.

^gSee A.14.4.3.2 Item 9(5).

^hThe voltmeter sensitivity has been changed from 1000 ohms per volt to 100 ohms per volt so that the false ground readings (caused by induced voltages) are minimized.

ⁱInitiating devices such as smoke detectors used for elevator recall, closing dampers, or releasing doors held in the open position that are permitted by the Code (*see 9.6.3 of NFPA 101*) to initiate supervisory signals at the fire alarm control unit (FACU) should be tested at the same frequency (annual) as those devices when they are generating an alarm signal. They are not supervisory devices, but they initiate a supervisory signal at the FACU.

^jFusible thermal link detectors are commonly used to close fire doors and fire dampers electrically connected to the fire alarm control unit. They are actuated by the presence of external heat, which causes a solder element in the link to fuse, or by an electric thermal device, which, when energized, generates heat within the body of the link, causing the link to fuse and separate.

^kNote, it is customary for the manufacturer of the smoke detector to test a particular product from an aerosol provider to determine acceptability for use in smoke entry testing of their smoke detector/smoke alarm. Magnets are not acceptable for smoke entry tests.

^lThere are some detectors that use magnets as a manufacturer's calibrated sensitivity test instrument.

^mFor example, it might not be possible to individually test the heat sensor in a thermally enhanced smoke detector.

ⁿManufacturer's published instructions should be consulted to ensure a proper operational test. No suppression gas or agent is expected to be discharged during the test of the solenoid. *See Test Plan of 14.2.10.*

^oA monitor module installed on an interface device is not considered a supervisory device and therefore not subject to the quarterly testing frequency requirement. Test frequencies for interface devices should be in accordance with the applicable standard. For example, fire pump controller alarms such as phase reversal are required to be tested annually. If a monitor module is installed to identify phase reversal on the fire alarm control unit, it is not necessary to test for phase reversal four times a year.

^pChapter 18 would require 15 dB over average ambient sound for public mode spaces. Sometimes the ambient sound levels are different from what the design was based upon. Private operating mode would require 10 dB over average ambient at the location of the device.

^qWhere building, system, or occupancy changes have been observed, the owner should be notified of the changes. New devices might need to be installed and tested per the initial acceptance testing criteria.

^rSee A.14.4.3.2 and Table 14.4.3.2, Item 24.

14.4.4.5.4 Within 5 years, each detector shall have been tested.

14.4.4.5.5 Carbon monoxide apparatus that require resetting to maintain normal operation shall be restored to normal as promptly as possible after each test and alarm and kept in normal condition for operation. All test signals received shall be recorded to indicate date and time.

14.4.4.6* Circuit and pathway testing of each monitored circuit or pathway shall be conducted with initial acceptance or reacceptance testing to verify signals are indicated at the control unit for each of the abnormal conditions specified in Sections 23.5 through 23.7.

14.4.4.7 Unless otherwise permitted by 14.4.4.8, the retransmission means as defined in Section 26.3 shall be tested at intervals of not more than 12 hours.

14.4.4.8 When the retransmission means is the public-switched telephone network, testing shall be permitted at weekly intervals to confirm its operation to each communications center.

14.4.4.9 As a part of the testing required in 14.4.4.7, the retransmission signal and the time and date of the retransmission shall be recorded in the central station.

14.4.5 Single- and Multiple-Station Alarms. (SIG-HOU)

14.4.5.1 Single- and multiple-station alarms and connected appliances shall be inspected, tested, and maintained in accordance with Table 14.3.1, Table 14.4.3.2, and the manufacturer's published instructions.

14.4.5.2 Alarms and connected appliances shall be inspected and tested at least monthly.

14.4.5.3* The responsibility for inspection, testing, and maintenance of smoke alarms and connected appliances shall be in accordance with 14.2.3.

14.4.5.4* Notwithstanding other requirements of 14.2.3, the occupant of a dwelling unit shall be deemed qualified to perform inspection, testing, and maintenance on single- and multiple-station alarms protecting that dwelling unit when provided with information from the manufacturer or a manufacturer's certified representative.

14.4.5.5 Alarms and connected appliances shall be replaced when they fail to respond to operability tests.

14.4.5.6 Smoke alarms shall not remain in service longer than 10 years from the date of manufacture, unless otherwise provided by the manufacturer's published instructions.

14.4.5.7 Carbon monoxide alarms shall be replaced when either the end-of-life signal is actuated or the manufacturer's replacement date is reached.

14.4.5.8 Combination smoke/carbon monoxide alarms shall be replaced when the end-of-life signal actuates or 10 years from the date of manufacture, whichever comes first, unless otherwise provided by the manufacturer's published instructions.

14.4.5.9 Where batteries are used as a source of energy for alarms, the batteries shall be replaced in accordance with the alarm equipment manufacturer's published instructions.

14.4.6 Household Fire Alarm Systems. (SIG-HOU)

14.4.6.1 Household alarm systems shall be inspected, tested, and maintained at least annually according to Table 14.3.1, Table 14.4.3.2, and the manufacturer's published instructions.

14.4.6.2 The responsibility for inspection, testing, and maintenance of smoke alarms and connected appliances shall be in accordance with 14.2.3.

14.4.6.3* Notwithstanding other requirements of 14.2.3, the occupant of a dwelling unit shall be deemed qualified to perform inspection, testing, and maintenance on a household alarm system protecting that dwelling unit when provided with information and/or training from the manufacturer or a manufacturer's certified representative.

14.4.6.4 The installing contractor shall be required to provide the information in 14.4.6.3 in writing to the customer upon completion of the system installation.

14.4.6.5 Carbon monoxide detectors shall be replaced when the end-of-life signal is actuated, the manufacturer's replacement date is reached, or when they fail to respond to operability tests.

14.4.6.6 Maintenance of household alarm systems shall be conducted according to the manufacturer's published instructions.

14.4.7 Circuits from Central Station. (SIG-SSS) Circuits extending from the central station that have had no signal activity in the preceding 24 hours shall be tested at intervals of not more than 24 hours.

14.4.8 Household Carbon Monoxide Detection Systems. (SIG-HOU)

14.4.8.1 Testing of Household Carbon Monoxide Detection Systems.

14.4.8.1.1 Household carbon monoxide detection systems shall be tested by a qualified service technician at least every 3 years according to the methods in line 1 of Table 14.4.3.2.

14.4.8.1.2 Household carbon monoxide detection systems shall be tested in accordance with the manufacturer's published instructions.

14.4.8.1.3* Notwithstanding other requirements of 14.2.3.6, the occupant of a dwelling unit shall be deemed qualified to perform inspection, testing, and maintenance on an alarm system protecting that dwelling unit when provided with information and training from the manufacturer or a manufacturer's certified representative.

14.4.9 Public Emergency Alarm Reporting Systems. (SIG-PRS)

14.4.9.1 Emergency power sources other than batteries shall be tested at least weekly in accordance with 14.4.9.1.1 and 14.4.9.1.2.

14.4.9.1.1 Testing shall include operation of the power source to supply the system for a continuous period of 1 hour.

14.4.9.1.2 Testing shall require simulated failure of the normal power source.

14.4.9.2 Unless otherwise permitted by 14.4.9.3, testing facilities shall be installed at the communications center and each subsidiary communications center, if used.

14.4.9.3 Testing facilities for systems leased from a nonmunicipal organization shall be permitted to be installed at locations other than the communications center if approved by the authority having jurisdiction.

14.4.10 In-Building Emergency Radio Communication Systems. (SIG-ECS) In-building emergency radio communication systems shall be inspected and operationally tested in accordance with the requirements of NFPA 1221.

14.4.11* Voice Intelligibility.

14.4.11.1 Voice communication using prerecorded messages and manual voice announcements shall be verified as being intelligible in accordance with the requirements of 18.4.11.

14.4.11.2 Intelligibility shall not be required to be determined through quantitative measurements.

14.4.11.3 Quantitative measurements as described in Annex D shall be permitted but shall not be required.

14.5 Maintenance.

14.5.1 System equipment shall be maintained in accordance with the manufacturer's published instructions.

14.5.2 The frequency of maintenance of system equipment shall depend on the type of equipment and the local ambient conditions.

14.5.3 The frequency of cleaning of system equipment shall depend on the type of equipment and the local ambient conditions.

14.5.4 All apparatus requiring rewinding or resetting to maintain normal operation shall be rewound or reset as promptly as possible after each test and alarm.

14.6 Records.

14.6.1* Permanent Records. After successful completion of acceptance tests approved by the authority having jurisdiction, the requirements in 14.6.1.1 through 14.6.1.3 shall apply.

14.6.1.1* A set of reproducible as-built installation drawings, operation and maintenance manuals, and a written sequence of operation shall be provided to the building owner or the owner's designated representative.

14.6.1.2* The requirements of 7.5.7 shall apply to site-specific software.

14.6.1.3 The system owner shall be responsible for maintaining these records for the life of the system for examination by any authority having jurisdiction. Paper or electronic media shall be permitted.

14.6.2 Maintenance, Inspection, and Testing Records.

14.6.2.1 Records shall be retained until the next test and for 1 year thereafter.

14.6.2.2 For systems with restorable fixed-temperature, spot-type heat detectors tested over multiple years, records shall be retained for the 5 years of testing and for 1 year thereafter.

14.6.2.3 The records shall be on a medium that will survive the retention period. Paper or electronic media shall be permitted.

14.6.2.4 A record of all inspections, testing, and maintenance shall be provided in accordance with 7.6.6.

14.6.3 Supervising Station Records. For supervising station alarm systems, records pertaining to signals received at the supervising station that result from maintenance, inspection, and testing shall be maintained for not less than 12 months.

14.6.3.1 Records shall be permitted to be maintained on either paper or electronic media.

14.6.3.2 Upon request, a hard copy record shall be provided to the authority having jurisdiction.

14.6.4 Simulated Operation Note. If the operation of a device, circuit, fire alarm control unit function, or special hazard system interface is simulated, it shall be noted on the inspection/test form that the operation was simulated.

Chapter 15 Reserved

Chapter 16 Reserved

Chapter 17 Initiating Devices

17.1 Application.

17.1.1* The performance, selection, use, and location of automatic or manual initiating devices shall comply with the minimum requirements of this chapter.

17.1.2* This chapter establishes the minimum installation criteria for initiating devices required by other governing laws, codes, standards, or sections of this document. This chapter does not, by itself, require the installation of initiating devices.

17.1.3 The requirements of Chapters 7, 10, 11, 12, 21, 23, and 24 shall also apply unless they are in conflict with this chapter.

17.1.4 The requirements of Chapter 14 shall apply.

17.1.5 The requirements of single- and multiple-station alarms and household fire alarm systems shall be determined in accordance with Chapter 29.

17.1.6 The material in this chapter shall be applied by persons knowledgeable in the application of fire detection and fire alarm systems and services.

17.1.7 The interconnection of initiating devices with control unit configurations and power supplies, or with output systems responding to external actuation, shall be as detailed elsewhere in this Code or in other governing laws, codes, or standards.

17.2 Purpose. Automatic and manual initiating devices shall contribute to life safety, fire protection, and property conservation by providing a reliable means to signal other equipment arranged to monitor the initiating devices and to initiate a response to those signals.

17.3* Performance-Based Design.

17.3.1 Performance-based designs submitted to the authority having jurisdiction for review and approval shall include documentation, in an approved format, of each performance objective and applicable scenario, together with any calculations, modeling, or other technical substantiation used in establishing the proposed design's fire and life safety performance.

17.3.2 The authority having jurisdiction shall determine whether such identified performance objectives are appropriate and have been met.

17.3.3 The authority having jurisdiction shall approve modifications to or variations from the approved design or design basis in advance.

17.4 General Requirements.

17.4.1 The requirements of 17.4.2 through 17.4.8 shall apply to all initiating devices.

17.4.2 Mechanical Protection.

17.4.2.1 Initiating devices subject to mechanical damage shall be protected.

17.4.2.2 If guards or covers are employed, they shall be listed for use with the initiating device.

17.4.2.3* The protection shall not prevent the initiating device from achieving the objectives of the system by adversely affecting the use, operation, or performance of the initiating device.

17.4.3 Initiating devices shall be installed in a manner that provides accessibility for periodic inspection, testing, and maintenance.

17.4.4 Initiating devices shall be supported independently of their attachment to the circuit conductors.

17.4.5 Initiating devices shall be installed in all areas, compartments, or locations where required by other governing laws, codes, or standards.

17.4.6* Duplicate terminals, leads, or connectors that provide for the connection of installation wiring shall be provided on each initiating device for the express purpose of connecting into the fire alarm system to monitor the integrity of the signaling and power wiring unless the initiating devices are connected to a system that provides the required monitoring.

17.4.7* Unless otherwise permitted by 17.4.7.3, where detectors are installed in concealed locations or in arrangements where the detector's alarm or supervisory indicator is not visible to responding personnel, the detectors shall be provided with remote alarm or supervisory indication in a location acceptable to the authority having jurisdiction.

17.4.7.1* The location of the detector and the area protected by the detector shall be prominently indicated at the remote indicator by a permanently attached placard or by other approved means.

17.4.7.2* Remote alarm and supervisory indicators shall be installed in an accessible location acceptable to the authority having jurisdiction.

17.4.7.3 Detectors installed in concealed locations where the specific detector alarm or supervisory signal is indicated at the control unit (and on the drawings with its specific location and functions) shall not be required to be provided with remote alarm indicators as specified in 17.4.7.

17.4.7.4 Remote alarm and supervisory indicators shall be labeled to indicate their function and any device or equipment associated with each detector.

17.4.8* If the intent is to initiate action when smoke/fire threatens a specific object or space, the detector shall be permitted to be installed in close proximity to that object or space.

17.5 Requirements for Smoke and Heat Detectors.

17.5.1 Recessed Mounting. Unless tested and listed for recessed mounting, detectors shall not be recessed into the mounting surface.

17.5.2* Partitions. Where partitions extend to within 15 percent of the ceiling height, the spaces separated by the partitions shall be considered as separate rooms.

17.5.3* Detector Coverage.

17.5.3.1* Total (Complete) Coverage. Where required by other governing laws, codes, or standards, and unless otherwise modified by 17.5.3.1.1 through 17.5.3.1.5, total coverage of a building or a portion thereof, shall include all rooms, halls, storage areas, basements, attics, lofts, spaces above suspended ceilings, and other subdivisions and accessible spaces.

17.5.3.1.1 Where inaccessible areas are constructed of or contain combustible material, unless otherwise specified in 17.5.3.1.2, they shall be made accessible and shall be protected by a detector(s).

17.5.3.1.2 Detectors shall not be required in combustible blind spaces if any of the following conditions exist:

- (1) Where the ceiling is attached directly to the underside of the supporting beams of a combustible roof or floor deck.
- (2) Where the concealed space is entirely filled with a noncombustible insulation. (In solid joist construction, the insulation shall be required to fill only the space from the ceiling to the bottom edge of the joist of the roof or floor deck.)
- (3) Where there are small concealed spaces over rooms, provided that any space in question does not exceed 50 ft² (4.6 m²) in area.
- (4) In spaces formed by sets of facing studs or solid joists in walls, floors, or ceilings, where the distance between the facing studs or solid joists is less than 6 in. (150 mm).

17.5.3.1.3 Detectors shall not be required below open grid ceilings if all of the following conditions exist:

- (1) Openings of the grid are ¼ in. (6.4 mm) or larger in the least dimension.
- (2) Thickness of the material does not exceed the least dimension.
- (3) Openings constitute at least 70 percent of the area of the ceiling material.

17.5.3.1.4* Where concealed accessible spaces above suspended ceilings are used as a return air plenum meeting the requirements of NFPA 90A detection shall be provided in one of the following means:

- (1) Smoke detection shall be provided in accordance with 17.7.5.2, or
- (2) Smoke detection shall be provided at each connection from the return air plenum to the central air-handling system.

17.5.3.1.5 Detectors shall not be required underneath open loading docks or platforms and their covers and for accessible underfloor spaces if all of the following conditions exist:

- (1) Space is not accessible for storage purposes or entrance of unauthorized persons and is protected against the accumulation of windborne debris.
- (2) Space contains no equipment such as steam pipes, electric wiring, shafting, or conveyors.
- (3) Floor over the space is tight.
- (4) No flammable liquids are processed, handled, or stored on the floor above.

17.5.3.2* Partial or Selective Coverage. Where other governing laws, codes, or standards require the protection of selected areas only, the specified areas shall be protected in accordance with this Code.

17.5.3.3* Nonrequired Coverage.

17.5.3.3.1 Detection installed for reasons of achieving specific fire safety objectives, but not required by any laws, codes, or standards, shall meet all of the requirements of this Code, with the exception of the prescriptive spacing criteria of Chapter 17.

17.5.3.3.2 Where nonrequired detectors are installed for achieving specific fire safety objectives, additional detectors not necessary to achieve the objectives shall not be required.

17.6 Heat-Sensing Fire Detectors.

17.6.1 General.

17.6.1.1* The heat detection design documentation shall state the required performance objective of the system.

17.6.1.2 Designs not in accordance with 17.6.1.3 shall be deemed prescriptive designs and shall be designed in accordance with the prescriptive requirements of this chapter.

17.6.1.3* Performance-based designs shall be executed in accordance with Section 17.3.

17.6.1.4 Heat sensing fire detectors shall be listed in accordance with applicable standards such as UL 521, *Heat Detectors for Fire Protective Signaling Systems*.

17.6.1.5* Spot-type heat detectors shall include in their installation instructions, technical data, and listing documentation the operating temperature and response time index (RTI) as determined by the organization listing the device.

17.6.2 Temperature.

17.6.2.1 Classification. Heat-sensing fire detectors of the fixed-temperature or rate-compensated, spot type shall be classified as to the temperature of operation in accordance with Table 17.6.2.1.

17.6.2.2 Marking.

17.6.2.2.1 Color Coding.

17.6.2.2.1.1 Non-field-programmable heat sensing fire detectors of the fixed-temperature or rate-compensated spot type shall be marked with a color code in accordance with Table 17.6.2.1.

17.6.2.2.1.2 If the overall color of a heat-sensing fire detector is the same as the color code marking required for that detector, one of the following arrangements, applied in a contrasting color and visible after installation, shall be employed:

Table 17.6.2.1 Temperature Classification and Color Code for Heat-Sensing Fire Detectors

Temperature Classification	Temperature Rating Range		Maximum Ceiling Temperature		Color Code
	°F	°C	°F	°C	
Low	100–134	38–56	80	28	Uncolored
Ordinary	135–174	57–79	115	47	Uncolored
Intermediate	175–249	80–121	155	69	White
High	250–324	122–162	230	111	Blue
Extra high	325–399	163–204	305	152	Red
Very extra high	400–499	205–259	380	194	Green
Ultra high	500–575	260–302	480	249	Orange

- (1) Ring on the surface of the detector
- (2) Temperature rating in numerals at least $\frac{3}{8}$ in. (9.5 mm) high

17.6.2.2.2 Operating Temperature.

17.6.2.2.2.1 Heat-sensing fire detectors shall be marked with their listed operating temperature.

17.6.2.2.2.2 Heat-sensing fire detectors where the alarm threshold is field adjustable shall be marked with the temperature range.

17.6.2.2.2.3 Spot-type heat detectors shall also be marked with their RTI.

17.6.2.3* Ambient Ceiling Temperature.

17.6.2.3.1 Detectors having fixed-temperature or rate-compensated elements shall be selected in accordance with Table 17.6.2.1 for the maximum expected ambient ceiling temperature.

17.6.2.3.2 The temperature rating of the detector shall be at least 20°F (11°C) above the maximum expected temperature at the ceiling.

17.6.3 Location and Spacing.

17.6.3.1 Smooth Ceiling.

17.6.3.1.1* Spacing. One of the following requirements shall apply:

- (1) The distance between detectors shall not exceed their listed spacing, and there shall be detectors within a distance of one-half the listed spacing, measured at right angles from all walls or partitions extending upward to within the top 15 percent of the ceiling height.
- (2) All points on the ceiling shall have a detector within a distance equal to or less than 0.7 times the listed spacing (0.7S).

17.6.3.1.2 Irregular Areas. For irregularly shaped areas, the spacing between detectors shall be permitted to be greater than the listed spacing, provided that the maximum spacing from a detector to the farthest point of a sidewall or corner within its zone of protection is not greater than 0.7 times the listed spacing.

17.6.3.1.3 Location.

17.6.3.1.3.1* Unless otherwise modified by 17.6.3.2.2, 17.6.3.3.2, or 17.6.3.7, spot-type heat-sensing fire detectors shall be located on the ceiling not less than 4 in. (100 mm) from the sidewall or on the sidewalls between 4 in. and 12 in. (100 mm and 300 mm) from the ceiling.

17.6.3.1.3.2 Unless otherwise modified by 17.6.3.2.2, 17.6.3.3.2, or 17.6.3.7, line-type heat detectors shall be located on the ceiling or on the sidewalls not more than 20 in. (510 mm) from the ceiling.

17.6.3.2* Solid Joist Construction.

17.6.3.2.1 Spacing. The design spacing of heat detectors, where measured at right angles to the solid joists, shall not exceed 50 percent of the listed spacing.

17.6.3.2.2 Location. Detectors shall be mounted at the bottom of the joists.

17.6.3.3* Beam Construction.**17.6.3.3.1 Spacing.**

17.6.3.3.1.1 A ceiling shall be treated as a smooth ceiling if the beams project no more than 4 in. (100 mm) below the ceiling.

17.6.3.3.1.2 Where the beams project more than 4 in. (100 mm) below the ceiling, the spacing of spot-type heat detectors at right angles to the direction of beam travel shall be not more than two-thirds of the listed spacing.

17.6.3.3.1.3 Where the beams project more than 18 in. (460 mm) below the ceiling and are more than 8 ft (2.4 m) on center, each bay formed by the beams shall be treated as a separate area.

17.6.3.3.2 Location. Where beams are less than 12 in. (300 mm) in depth and less than 8 ft (2.4 m) on center, detectors shall be permitted to be installed on the bottom of beams.

17.6.3.4* Sloping Ceilings (Peaked and Shed).**17.6.3.4.1 Spacing.**

17.6.3.4.1.1 Ceiling Slope Less Than 30 Degrees. For a ceiling slope of less than 30 degrees, all detectors shall be spaced using the height at the peak.

17.6.3.4.1.2 Ceiling Slopes of 30 Degrees or Greater. All detectors, other than those located in the peak, shall be spaced using the average slope height or the height of the peak.

17.6.3.4.1.3 Spacing shall be measured along a horizontal projection of the ceiling in accordance with the type of ceiling construction.

17.6.3.4.2 Location.

17.6.3.4.2.1 A row of detectors shall first be located at or within 36 in. (910 mm) of the peak of the ceiling.

17.6.3.4.2.2 Additional detectors shall be located as determined in 17.6.3.4.1.

17.6.3.5 High Ceilings.

17.6.3.5.1* Unless otherwise modified by 17.6.3.5.2, on ceilings 10 ft to 30 ft (3.0 m to 9.1 m) high, heat detector spacing shall be reduced in accordance with Table 17.6.3.5.1 prior to

any additional reductions for beams, joists, or slope, where applicable.

17.6.3.5.2 For line-type electrical conductivity detectors (*see* 3.3.77.12) and pneumatic rate-of-rise tubing heat detectors (*see* 3.3.77.16), which rely on the integration effect, the derating required by Table 17.6.3.5.1 shall not apply, and the manufacturer's published instructions shall be followed for appropriate alarm point and spacing.

17.6.3.5.3* Spacing Minimum. The spacing of heat detectors shall not be required to be less than 0.4 times the height of the ceiling.

17.6.3.6* Integral Heat Sensors on Combination and Multi-Sensor Detectors. A heat-sensing detector integrally mounted on a smoke detector shall be listed for not less than 50 ft (15.2 m) spacing.

17.6.3.7 Other Applications. Where a detector is used in an application other than open area protection, the manufacturer's published instructions shall be followed.

17.6.3.8 Alternative Design Methods. Annex B shall be permitted to be used as one alternative design method for determining detector spacing.

17.7 Smoke-Sensing Fire Detectors.**17.7.1 General.**

17.7.1.1* The smoke detection design documentation shall state the required performance objective of the system.

17.7.1.2* Designs not in accordance with 17.7.1.3 shall be deemed prescriptive designs and shall be designed in accordance with the prescriptive requirements of this chapter.

17.7.1.3* Performance-based designs shall be executed in accordance with Section 17.3.

17.7.1.4 The prescriptive requirements in this section shall be applied only where detectors are installed in ordinary indoor locations.

17.7.1.5 Where smoke detectors are being installed to control the spread of smoke, they shall be installed in accordance with the requirements of 17.7.6.

Table 17.6.3.5.1 Heat Detector Spacing Reduction Based on Ceiling Height

Ceiling Height Greater than (>)		Up to and Including		Multiply Listed Spacing by
ft	m	ft	m	
0	0	10	3.0	1.00
10	3.0	12	3.7	0.91
12	3.7	14	4.3	0.84
14	4.3	16	4.9	0.77
16	4.9	18	5.5	0.71
18	5.5	20	6.1	0.64
20	6.1	22	6.7	0.58
22	6.7	24	7.3	0.52
24	7.3	26	7.9	0.46
26	7.9	28	8.5	0.40
28	8.5	30	9.1	0.34

17.7.1.6 Smoke detectors shall be installed in all areas where required by other governing laws, codes, or standards or by other parts of this Code.

17.7.1.7 The selection and placement of smoke detectors shall take into account both the performance characteristics of the detector and the areas into which the detectors are to be installed to prevent nuisance and unintentional alarms or improper operation after installation.

17.7.1.8* Unless specifically designed and listed for the expected conditions, smoke detectors shall not be installed if any of the following ambient conditions exist:

- (1) Temperature below 32°F (0°C)
- (2) Temperature above 100°F (38°C)
- (3) Relative humidity above 93 percent
- (4) Air velocity greater than 300 ft/min (1.5 m/sec)

17.7.1.9* Smoke detectors installed in ducts and other locations with air velocities greater than 300 ft/min (1.5 m/sec) shall be listed for the velocity conditions anticipated and installed in accordance with the manufacturer's published instructions.

17.7.1.10* The location of smoke detectors shall be based on an evaluation of potential ambient sources of smoke, moisture, dust, or fumes, and electrical or mechanical influences, to minimize nuisance alarms.

17.7.1.11* The effect of stratification below the ceiling shall be taken into account. The guidelines in Annex B shall be permitted to be used.

17.7.2* Protection During Construction.

17.7.2.1 Where detectors are installed for signal initiation during construction, they shall be cleaned and verified to be operating in accordance with the listed sensitivity, or they shall be replaced prior to the final acceptance test of the system.

17.7.2.2 Where detectors are installed but not operational during construction, they shall be protected from construction debris, dust, dirt, and damage in accordance with the manufacturer's recommendations and verified to be operating in accordance with the listed sensitivity, or they shall be replaced prior to the final acceptance test of the system.

17.7.2.3 Where detection is not required during construction, detectors shall not be installed until after all other construction trades have completed cleanup.

17.7.3* Sensitivity.

17.7.3.1* Smoke detectors shall be marked with their nominal production sensitivity and tolerance in percent per foot (percent per meter) obscuration, as required by the listing.

17.7.3.2 Spot-type smoke detectors that have provision for field adjustment of sensitivity via a mechanical means shall have an adjustment range of not less than 0.6 percent per foot (1.95 percent per meter) obscuration.

17.7.3.3 If the means of adjustment of sensitivity is on the detector, a method shall be provided to restore the detector to its factory calibration.

17.7.3.4 Detectors that have provision for program-controlled adjustment of sensitivity shall be permitted to be marked with their programmable sensitivity range only.

17.7.4 Location and Spacing.

17.7.4.1* General.

17.7.4.1.1 The location and spacing of smoke detectors shall be based upon the anticipated smoke flows due to the plume and ceiling jet produced by the anticipated fire, as well as any pre-existing ambient airflows that could exist in the protected compartment.

17.7.4.1.2 The design shall account for the contribution of the following factors in predicting detector response to the anticipated fires to which the system is intended to respond:

- (1) Ceiling shape and surface
- (2) Ceiling height
- (3) Configuration of contents in the protected area
- (4) Combustion characteristics and probable equivalence ratio of the anticipated fires involving the fuel loads within the protected area
- (5) Compartment ventilation
- (6) Ambient temperature, pressure, altitude, humidity, and atmosphere

17.7.4.1.3 If the intent is to protect against a specific hazard, the detector(s) shall be permitted to be installed closer to the hazard in a position where the detector can intercept the smoke.

17.7.4.2* Spot-Type Smoke Detectors.

17.7.4.2.1* Spot-type smoke detectors shall be located on the ceiling or, if on a sidewall, between the ceiling and 12 in. (300 mm) down from the ceiling to the top of the detector.

17.7.4.2.2* To minimize dust contamination, smoke detectors, where installed under raised floors, shall be mounted only in an orientation for which they have been listed.

17.7.4.2.3 On smooth ceilings, spacing for spot-type smoke detectors shall be in accordance with 17.7.4.2.3.1 through 17.7.4.2.3.4.

17.7.4.2.3.1* In the absence of specific performance-based design criteria, one of the following requirements shall apply:

- (1) The distance between smoke detectors shall not exceed a nominal spacing of 30 ft (9.1 m) and there shall be detectors within a distance of one-half the nominal spacing, measured at right angles from all walls or partitions extending upward to within the top 15 percent of the ceiling height.
- (2)* All points on the ceiling shall have a detector within a distance equal to or less than 0.7 times the nominal 30 ft (9.1 m) spacing (0.7S).

17.7.4.2.3.2 In all cases, the manufacturer's published instructions shall be followed.

17.7.4.2.3.3 Other spacing shall be permitted to be used depending on ceiling height, different conditions, or response requirements.

17.7.4.2.3.4 For the detection of flaming fires, the guidelines in Annex B shall be permitted to be used.

17.7.4.2.4* For solid joist and beam construction, spacing for spot-type smoke detectors shall be in accordance with 17.7.4.2.4.1 through 17.7.4.2.4.6.

17.7.4.2.4.1 Solid joists shall be considered equivalent to beams for smoke detector spacing guidelines.

17.7.4.2.4.2 For level ceilings, the following shall apply:

- (1) For ceilings with beam depths of less than 10 percent of the ceiling height ($0.1 H$), the following shall apply:
 - (a) Smooth ceiling spacing shall be permitted.
 - (b) Spot-type smoke detectors shall be permitted to be located on ceilings or on the bottom of beams.
- (2) For ceilings with beam depths equal to or greater than 10 percent of the ceiling height ($0.1 H$), the following shall apply:
 - (a) Where beam spacing is equal to or greater than 40 percent of the ceiling height ($0.4 H$), spot-type detectors shall be located on the ceiling in each beam pocket.
 - (b) Where beam spacing is less than 40 percent of the ceiling height ($0.4 H$), the following shall be permitted for spot detectors:
 - i. Smooth ceiling spacing in the direction parallel to the beams and at one-half smooth ceiling spacing in the direction perpendicular to the beams
 - ii. Location of detectors either on the ceiling or on the bottom of the beams
- (3)* For beam pockets formed by intersecting beams, including waffle or pan-type ceilings, the following shall apply:
 - (a) For beam depths less than 10 percent of the ceiling height ($0.1 H$), spacing shall be in accordance with 17.7.4.2.4.2(1).
 - (b) For beam depths greater than or equal to 10 percent of the ceiling height ($0.1 H$), spacing shall be in accordance with 17.7.4.2.4.2(2).
- (4)* For corridors 15 ft (4.6 m) in width or less having ceiling beams or solid joists perpendicular to the corridor length, the following shall apply:
 - (a) Smooth ceiling spacing shall be permitted.
 - (b) Location of spot-type smoke detectors shall be permitted on ceilings, sidewalls, or the bottom of beams or solid joists.
- (5) For rooms of 900 ft² (84 m²) or less, the following shall apply:
 - (a) Use of smooth ceiling spacing shall be permitted.
 - (b) Location of spot-type smoke detectors shall be permitted on ceilings or on the bottom of beams.

17.7.4.2.4.3* For sloping ceilings with beams running parallel up slope, the following shall apply:

- (1) Spot-type detector(s) shall be located on the ceiling within beam pocket(s).
- (2) The ceiling height shall be taken as the average height over slope.
- (3) Spacing shall be measured along a horizontal projection of the ceiling.
- (4) Smooth ceiling spacing shall be permitted within beam pocket(s) parallel to the beams.
- (5) For beam depths less than or equal to 10 percent of the ceiling height ($0.1 H$), spot-type detectors shall be located with smooth ceiling spacing perpendicular to the beams.
- (6) For beam depths greater than 10 percent of the ceiling height ($0.1 H$), the following shall apply for spacing perpendicular to the beams:

- (a) For beam spacing greater than or equal to 40 percent of the ceiling height ($0.4 H$), spot-type detectors shall be located in each beam pocket.
- (b) For beam spacing less than 40 percent of the ceiling height ($0.4 H$), spot-type detectors shall not be required in every beam pocket but shall be spaced not greater than 50 percent of smooth ceiling spacing.

17.7.4.2.4.4* For sloping ceilings with beams running perpendicular across slope, the following shall apply:

- (1) Spot-type detector(s) shall be located at the bottom of the beams.
- (2) The ceiling height shall be taken as the average height over slope.
- (3) Spacing shall be measured along a horizontal projection of the ceiling.
- (4) Smooth ceiling spacing shall be permitted within beam pocket(s).
- (5) For beam depths less than or equal to 10 percent of the ceiling height ($0.1 H$), spot-type detectors shall be located with smooth ceiling spacing.
- (6) For beam depths greater than 10 percent of the ceiling height ($0.1 H$), spot-type detectors shall not be required to be located closer than ($0.4 H$) and shall not exceed 50 percent of smooth ceiling spacing.

17.7.4.2.4.5* For sloped ceilings with beam pockets formed by intersecting beams, the following shall apply:

- (1) Spot-type detector(s) shall be located at the bottom of the beams.
- (2) The ceiling height shall be taken as the average height over slope.
- (3) Spacing shall be measured along a horizontal projection of the ceiling.
- (4) For beam depths less than or equal to 10 percent of the ceiling height ($0.1 H$), spot-type detectors shall be spaced with not more than three beams between detectors and shall not exceed smooth ceiling spacing.
- (5) For beam depths greater than 10 percent of the ceiling height ($0.1 H$), spot-type detectors shall be spaced with not more than two beams between detectors, but shall not be required to be spaced closer than ($0.4 H$), and shall not exceed 50 percent of smooth ceiling spacing.

17.7.4.2.4.6 For sloped ceilings with solid joists, the detectors shall be located on the bottom of the joist.

17.7.4.3* Peaked.

17.7.4.3.1 Detectors shall first be spaced and located within 36 in. (910 mm) of the peak, measured horizontally.

17.7.4.3.2 The number and spacing of additional detectors, if any, shall be based on the horizontal projection of the ceiling.

17.7.4.4* Shed.

17.7.4.4.1 Detectors shall first be spaced and located within 36 in. (910 mm) of the high side of the ceiling, measured horizontally.

17.7.4.4.2 The number and spacing of additional detectors, if any, shall be based on the horizontal projection of the ceiling.

17.7.4.5 Raised Floors and Suspended Ceilings.

17.7.4.5.1 Spaces beneath raised floors and above suspended ceilings shall be treated as separate rooms for smoke detector spacing purposes.

17.7.4.5.2 Detectors installed beneath raised floors or above suspended ceilings, or both, including raised floors and suspended ceilings used for environmental air, shall not be used in lieu of providing detection within the room.

17.7.4.5.3 For raised floors, the following shall apply:

- (1) Detectors installed beneath raised floors shall be spaced in accordance with 17.7.4.1, 17.7.4.1.3, and 17.7.4.2.2.
- (2) Where the area beneath the raised floor is also used for environmental air, detector spacing shall also conform to 17.7.5.1 and 17.7.5.2.

17.7.4.5.4 For suspended ceilings, the following shall apply:

- (1) Detector spacing above suspended ceilings shall conform to the requirements of 17.7.4 for the ceiling configuration.
- (2) Where detectors are installed in ceilings used for environmental air, detector spacing shall also conform to 17.7.5.1, 17.7.5.2, and 17.7.5.4.

17.7.4.6 Air Sampling-Type Smoke Detector.

17.7.4.6.1 General.

17.7.4.6.1.1* In the absence of specific performance-based design criteria, each sampling port of an air sampling-type smoke detector shall be treated as a spot-type smoke detector for the purpose of location and spacing in accordance with 17.7.4.

17.7.4.6.1.2 Air sampling-type smoke detectors shall produce trouble signals if the airflow is outside the manufacturer's specified range.

17.7.4.6.1.3 If provided, atmospheric contaminant filtration shall be listed for use with the detector and installed and maintained in accordance with the air sampling-type smoke detector manufacturer's published instructions.

17.7.4.6.2 Pipe Network.

17.7.4.6.2.1 Maximum air sample transport time from the farthest sampling port to the detector shall not exceed 120 seconds.

17.7.4.6.2.2 Sampling pipe networks shall be designed on the basis of, and shall be supported by, computer-based fluid dynamics design calculations to ensure required performance.

17.7.4.6.2.3 The sampling pipe network design calculations shall include pressure, volumetric flow, and alarm sensitivity at each sampling port.

17.7.4.6.2.4 Software applications for the design of pipe networks shall be listed for use with the manufacturer's equipment.

17.7.4.6.2.5 Sampling system piping shall be conspicuously identified as "SMOKE DETECTOR SAMPLING TUBE — DO NOT DISTURB," as follows:

- (1) At changes in direction or branches of piping
- (2) At each side of penetrations of walls, floors, or other barriers

- (3) At intervals on piping that provide visibility within the space, but no greater than 20 ft (6.1 m)

17.7.4.6.2.6* Sampling ports shall be identified as such.

17.7.4.6.2.7* If provided, test ports at the end (most remote location) of a pipe run installed in the pipe network solely for the purpose of validating consistency in performance (also referred to as benchmark test points) shall be included in the design calculations and allowed, but not required, to comply with the requirements of 17.7.4.6.2.

17.7.4.6.2.8 If the piping and fittings are painted, the painting shall be performed in accordance with the air sampling-type smoke detector manufacturer's published instructions.

17.7.4.6.2.9* Pipe network materials, sizing, and installation shall be in accordance with the manufacturer's published requirements and suitable for use in the environment in which they are installed.

17.7.4.6.2.10 Where used, capillary tubing shall be sized and affixed in accordance with the manufacturer's published instructions and computer-based design calculations.

17.7.4.6.3 Installation and Spacing.

17.7.4.6.3.1* Air sampling pipe network fittings shall be installed air-tight and permanently affixed.

17.7.4.6.3.2 Sampled air shall be exhausted to a lessor or equal pressure zone. The pressure differential between the sampled air and detector exhaust shall not exceed the manufacturer's published instructions.

17.7.4.6.3.3* Supports for sampling pipe shall be in accordance with the air sampling-type smoke detector manufacturer's published instructions.

17.7.4.6.4 Special Applications.

17.7.4.6.4.1 Air Duct Applications.

(A) The air sampling system shall be listed for air duct applications and shall be installed in accordance with the manufacturer's published instructions.

(B) The inlet and exhaust sections of pipe that are installed inside the air duct shall be air-tight and shall exhaust the sampled air in accordance with the manufacturer's published instructions.

17.7.4.6.4.2* Electrical Cabinet Applications. For protection of cabinets containing electrical equipment, the air sampling ports shall be located in the main airflow at the exhaust vents, downstream of the airflow distribution path, or in accordance with the manufacturer's published instructions.

17.7.4.7 Projected Beam-Type Smoke Detectors.

17.7.4.7.1 Projected beam-type smoke detectors shall be located in accordance with the manufacturer's published instructions.

17.7.4.7.2* The effects of stratification shall be evaluated when locating the detectors.

17.7.4.7.3 The beam length shall not exceed the maximum permitted by the equipment listing.

17.7.4.7.4 If reflectors are used with projected beams, the reflectors shall be installed in accordance with the manufacturer's published instructions.

17.7.4.7.5 A projected beam-type smoke detector shall be considered equivalent to a row of spot-type smoke detectors for level and sloping ceiling applications.

17.7.4.7.6 Projected beam-type detectors and reflectors shall be mounted on stable surfaces to prevent false or erratic operation due to movement.

17.7.4.7.7 The beam shall be designed so that small angular movements of the light source or receiver do not prevent operation due to smoke and do not cause nuisance or unintentional alarms.

17.7.4.7.8* Unless otherwise permitted by 17.4.2.2, the design and installation of projected beam-type detectors shall address the potential for the obstruction of the light path.

17.7.5 Heating, Ventilating, and Air-Conditioning (HVAC).

17.7.5.1* In spaces served by air-handling systems, detectors shall not be located where airflow prevents operation of the detectors.

17.7.5.2 In under-floor spaces and above-ceiling spaces that are used as HVAC plenums, detectors shall be listed for the anticipated environment as required by 17.7.1.8.

17.7.5.3 Detector spacings and locations shall be selected on the basis of anticipated airflow patterns and fire type.

17.7.5.4* Detectors placed in environmental air ducts or plenums shall not be used as a substitute for open area detectors.

17.7.5.4.1 Where detectors are used for the control of smoke spread, the requirements of 17.7.6 shall apply.

17.7.5.4.2 Where open area protection is required, 17.7.4 shall apply.

17.7.5.5 Detectors placed in environmental air ducts or plenums shall be permitted to be either supervisory or alarm initiating devices.

17.7.6* Smoke Detectors for Control of Smoke Spread.

17.7.6.1* Classifications. Smoke detectors installed and used to prevent smoke spread by initiating control of fans, dampers, doors, and other equipment shall be classified in the following manner:

- (1) Area detectors that are installed in the related smoke compartments
- (2) Detectors that are installed in the air duct systems
- (3) Video image smoke detection that is installed in related smoke compartments

17.7.6.2* Limitations.

17.7.6.2.1 Detectors that are installed in the air duct system in accordance with 17.7.6.1(2) shall not be used as a substitute for open area protection.

17.7.6.2.2 Where open area protection is required, 17.7.4 shall apply.

17.7.6.3* Purposes.

17.7.6.3.1 To minimize the recirculation of smoke, a detector approved for air duct use shall be installed as required by NFPA 90A and 17.7.6.4.2.

17.7.6.3.2 If smoke detectors are used to initiate selectively the operation of equipment to control smoke spread, the requirements of 17.7.6.4.2.2 shall apply.

17.7.6.3.3 If detectors are used to initiate the operation of smoke doors, the requirements of 17.7.6.6 shall apply.

17.7.6.3.4 If duct detectors are used to initiate the operation of smoke dampers within ducts, the requirements of 17.7.6.5 shall apply.

17.7.6.4 Application.

17.7.6.4.1 Area Smoke Detectors Within Smoke Compartments. Area smoke detectors within smoke compartments shall be permitted to be used to control the spread of smoke by initiating operation of doors, dampers, and other equipment.

17.7.6.4.2* Smoke Detection for Air Duct System.

17.7.6.4.2.1 Supply Air System.

(A) Where the detection of smoke in the supply air system is required by other NFPA standards, a detector(s) listed for the air velocity present shall be installed in the supply air duct downstream of both the fan and the filters.

(B) Where the air duct system passes through other smoke compartments not served by the duct, additional smoke detectors shall not be required to be installed.

17.7.6.4.2.2* Return Air System. Unless otherwise modified by 17.7.6.4.2.2(A) or 17.7.6.4.2.2(B), if the detection of smoke in the return air system is required by other NFPA standards, a detector(s) listed for the air velocity present shall be located where the air leaves each smoke compartment, or in the duct system before the air enters the return air system common to more than one smoke compartment.

(A) Additional smoke detectors shall not be required to be installed in ducts where the air duct system passes through other smoke compartments not served by the duct.

(B) Where total coverage smoke detection is installed in accordance with 17.5.3.1 in all areas of the smoke compartment served by the return air system, installation of additional detector(s) listed for the air velocity present where the air leaves each smoke compartment, or in the duct system before the air enters in the return air system shall not be required, provided that their function is accomplished by the design of the total coverage smoke detection system.

17.7.6.5 Location and Installation of Detectors in Air Duct Systems.

17.7.6.5.1 Detectors shall be listed for the purpose for which they are being used.

17.7.6.5.2* Air duct detectors shall be installed in such a way as to obtain a representative sample of the airstream.

17.7.6.5.3 This installation shall be permitted to be achieved by any of the following methods:

- (1) Rigid mounting within the duct

- (2) Rigid mounting to the wall of the duct with the sensing element protruding into the duct
- (3) Installation outside the duct with rigidly mounted sampling tubes protruding into the duct
- (4) Installation through the duct with projected light beam

17.7.6.5.4 Detectors shall be mounted in accordance with the manufacturer's published instructions and shall be accessible for cleaning by providing access doors or panels in accordance with NFPA 90A.

17.7.6.5.5 The location of all detectors in air duct systems shall be permanently and clearly identified and recorded.

17.7.6.5.6 Detectors mounted outside of a duct that employs sampling tubes for transporting smoke from inside the duct to the detector shall be designed and installed to allow verification of airflow from the duct to the detector.

17.7.6.5.7 Detectors shall be listed for operation over the complete range of air velocities, temperature, and humidity expected at the detector when the air-handling system is operating.

17.7.6.5.8 All penetrations of a return air duct in the vicinity of detectors installed on or in an air duct shall be sealed to prevent entrance of outside air and possible dilution or redirection of smoke within the duct.

17.7.6.6 Smoke Detectors for Door Release Service.

17.7.6.6.1 Smoke detectors that are part of an open area protection system covering the room, corridor, or enclosed space on each side of the smoke door and that are located and spaced as required by 17.7.4 shall be permitted to accomplish smoke door release service.

17.7.6.6.2 Smoke detectors that are used exclusively for smoke door release service shall be located and spaced as required by 17.7.6.6.

17.7.6.6.3 Where smoke door release is accomplished directly from the smoke detector(s), the detector(s) shall be listed for releasing service.

17.7.6.6.4 The number of detectors required shall be determined in accordance with 17.7.6.6.4.1 through 17.7.6.6.4.4.

17.7.6.6.4.1 If doors are to be closed in response to smoke flowing in either direction, the requirements of 17.7.6.6.4.1 (A) through 17.7.6.6.4.1 (D) shall apply.

(A) If the depth of wall section above the door is 24 in. (610 mm) or less, one ceiling-mounted smoke detector shall be required on one side of the doorway only, or two wall-mounted detectors shall be required, one on each side of the doorway. Figure 17.7.6.6.4.1(A), part A or B, shall apply.

(B) If the depth of wall section above the door is greater than 24 in. (610 mm) on one side only, one ceiling-mounted smoke detector shall be required on the higher side of the doorway only, or one wall-mounted detector shall be required on both sides of the doorway. Figure 17.7.6.6.4.1(A), part D, shall apply.

(C)* If the depth of wall section above the door is greater than 24 in. (610 mm) on both sides, two ceiling-mounted or wall-mounted detectors shall be required, one on each side of the doorway. Figure 17.7.6.6.4.1(A), part F, shall apply.

(D) If a detector is specifically listed for door frame mounting, or if a listed combination or integral detector-door closer

assembly is used, only one detector shall be required if installed in the manner recommended by the manufacturer's published instructions. Figure 17.7.6.6.4.1(A), parts A, C, and E, shall apply.

17.7.6.6.4.2 If door release is intended to prevent smoke transmission from one space to another in one direction only, detectors located in the space to which smoke is to be confined, regardless of the depth of wall section above the door, shall be in accordance with 17.7.6.6.5. Alternatively, a smoke detector conforming with 17.7.6.6.4.1(D) shall be permitted to be used.

17.7.6.6.4.3 If there are multiple doorways, additional ceiling-mounted detectors shall be required as specified in 17.7.6.6.4.3(A) through 17.7.6.6.4.3(C).

(A) If the separation between doorways exceeds 24 in. (610 mm), each doorway shall be treated separately. Figure 17.7.6.6.4.3(A), part E, shall apply.

(B) Each group of three or more doorway openings shall be treated separately. Figure 17.7.6.6.4.3(B) shall apply.

(C) Each group of doorway openings that exceeds 20 ft (6.1 m) in width, measured at its overall extremes, shall be treated separately. Figure 17.7.6.6.4.3(C) shall apply.

17.7.6.6.4.4 If there are multiple doorways and listed door frame-mounted detectors, or if listed combination or integral detector-door closer assemblies are used, there shall be one detector for each single or double doorway.

17.7.6.6.5 The locations of detectors shall be determined in accordance with 17.7.6.6.5.1 and 17.7.6.6.5.2.

17.7.6.6.5.1 If ceiling-mounted smoke detectors are to be installed on a smooth ceiling for a single or double doorway, they shall be located as follows [Figure 17.7.6.6.4.3(A) shall apply]:

- (1) On the centerline of the doorway
- (2) No more than 5 ft (1.5 m), measured along the ceiling and perpendicular to the doorway [Figure 17.7.6.6.4.1(A) shall apply.]
- (3) No closer than shown in Figure 17.7.6.6.4.1(A), parts B, D, and F

17.7.6.6.5.2 If ceiling-mounted detectors are to be installed in conditions other than those outlined in 17.7.6.6.5.1, an engineering evaluation shall be made.

17.7.7 Special Considerations.

17.7.7.1 Spot-Type Detectors.

17.7.7.1.1 Combination and multi-sensor smoke detectors that have a fixed-temperature element as part of the unit shall be selected in accordance with Table 17.6.2.1 for the maximum ceiling temperature expected in service.

17.7.7.1.2* Holes in the back of a detector shall be covered by a gasket, sealant, or equivalent means, and the detector shall be mounted so that airflow from inside or around the housing does not prevent the entry of smoke during a fire or test condition.

17.7.7.2* High-Rack Storage. The location and spacing of smoke detectors for high-rack storage shall address the commodity, quantity, and configuration of the rack storage.







Depth of wall section above door	Door frame mounted	Ceiling or wall mounted
d	Smoke detector listed for frame mounting or as part of closer assembly	Smoke detector ceiling or wall mounted
0-24 in. (0-610 mm) on both sides of doorway	A  Detector or detector closer mounted on either side	B  One ceiling-mounted detector on either side or one wall-mounted detector on each side
Over 24 in. (610 mm) on one side only	C  Detector or detector closer mounted on higher side	D  One ceiling-mounted detector on higher side or one wall-mounted detector on each side
Over 24 in. (610 mm) on both sides	E  Detector or detector closer mounted on either side	F  Two detectors required
Over 60 in. (1.52 m)	G Might require additional detectors	

FIGURE 17.7.6.4.1(A) Detector Location Requirements for Wall Sections.




FIGURE 17.7.6.4.3(A) Detector Location Requirements for Single and Double Doors.




FIGURE 17.7.6.4.3(B) Detector(s) Location ± 24 in. (610 mm) Requirements for Group Doorways.




FIGURE 17.7.6.4.3(C) Detector(s) Location ± 24 in. (610 mm) Requirements for Group Doorways over 20 ft (6.1 m) in Width.

17.7.7.3 High Air Movement Areas.

17.7.7.3.1* General. The purpose and scope of 17.7.7.3 shall be to provide location and spacing guidance for smoke detectors intended for early warning of fire in high air movement areas.

17.7.7.3.2 Location. Smoke detectors shall not be located directly in the airstream of supply registers.

17.7.7.3.3* Spacing.

17.7.7.3.3.1 Smoke detector spacing shall be reduced where the airflow in a defined space exceeds 8 minutes per air change (total space volume) (equal to 7.5 air changes per hour).

17.7.7.3.3.2 Where spacing must be adjusted for airflow, spot-type smoke detector spacing shall be adjusted in accordance with Table 17.7.7.3.3.2 or Figure 17.7.7.3.3.2 before making any other spacing adjustments required by this Code.

17.7.7.3.3.3 Air sampling or projected beam smoke detectors shall be installed in accordance with the manufacturer's published instructions.

17.7.7.3.3.4 HVAC Mechanical Rooms. Where HVAC mechanical rooms are used as an air plenum for return air, the spacings of smoke detectors shall not be required to be reduced based on the number of air changes.

Table 17.7.7.3.3.2 Smoke Detector Spacing Based on Air Movement (Not to Be Used for Under-Floor or Above-Ceiling Spaces)

Minutes per Air Change	Air Changes per Hour	Spacing per Detector	
		ft ²	m ²
1	60	125	12
2	30	250	23
3	20	375	35
4	15	500	46
5	12	625	58
6	10	750	70
7	8.6	875	81
8	7.5	900	84
9	6.7	900	84
10	6	900	84




FIGURE 17.7.7.3.3.2 High Air Movement Areas (Not to Be Used for Under-Floor or Above-Ceiling Spaces).

17.7.8 Video Image Smoke Detection.

17.7.8.1 Video image smoke detection systems and all of the components thereof, including hardware and software, shall be listed for the purpose of smoke detection.

17.7.8.2 Video image smoke detection systems shall comply with all of the applicable requirements of Chapters 1, 10, 14, 17, and 23 of this Code.

17.7.8.2.1 Systems shall be designed in accordance with the performance-based design requirements of Section 17.3.

17.7.8.2.2 The location and spacing of video image smoke detectors shall comply with the requirements of 17.11.5.

17.7.8.3* Video signals generated by cameras that are components of video image smoke detection systems shall be permitted to be transmitted to other systems for other uses only through output connections provided specifically for that purpose by the video system manufacturer.

17.7.8.4* All component controls and software shall be protected from unauthorized changes.

17.7.8.5 All changes to the software or component settings shall be tested in accordance with Chapter 14.

17.8 Radiant Energy–Sensing Fire Detectors.

17.8.1* General.

17.8.1.1 The radiant energy detection design documentation shall state the required performance objective of the system.

17.8.1.2 The purpose and scope of Section 17.8 shall be to provide requirements for the selection, location, and spacing of fire detectors that sense the radiant energy produced by burning substances.

17.8.1.3 These detectors shall be categorized as flame detectors and spark/ember detectors.

17.8.2* Fire Characteristics and Detector Selection.

17.8.2.1* The type and quantity of radiant energy–sensing fire detectors shall be determined on the basis of the performance characteristics of the detector and an analysis of the hazard, including the burning characteristics of the fuel, the fire growth rate, the environment, the ambient conditions, and the capabilities of the extinguishing media and equipment.

17.8.2.2* The selection of the radiant energy–sensing detectors shall be based on the following:

- (1) Matching of the spectral response of the detector to the spectral emissions of the fire or fires to be detected
- (2) Minimizing the possibility of spurious nuisance alarms from non-fire sources inherent to the hazard area

17.8.3 Spacing Considerations.

17.8.3.1 General Rules.

17.8.3.1.1* Radiant energy–sensing fire detectors shall be employed consistent with the listing or approval and the inverse square law, which defines the fire size versus distance curve for the detector.

17.8.3.1.2 Detector quantity shall be based on the detectors being positioned so that no point requiring detection in the hazard area is obstructed or outside the field of view of at least one detector.

17.8.3.2 Spacing Considerations for Flame Detectors.

17.8.3.2.1* The location and spacing of detectors shall be the result of an engineering evaluation that includes the following:

- (1) Size of the fire that is to be detected
- (2) Fuel involved
- (3) Sensitivity of the detector
- (4) Field of view of the detector
- (5) Distance between the fire and the detector
- (6) Radiant energy absorption of the atmosphere
- (7) Presence of extraneous sources of radiant emissions
- (8) Purpose of the detection system
- (9) Response time required

17.8.3.2.2 The system design shall specify the size of the flaming fire of given fuel that is to be detected.

17.8.3.2.3* In applications where the fire to be detected could occur in an area not on the optical axis of the detector, the distance shall be reduced or detectors shall be added to compensate for the angular displacement of the fire in accordance with the manufacturer's published instructions.

17.8.3.2.4* In applications in which the fire to be detected is of a fuel that differs from the test fuel used in the process of listing or approval, the distance between the detector and the fire shall be adjusted consistent with the fuel specificity of the detector as established by the manufacturer.

17.8.3.2.5 Because flame detectors are line-of-sight devices, their ability to respond to the required area of fire in the zone that is to be protected shall not be compromised by the presence of intervening structural members or other opaque objects or materials.

17.8.3.2.6* Provisions shall be made to sustain detector window clarity in applications where airborne particulates and aerosols coat the detector window between maintenance intervals and affect sensitivity.

17.8.3.3 Spacing Considerations for Spark/Ember Detectors.

17.8.3.3.1* The location and spacing of detectors shall be the result of an engineering evaluation that includes the following:

- (1) Size of the spark or ember that is to be detected
- (2) Fuel involved
- (3) Sensitivity of the detector
- (4) Field of view of the detector
- (5) Distance between the fire and the detector
- (6) Radiant energy absorption of the atmosphere
- (7) Presence of extraneous sources of radiant emissions
- (8) Purpose of the detection systems
- (9) Response time required

17.8.3.3.2* The system design shall specify the size of the spark or ember of the given fuel that the detection system is to detect.

17.8.3.3.3 Spark detectors shall be positioned so that all points within the cross section of the conveyance duct, conveyor, or chute where the detectors are located are within the field of view (*as defined in 3.3.113*) of at least one detector.

17.8.3.3.4* The location and spacing of the detectors shall be adjusted using the inverse square law, modified for the atmospheric absorption and the absorption of nonburning fuel suspended in the air in accordance with the manufacturer's published instructions.

17.8.3.3.5* In applications where the sparks to be detected could occur in an area not on the optical axis of the detector, the distance shall be reduced or detectors shall be added to compensate for the angular displacement of the fire in accordance with the manufacturer's published instructions.

17.8.3.3.6* Provisions shall be made to sustain the detector window clarity in applications where airborne particulates and aerosols coat the detector window and affect sensitivity.

17.8.4 Other Considerations.

17.8.4.1 Radiant energy-sensing detectors shall be protected either by design or installation to ensure that optical performance is not compromised.

17.8.4.2 If necessary, radiant energy-sensing detectors shall be shielded or otherwise arranged to prevent action from unwanted radiant energy.

17.8.4.3 Where used in outdoor applications, radiant energy-sensing detectors shall be shielded or otherwise arranged in a fashion to prevent diminishing sensitivity by conditions such as rain or snow and yet allow a clear field of vision of the hazard area.

17.8.4.4 A radiant energy-sensing fire detector shall not be installed in a location where the ambient conditions are known to exceed the extremes for which the detector has been listed.

17.8.5 Video Image Flame Detection.

17.8.5.1 Video image flame detection systems and all of the components thereof, including hardware and software, shall be listed for the purpose of flame detection.

17.8.5.2 Video image flame detection systems shall comply with all of the applicable requirements of Chapters 1, 10, 14, 17, and 23 of this Code.

17.8.5.3* Video signals generated by cameras that are components of video image flame detection systems shall be permitted to be transmitted to other systems for other uses only through output connections provided specifically for that purpose by the video system manufacturer.

17.8.5.4* All component controls and software shall be protected from unauthorized changes.

17.8.5.5 All changes to the software or component settings shall be tested in accordance with Chapter 14.

17.9 Combination, Multi-Criteria, and Multi-Sensor Detectors.

17.9.1 General. The requirements for the selection, location, and spacing of combination, multi-criteria, and multi-sensor detectors shall comply with Section 17.9.

17.9.2 Combination Detectors.

17.9.2.1 A combination detector shall be listed for each sensor.

17.9.2.2 The device listings shall determine the locations and spacing criteria in accordance with Chapter 17.

17.9.3 Multi-Criteria Detectors.

17.9.3.1 A multi-criteria detector shall be listed for the primary function of the device.

17.9.3.2 Because of the device-specific, software-driven solution of multi-criteria detectors to reduce unwanted alarms and

improve detector response to a nonspecific fire source, location and spacing criteria included with the detector installation instructions shall be followed.

17.9.4 Multi-Sensor Detectors.

17.9.4.1 A multi-sensor detector shall be listed for each sensor.

17.9.4.2 Because of the device-specific, software-driven solution of multi-sensor detectors to reduce unwanted alarms and improve detector response to a nonspecific fire source, location and spacing criteria included with the detector installation instructions shall be followed.

17.10 Gas Detection.

17.10.1 General. The purpose and scope of Section 17.10 shall be to provide requirements for the selection, installation, and operation of gas detectors other than carbon monoxide detectors.

17.10.2 Gas Characteristics and Detector Selection.

17.10.2.1 Gas detection equipment shall be listed in accordance with applicable standards such as UL 1484, *Residential Gas Detectors*, or UL 2075, *Gas and Vapor Detectors and Sensors*, for the specific gas or vapor it is intended to detect.

17.10.2.2 Any gas detection systems installed on a fire alarm system shall comply with all the applicable requirements of Chapters 1, 10, 14, 17, and 23 of this Code.

17.10.2.3 The requirements of this Code shall not apply to gas detection systems used solely for process control.

17.10.2.4* The selection and placement of the gas detectors shall be based on an engineering evaluation.

17.11 Other Fire Detectors.

17.11.1 Detectors that operate on principles different from those covered by Sections 17.6 through 17.8 shall be classified as other fire detectors.

17.11.1.1 Such detectors shall be installed in all areas where they are required either by other NFPA codes and standards or by the authority having jurisdiction.

17.11.2* Other fire detectors shall operate where subjected to the abnormal concentration of combustion effects that occur during a fire.

17.11.3 Detection layout shall be based upon the size and intensity of fire to provide the necessary quantity of required products and related thermal lift, circulation, or diffusion for operation.

17.11.4 Room sizes and contours, airflow patterns, obstructions, and other characteristics of the protected hazard shall be taken into account.

17.11.5 Location and spacing of detectors shall comply with 17.11.5.1 through 17.11.5.3.

17.11.5.1 The location and spacing of detectors shall be based on the principle of operation and an engineering survey of the conditions anticipated in service.

17.11.5.1.1 The manufacturer's published instructions shall be consulted for recommended detector uses and locations.

17.11.5.2 Detectors shall not be spaced beyond their listed or approved maximums.

17.11.5.2.1 Closer spacing shall be used where the structural or other characteristics of the protected hazard warrant.

17.11.5.3 The location and sensitivity of the detectors shall be based on a documented engineering evaluation that includes the manufacturer's installation instructions and the following:

- (1) Structural features, size, and shape of the rooms and bays
- (2) Occupancy and uses of the area
- (3) Ceiling height
- (4) Ceiling shape, surface, and obstructions
- (5) Ventilation
- (6) Ambient environment
- (7) Burning characteristics of the combustible materials present
- (8) Configuration of the contents in the area to be protected

17.12 Carbon Monoxide Detectors.

17.12.1* Where carbon monoxide protection of a building is required, carbon monoxide detectors shall be installed in accordance with all of the following, unless a performance-based design in accordance with Section 17.3 is used:

- (1)* On the ceiling in the same room as permanently installed fuel-burning appliances
- (2)* Centrally located on every habitable level and in every HVAC zone of the building
- (3)* Outside of each separate dwelling unit, guest room, and guest suite sleeping area within 21 ft (6.4 m) of any door to a sleeping room, with the distance measured along a path of travel
- (4)* Other locations where required by applicable laws, codes, or standards

17.12.2 Carbon monoxide detectors shall meet the following requirements:

- (1) Carbon monoxide detectors shall be listed in accordance with applicable standards, such as UL 2075, *Gas and Vapor Detectors and Sensors*.
- (2) Carbon monoxide detectors shall be set to respond to the sensitivity limits specified in UL 2034, *Single and Multiple Station Carbon Monoxide Alarms*.

17.12.3* Carbon monoxide detectors that are installed in air duct systems shall not be used as a substitute for open area protection.

17.12.4 All carbon monoxide detectors shall be located and mounted so that accidental operation will not be caused by jarring or vibration.

17.12.5 The location of carbon monoxide detectors shall be based on an evaluation of potential ambient sources and flows of carbon monoxide, moisture, temperature, dust, or fumes and of electrical or mechanical influences to minimize nuisance alarms.

17.12.6 The selection and placement of carbon monoxide detectors shall take into account both the performance characteristics of the detector and the areas into which the detectors are to be installed to prevent nuisance and unintentional alarms or improper operation after installation.

17.12.7 Unless tested and listed for recessed mounting, carbon monoxide detectors shall not be recessed into the mounting surface.

17.12.8 Protection During Construction.

17.12.8.1 Where detectors are installed for signal initiation during construction, they shall be replaced prior to the final commissioning of the system.

17.12.8.2 Where detection is not required during construction, detectors shall not be installed until after all other construction trades have completed cleanup.

17.12.9 Carbon Monoxide Detectors for Control of Carbon Monoxide Spread.

17.12.9.1 System designers shall consider the spread of carbon monoxide through an occupancy through the HVAC system.

17.12.9.2 Interaction with smoke control systems, if such is provided, shall be coordinated.

17.13 Sprinkler Waterflow Alarm-Initiating Devices.

17.13.1* The provisions of Section 17.13 shall apply to devices that initiate an alarm indicating a flow of water in a sprinkler system.

17.13.2* Activation of the initiating device shall occur within 90 seconds of waterflow at the alarm-initiating device when flow occurs that is equal to or greater than that from a single sprinkler of the smallest orifice size installed in the system.

17.13.3 Movement of water due to waste, surges, or variable pressure shall not initiate an alarm signal.

17.14* Detection of Operation of Other Automatic Extinguishing Systems. The operation of fire extinguishing systems or suppression systems shall initiate an alarm signal by alarm-initiating devices installed in accordance with their individual listings.

17.15 Manually Actuated Alarm-Initiating Devices.

17.15.1 Manually actuated alarm-initiating devices shall be listed in accordance with applicable standards such as UL 38, *Manual Signaling Boxes for Fire Alarm Systems*.

17.15.2 Manually actuated alarm-initiating devices for initiating signals other than for fire alarm shall be permitted if the devices are differentiated from manual fire alarm boxes by a color other than red and labeling.

17.15.3 Combination manual fire alarm boxes and guard's signaling stations shall be permitted.

17.15.4 Manually actuated alarm-initiating devices shall be securely mounted.

17.15.5 Manually actuated alarm-initiating devices shall be mounted on a background of contrasting color.

17.15.6 The operable part of a manually actuated alarm-initiating device shall be not less than 42 in. (1.07 m) and not more than 48 in. (1.22 m) from the finished floor.

17.15.7 Manually actuated alarm-initiating devices shall be permitted to be single action or double action.

17.15.8* Listed protective covers shall be permitted to be installed over single- or double-action manually actuated alarm-initiating devices.

17.15.9 Manual fire alarm boxes shall comply with 17.15.9.1 through 17.15.9.6.

17.15.9.1 Manual fire alarm boxes shall be used only for fire alarm initiating purposes.

17.15.9.2 Manual fire alarm boxes shall be installed so that they are conspicuous, unobstructed, and accessible.

17.15.9.3* Unless installed in an environment that precludes the use of red paint or red plastic, manual fire alarm boxes shall be red in color.

17.15.9.4 Manual fire alarm boxes shall be located within 5 ft (1.5 m) of each exit doorway on each floor.

17.15.9.5* Additional manual fire alarm boxes shall be provided so that the travel distance to the nearest manual fire alarm box will not exceed 200 ft (61 m), measured horizontally on the same floor.

17.15.9.6 Manual fire alarm boxes shall be mounted on both sides of grouped openings over 40 ft (12.2 m) in width, and within 5 ft (1.5 m) of each side of the grouped opening.

17.16 Fire Extinguisher Electronic Monitoring Device. A fire extinguisher electronic monitoring device shall indicate those conditions for a specific fire extinguisher required by NFPA 10 to a fire alarm control unit or other control unit.

17.17 Supervisory Signal–Initiating Devices.

17.17.1 Control Valve Supervisory Signal–Initiating Device.

17.17.1.1 Two separate and distinct signals shall be initiated: one indicating movement of the valve from its normal position (off-normal), and the other indicating restoration of the valve to its normal position.

17.17.1.2 The off-normal signal shall be initiated during the first two revolutions of the handwheel or during one-fifth of the travel distance of the valve control apparatus from its normal position.

17.17.1.3 The off-normal signal shall not be restored at any valve position except normal.

17.17.1.4 An initiating device for supervising the position of a control valve shall not interfere with the operation of the valve, obstruct the view of its indicator, or prevent access for valve maintenance.

17.17.2 Pressure Supervisory Signal–Initiating Device.

17.17.2.1 Two separate and distinct signals shall be initiated: one indicating that the required pressure has increased or decreased (off-normal), and the other indicating restoration of the pressure to its normal value.

17.17.2.2 The requirements in 17.17.2.2.1 through 17.17.2.2.4 shall apply to pressure supervisory signal-initiating devices.

17.17.2.2.1 Pressure Tank.

(A) A pressure tank supervisory signal-initiating device for a pressurized limited water supply, such as a pressure tank, shall indicate both high- and low-pressure conditions.

(B) The off-normal signal shall be initiated when the required pressure increases or decreases by 10 psi (70 kPa).

17.17.2.2.2* Dry Pipe and Preaction Sprinkler Systems.

(A) A pressure supervisory signal-initiating device shall indicate both high- and low-pressure conditions.

(B) Unless otherwise permitted by the manufacturer's published installation instructions, the off-normal signal shall be initiated when the pressure increases or decreases by 10 psi (70 kPa).

17.17.2.2.3 Steam Pressure.

(A) A steam pressure supervisory signal-initiating device shall indicate a low pressure condition.

(B) The off-normal signal shall be initiated prior to the pressure falling below 110 percent of the minimum operating pressure of the steam-operated equipment supplied.

17.17.2.2.4 Other Sources. An initiating device for supervising the pressure of sources other than those specified in 17.17.2.2.1 through 17.17.2.2.3 shall be provided as required by the authority having jurisdiction.

17.17.3 Water Level Supervisory Signal–Initiating Device.

17.17.3.1 Two separate and distinct signals shall be initiated: one indicating that the required water level has been lowered or raised (off-normal), and the other indicating restoration.

17.17.3.2 A pressure tank signal-initiating device shall indicate both high and low water level conditions.

17.17.3.2.1 The off-normal signal shall be initiated when the water level falls 3 in. (76 mm) or rises 3 in. (76 mm).

17.17.3.3 A supervisory signal-initiating device for other than pressure tanks shall initiate a low water level signal when the water level falls 12 in. (300 mm).

17.17.4 Water Temperature Supervisory Signal–Initiating Device.

17.17.4.1 A temperature supervisory device for a water storage container exposed to freezing conditions shall initiate two separate and distinctive signals, as specified in 17.17.4.2.

17.17.4.2 One signal shall indicate a decrease in water temperature to 40°F (4.4°C), and the other shall indicate its restoration to above 40°F (4.4°C).

17.17.5 Room Temperature Supervisory Signal–Initiating Device. A room temperature supervisory device shall indicate a decrease in room temperature to 40°F (4.4°C) and its restoration to above 40°F (4.4°C).

Chapter 18 Notification Appliances

18.1* Application.

18.1.1 The requirements of this chapter shall apply where required by the authority having jurisdiction governing laws, codes, or standards; or other parts of this Code.

18.1.2 The requirements of this chapter shall address the reception of a notification signal and not the signal's information content.

18.1.3 The performance, location, and mounting of notification appliances used to initiate or direct evacuation or relocation of the occupants, or for providing information to occupants or staff, shall comply with this chapter.

18.1.4 The performance, location, and mounting of annunciators, displays, and printers used to display or record information for use by occupants, staff, responding emergency

personnel, or supervising station personnel shall comply with this chapter.

18.1.5* The requirements of this chapter shall apply to the areas, spaces, or system functions where required by the authority having jurisdiction governing laws, codes, or standards; or other parts of this Code requiring compliance with this chapter.

18.1.6 Notification appliances shall be permitted to be used within buildings or outdoors and to target the general building, area, or space, or only specific parts of a building, area, or space designated in specific zones and sub-zones.

18.1.7 The requirements of Chapters 10, 11, 14, 23, and 24 shall apply to the interconnection of notification appliances, the cybersecurity of control and communication configurations, the power supplies, and the use of the information provided by notification appliances.

18.2 Purpose. Notification appliances shall provide stimuli for initiating emergency action and provide information to users, emergency response personnel, and occupants.

18.3 General.

18.3.1 Listing. All notification appliances installed in conformity with Chapter 18 shall be listed for the purpose for which they are used.

18.3.2 Nameplates.

18.3.2.1 Notification appliances shall include on their nameplates reference to electrical requirements and rated audible or visual performance, or both, as defined by the listing authority.

18.3.2.2 Audible appliances shall include on their nameplates reference to their parameters or reference to installation documents (supplied with the appliance) that include the parameters in accordance with 18.4.4 or 18.4.5.

18.3.2.3 Visual notification appliances shall include on their nameplates reference to their parameters or reference to installation documents (supplied with the appliance) that include the parameters in accordance with 18.5.3.1 or Section 18.6.

18.3.3 Physical Construction.

18.3.3.1 Appliances intended for use in special environments, such as outdoors versus indoors, high or low temperatures, high humidity, dusty conditions, and hazardous locations, or where subject to tampering, shall be listed for the intended application.

18.3.3.2* Notification appliances used for signaling other than fire shall not have the word FIRE, or any fire symbol, in any form (i.e., stamped, imprinted, etc.) on the appliance visible to the public.

18.3.3.3 Notification appliances with multiple visible elements used for signaling other than fire shall be permitted to have fire markings only on those visible elements used for fire signaling.

18.3.3.4 In situations where existing notification appliances previously used exclusively for fire alarm signaling and marked with the word 'FIRE' are to be used for signaling other than fire, field modification to the marking shall be permitted provided that it is accomplished by one of the following methods:

(1) In accordance with manufacturers' published instructions

(2) Installation of a permanent sign directly adjacent or below the notification appliance indicating that it is multipurpose and will operate for fire and other emergency conditions

18.3.4* Mechanical Protection.

18.3.4.1 Appliances subject to mechanical damage shall be suitably protected.

18.3.4.2 If guards, covers, or lenses are employed, they shall be listed for use with the appliance.

18.3.4.3 The effect of guards, covers, or lenses on the appliance's field performance shall be in accordance with the listing requirements.

18.3.5 Mounting.

18.3.5.1 Appliances shall be supported independently of their attachments to the circuit conductors.

18.3.5.2 Appliances shall be mounted in accordance with the manufacturer's published instructions.

18.3.6* Connections. Terminals, leads, or addressable communication, that provide for monitoring the integrity of the notification appliance connections shall be provided.

18.3.7 Notification Appliance Circuits.

18.3.7.1* A notification appliance circuit shall comply with Chapter 12.

18.3.7.2 The selection of wire size and material shall meet the performance requirements of this chapter and Chapter 14.

18.4 Audible Characteristics.

18.4.1 General Requirements.

18.4.1.1* An average ambient sound level greater than 105 dBA shall require the use of a visual notification appliance(s) in accordance with Section 18.5 where the application is public mode or Section 18.6 where the application is private mode.

18.4.1.2* The total sound pressure level produced by combining the ambient sound pressure level with all audible notification appliances operating shall not exceed 110 dBA at the minimum hearing distance.

18.4.1.3* Sound from normal or permanent sources, having a duration of at least 60 seconds, shall be included when measuring maximum ambient sound level.

18.4.1.4 Sound from temporary or abnormal sources lasting less than 60 seconds shall not be required to be included when measuring maximum ambient sound level.

18.4.1.5 Audible alert and evacuation signal tones, including those that precede or follow voice messages, shall meet the requirements of 18.4.4 (Public Mode Audible Requirements), 18.4.5 (Private Mode Audible Requirements), 18.4.6 (Sleeping Area Requirements), or 18.4.7 (Narrow Band Tone Signaling for Exceeding Masked Thresholds), as applicable.

18.4.1.5.1* The designer of the audible notification system shall identify the rooms and spaces that will have audible notification and those where audible notification will not be provided.

18.4.1.5.2 Unless otherwise required by other sections of this Code, the coverage area for audible occupant notification shall be as required by other governing laws, codes, or standards.

18.4.1.5.3 Where other governing laws, codes, or standards require audible occupant notification for all or part of an area or space, coverage shall only be required in occupiable areas as defined in 3.3.195

18.4.1.5.4 The sound pressure levels that must be produced by the audible appliances in the coverage areas to meet the requirements of this Code shall be documented by the system designer during the planning and design of the notification system.

18.4.1.5.5 The greater of the expected average ambient sound pressure level or expected maximum sound pressure level having a duration of at least 60 seconds shall be documented for the coverage area by the system designer to ensure compliance with 18.4.4, 18.4.5, 18.4.6, or 18.4.7.

18.4.1.5.6 The design sound pressure levels to be produced by the notification appliances for the various coverage areas shall be documented for use during acceptance testing of the system.

18.4.1.5.7 Where required by the authority having jurisdiction, documentation of the design sound pressure levels for the various coverage areas shall be submitted for review and approval.

18.4.1.6* Voice messages shall not be required to meet the audibility requirements of 18.4.4 (Public Mode Audible Requirements), 18.4.5 (Private Mode Audible Requirements), 18.4.6 (Sleeping Area Requirements), or 18.4.7 (Narrow Band Tone Signaling for Exceeding Masked Thresholds), but shall meet the intelligibility requirements of 18.4.11 where voice intelligibility is required.

18.4.1.7 Audible notification appliances used for exit marking shall not be required to meet the audibility requirements of 18.4.4 (Public Mode Audible Requirements), 18.4.5 (Private Mode Audible Requirements), 18.4.6 (Sleeping Area Requirements), or 18.4.7 (Narrow Band Tone Signaling for Exceeding Masked Thresholds), except as required by 18.4.8 (Exit Marking Audible Notification Appliance Requirements).

18.4.2 Distinctive Evacuation Signal.

18.4.2.1* To meet the requirements of Section 10.10, the alarm audible signal pattern used to notify building occupants of the need to evacuate (i.e., leave the building) or relocate (i.e., from one area to another) shall be the standard alarm evacuation signal consisting of a three-pulse temporal pattern in accordance with ANSI/ASA S3.41, *Audible Emergency Evacuation (E2) and Evacuation Signals With Relocation Instructions (ESRI)*.

18.4.2.2* The signal shall be repeated until the fire alarm system is manually silenced or reset by authorized or emergency personnel.

18.4.2.3 Where approved by the authority having jurisdiction based on an emergency plan, the signal shall be permitted to automatically silence, but not less than 180 seconds after the signal was initiated.

18.4.2.4 The minimum repetition time shall be permitted to be automatically interrupted for the transmission of mass notification messages in accordance with Chapter 24.

18.4.2.5* The standard evacuation signal shall be synchronized within a notification zone.

18.4.3 Distinctive Carbon Monoxide Audible Alarm Signal.

18.4.3.1 Where a carbon monoxide detector or alarm is required by other codes or standards or by the authority having jurisdiction and where an audible signal is required, a distinctive signal pattern shall be required that is different from a fire evacuation signal.

18.4.3.2 Where an audible signal is required, the carbon monoxide signal shall be a four-pulse temporal pattern and comply with the following:

- (1) Signals shall be a pattern consisting of four cycles of 100 milliseconds $\pm$ 10 percent "on" and 100 milliseconds $\pm$ 10 percent "off," followed by 5 seconds $\pm$ 10 percent "off," as demonstrated in Figure 18.4.3.2.
- (2) After the initial 4 minutes of the carbon monoxide signal, the 5-second "off" time shall be permitted to be changed to 60 seconds $\pm$ 10 percent.
- (3) The alarm signal shall be repeated in compliance with 18.4.3.2(1) and 18.4.3.2(2) until the alarm resets or the alarm signal is manually silenced.

18.4.3.3 The signal shall be synchronized within a notification zone of a protected premises.

18.4.4* Public Mode Audible Requirements.

18.4.4.1* To ensure that audible public mode signals are clearly heard, unless otherwise permitted by 18.4.4.2 through 18.4.4.5, they shall have a sound level at least 15 dB above the average ambient sound level or 5 dB above the maximum sound level having a duration of at least 60 seconds, whichever is greater, measured 5 ft (1.5 m) above the floor in the area required to be served by the system using the A-weighted scale (dBA).


18.4.4.2 Where approved by the authority having jurisdiction or other governing codes or standards, the requirements for audible signaling shall be permitted to be reduced or eliminated when visual signaling is provided in accordance with Section 18.5.

18.4.4.3* Audible notification appliances installed in elevator cars shall be permitted to use the audibility criteria for private mode appliances detailed in 18.4.5.1.

18.4.4.4 If approved by the authority having jurisdiction, audible notification appliances installed in restrooms shall be permitted to use the audibility criteria for private mode appliances detailed in 18.4.5.1.

18.4.4.5 A signaling system arranged to stop or reduce ambient noise shall comply with 18.4.4.5.1 through 18.4.4.5.3.

18.4.4.5.1 A signaling system arranged to stop or reduce ambient noise shall produce a sound level at least 15 dB above the reduced average ambient sound level or 5 dB above the maximum sound level having a duration of at least 60 seconds after reduction of the ambient noise level, whichever is greater, measured 5 ft (1.5 m) above the floor in the area required to be served by the system using the A-weighted scale (dBA).



Although the diagram shows a square waveform, the wave can have other shapes that produce a similar effect.

FIGURE 18.4.3.2 Temporal Pattern Parameters — Carbon Monoxide Signal.

18.4.4.5.2 Visual notification appliances shall be installed in the affected areas in accordance with Sections 18.5 or 18.6.

18.4.4.5.3* Relays, circuits, or interfaces necessary to stop or reduce ambient noise shall meet the requirements of Chapters 10, 12, 21, and 23.

18.4.5 Private Mode Audible Requirements.

18.4.5.1* To ensure that audible private mode signals are clearly heard, they shall have a sound level at least 10 dB above the average ambient sound level or 5 dB above the maximum sound level having a duration of at least 60 seconds, whichever is greater, measured 5 ft (1.5 m) above the floor in the area required to be served by the system using the A-weighted scale (dBA).

18.4.5.2* Where approved by the authority having jurisdiction or other governing codes or standards, the requirements for audible signaling shall be permitted to be reduced or eliminated when visual signaling is provided in accordance with Section 18.5.

18.4.5.3 A system arranged to stop or reduce ambient noise shall comply with 18.4.5.3.1 through 18.4.5.3.3.

18.4.5.3.1 A system arranged to stop or reduce ambient noise shall be permitted to produce a sound level at least 10 dB above the reduced average ambient sound level or 5 dB above the maximum sound level having a duration of at least 60 seconds after reduction of the ambient noise level, whichever is greater, measured 5 ft (1.5 m) above the floor, using the A-weighted scale (dBA).

18.4.5.3.2 Visual notification appliances shall be installed in the affected areas in accordance with Sections 18.5 or 18.6.

18.4.5.3.3 Relays, circuits, or interfaces necessary to stop or reduce ambient noise shall meet the requirements of Chapters 10, 12, 21, and 23.

18.4.6 Sleeping Area Requirements.

18.4.6.1* Where audible appliances are installed to provide signals for sleeping areas, they shall have a sound level of at

least 15 dB above the average ambient sound level or 5 dB above the maximum sound level having a duration of at least 60 seconds or a sound level of at least 75 dBA, whichever is greater, measured at the pillow level in the area required to be served by the system using the A-weighted scale (dBA).

18.4.6.2 If any barrier, such as a door, curtain, or retractable partition, is located between the notification appliance and the pillow, the sound pressure level shall be measured with the barrier placed between the appliance and the pillow.

18.4.6.3* Audible appliances provided for the sleeping areas to awaken occupants shall produce a low frequency alarm signal that complies with the following:

- (1) The waveform shall have a fundamental frequency of 520 Hz ± 10 percent.
- (2)* The notification equipment shall be listed for producing the low frequency waveform.

18.4.7* Narrow Band Tone Signaling for Exceeding Masked Thresholds.

18.4.7.1 Masked Threshold Allowance. Audible tone signaling shall be permitted to comply with the masked threshold requirements in this subsection in lieu of the A-weighted signaling requirements in 18.4.4 and 18.4.5.

18.4.7.2* Calculation Method. The effective masked threshold shall be calculated in accordance with ISO 7731, *Ergonomics — Danger signals for public and work places — Auditory danger signals*.

18.4.7.3 Noise Data. Noise data for calculating the effective masked threshold shall be the peak value of noise lasting 60 seconds or more for each octave or one-third octave band.

18.4.7.4 Documentation. Analysis and design documentation shall be submitted to the authority having jurisdiction and shall contain the following information:

- (1) Frequency data for the ambient noise, including the date, time, and location where measurements were taken for existing environments, or projected data for environments not yet constructed

- (2) Frequency data of the audible notification appliance
- (3) Calculations of the effective masked threshold for each set of noise data
- (4) A statement of the sound pressure level that would be required by 18.4.4 or 18.4.5 if masked threshold signaling had not been done

18.4.7.5 Sound Pressure Level. For masked threshold signaling, the audible signal tone shall meet the requirements of either 18.4.7.5.1 or 18.4.7.5.2 but not for the reproduction of prerecorded, synthesized, or live messages.

18.4.7.5.1 The sound pressure level of the audible tone signal shall exceed the masked threshold in one or more octave bands by at least 10 dB in the octave band under consideration.

18.4.7.5.2 The sound pressure level of the audible tone signal shall exceed the masked threshold in one or more one-third octave bands by at least 13 dB in the one-third octave band under consideration.

18.4.8 Exit Marking Audible Notification Appliance Requirements.

18.4.8.1* Exit marking audible notification appliances shall meet or exceed the frequency and sound level settings and guidelines specified in the manufacturer's documented instructions.

18.4.8.2* In addition to 18.4.8.1, as a minimum, to ensure that exit marking audible notification appliance signals are clearly heard and produce the desired directional effects for 50 ft (15.24 m) within an unobstructed egress path, they shall meet the audibility requirements of 18.4.7 in at least one one-third octave band or one octave band within the effective frequency ranges of the interaural time difference (ITD), interaural level or intensity difference (ILD or IID), and anatomical transfer function or head-related transfer function (ATF or HRTF) localization cues.

18.4.8.3 The exit marking audible notification appliance signal shall penetrate both the ambient noise and the fire alarm signal.

18.4.8.4 Where required by the authority having jurisdiction governing laws, codes, or standards; or other parts of this Code, exit marking audible notification appliances shall be installed in accordance with the manufacturer's published instructions.

18.4.8.5* Where required by the authority having jurisdiction governing laws, codes, or standards; or other parts of this Code, exit marking audible notification shall be located at the entrance to all building exits and areas of refuge as defined by the applicable building or fire code.

18.4.8.6 Where exit marking audible notification appliances are utilized to mark areas of refuge, they shall provide an audible signal distinct from that used for other exits that do not have areas of refuge.

18.4.9 Location of Audible Notification Appliances for Building or Structure.

18.4.9.1 If ceiling heights allow, and unless otherwise permitted by 18.4.9.2 through 18.4.9.5, wall-mounted appliances shall have their tops above the finished floors at heights of not less than 90 in. (2.29 m) and below the finished ceilings at distances of not less than 6 in. (150 mm).

18.4.9.2 Ceiling-mounted or recessed appliances shall be permitted.

18.4.9.3 If combination audible/visual notification appliances are installed, the location of the installed appliance shall be determined by the requirements of 18.5.5.

18.4.9.4 Appliances that are an integral part of a smoke detector, carbon monoxide detector, smoke alarm, carbon monoxide alarm, or other initiating device shall be located in accordance with the requirements for that device.

18.4.9.5 Mounting heights other than required by 18.4.9.1 and 18.4.9.2 shall be permitted, provided that the sound pressure level requirements of 18.4.4 for public mode or 18.4.5 for private mode, or 18.4.6 for sleeping areas, based on the application, are met.

18.4.10 Location of Audible Notification Appliances for Wide-Area Signaling. Audible notification appliances for wide-area signaling shall be installed in accordance with the requirements of the authority having jurisdiction, approved design documents, and the manufacturer's installation instruction to achieve the required performance.

18.4.11* Voice Intelligibility. Within the acoustically distinguishable spaces (ADS) where voice intelligibility is required, voice communications systems shall reproduce prerecorded, synthesized, or live (e.g., microphone, telephone handset, and radio) messages with voice intelligibility.

18.4.11.1* ADSs shall be determined by the system designer during the planning and design of all emergency communications systems.

18.4.11.2 Each ADS shall be identified as requiring or not requiring voice intelligibility.

18.4.11.3* Unless specifically required by other governing laws, codes, or standards, or by other parts of this Code, intelligibility shall not be required in all ADSs.

18.4.11.4* Where required by the authority having jurisdiction governing laws, codes, or standards; or other parts of this Code, ADS assignments shall be submitted for review and approval.

18.4.11.5 Quantitative measurements shall not be required.

18.4.11.6 Quantitative measurements shall be permitted. (*See D.2.4.*)

18.5* Visual Characteristics — Public Mode.

18.5.1* Visual Signaling.

18.5.1.1 Public mode visual signaling shall meet the requirements of Section 18.5 using visual notification appliances.

18.5.1.2* The coverage area for visual notification shall be as required by other governing laws, codes, or standards.

18.5.1.3 Where other governing laws, codes, or standards require visual notification for all or part of an area or space, coverage shall only be required in occupiable areas as defined in 3.3.195.

18.5.2 Area of Coverage.

18.5.2.1 The designer of the visual notification system shall document the rooms and spaces that will have visual notification and those where visual notification will not be provided.

18.5.2.2* Unless otherwise specified or required by other sections of this Code, the required coverage area for visual notification shall be as required by other governing laws, codes, or standards.

18.5.2.3 Where required by the authority having jurisdiction, documentation of the effective intensity (cd) of the visual notification appliances for the area of coverage shall be submitted for review and approval.

18.5.3 Light, Color, and Pulse Characteristics.

18.5.3.1 The flash rate shall not exceed two flashes per second (2 Hz) nor be less than one flash every second (1 Hz) throughout the listed voltage range of the appliance.

18.5.3.2 The maximum light pulse duration shall be 20 milliseconds, except as permitted in 18.5.3.3.

18.5.3.3* Light pulse durations greater than 20 milliseconds, but not greater than 100 milliseconds, shall be permitted where the alerting capability of the visual notification appliance is demonstrated to be equal to or greater than visual notification appliances with a 20-millisecond pulse duration.

18.5.3.4 The pulse duration shall be defined as the time interval between initial and final points of 10 percent of maximum signal.

18.5.3.5* Visual notification appliances used for fire alarm signaling only or to signal the intent for complete evacuation shall be clear or nominal white and shall not exceed 1000 cd (effective intensity).

18.5.3.6 Visual notification appliances used to signal occupants to seek information or instructions shall be clear, nominal white, or other color as required by the emergency plan and the authority having jurisdiction for the area or building.

18.5.3.7* The visual synchronization requirements of this chapter shall not apply where the visual notification appliances located inside the building are viewed from outside of the building.

18.5.3.8 Visual notification appliances used for carbon monoxide signaling shall be as required by the emergency plan and the authority having jurisdiction for the area or building and shall not exceed 1000 cd (effective intensity).

18.5.4* Appliance Photometrics. The light output shall comply with the polar dispersion requirements for public mode signaling as described in UL 1638, *Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories*, or equivalent.

18.5.5 Appliance Location.

18.5.5.1* Wall-mounted appliances shall be mounted such that the entire lens is not less than 80 in. (2.03 m) and not greater than 96 in. (2.44 m) above the finished floor or at the mounting height specified using the performance-based alternative of 18.5.5.9.

18.5.5.2 Where low ceiling heights do not permit wall mounting at a minimum of 80 in. (2.03 m), wall mounted visual notification appliances shall be mounted within 6 in. (150 mm) of the ceiling.

18.5.5.3 Where low ceiling heights do not permit wall mounting at a minimum of 80 in. (2.03 m), the room size covered by a visual notification appliance of a given value shall be reduced

by twice the difference between the minimum mounting height of 80 in. (2.03 m) and the actual lower mounting height.

18.5.5.4* Visual notification appliances listed for mounting parallel to the floor shall be permitted to be located on the ceiling or suspended below the ceiling.

18.5.5.5* The minimum mounting height of a visual notification appliance listed for ceiling mounting shall be 80 in. (2.03 m) above the finished floor or the actual ceiling height, whichever is less.

18.5.5.6* Obstructions.

18.5.5.6.1 Ceiling mount visual notification appliances shall be mounted such that the effect of the appliance is not blocked by obstructions.

18.5.5.6.2 The effect of obstructions on distribution of light from wall-mounted appliances shall be considered when determining the location of appliances.

18.5.5.6.3 The effect of obstructions on the direct viewing of corridor appliances shall be considered when determining the location of appliances.

18.5.5.7* Spacing in Rooms.

18.5.5.7.1* Spacing shall be in accordance with either Table 18.5.5.7.1(a) and Figure 18.5.5.7.1 or Table 18.5.5.7.1(b).

18.5.5.7.2 Visual notification appliances shall be installed in accordance with Table 18.5.5.7.1(a) or Table 18.5.5.7.1(b) using one of the following:

- (1) A single visual notification appliance.
- (2)* Two groups of visual notification appliances, where visual notification appliances of each group are synchronized, in the same room or adjacent space within the field of view. This shall include synchronization of visual appliances operated by separate systems.
- (3) More than two visual notification appliances or groups of synchronized appliances in the same room or adjacent space within the field of view that flash in synchronization.

18.5.5.7.3 Room spacing in accordance with Table 18.5.5.7.1(a) and Figure 18.5.5.7.1 for wall-mounted appliances shall be based on locating the visual notification appliance at the halfway distance of the wall.

18.5.5.7.4 In square rooms with appliances not centered or in nonsquare rooms, the effective intensity (cd) from one wall-mounted visual notification appliance shall be determined by maximum room size dimensions obtained either by measuring the distance to the farthest wall or by doubling the distance to the farthest adjacent wall, whichever is greater, as required by Table 18.5.5.7.1(a) and Figure 18.5.5.7.1.

18.5.5.7.5 If a room configuration is not square, the square room size that allows the entire room to be encompassed or allows the room to be subdivided into multiple squares shall be used.

18.5.5.7.6* If ceiling heights exceed 30 ft (9.1 m), ceiling-mounted visual notification appliances shall be suspended at or below 30 ft (9.1 m) or at the mounting height determined using the performance-based alternative of 18.5.5.9, or wall-mounted visual notification appliances shall be installed in accordance with Table 18.5.5.7.1(a).

Table 18.5.5.7.1(a) Room Spacing for Wall-Mounted Visual Notification Appliances

Maximum Room Size		Minimum Required Light Output [Effective Intensity (cd)]	
		One Visual Notification Appliance per Room	Four Visual Notification Appliances per Room (One per Wall)
ft	m		
20 × 20	6.10 × 6.10	15	NA
28 × 28	8.53 × 8.53	30	NA
30 × 30	9.14 × 9.14	34	NA
40 × 40	12.2 × 12.2	60	15
45 × 45	13.7 × 13.7	75	19
50 × 50	15.2 × 15.2	94	30
54 × 54	16.5 × 16.5	110	30
55 × 55	16.8 × 16.8	115	30
60 × 60	18.3 × 18.3	135	30
63 × 63	19.2 × 19.2	150	37
68 × 68	20.7 × 20.7	177	43
70 × 70	21.3 × 21.3	184	60
80 × 80	24.4 × 24.4	240	60
90 × 90	27.4 × 27.4	304	95
100 × 100	30.5 × 30.5	375	95
110 × 110	33.5 × 33.5	455	135
120 × 120	36.6 × 36.6	540	135
130 × 130	39.6 × 39.6	635	185

NA: Not allowable.

Table 18.5.5.7.1(b) Room Spacing for Ceiling-Mounted Visual Notification Appliances

Maximum Room Size		Maximum Lens Height*		Minimum Required Light Output (Effective Intensity); One Visual Notification Appliance (cd)
		ft	m	
ft	m			
20 × 20	6.1 × 6.1	10	3.0	15
30 × 30	9.1 × 9.1	10	3.0	30
40 × 40	12.2 × 12.2	10	3.0	60
44 × 44	13.4 × 13.4	10	3.0	75
20 × 20	6.1 × 6.1	20	6.1	30
30 × 30	9.1 × 9.1	20	6.1	45
44 × 44	13.4 × 13.4	20	6.1	75
46 × 46	14.0 × 14.0	20	6.1	80
20 × 20	6.1 × 6.1	30	9.1	55
30 × 30	9.1 × 9.1	30	9.1	75
50 × 50	15.2 × 15.2	30	9.1	95
53 × 53	16.2 × 16.2	30	9.1	110
55 × 55	16.8 × 16.8	30	9.1	115
59 × 59	18.0 × 18.0	30	9.1	135
63 × 63	19.2 × 19.2	30	9.1	150
68 × 68	20.7 × 20.7	30	9.1	177
70 × 70	21.3 × 21.3	30	9.1	185

*This does not preclude mounting lens at lower heights.




FIGURE 18.5.5.7.1 Room Spacing for Wall-Mounted Visual Notification Appliances.

18.5.5.7.7 Table 18.5.5.7.1(b) shall be used if the ceiling-mounted visual notification appliance is at the center of the room.

18.5.5.7.8 If the ceiling-mounted visual notification appliance is not located at the center of the room, the effective intensity (cd) shall be determined by doubling the distance from the appliance to the farthest wall to obtain the maximum room size.

18.5.5.8* Spacing in Corridors.

18.5.5.8.1 The installation of visual notification appliances in corridors 20 ft (6.1 m) or less in width shall be in accordance with the requirements of either 18.5.5.7 or 18.5.5.8.

18.5.5.8.2 Paragraph 18.5.5.8 shall apply to corridors not exceeding 20 ft (6.1 m) in width.

18.5.5.8.3 In a corridor application, visual notification appliances shall be rated not less than 15 cd.

18.5.5.8.4 Corridors greater than 20 ft (6.1 m) wide shall comply with the spacing requirements for rooms in accordance with 18.5.5.7.

18.5.5.8.5* Except as permitted by 18.5.5.6 or 18.5.5.8, visual notification appliances shall be located not more than 15 ft (4.6 m) from the end of the corridor with a separation not greater than 100 ft (30.5 m) between appliances.

18.5.5.8.6 If there is an interruption of the concentrated viewing path, such as a fire door or an elevation change, the area shall be treated as a separate corridor.

18.5.5.8.7 In corridors where more than two visual notification appliances are in any field of view, they shall flash in synchronization.

18.5.5.8.8 Visual notification appliances in corridors shall be permitted to be mounted on the ceiling, end wall, or the side wall of the corridor.

18.5.5.9* Performance-Based Alternative.

18.5.5.9.1 Any design that provides a minimum of 0.0375 lumens/ft² (0.4036 lumens/m²) of illumination at any point within the covered area at all angles specified by the polar dispersion planes for wall- or ceiling-mounted public mode visual notification appliances in UL 1638, *Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories*, or equivalent, as calculated for the maximum distance from the nearest visual notification appliance, shall be permitted in lieu of the requirements of 18.5.5, excluding 18.5.5.10.

18.5.5.9.2 Documentation.

18.5.5.9.2.1 Documentation provided to the authority having jurisdiction shall include the inverse square law calculations using each of the vertical and horizontal polar distribution angles in UL 1638, *Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories*, or equivalent.

18.5.5.9.2.2 The inverse square law calculations shall account for the effects of polar distribution using one of the following:

- (1) The percentages from the applicable table(s) in UL 1638, *Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories*, or equivalent
- (2) The actual results of laboratory tests of the specific appliance to be used as recorded by the listing organization

18.5.5.10 Sleeping Areas.

18.5.5.10.1 Combination smoke detectors and visual notification appliances or combination smoke alarms and visual notification appliances shall be installed in accordance with the applicable requirements of Chapters 17, 18, 23, and 29.

18.5.5.10.2 Combination carbon monoxide detectors or alarms with visual notification appliances shall be located in accordance with the applicable requirements for the visual notification appliance and the applicable requirements for the carbon monoxide detector or alarm of Chapters 17, 18, 23, and 29.

18.5.5.10.3* Table 18.5.5.10.3 shall apply to the minimum required intensity of visual notification appliances in sleeping areas after establishing the mounting height.

18.5.5.10.4* For rooms with a linear dimension greater than 16 ft (4.9 m), the visual notification appliance shall be located within 16 ft (4.9 m) of the pillow.

18.5.6 Location of Visual Notification Appliances for Wide-Area Signaling. Visual notification appliances for wide-area signaling shall be installed in accordance with the requirements of the authority having jurisdiction, approved design

Table 18.5.5.10.3 Effective Intensity Requirements for Sleeping Area Visual Notification Appliances

Distance from Ceiling to Top of Lens		
in.	mm	Minimum Intensity (cd)
≥24	≥610	110
<24	<610	177

documents, and the manufacturer's published instructions to achieve the required performance.

18.6* Visual Characteristics — Private Mode. Visual notification appliances used in the private mode shall be of a sufficient quantity and intensity and located so as to meet the intent of the user and the authority having jurisdiction.

18.7 Supplementary Visual Signaling Method. A supplementary visual notification appliance shall be intended to augment an audible or visual signal.

18.7.1 A supplementary visual notification appliance shall comply with its marked rated performance.

18.7.2 Supplementary visual notification appliances shall be permitted to be located less than 80 in. (2.03 m) above the floor.

18.8 Textual Audible Appliances.

18.8.1 Loudspeaker Appliances.

18.8.1.1 Loudspeaker appliances shall comply with Section 18.4.

18.8.1.2* The sound pressure level, in dBA, of the tone produced by a signaling loudspeaker shall comply with all the requirements in 18.4.4 (public), 18.4.5 (private), or 18.4.6 (sleeping) for the intended mode or shall comply with the requirements of 18.4.7 (narrow band tone signaling).

18.8.2 Telephone Appliances. Telephone appliances shall be in accordance with Section 24.8.

18.9* Textual and Graphical Visual Appliances.

18.9.1 Application.

18.9.1.1 Textual and graphical visual appliances shall be permitted to be used to signal information about fire or other emergency conditions or to direct intended responses to those conditions.

18.9.1.2 This section does not apply to means of egress signs, room identification signs, and other signage that could be required by other governing laws, codes, or standards.

18.9.1.3 Textual visual appliance messages shall be permitted to be static, flashing, or scrolling.

18.9.2 Location.

18.9.2.1 Private Mode. Unless otherwise permitted or required by other governing laws, codes, or standards, or by other parts of this Code or by the authority having jurisdiction, all textual and graphical visual notification appliances in the private mode shall be located in rooms that are accessible only to those persons directly concerned with the implementation and direction of emergency response in the areas protected by the system.

18.9.2.2 Public Mode. Textual and graphical visual notification appliances used in the public mode shall be located to ensure visibility to the occupants of the protected area or to the intended recipients.

18.9.2.3 Mounting. Desktop and surface-mounted textual and graphical visual notification appliances shall be permitted.

18.9.3 Performance. The information produced by textual and graphical visual appliances shall be clear and legible at the intended viewing distance.

18.9.4* Character and Symbol Requirements and Viewing Distance.

18.9.4.1 This section applies to visual characters and graphic elements and does not address raised characters or braille that could be required by other governing laws, codes, or standards.

18.9.4.2* Characters and symbols shall contrast with their background using either positive contrast (light on a dark background) or negative contrast (dark on a light background).

18.9.4.3 Characters and symbols and their background shall have a nonglare finish.

18.9.4.4* Characters shall be permitted to be uppercase or lowercase, or a combination of both.

18.9.4.5 Characters shall be conventional in form and not italic, oblique, script, highly decorative, or of other unusual form and shall use sans serif fonts.

18.9.4.6 Characters shall be selected from fonts where the width of the uppercase letter "O" is 55 percent minimum and 110 percent maximum of the height of the uppercase letter "I".

18.9.4.7* Character and symbol height for appliances other than desktop monitors or displays shall meet all of the following criteria:

- (1) Minimum character height shall comply with Table 18.9.4.7.
- (2) Viewing distance shall be measured as the horizontal distance between the character and an obstruction preventing further approach towards the appliance.
- (3) Character height shall be based on the uppercase letter "I".

18.9.4.8* All characters and symbols displayed by textual and graphical visual notification appliances shall be a minimum of 40 in. (1.02 m) above the ground or finished floor.

18.9.4.9 Stroke thickness of the uppercase letter "I" shall be minimum 10 percent and maximum 30 percent of the height of the character.

18.9.4.10 Character spacing shall be measured between the two closest points of adjacent characters, excluding word spaces. Spacing between individual characters shall be minimum 10 percent and maximum 35 percent of character height.

18.9.4.11 Spacing between the baselines of separate lines of characters within a message shall be 135 percent minimum and 170 percent maximum of the character height.

18.10 Tactile Appliances.

18.10.1 Application. Tactile appliances shall be permitted if used in addition to audible and/or visual notification appliances.

18.10.2* Performance. Tactile appliances shall meet the performance requirements of UL 1971, *Signaling Devices for the Hearing Impaired*, or equivalent.

Table 18.9.4.7 Visual Character and Graphic Symbol Height Based on Height and Distance

Horizontal Viewing Distance		Minimum Character or Symbol Height for Installed Elevation					
		At 40 in. to 70 in. (1.0 m to 1.8 m) Above the Floor		At Greater Than 70 in. to 120 in. (1.8 m to 3.1 m) Above the Floor		At Greater Than 120 in. (3.0 m) Above the Floor	
		in.	mm	in.	mm	in.	mm
1	0.3	$\frac{3}{8}$	16	2	51	3	76
2	0.6	$\frac{3}{8}$	16	2	51	3	76
3	0.9	$\frac{3}{8}$	16	2	51	3	76
4	1.2	$\frac{3}{8}$	16	2	51	3	76
5	1.5	$\frac{3}{8}$	16	2	51	3	76
6	1.8	$\frac{3}{8}$	16	2	51	3	76
7	2.1	$\frac{3}{4}$	19	2	51	3	76
8	2.4	$\frac{3}{8}$	22	2	51	3	76
9	2.7	1	25	2	51	3	76
10	3	$1\frac{1}{8}$	29	2	51	3	76
11	3.4	$1\frac{1}{4}$	32	2	51	3	76
12	3.7	$1\frac{3}{8}$	35	2	51	3	76
13	4	$1\frac{1}{2}$	38	2	51	3	76
14	4.3	$1\frac{3}{8}$	41	2	51	3	76
15	4.6	$1\frac{3}{4}$	44	2	51	3	76
16	4.9	$1\frac{7}{8}$	48	$2\frac{1}{8}$	54	3	76
17	5.2	2	51	$2\frac{1}{4}$	57	3	76
18	5.5	$2\frac{1}{8}$	54	$2\frac{3}{8}$	60	3	76
19	5.8	$2\frac{1}{4}$	57	$2\frac{1}{2}$	64	3	76
20	6.1	$2\frac{3}{8}$	60	$2\frac{5}{8}$	67	3	76
21	6.4	$2\frac{1}{2}$	64	$2\frac{3}{4}$	70	3	76
22	6.7	$2\frac{5}{8}$	67	$2\frac{7}{8}$	73	$3\frac{1}{8}$	79
23	7	$2\frac{3}{4}$	70	3	76	$3\frac{1}{4}$	83
24	7.3	$2\frac{7}{8}$	73	$3\frac{1}{8}$	79	$3\frac{3}{8}$	86
25	7.6	3	76	$3\frac{1}{4}$	83	$3\frac{1}{2}$	89
>25	>7.6	$3 + h^*$	$76 + h^*$	$3\frac{1}{4} + h^*$	$83 + h^*$	$3\frac{1}{2} + h^*$	$89 + h^*$

*For each foot of horizontal viewing distance greater than 25 ft (7.6 m), add $\frac{1}{8}$ in. (3 mm) to the character or symbol height.

Chapter 19 Reserved

Chapter 20 Reserved

Chapter 21 Emergency Control Function Interfaces

21.1* Application. The provisions of Chapter 21 shall cover the minimum requirements and methods for emergency control function interfaces with fire alarm or signaling systems in accordance with this chapter.

21.1.1 The requirements of Chapters 7, 10, 11, 12, 14, 17, 18, 23, 24, and 26 shall apply, unless otherwise noted in this chapter.

21.1.2 The requirements of this chapter shall not apply to Chapter 29 unless otherwise stated.

21.2 General.

21.2.1* Emergency control functions shall be permitted to be performed automatically.

21.2.2 The performance of automatic emergency control functions shall not interfere with power for lighting or for operating elevators.

21.2.3 The performance of automatic emergency control functions shall not preclude the combination of fire alarm services with other services requiring monitoring of operations.

21.2.4* Emergency control function interface devices shall be located within 3 ft (0.9 m) of the component controlling the emergency control function where the control circuit is not configured as a Class D circuit.

21.2.5 The emergency control function interface device shall function within the voltage and current limitations of the fire alarm control unit.

21.2.6 The installation wiring between the fire alarm control unit and the emergency control function interface device shall be Class A, Class B, Class D, Class N, or Class X in accordance with Chapter 12.

21.2.7 Emergency control functions shall not interfere with other operations of the fire alarm system.

21.2.8 The method(s) of interconnection between the fire alarm system and emergency control function interface device shall be monitored for integrity in accordance with Section 12.6.

21.2.9 The method(s) of interconnection between the emergency control function interface device and the component controlling the emergency control function shall comply with the applicable provisions of *NFPA 70*.

21.2.10 The method(s) of interconnection between the emergency control function interface device and the component controlling the emergency control function shall be achieved by one of the following recognized means:

- (1) Electrical contacts listed for the connected load
- (2) Data communications over a signaling line circuit(s) dedicated to the fire alarm or shared with other premises operating systems
- (3) Other listed methods

21.2.11 If a fire alarm system is a component of a life safety network and it communicates data to other systems providing life safety functions, or it receives data from such systems, the following shall apply:

- (1) The path used for communicating data shall be monitored for integrity. This shall include monitoring the physical communications media and the ability to maintain intelligible communications.
- (2) Data received from the network shall not affect the operation of the fire alarm system in any way other than to display the status of life safety network components.
- (3) Where non-fire alarm systems are interconnected to the fire alarm system using a network or other digital communications technique, a signal (e.g., heartbeat, poll, ping, query) shall be generated between the fire alarm system and the non-fire alarm system. Failure of the fire alarm system to receive confirmation of the transmission shall cause a trouble signal to indicate within 200 seconds.

21.3* Elevator Phase I Emergency Recall Operation.

21.3.1 All fire alarm initiating devices used to initiate elevator Phase I Emergency Recall Operation shall be connected to the required building fire alarm system.

21.3.2* In facilities without a required building fire alarm system, fire alarm initiating devices used to initiate elevator Phase I Emergency Recall Operation shall be connected to either a nonrequired building fire alarm system or a dedicated function fire alarm control unit that shall be designated as "elevator recall control and supervisory control unit," permanently identified on the dedicated function fire alarm control unit and on the record drawings.

21.3.3 Phase I Emergency Recall Operation Initiation.

21.3.3.1 Unless otherwise permitted by 21.3.3.2 or required by the authority having jurisdiction, only the elevator lobby, elevator hoistway, elevator machine room, elevator machinery space, elevator control room, and elevator control space smoke detectors or other automatic fire detection as permitted by 21.3.10 shall be used to initiate Elevator Phase I Emergency Recall Operation.

21.3.3.2 A waterflow switch shall be permitted to initiate Elevator Phase I Emergency Recall Operation upon activation of a sprinkler installed at the bottom of the elevator hoistway (the elevator pit), provided the waterflow switch and pit sprinkler are installed on a separately valved sprinkler line dedicated solely for protecting the elevator pit.

21.3.4 Each fire alarm initiating device used to initiate elevator Phase I Emergency Recall Operation shall be capable of initiating the elevator recall function when all other devices on the same initiating device circuit have been manually or automatically placed in the alarm condition.

21.3.5* Elevator Lobby Detector Location.

21.3.5.1 A lobby smoke detector shall be located on the ceiling within 21 ft (6.4 m) of the centerline of each elevator door within the elevator bank under control of the detector.

21.3.5.2 For lobby ceiling configurations exceeding 15 ft (4.6 m) in height or that are other than flat and smooth, detector locations shall be determined in accordance with Chapter 17.

21.3.6 Fire Detection in Unsprinklered Elevator Hoistways.

21.3.6.1 Smoke detectors or other automatic fire detection as permitted in 21.3.10 shall not be installed in unsprinklered elevator hoistways unless they are required by ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*, to initiate Elevator Phase I Emergency Recall Operation as specified in 21.3.14.1(2) and 21.3.14.2(2) for either of the following:

- (1) Hoistway machinery spaces containing a motor controller or driving machine
- (2) Control spaces located in the hoistway

21.3.6.2 Smoke detectors or other automatic fire detection as permitted in 21.3.10 shall be permitted to be installed in unsprinklered elevator hoistways if required by other governing codes or standards for the actuation of the elevator hoistway smoke relief equipment.

21.3.6.3 Detectors installed in accordance with 21.3.6.2 shall initiate Elevator Phase I Emergency Recall Operation as specified in 21.3.14.1(2) and 21.3.14.2(2).

21.3.7* Fire Alarm Initiating Device(s) Inside Elevator Hoistways. Fire alarm initiating device(s) required to be installed inside an elevator hoistway by other sections of this Code or by other governing laws, codes, or standards shall be required to be accessible for service, testing, and maintenance from outside the elevator hoistway.

21.3.8* When sprinklers are required in elevator hoistways by other codes and standards, fire alarm initiating devices shall be installed to initiate Elevator Phase I Emergency Recall Operation in accordance with ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*, and the following shall apply:

- (1) Where sprinklers are located at the top of the hoistway, associated fire detection device(s) shall be located at the top of the hoistway.
- (2) Where sprinklers are located at the bottom of the hoistway (the pit), associated fire detection device(s) shall be installed in the pit in accordance with Chapter 17.
- (3) Outputs from the fire alarm system to the elevator system shall comply with 21.3.14.
- (4) The fire alarm initiating device(s) shall be installed in accordance with Chapter 17.

21.3.9* Smoke detectors shall not be installed in elevator hoistways to initiate Elevator Phase I Emergency Recall Operation unless listed for the environmental conditions.

21.3.10* If ambient conditions prohibit installation of automatic smoke detection used to initiate elevator Phase I Emergency Recall Operation, other automatic fire detection initiating devices shall be permitted.

21.3.11 When actuated, any fire alarm initiating device that is used to initiate elevator Phase I Emergency Recall Operation

shall be annunciated at the building fire alarm control unit or at the fire alarm control unit described in 21.3.2.

21.3.12 Actuation of the elevator hoistway, elevator machine room, elevator machinery space, elevator control space, or elevator control room smoke detectors or other automatic fire detection as permitted by 21.3.10 shall cause separate and distinct visible annunciation at the building fire alarm control unit or at the fire alarm control unit described in 21.3.2.

21.3.13 Where approved by the authority having jurisdiction, the detectors used to initiate Elevator Phase I Emergency Recall Operation shall be permitted to initiate a supervisory signal in lieu of an alarm signal.

21.3.14 The following three separate outputs from the building fire alarm control unit or the fire alarm control unit described in 21.3.2 to the elevator system shall be provided to implement Elevator Phase I Emergency Recall Operation in accordance with Section 2.27 of ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*, as required in 21.3.14.1 and 21.3.14.2:

- (1) Designated level associated output
- (2) Alternate level associated output
- (3) Elevator machine room, elevator machinery space, elevator control space, or elevator control room associated output

21.3.14.1* Elevator Phase I Emergency Recall Operation to Designated Level. For each elevator or group of elevators operating in a group automatic operation, an output shall be provided from the fire alarm system to the elevator system in response to the following:

- (1) Activation of smoke detector(s) or other automatic fire detection as permitted by 21.3.10 located at any associated elevator(s) lobby other than the lobby at the designated level
- (2) Activation of smoke detector(s) or other automatic fire detection as permitted by 21.3.10 located at any associated elevator(s) machine room, elevator machinery space containing a motor controller or driving machine, elevator control space, or elevator control room, except where such rooms or spaces are located at the designated level
- (3) Activation of smoke detector(s) or other automatic fire detection as permitted by 21.3.10 located at any associated elevator(s) hoistway when sprinklers are located in those hoistways, unless otherwise specified in 21.3.14.2(3)

21.3.14.2* Elevator Phase I Emergency Recall Operation to Alternate Level. For each elevator or group of elevators operating in a group automatic operation, an output shall be provided from the fire alarm system to the elevator system in response to the following:

- (1) Activation of smoke detector(s), or other automatic fire detection as permitted by 21.3.10, located at the designated level lobby served by the elevator(s)
- (2) Activation of smoke detector(s), or other automatic fire detection as permitted by 21.3.10, located in the elevator machine room, elevator machinery space containing a motor controller or driving machine, elevator control space, or elevator control room serving the elevator(s) if such rooms or spaces are located at the designated level
- (3)* Activation of the fire alarm initiating device(s) identified in 21.3.14.1(3) if they are installed at or below the lowest

level of recall in the elevator hoistway and the alternate level is located above the designated level

21.4 Elevator Power Shutdown.

21.4.1* When heat detector(s) are used to actuate the disconnecting means described in 2.8 of ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*, to disconnect the main line power supply to the affected elevator and any other power supplies used to move the elevator, upon or prior to the activation of sprinkler(s), the detector(s) shall have both a lower temperature rating and a lower response time index (RTI) as compared to the sprinkler(s).

21.4.2* The heat detector(s) specified in 21.4.1 shall be placed within 24 in. (610 mm) of each sprinkler and be installed in accordance with the requirements of Chapter 17.

21.4.2.1 Engineering methods, such as those specified in Annex B, shall be permitted to be used to select and place heat detectors to ensure response prior to any sprinkler operation under a variety of fire growth rate scenarios.

21.4.3* If pressure or waterflow switches are used to actuate the disconnecting means specified in 21.4.1, the use of devices with time-delay capability shall not be permitted.

21.4.4* Control circuit(s) of the disconnecting means specified in 21.4.1 shall be monitored for the presence of operating voltage.

21.4.5 Loss of voltage to the control circuit(s) in 21.4.4 shall cause a supervisory signal to be indicated at the building fire alarm control unit or at the control unit specified in or in 21.3.2.

21.4.6 The devices specified in 21.4.2 and 21.4.3 shall be monitored for integrity by the fire alarm control unit specified in 21.3.1 or 21.3.2.

21.5* Fire Service Access Elevators. Where one or more elevators are specifically designated and marked as fire service access elevators, temperature and presence of smoke in elevator lobbies, machine rooms, control rooms, machinery spaces, or control spaces shall be continuously monitored and displayed on a building fire alarm system annunciator(s), or other annunciator(s) as approved by the authority having jurisdiction.

21.6* Occupant Evacuation Elevators (OEE).

21.6.1 Elevator Status. Where elevators are to be used for occupant self-evacuation during fires and non-fire emergencies, they shall comply with Sections 21.5 and 21.6.

21.6.2 Occupant Evacuation Operation (OEO). Outputs from the fire alarm system to the elevator system shall be provided to implement elevator occupant evacuation operation in accordance with Section 2.27 of ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*, as required in 21.6.2.1 through 21.6.2.5.

21.6.2.1 Applicability. OEO shall only be initiated upon an automatic or manual signal from the fire alarm system to the elevator system.

21.6.2.1.1* OEO shall apply separately to each individual elevator and to elevators having *group automatic operation* or designated as an *elevator group* or *group of elevators*.

21.6.2.1.2* OEO shall function per 21.6.2.1.1 only prior to Elevator Phase I Emergency Recall Operation.

21.6.2.2 Partial Building Evacuation. Where an elevator or group of elevators is designated for use by occupants for self-evacuation, the provisions of 21.6.2.3 through 21.6.2.6 shall apply for partial building evacuation.

21.6.2.3 Initiation. OEO shall be initiated by either manual means from the Fire Command Center or Emergency Command Center in accordance with 21.6.2.4 or by actuation of an automatic fire alarm initiating device in accordance with 21.6.2.3.1.

21.6.2.3.1* An active automatic fire alarm initiating device that does not initiate Elevator Phase I Emergency Recall Operation shall cause the fire alarm system to provide a signal to the elevator system indicating the floor of an active alarm, except as prohibited by 21.6.2.3.6.

21.6.2.3.2* The floors to be evacuated shall be a contiguous block of floors designated as “the elevator evacuation zone” consisting of at least the floor with an active alarm, two floors above the floor with the active alarm, and two floors below the floor with the active alarm.

21.6.2.3.3* When the floor designated as the elevator discharge level falls within the elevator evacuation zone, it is not to be evacuated by the elevator(s), and the fire alarm system shall initiate a voice message to instruct the occupants on that level to exit the building.

21.6.2.3.4 If activation of an automatic fire alarm initiating device that does not initiate Elevator Phase I Emergency Recall Operation occurs on an additional floor(s), including the elevator discharge level at any time while OEO is in effect, the elevator evacuation zone shall be expanded to include all floors with an active alarm, all floors between the highest and lowest floor with an active alarm, plus two floors above the highest floor with an active alarm and two floors below the lowest floor with an active alarm.

21.6.2.3.5 If the first active alarm is on the elevator discharge level, automatic initiation of OEO shall not be permitted for all elevators having that same elevator discharge level.

21.6.2.3.6* When the first active alarm is on an elevator discharge level, the fire alarm system shall not send a signal to the elevator system for that alarm or any other active alarm that does not initiate Elevator Phase I Emergency Recall Operation for that group of elevators.

21.6.2.4* Manual Floor Selection.

21.6.2.4.1 A means shall be furnished at the Fire Command Center or the Emergency Command Center to provide for the manual selection of each floor in the building.

21.6.2.4.2 The manual floor selection shall be actuated only by authorized or emergency personnel.

21.6.2.4.3 When OEO is not yet in effect and a manual floor selection is made to initiate OEO, a signal shall be sent to the elevator system simulating an active alarm for that floor.

21.6.2.4.4 When OEO is in effect and a manual floor selection is made, the elevator evacuation zone shall be permitted by the authority having jurisdiction to be expanded as described in 21.6.2.3.4 or by adding that floor to the evacuation zone.

21.6.2.4.5 Each manual selection means shall have the capability to cancel a manually actuated output signal.

21.6.2.5* Fire Alarm Output Signals to Elevator System.

21.6.2.5.1 Output from the fire alarm system to the elevator system shall identify each floor with an actuated automatic fire alarm initiating device.

21.6.2.5.2 Output from the fire alarm system to the elevator system shall include the following:

- (1) Floor(s) with any actuated fire alarm initiating device(s)
- (2) Floor(s) selected by manual means from the Fire Command Center or the Emergency Command Center

21.6.2.5.3 The identified floor(s) and all other associated floors comprising the elevator evacuation zone shall be displayed on the building fire alarm system annunciator or on a listed non-fire alarm system annunciator or other annunciator as approved by the authority having jurisdiction.

21.6.2.5.4 The annunciator referenced in 21.6.2.5.3 shall be located at the Fire Command Center or Emergency Command Center.

21.6.2.6* Occupant Notification. The in-building emergency voice/alarm communications system shall transmit messages coordinated with the elevator system’s variable message signs in all elevator lobbies.

21.6.2.6.1 Automatic voice evacuation messages shall be transmitted to the elevator evacuation zone floors to indicate the need to evacuate and that elevator service is available.

21.6.2.6.2 Automatic voice messages shall be transmitted to the floors that are not in the elevator evacuation zone and are served by the group, to inform occupants that elevator service is not available.

21.6.2.6.3* Automatic voice messages shall be transmitted to the floors in the elevator evacuation zone when no elevators serving that elevator evacuation zone are available.

21.6.2.6.4* Where required by other governing laws, codes, or standards, the emergency voice/alarm communications system’s loudspeaker(s) located in each OEE lobby shall be connected to a separate notification zone for manual paging only.

21.6.2.6.4.1 Individual paging zones per each OEE lobby on each floor or a grouped paging zone for all OEE lobbies on a floor shall be permitted if approved.

21.6.2.6.4.2 A vertical paging zone for each elevator group shall be permitted if approved.

21.6.2.6.5 Visual notification appliances (strobes) shall comply with 24.5.17.3(1), 24.5.17.3(2), and 24.5.17.3(3).

21.6.2.7 Total Evacuation. A means to initiate total building evacuation labeled “ELEVATOR TOTAL BUILDING EVACUATION” shall be provided at the Fire Command Center or at the Emergency Command Center.

21.6.2.7.1 When the total building evacuation means is actuated, the fire alarm system shall provide a signal to the elevator system indicating that all floors in the building are to be evacuated.

21.6.2.7.2 When the total building evacuation means is actuated, the in-building fire emergency voice/alarm communications system shall transmit an evacuation message throughout the building.

21.6.2.8* Suspension of OEO for an Individual Elevator or Group of Elevators. When OEO has been suspended, the in-building fire emergency voice/alarm communications system shall transmit messages coordinated with the elevator system's variable message signs in compliance with 21.6.2.6.

21.6.2.9* Partial Termination of OEO.

21.6.2.9.1 OEO shall be terminated for a specific group of elevator(s) when the signal(s) provided in 21.3.14.1 and 21.3.14.2 associated with this group of elevator(s) has initiated Elevator Phase I Emergency Recall Operation for this group of elevator(s).

21.6.2.9.2 When OEO has been partially terminated, the in-building fire emergency voice/alarm communications system shall transmit messages coordinated with the elevator system's variable message signs in compliance with 21.6.2.6.

21.6.2.10* Total Termination of OEO. OEO shall be terminated for all elevators in the building upon reset of the fire alarm system.

21.7 Heating, Ventilating and Air-Conditioning (HVAC) Systems.

21.7.1 The provisions of Section 21.7 shall apply to the basic method by which a fire alarm system interfaces with the heating, ventilating, and air-conditioning (HVAC) systems.

21.7.2* If connected to the fire alarm system serving the protected premises, all detection devices used to cause the operation of HVAC systems, smoke dampers, fire dampers, fan control, smoke doors, or fire doors shall be monitored for integrity in accordance with Section 12.6 and 23.8.5.3.

21.7.3 Connections between fire alarm systems and the HVAC system for the purpose of monitoring and control shall operate and be monitored in accordance with applicable NFPA standards.

21.7.4 Smoke detectors mounted in the air ducts of HVAC systems shall initiate a supervisory signal.

21.7.4.1 Smoke detectors mounted in the air ducts of HVAC systems in a fire alarm system without a constantly attended location or supervising station shall be permitted to initiate an alarm signal.

21.7.4.2 Smoke detectors mounted in the air ducts of HVAC systems shall be permitted to initiate an alarm signal where required by other governing laws, codes, or standards.

21.7.5 If the fire alarm control unit actuates the HVAC system for the purpose of smoke control, the automatic alarm-initiating zones shall be coordinated with the smoke control zones they actuate.

21.7.6 If carbon monoxide detection or a dedicated carbon monoxide system initiates a ventilation response, a smoke control response of the fire alarm system shall take precedence over the response of the carbon monoxide detectors during a fire alarm condition.

21.7.7 Where interconnected as a combination system, a fire fighter's smoke control station (FSCS) shall be provided to perform manual control over the automatic operation of the system's smoke control strategy.

21.7.8 Where interconnected as a combination system, the smoke control system programming shall be designed such that

normal HVAC operation or changes do not prevent the intended performance of the smoke control strategy.

21.8 High Volume Low Speed (HVLS) Fans. Where required by NFPA 13, all HVLS fans shall be interlocked to shut down upon actuation of a sprinkler waterflow switch that indicates waterflow in the area served by the fans.

21.9 Door and Shutter Release.

21.9.1 The provisions of Section 21.9 shall apply to the methods of connection of door and shutter hold-open release devices and to integral door and shutter hold-open release, closer, and smoke detection devices.

21.9.2 Other than smoke detectors used only for door and shutter release and not for open area protection, all detection devices used for door and shutter hold-open release service shall be monitored for integrity in accordance with Section 12.6.

21.9.3 Unless installed as Class D circuits in accordance with 12.3.4, all door and shutter hold-open release and integral door and shutter release and closure devices used for release service shall be monitored for integrity in accordance with Section 12.6.

21.9.4 Magnetic door and shutter holders that allow doors to close upon loss of operating power shall not be required to have a secondary power source.

21.10 Electrically Locked Doors.

21.10.1* Electrically locked doors in a required means of egress shall unlock in the direction of egress where required by other laws, codes, and governing standards.

21.10.2 For all means of egress doors connected in accordance with 21.10.1 where secondary power supplies of fire alarm control units are used, they shall comply with 10.6.7.

21.10.3* Secondary power supplies of fire alarm control units shall not be utilized to maintain means of egress doors in the locked condition unless the fire alarm control unit is arranged with circuitry and sufficient secondary power to ensure that the means of egress doors will unlock within 10 minutes of loss of primary power.

21.10.4 Locks powered by independent power supplies dedicated to lock power and access control functions, and that unlock upon loss of power, shall not be required to comply with 21.10.2.

21.10.5 If means of egress doors are unlocked by the fire alarm system, the unlocking function shall occur prior to, or concurrent with, activation of any public-mode notification appliances in the area(s) served by the normally locked means of egress doors.

21.10.6 All doors that are required to be unlocked by the fire alarm system in accordance with 21.10.1 shall remain unlocked until the fire alarm condition is manually reset.

21.11* Exit Marking Audible Notification Systems.

21.11.1 Where required by other governing laws, codes, standards, or the authority having jurisdiction, exit marking audible notification appliances shall be actuated by the building fire alarm system.

21.11.2 Exit marking systems shall meet the requirements of Chapter 18.

Chapter 22 Reserved

Chapter 23 Protected Premises Alarm and Signaling Systems

23.1 Application.

23.1.1* The application, installation, and performance of alarm and signaling systems within protected premises shall comply with the requirements of this chapter.

23.1.2 The requirements of Chapters 7, 10, 11, 12, 14, 17, 18, 21, 24, and 26 shall apply unless otherwise noted in this chapter.

23.1.3 The requirements of this chapter shall not apply to Chapter 29 unless otherwise noted.

23.2 General.

23.2.1* Purpose. The systems covered in Chapter 23 shall be for the protection of life or property, or both, by indicating the existence of heat, fire, smoke, carbon monoxide, or other emergencies impacting the protected premises.

23.2.2 Software and Firmware Control.

23.2.2.1 A record of installed software and firmware version numbers shall be prepared and maintained in accordance with Sections 7.5 and 7.7.

23.2.2.1.1* Software and firmware within the alarm and signaling system that interfaces to other required software or firmware shall be functionally compatible.

23.2.2.1.2* The compatible software or firmware versions shall be documented at the initial acceptance test and at any reacceptance tests.

23.2.2.2* All software and firmware shall be protected from unauthorized changes.

23.2.2.3 All changes shall be tested in accordance with 14.4.2.

23.2.3 Separate Systems. The requirements of this chapter shall not preclude the use of separate fire, carbon monoxide, or other life safety systems provided the systems do not generate simultaneous conflicting notification to the building occupants or conflicting actuation of safety functions.

23.3 System Features. The features required for a protected premises fire alarm system shall be documented as a part of the system design and shall be determined in accordance with 23.3.1 through 23.3.3.

23.3.1* Required Systems. Features for required systems shall be based on the requirements of other applicable codes or statutes that have been adopted by the enforcing jurisdiction.

23.3.2* Nonrequired (Voluntary) Systems and Components. The features for a nonrequired system shall be established by the system designer on the basis of the goals and objectives intended by the system owner.

23.3.2.1 Nonrequired protected premises systems and components shall meet the requirements of this Code.

23.3.2.2 Nonrequired systems and components shall be identified on the record drawings required in 7.2.1(15).

23.3.3 Required Features.

23.3.3.1* Building Alarm and Signaling Systems. Protected premises systems that serve the alarm and signaling needs of a building or buildings shall include one or more of the following systems or functions:

- (1) Manual fire alarm signal initiation
- (2) Automatic fire alarm and supervisory signal initiation
- (3) Monitoring of abnormal conditions in fire suppression systems
- (4) Actuation of fire suppression systems
- (5) Actuation of emergency control functions
- (6) Actuation of fire alarm notification appliances
- (7) In-building fire emergency voice/alarm communications
- (8) Automatic carbon monoxide alarm and supervisory signal initiation
- (9) Actuation of carbon monoxide notification appliances
- (10) Guard's tour supervisory service
- (11) Process monitoring supervisory systems
- (12) Actuation of off-premises signals
- (13) Combination systems

23.3.3.2* Dedicated Function Fire Alarm Systems.

23.3.3.2.1 In facilities without a building fire alarm system, a dedicated function fire alarm system shall be permitted and shall not be required to include other functions or features of a building fire alarm system.

23.3.3.2.2 Where a dedicated function fire alarm system exists and a building fire alarm system is subsequently installed, the systems shall be interconnected and comply with 23.8.2.

23.4 System Performance and Integrity.

23.4.1 Purpose. Section 23.4 provides information that shall be used in the design and installation of protected premises fire alarm systems for the protection of life and property.

23.4.2 Circuit Designations. Initiating device circuits, notification appliance circuits, and signaling line circuits shall be designated by class, depending on the circuit's capability to continue to operate during specified fault conditions as indicated in Sections 23.5 through 23.7.

23.4.2.1 Specified fault conditions shall result in the annunciation of a trouble signal at the protected premises within 200 seconds as required in Section 12.6.

23.4.2.2* Where the power to a device is supplied over a separate circuit from the signaling line circuit or initiating device circuit, the operation of the power circuit shall meet the performance requirements of the initiating device circuit or signaling line circuit, unless different performance requirements are established in accordance with the evaluation in 23.4.3 and approved by the authority having jurisdiction.

23.4.3 Pathway Classification.

23.4.3.1 The class of pathways shall be determined from an evaluation based on the path performance as required by governing laws, codes, standards, and a site-specific engineering analysis.

23.4.3.2 When determining the integrity and reliability of the interconnecting signaling paths (circuits) installed within the

protected premises, the following influences shall be considered:

- (1) Transmission media used
- (2) Length of the circuit conductors
- (3) Total building area covered by, and the quantity of initiating devices and notification appliances connected to, a single circuit
- (4) Effect of a fault in the fire alarm system that would hinder the performance objectives of the system that protects the occupants, mission, and property of the protected premises
- (5) Nature of hazards present within the protected premises
- (6) Functional requirements of the system necessary to provide the level of protection required for the system
- (7) Size and nature of the population of the protected premises

23.4.3.3 Results of the evaluation required by 23.4.3.1 shall be included with the documentation required by 7.3.9.

23.5 Performance of Initiating Device Circuits (IDCs). The assignment of class designations to initiating device circuits shall be based on their performance capabilities under abnormal (fault) conditions in accordance with the requirements for Class A or Class B pathways specified in Chapter 12.

23.6 Performance of Signaling Line Circuits (SLCs). The assignment of class designations to signaling line circuits shall be based on their performance capabilities under abnormal (fault) conditions in accordance with the requirements for Class A, Class B, Class N, or Class X pathways specified in Chapter 12.

23.6.1* SLC Zones. A single fault on a pathway connected to the addressable devices shall not cause the loss of the devices in more than one zone.

23.6.1.1 For the purpose of this section, each floor of the building shall be considered a separate zone.

23.6.1.2 For the purpose of this section, if a floor of the building is subdivided into multiple zones by fire or smoke barriers and the fire plan for the protected premises allows relocation of occupants from the zone of origin to another zone on the same floor, each zone on the floor shall be considered a separate zone.

23.6.1.3* The requirements in 23.6.1 shall not apply to the following:

- (1) Circuits between enclosures containing transponders and control units regardless of the number of initiating devices, notification appliances, or control relays that might be connected to those control units
- (2) Circuits connecting short-circuit fault isolation modules to enclosures containing transponders and control units where the conductors are installed in metallic raceway or equivalently protected against mechanical injury and where the circuit does not exceed 3 ft (0.9 m) in length
- (3)* Alterations or modifications made to an existing SLC not required to comply with 23.6.1 when originally installed

23.6.1.4 The loss of more than one zone shall be permitted on a documented performance-based design approach.

23.6.1.5* Performance-based designs submitted to the authority having jurisdiction for review and approval shall include documentation, in an approved format, of each performance

objective and applicable scenario, together with technical substantiation used in establishing the proposed zone performance.

23.6.2* Class N Devices. Unless permitted in 23.6.2.1 or 23.6.2.2, no area or zone shall be served solely by a single device where Class N pathways are deployed, such that a single device failure resulting from a multiple ground-fault pathway failure would render an area or zone incapable of initiating input signals or receiving output signals.

23.6.2.1 Where a risk analysis shows that only one device is required and where acceptable to the authority having jurisdiction, the requirements of 23.6.2 shall not apply.

23.6.2.2 Multiple devices shall not be required in areas served by pathways not susceptible to ground faults, such as optical fiber cable or wireless pathways.

23.6.2.3* Where a device as referenced by 23.6.2 is serviced by only a single pathway, it shall terminate that pathway with no ability to connect additional endpoint devices to the pathway.

23.6.2.4* A single fault on a Class N pathway shall not cause the loss of more than one addressable device.

23.6.3 Class N Shared Pathways. Class N pathways shall be required to use shared pathway Level 3 as specified in 12.5.4 except as permitted by 23.6.3.2.

23.6.3.1 Accessibility. Class N pathways shall not be accessible to the general public or building occupants for any purpose other than specified in the network design analysis, maintenance, and deployment plans.

23.6.3.2 Level 1 and Level 2. Shared pathways Levels 1 and 2 shall be permitted subject to approval of the authority having jurisdiction, based on documentation of the deployment, change control, maintenance plans, management organization, network design analysis, and a risk analysis as identified in 23.6.3.3 through 23.6.3.8.

23.6.3.3* Deployment Plan.

23.6.3.3.1 All equipment connected to shared pathways shall be documented in the deployment plan.

23.6.3.3.1.1 The documentation shall include manufacturer, model, listings, and intended purpose and reason for inclusion on the shared network.

23.6.3.3.1.2* The deployment plan shall identify how and where each piece of equipment is connected.

23.6.3.3.2* All connection ports, used or spare, where any unauthorized or unintended equipment could be added to the shared network, shall be identified as for use only by equipment consistent with the deployment plan.

23.6.3.3.3 Equipment Location.

23.6.3.3.3.1 The requirements of 23.6.3.3.3.2 through 23.6.3.3.3.4 shall apply to all equipment rooms, equipment closets, telecommunication rooms, telecommunication enclosures, or the like, for which both Class N life safety network infrastructure and non-life safety network equipment resides.

23.6.3.3.3.2* Equipment rooms or enclosures shall be permitted to contain both Class N life safety networking cable, equipment, and associated infrastructure provided the deployment satisfies 23.6.3.3.3.3 through 23.6.3.3.3.4.

23.6.3.3.3.3 Class N life safety network cabling, equipment, and infrastructure shall be clearly segregated and identified as "Life Safety Network."

23.6.3.3.3.4 Equipment rooms or enclosures shall be accessible to only authorized personnel via a locked access or via an enclosure requiring the use of tools to open, as acceptable by the authority having jurisdiction.

23.6.3.4 Change Control Plan. Configuration upgrades and updates shall be governed by a change control plan that determines the policy and procedure of the change and ensures that all documentation is correspondingly updated.

23.6.3.5 Management Organization.

23.6.3.5.1* An organization shall be established and maintained to manage the life safety network and shall perform the following:

- (1) Contain members appropriately certified by each manufacturer of the equipment and devices deployed on shared pathways to maintain such a network
- (2) Service and maintain all shared Class N pathways
- (3) Maintain the deployment and shared pathways plan for the lifetime of the shared pathways

23.6.3.5.2* Other service personnel, even when certified to service a specific system (i.e., fire alarm or MNS), shall be authorized and managed by this organization to ensure any outages of any system are planned, managed, and documented and appropriate steps are taken during outages to provide alternate protection of life and property.

23.6.3.6 Network Design Analysis.

23.6.3.6.1* The analysis shall be performed to determine and document communications capability as follows:

- (1) Calculation of minimum required bandwidth such that all life safety systems can be guaranteed to operate simultaneously and within required time limits
- (2) Total bandwidth provided by the network
- (3) Future bandwidth requirements
- (4) Method of providing and maintaining the prioritization of life safety traffic over non-life safety traffic

23.6.3.6.2* The analysis shall determine and document the power distribution capability as follows:

- (1) The methods provided to maintain power to all shared pathway equipment
- (2)* A calculation of power requirements of all connected equipment
- (3) Secondary power capacities provided to maintain all life safety equipment with minimum operational capacity in accordance with 10.6.7.2.3
- (4) Methods to disengage any non-life safety equipment in the event of emergency operation if required to support the minimum operational capacity requirements

23.6.3.7 Maintenance Plan.

23.6.3.7.1* The maintenance plan shall identify policy and procedures to monitor, maintain, test, and control change of the shared pathways.

23.6.3.7.2* Written procedures shall be presented in maintenance plans to govern the following:

- (1) Physical access to all parts of the Class N network equipment (i.e., switches, ports, server, controllers, devices, or components)
- (2) Electronic access to all parts of the Class N network (i.e., passwords, addresses)
- (3)* Service outage impairment process with notices of impairment and contingency plans for affected systems
- (4) Upgrade procedures
- (5) Change control procedures, with consideration given to require an updated risk analysis if necessary
- (6) Prioritization and/or segregation configuration information for life safety traffic
- (7) Maintenance and testing plans to ensure the minimum operational capacity with respect to secondary power is maintained
- (8) Other service, maintenance, or reconfiguration plans for any connected equipment

23.6.3.8* Network Risk Analysis for Class N.

23.6.3.8.1 Each application of a Class N deployment shall be specific to the nature and anticipated risks of each facility for which it is designed.

23.6.3.8.2 The risk analysis shall address both fire and non-fire emergencies when determining risk tolerances for the survivability of the network and the systems and devices it serves.

23.6.3.8.3 The detail and complexity of the risk analysis shall be commensurate with the complexity of the facility for which the network is to be installed.

23.6.3.8.4 The risk analysis shall be permitted to be limited in scope to address the requirements of an existing emergency response plan.

23.6.3.8.5 The risk analysis shall consider characteristics of the buildings, areas, spaces, campuses or regions, equipment, and operations that are not inherent in the design specifications.

23.6.3.8.6 Those elements that are not inherent in the design specifications, but that affect occupant behavior or the rate of hazard development, shall be explicitly identified and included in the risk analysis.

23.6.3.8.7 The risk analysis shall consider the following types of potential events, which are not all-inclusive but reflect the general categories that shall be considered in the risk analysis:

- (1) Natural hazards — geological events
- (2) Natural hazards — meteorological events
- (3) Human caused — accidental events
- (4) Human caused — intentional events
- (5) Technological — caused events

23.6.3.8.8 All other identified risks as required by the authority having jurisdiction shall be discussed and addressed in the analysis and maintenance plans.

23.7 Performance of Notification Appliance Circuits (NACs). The assignment of class designations to notification appliance circuits shall be based on their performance capabilities under abnormal (fault) conditions in accordance with the requirements for Class A, Class B, or Class X pathways specified in Chapter 12.

23.8 System Requirements.

23.8.1 General.

23.8.1.1* Presignal Feature.

23.8.1.1.1 Systems that have a presignal feature complying with 23.8.1.1 shall be permitted if approved by the authority having jurisdiction.

23.8.1.1.2 A presignal feature shall meet the following conditions:

- (1) The initial fire alarm signals sound only in department offices, control rooms, fire brigade stations, or other constantly attended locations.
- (2) Where there is a connection to a remote location, the transmission of the fire alarm signal to the supervising station actuates upon the initial alarm signal.
- (3) Subsequent system operation is by either of the following means:
 - (a) Human action that actuates the evacuation alarm signal or other response per the emergency response plan
 - (b) A feature that allows the control unit to delay the general alarm by more than 1 minute after the start of the alarm processing
- (4) Investigation of a presignal alarm is performed by qualified personnel.
- (5) The emergency response plan of a presignal facility includes details of the alarm receipt, investigation, and alarm activation procedures and is approved by the authority having jurisdiction.

23.8.1.2 Positive Alarm Sequence.

23.8.1.2.1 Systems that have positive alarm features complying with 23.8.1.2 shall be permitted if approved by the authority having jurisdiction.

23.8.1.2.1.1 The positive alarm sequence operation shall comply with the following:

- (1) To initiate the positive alarm sequence operation, unless otherwise permitted by 23.8.1.2.1.3, the signal from an automatic fire detection device selected for positive alarm sequence operation shall be acknowledged at the fire alarm control unit by qualified personnel within 15 seconds of annunciation.
- (2) If the signal is not acknowledged within 15 seconds, notification signals in accordance with the building evacuation or relocation plan and remote signals shall be automatically and immediately actuated.
- (3) If the positive alarm sequence operation is initiated in accordance with 23.8.1.2.1.1(1), qualified personnel shall have an alarm investigation phase of up to 180 seconds to evaluate the fire condition and reset the system.
- (4) If the system is not reset during the alarm investigation phase, notification signals in accordance with the building evacuation or relocation plan and remote signals shall be automatically and immediately actuated.
- (5) If a second automatic fire detector selected for positive alarm sequence is actuated during the alarm investigation phase, notification signals in accordance with the building evacuation or relocation plan and remote signals shall be automatically and immediately actuated.
- (6)* If any other fire alarm initiating device is actuated, notification signals in accordance with the building evacuation

or relocation plan and remote signals shall be automatically and immediately actuated.

23.8.1.2.1.2* The system shall provide means for bypassing the positive alarm sequence.

23.8.1.2.1.3 Manually actuated alarm-initiating devices shall be permitted to be included in a positive alarm sequence where specifically approved by the authority having jurisdiction.

23.8.2* Alarm Control Units.

23.8.2.1 Alarm and signaling systems shall be permitted to combine all detection, notification, and auxiliary functions in a single system or be a combination of component subsystems.

23.8.2.2 Except as permitted in 23.8.2.3, the alarm and signaling system components shall be permitted to share equipment or shall be able to operate as stand-alone subsystems, but shall be arranged to function as a single system in accordance with 23.8.2.4 through 23.8.2.10.

23.8.2.3 Where the building is not served by a building fire alarm system, independent dedicated function fire alarm systems and/or releasing fire alarm systems shall not be required to be interconnected to function as a single system.

23.8.2.4 All component subsystems shall be capable of simultaneous, full-load operation without degradation of the required overall system performance.

23.8.2.5 The method of interconnection of fire alarm control units shall meet the monitoring requirements of Section 12.6 and *NFPA 70*, Article 760, and shall be achieved by the following recognized means:

- (1) Electrical contacts listed for the connected load
- (2) Data communications over a signaling line circuit(s) dedicated to the fire alarm or shared with other premises operating systems
- (3) Other listed methods

23.8.2.6 Where the signaling line circuit is shared by other premises operating systems, operation shall be in accordance with 23.8.4.

23.8.2.6.1 All signal control and transport equipment (such as routers and servers) located in a critical fire alarm or emergency control function interface device signaling path shall be listed for fire alarm service, unless the following conditions are met:

- (1) The equipment meets the performance requirements of 10.3.5.
- (2) The equipment is provided with primary and secondary power and monitored for integrity as required in Section 10.6, 10.6.9, Section 10.19, and Section 12.6.
- (3) All programming and configuration ensure a fire alarm system actuation time as required in 10.11.1.
- (4) System bandwidth is monitored to confirm that all communications between equipment that is critical to the operation of the fire alarm system or emergency control function interface devices take place within 10 seconds; failure shall be indicated within 200 seconds.
- (5) Failure of any equipment that is critical to the operation of the fire alarm system or emergency control function interface devices is indicated at the master fire alarm control unit within 200 seconds.

23.8.2.6.2 A listed barrier gateway, integral with or attached to each control unit or group of control units, as appropriate, shall be provided to prevent the other systems from interfering with or controlling the fire alarm system.

23.8.2.6.3 Where Class N is utilized for shared equipment, the requirements in 23.6.3 shall also apply.

23.8.2.7 Each interconnected alarm control unit shall be separately monitored for alarm, supervisory, and trouble conditions with supervised pathways that are in accordance with the manufacturers' published instructions.

23.8.2.7.1 Alarm conditions on interconnected alarm control units shall annunciate as alarm signals and initiate the evacuation signals.

23.8.2.7.2 Supervisory conditions on interconnected alarm control units shall annunciate as supervisory signals.

23.8.2.7.3 Trouble conditions on interconnected alarm control units shall annunciate as trouble signals.

23.8.2.7.4* Where supervised pathways between interconnected fire alarm control units is not achievable, a supervised annunciator shall be installed adjacent to control unit(s) to annunciate the status of each control unit.

23.8.2.8 Interconnected fire alarm control unit alarm signals shall be permitted to be monitored by zone or by combined common signals.

23.8.2.9 Protected premises alarm control units shall be capable of being reset or silenced only from the protected premises, unless otherwise permitted by 23.8.2.10.

23.8.2.9.1 Where multiple control units of the same manufacturer are interconnected in a network arrangement and serve the same protected premises, the control units shall be arranged to be reset or silenced from one location.

23.8.2.9.2 Where multiple control units of the different manufacturers are interconnected in accordance with 23.8.2.5 through 23.8.2.8 and serve the same protected premises, the control units shall be permitted to be reset or silenced individually at each control unit.

23.8.2.9.3 Resetting procedures shall be documented and permanently posted beside each control unit and annunciator.

23.8.2.10 Remote resetting and silencing of a fire alarm control unit from other than the protected premises shall be permitted with the approval of the authority having jurisdiction.

23.8.2.11 Remote Access.

23.8.2.11.1* Remote access to fire alarm or signaling systems shall be permitted in accordance with 23.8.2.11.

23.8.2.11.2 Remote access shall not affect the operation or response of the fire alarm or signaling systems unless permitted by 23.8.2.11.3 or 23.8.2.11.5.

23.8.2.11.3 Remote access shall be permitted for testing and maintenance activities, including resetting, silencing, or operation of emergency control functions provided all of the following are met:

- (1)* The system shall provide a means to manually terminate the remote access connection at the remote device and at the fire alarm or signaling system control unit at any time.

- (2)* Remote access shall be automatically terminated within a maximum of 1 hour of inactivity in the remote access mode.

- (3) Resetting, silencing, or operation of emergency control functions shall be limited to portion(s) of the system taken out of service.

- (4) Qualified personnel shall be on-site to enable resetting, silencing, and operation of emergency control functions at the affected system(s) by password or limited access.

23.8.2.11.4* Remote access shall be permitted to be enabled remotely for the purposes of performing remote diagnostics when both of the following are met:

- (1)* The system shall provide a means to manually terminate the remote access connection at the remote device and at the fire alarm or signaling system control unit at any time.

- (2)* Remote access shall be automatically terminated within a maximum of 1 hour of inactivity in the remote access mode.

23.8.2.11.5 Remote access for the purposes of software updating shall be permitted when all of the following are met:

- (1)* The system shall provide a means to manually terminate the remote access connection at the remote device and at the fire alarm or signaling system control unit at any time.

- (2)* Remote access shall be automatically terminated within a maximum of 1 hour of inactivity in the remote access mode.

- (3) Qualified personnel shall be on-site to enable software updating at the affected fire alarm or signaling system control unit by password or limited access.

- (4) All software changes shall be tested in accordance with Section 14.4.

23.8.3 Protected Premises Alarm and Signaling Systems Interconnected with Dwelling Unit Fire and Carbon Monoxide Warning Equipment.

23.8.3.1 A protected premises system shall be permitted to be interconnected to the household warning equipment for the purpose of actuating the notification appliances connected to the household warning equipment.

23.8.3.2 The actuation of household warning equipment shall only be permitted to be displayed at the protected premises control unit and annunciators as supervisory signals.

23.8.3.3 If interconnected, an alarm condition at the protected premises system shall cause the intended notification alarm signal of the household's warning equipment to become activated and remain activated until the protected premises system is silenced or reset.

23.8.3.4 The interconnection circuit or path from the protected premises system to the household warning equipment shall be monitored for integrity by the protected premises system in accordance with Section 12.6.

23.8.3.5 An alarm condition occurring at the household fire warning equipment or the operation of any test switches provided as part of the household warning equipment shall not cause an alarm condition at the protected premises system.

23.8.4 Combination Systems.

23.8.4.1* Fire alarm systems shall be permitted to share components, equipment, circuitry, and installation wiring with non-fire alarm systems.

23.8.4.2 Building System Information Unit (BSIU).

23.8.4.2.1* A building system information unit (BSIU) shall be listed to product safety standard UL 60950-1, *Information Technology Equipment — Safety — Part 1: General Requirements*, or UL 62368-1, *Audio/Video, Information and Communication Technology Equipment — Part 1: Safety Requirements*, or equivalent.

23.8.4.2.2 Where a BSIU provides control of the fire alarm system, the requirements in 23.8.4.2.2.1 through 23.8.4.2.2.4 shall also apply.

23.8.4.2.2.1 A fire alarm control unit (FACU) controlling the fire alarm system shall be located within the same room as the BSIU.

23.8.4.2.2.2* The BSIU shall not be permitted to perform fire alarm system control features that cannot be accomplished by the FACU within the room.

23.8.4.2.2.3 The communication path from the FACU and the BSIU shall meet the requirements of 23.8.4.4.1 through 23.8.4.4.3.

23.8.4.2.2.4 The application software for the BSIU shall be listed to UL 864, *Control Units and Accessories for Fire Alarm Systems*.

23.8.4.3 Operation of a non-fire system function(s) originating within a connected non-fire system shall not interfere with the required operation of the fire alarm system, unless otherwise permitted by this Code.

23.8.4.4* For non-fire alarm equipment listed to the performance requirements specified in 10.3.5, the requirements of 23.8.4.4.1 through 23.8.4.4.3 shall apply.

23.8.4.4.1 The equipment shall be permitted to be attached to a fire alarm circuit, either among the fire alarm devices or as a branch or extension of the fire alarm pathways, when the following requirements are met:

- (1) All the equipment and pathways shall meet the monitoring for integrity requirements of 10.6.9, Section 10.19, and Section 12.6.
- (2) All the equipment and pathways shall be maintained by a single service organization.
- (3) All the equipment and pathways shall be installed in accordance with the requirements of this Code.
- (4) All the equipment shall be listed as compatible with the fire alarm equipment or the equipment shall have an interface listed as compatible with the fire alarm equipment.

23.8.4.4.2 If the equipment is attached to the fire alarm system via separate pathways, then short circuits or open circuits in this equipment, or between this equipment and the fire alarm system pathways, shall not impede or impair the monitoring for integrity of the fire alarm system or prevent alarm, supervisory, or fire safety control signal transmissions.

23.8.4.4.3 Grounds in this equipment, or between this equipment and the fire alarm system pathways, shall be reported, annunciated, and corrected in the same manner as grounds in the rest of the fire alarm system.

23.8.4.5 For non-fire equipment not listed to the performance requirements specified in 10.3.5, the requirements of 23.8.4.5.1 through 23.8.4.5.3 shall apply.

23.8.4.5.1 Short circuits or open circuits in the equipment, or between the equipment and the fire alarm system pathways, shall not impede or impair the monitoring for integrity of the fire alarm system or prevent alarm, supervisory, or fire safety control signal transmissions.

23.8.4.5.2 Grounds in this equipment, or between this equipment and the fire alarm system pathways, shall be reported, annunciated, and corrected in the same manner as grounds in the rest of the fire alarm system.

23.8.4.5.3 Removal, replacement, failure, maintenance procedures, or ground on this hardware, software, or circuits shall not impair the required operation of the fire alarm system.

23.8.4.6 Loudspeakers used as alarm notification appliances on fire alarm systems shall also be permitted to be used for emergency communications systems when installed in accordance with Chapter 24.

23.8.4.7* In combination systems, fire alarm signals shall be distinctive, clearly recognizable, and shall be indicated as follows in descending order of priority, except where otherwise required by other governing laws, codes or standards, or by other parts of this Code:

- (1) Signals associated with life safety
- (2) Signals associated with property protection
- (3) Trouble signals associated with life and/or property protection
- (4) All other signals

23.8.4.8 If the authority having jurisdiction determines that the information being displayed or annunciated on a combination system is excessive and is causing confusion and delayed response to a fire emergency, the authority having jurisdiction shall be permitted to require that the display or annunciation of information for the fire alarm system be separate from, and have priority in accordance with, 23.8.4.7, over information for the non-fire alarm systems.

23.8.4.9 Carbon Monoxide Detector Signals. Unless otherwise permitted by 23.8.4.9.1, signals from carbon monoxide detectors and carbon monoxide detection systems transmitted to a fire alarm system shall be indicated as a carbon monoxide alarm signal.

23.8.4.9.1 When in accordance with the emergency response plan, evacuation plan, fire safety plan, or similar documentation, signals from carbon monoxide detectors and carbon monoxide detection systems transmitted to a fire alarm system shall be permitted to be supervisory signals.

23.8.4.9.2* Fire alarm system processing for and occupant response to carbon monoxide alarm signals shall be in accordance with the emergency response plan, evacuation plan, fire safety plan, or similar documentation.

23.8.4.9.3 Where carbon monoxide warning equipment is connected to a protected premises fire alarm system, receipt of signals shall initiate the signal required by Section 18.4.

23.8.4.9.4 Operation of carbon monoxide alarms or detectors shall not cause fire alarm or combination system control units to actuate either protected premises or supervising station fire alarm signals.

23.8.4.10* Signals from a fire extinguisher electronic monitoring device or fire extinguisher monitoring system transmitted

to a fire alarm system shall be permitted to be supervisory signals.

23.8.5 Fire Alarm System Inputs.

23.8.5.1 General.

23.8.5.1.1 All initiating devices shall be installed in accordance with Chapter 17 and tested in accordance with Chapter 14.

23.8.5.1.2* Where connected to a supervising station, fire alarm systems employing automatic fire detectors or waterflow detection devices shall include a manual fire alarm box to initiate a signal to the supervising station.

23.8.5.1.3 Fire alarm systems dedicated to elevator recall control and supervisory service as permitted in Section 21.3 shall not be required to meet 23.8.5.1.2.

23.8.5.2 Fire Alarm Signal Initiation — Manual. Manual fire alarm signal initiation shall comply with the requirements of Section 17.15.

23.8.5.2.1 If signals from manual fire alarm boxes and other fire alarm initiating devices within a building are transmitted over the same signaling line circuit, there shall be no interference with manual fire alarm box signals when both types of initiating devices are operated at the same time.

23.8.5.2.2 Provision of the shunt noninterfering method of operation shall be permitted for this performance.

23.8.5.3 Fire Alarm Signal Initiation — Initiating Devices with Separate Power and Signaling Wiring.

23.8.5.3.1 Automatic fire alarm signal initiating devices that have integral trouble signal contacts shall be connected to the initiating device circuit so that a trouble condition within a device does not impair alarm transmission from any other initiating device, unless the trouble condition is caused by electrical disconnection of the device or by removing the initiating device from its plug-in base.

23.8.5.3.2* Automatic fire alarm signal initiating devices that use a nonintegral device to monitor the integrity of the power supply wiring to the individual initiating devices shall have the nonintegral device connected to the initiating device circuit so that a fault on the power supply wiring does not impair alarm transmission from any operational initiating device.

23.8.5.4 Fire Alarm Signal Initiation — Detection Devices.

23.8.5.4.1* Systems equipped with alarm verification features shall be permitted under the following conditions:

- (1) The alarm verification feature is not initially enabled, unless conditions or occupant activities that are expected to cause nuisance alarms are anticipated in the area that is protected by the smoke detectors. Enabling of the alarm verification feature shall be protected by password or limited access.
- (2) A smoke detector that is continuously subjected to a smoke concentration above alarm threshold does not delay the system functions of Sections 10.7 through 10.17, or 21.2.1 by more than 1 minute.
- (3) Actuation of an alarm-initiating device other than a smoke detector causes the system functions of Sections 10.7 through 10.17, or 21.2.1 without additional delay.

- (4) The current status of the alarm verification feature is shown on the record of completion [see Figure 7.8.2(a), item 4.3].

23.8.5.4.2 If automatic drift compensation of sensitivity for a fire detector is provided, the fire alarm control unit shall identify the affected detector when the limit of compensation is reached.

23.8.5.4.3 Systems that require the operation of two automatic detectors to initiate the alarm response shall be permitted, provided that the following conditions are satisfied:

- (1) The systems are not prohibited by the authority having jurisdiction.
- (2) At least two automatic detectors are in each protected space.
- (3) The alarm verification feature is not used.
- (4) The specific sequence of operations is detailed in the design documents as defined by Chapter 7 of this Code.

23.8.5.4.4 For systems that require the operation of two automatic detectors to initiate emergency control functions or to actuate fire extinguishing or suppression systems, the detectors shall be installed at the spacing determined in accordance with Chapter 17.

23.8.5.4.5 For systems that require the operation of two automatic detectors to actuate public mode notification, the detectors shall be installed at a linear spacing not more than 0.7 times the linear spacing determined in accordance with Chapter 17.

23.8.5.4.6 Signal Initiation — Duct Smoke Detectors.

23.8.5.4.6.1 Where duct smoke detectors are required to be monitored and a building fire alarm system is installed, a duct detector activation signal shall meet the requirements of 21.7.4.

23.8.5.4.6.2 Where duct smoke detectors are connected to a protected premises fire alarm system, the operation of the power circuit shall meet the requirements of 23.4.2.2.

23.8.5.4.6.3* Where duct smoke detectors with separate power and signal wiring are installed and connected to a protected premises fire alarm system, they shall meet the requirements of 23.8.5.3.

23.8.5.4.6.4 Where duct smoke detectors are not resettable from the protected premises fire alarm system, a listed alarm/supervisory indicator with an integral reset switch shall be provided in an accessible location.

23.8.5.5* Fire Alarm Signal Initiation — Sprinkler Systems.

23.8.5.5.1 Where required by other governing laws, codes, or standards to be electronically monitored, waterflow alarm-initiating devices shall be connected to a dedicated function fire alarm control unit designated as “sprinkler waterflow and supervisory system” and permanently identified on the control unit and record drawings.

23.8.5.5.2 Waterflow alarm-initiating devices connected to a building alarm system shall not be required to meet the requirements of 23.8.5.5.1.

23.8.5.5.3* The number of waterflow alarm-initiating devices permitted to be connected to a single initiating device circuit shall not exceed five.

23.8.5.5.4 If a valve is installed in the connection between a sprinkler system and an initiating device, the valve shall be supervised in accordance with 17.17.1.

23.8.5.6* Supervisory Signal Initiation — Sprinkler Systems.

23.8.5.6.1 Where required by other governing laws, codes, or standards to be electronically monitored, supervisory signal-initiating devices shall be connected to a dedicated function fire alarm control unit designated as “sprinkler waterflow and supervisory system” and permanently identified on the control unit and record drawings.

23.8.5.6.2 Supervisory signal-initiating devices connected to a building alarm system shall not be required to meet the requirements of 23.8.5.6.1.

23.8.5.6.3* The number of supervisory signal-initiating devices permitted to be connected to a single initiating device circuit shall not exceed 20.

23.8.5.6.4* If a valve is installed in the connection between a sprinkler system and an initiating device, the valve shall be supervised in accordance with 17.17.1 unless the valve is arranged to cause operation of the supervisory signal initiating device when it is in its off-normal position.

23.8.5.7 Alarm Signal Initiation — Fire Suppression Systems Other Than Sprinklers.

23.8.5.7.1 Where required by other governing laws, codes, or standards to be monitored and a building fire alarm system is installed, the actuation of a fire suppression system shall annunciate an alarm or supervisory condition at the building fire alarm control unit.

23.8.5.7.2 The integrity of each fire suppression system actuating device and its circuit shall comply with 12.6.1, 12.6.2, and other applicable NFPA standards.

23.8.5.7.3 If a valve is installed in the connection between a suppression system and an initiating device, the valve shall be supervised in accordance with 17.17.1.

23.8.5.8* Supervisory Signal Initiation — Fire Suppression Systems Other Than Sprinklers.

23.8.5.8.1 Where required to be monitored and a building fire alarm system is installed, an off-normal condition of a fire suppression system shall annunciate a supervisory condition at the building fire alarm control unit.

23.8.5.8.2 Supervisory signals that latch in the off-normal state and require manual reset of the system to restore them to normal shall be permitted.

23.8.5.8.3 If a valve is installed in the connection between a suppression system and an initiating device, the valve shall be supervised in accordance with 17.17.1.

23.8.5.9 Signal Initiation — Fire Pump.

23.8.5.9.1 Where fire pumps are required to be monitored and a building fire alarm system is installed, a pump running signal shall be permitted to be a supervisory or alarm signal.

23.8.5.9.2 Where fire pumps are required to be monitored and a building fire alarm system is installed, signals other than pump running shall be supervisory signals.

23.8.5.10 Fire Alarm and Supervisory Signal Initiation — Releasing Fire Alarm Systems.

23.8.5.10.1 Releasing service fire alarm control units shall be connected to the protected premises fire alarm system.

23.8.5.10.2 Fire alarm and supervisory signals generated at the releasing service fire alarm control unit shall be annunciated at a protected premises fire alarm unit.

23.8.5.10.3 Where required by other governing laws, codes, or standards, actuation of any suppression system connected to a releasing service fire alarm control unit shall be annunciated at the protected premises fire alarm control unit, even where the system actuation is by manual means or otherwise accomplished without actuation of the releasing service fire alarm control unit.

23.8.5.10.4 If a valve is installed in the connection between a suppression system and an initiating device, the valve shall be supervised in accordance with Chapter 17.

23.8.5.10.5 In facilities that are not required to install a protected premises fire alarm system, the alarm and supervisory devices shall be connected to the releasing service fire alarm control unit, and their actuation shall be annunciated at the releasing service control unit.

23.8.5.11 Trouble Signal Initiation.

23.8.5.11.1 Automatic fire suppression system alarm-initiating devices and supervisory signal-initiating devices and their circuits shall be designed and installed so that they cannot be subject to tampering, opening, or removal without initiating a signal.

23.8.5.11.2 Covers of junction boxes inside of buildings shall not be required to meet the requirements of 23.8.5.11.1.

23.8.5.11.3 The requirements of 23.8.5.11.1 shall apply to junction boxes and device covers installed outside of buildings to facilitate access to the initiating device circuit unless tamper-resistant screws or other approved mechanical means are used for preventing access.

23.8.5.11.4 The integrity of each fire suppression system actuating device and its circuit shall be supervised in accordance with 12.6.1 and 12.6.2 and with other applicable NFPA standards.

23.8.5.12 Disconnect Switches and Disable Functions. Operation of any disconnect switch or disable function associated with the fire alarm system, when in the off-normal condition, shall be indicated at the building fire alarm control unit or at a dedicated function(s) fire alarm control unit if provided.

23.8.6 Alarm System Notification Outputs.

23.8.6.1 Occupant Notification.

23.8.6.1.1 Fire alarm systems provided for evacuation or relocation of occupants shall have one or more notification appliances listed for the purpose in each notification zone of the building and be so located that they have the characteristics described in Chapter 18 for public mode or private mode, as required.

23.8.6.1.2 Except as permitted in 23.8.6.1.3, occupant notification of carbon monoxide systems shall be throughout the protected premises.

23.8.6.1.3 Where carbon monoxide alarm signals are transmitted to a constantly attended on-site location or off-premises location in accordance with this chapter, selective public mode occupant notification shall be permitted to be limited to the notification zone encompassing the area where the carbon monoxide alarm signal was initiated.

23.8.6.2* Notification Appliances in Exit Stair Enclosures, Exit Passageways, and Elevator Cars. Notification appliances shall not be required in exit stair enclosures, exit passageways, and elevator cars in accordance with 23.8.6.2.1 through 23.8.6.2.4 unless required by other codes and standards.

23.8.6.2.1 Visual signals shall not be required in exit stair enclosures and exit passageways.

23.8.6.2.2 Visual signals shall not be required in elevator cars.

23.8.6.2.3 The emergency evacuation signal specified in 18.4.2 shall not be required to automatically operate in exit stair enclosures and exit passageways.

23.8.6.2.4 The emergency evacuation signal specified in 18.4.2 shall not be required to automatically operate in elevator cars.

23.8.6.3 Notification Zones.

23.8.6.3.1 Notification zones shall be consistent with the emergency response or evacuation plan for the protected premises.

23.8.6.3.2 The boundaries of fire alarm notification zones shall be coincident with building outer walls, building fire or smoke compartment boundaries, floor separations, or other fire safety subdivisions.

23.8.6.3.3* The boundaries of carbon monoxide alarm notification zones shall be coincident with the area where the alarm initiation originated and other notification zones in accordance with the building's emergency response plan.

23.8.6.4 Circuits for Addressable Notification Appliances.

23.8.6.4.1 Circuit configuration for addressable notification appliances shall comply with the applicable performance requirements for notification zones.

23.8.6.4.2 Where there are addressable notification appliances on a signaling line circuit that serves different notification zones, a single open, short-circuit, or ground on that signaling line circuit shall not affect operation of more than one notification zone.

23.8.6.4.3 Riser conductors installed in accordance with 24.4.8.6.3 that are monitored for integrity shall not be required to operate in accordance with 23.8.6.4.2.

23.9 In-Building Emergency Voice/Alarm Communications.

23.9.1 In-building fire emergency voice/alarm communications shall meet the requirements of Chapter 24.

23.9.2 Where a voice/alarm communications system is installed for the purpose of occupant notification related to carbon monoxide detection, it shall meet the requirements of Section 24.4 excluding the requirements of 24.4.8.6.

23.9.3 All live voice communications systems shall meet the requirements of Chapter 24.

23.9.4 Two-Way Communication Service. Two-way communication service shall meet the requirements of Chapter 24.

23.10 Fire Alarm Systems Using Tone.

23.10.1 The requirements of Section 23.10 shall apply to tone and visual notification appliance circuits.

23.10.2* Fire alarm systems used for partial evacuation and relocation shall be designed and installed such that attack by fire within a notification zone shall not impair control and operation of the notification appliances outside that notification zone.

23.10.3 Performance features provided to ensure survivability shall be described and technical justification provided in the documentation submitted to the authority having jurisdiction.

23.10.4 Loudspeakers that transmit tone signals shall be permitted to be used as fire alarm notification appliances.

23.11 Suppression System Actuation.

23.11.1 Releasing service fire alarm control units used for automatic or manual activation of a fire suppression system shall be listed for releasing service.

23.11.2 Releasing devices for suppression systems shall be listed for use with releasing service control units.

23.11.3 Each releasing device (e.g., solenoid, relay) shall be monitored for integrity (supervised) in accordance with applicable NFPA standards.

23.11.4 The installation wiring shall be monitored for integrity in accordance with the requirements of Section 12.6.

23.11.5 Releasing service fire alarm systems used for fire suppression—releasing service shall be provided with a disconnect switch to allow the system to be tested without actuating the fire suppression systems.

23.11.5.1 Operation of a disconnect switch or a disable function shall cause a supervisory signal at the releasing service fire alarm control unit.

23.11.5.2 The disconnect shall be a physical switch and not be accomplished by using software.

23.11.5.3 Software disconnects, even if actuated by dedicated buttons or key switches, shall not be permitted as a method to secure a suppression system from inadvertent discharge.

23.11.6 Sequence of operation shall be consistent with the applicable suppression system standards.

23.11.7* Each space protected by an automatic fire suppression system actuated by the fire alarm system shall contain one or more automatic fire detectors installed in accordance with Chapter 17.

23.11.8 Suppression systems or groups of systems shall be controlled by a single releasing service fire alarm control unit that monitors the associated initiating device(s), actuates the associated releasing device(s), and controls the associated agent release notification appliances.

23.11.9 If the configuration of multiple control units is listed for releasing device service, and if a trouble condition or manual disconnect on either control unit causes a trouble or supervisory signal, the initiating device on one control unit shall be permitted to actuate releasing devices on another control unit in lieu of 23.11.8.

23.11.10 If the releasing service fire alarm control unit is located in a protected premises having a separate fire alarm system, it shall be monitored for alarm, supervisory, and trouble signals, but shall not be dependent on or affected by the operation or failure of the protected premises fire alarm system.

23.11.11 Releasing fire alarm systems performing suppression system releasing functions shall be installed in such a manner that they are effectively protected from damage caused by activation of the suppression system(s) they control.

23.12 Off-Premises Signals.

23.12.1 Systems requiring transmission of signals to continuously attended locations providing supervising station service (e.g., central station, proprietary supervising station, remote supervising station) shall also comply with the applicable requirements of Chapter 26.

23.12.2 Relays or modules providing transmission of trouble signals to a supervising station shall be arranged to provide fail-safe operation.

23.12.3 Means provided to transmit trouble signals to supervising stations shall be arranged so as to transmit a trouble signal to the supervising station for any trouble condition received at the protected premises control unit, including loss of primary or secondary power.

23.12.4* It shall be permitted to provide supplementary transmission of real-time data from the fire system to off-premises equipment.

23.12.4.1 Transmission of real-time data off-premises shall not affect the operation or response of the fire alarm control unit.

23.12.4.2 Any data transmitted shall be consistent with the data generated by the system.

23.13 Guard's Tour Supervisory Service.

23.13.1 Guard's tour reporting stations shall be listed for the application.

23.13.2 The number of guard's tour reporting stations, their locations, and the route to be followed by the guard for operating the stations shall be approved for the particular installation in accordance with NFPA 601.

23.13.3 A permanent record indicating every time each signal-transmitting station is operated shall be made at a protected premises fire alarm control unit.

23.13.4 Where intermediate stations that do not transmit a signal are employed in conjunction with signal-transmitting stations, distinctive signals shall be transmitted at the beginning and end of each tour of a guard.

23.13.5 A signal-transmitting station shall be provided at intervals not exceeding 10 intermediate stations.

23.13.6 Intermediate stations that do not transmit a signal shall be capable of operation only in a fixed sequence.

23.14 Suppressed (Exception Reporting) Signal System.

23.14.1 The suppressed signal system shall comply with the provisions of 23.13.2.

23.14.2 The system shall transmit a start signal to the signal-receiving location.

23.14.3 The start signal shall be initiated by the guard at the start of continuous tour rounds.

23.14.4 The system shall automatically transmit a delinquency signal within 15 minutes after the predetermined actuation time if the guard fails to actuate a tour station as scheduled.

23.14.5 A finish signal shall be transmitted within a predetermined interval after the guard's completion of each tour of the premises.

23.14.6 For periods of over 24 hours during which tours are continuously conducted, a start signal shall be transmitted at least every 24 hours.

23.14.7 The start, delinquency, and finish signals shall be recorded at the signal-receiving location.

23.15 Protected Premises Emergency Control Functions.

23.15.1 Emergency Elevator Operations. Emergency elevator operations shall meet the requirements of Sections 21.3, 21.4, 21.5, and 21.6.

23.15.2 HVAC Systems. HVAC systems shall meet the requirements of Section 21.7.

23.15.3 Door Release Service. Door release service shall meet the requirements of Section 21.9.

23.15.4 Electrically Locked Doors. Door-unlocking devices shall meet the requirements of Section 21.10.

23.15.5 Exit Marking Audible Notification Systems. Exit marking audible notification systems shall meet the requirements of Section 21.11.

23.15.6 Carbon Monoxide. Where provided, carbon monoxide control functions shall comply with the requirements of 21.7.6.

23.16* Special Requirements for Low-Power Radio (Wireless) Systems.

23.16.1* Listing Requirements. Compliance with Section 23.16 shall require the use of low-power radio equipment specifically listed for the purpose.

23.16.2* Power Supplies. A primary battery(s) (dry cell) that meet the requirements of 23.16.2.1 or 23.16.2.2 shall be permitted to be used as the sole power source for devices incorporating a low-power radio transmitter/transceiver.

23.16.2.1 The following conditions shall be met when one or more primary batteries are utilized and a catastrophic (open or short) single battery failure affects the alarm operation of the device:

- (1) Each transmitter/transceiver shall serve only one device and shall be individually identified at the system control unit.
- (2) The battery(s) shall be capable of operating the low-power radio transmitter/transceiver and its associated device for not less than 1 year before the battery depletion threshold is reached.
- (3) A low battery signal shall be transmitted before the device is no longer capable of providing 7 days of trouble signal operation followed by the signaling of a single non-trouble response.
- (4) The low battery signal shall be distinctive from alarm, supervisory, tamper, and trouble signals, shall visibly iden-

tify the affected low-power radio transmitter/transceiver, and, when silenced, shall automatically re-sound at least once every 4 hours.

- (5) Catastrophic (open or short) battery failure shall cause a trouble signal identifying the affected low-power radio transmitter/transceiver at the system control unit. When silenced, the trouble signal shall automatically re-sound at least once every 4 hours.
- (6) Any mode of failure of a primary battery in a low-power radio transmitter/transceiver shall not affect any other low-power radio transmitter/transceiver.

23.16.2.2 The following conditions shall be met when multiple batteries are utilized and a catastrophic (open or short) single battery failure does not affect the alarm operation of the device:

- (1) Two or more batteries shall be provided.
- (2) The combined batteries shall be capable of operating the low-power radio transmitter/transceiver and its associated device for not less than 1 year before the battery depletion threshold in 23.16.2.2(3) is reached.
- (3) A low battery signal shall be transmitted before the device is no longer capable of providing 7 days of trouble signal operation followed by the signaling of a single non-trouble response.
- (4) Each individual battery, primary and secondary, shall be separately monitored for the battery depletion threshold, and a low battery signal shall be transmitted when an individual battery has reached the battery depletion threshold.
- (5) Following the failure of a single battery, the remaining battery(s) shall be capable of operating the low-power radio transmitter/transceiver and its associated device for not less than 7 days when the battery depletion threshold in 23.16.2.2(3) is reached.
- (6) The low battery signal shall be distinctive from alarm, supervisory, tamper, and trouble signals, shall visibly identify the affected low-power radio transmitter/transceiver, and, when silenced, shall automatically re-sound at least once every 4 hours.
- (7) Catastrophic (open or short) failure of any individual battery shall cause a trouble signal identifying the affected low-power radio transmitter/transceiver at the system control unit. When silenced, the trouble signal shall automatically re-sound at least once every 4 hours.
- (8) Each transmitter/transceiver shall be permitted to serve more than one device and shall be individually identified at the system control unit.

23.16.3 Alarm Signals.

23.16.3.1* When a wireless initiating device is actuated, its low-power radio transmitter/transceiver shall comply with 23.16.3.1.1 through 23.16.3.1.4.

23.16.3.1.1 It shall automatically transmit an alarm signal and be identified at the fire alarm system.

23.16.3.1.2 To ensure the receipt of an alarm signal by the control unit, the low-power radio transmitter/transceiver shall automatically repeat alarm transmissions at intervals not exceeding 60 seconds until the transmitter/transceiver receives a signal confirming receipt of the alarm signal by the control unit.

23.16.3.1.3* Signals shall have priority in accordance with 23.8.4.7.

23.16.3.1.4 Response time shall be in accordance with 10.11.1.

23.16.3.1.5* An alarm signal from a low-power radio transmitter/transceiver shall latch at the fire alarm control system until manually reset and shall identify the particular initiating device in alarm.

23.16.3.1.6 Sixty seconds after the conclusion of resetting the fire alarm system, a non-restored actuated low-power radio transmitter/transceiver shall be identified at the fire alarm systems.

23.16.4 Monitoring for Integrity.

23.16.4.1 The low-power radio transmitter/transceiver shall be specifically listed as using a communication method that is highly resistant to misinterpretation of simultaneous transmissions and to interference (e.g., impulse noise and adjacent channel interference).

23.16.4.2 The occurrence of any single fault that disables communication between any low-power radio transmitter/transceiver and the receiver/transceiver system control unit shall cause a latching trouble signal within 200 seconds at the system control unit that individually identifies the affected device.

23.16.4.3 A single fault on the signaling channel shall not cause an alarm signal.

23.16.4.4 The periodic communication required to comply with 23.16.4.2 shall ensure successful alarm transmission capability.

23.16.4.5 Removal of a low-power radio transmitter/transceiver from its installed location shall cause immediate transmission of a distinctive trouble signal that indicates its removal and individually identifies the affected device.

23.16.4.6 Reception of any unwanted (interfering) transmission by a retransmission device or by the receiver system control unit for a continuous period of 20 seconds or more shall cause an audible and visible trouble indication at the system control unit.

23.16.4.7 The indication required by 23.16.4.6 shall identify the specific trouble condition as an interfering signal.

23.16.4.8 Operation of Class A Radio Pathways.

23.16.4.8.1 Radio frequency pathways designated as Class A shall operate as follows:

- (1) A redundant pathway is included.
- (2) Operational capability is verified via end-to-end communication.
- (3) Conditions that affect the intended operation of the required pathways are annunciated as a trouble signal when two pathways are no longer available to each transceiver/device.
- (4) Operational capability in a radio frequency pathway/channel continues during conditions that affect the intended operation of one of the two remaining pathways.
- (5) Each transceiver or repeater in a radio frequency or wireless pathway is powered by one of the following means:
 - (a) Both a primary and a secondary source meeting Section 10.6
 - (b) Multiple primary batteries meeting 23.16.2.2

23.16.4.8.2 Where operational capability is to be maintained during a fault, the operational capability shall be restored within 200 seconds of the application of the fault.

23.16.4.9 Operation of Class B Radio Pathways.

23.16.4.9.1 Radio frequency pathways designated as Class B shall operate as follows:

- (1) A redundant path is not included.
- (2) Operational capability is verified via end-to-end communication.
- (3) Conditions that affect the intended operation of the pathway are annunciated as a trouble signal.
- (4) Operational capability stops at the affected portion of the pathway.
- (5) Each transceiver and/or repeater in a radio frequency pathway is powered by one of the following means:
 - (a) Both a primary and a secondary source meeting Section 10.6
 - (b) Multiple primary batteries meeting 23.16.2.2

23.16.4.9.2 Where operational capability is to be maintained during a fault, the operational capability shall be restored within 200 seconds of the application of the fault.

23.16.5 Output Signals from a Wireless Receiver/Transceiver of a Control Unit. Where a wireless receiver/transceiver of a control unit is used to actuate remote devices, such as notification appliances and relays, by wireless means, the remote devices shall meet the following requirements:

- (1) Power supplies shall comply with Chapter 10 or the requirements of 23.16.2.
- (2) All monitoring for integrity requirements of Chapters 10, 12, 23, and 23.16.4 shall apply.
- (3) Response time shall be in accordance with 10.11.1.
- (4) Each wireless receiver/transceiver of a control unit shall automatically repeat actuated response signals associated with life safety events at intervals not exceeding 60 seconds or until confirmation that the output device has received the alarm signal.
- (5) The remote devices shall continue to operate (latch-in) until manually reset at the system control unit.

Chapter 24 Emergency Communications Systems (ECS)

24.1 Application.

24.1.1 The application, installation, and performance of emergency communications systems and their components shall comply with the requirements of this chapter.

24.1.2* The requirements of this chapter shall apply to emergency communications systems within buildings and outdoor areas.

24.1.3 The requirements of Chapters 7, 10, 11, 12, 17, 18, 21, 23, 26, and 27 shall also apply unless otherwise noted in this chapter.

24.1.4 Inspection, testing, and maintenance shall be performed in accordance with testing frequencies and methods in Chapter 14.

24.1.5 The requirements of this chapter shall not apply to Chapter 29 unless specifically indicated.

24.2 Purpose.

24.2.1 The systems covered under Chapter 24 shall be for the protection of life by indicating the existence of an emergency situation and communicating information necessary to facilitate an appropriate response and action.

24.2.2 This chapter establishes minimum required levels of performance, reliability, and quality of installation for emergency communications systems but does not establish the only methods by which these requirements are to be achieved.

24.2.3 An emergency communications system is intended to communicate information about emergencies including, but not limited to, fire, human-caused events (accidental and intentional), other dangerous situations, accidents, and natural disasters.

24.3 General.

24.3.1 Intelligible Voice Messages.

24.3.1.1* Emergency communications systems shall be capable of the reproduction of prerecorded, synthesized, or live (e.g., microphone, telephone handset, and radio) messages with voice intelligibility in accordance with Chapter 18.

24.3.1.2* Where listed loudspeakers do not achieve the intelligibility requirements of the Code for a notification zone, non-listed loudspeakers shall be permitted to be installed to achieve the intelligibility for that notification zone.

24.3.2* Microphone Use. All users of systems that have microphones for live voice announcements shall be provided with posted instructions for using the microphone.

24.3.3* Required Emergency Communications Systems. An emergency communications system shall be installed in occupancies where required by the authority having jurisdiction or by other applicable governing laws, codes, or standards.

24.3.4* Nonrequired (Voluntary) Emergency Communications Systems.

24.3.4.1 Nonrequired emergency communications systems and components shall meet the requirements of this chapter.

24.3.4.2 Nonrequired emergency communications systems and components shall be identified on the record drawings.

24.3.5 Ancillary Functions.

24.3.5.1 Ancillary functions shall not impair the required operation of the emergency communications system.

24.3.5.2* Loudspeakers used for emergency communications system functions also providing ancillary functions shall meet the conditions of either 24.3.5.2(1) or 24.3.5.2(2):

- (1) The fire command center or the emergency command center as applicable shall be constantly attended by trained personnel, and selective paging is permitted by the authority having jurisdiction.
- (2) All of the following conditions shall be met:
 - (a) The loudspeakers and associated audio equipment are installed or located with safeguards to resist tampering or misadjustment of those components essential for intended emergency notification.
 - (b) The monitoring integrity requirements of 10.6.9 and Sections 10.19 and 12.6 continue to be met

while the system is used for non-emergency purposes.

24.3.5.3 Ancillary functions shall be inspected and tested annually to verify they will not impair the operation of the fire alarm system or the mass notification system.

24.3.5.4 Where emergency communications systems utilize Class N pathways that are also shared Level 1 or Level 2 pathways as a means to support ancillary functions, devices, or interconnected systems, the shared pathways shall meet the requirements of 23.6.3.

24.3.5.4.1 In addition to the requirements of 23.6.3, a risk analysis shall be performed and approved by the AHJ.

24.3.6 Messages for One-Way Emergency Communications Systems.

24.3.6.1* Messages shall be developed for each scenario identified in the emergency response plan.

24.3.6.1.1 Based on the emergency response plan, emergency messages shall have content that provides information and instructions to people in the building, area, site, or installation.

24.3.6.1.2 The proposed verbiage of prerecorded automatic emergency messages shall be identified on the permit plans and be approved by the authority having jurisdiction prior to their programming into the emergency voice communications system.

24.3.6.1.3 As a minimum, the proposed verbiage of prerecorded messages shall be in the official spoken language acceptable to the authority having jurisdiction.

24.3.6.1.4 Additional prerecorded message(s) shall be permitted as approved by the authority having jurisdiction.

24.3.6.2* A message template shall be developed for each message required in 24.3.6.1.

24.3.6.3 For an evacuation message, a tone in accordance with 18.4.2 shall be used with a minimum of two cycles preceding and following the voice message.

24.3.6.4 Test messages shall clearly state the phrase "This is a test."

24.3.7* System Classification. Emergency communications systems (ECS) shall be designated as one-way or two-way.

24.3.7.1* One-way emergency communications systems shall consist of one or more of the following:

- (1) In-building fire emergency voice/alarm communications systems (EVACS) (*see Section 24.4*)
- (2) In-building mass notification systems (*see Section 24.5*)
- (3) Wide-area mass notification systems (*see Section 24.6*)
- (4) Distributed recipient mass notification systems (DRMNS) (*see Section 24.7*)

24.3.7.2* Two-way emergency communications systems shall consist of one or more of the following:

- (1) Two-way, in-building wired emergency services communications systems (i.e., fire fighters' telephone systems) (*see Section 24.8*)
- (2) Two-way radio communications enhancement systems (*see Section 24.9*)
- (3) Area of refuge emergency communications systems (*see Section 24.10*)

- (4) Stairway communications systems (*see Section 24.10*)
- (5) Elevator landing communications systems (*see Section 24.10*)
- (6) Occupant evacuation elevator lobby communications systems (*see Section 24.10*)

24.3.8* Mass Notification Layers. Emergency communications used for mass notification shall be categorized into layers and take into consideration type of audience and reach as follows:

- (1) Layer 1 relates to means of notification of occupants by systems/equipment installed inside a building and controlled only by authorized users (in-building ECS)
- (2) Layer 2 relates to means of notification of occupants on the exterior of a building and controlled only by authorized users (wide-area MNS)
- (3) Layer 3 relates to means of notification of personnel through individual measures (distributed recipient MNS)
- (4) Layer 4 relates to means of notification of personnel by public measures (broadcast radio, television, and so forth)

24.3.9* Design Documentation. Design documents in accordance with Section 7.3 shall be prepared prior to installation of any new system.

24.3.9.1 Systems that are altered shall have design documents prepared that apply to the portions of the system that are altered.

24.3.9.2 Documents shall be revised as necessary following installation to represent as-built conditions and include record drawings.

24.3.10* Control Unit Listing for Mass Notification Systems. Control units installed as part of a mass notification system shall be listed in accordance with applicable standards such as UL 2572, *Mass Notification Systems*.

24.3.11 Building System Information Unit. A building system information unit that displays information and events from the mass notification system shall comply with 23.8.4.4.1 through 23.8.4.4.3.

24.3.12* Risk Analysis for Mass Notification Systems.

24.3.12.1* Each application of a mass notification system shall be specific to the nature and anticipated risks of each facility for which it is designed.

24.3.12.1.1 When an owner has developed a risk analysis in accordance with 24.3.12, such risk analysis shall be permitted to be used as a baseline in preparing the risk analysis for new or renovated facilities that are similar in nature.

24.3.12.2 The designer shall consider both fire and non-fire emergencies when determining risk tolerances for survivability for the mass notification system.

24.3.12.3 The detail and complexity of the risk analysis shall be commensurate with the complexity of the facility for which the mass notification system is designed.

24.3.12.4 The risk analysis shall be permitted to be limited in scope to address the communication requirements of an existing emergency response plan.

24.3.12.5 The risk analysis shall consider the number of persons, type of occupancy, and perceived peril to occupants.

24.3.12.6 The analysis shall be based on the maximum occupant load calculation for every occupiable room, building, area, space, campus, or region is expected to contain.

24.3.12.7 Occupancy characteristics shall comply with 24.3.12.7.1 and 24.3.12.7.2.

24.3.12.7.1 The risk analysis shall consider characteristics of the buildings, areas, spaces, campuses or regions, equipment, and operations that are not inherent in the design specifications.

24.3.12.7.2 Those elements that are not inherent in the design specifications, but that affect occupant behavior or the rate of hazard development, shall be explicitly identified and included in the risk analysis.

24.3.12.8 The risk analysis shall consider the following types of potential events, which are not all-inclusive but reflect the general categories that shall be considered in the risk analysis:

- (1) Natural hazards — Geological events
- (2) Natural hazards — Meteorological events
- (3) Natural hazards — Biological events
- (4) Human caused — Accidental events
- (5) Human caused — Intentional events
- (6) Technological — Caused events

24.3.12.9 The risk analysis shall include a review of the extent to which occupants and personnel are notified, based on the anticipated event (potential hazard).

24.3.12.10* The risk analysis shall be used as the basis for development of the MNS provisions of the facility emergency response plan.

24.3.12.11 The risk analysis shall consider cybersecurity risks in accordance with Chapter 11.

24.3.13* Emergency Response Plan Elements. A well-defined emergency response plan shall be developed in accordance with *NFPA 1600* and *NFPA 1620* as part of the design and implementation of a mass notification system.

24.3.14 Pathway Survivability.

24.3.14.1 Pathway survivability levels shall be as described in Section 12.4.

24.3.14.2 Other component survivability shall comply with the provisions of 24.4.8.6.6.

24.3.14.3* The pathway survivability requirements in 24.3.14.4 through 24.3.14.16 shall apply to notification and communications circuits and other circuits necessary to ensure the continued operation of the emergency communications system.

24.3.14.4 In-building fire emergency voice/alarm communications systems shall comply with 24.3.14.4.1 or 24.3.14.4.2.

24.3.14.4.1 For systems that do not employ relocation or partial evacuation, a Level 0, Level 1, Level 2, Level 3, or Level 4 pathway survivability shall be permitted.

24.3.14.4.2* For systems employing relocation or partial evacuation, the requirements of 24.3.14.4.3 through 24.3.14.4.6.4 shall apply to the communication and control circuit pathways between a room or rated enclosure containing fire alarm equipment and other room(s) or rated enclosure(s) containing fire alarm equipment required for occupant notification.

24.3.14.4.3* Where the building is constructed with a fire resistance rating that is equal to or greater than 2 hours, the installation shall comply with 24.3.14.4.6 or provide a pathway survivability of Level 2 or Level 3.

24.3.14.4.4* Where the building is constructed with a fire resistance rating that is at least 1 hour and less than 2 hours, the installation shall comply with 24.3.14.4.6 or provide a pathway survivability of Level 4.

24.3.14.4.5 Where the building is constructed with a fire resistance rating that is less than 1 hour, the installation shall comply with 24.3.14.4.6.

24.3.14.4.6 Class N or Class X circuits complying with Level 1 pathway survivability shall be installed in accordance with the requirements of 24.3.14.4.6.1 through 24.3.14.4.6.4.

24.3.14.4.6.1* The requirements of 12.3.8 for pathway separation shall not apply to conductors installed in accordance with 24.3.14.4.6.

24.3.14.4.6.2* The requirements of 23.6.1 for pathway faults shall not apply to conductors installed in accordance with 24.3.14.4.6.

24.3.14.4.6.3* Circuits shall be separated in accordance with at least one of the following:

- (1) The primary and redundant, or outgoing and return, conductors are separated by a floor assembly.
- (2) The primary and redundant, or outgoing and return, conductors are located in dissimilar protected areas separated by a minimum of 1-hour fire-rated construction.
- (3) The primary and redundant, or outgoing and return, conductors are separated by at least one-third the maximum diagonal of the notification zone.
- (4) Performance alternatives are approved by the authority having jurisdiction.

24.3.14.4.6.4* An open, ground fault, or short-circuit fault on the communication and control circuits between rooms or enclosures required by 24.4.8.6.6 shall not affect the operation of the in-building fire emergency voice/alarm control equipment within these rooms or enclosures.

24.3.14.5 Pathway survivability levels for in-building mass notification systems shall be determined by the risk analysis.

24.3.14.6 Pathway survivability levels for wide-area mass notification systems shall be determined by the risk analysis.

24.3.14.7 Two-way in-building wired emergency services communications systems (i.e., fire fighters' telephone systems) that are installed where the building has less than 2-hour fire-rated construction shall have a pathway survivability of Level 1, 2, 3, or 4.

24.3.14.8 Two-way in-building wired emergency services communications systems (i.e., fire fighters' telephone systems) that are installed where the building has 2-hour fire-rated construction or greater shall have a pathway survivability of Level 2 or 3.

24.3.14.9* Area of refuge two-way emergency communications systems for rescue assistance shall comply with 24.3.14.9.1 and 24.3.14.9.2.

24.3.14.9.1 Installation of all circuit pathways between locations, room(s), or rated enclosure(s) containing communica-

tions system equipment shall comply with the requirements of 24.3.14.4.3 through 24.3.14.4.6.4.

24.3.14.9.2 Circuits intended to transmit off-premises shall have a pathway survivability of Level 0, Level 1, Level 2, Level 3, or Level 4.

24.3.14.10 Elevator landing two-way emergency communications systems installation of all circuit pathways between all elevator lobbies and other room(s) or rated enclosure(s) containing related control equipment required for occupant communications shall comply with the requirements of 24.3.14.4.3 through 24.3.14.4.6.4.

24.3.14.11 Elevator landing two-way emergency communications systems circuits intended to transmit off-premises shall have a pathway survivability of Level 0, Level 1, Level 2, Level 3, or Level 4.

24.3.14.12 Occupant evacuation elevator lobby two-way wired emergency communications systems installation of communication and control circuit pathways shall have a pathway survivability of Level 3.

24.3.14.12.1* A single open, ground fault, or short-circuit fault on any circuit between control equipment and elevator lobbies shall not affect the operation of the communication to any other elevator lobby.

24.3.14.12.2 Circuits intended to transmit off-premises shall have a pathway survivability of Level 0, Level 1, Level 2, Level 3, or Level 4.

24.3.14.13* Stairway communications systems required for access control provisions of other codes (locked stair doors) that are not required to be provided by other codes or standards for required use during fire evacuations shall be permitted to have a pathway survivability Level 0, Level 1, Level 2, Level 3, or Level 4 for all system circuits.

24.3.14.14* Stairway communications systems required by other codes or standards for required use during fire evacuations shall comply with 24.3.14.9.

24.3.14.15 Central command station emergency communications systems shall have pathway survivability as determined by the risk analysis.

24.3.14.16 All other emergency communications system circuits shall have pathway survivability as determined by the risk analysis.

24.4* In-Building Fire Emergency Voice/Alarm Communications Systems (EVACS). Section 24.4 shall be used in the design and application of in-building fire emergency voice/alarm communications for fire alarm systems.

24.4.1 Automatic Response. The in-building fire emergency voice/alarm communications system shall be used to provide an automatic response to the receipt of a signal indicative of a fire alarm or other emergency.

24.4.1.1 When the monitoring location is constantly attended by trained operators, and operator acknowledgment of receipt of a fire alarm or other emergency signal is received within 30 seconds, automatic response shall not be required.

24.4.1.2 If acceptable to the authority having jurisdiction, the system shall permit the application of an automatic evacuation signal to one or more signaling zones and, at the same time,

shall permit manual voice paging to the other signaling zones selectively or in any combination.

24.4.2 Voice Evacuation Messages.

24.4.2.1* Unless otherwise permitted by 24.4.8, evacuation messages shall be preceded and followed by a minimum of two cycles of the emergency signal specified in 18.4.2 or 18.4.3.

24.4.2.2 Voice messages shall comply with the requirements of 24.3.1.

24.4.2.2.1 The following requirements shall be met for layout and design:

- (1) The loudspeaker layout of the system shall be designed to ensure intelligibility and audibility.
- (2) Intelligibility shall first be determined by ensuring that all areas in the building have the required level of audibility.

24.4.2.2.2* System design shall incorporate designation of acoustically distinguishable spaces (ADS) within the occupiable areas as required in Chapter 18.

24.4.2.2.3 Audibility shall be required in all areas in accordance with Chapter 18.

24.4.3 Positive Alarm Sequence. In-building fire emergency voice/alarm communications systems shall be permitted to use positive alarm sequence complying with 23.8.1.2.

24.4.4 Tones. The tone preceding any message shall comply with 24.4.4.1 through 24.4.4.4.

24.4.4.1 The tone preceding any message shall be permitted to be a part of the voice message or to be transmitted automatically from a separate tone generator.

24.4.4.2* Except as specified in 24.4.4.3, in occupancies where sleeping accommodations are provided and the voice message is intended to communicate information to those who could be asleep, a low frequency tone that complies with 18.4.6 shall be used.

24.4.4.3* In areas where sleeping accommodation are provided, but the voice communication system is used to communicate to occupants who are awake, the low frequency tone shall not be required.

24.4.4.4 Audible signal tones for alert or evacuation shall meet the audibility requirements of either 18.4.4 (public mode audible requirements), 18.4.5 (private mode audible requirements), 18.4.6.1 and 18.4.6.2 (sleeping area requirements), or 18.4.7 (narrow band tone signaling for exceeding masked thresholds), as applicable.

24.4.5 Operating Controls.

24.4.5.1* Controls for the in-building fire emergency voice/alarm communications system shall be at a location approved by the authority having jurisdiction.

24.4.5.2 Controls shall be located or secured to allow access only by trained and authorized personnel.

24.4.5.3 Operating controls shall be clearly identified.

24.4.5.4 If there are multiple in-building fire emergency voice/alarm communications control locations, only one shall be in control at any given time.

24.4.5.5 The location having control of the system shall be identified by a visual indication at that location.

24.4.5.6 Manual controls shall be arranged to provide visual indication of the on/off status for their associated signaling zone.

24.4.5.7 If live voice instructions are provided, they shall perform as follows:

- (1) They shall override previously initiated signals to the selected notification zone.
- (2) They shall have priority over any subsequent automatically initiated signals to the selected notification zone.
- (3) If a previously initiated recorded message is interrupted by live voice instructions, upon release of the microphone, the previously initiated recorded messages to the selected notification zones shall not resume playing automatically unless required by the emergency response plan.

24.4.6 Loudspeakers.

24.4.6.1* Loudspeakers and their enclosures shall be installed in accordance with Chapter 18.

24.4.6.2 Loudspeakers used as alarm notification appliances on fire alarm systems shall also be permitted to be used for mass notification.

24.4.7 Priority.

24.4.7.1* Notification appliances required to provide special suppression predischARGE notification shall not be overridden by other systems.

24.4.7.2 Priority of mass notification messages over fire alarm evacuation shall be permitted when evaluated by the stakeholders through a risk analysis in accordance with 24.3.12.

24.4.7.3 When the fire alarm system has been activated, and mass notification has been given priority over the fire alarm system, a distinctive audible and visual indication shall be provided at the building fire alarm control unit to indicate MNS is active.

24.4.7.4 It shall not be required to transmit this condition to a supervising station.

24.4.7.5 The fire alarm system shall not automatically override emergency mass notification messages.

24.4.8* Relocation and Partial Evacuation. The requirements of 24.4.8 shall apply only to systems used for relocation or partial evacuation during a fire condition.

24.4.8.1 New systems employing relocation or partial evacuation shall require documentation in accordance with Sections 7.3, 7.4, and 7.5 in addition to the minimum documentation requirements of Sections 7.2 and 24.13.

24.4.8.2 Systems shall be provided with manual voice transmission capabilities selectively to one or more notification zones or on an all-call basis.

24.4.8.3 Where the system is used to transmit relocation instructions or other fire emergency non-evacuation messages, a 1-second to 3-second alert tone followed by a message (or messages where multi-channel capability is used) shall be provided.

24.4.8.3.1* The sequence [the alert tone followed by the message(s)] shall be repeated at least three times to inform and direct occupants in the signaling zone where the alarm initiation originated, as well as other signaling zones in accordance with the building fire safety plan.

24.4.8.3.2* When the message is recorded, the repeated message sequence of 24.4.8.3.1 shall itself be repeated after a pause of 180 seconds maximum, or other time as established by the building safety fire plan and approved by the authority having jurisdiction, until automatically silenced or reset by emergency personnel.

24.4.8.3.3 Approved alternative fire alarm notification schemes shall be permitted as long as the occupants are effectively notified and are provided instructions in a timely and safe manner in accordance with the emergency response plan.

24.4.8.4* Where the system is used to transmit partial evacuation instructions, the alert tone specified in 24.4.2.1 followed by a message (or messages where multi-channel capability is used) shall be provided.

24.4.8.5 Where provided, loudspeakers in each enclosed stairway, each exit passageway, each occupant evacuation elevator lobby, and each group of elevator cars within a common hoistway or bank shall be connected to separate notification zones for manual paging only.

24.4.8.5.1 The evacuation signal specified in 18.4.2 shall not operate in elevator cars, exit stair enclosures, and exit passageways.

24.4.8.5.2 Manually activated loudspeakers shall be permitted in exit stair enclosures, exit passageways, and elevators in buildings that have emergency voice/alarm communications systems in accordance with Section 24.4.

24.4.8.5.3 Where required by other governing laws, codes, or standards, loudspeakers shall be provided in locations specified in 24.4.8.5 and shall conform to Section 24.4.

24.4.8.6 The requirements of 24.4.8.6 shall apply to both audible (tone and voice) and visual notification appliance circuits.

24.4.8.6.1* Fire alarm systems used for partial evacuation and relocation shall be designed and installed such that attack by fire within a notification zone does not impair control and operation of the notification appliances outside the notification zone.

24.4.8.6.2 Performance features provided to ensure operational reliability under adverse conditions shall be described and technical justification provided in the documentation submitted to the authority having jurisdiction with the analysis required in 23.4.3.1.

24.4.8.6.3* All circuits necessary for the operation of the notification appliances shall be protected until they enter the notification zone that they serve by the protection provided by the pathway survivability level required in 24.3.14.4.2.

24.4.8.6.4 Where the separation of in-building fire emergency voice/alarm control equipment locations results in the portions of the system controlled by one location being dependent upon the control equipment in other locations, the circuits between the dependent controls shall be protected against attack by fire by the protection provided by the pathway survivability level required in 24.3.14.4.2.

24.4.8.6.5 Protection of circuits between redundant control equipment locations that are not mutually dependent shall not be required.

24.4.8.6.6 Where the separation of the in-building fire emergency voice/alarm control equipment occurs as in 24.4.8.6.4, and where the circuits are run through junction boxes, terminal cabinets or control equipment, such as system control units, power supplies and amplifiers, and where cable integrity is not maintained, these components shall, in addition to the pathway survivability required by 24.3.14.4.2, be protected by using one of the following methods:

- (1) A 2-hour fire-rated enclosure
- (2) A 2-hour fire-rated room
- (3) Other equivalent means to provide a 2-hour fire resistance rating approved by the authority having jurisdiction

24.4.8.6.7 Paragraphs 24.4.8 through 24.4.8.6.6 shall not automatically apply when relocation or partial evacuation is of a non-fire emergency unless identified and required by a risk analysis.

24.4.9 Signal Zoning.

24.4.9.1* Undivided fire or smoke areas shall not be divided into multiple notification zones.

24.4.9.2 If multiple notification appliance circuits are provided within a single zone, all of the notification appliances within the zone shall be arranged to activate or deactivate simultaneously, either automatically or by actuation of a common manual control.

24.4.9.3 Where there are different notification appliance circuits within a signaling zone that perform separate functions, such as presignal and general alarm signals and pre-discharge and discharge signals, they shall not be required to activate or deactivate simultaneously.

24.5* In-Building Mass Notification Systems. The requirements of Section 24.5 shall apply to mass notification systems installed in buildings or structures for the purpose of notifying and instructing occupants in an emergency.

24.5.1* General Performance. The performance, selection, installation, operation, and use of a mass notification system shall comply with the requirements of Section 24.5.

24.5.1.1 Interconnection of protected premises emergency control functions with the mass notification systems shall comply with Chapter 21.

24.5.1.2 An in-building mass notification system shall include one or more of the following components:

- (1) Autonomous control unit (ACU)
- (2) Local operating console (LOC)
- (3) Fire alarm control interface
- (4) Notification appliance network
- (5) Initiating devices
- (6)* Interface to other systems and alerting sources

24.5.1.3 All mass notification system notification appliances that receive their power from a signaling line circuit of a mass notification system control unit shall be listed for use with the control unit.

24.5.1.4 Mass notification system components shall be installed, tested, and maintained in accordance with the manufacturer's published instructions and this Code.

24.5.1.5 In-building emergency mass notification operation shall be permitted to be initiated by manual or automatic means.

24.5.1.6 Mass notification system activation shall initiate recorded messages or live voice and visual notification.

24.5.1.7 The priority level of recorded messages shall be determined by the emergency response plan.

24.5.1.8 Only recorded messages determined by the emergency response plan to be of higher priority than fire alarm activation shall be permitted to override the fire alarm notification and initiate the mass notification priority indicator.

24.5.1.9 Activation of any other recorded message shall not interfere with the operation of fire alarm notification.

24.5.1.10 Initiation of live voice announcements from microphones on the fire alarm system at an ACU, and at an LOC, shall not automatically place the fire alarm system in a mass notification priority mode.

24.5.1.11 Combination of mass notification with fire alarm systems shall be permitted and shall meet the requirements of 23.8.4.

24.5.2 System Operation.

24.5.2.1* Authorized personnel shall be permitted to control message initiation over the mass notification system.

24.5.2.2* Where required by the emergency response plan, the mass notification system shall provide the capability for authorized personnel to remotely activate live and prerecorded emergency messages.

24.5.2.3* Operating controls shall be clearly identified.

24.5.2.4 If there are multiple control locations, only one shall be in control at any given time.

24.5.2.5* Any ACU shall provide a control status of all interconnected LOCs.

24.5.2.6 If there are multiple control locations, a visual indication shall be provided at all other control locations indicating that another control location is in use.

24.5.2.7 Manual controls shall be arranged to provide visual indication of the on/off status for their associated notification zone.

24.5.2.8 If live voice instructions are provided, they shall perform as follows:

- (1) Override previously initiated signals to the selected notification zone(s).
- (2) Have priority over any subsequent automatically initiated signals to the selected zone(s).

24.5.2.9 A manual means shall be provided at each mass notification system control location to permit the mass notification system to relinquish control of the fire alarm system.

24.5.2.10* During the period after the mass notification system has seized control of the audible and visual notification appliances, but before the mass notification system relinquishes control, the mass notification system shall activate the audible and visual notification appliances at least once every 30 seconds.

24.5.3 Notification Coverage.

24.5.3.1* The mass notification system shall provide for live voice and prerecorded localized messaging within a protected individual building, areas surrounding the building, and other outdoor designated areas.

24.5.3.2 System design shall incorporate designation of acoustically distinguishable spaces (ADS) within any occupiable areas as required in Chapter 18.

24.5.3.3 Notification zones shall be established on the basis of a risk analysis.

24.5.3.4* If the mass notification system serves more than one building, it shall be capable of providing separate messages to one individual building or to multiple buildings at any given time.

24.5.4 Loudspeaker Circuits.

24.5.4.1* Loudspeaker circuits used for mass notification that are not fire alarm circuits shall be exempt from the monitoring requirements of this Code, provided that alternate methods of achieving comparable reliability are accepted by the authority having jurisdiction.

24.5.4.2 Survivability for loudspeaker circuits used for mass notification shall be determined by the risk analysis for the building.

24.5.5 Impairments. The requirements of Section 10.21 shall be applicable when a mass notification system is impaired.

24.5.6 Inspection, Testing, and Maintenance Requirements. Mass notification systems shall be inspected, tested, and maintained in accordance with the manufacturer's published instructions and the inspection, testing, and maintenance requirements of Chapter 14.

24.5.7* System Response Priorities. Priority levels shall be established on the basis of the risk analysis.

24.5.8 Initiation Indication. The source of system activation shall be visibly and audibly indicated at the emergency command center and at the building control unit, unless otherwise required by the emergency response plan.

24.5.9 Initiating Devices.

24.5.9.1 Devices connected to a mass notification system for the purpose of initiating an automatic response to an emergency shall be evaluated based on the emergency response plan.

24.5.9.2* All mass notification initiating devices shall be listed for their intended purpose.

24.5.9.3 Where no listed device exists for the detection required by the emergency response plan, non-listed devices shall be permitted to be used if their failure will not impair the operation of the mass notification system.

24.5.9.4 Non-fire emergency manual actuating stations (boxes) shall be listed to UL 2017, *General-Purpose Signaling Devices and Systems*.

24.5.9.5 Non-fire emergency manual actuating boxes shall have tactile markings, be of a contrasting color to manual fire alarm boxes on the protected premises, and not be red.

24.5.9.6 Non-fire emergency manual actuating boxes shall be installed similarly to manual fire alarm boxes in accordance with the requirements of 17.15.4, 17.15.6, and 17.15.9.2.

24.5.10* Secure Access of Fire Alarm/Mass Notification System Interface. Access to, and physical protection of, the fire alarm/mass notification system interface shall be determined by the risk analysis and as defined in the emergency response plan.

24.5.11 Autonomous Control Unit (ACU).

24.5.11.1 Where provided, the building ACU shall monitor and control the notification appliance network.

24.5.11.2 Building occupants meeting the requirements of 24.5.2.1 shall be permitted to initiate communications from the ACU.

24.5.11.3 Unless otherwise identified in the emergency response plan, actions taken at the building ACU shall take precedence over actions taken at any remote location, including the LOC, or inputs from a wide-area mass notification system.

24.5.11.4 When there are multiple ACUs controlling the same notification appliance network, only one shall be in control at any given time.

24.5.11.5 When the ACU is integrated with the building fire alarm control unit to form one combined system that performs both functions, the system shall meet the secondary (standby) power requirements of this chapter.

24.5.11.6 When a combined system is installed with an ACU and fire alarm control unit and placed in separate equipment enclosures, the ACU and fire alarm control unit shall be interfaced as required by this chapter.

24.5.11.7 When the ACU is part of a stand-alone mass notification system and no fire alarm system exists, the ACU shall meet the requirements of this chapter.

24.5.12 Local Operating Console (LOC).

24.5.12.1* Building occupants meeting the authorized personnel requirement of 24.5.2.1 shall be permitted to initiate communications from the LOC.

24.5.12.2 The use of lock wire seals or break-glass-type enclosures to house the operating consoles for the system, or equivalent protection against unauthorized use, shall be permitted.

24.5.12.3 Operating controls shall be clearly identified.

24.5.12.4 If there are multiple control locations, only one shall be in control at any given time.

24.5.12.5 The location having control of the system shall be identified by a visual indication at that location.

24.5.12.6 If live voice instructions are provided, they shall override previously initiated signals to the selected notification zone(s) and shall have priority over any subsequent automatically initiated signals to the selected zone(s).

24.5.12.7 Upon initiation of an emergency message, a visual indication shall be provided to the user that the LOC is connected to the audio network.

24.5.12.8 Manual controls shall be permitted to provide visual indication of the on/off status for their associated notification zone.

24.5.12.9 The emergency message shall be an all-call basis unless otherwise permitted by 24.5.12.10.

24.5.12.10 Selective notification zone paging shall be permitted only if the LOC has manual controls with visual indication of the on/off status for each associated notification zone.

24.5.13 Voice Message Priority.

24.5.13.1* The priority of mass notification messages shall be established using the emergency response plan.

24.5.13.2 The local building mass notification system shall have the ability to override the fire alarm system with live voice or manual activation of a higher priority message, but only where that message and operation are approved under the emergency response plan.

24.5.13.3 All other messages shall also be prioritized by using the emergency response plan.

24.5.13.4 When identified by the emergency response plan, messages from the mass notification system shall be permitted to take priority over fire alarm messages and signals.

24.5.13.5 If the fire alarm system is in the alarm mode and a recorded voice message is playing, or the audible signals are sounding, and then the mass notification system is activated, it shall cause deactivation of all fire alarm-initiated audible and visual notification.

24.5.13.6 After the mass notification system relinquishes control, the following shall occur:

- (1) Without an active fire alarm signal, the fire alarm system shall automatically restore to normal operation.
- (2)* With an active fire alarm signal, the fire alarm system shall operate based on the emergency response plan.

24.5.13.7 Overriding of fire alarm audible and visual notification signals shall cause an audible and distinctive visual indication at each affected fire alarm control unit to indicate the MNS is active.

24.5.13.8 The fire alarm signal deactivation function shall be permitted to occur only when both the fire alarm system is in an alarm condition and notification is being given by the mass notification system.

24.5.13.9 When the fire alarm notification is overridden as permitted in 24.5.13.8, all other features of the fire alarm system shall remain unaffected.

24.5.14* Mounting of LOC Controls.

24.5.14.1 Controls that are intended to be accessed by authorized users shall be mounted in accordance with 24.5.14.

24.5.14.2 LOC controls, including switches, microphone, latches, and so forth, shall be located above the finished floor a minimum of 36 in. (910 mm) and a maximum of 48 in. (1.22 m) where the horizontal reach is less than 10 in. (254 mm).

24.5.14.3 If a horizontal reach of 10 in. (254 mm) to 24 in. (610 mm) is required, the maximum elevation shall be limited to 42 in. (1.07 m) above the finished floor and the minimum elevation shall be limited to 28 in. (711 mm).

24.5.14.4 Text and visual indicators, including lamps, screens, displays, instructions, or labels, associated with control or operation shall be visible within all points of elevation between 40 in. (1.02 m) and 60 in. (1.52 m) above the finished floor.

24.5.14.5 Where controls and information are provided in accordance with 24.5.14.2 through 24.5.14.4, provision of additional or redundant controls shall be permitted within the same vicinity at an elevation or reach other than those indicated.

24.5.14.6 Dimensions other than those identified in 24.5.14.2 through 24.5.14.4 shall be permitted when documented within the emergency response plan that ADA guidelines are not applicable, or when otherwise required by the AHJ.

24.5.15 Volume Control.

24.5.15.1 Local controls shall be permitted to adjust volume levels of ancillary functions.

24.5.15.2 Upon activation of an emergency signal, the system shall override any local volume setting to deliver at a preset volume setting that has been established through testing and acceptance of sound level and speech intelligibility as required by this Code.

24.5.16 Visual Notification.

24.5.16.1 Where audible notification is provided, mass notification systems shall also provide visual notification information to serve the deaf or hard of hearing and for high-noise areas.

24.5.16.2 The visual notification required by 24.5.16.1 shall be accomplished using visual notification appliances.

24.5.16.3 In addition to the visual notification appliances required by 24.5.16.1, textual, graphic, or video displays shall be permitted.

24.5.16.4 Transmission of visual notification and messages shall be simultaneous to audible notification and messages.

24.5.17 Visual Appliances.

24.5.17.1 Where visual notification appliances are used, they shall meet the requirements of 24.5.17.2 through 24.5.17.9.

24.5.17.2 Visual notification appliances shall be of a sufficient quantity and intensity and located so as to meet the intent of the design and be in compliance with Section 18.5.

24.5.17.3 Visual notification appliances used in combination systems where the same visual notification appliance is used for both mass notification and fire notification shall comply with the following:

- (1) Be clear or nominal white, meeting the listing requirements of UL 1638, *Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories*, or equivalent
- (2) Have no marking or be marked with the word "ALERT" stamped or imprinted on the appliance
- (3) Be visible to the public

24.5.17.4 In situations where existing notification appliances previously used exclusively for fire alarm applications, and are marked with the word "FIRE," and are to be used for other emergency notification purposes, field modification to the marking shall be permitted, provided that it is accomplished by one of the following methods:

- (1) Replacement of the manufacturer's approved escutcheon or trim plate
- (2) Covering of, or removal of, the word "FIRE" using a manufacturer's approved method
- (3) Installation of a permanent sign directly adjacent or below the notification appliance indicating that it is multipurpose and will operate for fire and other emergency conditions

24.5.17.5 Visual notification appliances with colored lenses shall be marked with the listed effective intensity using the lens color installed.

24.5.17.6 The spacing of colored visual notification appliances shall be in accordance with public mode spacing requirements of Section 18.5 using the effective intensity as the basis for spacing.

24.5.17.7 Where visual notification appliances are used solely for mass notification, the word "ALERT" shall be stamped or imprinted on the appliance and be visible to the public.

24.5.17.8 Where visual notification appliances are used solely for mass notification, they shall be listed to an applicable standard such as UL 1638, *Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories*.

24.5.17.9 Visual notification appliances used for mass notification shall meet the synchronization requirements of Section 18.5.

24.5.18* Textual and Graphical Visual Appliances.

24.5.18.1 Textual and graphical visual notification appliances shall be permitted to be used for primary or supplemental notification.

24.5.18.2* Textual and graphical visual notification shall be considered to be primary notification where it is the only method used to convey emergency mass notification information to the general public or to specific individuals.

24.5.18.3 Primary and supplemental textual and graphical visual appliances shall meet the requirements of Chapter 18.

24.5.18.4 Primary textual and graphical visual appliances other than a main control unit shall be permitted to not have a dedicated primary power circuit as required by Chapter 10 but shall meet all other requirements for the monitoring of primary power and all requirements for secondary power.

24.5.18.5 Textual and graphical visual appliances shall be permitted to be used for nonemergency purposes.

24.5.18.6 Emergency textual and graphical messages shall override nonemergency textual and graphical messages.

24.5.18.7 Supplemental textual and graphical visual appliances that are not monitored for integrity or loss of communication by a control unit shall be provided with visual status indicators, including loss of communication or loss of power, that are clearly visible on the appliance.

24.5.18.8 Addressable primary textual and graphical visual appliances using signaling line circuits shall meet the performance requirements of Section 23.6.

24.5.18.9 Non-addressable primary textual and graphical visual appliance circuits shall meet the performance requirements of Section 23.7.

24.5.19 Tactile Notification Appliances. Where tactile notification appliances are provided for emergency notification, they shall meet the requirements of Section 18.10.

24.5.20* Video Alerting. Video display systems that provide alerts and messages to video appliances shall be permitted to be used to supplement mass notification.

24.5.21 Supplemental Notification. Supplemental notification shall be permitted to provide additional information or more detailed instructions than those transmitted by the primary notification means.

24.5.22 Interfaces. Any abnormal condition that would prevent reliable emergency operation of any interfaced system shall be annunciated both audibly and visibly as a trouble signal at the affected control location.

24.5.22.1 Fire Alarm Control Interface (FACI).

24.5.22.1.1 Where a fire alarm system is installed covering all or part of the same building or other area as the mass notification system, an interface shall be provided between the systems for operational coordination purposes.

24.5.22.1.2 A listed barrier gateway in accordance with 10.3.1, integral with, or attached to, each control unit or group of control units, as appropriate, shall be provided to prevent the other systems from interfering with or controlling the fire alarm system.

24.5.22.1.3* The fire alarm control interface shall coordinate signals to and from each system to accomplish the following:

- (1) Indicate the failure at the system control unit that will be impaired
- (2) Provide an audible and distinctive visual indication at the affected FACU(s) to indicate the MNS is active.
- (3) Cause the fire alarm system to deactivate all audible and visual notification appliances whose operation could interfere with the intelligibility of the mass notification message or that will deliver conflicting information to occupants
- (4) Not permit the fire alarm system to turn off audible and visual notification appliances for special suppression pre-discharge notification required by 24.4.7.1
- (5) Where required by the emergency response plan or by other governing laws, codes, or standards, or by other parts of this Code, or by the authority having jurisdiction, provide for a supervisory signal to a supervising station with a response as directed by the emergency response plan that is indicative of the mass notification system overriding the fire alarm system notification appliances during simultaneous fire and mass notification events

24.5.22.1.4 If the fire alarm control interface is used to broadcast nonemergency messages, music, or other signals over the fire alarm notification appliance circuits, the operation shall meet the requirements of 24.5.15 and 23.8.4.

24.5.22.2 Interfaces to Emergency Control Functions. The mass notification system shall be permitted to provide emergency control functions in accordance with Chapter 21 as required by the emergency response plan and as permitted by the authority having jurisdiction.

24.5.22.2.1 When mass notifications systems are controlling building life safety systems, the mass notifications systems

equipment shall be listed for UL 864, *Control Units and Accessories for Fire Alarm Systems*.

24.5.22.3 Interfaces with Wide-Area Mass Notification Systems.

24.5.22.3.1* Individual building mass notification systems shall be permitted to interface with wide-area mass notification systems.

24.5.22.3.2 The in-building mass notification system shall not be activated or controlled by a wide-area mass notification system, unless the wide-area mass notification system also meets the design and performance requirements of this chapter or has been deemed to be acceptable by the risk analysis and the authority having jurisdiction.

24.5.23 Combination Emergency Communications Systems.

24.5.23.1* When the mass notification system is integrated with the building fire alarm control unit to form one combined system that performs both functions, the system shall comply with this chapter.

24.5.23.2 All components that affect the operation of the fire alarm system shall be listed for fire alarm use and shall be in compliance with applicable standards such as UL 864, *Control Units and Accessories for Fire Alarm Systems*.

24.5.24 Public Address (PA) Systems Used for Emergency Communications.

24.5.24.1 The voice communications or public address system that is to be used for mass notification shall be evaluated by the emergency communications system designer, as defined in Chapter 10, to determine applicability and compliance.

24.5.24.2* Evaluation documentation in accordance with 7.3.9 shall be provided by the emergency communications system designer attesting to the fact that the public address system has been evaluated and meets the needs of the emergency response plan and, where not compliant with the prescriptive requirements of Chapter 24, shall provide equivalent system performance requirements.

24.5.25 Public Address (PA) System Interface with Facility Fire Alarm System.

24.5.25.1 When a public address system is used to deliver mass notification messages, the public address system shall provide (either internally as a design feature or with an approved or listed external controller) for a signal to control the facility's fire alarm system for the purpose of deactivating the fire alarm audible and visual notification appliances in accordance with 24.5.22.1.

24.5.25.2 All of the following features shall be provided in, or added to, the public address system:

- (1) Emergency messages must have priority over non-emergency messages.
- (2) All individual or zone loudspeaker volume controls must default to the emergency sound level when used for an emergency mass notification message.
- (3) When monitoring of circuit integrity is provided by the public address system, monitoring must continue, even if local loudspeaker volume controls are placed in the "off" position.
- (4) The required visual notification appliance network (i.e., visual notification appliances and textual signs) must be provided where required.

24.6* Wide-Area Mass Notification Systems.

24.6.1 Voice Messages.

24.6.1.1 Voice messages shall comply with the requirements of 24.3.1.

24.6.1.2 Where required by the emergency response plan, multiple languages shall be permitted to be used.

24.6.1.3 Where required by the emergency response plan, specific warning tones shall be provided.

24.6.2* Password Protection. Wide-area mass notification systems shall have multiple levels of password protection access control, including levels for system administrators, system operators, maintainers, supervisors, and executives, or other means to limit access to system controls shall be provided based on the emergency response plan.

24.6.3* External Connections. Wide-area mass notification systems shall be permitted to connect to regional mass notification systems and public emergency alarm reporting systems as defined in this Code, and public reporting systems as defined in NFPA 1221.

24.6.4 Emergency Command Center. Refer to Section 24.11 for requirements of an emergency command center.

24.6.5* High Power Loudspeaker Array (HPLA). When required by the risk analysis, high power loudspeaker arrays (HPLAs) shall be provided, installed, and maintained.

24.6.5.1 The HPLA shall be arranged in such a manner to provide intelligible voice and audible tone communications.

(A) When multiple HPLAs are used, they shall be arranged in physical or virtual notification zones so that each notification zone can be individually controlled by the emergency command center.

(B)* HPLAs shall be designed to maintain the intelligibility of voice signals within the notification zone in accordance with the requirements of Chapter 18.

24.6.5.2 Secondary power for HPLAs used for wide-area mass notification systems shall have sufficient capacity to operate the unit for a minimum of 3 days in standby, followed by 60 minutes of operation at full load.

24.6.5.3 An HPLA shall have the capability to provide voice communications and tones as determined by the emergency response plan.

24.6.5.4* An HPLA shall operate in the environment in which it is located, considering such factors as temperature, humidity, wind, dust, vibration, and other environmental factors.

24.6.6 High Power Loudspeaker Array Enclosures.

24.6.6.1 Enclosures for HPLAs shall be of the NEMA 4 or 4X type.

24.6.6.2 HPLA enclosures shall have intrusion detection that signals the emergency command center.

(A) The signal shall be initiated whenever the door of the enclosure is in the open position.

(B) The transmitted signal shall be a latching supervisory signal.

24.6.7 High Power Loudspeaker Array Mounting.

24.6.7.1 HPLAs shall be mounted at a minimum mounting height that is based on the rated output of the array.

24.6.7.2* HPLAs shall be installed at a height and orientation to prevent hearing damage to anyone in the immediate vicinity of the appliances.

24.6.7.3 All external conductors (conductors passing outside of the HPLA equipment cabinet) shall be provided with surge suppression to minimize potential equipment damage from lightning strikes.

24.6.8 High Power Loudspeaker Array Noise Consideration. HPLA notification zones shall not be used to provide mass notification inside any structures.

24.6.9* High Power Loudspeaker Array Structural Loads, Wind, and Seismic Design. HPLAs and their supporting structures shall meet the structural, wind, and seismic loads as identified in the risk analysis.

24.6.10 Textual Visual Appliances. Textual visual appliances shall meet the requirements of Section 18.9 and 24.5.18.

24.6.10.1 After loss of primary power, primary textual visual notification appliances shall have sufficient secondary power to operate for a minimum of 2 hours of continuous display time during an emergency event.

24.6.10.2 Scrolling message boards shall be provided with means to control the scrolling rate.

24.6.11 Interfaces with Wide-Area Mass Notification Systems. Interfaces between wide-area mass notification systems and in-building mass notification systems, other alert and notification systems, regional mass notification systems, and off-premises interfaces shall have a standard interface method (such as an audio line-level output and multiple relay contacts) or supply the necessary communications protocols to provide interoperability and a secure communications link.

24.6.11.1 The interface shall be such that the primary function of both systems shall not be compromised.

24.6.11.2 The interface shall be monitored for integrity in accordance with 10.6.9, Section 10.19, and Section 12.6, so that an abnormal condition that could prevent reliable system operation is audibly and visibly annunciated as a trouble signal at both systems' control units.

24.6.12 Control Hierarchy. There shall be a predefined control hierarchy between the wide-area mass notification system, the in-building mass notification system, and the regional mass notification system for information flow from the remote control center, as well as information from specific locations.

24.6.13 Communications Links.

24.6.13.1 The wide-area mass notification system, including communications links, shall minimize the potential for interference from jamming, spoofing, hacking, eavesdropping, or other malicious acts.

24.6.13.2 The wide-area mass notification system shall have a primary and redundant communications link with minimal functional and spatial interconnection with each other.

24.6.13.3 Wide-area and in-building mass notification systems equipment and interface methods connecting to or utilizing public emergency alarm reporting systems and associated communications infrastructure shall be electrically and operationally compatible so as not to interfere with the public emergency alarm reporting systems.

24.7* Distributed Recipient Mass Notification Systems (DRMNS).

24.7.1* Overview. Distributed recipient mass notification system (DRMNS) alerting shall not be used in lieu of required audible and visual alerting mass notification systems but shall be integrated with mass notification systems whenever possible.

24.7.2* Targeted Recipients. The DRMNS shall be capable of sending alert messages to target recipients.

24.7.3 Network Security Compliance. DRMNSs shall be installed behind the appropriate Internet system firewalls to protect the integrity of the network.

24.7.4 Network Architecture. The network shall be provided with net-centric architecture that fully supports local designated standards and security requirements.

24.7.5* Delivery Methods. The DRMNS shall be capable of sending alert messages to end users (recipients) via multiple delivery methods.

24.7.6* Backup Distributed Recipient Mass Notification Systems. A DRMNS used to send emergency messages shall be provided with a backup configuration to facilitate distribution of messages.

24.8* Two-Way, In-Building Wired Emergency Services Communications Systems.

24.8.1 Two-way telephone communications equipment shall be listed for two-way telephone communications service and installed in accordance with Section 24.8.

24.8.2 Two-way telephone communications service, if provided, shall be for use by the fire service and collocated with the in-building fire emergency voice/alarm communications equipment.

24.8.3 Monitoring of the integrity of two-way telephone communications circuits shall be in accordance with 10.19.2.

24.8.4 Additional uses shall be permitted to include signaling and communications for a building fire warden organization and signaling and communications for reporting a fire and other emergencies (e.g., voice call box service, signaling, and communications for guard's tour service).

24.8.5 Variation of equipment and system operation provided to facilitate additional use of the two-way telephone communications service shall not adversely affect performance when used by the fire service.

24.8.6* Two-way telephone communications service shall be capable of permitting the simultaneous operation of any five telephone stations in a common talk mode.

24.8.7 A notification signal at the control equipment, distinctive from any other alarm, supervisory, or trouble signal, shall indicate the off-hook condition of a calling telephone circuit.

24.8.8 Where a selective talk telephone communications service is supplied, a distinctive visual indicator shall be furnished

for each selectable circuit, so that all circuits with telephones off-hook are continuously and visibly indicated.

24.8.9 A means for silencing the audible call-in signal sounding appliance shall be permitted, where both of the following conditions are met:

- (1) The means is key-operated or located in a locked cabinet or provided with protection to prevent use by unauthorized persons.
- (2) The means operates a visual indicator and sounds a trouble signal whenever the means is in the silence position and no telephone circuits are in an off-hook condition.

24.8.10 If a selective talk system is used, means as specified in 24.8.9 shall be permitted, provided that subsequent telephone circuits going off-hook operate the distinctive off-hook signal.

24.8.11 Two-way telephone systems with common talk mode (i.e., a conference or party line circuit) shall be permitted.

24.8.12 In buildings provided with a two-way telephone communications system, at least one telephone station or jack shall be provided at the following locations:

- (1) Each floor level
- (2) Each notification zone
- (3) Each elevator cab
- (4) Elevator lobbies
- (5) Elevator machine room(s)
- (6) Emergency and standby power room(s)
- (7) Fire pump room(s)
- (8) Area(s) of refuge
- (9) Each floor level inside an enclosed exit stair(s)
- (10) Other room(s) or area(s) as required by the authority having jurisdiction

24.8.13 If the two-way telephone system is intended to be used by fire wardens in addition to the fire service, the minimum requirement shall be a selective talk system, where phones are selected from the control location.

24.8.14 Telephone circuits shall be selectable from the control location either individually or, if approved by the authority having jurisdiction, by floor or stairwell.

24.8.15 If the control equipment provided does not indicate the location of the caller (common talk systems), each telephone station or telephone jack shall be clearly and permanently labeled to allow the caller to identify his or her location to the control center by voice.

24.8.16 If telephone jacks are provided, two or more portable handsets, as determined by the authority having jurisdiction, shall be stored at each control center for use by emergency responders.

24.8.17 Wall-mounted telephone appliances or related jacks shall be not less than 36 in. (910 mm) and not more than 66 in. (1.68 m) above floor level with clear access to the appliance that is at least 30 in. (760 mm) wide.

24.8.18 If accessible to the general public, one telephone appliance per location shall be not more than 48 in. (1.22 m) above floor level.

24.8.19* All circuits necessary for the operation of two-way telephone communications systems shall be installed in accordance with the pathway survivability requirements in 24.3.14.7.

24.9* Two-Way Radio Communications Enhancement Systems. All in-building two-way radio communications enhancement systems shall be designed, installed, and maintained in accordance with NFPA 1221.

24.10* Two-Way Emergency Communications Systems for Rescue Assistance.

24.10.1 Systems used for area of refuge emergency communications systems, stairway communications systems, elevator landing communications systems, and occupant evacuation elevator lobby communications systems shall be listed in accordance with applicable standards, such as UL 2525, *Two-way Emergency Communications Systems for Rescue Assistance*.

24.10.2 Where required by the enforcing authority, governing laws, codes, or standards, any communications system specified in this section shall be installed in accordance with 24.10.2 through 24.10.14.

24.10.2.1 The secondary power supply for two-way emergency communications systems shall be capable of operating the system under quiescent load for a minimum of 24 hours and then subsequently during a fire or other emergency condition for a period of 4 hours with all remote call stations activated and all master control stations annunciating the calls.

24.10.2.2 The communications system shall be capable of monitoring additional power supplies for communications equipment vital to the transmission of off-premises signals.

24.10.3* The communications system shall comprise remotely located communications stations (remote call stations), a master control station, and a primary and secondary power supply as required by Section 10.6.

24.10.3.1 When a remote call station(s) is activated by a building occupant(s), a two-way live voice communication shall be required to operate between the remote call station(s) and a constantly attended location.

24.10.3.2* The master control station shall be installed in a central control point within the building.

24.10.3.3* The constantly attended location shall be located either within the building or at a monitoring location and be approved by the authority having jurisdiction.

24.10.4 The remote call stations and the master control station shall communicate with each other via pathways based on their performance capabilities under abnormal (fault) conditions in accordance with the requirements for Class A, Class B, Class N, or Class X pathways specified in Chapter 12.

24.10.5 All pathways between the remote call stations and the master control station shall be monitored for integrity.

24.10.6* If the central control point is not constantly attended, the system shall have a timed automatic communications capability to connect with an off-premises constantly attended monitoring location approved by the authority having jurisdiction, where trained personnel can initiate the appropriate response.

24.10.7* In the event of an off-premises connection, a signal shall be transmitted to the off-premises monitoring location, identifying the specific building prior to initiating the live voice two-way communication.

24.10.8 Two-way emergency communications systems shall have the capability of transmitting a verbal signal to identify the specific building address to off-premises monitoring personnel before operators complete the connection to the remote call station.

24.10.9* The physical locations of the remote call stations and the master control station shall be as designated by the building code in force and the system designer and approved by the authority having jurisdiction.

24.10.10 The specific location of each active remote call station shall be identified on the master control station display on a floor and area basis in accordance with 24.10.11.

24.10.11 Where all active calls are not simultaneously displayed, the master control stations shall provide the following:

- (1) Previously answered calls shall be capable of being prioritized as urgent on the master control station to differentiate more urgent life safety related calls from less urgent calls.
- (2) A minimum of 8 active call station identifiers shall be visible in the following order of priority:
 - (a) Previously unanswered calls, oldest first
 - (b) Previously answered calls, prioritized as urgent, oldest first
 - (c) Previously answered calls, not prioritized as urgent, oldest first

24.10.12 The remote call stations shall provide for hands-free, two-way communication and provide an audible and a visual signal to indicate communication has occurred.

24.10.13 Signage.

24.10.13.1 Directions for the use of the two-way communications system, instructions for summoning assistance via the two-way communications system, and written identification, including in braille, of the location shall be posted adjacent to the two-way communications system.

24.10.13.2 Signage shall comply with ICC/ANSI A117.1, *Accessible and Usable Buildings and Facilities*, requirements for visual characters.

24.10.14* The two-way communications systems specified in this section, as intended for different types of locations, shall be permitted to be integrated with each other or other emergency communications systems provided they are installed in accordance with Section 24.10.

24.10.15* Training for Two-Way Communications Systems. Operators of two-way communications systems master control stations shall be trained and qualified.

24.11* Information, Command, and Control. The requirements of Section 24.11 shall apply to the communications methods and equipment used to receive and transmit information between premises sources or premises systems and the emergency command center(s).

24.11.1* Emergency Command Center for Emergency Communications Systems.

24.11.1.1* The location and accessibility of the emergency command center shall be determined by the risk analysis and approved by the emergency management coordinator.

24.11.1.2 The emergency command center shall contain the following where provided:

- (1) In-building fire emergency voice/alarm communications system equipment, including the following:
 - (a) Fire alarm system controls
 - (b) Fire alarm system annunciator
 - (c) In-building fire emergency voice/alarm communications system controls
 - (d) Two-way in-building wired emergency services communications system (i.e., fire fighters' telephone system) equipment
- (2) In-building mass notification system equipment controls
- (3) Area of refuge emergency communications system equipment
- (4) Elevator landing or occupant evacuation elevator lobby emergency communications system equipment
- (5) Distributed recipient MNS control stations where provided
- (6) Tables and chairs to accommodate emergency management staff
- (7) Other equipment/information deemed necessary by the facility emergency response plan such as the following:
 - (a) Displays indicating the location of the elevators and whether they are operational
 - (b) Status indicators and controls for air-handling systems
 - (c) Fire fighter's control panel for smoke control systems
 - (d) Fire department communications unit
 - (e) Controls for unlocking stairway doors simultaneously
 - (f) Security systems
 - (g) Emergency and standby power status indicators
 - (h) Telephone for emergency use with controlled access to the public telephone system
 - (i) Schematic building plans indicating the typical floor plan and detailing the building core, means of egress, fire protection systems, security systems, fire-fighting equipment, and fire department access
 - (j) Generator supervision devices, manual start, and transfer features
 - (k) Other monitoring, control, information display, and management systems associated with operation of the emergency command center

24.11.1.3 The level of security at the emergency command center shall be defined in the emergency response plan.

24.11.1.4* Emergency command center personnel requirements shall be defined in the documentation in the emergency response plan.

24.11.1.5* Individuals expected to operate an emergency communications system shall be properly trained in the purpose, functions, procedures, and anticipated actions of such systems.

24.11.1.6 The emergency command center shall be capable of receiving voice messages by telephone or radio and transmitting via equipment at the emergency command center.

24.11.1.7 The emergency command center operator shall have the ability to monitor inputs/sensors and control output

devices automatically, manually, or automatically with operator override.

24.11.2 Emergency Communications Control Unit (ECCU).

24.11.2.1 An emergency communications control unit (ECCU), where identified by the risk analysis, and defined in the emergency response plan, shall be provided at each emergency command center.

24.11.2.2 The system operator shall be able to broadcast live voice signals or activated prerecorded voice messages, tones, and other signals.

24.11.2.3 The signals shall be selectable to individual buildings; zones of buildings; individual outdoor loudspeaker arrays; zones of outdoor loudspeaker arrays; or a building, multiple buildings, outside areas, or a combination of these, in accordance with the emergency response plan established for the premises.

24.11.2.4 The central control emergency communications control unit shall automatically or manually assign priorities to all transmitted signals.

24.11.2.5 In wide-area mass notification systems, the emergency command center shall have a primary emergency communications control unit.

24.11.2.6 Multiple emergency communications control units shall be permitted.

24.11.3* Signals. Where identified by the risk analysis and defined in the emergency response plan, the emergency communications control unit shall be permitted to automatically or manually send different messages or signals to different locations.

24.11.4 Power Supplies.

24.11.4.1 All control units shall meet the power supply requirements of Section 10.6 and 24.11.4.2.

24.11.4.2 The power supply for the emergency command center for emergency communications systems shall include an uninterrupted power source with capacity sufficient to support the emergency response plan established for the specific premises.

24.11.5 Transmission. Signals shall be capable of being automatically or manually transmitted to a regional or national emergency response center or to other nearby facilities that have a need to be alerted of the emergency.

24.11.6* Other Systems. The emergency command center shall be capable of interfacing with and controlling other notification systems, such as telephone dialers, tone alert systems, computer network alerting systems, pagers, facsimile machines, textual devices, and other visual control signs, as determined by the emergency response plan.

24.11.7 Inspection, Testing, and Maintenance. Inspection, testing, and maintenance shall be performed on a periodic basis, as described in Chapter 14, to verify and ensure proper system operation and readiness.

24.12* Performance-Based Design of Mass Notification Systems. The requirements of Section 24.12 shall apply to mass notification systems designed using performance-based practices.

24.12.1 Goals and Objectives. The performance-based design shall meet the following goals and objectives:

- (1) The design criteria, design brief, system performance, and testing criteria are developed in accordance with this section.
- (2) The system disseminates information to the target audience in an accurate and timely manner.
- (3) The design and performance criteria are specific to the nature and anticipated risks of each location.
- (4) Message initiation can be effected by all responding entities responsible for the safety and security of those affected by the events of concern.

24.12.2* Qualifications. The performance-based design and risk analysis shall be prepared by a design professional certified or approved by the authority having jurisdiction.

24.12.3 Independent Review. The authority having jurisdiction shall be permitted to require an approved, independent third party to review the proposed design brief and provide an evaluation of the design to the authority having jurisdiction.

24.12.4 Final Determination. The authority having jurisdiction shall make the final determination as to whether the performance objectives have been met.

24.12.5 Maintenance of Design Features. The design features required for the system to continue to meet the performance goals and objectives of this Code shall be maintained for the life of the building.

24.12.6 Performance Criteria.

24.12.6.1 General. All designs shall meet the goals and objectives specified in 24.12.1 and shall be considered equivalent, provided that the performance criterion in 24.12.6.2 is met, the design team concurs with the design, and the risk analysis considers the following factors:

- (1) Number of persons to be notified
- (2) Occupancy characteristics
- (3) Anticipated threat
- (4) Staff capabilities
- (5) Coordination with the emergency response plan

24.12.6.2 Performance Criterion. The performance criterion shall include timely and accurate notification of all persons within the boundaries of the mass notification system in a medium to which they can respond when given directions by responding entities.

24.12.6.3* Design Team. The design team shall be comprised of the design professional, the owner or owner's representative, representatives of the authority having jurisdiction, and representatives of the responding entities.

24.12.6.4 Risk Analysis. The design of the mass notification system shall be based upon a risk analysis prepared in accordance with 24.3.12 specific to the nature and anticipated risks of each facility for which it is designed.

24.12.6.5 Operational Status and System Effectiveness. The performance of the system shall reflect the documented performance and reliability of the components of those systems or features, unless design specifications are incorporated to modify the expected performance.

24.12.6.5.1 The inclusion of trained employees as part of the mass notification system shall be identified and documented.

24.12.6.5.2 Emergency Response Personnel. The design shall consider the characteristics or other conditions related to the availability, speed of response, effectiveness, roles, and other characteristics of emergency response personnel.

24.12.6.6* Design Brief. The design of the mass notification system shall include the preparation of a design brief that is prepared utilizing recognized performance-based design practices.

24.12.6.6.1 Design specifications and briefs used in the performance-based design shall be clearly stated and shown to be realistic and sustainable.

24.12.6.6.2 Specific testing requirements that are necessary to maintain reliable performance shall be stated in the design brief.

24.13 Documentation for Emergency Communications Systems.

24.13.1 New Systems. Documentation requirements for new emergency communications systems shall comply with Sections 7.3 through 7.8 in addition to the minimum requirements of Section 7.2.

Chapter 25 Reserved

Chapter 26 Supervising Station Alarm Systems

26.1* Application. The performance, installation, and operation of alarm systems at a continuously attended supervising station and between the protected premises and the continuously attended supervising station shall comply with the requirements of this chapter.

26.1.1* Where any system regulated by this Code sends signals to a supervising station, the entire system shall become a supervising station alarm system.

26.1.2 The requirements of Chapters 7, 10, 11, 12, 14, and 23 shall apply unless otherwise noted in this chapter.

26.1.3 The requirements of this chapter shall not apply to Chapter 29 unless otherwise noted.

26.2 General.

26.2.1 Alarm Signal Disposition.

26.2.1.1 Alarm signals initiated by manual fire alarm boxes, automatic fire detectors, waterflow from the automatic sprinkler system, or actuation of other fire suppression system(s) or equipment shall be treated as fire alarm signals.

26.2.1.2* Except as permitted by 26.2.2 and 29.10.9.7, all fire alarm signals received by a supervising station shall be immediately retransmitted to the communications center.

26.2.1.3 Fire alarm signals received at the supervising station shall be retransmitted to the communications center by one of the following methods:

- (1) Signals that are identified by zone at the supervising station shall be retransmitted by zone to the communications center.
- (2) Signals that are identified as an individual point or points at the supervising station shall be retransmitted by point or points to the communications center.

- (3)* Signals that are received at the supervising station as events shall be retransmitted by event to the communications center.

26.2.1.4 Retransmission of subsequent signals shall comply with 26.2.1.4.1 and 26.2.1.4.2.

26.2.1.4.1 The supervising station shall continue to retransmit subsequent signals from a protected premises to the communications center until advised otherwise by the communications center.

26.2.1.4.2 Subsequent signals that are suppressed by the supervising station as directed by the communications center shall be permitted to be suppressed for a maximum of one hour.

26.2.2* Fire Alarm Signal Verification. For applications other than those addressed under the scope of 29.10.9.7, supervising station personnel shall attempt to verify alarm signals prior to reporting them to the communications center only where all the following conditions exist:

- (1)* Alarm signal verification is required by the responsible fire department for a specific protected premises.
- (2) Documentation of the requirement for alarm signal verification is provided by the responsible fire department to the supervising station and the protected premises.
- (3) If the requirement for verification changes, the responsible fire department notifies the supervising station and the protected premises.
- (4)* The verification process does not take longer than 90 seconds from the time the alarm signal is received at the supervising station until the time that retransmission of the verified alarm signal is initiated.
- (5) Verification of a true fire is received from anyone on premises or verification of an unwanted alarm signal is received only from a pre-assigned list of authorized personnel within the protected premises.
- (6)* Verified alarm signals are immediately retransmitted to the communications center and include information that the signal was verified at the protected premises to be an emergency.
- (7)* Alarm signals where verification is not conclusive are immediately retransmitted to the communications center.
- (8)* Alarm signals that are verified as unwanted alarms shall be reported to the responsible fire department in a manner and at a frequency specified by the responsible fire department.

26.2.3 Alarm Signal Content. Where required by the enforcing authority, governing laws, codes, or standards, alarm signals transmitted to a supervising station shall be by addressable device or zone identification.

26.2.4 Carbon Monoxide Signal Disposition.

26.2.4.1 Carbon Monoxide Alarm Signal Disposition.

26.2.4.1.1 A carbon monoxide alarm signal shall take precedence over supervisory or trouble signals.

26.2.4.1.2 The actuation of a carbon monoxide detector or system shall be distinctively indicated as a carbon monoxide alarm signal.

26.2.4.1.3* Servicing of a system in alarm that cannot be reset shall be in accordance with Chapter 14 and shall occur within 4 hours of the carbon monoxide alarm signal.

26.2.4.1.4 Upon receipt of a carbon monoxide alarm signal, supervising station personnel shall perform the following actions in the order listed:

- (1) Where required by the emergency response agency, immediately retransmit indication of the carbon monoxide alarm signal to the communications center
- (2) Contact the responsible party(s) in accordance with the notification plan
- (3) Once contacted, inform the subscriber to take one of the actions in (a) or (b):
 - (a) Where the subscriber has a carbon monoxide emergency response plan, implement the plan
 - (b) Where the subscriber has no carbon monoxide emergency response plan:
 - i. Immediately move to fresh air, either outdoors or by an open door or window
 - ii. Verify that all occupants are accounted for
 - iii. Do not re-enter the premises or move away from an open door or window until the emergency service responders have arrived, the premises have been aired out, and the alarm returns to its normal condition

26.2.4.2 Carbon Monoxide Trouble Signal Disposition.

26.2.4.2.1 Upon receipt of a carbon monoxide trouble signal, the responsible party(s) shall be notified.

26.2.4.2.2 Servicing of a system in trouble shall be in accordance with Chapter 14 and shall occur within 4 hours of the trouble indication.

26.2.4.2.3 Carbon monoxide end-of-life signals, if provided, shall be treated as trouble signals.

26.2.5 Restoral Signals.

26.2.5.1 All supervising station fire alarm systems shall be programmed to report restoral signals to the supervising station of all alarm, supervisory, and trouble signals upon restoration of the activation.

26.2.5.2 Except as permitted in 26.2.5.2.2, any signal received by the supervising station that has not restored to normal condition within 24 hours of initial receipt shall be redisplayed to an operator as a nonrestored signal.

26.2.5.2.1 A nonrestored signal that is redisplayed shall be reported to the subscriber.

26.2.5.2.2* Paragraph 26.2.5.2 shall not apply to signals received as a result of a scheduled impairment.

26.2.6 Multiple Buildings. For multiple building premises, the requirements of 10.18.5.3 shall apply to the alarm, supervisory, and trouble signals transmitted to the supervising station.

26.2.7* Change of Service.

26.2.7.1* Supervising station customers or clients and the authority having jurisdiction shall be notified in writing by the new supervising station within 30 calendar days of any change of service provider that results in signals from the client's property being handled by a new supervising station.

26.2.7.2 Where the new provider of supervising station services covered by 26.2.7.1 also provides the required testing, the new provider shall test zones, points, and signals from each

affected property in accordance with the requirements of Chapter 14 at or prior to the next scheduled periodic test.

26.2.7.3 Where the new provider of supervising station services covered by 26.2.7.1 does not provide the required testing, the new provider shall notify the alarm system owner of the need to test zones, points, and signals from each affected property in accordance with the requirements of Chapter 14 prior to or at the next scheduled periodic test.

26.2.7.4 The supervising station shall notify the authority having jurisdiction prior to terminating service.

26.2.8 Supervising Station Signal Processing Equipment. Signal processing equipment located at the supervising station listed to UL 60950-1, *Information Technology Equipment — Safety — Part 1: General Requirements*, and used for computer-aided alarm and supervisory signal processing shall not be required to comply with 10.3.5 provided it is installed and operated conforming to UL 1981, *Central Station Automation Systems*, within an environment that is maintained at a level within the temperature, humidity, and voltage rating range of the equipment, and the equipment manufacturer's published instructions are available for examination.

26.2.9 Qualification of Supervising Station Operators. Supervising station operators shall be qualified in accordance with the requirements of 10.5.5.

26.2.10 Emergency Monitoring Locations.

26.2.10.1 Upon an emergency declaration made by a national, state, or local authority that results in a business disruption event that inhibits normal operation of a supervising station, fire alarm system signals shall be permitted to be received at alternate locations other than a listed central station, proprietary supervising station, or remote supervising station.

26.2.10.2 The provision of 26.2.10.1 shall be permitted to remain in effect for the duration of the emergency declaration.

26.2.10.3 Specific authorization by local authorities having jurisdiction shall not be required for emergencies declared by a higher authority.

26.2.10.4 The provision of 26.2.10.1 shall be permitted to remain in place for not more than 30 calendar days following the termination of the declared emergency.

26.3 Central Station Service Alarm Systems. Alarm systems used to provide central station service shall comply with the general requirements and the use requirements of Section 26.3.

26.3.1 System Scope. Alarm systems for central station service shall include the central station physical plant, exterior communications channels, subsidiary stations, and alarm and signaling equipment located at the protected premises.

26.3.2* Service Scope. Section 26.3 shall apply to central station service, which consists of the following elements:

- (1) Installation of alarm transmitters
- (2) Alarm, guard, supervisory, and trouble signal monitoring
- (3) Retransmission
- (4) Associated record keeping and reporting
- (5) Testing and maintenance
- (6) Runner service

26.3.3 Contract Requirements. The central station service elements shall be provided under contract to a subscriber by a prime contractor that has a listing for central station fire alarm services.

26.3.3.1 The prime contractor shall be responsible for code-compliant service delivery, regardless of any subcontracting arrangements involved in the delivery of service.

26.3.3.2 Signal monitoring, retransmission, and associated recordkeeping and reporting shall be provided by a company that has a listing for central station alarm services covering these elements.

26.3.4* Indication of Central Station Service. The prime contractor shall conspicuously indicate that the alarm system providing service at a protected premises complies with all the requirements of this Code through the use of a systematic follow-up program under the control of the organization that has listed the prime contractor.

26.3.4.1* Documentation indicating Code compliance of the alarm system shall be issued by the organization that has listed the prime contractor.

26.3.4.2 The documentation shall include, at a minimum, the following information:

- (1) Name of the prime contractor involved with the ongoing Code compliance of the central station service
- (2)* Full description of the alarm system as installed
- (3) Issue and expiration dates of the documentation
- (4) Name, address, and contact information of the organization issuing the document
- (5) Identification of the authority(ies) having jurisdiction for the central station service installation

26.3.4.3 The documentation shall be physically posted within 3 ft (1 m) of the control unit, and copies of the documentation shall be made available to the authority(ies) having jurisdiction upon request.

26.3.4.4 A central repository of issued documentation, accessible to the authority having jurisdiction, shall be maintained by the organization that has listed the prime contractor.

26.3.4.5* Alarm system service that does not comply with all the requirements of Section 26.3 shall not be designated as central station service.

26.3.4.6* For the purpose of Section 26.3, the subscriber shall notify the prime contractor, in writing, of the identity of the authority(ies) having jurisdiction.

26.3.4.7 The authority(ies) having jurisdiction identified in 26.3.4.2(5) shall be notified within 30 calendar days of the expiration or cancellation by the organization that has listed the prime contractor.

26.3.4.8 The subscriber shall surrender expired or canceled documentation to the prime contractor within 30 days of the termination date.

26.3.5 Facilities.

26.3.5.1 The central station building or that portion of a building occupied by a central station shall conform to the construction, fire protection, restricted access, emergency lighting, and power facilities requirements of the latest edition of UL 827, *Central-Station Alarm Services*.

26.3.5.2 Subsidiary station buildings or those portions of buildings occupied by subsidiary stations shall conform to the construction, fire protection, restricted access, emergency lighting, and power facilities requirements of the latest edition of UL 827, *Central-Station Alarm Services*.

26.3.5.2.1 All intrusion, fire, power, and environmental control systems for subsidiary station buildings shall be monitored by the central station in accordance with 26.3.5.

26.3.5.2.2 The subsidiary facility shall be inspected at least monthly by central station personnel for the purpose of verifying the operation and condition of all supervised equipment, telephones, energy storage systems, batteries, and generators, in accordance with the manufacturer's published instructions.

26.3.5.2.3 In the event of the failure of equipment at the subsidiary station or the communications channel to the central station, a backup shall be operational within 90 seconds.

26.3.5.2.4 With respect to 26.3.5.2.3, restoration of a failed unit shall be accomplished within 5 days.

26.3.5.2.5 Each communications channel shall be continuously supervised between the subsidiary station and the central station.

26.3.5.2.6 When the communications channel between the subsidiary station and the supervising station fails, the communications shall be switched to an alternate path.

26.3.5.2.7 Managed facilities-based voice networks shall be used only to provide an alternate path between the subsidiary station and the supervising station.

26.3.5.2.8 In the subsidiary station, there shall be a communications path, such as a cellular telephone, that is independent of the telephone cable between the subsidiary station and the serving wire center.

26.3.5.2.9 A plan of action to provide for restoration of services specified by this Code shall exist for each subsidiary station.

26.3.5.2.9.1 This plan shall provide for restoration of services within 4 hours of any impairment that causes loss of signals from the subsidiary station to the central station.

26.3.5.2.9.2 An exercise to demonstrate the adequacy of the plan shall be conducted at least annually.

26.3.6 Equipment.

26.3.6.1 The central station and all subsidiary stations shall be equipped so as to receive and record all signals in accordance with 26.6.6.

26.3.6.2 Circuit-adjusting means for emergency operation shall be permitted to be automatic or to be provided through manual operation upon receipt of a trouble signal.

26.3.6.3 Computer-aided alarm and supervisory signal-processing hardware and software shall be listed for the purpose.

26.3.6.4 Power supplies shall comply with the requirements of Chapter 10.

26.3.6.5 Transmission means shall comply with the requirements of Section 26.6.

26.3.6.6* Two independent means shall be provided to retransmit an alarm signal to the designated communications center.

26.3.6.6.1 The use of a universal emergency number, such as the 911 public safety answering point, shall not meet the intent of this Code for the principal means of retransmission.

26.3.6.6.2 If the principal means of retransmission is not equipped to allow the communications center to acknowledge receipt of each alarm report, both means shall be used to retransmit.

26.3.6.6.3 The retransmission means shall be tested in accordance with Chapter 14.

26.3.6.6.4 The retransmission signal and the time and date of retransmission shall be recorded at the central station.

26.3.7 Personnel.

26.3.7.1 The central station shall have not less than two qualified operators on duty at the central station at all times to ensure disposition of signals in accordance with the requirements of 26.3.8.3.

26.3.7.2 Operation and supervision shall be the primary functions of the operators, and no other interest or activity shall take precedence over the protective service.

26.3.8 Procedures.

26.3.8.1 The procedural requirements outlined in Section 26.2 shall be followed.

26.3.8.2 The additional procedural requirements outlined in 26.3.8 shall also be followed.

26.3.8.3 Disposition of Signals.

26.3.8.3.1 Alarm Signals. The central station shall perform the following actions:

- (1)* Retransmit the alarm to the communications center in accordance with 26.2.1 unless the signal is a result of a prearranged test.
- (2) Dispatch a runner or technician to the protected premises to arrive within 2 hours after receipt of an alarm signal if equipment needs to be manually reset by the prime contractor. Except where prohibited by the authority having jurisdiction, the runner or technician shall be permitted to be recalled prior to arrival at the premises if a qualified representative of the subscriber at the premises can provide the necessary resetting of the equipment and is able to place the system back in operating condition.
- (3) Immediately notify the subscriber unless the signal is a result of a prearranged test.
- (4) Provide notice to the subscriber or authority having jurisdiction, or both, if required.

26.3.8.3.2 Guard's Tour Supervisory Signal.

26.3.8.3.2.1 Upon failure to receive a guard's tour supervisory signal within a 15-minute maximum grace period, the central station shall perform the following actions:

- (1) Communicate without unreasonable delay with personnel at the protected premises

- (2) Dispatch a runner to the protected premises to arrive within 30 minutes of the delinquency if communications cannot be established
- (3) Report all delinquencies to the subscriber or authority having jurisdiction, or both, if required

26.3.8.3.2.2 Failure of the guard to follow a prescribed route in transmitting signals shall be handled as a delinquency.

26.3.8.3.3* Supervisory Signals. Upon receipt of a supervisory signal that is not prearranged, the central station shall perform the following actions:

- (1)* Communicate immediately with the persons designated by the subscriber and notify the fire department, law enforcement agency, or both when required by the authority having jurisdiction
- (2) Dispatch a runner or maintenance person to arrive within 2 hours to investigate unless the supervisory signal is cleared in accordance with a scheduled procedure determined by 26.3.8.3.3(1)
- (3) Notify the authority having jurisdiction and the subscriber when sprinkler systems or other fire suppression systems or equipment have been wholly or partially out of service for 8 hours
- (4) When service has been restored, provide notice to the subscriber and the authority having jurisdiction of the nature of the signal, the time of occurrence, and the restoration of service when equipment has been out of service for 8 hours or more

26.3.8.3.4 Trouble Signals. Upon receipt of trouble signals or other signals pertaining solely to matters of equipment maintenance of the alarm systems, the central station shall perform the following actions:

- (1)* If a received trouble signal does not restore within 15 minutes, communicate immediately with persons designated by the subscriber
- (2) Dispatch personnel to arrive within 4 hours to initiate maintenance, if necessary
- (3) When the interruption is more than 8 hours, provide notice to the subscriber and the fire department if so required by the authority having jurisdiction as to the nature of the interruption, the time of occurrence, and the restoration of service

26.3.8.3.5 Test Signals.

26.3.8.3.5.1 All test signals received shall be recorded to indicate date, time, and type.

26.3.8.3.5.2 Test signals initiated by the subscriber, including those for the benefit of an authority having jurisdiction, shall be acknowledged by central station personnel whenever the subscriber or authority inquires.

26.3.8.3.5.3* Any test signal not received by the central station shall be investigated immediately, and action shall be taken to reestablish system integrity.

26.3.8.3.5.4 The central station shall dispatch personnel to arrive within 2 hours if protected premises equipment needs to be manually reset after testing.

26.3.8.3.5.5 The prime contractor shall provide each of its representatives and each alarm system user with a unique personal identification code.

26.3.8.3.5.6 In order to authorize the placing of an alarm system into test status, a representative of the prime contractor or an alarm system user shall first provide the central station with his or her personal identification code.

26.3.9 Record Keeping and Reporting.

26.3.9.1 Complete records of all signals received shall be retained for at least 1 year.

26.3.9.2 Testing and maintenance records shall be retained as required by 14.6.3.

26.3.9.3 The central station shall make arrangements to furnish reports of signals received to the authority having jurisdiction in a manner approved by the authority having jurisdiction.

26.3.10 Testing and Maintenance. Testing and maintenance for central station service shall be performed in accordance with Chapter 14.

26.4 Proprietary Supervising Station Alarm Systems.

26.4.1 Application.

26.4.1.1 Supervising facilities of proprietary alarm systems shall comply with the operating procedures of Section 26.4.

26.4.1.2 The facilities, equipment, personnel, operation, testing, and maintenance of the proprietary supervising station shall also comply with Section 26.4.

26.4.2 General.

26.4.2.1 Proprietary supervising stations shall be operated by trained, competent personnel in constant attendance who are responsible to the owner of the protected property.

26.4.2.2 The protected property shall be either a contiguous property or noncontiguous properties under one ownership.

26.4.2.3 If a protected premises control unit is integral to or colocated with the supervising station equipment, the requirements of Section 26.6 shall not apply.

26.4.3 Facilities.

26.4.3.1* The proprietary supervising station shall be located in either of the following:

- (1) Fire-resistive, detached building
- (2) A fire-resistive room protected from the hazardous parts of the building

26.4.3.2 Access to the proprietary supervising station shall be restricted to those persons directly concerned with the implementation and direction of emergency action and procedure.

26.4.3.3 The proprietary supervising station, as well as remotely located power rooms for batteries or engine-driven generators, shall be provided with portable fire extinguishers that comply with the requirements of NFPA 10.

26.4.3.4 The emergency lighting system shall comply with the requirements of 26.4.3.4.1 through 26.4.3.4.3.

26.4.3.4.1 The proprietary supervising station shall be provided with an automatic emergency lighting system.

26.4.3.4.2 The emergency source shall be independent of the primary lighting source.

26.4.3.4.3 In the event of a loss of the primary lighting for the supervising station, the emergency lighting system shall provide illumination for a period of not less than 26 hours to permit the operators to carry on operations and shall be tested in accordance with the requirements of Chapter 14.

26.4.3.5 If 25 or more protected buildings or premises are connected to a subsidiary station, both of the following shall be provided at the subsidiary station:

- (1) Automatic means for receiving and recording signals
- (2) A telephone

26.4.3.6* Retransmission Means. The means of retransmission shall be accepted by the authority having jurisdiction and shall be in accordance with 26.3.6.6, 26.5.4.4, or Chapter 27.

26.4.4 Equipment.

26.4.4.1 Signal-Receiving Equipment.

26.4.4.1.1 Signal-receiving equipment in a proprietary supervising station shall comply with 26.4.4.

26.4.4.1.2 Provision shall be made to designate the building in which a signal originates.

26.4.4.1.3* The floor, section, or other subdivision of the building in which a signal originates shall be designated at the proprietary supervising station or at the building that is protected where required by the authority having jurisdiction.

26.4.4.1.4 Designation, as required by 26.4.4.1.2 and 26.4.4.1.3, shall use private-mode notification appliances approved by the authority having jurisdiction.

26.4.4.2 Signal-Alerting Equipment.

26.4.4.2.1 The proprietary supervising station shall have, in addition to a recording device, two different means for alerting the operator when each signal is received that indicates a change of state of any connected initiating device circuit.

26.4.4.2.1.1 One of these means shall be an audible signal, which shall persist until manually acknowledged.

26.4.4.2.1.2 Means shall include the receipt of alarm, supervisory, and trouble signals, including signals indicating restoration.

26.4.4.2.1.3 If means is provided in the proprietary supervising station to identify the type of signal received, a common audible indicating appliance shall be permitted to be used for alarm, supervisory, and trouble indication.

26.4.4.2.1.4 At a proprietary supervising station, an audible trouble signal shall be permitted to be silenced, provided that the act of silencing does not prevent the signal from operating immediately upon receipt of a subsequent trouble signal.

26.4.4.2.2 All signals required to be received by the proprietary supervising station that show a change in status shall be automatically and permanently recorded, including time and date of occurrence, in a form that expedites operator interpretation in accordance with any one of the means detailed in 26.4.4.2.2.1 through 26.4.4.2.2.4.

26.4.4.2.2.1 If a visual display is used that automatically provides change of status information for each required signal, including type and location of occurrence, any form of automatic permanent visual record shall be permitted.

(A) The recorded information shall include the content described in 26.4.4.2.2.

(B) The visual display shall show status information content at all times and be distinctly different after the operator has manually acknowledged each signal.

(C) Acknowledgment shall produce recorded information indicating the time and date of acknowledgment.

26.4.4.2.2.2 If a visual display is not provided, required signal content information shall be automatically recorded on duplicate, permanent visual recording instruments.

26.4.4.2.2.3 One recording instrument shall be used for recording all incoming signals, while the other shall be used for required alarm, supervisory, and trouble signals only.

(A) Failure to acknowledge a signal shall not prevent subsequent signals from recording.

(B) Restoration of the signal to its prior condition shall be recorded.

26.4.4.2.2.4 In the event that a system combines the use of a sequential visual display and recorded permanent visual presentation, the required signal content information shall be displayed and recorded.

(A) The visual information component shall be retained either on the display until manually acknowledged or repeated at intervals not greater than 5 seconds, for durations of 2 seconds each, until manually acknowledged.

(B) Each new displayed status change shall be accompanied by an audible indication that persists until manual acknowledgment of the signal is performed.

26.4.4.3* Redisplay of Status. A means shall be provided for the operator to redisplay the status of required signal-initiating inputs that have been acknowledged but not yet restored.

26.4.4.3.1 If the system retains the signal on the visual display until manually acknowledged, subsequent recorded presentations shall not be inhibited upon failure to acknowledge.

26.4.4.3.2 Alarm signals shall be segregated on a separate visual display in this configuration unless they are given priority status on the common visual display.

26.4.4.4 Display Rate. To facilitate the prompt receipt of alarm signals from systems handling other types of signals that are able to produce multiple simultaneous status changes, the requirements of either of the following shall be met:

- (1) Record simultaneous status changes at a rate not slower than either a quantity of 50 or 10 percent of the total number of initiating device circuits connected, within 90 seconds, whichever number is smaller, without loss of any signal
- (2) Display or record alarm signals at a rate not slower than one every 10 seconds, regardless of the rate or number of status changes occurring, without loss of any signals

26.4.4.5 Trouble Signals. Trouble signals and their restoration shall be automatically indicated and recorded at the proprietary supervising station.

26.4.4.5.1 The recorded information for the occurrence of any trouble condition of signaling line circuit, leg facility, or trunk facility that prevents receipt of alarm signals at the

proprietary supervising station shall be such that the operator is able to determine the presence of the trouble condition.

26.4.4.5.2 Trouble conditions in a leg facility shall not affect or delay receipt of signals at the proprietary supervising station from other leg facilities on the same trunk facility.

26.4.5 Personnel.

26.4.5.1 Except as permitted in 26.4.5.2, the proprietary supervising station shall be staffed at all times by a minimum of two qualified operators.

26.4.5.2 Where the means for transmitting alarms to the communications center is automatic, the proprietary supervising station shall be permitted to be staffed by a minimum of one qualified operator at all times.

26.4.5.3 Where the proprietary supervising station is staffed by two qualified operators, one of the operators shall be permitted to be a runner.

26.4.5.4 When the runner is not in attendance at the proprietary supervising station, the runner shall establish two-way communications with the station at intervals not exceeding 15 minutes, unless otherwise permitted by 26.4.5.5.

26.4.5.5 Where two or more operators are on duty in the supervising station, a runner physically in attendance at a noncontiguous protected premises and immediately available via telephone or other approved means of communication shall not be required to maintain two-way communications at 15-minute intervals if that runner is not responsible for another protected premises.

26.4.5.6 The primary duties of the operator(s) shall be to monitor signals, operate the system, and take such action as shall be required by the authority having jurisdiction.

26.4.5.7 The operator(s) shall not be assigned any additional duties that would take precedence over the primary duties.

26.4.6 Operations.

26.4.6.1 Procedures.

26.4.6.1.1 The procedural requirements outlined in Section 26.2 shall be followed.

26.4.6.1.2 The additional procedural requirements outlined in 26.4.6.1 shall also be followed.

26.4.6.1.3 Communications and Transmission Channels.

26.4.6.1.3.1 All communications and transmission channels used to receive signals between the proprietary supervising station and the protected premises control unit shall be operated manually or automatically once every 24 hours to verify operation.

26.4.6.1.3.2 If a communications or transmission channel fails to operate, the operator shall immediately notify the person(s) identified by the owner or authority having jurisdiction.

26.4.6.1.3.3* Coded Retransmission. Retransmission by coded signals shall be confirmed by two-way voice communications indicating the nature of the alarm.

26.4.6.1.4 Operator Controls.

26.4.6.1.4.1 All operator controls at the proprietary supervising station(s) designated by the authority having jurisdiction shall be operated at each change of shift.

26.4.6.1.4.2 If operator controls fail, the operator shall immediately notify the person(s) identified by the owner or authority having jurisdiction.

26.4.6.1.5 Retransmission. Indication of a fire shall be immediately retransmitted to the communications center or other locations accepted by the authority having jurisdiction, indicating the building or group of buildings from which the alarm has been received.

26.4.6.1.6 Dispositions of Signals.

26.4.6.1.6.1 Alarms. Upon receipt of an alarm signal, the proprietary supervising station operator shall initiate action to perform the following:

- (1) Notify the communications center, the emergency response team, and such other parties as the authority having jurisdiction requires in accordance with 26.2.1
- (2) Dispatch a runner or technician to the alarm location to arrive within 2 hours after receipt of a signal
- (3) Restore the system as soon as possible after disposition of the cause of the alarm signal

26.4.6.1.6.2 Guard's Tour Supervisory Signal. If a guard's tour supervisory signal is not received from a guard within a 15-minute maximum grace period, or if a guard fails to follow a prescribed route in transmitting the signals (where a prescribed route has been established), the proprietary supervising station operator shall initiate action to perform the following:

- (1) Communicate at once with the protected areas or premises by telephone, radio, calling back over the system circuit, or other means accepted by the authority having jurisdiction
- (2) Dispatch a runner to arrive within 30 minutes to investigate the delinquency if communications with the guard cannot be immediately established

26.4.6.1.6.3 Supervisory Signals. Upon receipt of sprinkler system and other supervisory signals, the proprietary supervising station operator shall initiate action to perform the following, if required:

- (1) Communicate immediately with the designated person(s) to ascertain the reason for the signal
- (2) Dispatch personnel to arrive within 2 hours to investigate, unless supervisory conditions are immediately restored
- (3) Notify the fire department if required by the authority having jurisdiction
- (4) Notify the authority having jurisdiction when sprinkler systems are wholly or partially out of service for 8 hours or more
- (5)* Provide written notice to the authority having jurisdiction as to the nature of the signal, time of occurrence, and restoration of service when equipment has been out of service for 8 hours or more

26.4.6.1.6.4 Trouble Signals. Upon receipt of trouble signals or other signals pertaining solely to matters of equipment maintenance of the alarm system, the proprietary supervising station operator shall initiate action to perform the following, if required:

- (1) Communicate immediately with the designated person(s) to ascertain reason for the signal
- (2) Dispatch personnel to arrive within 4 hours to initiate maintenance, if necessary
- (3) Notify the fire department if required by the authority having jurisdiction
- (4) Notify the authority having jurisdiction when interruption of service exists for 4 hours or more
- (5) When equipment has been out of service for 8 hours or more, provide written notice to the authority having jurisdiction as to the nature of the signal, time of occurrence, and restoration of service

26.4.7 Record Keeping and Reporting.

26.4.7.1 Complete records of all signals received shall be retained for at least 1 year.

26.4.7.2 Testing and maintenance records shall be retained as required by 14.6.3.

26.4.7.3 The proprietary supervising station shall make arrangements to furnish reports of signals received to the authority having jurisdiction in a manner approved by the authority having jurisdiction.

26.4.8 Testing and Maintenance. Testing and maintenance of proprietary alarm systems shall be performed in accordance with Chapter 14.

26.5 Remote Supervising Station Alarm Systems.

26.5.1 Application and General.

26.5.1.1 Section 26.5 shall apply where central station service is neither required nor elected.

26.5.1.2 The installation, maintenance, testing, and use of a remote supervising station alarm system that serves properties under various ownership from a remote supervising station shall comply with the requirements of Section 26.5.

26.5.1.3 Remote supervising station physical facilities, equipment, operating personnel, response, retransmission, signals, reports, and testing shall comply with the minimum requirements of Section 26.5.

26.5.1.4 Remote supervising station alarm systems shall provide an automatic audible and visible indication of alarm, supervisory, and trouble conditions at a location remote from the protected premises.

26.5.1.5 Audible or visual notification appliances at the protected premises shall comply with 26.5.1.5.1 and 26.5.1.5.2.

26.5.1.5.1 Audible or visual notification appliances shall not be required other than those required at the remote supervising station.

26.5.1.5.2 Where audible or visual appliances are provided at the protected premises, the alarm signals, circuits, and controls shall comply with the provisions of Chapter 18 and Chapter 23 in addition to the provisions of Section 26.5.

26.5.1.6 The loading capacities of the remote supervising station equipment for any approved method of transmission shall be as designated in Section 26.6.

26.5.2 Indication of Remote Station Service.

26.5.2.1 Owners utilizing remote station alarm systems shall provide annual documentation to the authority having jurisdiction identifying the party responsible for the inspection, testing, and maintenance requirements of Chapter 14.

26.5.2.2 The documentation required by 26.5.2.1 shall take one of the following forms:

- (1)* Affidavit attesting to the responsibilities and qualifications of the parties performing the inspection, testing, and maintenance and accepting responsibility of compliance with Chapter 14 and signed by a representative of the service provider
- (2) Documentation indicating code compliance of the remote station alarm system issued by the organization that listed the service provider
- (3) Other documentation acceptable to the authority having jurisdiction

26.5.3* Facilities.

26.5.3.1 Alarm systems utilizing remote supervising station connections shall transmit alarm and supervisory signals to a facility meeting the requirements of 26.5.3.1.1, 26.5.3.1.2, 26.5.3.1.3, or 26.5.3.1.4.

26.5.3.1.1 Alarm, supervisory, and trouble signals shall be permitted to be received at a communications center that complies with the requirements of NFPA 1221.

26.5.3.1.2 Alarm, supervisory, and trouble signals shall be permitted to be received at the fire station or at the governmental agency that has public responsibility for taking prescribed action to ensure response upon receipt of an alarm signal.

26.5.3.1.3 Where permitted by the authority having jurisdiction, alarm, supervisory, and trouble signals shall be permitted to be received at a listed central supervising station.

26.5.3.1.4* Where permitted by the authority having jurisdiction, alarm, supervisory, and trouble signals shall be permitted to be received at an alternate location approved by the authority having jurisdiction.

26.5.3.2* Trouble signals shall be permitted to be received at locations in accordance with 26.5.3.2.1 and 26.5.3.2.2.

26.5.3.2.1 Trouble signals shall be permitted to be received at an approved location that has personnel on duty who are trained to recognize the type of signal received and take prescribed action.

26.5.3.2.2 Trouble signals shall be permitted to be received at an approved location other than that which receives alarm and supervisory signals.

26.5.3.3 If locations other than the communications center are used for the receipt of signals, access to receiving equipment shall be restricted in accordance with the requirements of the authority having jurisdiction.

26.5.4 Equipment.

26.5.4.1 Signal-receiving equipment shall indicate receipt of each signal both audibly and visibly.

26.5.4.1.1 Audible signals shall meet the requirements of Chapter 18 for the private operating mode.

26.5.4.1.2 Means for silencing alarm, supervisory, and trouble signals shall be provided and shall be arranged so that subsequent signals shall re-sound.

26.5.4.1.3 A trouble signal shall be received when the system or any portion of the system at the protected premises is placed in a bypass or test mode.

26.5.4.1.4 An audible and visible indication shall be provided upon restoration of the system after receipt of any signal.

26.5.4.1.5 If visible means are provided in the remote supervising station to identify the type of signal received, a common audible notification appliance shall be permitted to be used.

26.5.4.2 Power supplies shall comply with the requirements of Chapter 10.

26.5.4.3 Transmission means shall comply with the requirements of Section 26.6.

26.5.4.4 Retransmission of an alarm signal, if required, shall be by one of the following methods, which appear in descending order of preference as follows:

- (1) A dedicated circuit that is independent of any switched telephone network and is capable of voice or data communications
- (2) A one-way (outgoing only) telephone at the remote supervising station that utilizes a managed facilities-based voice network and is used primarily for voice transmission of alarms to a telephone at the communications center that cannot be used for outgoing calls
- (3) A private radio system using the fire department frequency, where permitted by the fire department
- (4) Other methods accepted by the authority having jurisdiction

26.5.5 Personnel.

26.5.5.1 The remote supervising station shall have not less than two qualified operators on duty at the remote supervising station at all times to ensure disposition of signals in accordance with the requirements of 26.5.6.

26.5.5.2 Duties pertaining to other than operation of the remote supervising station receiving and transmitting equipment shall be permitted, subject to the approval of the authority having jurisdiction.

26.5.6 Procedures.

26.5.6.1 The procedural requirements outlined in Section 26.2 shall be followed.

26.5.6.2 The additional procedural requirements outlined in 26.5.6 shall also be followed.

26.5.6.3 Disposition of Signals.

26.5.6.3.1 Alarm Signals. The remote station shall perform the following actions:

- (1) If the remote station is at a location other than the communications center, retransmit alarm signals to the communications center in accordance with 26.2.1.
- (2) Immediately notify the owner or the owner's designated representative.

26.5.6.3.2 Supervisory Signals. Upon receipt of a supervisory signal that is not prearranged, the remote station shall perform the following actions:

- (1) Immediately notify the owner or the owner's designated representative.
- (2) Where required, notify the authority having jurisdiction.

26.5.6.3.3 Trouble Signals.

26.5.6.3.3.1 Upon receipt of a trouble signal that is not prearranged, the remote station shall perform the following action:

- (1) Immediately notify the owner or the owner's designated representative.
- (2) Where required, notify the authority having jurisdiction.

26.5.6.3.3.2 For trouble signals, the remote station operator shall be permitted to delay transmission for 15 minutes to allow for a status change in the signal that would resolve the trouble signal.

26.5.6.3.3.3 If a trouble restoral signal is received within 15 minutes, the operator shall not be required to notify the owner or the owner's designated representative or the authority having jurisdiction.

26.5.7 Operations. All operator controls at the remote supervising station shall be operated at the beginning of each shift or change in personnel, and the status of all alarm, supervisory, and trouble signals shall be noted and recorded.

26.5.8 Record Keeping and Reporting.

26.5.8.1 A permanent record of the time, date, and location of all signals and restorations received and the action taken shall be maintained for at least 1 year and shall be able to be provided to the authority having jurisdiction.

26.5.8.2 Testing and maintenance records shall be retained as required in 14.6.3.

26.5.8.3 Records shall be permitted to be created by manual means.

26.5.9 Inspection, Testing, and Maintenance.

26.5.9.1 Inspection, testing, and maintenance for remote supervising stations shall be performed in accordance with Chapter 14.

26.5.9.2 Where required, inspection, testing, and maintenance reports shall be submitted to the authority having jurisdiction in a form acceptable to the authority having jurisdiction.

26.6 Communications Methods for Supervising Station Alarm Systems.

26.6.1* Application.

26.6.1.1 Section 26.6 shall apply to the following:

- (1) Transmitter located at the protected premises
- (2) Transmission channel between the protected premises and the supervising station or subsidiary station
- (3) If used, any subsidiary station and its communications channel
- (4) Signal receiving, processing, display, and recording equipment at the supervising station

26.6.1.2 The minimum signaling requirement shall be an alarm signal, trouble signal, and supervisory signal, where used.

26.6.2 General.

26.6.2.1 Master Control Unit. If the protected premises master control unit is neither integral to nor colocated with the supervising station, the communications methods of Section 26.6 shall be used to connect the protected premises to either a subsidiary station, if used, or a supervising station for central station service in accordance with Section 26.3, proprietary station in accordance with Section 26.4, or remote station in accordance with Section 26.5.

26.6.2.2* Alternate Methods. Nothing in Chapter 26 shall be interpreted as prohibiting the use of listed equipment using alternate communications methods that provide a level of reliability and supervision consistent with the requirements of Chapter 10 and the intended level of protection.

26.6.2.3 Remote Programming of Transmitting Technologies. Remote programming of protected premises transmission technologies covered by 26.6.3, 26.6.4, and 26.6.5 shall be permitted when all the conditions in 26.6.2.3.1 through 26.6.2.3.8 are met.

26.6.2.3.1 A qualified person in accordance with 14.4.2.6 shall be at the protected premises at all times during the remote programming.

26.6.2.3.2 Before remote programming of protected premises transmission technologies occurs, notifications shall be made in accordance with 14.2.4.1.

26.6.2.3.3 A test plan shall be developed in accordance with 14.2.10.

26.6.2.3.4 A mitigation plan shall be initiated by the responsible party for the alarm system, which assigns an individual, or individuals, who will be charged with contacting the communications center in the event that an actual alarm occurs during the remote programming of the transmitting equipment.

26.6.2.3.5 Where the transmission technology is integral to the control unit, reacceptance testing shall occur in accordance with 14.4.2.5 and item 4, Supervising station alarm systems — transmission equipment, in Table 14.4.3.2 when executive software for the transmission technology is changed.

26.6.2.3.6 Where the transmission technology is integral to the control unit, reacceptance testing shall occur in accordance with 14.4.2.4 and item 4, Supervising station alarm systems — transmission equipment, in Table 14.4.3.2 when site-specific software for the transmission technology is changed.

26.6.2.3.7 Where the transmission technology is not integral to the control unit, testing shall occur in accordance with item 4, Supervising station alarm systems — transmission equipment, in Table 14.4.3.2.

26.6.2.3.8 At the conclusion of testing, notifications shall be in accordance with 14.2.4.2.

26.6.2.4* Equipment.

26.6.2.4.1 Alarm system equipment and installations shall comply with Federal Communications Commission (FCC) rules and regulations, as applicable.

26.6.2.4.2 Equipment shall be installed in compliance with *NFPA 70*.

26.6.2.4.3 The external antennas of all radio transmitting and receiving equipment shall be protected in order to minimize the possibility of damage by static discharge or lightning.

26.6.2.5 Communications Technologies. The communications methods used to transmit signals to supervising stations shall meet the requirements of 26.6.3 for performance-based technologies, or 26.6.4 or 26.6.5 for prescriptive-based technologies.

26.6.3* Performance-Based Technologies.

26.6.3.1 Conformance. Communications methods operating on principles different from specific methods covered by this chapter shall be permitted to be installed if they conform to the performance requirements of this section and to all other applicable requirements of this Code.

26.6.3.2 Communications Integrity. Provision shall be made to monitor the integrity of the transmission technology and its communications path.

26.6.3.3 Single Communications Path. Unless prohibited by the enforcing authority, governing laws, codes, or standards, where a single communications path is used, the following requirements shall be met:

- (1) The path shall be supervised at an interval of not more than 60 minutes.
- (2) A failure of the path shall be annunciated at the supervising station within not more than 60 minutes.
- (3) The failure to complete a signal transmission shall be annunciated at the protected premises in accordance with Section 10.15.

26.6.3.4 Multiple Communications Paths. If multiple transmission paths are used, the following requirements shall be met:

- (1) Each path shall be supervised within not more than 6 hours.
- (2) The failure of any path of a multipath system shall be annunciated at the supervising station within not more than 6 hours.
- (3) Multiple communications paths shall be arranged so that a single point of failure shall not cause more than a single path to fail.
- (4) The failure to complete a signal transmission shall be annunciated at the protected premises in accordance with Section 10.15.

26.6.3.5* Single Technology. A single technology shall be permitted to be used to create the multiple paths provided that the requirements of 26.6.3.4(1) through 26.6.3.4(4) are met.

26.6.3.6 Spare System Unit Equipment. An inventory of spare equipment shall be maintained at the supervising station such that any failed piece of equipment can be replaced and the systems unit restored to full operation within 30 minutes of failure.

26.6.3.7 Loading Capacity of System Unit.

26.6.3.7.1 The maximum number of independent fire alarm systems connected to a single system unit shall be limited to 512.

26.6.3.7.2 If duplicate spare system units are maintained at the supervising station and switchover can be achieved in

30 seconds, then the system capacity shall be permitted to be unlimited.

26.6.3.8 End-to-End Communication Time for Alarm. The maximum duration between the initiation of an alarm signal at the protected premises, transmission of the signal, and subsequent display and recording of the alarm signal at the supervising station shall not exceed 90 seconds.

26.6.3.9 Unique Identifier. If a transmitter shares a transmission or communications channel with other transmitters, it shall have a unique transmitter identifier.

26.6.3.10 Recording and Display Rate of Subsequent Alarms. Recording and display of alarms at the supervising station shall be at a rate no slower than one complete signal every 10 seconds.

26.6.3.11 Signal Error Detection and Correction.

26.6.3.11.1 Communication of alarm, supervisory, and trouble signals shall be in accordance with this section to prevent degradation of the signal in transit, which in turn would result in either of the following:

- (1) Failure of the signal to be displayed and recorded at the supervising station
- (2) Incorrect corrupted signal displayed and recorded at the supervising station

26.6.3.11.2 Reliability of the signal shall be achieved by any of the following:

- (1) Signal repetition — multiple transmissions repeating the same signal
- (2) Parity check — a mathematical check sum algorithm of a digital message that verifies correlation between transmitted and received message
- (3) An equivalent means to 26.6.3.11.1(1) or 26.6.3.11.1(2) that provides a certainty of 99.99 percent that the received message is identical to the transmitted message

26.6.3.12* Sharing Communications Equipment On-Premises. If the fire alarm transmitter is sharing on-premises communications equipment, the shared equipment shall be listed as communications or information technology equipment.

26.6.3.13 Secondary Power.

26.6.3.13.1* Premises Equipment. The secondary power capacity for all transmitters and shared equipment necessary for the transmission of alarm, supervisory, trouble, and other signals located at the protected premises shall be a minimum of 24 hours or as permitted by 10.6.7.3.1(2), 26.6.3.13.1.1, or 26.6.3.13.1.2.

26.6.3.13.1.1* Secondary power capacity for shared equipment shall be permitted to have a capacity of 8 hours where acceptable to the authority having jurisdiction and where a risk analysis is performed to ensure acceptable availability is provided.

26.6.3.13.1.2* Secondary power capacity for shared and premises equipment used in additional communications paths shall not be required where the first communications path meets the performance requirements of 26.6.3.3.

26.6.3.13.2 Supervising Station. Secondary power capacity for all equipment necessary for reception of alarm, supervisory, trouble, and other signals located at the supervising station shall comply with 10.6.7.

26.6.3.14 Unique Flaws Not Covered by This Code. If a communications technology has a unique flaw that could result in the failure to communicate a signal, the implementation of that technology for alarm signaling shall compensate for that flaw so as to eliminate the risk of missing an alarm signal.

26.6.4 Digital Communicator Systems.

26.6.4.1* Digital Alarm Communicator Transmitter (DACT) Used as a Signaling Interface.

26.6.4.1.1 The requirements of 26.6.4.2 shall not apply when a DACT is used as a signaling interface from a fire alarm control unit to another listed communications means.

26.6.4.1.2 The listed communications means shall meet the requirements of either 26.6.3 or 26.6.5.

26.6.4.2 DACT.

26.6.4.2.1* Managed Facilities-Based Voice Network. A DACT shall be connected to a managed facilities-based voice network upstream of any private telephone system at the protected premises.

26.6.4.2.1.1 The connections to a managed facilities-based voice network shall be under the control of the subscriber for whom service is being provided by the supervising station alarm system.

26.6.4.2.1.2 Special attention shall be required to ensure that this connection is made only to a loop start telephone circuit and not to a ground start telephone circuit.

26.6.4.2.2 Signal Verification. All information exchanged between the DACT at the protected premises and the digital alarm communicator receiver (DACR) at the supervising or subsidiary station shall comply with 26.6.4.2.2.1 and 26.6.4.2.2.2.

26.6.4.2.2.1 Information exchanged shall be by digital code or some other approved means.

26.6.4.2.2.2 Signal verification shall be by signal repetition, digital parity check, or other approved means.

26.6.4.2.3* Requirements for DACTs.

26.6.4.2.3.1 A DACT shall be configured so that, when it is required to transmit a signal to the supervising station, it shall seize the telephone line (i.e., going off-hook) at the protected premises and disconnect an outgoing or incoming telephone call and prevent use of the telephone line for outgoing telephone calls until signal transmission has been completed. A DACT shall not be connected to a party line telephone facility.

26.6.4.2.3.2 A DACT shall have the means to satisfactorily obtain a dial tone, dial the number(s) of the DACR, obtain verification that the DACR is able to receive signals, transmit the signal, and receive acknowledgment that the DACR has accepted that signal. In no event shall the time from going off-hook to on-hook exceed 90 seconds per attempt.

26.6.4.2.3.3* A DACT shall have means to reset and retry if the first attempt to complete a signal transmission sequence is unsuccessful. A failure to complete connection shall not prevent subsequent attempts to transmit an alarm where such alarm is generated from any other initiating device circuit or signaling line circuit, or both. Additional attempts shall be made until the signal transmission sequence has been completed, up to a minimum of 5 and a maximum of 10 attempts.

26.6.4.2.3.4 If the maximum number of attempts to complete the sequence is reached, an indication of the failure shall be made at the premises.

26.6.4.2.4 Transmission Channels.

26.6.4.2.4.1 A system employing a DACT shall employ a single telephone line (number) and one of the following transmission means:

- (1) One-way private radio alarm system
- (2) Two-way RF multiplex system
- (3) Transmission means complying with 26.6.3
- (4) A second telephone line (number), where all of the following are met:
 - (a) Access to one of the technologies in 26.6.4.2.4.1(1), 26.6.4.2.4.1(2), or 26.6.4.2.4.1(3) is not available at the protected premises.
 - (b) The authority having jurisdiction approves the arrangement.
 - (c) The DACT is programmed to call a second DACR line (number) when the signal transmission sequence to the first called line (number) is unsuccessful.
 - (d) The DACT is capable of selecting the operable means of transmission in the event of failure of the other means.
 - (e) Each telephone line is tested in accordance with 26.6.4.2.4.2 or at alternating 6-hour intervals.

26.6.4.2.4.2 The following requirements shall apply to all combinations listed in 26.6.4.2.4.1:

- (1) The means for supervising each channel shall be in a manner approved for the method of transmission employed.
- (2) If a signal has not been processed over the subject channel in the previous 6 hours, a test signal shall be processed.
- (3) The failure of either channel shall send a trouble signal on the other channel within 4 minutes.
- (4) When one transmission channel has failed, all status change signals shall be sent over the other channel.
- (5) The primary channel shall be capable of delivering an indication to the DACT that the message has been received by the supervising station.
- (6)* Unless the primary channel is known to have failed, the first attempt to send a status change signal shall use the primary channel.
- (7) Simultaneous transmission over both channels shall be permitted.
- (8) Failure of telephone lines (numbers) shall be annunciated locally.

26.6.4.2.5 DACT Transmission Means. The following requirements shall apply to all DACTs:

- (1) A DACT shall be connected to two separate means of transmission at the protected premises so that a single point of failure on one means of transmission shall not affect the second means of transmission.
- (2) The DACT shall be capable of selecting the operable means of transmission in the event of failure of the other means.
- (3) The primary means of transmission shall be a telephone line (number) connected to a managed facilities-based voice network.

- (4)* The first transmission attempt shall utilize the primary means of transmission.
- (5) Each DACT shall be programmed to call a second receiver when the signal transmission sequence to the first called line (number) is unsuccessful.
- (6) Each transmission means shall automatically initiate and complete a test signal transmission sequence to its associated receiver at least once every 6 hours.
- (7) A successful signal transmission sequence of any other type, within the same 6-hour period, shall fulfill the requirement to verify the integrity of the reporting system, provided that signal processing is automated so that 6-hour delinquencies are individually acknowledged by supervising station personnel.
- (8)* If a DACT is programmed to call a telephone line (number) that is call forwarded to the line (number) of the DACR, a means shall be implemented to verify the integrity of the call forwarding feature every 4 hours.

26.6.4.3 Digital Alarm Communicator Receiver (DACR).

26.6.4.3.1 Equipment.

26.6.4.3.1.1 Spare DACRs shall be provided in the supervising or subsidiary station.

26.6.4.3.1.2 Spare DACRs shall be online or able to be switched into the place of a failed unit within 30 seconds after detection of failure.

26.6.4.3.1.3 One spare DACR shall be permitted to serve as a backup for up to five DACRs in use.

26.6.4.3.1.4 The number of incoming telephone lines to a DACR shall be limited to eight lines, unless the signal-receiving, processing, display, and recording equipment at the supervising or subsidiary station is duplicated and a switchover is able to be accomplished in less than 30 seconds with no loss of signal during this period, in which case the number of incoming lines to the unit shall be permitted to be unlimited.

26.6.4.3.2 Transmission Channels.

26.6.4.3.2.1* The DACR equipment at the supervising or subsidiary station shall be connected to a minimum of two separate incoming telephone lines (numbers).

26.6.4.3.2.2 The lines (numbers) shall have the following characteristics:

- (1) If the lines (numbers) are in a single hunt group, they shall be individually accessible; otherwise, separate hunt groups shall be required.
- (2) The lines (numbers) shall be used for no other purpose than receiving signals from a DACT.
- (3) The lines (numbers) shall be unlisted.

26.6.4.3.2.3 The failure of any telephone line (number) connected to a DACR due to loss of line voltage shall be annunciated visually and audibly in the supervising station.

26.6.4.3.2.4* The loading capacity for a hunt group shall be capable of demonstrating a 90 percent probability of immediately answering an incoming call or be in accordance with Table 26.6.4.3.2.4 and the following:

- (1) Table 26.6.4.3.2.4 shall be based on an average distribution of calls and an average connected time of 30 seconds for a message.

- (2) The loading figures in Table 26.6.4.3.2.4 shall presume that the lines are in a hunt group (i.e., DACT is able to access any line not in use).
- (3) A single-line DACR shall not be allowed for any of the configurations shown in Table 26.6.4.3.2.4.

Table 26.6.4.3.2.4 Loading Capacities for Hunt Groups

System Loading at the Supervising Station	Number of Lines in Hunt Group				
	1	2	3	4	5-8
With DACR lines processed in parallel					
Number of initiating circuits	NA	5,000	10,000	20,000	20,000
Number of DACTs	NA	500	1,500	3,000	3,000
With DACR lines processed serially (put on hold, then answered one at a time)					
Number of initiating circuits	NA	3,000	5,000	6,000	6,000
Number of DACTs	NA	300	800	1,000	1,000

NA: Not allowed.

26.6.4.3.2.5 Each supervised burglar alarm (open/close) or each suppressed guard's tour transmitter shall reduce the allowable DACTs as follows:

- (1) Up to a four-line hunt group, by 10
- (2) Up to a five-line hunt group, by 7
- (3) Up to a six-line hunt group, by 6
- (4) Up to a seven-line hunt group, by 5
- (5) Up to an eight-line hunt group, by 4

26.6.4.3.2.6 Each guard's tour transmitter shall reduce the allowable DACTs as follows:

- (1) Up to a four-line hunt group, by 30
- (2) Up to a five-line hunt group, by 21
- (3) Up to a six-line hunt group, by 18
- (4) Up to a seven-line hunt group, by 15
- (5) Up to an eight-line hunt group, by 12

26.6.4.3.2.7 A signal shall be received on each individual incoming DACR line at least once every 6 hours.

26.6.4.3.2.8 The failure to receive a test signal from the protected premises shall be treated as a trouble signal.

26.6.5 Radio Systems.

26.6.5.1 Two-Way Radio Frequency (RF) Multiplex Systems.

26.6.5.1.1 Maximum Operating Time. The maximum end-to-end operating time parameters allowed for a two-way RF multiplex system shall be as follows:

- (1) The maximum allowable time lapse from the initiation of a single alarm signal until it is recorded at the supervising station shall not exceed 90 seconds. When any number of subsequent alarm signals occur at any rate, they shall be

- recorded at a rate no slower than one every additional 10 seconds.
- (2) The maximum allowable time lapse from the occurrence of an adverse condition in any transmission channel until recording of the adverse condition is started shall not exceed 200 seconds for Type 4 and Type 5 systems. The requirements of 26.6.5.1.4 shall apply.
 - (3) In addition to the maximum operating time allowed for alarm signals, the requirements of one of the following shall be met:
 - (a) A system unit that has more than 500 initiating device circuits shall be able to record not less than 50 simultaneous status changes within 90 seconds.
 - (b) A system unit that has fewer than 500 initiating device circuits shall be able to record not less than 10 percent of the total number of simultaneous status changes within 90 seconds.

26.6.5.1.2 Supervisory and Control Functions. Facilities shall be provided at the supervising station for the following supervisory and control functions of the supervising or subsidiary station and the repeater station radio transmitting and receiving equipment, which shall be accomplished via a supervised circuit where the radio equipment is remotely located from the system unit:

- (1) RF transmitter in use (radiating)
- (2) Failure of ac power supplying the radio equipment
- (3) RF receiver malfunction
- (4) Indication of automatic switchover
- (5) Independent deactivation of either RF transmitter controlled from the supervising station

26.6.5.1.3 Transmission Channel.

26.6.5.1.3.1 The RF multiplex transmission channel shall terminate in an RF transmitter/receiver at the protected premises and in a system unit at the supervising or subsidiary station.

26.6.5.1.3.2 Operation of the transmission channel shall conform to the requirements of this Code whether channels are private facilities, such as microwave, or leased facilities furnished by a communications utility company.

26.6.5.1.3.3 If private signal transmission facilities are used, the equipment necessary to transmit signals shall also comply with requirements for duplicate equipment or replacement of critical components, as described in 26.6.6.3.

26.6.5.1.4* Categories. Two-way RF multiplex systems shall be divided into Type 4 or Type 5 classifications based on their ability to perform under adverse conditions.

26.6.5.1.4.1 A Type 4 system shall have two or more control sites configured as follows:

- (1) Each site shall have an RF receiver interconnected to the supervising or subsidiary station by a separate channel.
- (2) The RF transmitter/receiver located at the protected premises shall be within transmission range of at least two RF receiving sites.
- (3) The system shall contain two RF transmitters that are one of the following:
 - (a) Located at one site with the capability of interrogating all of the RF transmitters/receivers on the premises

- (b) Dispersed with all of the RF transmitters/receivers on the premises having the capability to be interrogated by two different RF transmitters
- (4) Each RF transmitter shall maintain a status that allows immediate use at all times. Facilities shall be provided in the supervising or subsidiary station to operate any off-line RF transmitter at least once every 8 hours.
 - (5) Any failure of one of the RF receivers shall in no way interfere with the operation of the system from the other RF receiver. Failure of any receiver shall be annunciated at the supervising station.
 - (6) A physically separate channel shall be required between each RF transmitter or RF receiver site, or both, and the system unit.

26.6.5.1.4.2 A Type 5 system shall have a single control site configured as follows:

- (1) A minimum of one RF receiving site
- (2) A minimum of one RF transmitting site

26.6.5.1.5 Loading Capacities.

26.6.5.1.5.1 The loading capacities of two-way RF multiplex systems shall be based on the overall reliability of the signal receiving, processing, display, and recording equipment at the supervising or subsidiary station and the capability to transmit signals during adverse conditions of the transmission channels.

26.6.5.1.5.2 Allowable loading capacities shall comply with Table 26.6.5.1.5.2.

26.6.5.1.5.3 The capacity of a system unit shall be permitted to be unlimited if the signal-receiving, processing, display, and recording equipment are duplicated at the supervising station and a switchover is able to be accomplished in not more than 30 seconds, with no loss of signals during this period.

26.6.5.1.6 Adverse Conditions.

26.6.5.1.6.1 The occurrence of an adverse condition on the transmission channel between a protected premises and the supervising station that prevents the transmission of any status change signal shall be automatically indicated and recorded at the supervising station.

26.6.5.1.6.2 The indication and recording of the adverse condition shall identify the affected portions of the system so that the supervising station operator will be able to determine the location of the adverse condition by trunk or leg facility, or both.

26.6.5.1.6.3 For two-way RF multiplex systems that are part of a central station alarm system, restoration of service to the affected portions of the system shall be automatically recorded.

26.6.5.1.6.4 When service is restored to a two-way RF multiplex system, the first status change of any initiating device circuit, any initiating device directly connected to a signaling line circuit, or any combination thereof that occurred at any of the affected premises during the service interruption also shall be recorded.

Table 26.6.5.1.5.2 Loading Capacities for Two-Way RF Multiplex Systems

Trunks	System Type	
	Type 4	Type 5
Maximum number of alarm service initiating device circuits per primary trunk facility	5,120	1,280
Maximum number of leg facilities for alarm service per primary trunk facility	512	128
Maximum number of leg facilities for all types of alarm service per secondary trunk facility*	128	128
Maximum number of all types of initiating device circuits per primary trunk facility in any combination	10,240	2,560
Maximum number of leg facilities for types of alarm service per primary trunk facility in any combination*	1,024	256
System Units at the Supervising Station		
Maximum number of all types of initiating device circuits per system unit*	10,240	10,240
Maximum number of protected buildings and premises per system unit	512	512
Maximum number of alarm service initiating device circuits per system	5,120	5,120
Systems Emitting from Subsidiary Station†	—	—

*Includes every initiating device circuit (e.g., waterflow, alarm, supervisory, guard, burglary, hold-up).

†Same as system units at the supervising station.

26.6.5.2* One-Way Private Radio Alarm Systems.

26.6.5.2.1 Independent Receivers.

26.6.5.2.1.1 The requirements of 26.6.5.2 for a radio alarm repeater station receiver (RARSR) shall be satisfied if the signals from each radio alarm transmitter (RAT) are received and supervised, in accordance with Chapter 26, by at least two independently powered, independently operating, and separately located RARSRs or radio alarm supervising station receivers (RASSRs), or by one of each.

26.6.5.2.1.2 At least two separate paths shall be provided from a RAT to the ultimate RASSR.

26.6.5.2.1.3 Only one path to the RASSR shall be required to be utilized in the event alarms can be transmitted from a RAT to the RASSR and the RAT has the ability to receive a positive acknowledgment that the RASSR has received the signal.

26.6.5.2.2* Maximum Operating Time. The end-to-end operating time parameters allowed for a one-way radio alarm system shall be as follows:

- (1) There shall be a 90 percent probability that the time between the initiation of a single alarm signal until it is recorded at the supervising station will not exceed 90 seconds.
- (2) There shall be a 99 percent probability that the time between the initiation of a single alarm signal until it is recorded at the supervising station will not exceed 180 seconds.
- (3) There shall be a 99.999 percent probability that the time between the initiation of a single alarm signal until it is recorded at the supervising station will not exceed 7.5 minutes (450 seconds), at which time the RAT shall cease transmitting. When any number of subsequent alarm signals occurs at any rate, they shall be recorded at an average rate no slower than one every additional 10 seconds.
- (4) In addition to the maximum operating time allowed for alarm signals, the system shall be able to record not less than 12 simultaneous status changes within 90 seconds at the supervising station.
- (5) The system shall be supervised to ensure that at least two independent RARSRs or one RARSR and one independent RASSR are receiving signals for each RAT during each 24-hour period.

26.6.5.2.3 Supervision.

26.6.5.2.3.1 Equipment shall be provided at the supervising station for the supervisory and control functions of the supervising or subsidiary station and for the repeater station radio transmitting and receiving equipment.

26.6.5.2.3.2 A supervised circuit shall be provided where the radio equipment is remotely located from the system unit and the conditions of 26.6.5.2.3.2(A) through 26.6.5.2.3.2(C) are met.

(A) The following conditions shall be supervised at the supervising station:

- (1) Failure of ac power supplying the radio equipment
- (2) Malfunction of RF receiver
- (3) Indication of automatic switchover, if applicable

(B) Interconnections between elements of transmitting equipment, including any antennas, shall be supervised either to cause an indication of failure at the protected premises or to transmit a trouble signal to the supervising station.

(C) Personnel shall be dispatched to arrive within 12 hours to initiate maintenance after detection of primary power failure.

26.6.5.2.4 Transmission Channels. Transmission channels shall comply with 26.6.5.2.4.1 through 26.6.5.2.4.6.

26.6.5.2.4.1 The one-way RF transmission channel shall originate with a RAT at the protected premises and shall terminate at the RF receiving system of an RARSR or RASSR capable of receiving transmissions from such transmitting devices.

26.6.5.2.4.2 A receiving network transmission channel shall terminate at an RARSR at one end and with either another RARSR or an RASSR at the other end.

26.6.5.2.4.3 Operation of receiving network transmission channels shall conform to the requirements of this Code

whether channels are private facilities, such as microwave, or leased facilities furnished by a communications utility company.

26.6.5.2.4.4 If private signal transmission facilities are used, the equipment necessary to transmit signals shall also comply with requirements for duplicate equipment or replacement of critical components as described in 26.6.6.3.

26.6.5.2.4.5 The system shall provide information that indicates the quality of the received signal for each RARSR supervising each RAT in accordance with 26.6.5.2 and shall provide information at the supervising station when such signal quality falls below the minimum signal quality levels set forth in 26.6.5.2.

26.6.5.2.4.6 Each RAT shall be installed in such a manner so as to provide a signal quality over at least two independent one-way RF transmission channels, of the minimum quality level specified, that satisfies the performance requirements in 26.6.2.4 and 26.6.6.

26.6.5.2.5 System Categories. One-way radio alarm systems shall be divided into two categories on the basis of the following number of RASSRs present in the system:

- (1) A Type 6 system shall have one RASSR and at least two RARSRs.
- (2) A Type 7 system shall have more than one RASSR and at least two RARSRs.
- (3) In a Type 7 system, when more than one RARSR is out of service and, as a result, any RATs are no longer being supervised, the affected supervising station shall be notified.
- (4) In a Type 6 system, when any RARSR is out of service, a trouble signal shall be annunciated at the supervising station.

26.6.5.2.6 Loading Capacities.

26.6.5.2.6.1 The loading capacities of one-way radio alarm systems shall be based on the overall reliability of the signal-receiving, processing, display, and recording equipment at the supervising or subsidiary station and the capability to transmit signals during adverse conditions of the transmission channels.

26.6.5.2.6.2 Loading capacities shall comply with 26.6.5.2.6.2(A) and 26.6.5.2.6.2(B).

(A) Allowable loading capacities shall be in accordance with Table 26.6.5.2.6.2(A), except as modified by the following:

- (1) Each guard's tour transmitter shall reduce the allowable RATs by 15.
- (2) Each supervised burglar alarm (open/close) or each suppressed guard's tour transmitter shall reduce the allowable RATs by 5.

(B) If the signal-receiving, processing, display, and recording equipment is duplicated at the supervising station and a switch-over is able to be accomplished in not more than 30 seconds, with no loss of signals during this period, the capacity of a system unit shall be permitted to be unlimited.

26.6.5.2.7 Adverse Conditions. The system shall be supervised to ensure that at least two independent radio alarm repeater station receivers (RARSRs) are receiving signals for each radio alarm transmitter (RAT) during each 24-hour period.

Table 26.6.5.2.6.2(A) Loading Capacities of One-Way Radio Alarm Systems

Radio Alarm Repeater Station Receiver (RARSR)	System Type	
	Type 6	Type 7
Maximum number of fire alarm service initiating device circuits per RARSR	5,120	5,120
Maximum number of RATs for fire	512	512
Maximum number of all types of initiating device circuits per RARSR in any combination*	10,240	10,240
Maximum number of RATs for all types of fire alarm service per RARSR in any combination*	1,024	1,024
System Units at the Supervising Station		
Maximum number of all types of initiating device circuits per system unit*	10,240	10,240
Maximum number of fire-protected buildings and premises per system unit	512	512
Maximum number of fire alarm service initiating device circuits per system unit	5,120	5,120

*Includes every initiating device circuit (e.g., waterflow, fire alarm, supervisory, guard, burglary, hold-up).

26.6.5.2.7.1 The occurrence of a failure to receive a signal by either RARSR shall be automatically indicated and recorded at the supervising station.

26.6.5.2.7.2 The indication shall identify which RARSR failed to receive such supervisory signals.

26.6.5.2.7.3 Received test signals shall not be required to be indicated at the supervising station.

26.6.5.2.8 Wireless Mesh Networks (WMN). A wireless mesh network utilizing listed components satisfies the requirements of 26.6.5.2.

26.6.6 Display and Recording Requirements for All Transmission Technologies.

26.6.6.1* Any status changes, including the initiation or restoration to normal of a trouble condition, that occur in an initiating device or in any interconnecting circuits or equipment, including the local protected premises controls from the location of the initiating device(s) to the supervising station, shall be presented in a form to expedite prompt operator interpretation.

26.6.6.2 Status change signals shall provide the following information:

- (1) Identification of the type of signal to show whether it is an alarm, supervisory, delinquency, or trouble signal
- (2) Identification of the signal to differentiate between an initiation of an alarm, a supervisory, a delinquency, or a trouble signal and a clearing from one or more of these conditions
- (3) Identification of the site of origin of each status change signal

- (4)* Identification of specific types of signals that dictate a different response

26.6.6.3* If duplicate equipment for signal receiving, processing, display, and recording is not provided for supervising stations other than proprietary station systems, the installed equipment shall be designed so that any critical assembly is able to be replaced from on-premises spares.

26.6.6.4* The system shall be able to be restored to service within 30 minutes.

26.6.6.5* Any method of recording and display or indication of change of status signals shall be permitted, provided that the status signals are not test signals required by 26.6.4.2.5 at a DACR and all of the following conditions are met:

- (1) Each change of status signal requiring action to be taken by the operator shall result in an audible signal and not less than two independent methods of identifying the type, condition, and location of the status change.
- (2) Each change of status signal shall be automatically recorded. The record shall provide the type of signal, condition, and location, as required by 26.6.6.1, in addition to the time and date the signal was received.
- (3) Failure of an operator to acknowledge or act upon a change of status signal shall not prevent subsequent alarm signals from being received, indicated or displayed, and recorded.
- (4) Change of status signals requiring action to be taken by the operator shall be displayed or indicated in a manner that clearly differentiates them from those that have been acted upon and acknowledged.
- (5) Each incoming signal to a DACR shall cause an audible signal that persists until manually acknowledged.

26.6.7 Testing and Maintenance Requirements for All Transmission Technologies. Testing and maintenance of communications methods shall be in accordance with the requirements of Chapter 14.

Chapter 27 Public Emergency Alarm Reporting Systems

27.1 Application.

27.1.1 The provisions of this chapter shall apply to the proper configuration, performance, installation, and operation of public emergency alarm reporting systems and auxiliary alarm systems.

27.1.1.1 Public emergency alarm reporting systems shall consist of alarm boxes, other signal initiating devices or technologies, and alarm processing equipment that communicate on a wired or wireless network(s), one-way or two-way, meeting the requirements of this chapter.

27.1.1.2 Public emergency alarm reporting systems shall include systems that use a communications infrastructure that is publicly owned, operated, and controlled or where public emergency alarm reporting systems and equipment are used in other applications.

27.1.2 The installation and use of public emergency alarm reporting systems and auxiliary alarm systems shall comply with the requirements of this chapter.

27.1.3 The requirements of this chapter shall apply to systems and equipment for the transmission and reception of alarm

and other emergency signals, including those from auxiliary alarm systems, connected to the public emergency alarm reporting system.

27.1.4 The requirements of Chapters 10, 11, and 14 shall apply unless otherwise noted in this chapter.

27.1.5 Only those requirements from Chapter 7 that are required by Chapter 14 shall apply.

27.1.6 The application of public emergency alarm reporting systems and auxiliary alarm systems to provide defined reporting functions from or within private premises shall be permitted where approved by the authority having jurisdiction.

27.1.7* Where a protected premises fire alarm system or other emergency system at the protected premises has its signals sent to a communications center via public emergency alarm reporting system, the protected premises system shall become an auxiliary alarm system.

27.2 General.

27.2.1* Public emergency alarm reporting systems shall be designed, installed, operated, and maintained in accordance with this chapter to provide reliable transmission and receipt of alarms in a manner acceptable to the authority having jurisdiction.

27.2.2 A public emergency alarm reporting system, as described herein, shall be permitted to be used for the transmission of other signals or calls of a public emergency nature, provided that such transmission does not interfere with the transmission and receipt of fire alarms.

27.2.3* All devices shall be designed to function satisfactorily under the climatic and environmental conditions to which they could be exposed.

27.2.3.1 All devices shall be identified as suitable for the location and conditions for which they are installed.

27.2.4 All circuits, paths, and equipment necessary for the receipt of signals from a protected premises shall be monitored for integrity.

27.3 Management and Maintenance.

27.3.1 All systems shall be under the control of a designated jurisdictional employee.

27.3.2 Maintenance by an organization or person other than from the jurisdiction or an employee of the jurisdiction shall be by written contract, guaranteeing performance acceptable to the authority having jurisdiction.

27.3.3 Where maintenance is provided by an organization or person(s) other than the jurisdiction or its employees, complete written records of the installation, maintenance, test, and extension of the system shall be forwarded to the designated employee in a time period and manner approved by the authority having jurisdiction.

27.3.4 All equipment shall be installed in locations accessible to the authority having jurisdiction for the purpose of maintenance and inspection.

27.3.5 Records of wired public emergency alarm reporting system circuits shall include all of the following:

- (1) Outline plans showing terminals and box sequence
- (2) Diagrams of applicable office wiring

- (3) List of materials used, including trade name, manufacturer, and year of purchase or installation

27.3.6 Public emergency alarm reporting systems as defined in this chapter shall, in their entirety, be subject to a complete operational acceptance test upon completion of system installation.

27.3.6.1 The test(s) required by 27.3.6 shall be made in accordance with the requirements of the authority having jurisdiction; however, in no case shall the operational functions tested be less than those stipulated in Chapter 14.

27.3.6.2 Operational acceptance tests shall be performed on any alarm-reporting devices, as covered in this chapter, that are installed or modified subsequent to the test required by 27.3.6.

27.3.7 Personnel Qualification. Personnel shall be qualified and experienced in accordance with the requirements of 10.5.6.

27.4 Communications Methods.

27.4.1 Application.

27.4.1.1 A public emergency alarm reporting system shall include wired or wireless network(s), for one-way signaling or two-way command and control communications between alarm boxes, alarm processing equipment, and the communications center.

27.4.1.2 A public emergency alarm reporting system shall be permitted to be used with emergency communications systems covered under Chapter 24.

27.4.2 Wired Network(s). The terms *wired network* and *public cable plant* shall be considered the same and interchangeable throughout this chapter.

27.4.2.1 All wired networks or public cable plants shall meet the requirements of Section 27.7.

27.4.2.1.1 Fiber-optic cabling shall be considered an acceptable transmission medium, provided that the cabling and installation comply with the requirements of Section 27.7 and the conversion equipment used to interface to the fiber-optic signal complies with all applicable requirements of Chapter 27.

27.4.2.2 Alarm processing equipment at the communications center shall meet the requirements of 27.5.2 and 27.5.4.

27.4.2.3 Alarm processing equipment at a remote communications center shall meet the requirements of 27.4.2.2 and 27.5.3.

27.4.2.4 Alarm boxes shall meet one of the following requirements:

- (1) Publicly accessible boxes shall meet the requirements of 27.6.1, 27.6.2, and 27.6.5.
- (2) Auxiliary boxes shall meet the requirements of 27.6.1, 27.6.3, and 27.6.5.
- (3) Master boxes shall meet the requirements of 27.6.1 through 27.6.3 and 27.6.5.

27.4.3 Wireless Network(s). The terms *wireless network* and *radio system* shall be considered the same and interchangeable throughout this chapter.

27.4.3.1 All wireless networks shall meet the requirements of 27.4.3.2 through 27.4.3.5.

27.4.3.2 In addition to the requirements of this Code, all wireless equipment shall be designed and operated in compliance with all applicable rules and regulations of the Federal Communications Commission (FCC) or, where required, the National Telecommunications and Information Administration (NTIA).

27.4.3.3* Unlicensed radio frequencies shall not be permitted.

27.4.3.4 Fire alarm signals, other emergency alarm signals, and monitoring for integrity signals shall be permitted on the same radio frequency, dedicated for that purpose.

27.4.3.5 The wireless network capacity for the number of alarm boxes permitted on a single radio frequency shall comply with one of the following:

- (1) For networks that use one-way radio communications, not more than 500 alarm boxes are permitted on a single radio frequency.
- (2) For networks that use two-way radio communications, not more than 250 alarm boxes are permitted on a single radio frequency.
- (3) For networks that use two-way radio communications where a radio frequency that differs from that used for receipt of alarms is used for responses, not more than 500 alarm boxes are permitted on a single radio frequency.

27.4.3.6 Alarm processing equipment at the communications center shall meet the requirements of 27.5.2 and 27.5.5.

27.4.3.7 Alarm processing equipment at a remote communications center shall meet the requirements of 27.4.3.6 and 27.5.3.

27.4.3.8 Alarm boxes shall meet one of the following requirements:

- (1) Publicly accessible boxes shall meet the requirements of 27.6.1, 27.6.2, and 27.6.6.
- (2) Auxiliary boxes shall meet the requirements of 27.6.1, 27.6.3, and 27.6.6.
- (3) Master boxes shall meet the requirements of 27.6.1 through 27.6.3 and 27.6.6.

27.5 Alarm Processing Equipment. The alarm processing equipment required to receive and control the public emergency alarm reporting system shall be installed in the communications center or remote communications center used by emergency response agencies as defined in NFPA 1221.

27.5.1 General. The requirements of 27.5.2 shall apply to all processing equipment, wired or wireless, for a public emergency alarm reporting network.

27.5.2 Alarm Processing Equipment at Communications Center.

27.5.2.1 Type A and Type B Systems.

27.5.2.1.1 Alarm systems shall be Type A or Type B.

27.5.2.1.2 A Type A system shall be provided where the number of all alarms required to be retransmitted exceeds 2500 per year.

27.5.2.1.3 Where a Type A system is required, the automatic electronic retransmission of incoming alarms shall be permitted, provided that both of the following conditions are met:

- (1) Approved facilities are provided for the automatic receipt, storage, retrieval, and retransmission of alarms in the order received.
- (2) The operator(s) of the dispatch facility has the capability to immediately override the automatic retransmission and revert to manual retransmission.

27.5.2.1.4 A Type B system shall be permitted where the number of alarms from alarm boxes is 2500 or less per year provided the following conditions are met:

- (1) Alarms from alarm boxes are automatically transmitted to an emergency response facility where approved equipment is provided for the automatic receipt, storage, and retrieval of alarms.
- (2) Audible and visual alerting devices are provided at the emergency communications center and the emergency response facility.
- (3) All circuits and pathways used for alarm receiving and alerting equipment are monitored for integrity between the emergency communications center and the emergency response facility.
- (4) Audible and visual trouble signals are provided at both the emergency communications center and the emergency response facility to indicate the failure of the circuit or pathway.

27.5.2.2 Visual Recording Devices.

27.5.2.2.1 Alarms from alarm boxes shall be automatically received and recorded at the communications center.

27.5.2.2.2 A device for producing a permanent graphic recording of all alarm, supervisory, trouble, and test signals received or retransmitted, or both, shall be provided at each communications center for each alarm circuit and tie circuit.

27.5.2.2.3 Reserve recording devices shall be provided in accordance with 27.5.2.2.3.1 and 27.5.2.2.3.2.

27.5.2.2.3.1 Where each circuit is served by a dedicated recording device, the number of reserve recording devices required on-site shall be equal to at least 5 percent of the circuits in service and in no case less than one device.

27.5.2.2.3.2 Where two or more circuits are served by a common recording device, a reserve recording device shall be provided on-site for each circuit connected to a common recorder.

27.5.2.2.4 In a Type B wired system, one such recording device shall be installed in each emergency response facility, and at least one shall be installed in the communications center.

27.5.2.2.5 Permanent visual records shall comply with 27.5.2.2.5.1 and 27.5.2.2.5.2.

27.5.2.2.5.1 A permanent visual record and an audible signal shall be required to indicate the receipt of an alarm.

27.5.2.2.5.2 The permanent record shall indicate the exact location from which the alarm is being transmitted.

27.5.2.2.6 The audible signal device shall be permitted to be common to two or more box circuits and arranged so that the emergency alarm operator is able to manually silence the signal temporarily by a self-restoring switch.

27.5.2.2.7 Facilities shall be provided with a device that automatically records the date and time of receipt of each alarm.

27.5.2.3 System Integrity.

27.5.2.3.1 Wired circuits upon which transmission and receipt of alarms depend shall be constantly monitored for integrity to provide prompt warning of conditions adversely affecting reliability.

27.5.2.3.2 The power supplied to all required circuits and devices of the system shall be constantly monitored for integrity.

27.5.2.4 Trouble Signals.

27.5.2.4.1 Trouble signals shall be indicated where there is a trained and competent person on duty at all times.

27.5.2.4.2 Trouble signals shall be distinct from alarm signals and shall be indicated by a visual and audible signal.

27.5.2.4.3 The audible signal shall be permitted to be common to more than one circuit that is monitored for integrity.

27.5.2.4.4 A switch for silencing the audible trouble signal shall be permitted, provided that the visual signal remains operating until the silencing switch is restored to its normal position.

27.5.2.4.5 The audible signal shall be responsive to faults on any other circuits that occur prior to restoration of the silencing switch to its normal position.

27.5.2.5 Power Supply.

27.5.2.5.1 Each box circuit or wireless receiving system shall be powered by one of the following:

- (1)* Form 4A, which is an inverter, powered from a common rectifier, receiving power by a single source of alternating current with a floating storage battery having a 24-hour standby capacity
- (2)* Form 4B, which is an inverter, powered from a common rectifier, receiving power from two sources of alternating current with a floating storage battery having a 4-hour standby capacity

27.5.2.5.2 Form 4A and Form 4B shall be permitted to distribute the system load between two or more common rectifiers and batteries.

27.5.2.5.3 The capacity of batteries, motor generators, rectifiers, or other permitted power supplies shall exceed the calculated load of all connected circuits, so that circuits developing grounds or crosses with other circuits each shall be able to be supplied by an independent source to the extent required by 27.5.2.5.1.

27.5.2.5.4 Provision shall be made to connect any circuit to any battery, generator, or rectifier, or other permitted power supply.

27.5.2.5.5 Individual circuits supplied from common leads shall be protected by the installation of enclosed fuses located at the point where the circuit conductors receive their supply.

27.5.2.5.6 Local circuits at communications centers shall be supplied in accordance with 27.5.2.5.6.1 and 27.5.2.5.6.2.

27.5.2.5.6.1 The source of power for local circuits required to operate the essential features of the system shall be monitored for integrity.

27.5.2.5.6.2 Local circuits at communications centers shall be permitted to be connected to the same power source as box circuits, wireless receiving system circuits, or a separate power source.

27.5.2.5.7 Visual and audible means to indicate a 15 percent or greater reduction of normal power supply (rated voltage) shall be provided.

27.5.2.5.8 Where the electrical service/capacity of the equipment required under Section 4.7 of NFPA 1221 satisfies the needs of equipment in this chapter, such equipment shall not be required to be duplicated.

27.5.2.6 Rectifiers, Converters, Inverters, and Motor Generators.

27.5.2.6.1 Rectifiers shall be supplied from the secondary of an isolating transformer.

27.5.2.6.1.1 The primary of the isolating transformer shall be connected to a circuit not exceeding 250 volts.

27.5.2.6.2 Complete spare units or spare parts shall be in reserve.

27.5.2.6.3 Systems with at least one rectifier shall comply with 27.5.2.6.3.1 and 27.5.2.6.3.2.

27.5.2.6.3.1 One spare rectifier shall be provided for every 10 operating rectifiers on a system.

27.5.2.6.3.2 All systems shall have at least one spare rectifier.

27.5.2.6.4 Leads from rectifiers or motor generators that have a float-charged battery shall be protected by fuses rated at a minimum of 1 ampere and a maximum of 200 percent of connected load at nominal circuit voltage.

27.5.2.6.5 Leads from rectifiers or motor generators that do not have a float-charged battery shall be protected by fuses rated at a minimum of 3 amperes and a maximum of 200 percent of connected load at nominal circuit voltage.

27.5.2.7 Engine-Driven Generators. The installation of engine-driven generator sets shall conform to the provisions of NFPA 37, NFPA 110, and NFPA 1221.

27.5.2.8 Float-Charged Batteries.

27.5.2.8.1 Float-charged batteries shall be of the storage type. Primary batteries (i.e., dry cells) shall not be used.

27.5.2.8.1.1 Vented lead-acid batteries shall be in approved transparent materials.

27.5.2.8.1.2 Other types of batteries shall be in containers identified or approved for the purpose.

27.5.2.8.2 Float-charged batteries shall be above building grade level.

27.5.2.8.3 Float-charged batteries shall be located on the same floor of the building as the operating equipment.

27.5.2.8.4 Float-charged batteries shall be accessible for maintenance and inspection.

27.5.2.8.5 Float-charged batteries shall be installed in accordance with Article 480 of NFPA 70.

27.5.2.8.6 Overcurrent protection shall be provided and arranged such that the intentional or unintentional opening of the overcurrent devices between either the batteries or rectifiers does not render the public emergency alarm reporting system inoperable.

27.5.2.8.7 Batteries shall be mounted to provide effective isolation from the ground or working platform and from other batteries.

27.5.2.8.7.1 Mounting equipment shall be listed and identified for the location.

27.5.2.8.7.2 It shall be permissible for the authority having jurisdiction to waive this requirement to allow the use of alternative mounting equipment where it is assured that equivalent objectives can be achieved.

27.5.2.8.8 Battery mounting shall be protected against deterioration and shall provide stability, especially in geographic areas subject to seismic disturbance.

27.5.2.9 Equipment Fire Protection. Where applicable, electronic computer/data processing equipment shall be protected in accordance with NFPA 75.

27.5.3* Remote Communications Center. Where the communications center is remotely located from the wired or wireless alarm processing equipment, the requirements of 27.5.3.1 through 27.5.3.7, in addition to all of the requirements of Section 27.5, shall apply.

27.5.3.1 All equipment shall be listed for its intended use and shall be installed in accordance with NFPA 70.

27.5.3.2 Alarm processing equipment located remote from the communications center shall be capable of providing basic dispatching information independent of the communications center.

27.5.3.3 The alarm processing equipment shall be located where it can be monitored for alarm and trouble conditions and shall be accessible to be manned in case of a pathway or communications failure with the communications center.

27.5.3.4 Wired or wireless alarm repeating systems used to repeat signals between a remote communications center and the alarm processing equipment location shall meet the requirements of 27.5.3.4.1 through 27.5.3.4.7.

27.5.3.4.1 There shall be a minimum of two complete and independent alarm repeater systems, including batteries and power supplies, to provide redundancy.

27.5.3.4.2 If the alarm repeater system is configured with one alarm repeater in standby mode, the system shall be capable of detecting a communications failure and shall automatically switch to the backup system without interruption or loss of any alarm or trouble transmission.

27.5.3.4.3 Alarm repeater systems shall not be used for any purpose other than alarm communications between the communications center and the alarm processing equipment.

27.5.3.4.4 Wireless alarm repeaters shall operate on a licensed frequency dedicated for this purpose.

27.5.3.4.4.1 Wireless alarm repeaters shall be licensed to a public entity.

27.5.3.4.4.2 Unlicensed frequencies shall not be permitted.

27.5.3.4.5 The communications method used for the alarm repeater, wired or wireless, shall be two-way.

27.5.3.4.6 The public emergency alarm reporting system communications infrastructure shall be used to repeat alarm and trouble signals between the alarm processing equipment and a remote communications center.

27.5.3.4.7 Where it is not possible to use the public emergency alarm reporting system communications infrastructure to provide communications between the alarm processing equipment and the remote communications center, an alternative repeater method shall be permitted and shall meet the requirements of 27.5.3.4.7.1 and 27.5.3.4.7.2.

27.5.3.4.7.1 If an alternative alarm repeater method is used it shall be publicly owned, operated, and controlled.

27.5.3.4.7.2 The alternative alarm repeater method shall meet the requirements of 27.5.3, except 27.5.3.4.2 shall not apply.

27.5.3.5 Pathways between the remote communications center and the alarm processing equipment shall be monitored for integrity and shall be dedicated and not used for any other purpose.

27.5.3.6 When communications between the communications center and the alarm processing equipment fails, the requirements of 27.5.3.6.1 through 27.5.3.6.3 shall apply.

27.5.3.6.1 A pathway or communications trouble condition shall be detected and annunciated at both the communications center and the alarm processing equipment location within 200 seconds and shall meet the requirements of 27.5.2.4.

27.5.3.6.2 Visual and audible trouble alarm indications pertaining to a pathway or communications failure between the communications center and the alarm processing equipment location shall be distinct from all other trouble alarms.

27.5.3.6.3 The alarm processing equipment shall be manned by trained personnel until communications can be re-established.

27.5.3.7 Power supplies shall be provided in accordance with 27.5.2.5.

27.5.4 Wired Network Systems.

27.5.4.1 System Arrangement and Operation.

27.5.4.1.1 For a Type B system, the effectiveness of noninterference and succession functions between box circuits shall be no less than between boxes in any one circuit.

27.5.4.1.2 A metallic box open circuit condition shall cause a warning signal in all other circuits, and, thereafter, the circuit(s) not in the open circuit condition shall be automatically restored to operative condition.

27.5.4.1.3 Box circuits shall be sufficient in number and laid out so that the areas that would be left without box protection in case of disruption of a circuit do not exceed those covered by 20 properly spaced boxes where all or any part of the circuit is of aerial open-wire, or by 30 properly spaced boxes where the

circuit is entirely in underground or messenger-supported cable.

27.5.4.1.4 Where all boxes on any individual circuit and associated equipment are designed and installed to provide for receipt of alarms through the ground in the event of a break in the circuit, the circuit shall be permitted to serve twice the number of aerial open-wire and cable circuits, respectively, as are specified in 27.5.4.1.3.

27.5.4.1.5 The installation of additional boxes in an area served by the number of boxes spaced as indicated in 27.5.4.1.1 through 27.5.4.1.4 shall not constitute geographical overloading of a circuit.

27.5.4.1.6 Sounding devices for signals shall be provided for box circuits.

27.5.4.1.6.1 A common sounding device for more than one circuit shall be permitted to be used in a Type A system and shall be installed at the communications center.

27.5.4.1.6.2 In a Type B system, a sounding device shall be installed in each emergency response facility at the same location as the recording device for that circuit, unless installed at the communications center, where a common sounding device shall be permitted.

27.5.4.2 Constant-Current Systems. Constant-current systems shall comply with the requirements of 27.5.4.2.1 through 27.5.4.2.6.

27.5.4.2.1 Means shall be provided for manually regulating the current in box circuits so that the operating current is maintained within 10 percent of normal throughout changes in external circuit resistance from 20 percent above normal to 50 percent below normal.

27.5.4.2.2 The voltage supplied to maintain normal line current on box circuits shall comply with both of the following:

- (1) The voltage shall not exceed 150 volts, measured under no-load conditions.
- (2) The voltage shall be such that the line current cannot be reduced below the approved operating value by the simultaneous operation of four boxes.

27.5.4.2.3 Visual and audible means to indicate a 20 percent or greater reduction in the normal current in any alarm circuit shall be provided.

27.5.4.2.4 All devices connected in series with any alarm circuit shall function when the alarm circuit current is reduced to 70 percent of normal.

27.5.4.2.5 Meters shall comply with 27.5.4.2.5.1 and 27.5.4.2.5.2.

27.5.4.2.5.1 Meters shall be provided to indicate the current in any box circuit and the voltage of any power source.

27.5.4.2.5.2 Meters used in common for two or more circuits shall be provided with cut-in devices designed to reduce the probability of cross-connecting circuits.

27.5.4.2.6 Necessary switches, testing, and signal transmitting and receiving devices shall be provided to allow the isolation, control, and test of each circuit up to at least 10 percent of the total number of box and dispatch circuits, but never less than two circuits.

27.5.4.3 Grounded Common-Current Systems. Where common-current source systems are grounded, the requirements of 27.5.4.3.1 and 27.5.4.3.2 shall apply.

27.5.4.3.1 Where common-current source systems are grounded, the resistance of the ground shall not exceed 10 percent of resistance of any connected circuit and shall be located at one side of the battery.

27.5.4.3.2 Visual and audible indicating devices shall be provided for each box and dispatch circuit to give immediate warning of ground leakage current that will have a detrimental effect on circuit operation.

27.5.4.4 Telephone (Series) Reporting Systems.

27.5.4.4.1 A permanent visual recording device installed in the communications center shall be provided to record all incoming box signals.

27.5.4.4.2 A spare recording device shall be provided for five or more box circuits.

27.5.4.4.3 A second visual means of identifying the calling box shall be provided.

27.5.4.4.4 Audible signals shall indicate all incoming calls from box circuits.

27.5.4.4.5 All voice transmissions from boxes for emergencies shall be recorded with the capability of instant playback.

27.5.4.4.6 A voice-recording facility shall be provided for each operator handling incoming alarms to eliminate the possibility of interference.

27.5.4.4.7 Box circuits shall be sufficient in number and laid out so that the areas that would be left without box protection in case of disruption of a circuit do not exceed those covered by 20 properly spaced boxes where all or any part of the circuit is of aerial open-wire, or 30 properly spaced boxes where the circuit is entirely in underground or messenger-supported cable.

27.5.4.4.8 Where all boxes on any individual circuit and associated equipment are designed and installed to provide for receipt of alarms through the ground in the event of a break in the circuit, the circuit shall be permitted to serve twice the number of aerial open-wire and cable circuits, respectively, as is specified in 27.5.4.4.7.

27.5.4.4.9 The installation of additional boxes in an area served by the number of boxes spaced as indicated in 27.5.4.4.7 shall not constitute geographical overloading of a circuit.

27.5.5 Wireless Network.

27.5.5.1 System Arrangement and Operation.

27.5.5.1.1* Type A systems shall comply with 27.5.5.1.1.1 through 27.5.5.1.1.7.

27.5.5.1.1.1 Two separate receiving networks shall be required for each frequency.

27.5.5.1.1.2 Each receiving network shall include the following:

- (1) Antenna
- (2) RF receiver
- (3) Signaling processing equipment
- (4) Time/date alarm printer

(5) Audible alerting device

(6) Power supply

27.5.5.1.1.3 Both receiving networks shall be installed at the communications center.

27.5.5.1.1.4 The failure of one receiving network shall not interfere with the other receiving network's ability to receive messages from boxes.

27.5.5.1.1.5 Where the system configuration is such that a polling device is incorporated into the receiving network to allow remote or selective initiation of box tests, a separate device shall be included in each of the two required receiving networks.

27.5.5.1.1.6 The polling devices shall be configured for automatic cycle initiation in their primary operating mode, shall be capable of continuous self-monitoring, and shall be integrated into the network(s) to provide automatic switchover and operational continuity in the event of failure of either device.

27.5.5.1.1.7 Test signals from boxes shall not be required to include the date as part of their permanent recording, provided that the date is automatically printed on the recording tape at the beginning of each calendar day.

27.5.5.1.2 Type B systems shall comply with 27.5.5.1.2.1 through 27.5.5.1.2.3.

27.5.5.1.2.1 For each frequency used, a single, complete receiving network shall be permitted in each emergency response facility, provided that the communications center conforms to 27.5.5.1.1.1 through 27.5.5.1.1.3.

27.5.5.1.2.2 Where the jurisdiction maintains two or more alarm reception points in operation, one receiving network shall be permitted to be at each alarm reception point.

27.5.5.1.2.3 Where alarm signals are transmitted to an emergency response facility from the communications center using the wireless-type receiving equipment in the emergency response facility to receive and record the alarm message, a second receiving network conforming to 27.5.5.1.2.1 shall be provided at each emergency response facility, and that receiving network shall employ a frequency other than that used for the receipt of box messages.

27.5.5.1.3 A device for producing a permanent graphic recording of all alarm, supervisory, trouble, and test signals received or retransmitted, or both, shall be provided at the communications center.

27.5.5.1.4* Where box message signals to the communications center or acknowledgment of message receipt signals from the communications center to the box are repeated, associated repeating facilities shall conform to the requirements of 27.5.5.1.1.2(1), 27.5.5.1.1.2(2), 27.5.5.1.1.2(3), and 27.5.5.1.1.2(6) and include two separate transmitters.

27.5.5.2 Power. Power shall be provided in accordance with 27.5.2.5.

27.5.5.3 Monitoring for Integrity.

27.5.5.3.1 All wireless box systems shall comply with 27.5.5.3.1.1 and 27.5.5.3.1.2.

27.5.5.3.1.1 All wireless box systems shall provide constant monitoring of each radio frequency in use.

27.5.5.3.1.2 Both an audible and a visual indication of any sustained signal in excess of a 15-second duration shall be provided for each receiving system at the communications center.

27.5.5.3.2 The power supplied to all required circuits and devices of the system shall be monitored for integrity.

27.5.5.3.3* Each wireless box shall automatically transmit a test message at least once in each 24-hour period.

27.5.5.3.4 Receiving equipment associated with wireless-type systems shall comply with 27.5.5.3.4.1 and 27.5.5.3.4.2.

27.5.5.3.4.1 Receiving equipment associated with wireless-type systems, including any related repeater(s), shall be tested at least hourly.

27.5.5.3.4.2 The receipt of test messages that do not exceed 60-minute intervals shall meet the requirement in 27.5.5.3.4.1.

27.5.5.3.5 Radio repeaters upon which receipt of alarms depend shall be provided with dual receivers, transmitters, and power supplies.

27.5.5.3.5.1 Failure of the primary receiver, transmitter, or power supply shall cause an automatic switchover to the secondary receiver, transmitter, or power supply.

27.5.5.3.5.2 Manual switchover shall be permitted, provided that it is completed within 30 seconds.

27.5.5.3.6 Trouble signals shall activate a sounding device located where there is always a trained, competent person on duty.

27.5.5.3.7 Trouble signals shall be distinct from alarm signals and shall be indicated by a visual and audible signal.

27.5.5.3.7.1 The audible signal shall be permitted to be common to two or more monitored circuits.

27.5.5.3.7.2 A switch for silencing the audible trouble signal shall be permitted where the visual signal remains operating until the silencing switch is restored to its normal position.

27.5.5.3.8 The audible signal shall be responsive to subsequent faults in other monitored functions prior to restoration of the silencing switch.

27.5.5.4 Physical Protection of Transmission Line. The antenna transmission line between the transmitter and the antenna shall be installed in rigid metal, intermediate metal conduit, or electrical metallic tubing in accordance with *NFPA 70*.

27.6 Alarm Boxes.

27.6.1* General. The requirements of 27.6.1.1 through 27.6.1.6 shall apply to all alarm boxes.

27.6.1.1 Concurrent operation of at least four boxes shall not result in the loss of an alarm.

27.6.1.2 Boxes and associated equipment, when in an abnormal condition, shall not disable the public emergency alarm reporting system circuit.

27.6.1.3 Boxes shall be designed so that recycling does not occur when a box-actuating device is held in the actuating position and shall be ready to accept a new signal as soon as the actuating device is released.

27.6.1.4* Boxes, when actuated, shall give a visual or audible indication to the user that the box is operating or that the signal has been transmitted to the communications center.

27.6.1.5 Box cases and parts that are accessible to the public shall be permitted to be of nonconductive material.

27.6.1.6 Box cases and parts that are accessible to the public and that are constructed of conductive materials shall be installed in accordance with the requirements of *NFPA 70*, Articles 250 and 760.

27.6.2* Publicly Accessible Alarm Boxes.

27.6.2.1 Fundamental Requirements. The requirements of 27.6.2.1.1 through 27.6.2.1.11 shall apply to all publicly accessible alarm boxes.

27.6.2.1.1 Means for actuation of alarms by the public shall be located where they are visible, unobstructed, and readily accessible.

27.6.2.1.2 The box housing shall protect the internal components and shall be identified for the location installed.

27.6.2.1.3 Doors on boxes shall remain operable under adverse climatic conditions, including icing and salt spray.

27.6.2.1.4 Boxes shall be recognizable as such and shall have instructions for use plainly marked on their exterior surfaces.

27.6.2.1.5 Boxes shall be securely mounted on poles, pedestals, or structural surfaces as directed by the authority having jurisdiction.

27.6.2.1.6* The location of publicly accessible boxes shall be designated by the authority having jurisdiction.

27.6.2.1.7 Schools, hospitals, nursing homes, and places of public assembly shall have a box located at the main entrance, as directed by the authority having jurisdiction.

27.6.2.1.8 Boxes shall be conspicuously visible and be highlighted with a distinctive color.

27.6.2.1.9 All publicly accessible boxes mounted on support poles shall be identified by a wide band of distinctive colors or signs placed 8 ft (2.44 m) above the ground and visible from all directions wherever possible.

27.6.2.1.10* Location-designating lights shall comply with 27.6.2.1.10.1 and 27.6.2.1.10.2.

27.6.2.1.10.1 Location-designating lights of distinctive color, visible for at least 1500 ft (460 m) in all directions, shall be installed over boxes.

27.6.2.1.10.2 The street light nearest the box, where equipped with a distinctively colored light, shall meet 27.6.2.1.10.1.

27.6.2.1.11 Where boxes are installed inside a structure, the installation shall comply with 27.6.2.1.11.1 through 27.6.2.1.11.4.

27.6.2.1.11.1 The box shall be placed as close as is practicable to the point of entrance of the circuit.

27.6.2.1.11.2* Outside plant cables entering buildings or other structures shall be installed in rigid metal conduit, intermediate metal conduit, or electrical metallic tubing.

27.6.2.1.11.3 Schedule 80 PVC or RTRC rigid nonmetallic conduit shall be permitted for underground installations,

provided that all elbows are rigid or intermediate metal conduit.

27.6.2.1.11.4 The installation shall comply with the requirements of the applicable raceway article of *NFPA 70*.

27.6.3 Auxiliary Alarm Box.

27.6.3.1 Fundamental Requirements. The requirements of 27.6.3.1.1 through 27.6.3.1.6 shall apply to all auxiliary alarm boxes.

27.6.3.1.1 The authority having jurisdiction shall designate the location of the auxiliary box.

27.6.3.1.2* Outside plant cables entering buildings or other structures shall be installed in rigid metal conduit, intermediate metal conduit, or electrical metallic tubing.

27.6.3.1.2.1 Schedule 80 PVC or RTRC rigid nonmetallic conduit shall be permitted for underground installations, provided that all elbows are rigid or intermediate metal conduit.

27.6.3.1.2.2 The use of schedule 40 PVC shall be permitted where encased by not less than 2 in. (300 mm) of concrete.

27.6.3.1.2.3 The installation shall comply with the requirements of the applicable raceway article of *NFPA 70*.

27.6.3.1.3* Wiring between the auxiliary alarm system and the auxiliary alarm box or master alarm box shall be installed in rigid metal conduit, intermediate metal conduit, or electrical metallic tubing and shall meet the requirements of pathway survivability Level 2 (*see 12.4.3*).

27.6.3.1.4 Where installed outside a structure, the requirements of 27.6.2.1.2 and 27.6.2.1.5 shall apply.

27.6.3.1.5 Where the auxiliary box is a wired box, the requirements of Section 27.7 shall apply.

27.6.3.1.6 Where the auxiliary box is a wireless box, the requirements of 27.6.6 shall apply.

27.6.3.2 Auxiliary Alarm Systems.

27.6.3.2.1 Application. The equipment and circuits necessary to connect a protected premises to a public emergency alarm reporting system shall comply with the requirements of 27.6.3.2.

27.6.3.2.1.1 Where permitted by the authority having jurisdiction, the use of systems described in Chapter 27 shall be permitted to provide defined reporting functions from or within private premises.

27.6.3.2.1.2 The requirements of Section 27.7 shall also apply to wired auxiliary alarm systems.

27.6.3.2.2 Types of Systems.

27.6.3.2.2.1* Auxiliary alarm systems shall be local-energy type with the following requirements:

- (1) Local-energy-type systems shall be permitted to be of the coded or noncoded type.
- (2) Power supply sources for local-energy-type systems shall conform to Chapter 10.
- (3) Transmitter trouble signals shall be indicated at the control unit and the building fire command center in accordance with 10.15.7.

27.6.3.2.2.2 The interface of auxiliary alarm systems with the three types of public emergency alarm reporting systems shall be in accordance with Table 27.6.3.2.2.2.

27.6.3.2.2.3 The application of auxiliary alarm systems shall be limited to the initiating devices specified in Table 27.6.3.2.2.3.

27.6.3.2.3 System Arrangement and Operation.

27.6.3.2.3.1 A separate auxiliary transmitter shall be provided for each building, or where permitted by the authority having jurisdiction, for each group of buildings of single ownership or occupancy.

27.6.3.2.3.2 The same box shall be permitted to be used as a public emergency alarm reporting system box and as a transmitting device for an auxiliary alarm system where permitted by the authority having jurisdiction, provided that the box is located at the outside of the entrance to the protected property.

27.6.3.2.3.3 Where 27.6.3.2.3.2 is applied, the authority having jurisdiction shall be permitted to require the box to be equipped with a signal light to differentiate between automatic and manual operation, unless local outside alarms at the protected property serve the same purpose.

27.6.3.2.3.4 The transmitting device shall be located as required by the authority having jurisdiction.

27.6.3.2.3.5 Design and arrangement of auxiliary alarm systems shall meet the following:

- (1) The system shall be designed and arranged so that a single fault on the auxiliary alarm system does not jeopardize operation of the public emergency alarm reporting system.
- (2) The system shall not, in case of a single fault on either the auxiliary or public emergency alarm reporting system, transmit a false alarm on either system.

27.6.3.2.3.6 A means that is available only to the agency responsible for maintaining the public emergency alarm reporting system shall be provided for disconnecting the auxiliary loop to the connected property.

Table 27.6.3.2.2.2 Application of Public Emergency Alarm Reporting Systems with Auxiliary Alarm Systems

Reporting Systems	Local-Energy Type
Wired	Yes
Wireless	Yes
Telephone series	Yes

Table 27.6.3.2.2.3 Application of Initiating Devices with Auxiliary Alarm Systems

Initiating Devices	Local-Energy Type
Manually actuated alarm-initiating device	Yes
Waterflow or actuation of the fire-extinguishing system(s) or suppression system(s)	Yes
Automatic detection devices	Yes

27.6.3.2.3.7 Notification shall be given to the designated representative of the property when the auxiliary box is not in service.

27.6.3.2.3.8 An auxiliary alarm system shall be used only in connection with a public emergency alarm reporting system that is approved for the service.

27.6.3.2.3.9 A system approved by the authority having jurisdiction shall meet the requirement in 27.6.3.2.3.8.

27.6.3.2.3.10 Permission for the connection of an auxiliary alarm system to a public emergency alarm reporting system, and acceptance of the type of auxiliary transmitter and its activating mechanism, circuits, and components connected thereto, shall be obtained from the authority having jurisdiction.

27.6.3.2.3.11 Paragraph 27.6.3.2 shall not require the use of audible alarm signals other than those necessary to operate the auxiliary alarm system.

27.6.3.2.3.12 Where it is desired to provide evacuation signals in the protected property, the notification appliances, circuits, and controls shall comply with the provisions of Chapter 23 in addition to the provisions of 27.6.3.2.

27.6.3.2.3.13 Where an auxiliary alarm system is in an alarm condition that has been acknowledged, deactivated, or bypassed, subsequent actuation of initiating devices on other initiating device circuits or subsequent actuation of addressable initiating devices on signaling line circuits shall cause an alarm signal to be transmitted to the communications center.

27.6.3.2.3.14 Where an auxiliary transmitter is located within a private premises, it shall be installed in accordance with 27.6.2.1.11 and 27.7.2.

27.6.3.2.3.15 Where data communications between a microprocessor-based control unit and an auxiliary alarm system are utilized, they shall comply with all of the requirements in 27.6.3.2.3.15(A) through 27.6.3.2.3.15(C).

(A) The monitoring for integrity shall include communications test messages transmitted between the control unit and the auxiliary alarm system.

(B) The communications test message shall comply with all of the following:

- (1) The communications test message shall be initiated by either the control unit or the auxiliary alarm system.
- (2) The communications test message shall require a response from the corresponding unit.
- (3) An invalid response or no response from the control unit or the auxiliary alarm system shall be recognized as a communications failure.
- (4) A communications failure shall initiate a specific communications failure trouble message. [See 27.6.3.2.3.15(B)(3).]
- (5) A communications failure trouble message as referenced in 27.6.3.2.3.15(B)(2) shall be both of the following:
 - (a) Transmitted from the auxiliary alarm system
 - (b) Automatically indicated within 200 seconds at the communications center
- (6) A trouble condition in 27.6.3.2.3.15(B)(4) shall activate an audible and distinctive visual signal at the auxiliary box indicating a communications failure.

- (7) A trouble condition shall be indicated at the control unit and the building fire command center in accordance with 10.15.7.

(C) Where a separate device is required to interface the control unit to the auxiliary alarm system, all communication paths shall be both of the following:

- (1) Monitored for integrity
- (2) Compliant comply with 27.6.3.2.3.15

27.6.4 Master Alarm Boxes. Master alarm boxes shall comply with the requirements of 27.6.2 and 27.6.3.

27.6.5 Wired Network Boxes. The requirements of Section 27.7 shall apply to wired network boxes.

27.6.5.1 Telephone Boxes. The requirements of Section 27.7 shall also apply to telephone boxes.

27.6.5.1.1 Where a handset is used, the caps on the transmitter and receiver shall be secured to reduce the probability of the telephone box being disabled due to vandalism.

27.6.5.1.2 Telephone boxes shall be designed to allow the communications center operator to determine whether or not the telephone box has been restored to normal condition after use.

27.6.6 Wireless Network Boxes.

27.6.6.1 In addition to the requirements of this Code, wireless boxes shall be designed and operated in compliance with all applicable rules and regulations of the Federal Communications Commission (FCC) or, where required by other governing laws, the National Telecommunications and Information Administration (NTIA).

27.6.6.2* Each wireless box shall automatically transmit a test message at least once in each 24-hour period.

27.6.6.3 Wireless network boxes shall be capable of transmitting no less than three specific signals to the communications center, in addition to the box number, with priority as follows:

- (1) Alarm
- (2) Tamper
- (3) Test

27.6.6.4 Wireless boxes shall transmit to the communications center with priority as follows:

- (1) No less than two repetitions for "alarm"
- (2) No less than one repetition for "tamper"
- (3) No less than one repetition for "test"

27.6.6.5 Where wireless network boxes transmit more than one alarm signal, in addition to those in 27.6.6.3, each such signal shall be individually identifiable.

27.6.6.6 Where wireless network boxes transmit more than one alarm signal, they shall be designed to prevent the loss of supplemental or concurrently activated signals.

27.6.6.7* Where wireless network boxes transmit more than one alarm signal, the priority of each alarm shall be as assigned by the authority having jurisdiction.

27.6.6.8 An actuating device held or locked in the activated position shall not prevent the activation and transmission of other signals.

27.6.6.9 The primary power source for wireless boxes shall be permitted to be from one or more of the following, as approved by the authority having jurisdiction:

- (1) Utility distribution system
- (2) Solar photovoltaic power system
- (3) User power
- (4) Self-powered, using either an integral battery or other stored energy source

27.6.6.10 Boxes powered by a utility distribution system shall comply with 27.6.6.10.1 through 27.6.6.10.6.

27.6.6.10.1 Boxes shall comply with 27.6.6.10.1.1 and 27.6.6.10.1.2.

27.6.6.10.1.1 Boxes shall have an integral standby, sealed, rechargeable battery that is capable of powering box functions for at least 60 hours in the event of primary power failure.

27.6.6.10.1.2 Transfer to standby battery power shall be automatic and without interruption to box operation.

27.6.6.10.2 A local trouble indication shall activate upon primary power failure.

27.6.6.10.3 Boxes operating from primary power shall be capable of operation with a dead or disconnected battery.

27.6.6.10.4 A battery charger shall be provided in compliance with 10.6.10.3, except as modified in 27.6.6.10.

27.6.6.10.5 When the primary power has failed, boxes shall transmit a power failure message to the communications center as part of subsequent test messages until primary power is restored.

27.6.6.10.6 A low-battery message shall be transmitted to the communications center where the remaining battery standby time is less than 54 hours.

27.6.6.11 Boxes powered by a solar photovoltaic system shall comply with 27.6.6.11.1 through 27.6.6.11.5.

27.6.6.11.1 Solar photovoltaic power systems shall provide box operation for not less than 6 months.

27.6.6.11.2 Solar photovoltaic power systems shall be monitored for integrity.

27.6.6.11.3 The battery shall have power to sustain operation for a minimum period of 15 days without recharging.

27.6.6.11.4 Boxes shall comply with 27.6.6.11.4.1 and 27.6.6.11.4.2.

27.6.6.11.4.1 The box shall transmit a trouble message to the communications center when the charger has failed for more than 24 hours.

27.6.6.11.4.2 The trouble message shall be part of all subsequent transmissions.

27.6.6.11.5 Where the remaining battery standby duration is less than 10 days, a low-battery message shall be transmitted to the communications center.

27.6.6.12 User-powered boxes shall have an automatic self-test feature.

27.6.6.13 Self-powered boxes shall comply with 27.6.6.13.1 through 27.6.6.13.3.

27.6.6.13.1 Self-powered boxes shall operate for a period of not less than 6 months.

27.6.6.13.2 Self-powered boxes shall comply with 27.6.6.13.2.1 and 27.6.6.13.2.2.

27.6.6.13.2.1 Self-powered boxes shall transmit a low-power warning message to the communications center for at least 15 days prior to the time the power source will fail to operate the box.

27.6.6.13.2.2 The low-power warning message shall be part of all subsequent transmissions.

27.6.6.13.3 Self-powered boxes shall comply with 27.6.6.13.3.1 and 27.6.6.13.3.2.

27.6.6.13.3.1 Use of a charger to extend the life of a self-powered box shall be permitted where the charger does not interfere with box operation.

27.6.6.13.3.2 The box shall be capable of operation for not less than 6 months with the charger disconnected.

27.7 Public Cable Plant. Metallic and fiber-optic cabling systems and interconnections between alarm transmission equipment and alarm-receiving equipment shall comply with the requirements of Section 27.7.

27.7.1 Requirements for Metallic and Fiber-Optic Systems — Metallic and Fiber-Optic Interconnections.

27.7.1.1 Circuit Conductors and Optical Fibers.

27.7.1.1.1 Exterior metallic conductors and optical fiber cables, other than those provided by a public utility on a lease basis, shall conform to International Municipal Signal Association (IMSA) specifications or an approved equivalent.

27.7.1.1.2 Where a public box is installed inside a building, the circuit from the point of entrance to the public box shall be installed in rigid metal conduit, intermediate metal conduit, or electrical metallic tubing in accordance with *NFPA 70*.

27.7.1.1.3 Wires and optical fibers shall be terminated to prevent breaking from vibration or stress.

27.7.1.1.4 Circuit conductors and optical fiber cables on terminal racks shall be identified and isolated from conductors of other systems wherever possible and shall be protected from mechanical injury.

27.7.1.2 Cables. The requirements of 27.7.1.2 shall apply to 27.7.1.3 through 27.7.1.6.

27.7.1.2.1 Exterior metallic conductors and optical fiber cables shall conform to IMSA specifications or an approved equivalent.

27.7.1.2.2 Overhead, underground, or direct-burial cables shall be specifically approved for the purpose.

27.7.1.2.3 Metallic conductors and optical fiber cables used in interior installations shall comply with both of the following:

- (1) *NFPA 70*
- (2) Be installed in accordance with the manufacturer's installation instructions and practices

27.7.1.2.4 Conductors or optical fibers used to transmit signals of other systems that are under the control of a governmental agency shall be permitted to be contained within the same

multi-conductor cable as conductors or optical fibers used to transmit signals of public emergency alarm reporting systems.

27.7.1.2.5 By special permission as defined in *NFPA 70*, cables not under the control of a governmental agency shall be permitted to contain conductors or optical fibers used to transmit signals of a public emergency alarm reporting system.

27.7.1.2.6 Signaling wire containing metallic protection or strength members and conductive optical fiber cables shall comply with 27.7.1.2.6.1 and 27.7.1.2.6.2.

27.7.1.2.6.1 Signaling wires supplied by a power source having a voltage or current rating sufficient to introduce a hazard shall be installed in accordance with *NFPA 70*, Article 760, Part II.

27.7.1.2.6.2 Conductive optical fiber cables shall be grounded and protected in accordance with *NFPA 70*.

27.7.1.2.7 Metallic cables shall comply with 27.7.1.2.7.1 and 27.7.1.2.7.2.

27.7.1.2.7.1 All metallic cables, with all taps and splices made, shall be tested for insulation resistance when installed but before connection to terminals.

27.7.1.2.7.2 Tests shall indicate an insulation resistance of at least 200 megohms per mile between any one conductor and all other conductors, the sheath, and the ground.

27.7.1.3 Underground Cables.

27.7.1.3.1 Underground metallic conductors and optical fiber cables in duct systems or direct burial shall be permitted to be brought aboveground only at locations approved by the authority having jurisdiction.

27.7.1.3.1.1 Protection from physical damage or heat incidental to fires in adjacent buildings shall be provided.

27.7.1.3.2 Only optical fiber and power-limited cables and conductors shall be permitted to be located in duct systems and manholes that contain power-limited public emergency alarm reporting system conductors.

27.7.1.3.3 Where located in duct systems or manholes that contain power circuit conductors over 250 volts to ground, metallic conductors and optical fiber cables for emergency alarm shall be both of the following:

- (1) Located as far as possible from such power cables
- (2) Separated from such power cables by a noncombustible barrier or other means approved by the authority having jurisdiction to protect the emergency alarm cables from physical damage

27.7.1.3.4 All cables installed in manholes shall be racked and marked for identification.

27.7.1.3.5 Raceways or ducts entering buildings from underground duct systems shall be sealed with an identified sealing compound or other means acceptable to the authority having jurisdiction to prevent the entrance of moisture or gases from the underground duct system.

27.7.1.3.6 All cable joints shall be located in manholes, emergency response facilities, or other accessible locations acceptable to the authority having jurisdiction where equivalent protection is provided to minimize physical damage to the cable.

27.7.1.3.6.1 Cable joints shall be made to provide and maintain conductivity, optical continuity for optical fiber cable, insulation, and protection at least equal to that afforded by the cables that are joined.

27.7.1.3.6.2 Open cable ends shall be sealed against moisture.

27.7.1.3.7 Direct-burial cable, without enclosure in ducts, shall be laid in grass plots, under sidewalks, or in other places where the ground is not likely to be opened for other underground construction.

27.7.1.3.7.1 Where splices are made, such splices shall be accessible for inspection and tests.

27.7.1.3.7.2 Such cables shall be both of the following:

- (1) Buried at least 18 in. (460 mm) deep
- (2) In duct or conduit where crossing streets or other areas likely to be opened for other underground construction

27.7.1.4 Aerial Construction.

27.7.1.4.1 Cables containing conductors or fiber optical fibers used to transmit signals of public emergency alarm reporting systems shall be located below all other cables and conductors, except those used for communications purposes.

27.7.1.4.1.1 Precautions shall be provided where passing through trees, under bridges, over railroads, and at other places where subject to physical damage.

27.7.1.4.1.2 Conductors and cables for public emergency alarm reporting system use shall not be attached to a crossarm that carries electric light and power conductors.

27.7.1.4.1.3 Conductors that operate at 250 volts or less and are part of the public emergency alarm reporting system shall be permitted to share the crossarm with conductors and cables for public emergency alarm reporting systems.

27.7.1.4.2 Aerial cable shall be either supported by messenger wire of approved tensile strength or conform to one of the following:

- (1) IMSA specifications as a self-supporting cable assembly or an approved equivalent
- (2) Optical fiber cable with integral supporting means or all-dielectric self-supporting (ADSS) type

27.7.1.4.3 Single wire shall comply with 27.7.1.4.3.1 and 27.7.1.4.3.2.

27.7.1.4.3.1 Single wire shall meet IMSA specifications and conform to one of the following:

- (1) Be at least No. 10 Roebling gauge if of galvanized iron or steel
- (2) Be at least 10 AWG if of hard-drawn copper
- (3) Be at least 12 AWG if of approved copper-covered steel
- (4) Be at least 6 AWG if of aluminum

27.7.1.4.3.2 Span lengths shall not exceed the manufacturer's recommendations.

27.7.1.4.4 Wires to buildings shall contact only intended supports.

27.7.1.4.5 Wires to buildings shall enter through an approved weatherhead or sleeves slanting upward and inward.

27.7.1.4.6 Drip loops shall be formed on wires outside of buildings.

27.7.1.5 Leads Down Poles.

27.7.1.5.1 Leads down poles shall be protected from physical damage. Any metallic covering shall form a continuous conducting path to ground. Installation, in all cases, shall prevent water from entering the conduit or box.

27.7.1.5.2 Leads to boxes shall have 600-volt insulation listed or approved for wet locations, as defined in *NFPA 70*.

27.7.1.6 Wiring Inside Buildings.

27.7.1.6.1 At the communications center, all conductors, cables, and optical fiber cables shall extend as directly as possible to the operations center in conduits, ducts, shafts, raceways, or overhead racks and troughs listed or identified as suitable to provide protection against physical damage.

27.7.1.6.2* Where installed in buildings, conductors and optical fiber cables shall be installed in any of the following wiring methods:

- (1) Electrical metallic tubing
- (2) Intermediate metal conduit
- (3) Rigid metal conduit

27.7.1.6.2.1 Where installed in buildings, conductors and optical fiber cables shall be permitted to be installed in rigid nonmetallic conduit where approved by the authority having jurisdiction.

27.7.1.6.3 Conductors and optical fiber cables shall comply with 27.7.1.6.3.1 and 27.7.1.6.3.2.

27.7.1.6.3.1 Conductors and optical fiber cables shall have an approved insulation.

27.7.1.6.3.2 The insulation or other outer covering shall be flame retardant and moisture resistant.

27.7.1.6.4 Conductors and optical fiber cables shall comply with 27.7.1.6.4.1 and 27.7.1.6.4.2.

27.7.1.6.4.1 Conductors and optical fiber cables shall be installed as far as possible without splices or joints.

27.7.1.6.4.2 Splices or joints shall be permitted only in listed junction boxes, terminal boxes, or other enclosures approved by the AHJ.

27.7.1.6.5 Enclosures shall comply with 27.7.1.6.5.1 and 27.7.1.6.5.2.

27.7.1.6.5.1 Enclosures containing public emergency alarm reporting system circuits shall be provided with red covers or doors.

27.7.1.6.5.2 The words "public emergency alarm reporting system circuit" shall be marked on all enclosures, terminal boxes, and junction locations to prevent unintentional interference.

27.7.1.6.6 Termination enclosures, terminals, splices, and joints for metallic conductors and optical fiber cables shall conform to *NFPA 70*.

27.7.1.6.7 Metallic conductors and optical fiber cables and wiring exposed to a hazard shall be protected in an approved manner.

27.7.1.6.8 Terminals and cross-connecting facilities for metallic conductors and optical fiber cables shall be located in or adjacent to the operations room.

27.7.1.6.9 Where signal conductors, nondielectric optical fiber cables, and electric light and power wires are run in the same shaft, they shall be either separated by at least 2 in. (51 mm), or encased in a noncombustible enclosure.

27.7.2 Signal Transmission and Receiving Circuits. Signal transmission and receiving circuits shall comply with the requirements of 27.7.2.1 and 27.7.2.2.

27.7.2.1 General.

27.7.2.1.1 ANSI/IEEE C2, *National Electrical Safety Code*, shall be used as a guide for the installation of outdoor circuitry.

27.7.2.1.2 Installation shall provide for the following:

- (1) Continuity of service
- (2) Protection from mechanical damage
- (3) Disablement from heat that is incidental to fire
- (4) Damage by floods, corrosive vapors, or other causes

27.7.2.1.3 Open local circuits within single buildings shall be permitted in accordance with Chapter 23.

27.7.2.1.4 All circuits shall be routed so as to allow tracing of circuits for trouble.

27.7.2.1.5 Circuits shall not pass over, under, or through or be attached to buildings or property not owned by or under the control of the authority having jurisdiction or the agency responsible for maintaining the system.

27.7.2.1.5.1 The requirements of 27.7.2.1.5 shall not apply where the circuit is terminated at a public emergency alarm reporting system initiating device on the building or property.

27.7.2.2 Interior Box Circuits.

27.7.2.2.1 A means accessible only to the authority having jurisdiction or the agency responsible for maintaining the public emergency alarm reporting systems shall be provided to disconnect all circuit conductors inside a building or other structure.

27.7.2.2.2 Definite notification shall be given to the designated building representative when the interior box(es) is out of service.

27.7.3* Circuit Protection.

27.7.3.1 The protective devices shall be located close to or be combined with the cable terminals.

27.7.3.2 Surge protective devices designed and approved for the purpose shall be installed at a location accessible to qualified persons and shall be marked with the name of the manufacturer and model designation.

27.7.3.3 All surge protective devices shall be connected to a ground in accordance with *NFPA 70*.

27.7.3.4 All fuses, fuseholders, and adapters shall be plainly marked with their ampere rating. All fuses rated over 2 amperes shall be of the enclosed type.

27.7.3.5 Circuit protection required at the communications center shall be provided in every building that houses communications center equipment.

27.7.3.6 Each metallic conductor entering an emergency response facility from partially or entirely aerial lines shall be protected by a surge protective device.

27.7.3.7 All metallic conductors entering the communications center shall be protected by the following devices, in the order named, starting from the exterior circuit:

- (1) Fuse rated at 3 amperes minimum to 7 amperes maximum and not less than 2000 volts
- (2) Surge protective device(s)
- (3) Fuse or circuit breaker rated at $\frac{1}{2}$ ampere

27.7.3.8 In regard to 27.7.3.7, the $\frac{1}{2}$ -ampere protection on the tie circuits shall be omitted at subsidiary communications centers.

27.7.3.9 Open aerial metallic conductors and metallic cable shall comply with 27.7.3.9.1 and 27.7.3.9.2.

27.7.3.9.1 At junction points of open aerial metallic conductors and metallic cable, each conductor shall be protected by a surge protective device of the weatherproof type.

27.7.3.9.2 A connection shall also be between the surge protective device ground, any metallic sheath, and the messenger wire.

27.7.3.10 Aerial open-wire and nonmessenger-supported, two-conductor cable circuits shall be protected by a surge protective device at intervals not to exceed 2000 ft (610 m).

27.7.3.11 Where used for aerial construction, surge protective device, other than of the air-gap or self-restoring types, shall not be installed in public emergency alarm reporting circuits.

27.7.3.12 All protective devices used for aerial construction shall be accessible for maintenance and inspection.

27.8 Emergency Communications Systems (ECS).

27.8.1* Public emergency alarm reporting systems that are capable of two-way wired or wireless communications with command and control capabilities and/or voice communications capabilities shall be permitted to be used as part of the communications infrastructure of an emergency communications system (ECS), provided that it does not interfere with the public emergency alarm reporting system.

27.8.2 The method of interfacing and monitoring for integrity between the public emergency alarm reporting system and the ECS shall be in accordance with 27.6.3.2.3 and treated as an auxiliary alarm system connected to a protected premises.

27.8.3 Wired or wireless alarm boxes shall be permitted for shared use with an emergency communications system and shall meet all the requirements of Chapter 27.

27.8.4 Trouble and alarm indications in the emergency communications system shall be visually and audibly annunciated at the communications center, except under fault conditions that prevent such a notification process.

27.8.5 When a fault condition prevents communications between the emergency communications system and the communications center, an audible and visual trouble indication shall be activated at the control unit.

27.8.6 Communications between the public emergency alarm reporting system and the emergency communications system shall be monitored for integrity, and faults shall be annunciated

at the communications center, as well as at the fire command center or the emergency command center or both, in the protected premises.

Chapter 28 Reserved

Chapter 29 Single- and Multiple-Station Alarms and Household Signaling Systems

29.1 Application.

29.1.1* The performance, selection, installation, operation, and use of single- and multiple-station alarms and household alarm systems shall comply with the requirements of this chapter.

29.1.2* Alarms shall be installed in all occupancies where required by other governing laws, codes, or standards.

29.1.3 The requirements of Chapters 7, 10, 11, 12, 14, 17, 18, 21, 23, 24, 26, and 27 shall not apply unless otherwise noted.

29.1.4* The requirements of this chapter shall not apply to installations in manufactured homes.

29.1.5 This chapter shall apply to the life safety of occupants and not to the protection of property.

29.2* Purpose.

29.2.1 Fire-warning equipment for residential occupancies shall provide a reliable means to notify the occupants of the presence of a threatening fire and the need to escape to a place of safety before such escape might be impeded by untenable conditions in the normal path of egress.

29.2.2 Carbon monoxide warning equipment for residential occupancies shall provide a reliable means to notify the occupants of the presence of carbon monoxide levels that constitute a potential life safety risk and the need for action as a consequence of those levels.

29.3 Basic Requirements.

29.3.1* All devices, combinations of devices, and equipment to be installed in conformity with this chapter shall be approved, labeled, or listed for the purposes for which they are intended.

29.3.2 Fire- and carbon monoxide-warning equipment shall be installed in accordance with the listing and manufacturer's published instructions.

29.3.3* The installation of smoke, heat, fire, or carbon monoxide alarms or systems, or combinations of these, shall comply with the requirements of this chapter and shall satisfy the minimum requirements for number and location of alarms or detectors by one of the following arrangements:

- (1) The required minimum number and location of detection devices shall be satisfied (independently) through the installation of alarms. The installation of additional alarms shall be permitted. The installation of additional system-based detectors, including partial or complete duplication of the alarms satisfying the required minimum, shall be permitted.
- (2) The required minimum number and location of detection devices shall be satisfied (independently) through

the installation of system detectors. The installation of additional detectors shall be permitted. The installation of additional alarms, including partial or complete duplication of the detectors satisfying the required minimum, shall be permitted.

29.3.4 Supplementary functions, including the extension of an alarm beyond the residential occupancy, shall be permitted and shall not interfere with the performance requirements of this chapter.

29.4 Remote Annunciation. Remote annunciation from single- and multiple-station alarms shall be permitted, provided signals at the remote annunciator properly identify the hazard.

29.5 Notification.

29.5.1* Unless otherwise permitted by 29.5.3, fire-warning equipment to be installed in residential occupancies shall produce the audible emergency evacuation signal described in ANSI/ASA S3.41, *Audible Emergency Evacuation (E2) and Evacuation Signals with Relocation Instructions (ESRI)*, whenever the intended response is to evacuate the building.

29.5.2 The audible emergency evacuation signal shall be permitted to be used for other devices as long as the desired response is immediate evacuation.

29.5.3 Where mechanically powered single-station heat alarms are used as supplementary devices, unless required by applicable laws, codes, or standards, such devices shall not be required to produce the emergency evacuation signal described in ANSI/ASA S3.41, *Audible Emergency Evacuation (E2) and Evacuation Signals with Relocation Instructions (ESRI)*.

29.5.4* Carbon monoxide-warning equipment to be installed in residential occupancies shall produce the T-4 signal. After the initial 4 minutes of alarm, the 5-second "off" time of the alarm signal shall be permitted to be changed to 60 seconds ± 10 percent.

29.5.5* Fire-warning equipment producing the audible emergency evacuation signal shall be permitted to incorporate voice notification under either or both of the following conditions:

- (1) Where the voice message is contained completely within the 1.5-second pause period of the audible emergency evacuation signal
- (2) Where the voice message complies with 29.5.5(2)(a) and 29.5.5(2)(b) as follows:
 - (a) The voice message is first preceded by a minimum of eight cycles of the audible emergency evacuation signal.
 - (b) The voice message periodically interrupts the signal for no longer than 10 seconds, followed by a minimum of two cycles of the audible emergency evacuation signal between each voice message. The initial eight-cycle period shall not be required to be repeated.

29.5.6* Carbon monoxide-warning equipment producing the audible notification signal shall be permitted to incorporate voice notification under either or both of the following:

- (1) Where the voice message is contained completely within the 5-second pause period of the audible notification signal
- (2) Where the voice message complies with 29.5.6(2)(a) and 29.5.6(2)(b) as follows:

- (a) The voice message is first preceded by a minimum of 6 cycles of the audible notification signal.
- (b) The voice message periodically interrupts the signal for no longer than 10 seconds, followed by a minimum of two cycles of the audible notification signal between each voice message. The initial 6-cycle period shall not be required to be repeated.

29.5.7 All audible notification signals installed shall meet the performance requirements of 18.4.4, 18.4.6.1, 18.4.6.2, and 29.5.10.

29.5.8* Where visual appliances are provided, they shall meet the requirements of Section 18.5.

29.5.9 Since hearing deficits are often not apparent, the responsibility for advising the appropriate person(s) of the existence of this deficit shall be that of the party with hearing loss.

29.5.10 Notification appliances provided in sleeping rooms and guest rooms for those with hearing loss shall comply with 29.5.10.1 and 29.5.10.2, as applicable.

29.5.10.1* Mild to Severe Hearing Loss. Notification appliances provided for those with mild to severe hearing loss shall comply with the following:

- (1) An audible notification appliance producing a low frequency alarm signal shall be installed in the following situations:
 - (a) Where required by governing laws, codes, or standards for people with hearing loss
 - (b) Where provided voluntarily for those with hearing loss
- (2)* The low frequency alarm signal output shall comply with the following:
 - (a) The waveform shall have a fundamental frequency of 520 Hz ± 10 percent.
 - (b) The minimum sound level at the pillow shall be 75 dBA, or 15 dB above the average ambient sound level, or 5 dB above the maximum sound level having a duration of at least 60 seconds, whichever is greater.

29.5.10.2* Moderately Severe to Profound Hearing Loss. Visual notification appliances in accordance with the requirements of 18.5.5.10 and tactile notification appliances in accordance with the requirements of Section 18.10 shall be required for those with moderately severe to profound hearing loss in the following situations:

- (1)* Where required by governing laws, codes, or standards for people with hearing loss
- (2) Where provided voluntarily for those with hearing loss

29.5.11 Signals from notification appliances shall not be required to be synchronized.

29.6 Assumptions.

29.6.1* Occupants.

29.6.1.1 The requirements of this chapter shall assume that occupants are capable of self-rescue.

29.6.1.2 Occupants intimate with the ignition of a fire shall not be assumed to be protected by the requirements of this chapter.

29.6.2* Escape Route.

29.6.2.1 The requirements of this chapter shall assume that the occupants have an escape plan.

29.6.2.2 An escape route shall be assumed to be available to occupants and to be unobstructed prior to the fire or carbon monoxide event.

29.6.2.3* The escape route shall be along the normal path of egress for the occupancy.

29.6.3* Equipment. The performance of fire- and carbon monoxide-warning equipment discussed in this chapter shall depend on such equipment being properly selected, installed, operated, tested, and maintained in accordance with the provisions of this Code and with the manufacturer's published instructions provided with the equipment.

29.7* Carbon Monoxide Detection. The warning functions intended in this standard shall be performed by single or multiple-station alarms or by detectors connected to a control unit and associated equipment.

29.7.1 Required Detection.

29.7.1.1* Where required by other governing laws, codes, or standards for a specific type of occupancy, listed carbon monoxide alarms or detectors shall be installed as follows:

- (1) Outside of each separate dwelling unit sleeping area, within 21 ft (6.4 m) of any door to a sleeping room, with the distance measured along a path of travel
- (2) On every occupiable level of a dwelling unit, including basements, excluding attics and crawl spaces
- (3) In all sleeping rooms and guest rooms containing installed fuel-burning appliances
- (4) Other locations where required by applicable laws, codes, or standards

29.7.1.2* Each alarm or detector shall be located on the wall, ceiling, or other location as specified in the manufacturer's published instructions that accompany the unit.

29.7.2 Carbon Monoxide Alarm Interconnection. Unless exempted by applicable laws, codes, or standards, carbon monoxide alarms used to provide a warning function, and where two or more alarms are installed within a dwelling unit, suite of rooms, or similar area, shall be arranged so that the operation of any carbon monoxide alarm causes all carbon monoxide alarms within these locations to sound.

29.8 Detection and Notification. The use of fire alarm system smoke detectors and notification appliances shall be permitted to meet the fire-warning requirements for smoke alarms specified in 29.8.1.

29.8.1* Required Smoke Detection.

29.8.1.1* Where required by other governing laws, codes, or standards for a specific type of occupancy, listed single- and multiple-station smoke alarms shall be installed as follows:

- (1)* In all sleeping rooms and guest rooms
- (2)* Outside of each separate dwelling unit sleeping area, within 21 ft (6.4 m) of any door to a sleeping room, with the distance measured along a path of travel
- (3) On every level of a dwelling unit, including basements
- (4) On every level of a residential board and care occupancy (small facility), including basements and excluding crawl spaces and unfinished attics

(5)* In the living area(s) of a guest suite

(6) In the living area(s) of a residential board and care occupancy (small facility)

29.8.1.2 Where the area addressed in 29.8.1.1(2) is separated from the adjacent living areas by a door, a smoke alarm shall be installed in the area between the door and the sleeping rooms, and additional alarms shall be installed on the living area side of the door as specified by 29.8.1.1 and 29.8.1.3.

29.8.1.3 In addition to the requirements of 29.8.1.1(1) through 29.8.1.1(3), where the interior floor area for a given level of a dwelling unit, excluding garage areas, is greater than 1000 ft² (93 m²), smoke alarms shall be installed per 29.8.1.3.1 and 29.8.1.3.2.

29.8.1.3.1* All points on the ceiling shall have a smoke alarm within a distance of 30 ft (9.1 m) travel distance or shall have an equivalent of one smoke alarm per 500 ft² (46 m²) of floor area.

29.8.1.3.2 Where dwelling units include great rooms or vaulted/cathedral ceilings extending over multiple floors, smoke alarms located on the upper floor that are intended to protect the aforementioned area shall be permitted to be considered as part of the lower floor(s) protection scheme used to meet the requirements of 29.8.1.3.1.

29.8.2 Required Occupant Notification.

29.8.2.1 Fire-warning equipment used to provide required or optional detection shall produce audible fire alarm signals that comply with 29.8.2.1.1 or 29.8.2.1.2.

29.8.2.1.1* Interconnected Smoke and Heat Alarms. For other than mechanically powered single-station heat alarms and unless exempted by applicable laws, codes, or standards, smoke or heat alarms used to provide a fire-warning function, and where two or more alarms are installed within a dwelling unit, suite of rooms, or similar area, shall be arranged so that the operation of any smoke or heat alarm causes all alarms within these locations to sound.

29.8.2.1.2 Household Fire Alarm System. Where a household fire alarm system is used to provide a fire-warning function, notification appliances shall be installed to meet the performance requirements of 29.5.7.

29.8.2.2* Unless otherwise permitted by the authority having jurisdiction, audible fire alarm signals shall sound only in an individual dwelling unit, suite of rooms, or similar area and shall not be arranged to operate fire-warning equipment or fire alarm systems outside these locations.

29.8.2.3 Remote annunciation shall be permitted.

29.9 Power Supplies.

29.9.1 Smoke and Heat and Carbon Monoxide Alarms. Smoke and heat and carbon monoxide alarms shall meet the requirements of 29.8.2.1.1 and be powered by one of the following means:

- (1) A commercial light and power source along with a secondary power source that is capable of operating the device for at least 7 days in the normal condition, followed by 4 minutes of alarm. Carbon monoxide alarms shall have sufficient capacity to operate the alarm signal(s) for at least 12 continuous hours.

- (2) If a commercial light and power source is not normally available, a dependable, noncommercial ac power source along with a secondary power source that is capable of operating the device for at least 7 days in the normal condition, followed by 4 minutes of alarm for smoke and heat alarms or 12 hours of alarm for carbon monoxide alarms.
- (3) A nonrechargeable, nonreplaceable primary battery that meets the requirements of 29.9.2.
- (4) If a battery primary power supply is specifically permitted by governing laws, codes, or standards, a battery meeting the requirements of 29.9.7 or the requirements of 29.9.2.
- (5) A suitable spring-wound mechanism for the nonelectrical portion of a listed single-station alarm with a visible indication to show that sufficient operating power is not available.

29.9.2 Primary Power Source Nonreplaceable Primary Battery.

If smoke, heat, or carbon monoxide alarms are powered by a nonrechargeable, nonreplaceable primary battery, the battery shall be monitored to ensure the following conditions are met:

- (1) Single-station smoke alarm power requirements are met for at least 10 years of battery life, including required periodic testing.
- (2) Single-station carbon monoxide alarm power requirements are met for at least 10 years of battery life, including required periodic testing.
- (3) Multiple-station alarm power requirements are met for at least 7 years of battery life, including required periodic testing.
- (4) A distinctive audible trouble signal occurs before the battery is incapable of operating the device(s) for alarm purposes.
- (5) At the battery voltage at which a trouble signal is obtained, the unit is capable of producing a fire alarm signal for at least 4 minutes, or a carbon monoxide alarm signal for at least 12 continuous hours in accordance with 29.5.4, followed by not less than 7 days of trouble signal operation.
- (6) The audible trouble signal is produced at least once every minute for 7 consecutive days.
- (7) The trouble signal is allowed to be silenced for up to 12 hours.
- (8) A visible "power on" indicator is provided.

29.9.3 Household Fire and Carbon Monoxide Alarm Systems.

Power for household alarm systems shall comply with the following requirements:

- (1) Household fire and carbon monoxide alarm systems shall have two independent power sources consisting of a primary source that uses commercial light and power and a secondary source that consists of a rechargeable battery.
- (2) The secondary source shall be capable of operating the household alarm system for at least 24 hours in the normal condition, followed by 4 minutes of fire alarm or 12 hours of carbon monoxide alarm.
 - (a) Effective January 1, 2022, the secondary power source of the household carbon monoxide system shall be capable of operating the system for at least 12 hours of alarm in accordance with 29.5.4.
 - (b) The secondary power source of a household carbon monoxide system shall not be required to operate the system for 12 hours of alarm if the power source of carbon monoxide detectors and carbon monox-

ide audible notification appliances incorporating a low-power radio (wireless) transmitter/transceiver is capable of providing at least 24 hours in the normal condition, followed by 12 hours of alarm.

- (3) The secondary power source shall be supervised and shall cause a distinctive audible and visible trouble signal upon removal or disconnection of a battery or a low-battery condition.
- (4) A rechargeable battery used as a secondary power source shall meet the following criteria:
 - (a) Be automatically recharged by an ac circuit of the commercial light and power source
 - (b) Be recharged within 48 hours
 - (c) Provide a distinctive audible trouble signal before the battery is incapable of operating the device(s) for alarm purposes
- (5) Low-power wireless systems shall comply with the performance criteria of Section 23.16, except as modified by 29.10.8.1.1.

29.9.4 AC Primary Power Source. The ac power source specified in 29.9.1 and 29.9.3 shall comply with the following conditions:

- (1) A visible "power on" indicator shall be provided.
- (2) All electrical systems designed to be installed by other than a qualified electrician shall be powered from a source not in excess of 30 volts that meets the requirements for power-limited fire alarm circuits as defined in Article 760 of *NFPA 70*.
- (3)* A restraining means shall be used at the plug-in of any cord-connected installation, unless the unit utilizes a secondary (standby) power source meeting the requirements of Section 29.9 and loss of the ac primary power source results in annunciation of an audible trouble signal meeting 29.10.6.5.
- (4) AC primary (main) power shall be supplied either from a dedicated branch circuit or the unswitched portion of a branch circuit also used for power and lighting.
- (5) Operation of a switch (other than a circuit breaker) shall not cause loss of primary (main) power. Alarms powered by branch circuits protected by arc-fault circuit-interrupters (AFCI) or ground-fault circuit-interrupters (GFCI) shall have a secondary power source.
- (6) Neither loss nor restoration of primary (main) power shall cause an alarm signal that exceeds 2 seconds.
- (7) Where a secondary (standby) battery is provided, the primary (main) power supply shall be of sufficient capacity to operate the system under all conditions of loading with any secondary (standby) battery disconnected or fully discharged.

29.9.5 Secondary (Standby) Power Source. Where alarms include a battery that is used as a secondary power source, the following conditions shall be met:

- (1) The secondary power source shall be supervised and shall cause a distinctive audible or visible trouble signal upon removal or disconnection of a battery or a low-battery condition.
- (2) Acceptable replacement batteries shall be clearly identified by the manufacturer's name and model number on the unit near the battery compartment.
- (3) A rechargeable battery used as a secondary power source shall meet the following criteria:

- (a) Be automatically recharged by the primary power source
 - (b) Be recharged within 4 hours where power is provided from a circuit that can be switched on or off by means other than a circuit breaker, or within 48 hours where power is provided from a circuit that cannot be switched on or off by means other than a circuit breaker
 - (c) Provide a distinctive audible trouble signal before the battery is incapable of operating the device(s) for alarm purposes
 - (d) At the battery condition at which a trouble signal is obtained, be capable of producing a fire alarm signal for at least 4 minutes or the carbon monoxide signal for 12 continuous hours, followed by not less than 7 days of trouble signal operation
 - (e) Produce an audible trouble signal at least once every minute for 7 consecutive days
- (4) Where required by law for disposal reasons, rechargeable batteries shall be removable.

29.9.6 Visual Notification Appliance (with Single- or Multiple-Station Alarm). If a visual notification appliance is used in conjunction with a single- or multiple-station alarm for compliance with 29.5.8, the notification appliance shall not be required to be supplied with a secondary power source.

29.9.7 Primary Replaceable Battery, Sole Power Source (Nonrechargeable). If alarms are powered solely by a replaceable primary battery, the battery shall be monitored to ensure the following conditions are met:

- (1) All power requirements are met for at least 1 year of battery life, including weekly required periodic testing.
- (2) A distinctive audible trouble signal before the battery is incapable of operating the device(s) for alarm purposes.
- (3) For a system-connected unit employing a lock-in alarm feature, automatic transfer is provided from alarm to a trouble condition when the unit has insufficient power to support an alarm condition.
- (4) At the battery voltage at which a trouble signal is obtained, the unit is capable of producing a fire alarm signal for at least 4 minutes or a carbon monoxide alarm signal for at least 12 continuous hours, followed by not less than 7 days of trouble signal operation.
- (5) The audible trouble signal is produced at least once every minute for 7 consecutive days.
- (6) Acceptable replacement batteries are clearly identified by the manufacturer's name and model number on the unit near the battery compartment.
- (7) A noticeable, visible indication is displayed when a primary battery is removed from the unit.

29.9.8 Primary Power Source (Rechargeable Battery). If alarms are powered by a rechargeable battery, the following conditions shall be met:

- (1) The battery shall, with proper charging, be able to power the alarm for a life of 1 year.
- (2) The battery shall be automatically recharged by a circuit of the commercial light and power source.
- (3) The battery shall be recharged within 4 hours where power is provided from a circuit that can be switched on or off by means other than a circuit breaker or within 48 hours where power is provided from a circuit that cannot be switched on or off by means other than a circuit breaker.

- (4) A distinctive audible trouble signal shall sound before the battery is incapable of operating the device(s) for alarm purposes.
- (5) For a unit employing a lock-in alarm feature, automatic transfer shall be provided from alarm to a trouble condition.
- (6) At the battery condition at which a trouble signal is obtained, the unit shall be capable of producing a fire alarm signal for at least 4 minutes or a carbon monoxide alarm signal for 12 continuous hours, followed by not less than 7 days of trouble signal operation.
- (7) The audible trouble signal shall be produced at least once every minute for 7 consecutive days.
- (8) The battery shall be nonremovable, or a noticeable and visible indication shall be displayed when the battery is removed from the unit.

29.9.9 Secondary (Standby) Non-Battery Power Source. Where alarms include a secondary power source (non-battery), the following conditions shall be met:

- (1) The secondary power source shall be supervised and shall cause a distinctive audible or visible trouble signal upon depletion or failure.
- (2) A distinctive audible trouble signal shall be provided before the power source is incapable of operating the device(s) for alarm purposes.
- (3) At a power source condition at which a trouble signal is obtained, the power source shall be capable of producing a fire alarm signal for at least 4 minutes or a carbon monoxide alarm signal for at least 12 continuous hours, followed by not less than 7 days of trouble signal operation.
- (4) The audible trouble signal shall be produced at least once every minute for 7 consecutive days.
- (5) A rechargeable secondary power source shall meet the following criteria:
 - (a) Be automatically recharged
 - (b) Be recharged within 4 hours where power is provided from a circuit that can be switched on or off by means other than a circuit breaker or within 48 hours where power is provided from a circuit that cannot be switched on or off by means other than a circuit breaker

29.10 Equipment Performance.

29.10.1 Self-Diagnostic. Any failure of any nonreliable or short-life component that renders the detector inoperable shall result in a trouble signal or otherwise be apparent to the occupant of the living unit without the need for test.

29.10.2* Smoke Alarms, System Smoke Detectors, and Other Non-Heat Fire Detectors. Each device shall detect abnormal quantities of smoke or applicable fire signature, shall operate in the normal environmental conditions, and shall be in compliance with applicable standards such as UL 268, *Smoke Detectors for Fire Alarm Systems*, or UL 217, *Smoke Alarms*.

29.10.3 Carbon Monoxide Alarms and Detectors.

29.10.3.1* Each carbon monoxide alarm shall be in compliance with UL 2034, *Single and Multiple Station Carbon Monoxide Alarms*.

29.10.3.2 Each carbon monoxide detector shall be in compliance with UL 2075, *Gas and Vapor Detectors and Sensors*, and shall

meet the sensitivity testing and alarm thresholds of UL 2034, *Single and Multiple Station Carbon Monoxide Alarms*.

29.10.3.3 All signals produced from periodic testing of carbon monoxide alarms or detectors shall be identical to the signal produced when the unit is in alarm.

29.10.3.4 Trouble signals shall be distinctive from alarm signals.

29.10.3.5 Unless otherwise recommended by the manufacturer's published instructions, carbon monoxide alarms and detectors shall be replaced when they fail to respond to tests.

29.10.4* Heat Detectors and Heat Alarms.

29.10.4.1 Each heat detector and heat alarm, including a heat detector or heat alarm integrally mounted on a smoke detector or smoke alarm, shall detect abnormally high temperature or rate-of-temperature rise, and all such detectors shall be listed for not less than 50 ft (15.2 m) spacing.

29.10.4.2* Fixed-temperature detectors or alarms shall have a temperature rating at least 25°F (14°C) above the normal ambient temperature and shall not be rated 50°F (28°C) higher than the maximum anticipated ambient temperature in the room or space where installed.

29.10.5 Operability. Single- and multiple-station alarms, including heat alarms, shall be provided with a convenient means for testing its operability by the occupant, system owner, or other responsible parties.

29.10.6 Control Unit.

29.10.6.1 The control unit shall be automatically restoring upon restoration of electrical power.

29.10.6.2* The control unit shall be of a type that "locks in" on an alarm condition.

29.10.6.3 Smoke detection circuits shall not be required to lock in.

29.10.6.4 If a reset switch is provided, it shall be of a self-restoring (momentary operation) type.

29.10.6.5 A means for silencing the trouble notification appliance(s) shall be permitted only if the following conditions are satisfied:

- (1) The means is key-operated or located within a locked enclosure, or arranged to provide equivalent protection against unauthorized use.
- (2) The means transfers the trouble indication to an identified lamp or other acceptable visible indicator, and the visible indication persists until the trouble condition has been corrected.

29.10.6.6 A means for turning off actuated alarm notification appliances shall be permitted only if the following conditions are satisfied:

- (1) The means is key-operated or located within a locked cabinet or arranged to provide equivalent protection against unauthorized use.
- (2) The means includes the provision of a visible alarm silence indication.
- (3) The silenced position is indicated by a distinctive signal.
- (4) The switch is a momentary or self-restoring switch.

29.10.6.7 Initiating devices and notification appliances connected to household control units shall be monitored for integrity so that the occurrence of a single open or single ground fault in the interconnection, which prevents normal operation of the interconnected devices, is indicated by a distinctive trouble signal.

29.10.6.8 The control unit shall be in compliance with applicable standards such as UL 985, *Household Fire Warning System Units*; UL 1730, *Smoke Detector Monitors and Accessories for Individual Living Units of Multifamily Residences and Hotel/Motel Rooms*; or UL 864, *Control Units and Accessories for Fire Alarm Systems*.

29.10.6.9 Any data exchange between the control unit and separate independent devices via remote access shall not compromise the integrity of the fire alarm system.

29.10.6.10 Remote resetting and silencing of a control unit from other than the protected premises shall be inhibited for a minimum of 4 minutes from the initial activation of the fire alarm signal.

29.10.6.11 Each electrical carbon monoxide detection system shall have an integral test means to allow testing of the system operation.

29.10.7 Combination System.

29.10.7.1 If designed and installed to perform additional functions, fire- and carbon monoxide-warning equipment shall operate reliably and without compromise to its primary functions.

29.10.7.2 Fire signals shall take precedence over any other signal or functions, even if a non-fire signal is actuated first.

29.10.7.3 Fire and carbon monoxide signals shall be distinctive so that a fire or carbon monoxide signal can be distinguished from all other signals.

29.10.7.4 The use of a common audible notification appliance shall be permitted as long as distinctive signals are generated.

29.10.7.5 Faults in other systems or components shall not affect the operation of the fire alarm system.

29.10.7.6 Where common wiring is employed for a combination system, the equipment for other than the fire and carbon monoxide alarm system shall be connected to the common wiring of the system so that short circuits, open circuits, grounds, or any fault in this equipment or interconnection between this equipment and the fire and carbon monoxide alarm system wiring does not interfere with the supervision of the fire and carbon monoxide alarm system or prevent alarm or trouble signal operation.

29.10.7.7 Audible notification signals shall be provided in the following priority order:

- (1) Fire alarm
- (2) Carbon monoxide
- (3) Other

29.10.7.8* Installations that include the connection of single- or multiple-station alarms with other input or output devices shall be permitted.

29.10.7.8.1 An open, ground fault, or short circuit of the wiring connecting input or output devices to the single- or multiple-station alarms shall not prevent operation of each individual alarm.

29.10.7.8.2 Single- or multiple-station smoke alarms shall be permitted to be connected to system control equipment located within the dwelling unit.

29.10.7.8.3 When connected, the actuation of a single- or multiple-station smoke alarm shall initiate an alarm signal at the system control equipment located within the dwelling unit.

29.10.7.8.4 A sprinkler waterflow alarm initiating device shall be permitted to be connected to the multiple-station alarms or household fire alarm system to actuate an alarm signal.

29.10.8 Wireless Devices.

29.10.8.1 Wireless Systems. Household fire alarm systems utilizing low-power wireless transmission of signals within the protected dwelling unit shall comply with the requirements of Section 23.16, except as modified by 29.10.8.1.1.

29.10.8.1.1 The requirements of 23.16.4.2 shall not apply where periodic monitoring for integrity complies with all of the following:

- (1) Each low-power transmitter/transceiver shall transmit check-in signals at intervals not exceeding 80 minutes.
- (2) Any transmission interruption between a low-power radio transmitter/transceiver and the receiver/fire alarm control unit exceeding 4 hours shall cause a latching trouble signal at the household fire alarm control unit/operator interface.
- (3) Low-power transmitters/transceivers shall be limited to serving a single initiating device; however, a single initiating device shall be permitted to send multiple types of alarm signals.
- (4) Redundant retransmission devices (repeaters) shall be provided such that disconnecting or failure of any single retransmission device (repeater) does not interrupt communications between any low-power transmitter/transceiver and the receiver/fire alarm control unit.

29.10.8.2 Nonsupervised Wireless Interconnected Alarms.

29.10.8.2.1 Nonsupervised, low-power wireless alarms shall be capable of reliably communicating at a distance of 100 ft (30.5 m) indoors as tested to an equivalent open area test distance.

29.10.8.2.2 Fire alarm signals shall have priority over all other signals.

29.10.8.2.3 The maximum allowable response delay from activation of an initiating device to receipt and alarm/display by the receiver/control unit shall be 20 seconds.

29.10.8.2.4* Wireless interconnected smoke alarms (in receive mode) shall remain in alarm as long as the originating unit (transmitter) remains in alarm.

29.10.8.2.5 The occurrence of any single fault that disables a transceiver shall not prevent other transceivers in the system from operating.

29.10.9 Supervising Stations.

29.10.9.1* Household alarm systems shall be permitted to be supervised by a supervising station or by a public emergency alarm reporting system.

29.10.9.1.1 Transmission of signals from single- and multiple-station alarms to a constantly attended supervising station or

public emergency alarm reporting system shall be processed by a household alarm system.

29.10.9.1.2 Where off-premises supervision is provided, the system shall transmit at least a general alarm signal.

29.10.9.1.3 Transmission of trouble signals and supervisory signals shall be permitted.

29.10.9.2* Supervising station systems and services shall meet the requirements of Chapter 26 for the type of system and type of service selected, except as modified by 29.10.9.5 through 29.10.9.10.

29.10.9.3 Public emergency alarm reporting systems shall meet the requirements of Chapter 27, except as modified by 29.10.9.7 through 29.10.9.10.

29.10.9.4 Public emergency alarm reporting systems shall transmit signals to an emergency services communications system meeting the requirements of NFPA 1221.

29.10.9.5 Supervising station systems shall not be required to comply with requirements for indication of central station service in 26.3.4.

29.10.9.6 Alarm, supervisory, and trouble signals shall be permitted to be received at a listed central supervising station.

29.10.9.7* Alarm signals shall be permitted to be verified prior to reporting them to the fire service, provided that the verification process does not delay the reporting by more than 90 seconds.

29.10.9.8 Household fire alarm systems shall be programmed by the manufacturer to generate at least a monthly test of the communication or transmission means.

29.10.9.9 The activation of a keypad fire alarm signal shall require a manual operation of two simultaneous or sequential operations.

29.10.9.10 Communications methods shall comply with 29.10.9.10.1 through 29.10.9.10.7.

29.10.9.10.1 Where a digital alarm communicator transmitter (DACT) is used, the DACT serving the protected premises shall only require a single telephone line and shall only require a call to a single digital alarm communicator receiver (DACR) number.

29.10.9.10.2 Where a DACT is used, the DACT test signals shall be transmitted at least monthly.

29.10.9.10.3 Where a communication or transmission means other than DACT is used, only a single communication technology and path shall be required to serve the protected premises.

29.10.9.10.4 Where a communication or transmission means other than DACT is used, all equipment necessary to transmit an alarm signal shall be provided with a minimum of 24 hours of secondary power capacity and shall report a trouble condition indicating loss of primary power.

29.10.9.10.5 Failure of the communication path referenced in 29.10.9.10.3 shall be annunciated at the supervising station and at the protected premises within not more than 7 days of the failure.

29.10.9.10.6 A dedicated cellular telephone connection shall be permitted to be used as a single means to transmit alarms to a constantly attended remote monitoring location.

29.10.9.10.7 Transmission devices connected to the supervising station shall be in compliance with applicable standards such as UL 985, *Household Fire Warning System Units*.

29.10.9.10.8 Transmission devices connected to the supervising station sharing on-premises equipment shall be listed as communications or information technology equipment.

29.10.10 Cybersecurity.

29.10.10.1* All control units shall be designed for cybersecurity as determined by the manufacturer.

29.10.10.2 All devices that are connected wirelessly to a control unit and rely on the control unit for occupant notification activation shall not diminish the cybersecurity of the control unit.

29.10.10.3 All system or software updates required or initiated by the manufacturer shall not diminish the cybersecurity of the control unit.

29.10.10.4* All alarms that use IP or cellular communication shall be designed for cybersecurity as determined by the manufacturer.

29.11 Installation.

29.11.1 General.

29.11.1.1 All equipment shall be installed in accordance with the manufacturer's published instructions and applicable electrical standards.

29.11.1.2 All devices shall be so located and mounted that accidental operation is not caused by jarring or vibration.

29.11.1.3 All equipment shall be mounted so as to be supported independently of its attachment to wires.

29.11.1.4 The supplier or installing contractor shall provide the system owner or other responsible parties with the following:

- (1) An instruction booklet illustrating typical installation layouts
- (2) Instruction charts describing the operation, method, and frequency of testing and maintenance of the warning equipment
- (3) Printed information for establishing an emergency evacuation plan
- (4) Printed information to inform system owners where they can obtain repair or replacement service, and where and how parts requiring regular replacement, such as batteries or bulbs, can be obtained within 2 weeks
- (5) Information noting both of the following:
 - (a) Unless otherwise recommended by the manufacturer's published instructions, smoke alarms shall be replaced when they fail to respond to tests.
 - (b) Smoke alarms shall not remain in service longer than 10 years from the date of manufacture unless otherwise provided by manufacturer's published instructions.
- (6) The instructions required in Section 29.14

29.11.2 Interconnection of Multiple-Station Alarms.

29.11.2.1* The interconnection of alarms shall comply with the following:

- (1) Alarms shall not be interconnected in numbers that exceed the manufacturer's published instructions.
- (2) In no case shall more than 18 initiating devices be interconnected (of which 12 can be smoke alarms) where the interconnecting means is not supervised.
- (3) In no case shall more than 64 initiating devices be interconnected (of which 42 can be smoke alarms) where the interconnecting means is supervised.
- (4) Alarms of different manufacturers shall not be interconnected unless listed as being compatible with the specific model.
- (5) When alarms of different types are interconnected, all interconnected alarms shall produce the appropriate audible response for the phenomena being detected or remain silent.

29.11.2.2 A single fault on the interconnecting means between multiple-station alarms shall not prevent single-station operation of any of the interconnected alarms.

29.11.2.3 Remote notification appliance circuits of multiple-station alarms shall be capable of being tested for integrity by activation of the test feature on any interconnected alarm.

29.11.2.4 Activation of the test feature shall result in the operation of all interconnected notification appliances.

29.11.3* Smoke Alarms and Smoke Detectors. Smoke alarms, smoke detectors, devices, combination of devices, and equipment shall be installed in accordance with the manufacturer's listing and published instructions, and, unless specifically listed for the application, shall comply with requirements in 29.11.3.1 through 29.11.3.4.

29.11.3.1* Peaked Ceilings. Smoke alarms or smoke detectors mounted on a peaked ceiling shall be located within 36 in. (910 mm) horizontally of the peak, but not closer than 4 in. (100 mm) vertically to the peak.

29.11.3.2* Sloped Ceilings. Smoke alarms or smoke detectors mounted on a sloped ceiling having a rise greater than 1 ft in 8 ft (1 m in 8 m) horizontally shall be located within 36 in. (910 mm) of the high side of the ceiling, but not closer than 4 in. (100 mm) from the adjoining wall surface.

29.11.3.3* Wall Mounting. Smoke alarms or smoke detectors mounted on walls shall be located not farther than 12 in. (300 mm) from the adjoining ceiling surface.

29.11.3.4 Specific Location Requirements. The installation of smoke alarms and smoke detectors shall comply with the following requirements:

- (1) Smoke alarms and smoke detectors shall not be located where ambient conditions, including humidity and temperature, are outside the limits specified by the manufacturer's published instructions.
- (2) Smoke alarms and smoke detectors shall not be located within unfinished attics or garages or in other spaces where temperatures can fall below 40°F (4.4°C) or exceed 100°F (38°C).
- (3)* Where the mounting surface could become considerably warmer or cooler than the room, such as a poorly insulated ceiling below an unfinished attic or an exterior wall,

smoke alarms and smoke detectors shall be mounted on an inside wall.

- (4)* Smoke alarms and smoke detectors shall not be installed between 10 ft (3.0 m) and 20 ft (6.1 m) along a horizontal flow path from a stationary or fixed cooking appliance unless the devices comply with the following:
 - (a) Prior to January 1, 2023, smoke alarms and smoke detectors shall be equipped with an alarm silencing means, use photoelectric detection, or be listed for resistance to common nuisance sources from cooking in accordance with the 8th edition of UL 217, *Smoke Alarms*, the 7th edition of UL 268, *Smoke Detectors for Fire Alarm Systems*, or subsequent editions.
 - (b) Effective January 1, 2023, smoke alarms and smoke detectors shall be listed for resistance to common nuisance sources from cooking in accordance with the 8th edition of UL 217, the 7th edition of UL 268, or subsequent editions.
- (5) Smoke alarms and smoke detectors shall not be installed within an area of exclusion determined by a 10 ft (3.0 m) radial distance along a horizontal flow path from a stationary or fixed cooking appliance. When the 10 ft (3.0 m) area of exclusion would prohibit the placement of a smoke alarm or smoke detector required by other sections of this Code, and when the kitchen or cooking area and adjacent spaces have no clear interior partitions or headers, smoke alarms or smoke detectors shall be permitted for installation at a radial distance between 6 ft (1.8 m) and 10 ft (3.0 m) from any stationary or fixed cooking appliance unless the devices comply with the following:
 - (a) Prior to January 1, 2023, the devices shall use photoelectric detection or be listed for resistance to common nuisance sources from cooking in accordance with the 8th edition of UL 217, the 7th edition of UL 268, or subsequent editions.
 - (b) Effective January 1, 2023, the devices shall be listed for resistance to common nuisance sources from cooking nuisance alarms in accordance with the 8th edition of UL 217, the 7th edition of UL 268, or subsequent editions.
- (6)* Smoke alarms and smoke detectors shall not be installed within a 36 in. (910 mm) horizontal path from a door to a bathroom containing a shower or tub unless listed for installation in close proximity to such locations.
- (7) Smoke alarms and smoke detectors shall not be installed within a 36 in. (910 mm) horizontal path from the supply registers of a forced air heating or cooling system and shall be installed outside of the direct airflow from those registers.
- (8)* Smoke alarms and smoke detectors shall not be installed within a 36 in. (910 mm) horizontal path from the tip of the blade of a ceiling-suspended (paddle) fan unless the room configuration restricts meeting this requirement.
- (9) Where stairs lead to other occupiable levels, a smoke alarm or smoke detector shall be located so that smoke rising in the stairway cannot be prevented from reaching the smoke alarm or smoke detector by an intervening door or obstruction.
- (10) For stairways leading up from a basement, smoke alarms or smoke detectors shall be located on the basement ceiling near the entry to the stairs.

- (11)* For tray-shaped ceilings (coffered ceilings), smoke alarms and smoke detectors shall be installed on the highest portion of the ceiling or on the sloped portion of the ceiling within 12 in. (300 mm) vertically down from the highest point.
- (12) Smoke alarms and detectors installed in rooms with joists or beams shall comply with the requirements of 17.7.4.2.4.
- (13) Heat alarms and detectors installed in rooms with joists or beams shall comply with the requirements of 17.6.3.

29.11.4* Heat Detectors and Heat Alarms.

29.11.4.1* On smooth ceilings, heat detectors and heat alarms shall be installed within the strict limitations of their listed spacing.

29.11.4.2* For sloped ceilings having a rise greater than 1 ft in 8 ft (1 m in 8 m) horizontally, the detector or alarm shall be located within 36 in. (910 mm) of the peak.

29.11.4.3 The spacing of additional detectors or alarms, if any, shall be based on a horizontal distance measurement, not on a measurement along the slope of the ceiling.

29.11.4.4* Heat detectors or alarms shall be mounted on the ceiling at least 4 in. (100 mm) from a wall or on a wall with the top of the detector or alarm not less than 4 in. (100 mm), nor more than 12 in. (300 mm), below the ceiling.

29.11.4.5 Where the mounting surface could become considerably warmer or cooler than the room, such as a poorly insulated ceiling below an unfinished attic or an exterior wall, the detectors or alarms shall be mounted on an inside wall.

29.11.4.6 In rooms with open joists or beams, all ceiling-mounted detectors or alarms shall be located on the bottom of such joists or beams.

29.11.4.7* Detectors or alarms installed on an open-joisted ceiling shall have their smooth ceiling spacing reduced where this spacing is measured at right angles to solid joists; in the case of heat detectors or heat alarms, this spacing shall not exceed one-half of the listed spacing.

29.11.5 Wiring and Equipment. The installation of wiring and equipment shall be in accordance with the requirements of Article 760 of *NEPA 70*.

29.11.6 Installation and Inspection Record. Where a form is required by the AHJ to document the installation and inspection of a household alarm system or single- or multiple-station alarms, 7.8.2(3) shall be used to document the record of completion and inspection.

29.12 Optional Functions. The following optional functions of fire-warning equipment shall be permitted:

- (1) Notification of the fire department, either directly or through an alarm monitoring service
- (2) Monitoring of other safety systems, such as fire sprinklers for alarm or proper operating conditions
- (3) Notification of occupants or others of potentially dangerous conditions, such as the presence of fuel gases or toxic gases such as carbon monoxide
- (4) Notification of occupants or others of the activation of intrusion (burglar alarm) sensors
- (5) Any other function, safety related or not, that could share components or wiring

29.13 Inspection, Testing, and Maintenance.

29.13.1 Fire and carbon monoxide alarm equipment shall be maintained and tested in accordance with the manufacturer's published instructions and per the requirements of 14.4.5, 14.4.6, and 14.4.8.

29.13.2 All fire and carbon monoxide alarm equipment shall be restored to a normal condition after each alarm or test.

29.14 Markings and Instructions.

29.14.1 Markings.

29.14.1.1 Alarms and Detectors.

29.14.1.1.1 All alarms and detectors shall be plainly marked with the following information on the unit:

- (1) Manufacturer's or listee's name, address, and model number
- (2) A mark or certification that the unit complies with the definition of "Listed" in 3.2.5
- (3) Electrical rating (where applicable)
- (4) Manufacturer's published operating and maintenance instructions
- (5) Test instructions
- (6) Replacement and service instructions
- (7) Explanation of signal indicators, including identification of lights, switches, meters, and similar devices, regarding their function, unless their function is obvious
- (8) Distinction between alarm and trouble signals on units employing both
- (9) The sensitivity setting for an alarm having a fixed setting (For an alarm that is intended to be adjusted in the field, the range of sensitivity shall be indicated. The marked sensitivity shall be indicated as a percent per foot obscuration level. The marking shall include a nominal value plus tolerance.)
- (10) Reference to an installation diagram and system owner's manual
- (11) Date of manufacture in the format YEAR (in four digits), MONTH (in letters), and DAY (in two digits) located on the outside of the alarm

29.14.1.1.2 Where space limitations prohibit inclusion of 29.14.1.1.1(4) and 29.14.1.1.1(6), it shall be permitted to include this information in the installation instructions instead.

29.14.1.2 Carbon Monoxide Alarms and Detectors. In addition to 29.14.1.1, carbon monoxide alarms or detectors shall be marked with the following information:

- (1) Statement that indicates the unit is not suitable as a fire detector
- (2) Warning that carbon monoxide is odorless, colorless, and tasteless
- (3) Emergency actions to be taken
- (4) Recommended replacement date

29.14.1.3 Household Alarm Control Units.

29.14.1.3.1 Unless otherwise permitted by 29.14.1.3.2, all household alarm control units shall be plainly marked with the following information on the unit:

- (1) Manufacturer's or listee's name, address, and model number
- (2) A mark or certification that the unit complies with the definition of "Listed" in 3.2.5

- (3) Electrical rating (where applicable)
- (4) Identification of all user interface components and their functions (such as, but not limited to, lights, switches, and meters) located adjacent to the component
- (5) Manufacturer's published operating and maintenance instructions
- (6) Test instructions
- (7) Replacement and service instructions
- (8) Reference to an installation wiring diagram and homeowner's manual, if not attached to control unit, by drawing number and issue number and/or date

29.14.1.3.2 Where space limitations prohibit inclusion of 29.14.1.3.1(5) and 29.14.1.3.1(7), it shall be permitted to include this information in the installation instructions instead.

29.14.2 Instructions.

29.14.2.1 Alarms and Detectors. The following information shall be included in the instructions provided with carbon monoxide alarms and detectors:

- (1) Installation instructions
- (2) Operating instructions
- (3) Testing instructions
- (4) Maintenance instructions
- (5) Replacement and service instructions

29.14.2.2 Carbon Monoxide Alarms and Detectors. In addition to 29.14.2.1, the following information shall be included in the instructions provided with carbon monoxide alarms detectors:

- (1) Statement indicating that smoke might not be present during a carbon monoxide alarm condition
- (2)* Information on the actions to be taken in case of an alarm
- (3) Minimum and recommended distances from fuel-burning appliances

Annex A Explanatory Material

Annex A is not a part of the requirements of this NFPA document but is included for informational purposes only. This annex contains explanatory material, numbered to correspond with the applicable text paragraphs.

A.1.2 Fire alarm systems intended for life safety should be designed, installed, and maintained to provide indication and warning of abnormal fire conditions. The system should alert building occupants and summon appropriate aid in adequate time to allow for occupants to travel to a safe place and for rescue operations to occur. The fire alarm system should be part of a life safety plan that also includes a combination of prevention, protection, egress, and other features particular to that occupancy.

A.1.2.4 The intent of this paragraph is to make it clear that the protection requirements are derived from the applicable building or fire code, not from NFPA 72.

A.1.6.5 Where dimensions are expressed in inches, it is intended that the precision of the measurement be 1 in., thus plus or minus ½ in. The conversion and presentation of dimensions in millimeters would then have a precision of 25 mm, thus plus or minus 13 mm.

A.3.2.1 Approved. The National Fire Protection Association does not approve, inspect, or certify any installations, procedures, equipment, or materials; nor does it approve or evaluate testing laboratories. In determining the acceptability of installations, procedures, equipment, or materials, the authority having jurisdiction may base acceptance on compliance with NFPA or other appropriate standards. In the absence of such standards, said authority may require evidence of proper installation, procedure, or use. The authority having jurisdiction may also refer to the listings or labeling practices of an organization that is concerned with product evaluations and is thus in a position to determine compliance with appropriate standards for the current production of listed items.

A.3.2.2 Authority Having Jurisdiction (AHJ). The phrase “authority having jurisdiction,” or its acronym AHJ, is used in NFPA documents in a broad manner, since jurisdictions and approval agencies vary, as do their responsibilities. Where public safety is primary, the authority having jurisdiction may be a federal, state, local, or other regional department or individual such as a fire chief; fire marshal; chief of a fire prevention bureau, labor department, or health department; building official; electrical inspector; or others having statutory authority. For insurance purposes, an insurance inspection department, rating bureau, or other insurance company representative may be the authority having jurisdiction. In many circumstances, the property owner or his or her designated agent assumes the role of the authority having jurisdiction; at government installations, the commanding officer or departmental official may be the authority having jurisdiction.

A.3.2.3 Code. The decision to designate a standard as a “code” is based on such factors as the size and scope of the document, its intended use and form of adoption, and whether it contains substantial enforcement and administrative provisions.

A.3.2.5 Listed. The means for identifying listed equipment may vary for each organization concerned with product evaluation; some organizations do not recognize equipment as listed unless it is also labeled. The authority having jurisdiction should utilize the system employed by the listing organization to identify a listed product.

A.3.3.6 Acoustically Distinguishable Space (ADS). All parts of a building or area intended to have occupant notification are subdivided into ADSs as defined. Some ADSs might be designated to have voice communications capability and require that those communications be intelligible. Other spaces might not require voice intelligibility or might not be capable of reliable voice intelligibility. An ADS might have acoustical design features that are conducive for voice intelligibility, or it might be a space where voice intelligibility could be difficult or impossible to achieve. Each is still referred to as an ADS.

In smaller areas, such as those under 400 ft² (40 m²), walls alone will define the ADS. In larger areas, other factors might have to be considered. In spaces that might be subdivided by temporary or movable partitions, such as ballrooms and meeting rooms, each individual configuration should be considered a separate ADS. Physical characteristics, such as a change in ceiling height of more than 20 percent, or a change in acoustical finish, such as carpet in one area and tile in another, would require those areas to be treated as separate ADSs. In larger areas, there might be noise sources that require a section to be treated as a separate ADS. Any significant change in ambient

noise level or frequency might necessitate an area be considered a separate ADS.

In areas of 85 dBA or greater ambient sound pressure level, meeting the pass/fail criteria for intelligibility might not be possible, and other means of communications might be necessary. So, for example, the space immediately surrounding a printing press or other high-noise machine might be designated as a separate ADS, and the design might call for some form of effective notification but not necessarily require the ability to have intelligible voice communications. The aisles or operator's control stations might be separate ADSs where intelligible voice communication might be desired.

Significant differences in furnishings — for example, an area with tables, desks, or low dividers adjacent to an area with high shelving — would require separate consideration. The entire desk area could be a single acoustic zone, whereas each area between shelving could be a unique zone. Essentially, any noteworthy change in the acoustical environment within an area will mandate consideration of that portion of the area to be treated as an acoustic zone. Hallways and stairwells will typically be considered as individual acoustic zones.

Spaces confined by walls with carpeting and acoustical ceilings can be deemed to be one ADS. An ADS should be an area of consistent size and material. A change of materials from carpet to hard tile, the existence of sound sources, such as decorative waterfalls, large expanses of glass, and changes in ceiling height, are all factors that might separate one ADS from another.

Each ADS might require different components and design features to achieve intelligible voice communication. For example, two ADSs with similar acoustical treatments and noise levels might have different ceiling heights. The ADS with the lower ceiling height might require more ceiling-mounted loudspeakers to ensure that all listeners are in a direct sound field (see Figure A.3.3.6). Other ADSs might benefit from the use of alternate loudspeaker technologies, such as line arrays, to achieve intelligibility.

An ADS that differs from another because of the frequency and level of ambient noise might require the use of loudspeakers and system components that have a wider frequency bandwidth than conventional emergency communications equipment. However, designers should not use higher bandwidth loudspeakers in all locations, unless needed to overcome certain acoustic and ambient conditions. This is because the higher bandwidth appliance will require more energy to perform properly. This increases amplifier and wire size and power supply requirements.

In some spaces, it might be impractical to achieve intelligibility, and, in such a case, alternatives to voice evacuation might be required within such areas.

There might be some areas of a facility where there are several spaces of the same approximate size and the same acoustic properties. For example, there might be an office space with multiple individual offices, each with one loudspeaker. If one or two are satisfactorily tested, there is no need to test all of them for speech intelligibility.




FIGURE A.3.3.6 Illustration Demonstrating the Effect of Ceiling Height. (Source: R. P. Schiffliti Associates, Inc.)

A.3.3.12.3 Manual Fire Alarm Box. The term *box* is currently the term used by building codes and nationally recognized testing laboratories. They are also called manual fire alarm stations, pull stations, and call points. (SIG-IDS)

A.3.3.20 Ancillary Functions. Ancillary functions can include general paging, background music, or other non-emergency signals. (SIG-ECS)

A.3.3.31 Average Ambient Sound Level. The term *average ambient sound level* is also called the equivalent A-weighted sound level measured over t hours, where t is the time period over which the measurement is made. The standard industry symbol is $L_{A,eq,t}$. Where a measurement is taken over a 24-hour time period, the designation would be $L_{A,eq,24}$.

A.3.3.32 Backbone. In a Class N network, all endpoints (i.e., alarm devices or panels) connect to a redundant backbone that has multiple paths. No panel or alarm device is directly connected to another. Class N must have a redundant backbone so that the loss of a single path (cable, fiber, or wireless segment) will not cause loss of communication between any two endpoints (i.e., alarm devices or panels). A backbone can interconnect diverse networks in the same building, in different buildings, in a campus environment, or over wide areas.

A.3.3.33 Battery. Common usage permits this designation to be applied to a single cell used independently. Cells can be connected in series or parallel, or both, to provide the required operating voltage and current levels. (SIG-TMS)

A.3.3.40 Ceiling. Areas with a suspended ceiling have two ceilings, one visible from the floor and one above the suspended ceiling.

A.3.3.40.3 Sloping Peaked-Type Ceiling. Curved or domed ceilings can be considered peaked with the slope figured as the slope of the chord from highest to lowest point.

Refer to Figure A.17.6.3.4(a) for an illustration of smoke or heat detector spacing on peaked-type sloped ceilings.

A.3.3.40.4 Sloping Shed-Type Ceiling. Refer to Figure A.17.6.3.4(b) for an illustration of smoke or heat detector spacing on shed-type sloped ceilings.

A.3.3.42.3 Smooth Ceiling. Open truss constructions are not considered to impede the flow of fire products unless the upper member, in continuous contact with the ceiling, projects below the ceiling more than 4 in. (100 mm).

A.3.3.43.4 Valve-Regulated Lead-Acid (VRLA) Cell. VRLA cells provide a means for recombination of internally generated oxygen and the suppression of hydrogen gas evolution to limit water consumption. (SIG-TMS)

A.3.3.50.2 Radio Channel. The width of the channel depends on the type of transmissions and the tolerance for the frequency of emission. Channels normally are allocated for radio transmission in a specified type for service by a specified transmitter.

A.3.3.54 Coded. Notification signal examples are numbered strokes of an impact-type appliance and numbered flashes of a visual appliance.

A.3.3.60 Communications Center. Examples of functions of a communications center are as follows:

- (1) Communications between the public and the communications center
- (2) Communications between the communications centers, the emergency response agency (ERA), and emergency response facilities (ERFs)
- (3) Communications within the ERA and between different ERAs

[1221, 2019]

- (4) Communications with the public emergency alarm reporting system

The central operating part of the public emergency alarm reporting system is usually located at the communications center.

A.3.3.65 Condition. See Figure A.3.3.65 that describes the Condition — Signal — Response model used in this Code. There are varying degrees of conditions that require varying degrees of response that are initiated by various types of signals. A condition could be present without being detected (either because detection of the condition was not required or was not feasible), in which case, there is no signal or response. A condition could be detected, resulting in a signal, but there could be no required response. A signal could be generated erroneously in the absence of a condition (due to malfunction or other causes) resulting in an unwarranted response. The condition is normal when no abnormal conditions are present.




FIGURE A.3.3.65 Condition-Signal-Response Model.

A.3.3.65.1.1 Alarm Condition. When an alarm condition is present, damage to life or property has begun or will begin. Detection, signaling, and response, effected quickly, can limit or prevent damage. The extent of damage is often reduced with inverse proportion to the time required for detection, signaling, and response. The amount of time available for detection, signaling, and response is generally not a known quantity and damage might not be preventable. Alarm conditions can result due to the presence of fire, chemicals, freezing temperatures, or other circumstances.

A.3.3.65.1.2 Pre-Alarm Condition. Some examples of pre-alarm conditions include the following: the presence of a very small amount of visible smoke (at levels below listed initiating device alarm thresholds), the presence of a smoke-like odor, a somewhat elevated temperature, and a gradually increasing temperature. Any abnormal condition that typically precedes an alarm condition can be termed a *pre-alarm condition*.

The amount of time available for investigating the cause of a pre-alarm condition is not a known quantity. If conditions deteriorate to the point of alarm, time is no longer available for investigation. Pre-alarm conditions might or might not progress to alarm conditions.

The detection of pre-alarm conditions could be desirable in some occupancies, particularly if environmental conditions are ordinarily well controlled (e.g., integrated circuit fabrication facility) and personnel are trained to respond appropriately. In other occupancies, the detection of pre-alarm conditions might not be desirable or necessary.

The term *pre-alarm condition* is different from the terms *positive alarm sequence*, *alarm verification*, and *pre-signal*.

A.3.3.65.1.3 Supervisory Condition. A supervisory condition occurs when one system supervises another system, process, or

equipment for failure or impairment, and a functional failure or impairment to operation of the supervised system, process or equipment has occurred. A supervisory condition might be a regularly occurring and expected event such as a valve closed on a sprinkler system. A closed valve is an abnormal condition for the sprinkler system, but it does not constitute a trouble condition in the fire alarm or signaling system.

In some cases, a fault in one system, causing a trouble condition in that system, results in a supervisory condition in another system because the other system is supervising some function of the faulted system, and the supervised function has been impaired. In those cases, both supervisory and trouble conditions exist at the same time.

Some examples of supervisory conditions can include the following:

- (1) An event causing the activation of a supervisory initiating device used to monitor an environmental parameter, system element, component, or function, whose failure poses a risk to life, property, or mission (e.g., sprinkler valve closed, water tank low water level, low building temperature, emergency communications system impairment, and so forth).
- (2) The failure of a guard to remain within established constraints while on tour, usually indicated by the absence of a guard's tour supervisory signal within prescribed timing requirements, or the presence of a guard's tour supervisory signal outside of prescribed sequencing requirements, or the presence of a delinquency signal.
- (3) Public safety radio communications enhancement system antenna malfunction, signal booster failure, or battery depletion.
- (4) In some cases, the presence of smoke in an HVAC duct or in other places as defined by the authority having jurisdiction.

A.3.3.65.1.4 Trouble Condition. A trouble condition is a fault in the fire alarm or signaling system. The system or some aspect of it is somehow broken. This is different from a supervisory condition that is an abnormal condition in a system that is supervised by the fire alarm or signaling system. Abnormal conditions, such as a closed valve in a sprinkler system, not caused by a fault are not considered trouble conditions.

In some cases, a fault in one system, causing a trouble condition in that system, results in a supervisory condition because another system is supervising some function of the faulted system, and the supervised function has been impaired by the fault (see A.3.3.65.1.3, *Supervisory Condition*). In those cases, both supervisory and trouble conditions exist at the same time.

A.3.3.69.1 Autonomous Control Unit (ACU). Although an ACU might incorporate provisions for messages or signals from external sources, the ACU is fully capable of building controls without the need for sources outside the building. An ACU is allowed to be located within a primary building and supply circuits to immediately adjacent support buildings such as detached storage buildings. Larger buildings will generally have their own ACUs to allow individual control within each building.

A.3.3.76 Design Professional. An architect/engineer working for the owner in the preparation of bid documents, overseeing systems covered by this standard as part of a design-build project, or an engineer performing a risk analysis, would be

considered a design professional under the requirements of this standard. (SIG-ECS)

A.3.3.77.2 Automatic Fire Detector. For this Code, automatic fire detectors are classified as follows: automatic fire extinguishing or suppression system operation detector, fire-gas detector, heat detector, other fire detectors, radiant-energy-sensing fire detector, and smoke detector.

A.3.3.77.5 Combination Detector. These detectors do not utilize a mathematical evaluation principle of signal processing more than a simple “or” function. Normally, these detectors provide a single response resulting from either sensing method, each of which operates independent of the other. These detectors can provide a separate and distinct response resulting from either sensing method, each of which is processed independent of the other. Typical examples are a combination of a heat detector with a smoke detector or a combination rate-of-rise and fixed-temperature heat detector.

A.3.3.77.8 Fixed-Temperature Detector. The difference between the operating temperature of a fixed-temperature device and the surrounding air temperature is proportional to the rate at which the temperature is rising. The rate is commonly referred to as *thermal lag*. The air temperature is always higher than the operating temperature of the device.

Typical examples of fixed-temperature sensing elements are as follows:

- (1) *Bimetallic.* A sensing element comprised of two metals that have different coefficients of thermal expansion arranged so that the effect is deflection in one direction when heated and in the opposite direction when cooled.
- (2) *Electrical Conductivity.* A line-type or spot-type sensing element in which resistance varies as a function of temperature.
- (3) *Fusible Alloy.* A sensing element of a special composition metal (eutectic) that melts rapidly at the rated temperature.
- (4) *Heat-Sensitive Cable.* A line-type device in which the sensing element comprises, in one type, two current-carrying wires separated by heat-sensitive insulation that softens at the rated temperature, thus allowing the wires to make electrical contact. In another type, a single wire is centered in a metallic tube, and the intervening space is filled with a substance that becomes conductive at a critical temperature, thus establishing electrical contact between the tube and the wire.
- (5) *Liquid Expansion.* A sensing element comprising a liquid that is capable of marked expansion in volume in response to an increase in temperature.

A.3.3.77.9 Flame Detector. Flame detectors are categorized as ultraviolet, single wavelength infrared, ultraviolet infrared, or multiple wavelength infrared.

A.3.3.77.12 Line-Type Detector. Typical examples are rate-of-rise pneumatic tubing detectors, projected beam smoke detectors, and heat-sensitive cable.

A.3.3.77.13 Multi-Criteria Detector. A multi-criteria detector is a detector that contains multiple sensing methods that respond to fire signature phenomena and utilizes mathematical evaluation principles to determine the collective status of the device and generates a single output. Typical examples of multi-criteria detectors are a combination of a heat detector with a smoke detector, or a combination rate-of-rise and fixed-

temperature heat detector that evaluates both signals using an algorithm to generate an output such as pre-alarm or alarm. The evaluation can be performed either at the detector or at the control unit. Other examples are detectors that include sensor combinations that respond in a predictable manner to any combination of heat, smoke, carbon monoxide, or carbon dioxide.

A.3.3.77.14 Multi-Sensor Detector. Typical examples of multi-sensor detectors are a combination of a heat detector with a smoke detector, or a combination rate-of-rise and fixed-temperature heat detector that evaluates both signals using an algorithm to generate an output such as pre-alarm or alarm. The evaluation can be performed either at the detector or at the control unit. Other examples are detectors that include sensor combinations that respond in a predictable manner to any combination of heat, smoke, carbon monoxide, or carbon dioxide.

A.3.3.77.19 Rate Compensation Detector. A typical example of a rate compensation detector is a spot-type detector with a tubular casing of a metal that tends to expand lengthwise as it is heated and an associated contact mechanism that closes at a certain point in the elongation. A second metallic element inside the tube exerts an opposing force on the contacts, tending to hold them open. The forces are balanced in such a way that, on a slow rate-of-temperature rise, there is more time for heat to penetrate to the inner element, which inhibits contact closure until the total device has been heated to its rated temperature level. However, on a fast rate-of-temperature rise, there is not as much time for heat to penetrate to the inner element, which exerts less of an inhibiting effect so that contact closure is achieved when the total device has been heated to a lower temperature. This, in effect, compensates for thermal lag.

A.3.3.77.20 Rate-of-Rise Detector. Typical examples of rate-of-rise detectors are as follows:

- (1) *Pneumatic Rate-of-Rise Tubing.* A line-type detector comprising small-diameter tubing, usually copper, that is installed on the ceiling or high on the walls throughout the protected area. The tubing is terminated in a detector unit that contains diaphragms and associated contacts set to actuate at a predetermined pressure. The system is sealed except for calibrated vents that compensate for normal changes in temperature.
- (2) *Spot-Type Pneumatic Rate-of-Rise Detector.* A device consisting of an air chamber, a diaphragm, contacts, and a compensating vent in a single enclosure. The principle of operation is the same as that described for pneumatic rate-of-rise tubing.
- (3) *Electrical Conductivity-Type Rate-of-Rise Detector.* A line-type or spot-type sensing element in which resistance changes due to a change in temperature. The rate of change of resistance is monitored by associated control units, and an alarm is initiated when the rate of temperature increase exceeds a preset value.

A.3.3.77.22 Spark/Ember Detector. These devices are normally intended to operate in the infrared part of the spectrum.

A.3.3.77.23 Spot-Type Detector. Typical examples are bimetallic detectors, fusible alloy detectors, certain pneumatic rate-of-rise detectors, certain smoke detectors, and thermoelectric detectors.

A.3.3.78 Device (Class N). Class N devices include components connected to a Class N network that monitor the environment (e.g., smoke, heat, contact closure, manual “in case of fire” pull) and/or provide some output(s) (e.g., dry contact, audible/visual alert/notification, addressable loudspeaker) that are required to provide the real-time functionality necessary for the protection of life and property. In this way, a component connected to the network used for noncritical functions (i.e., maintenance) can be differentiated and excluded from the monitoring for integrity requirements of Class N.

Also in this way, transport equipment (e.g., switches, routers, hubs, media converters) and other equipment (e.g., printers, storage devices) can be differentiated from the requirements applied to Class N devices if they do not provide life safety-specific environmental monitoring, inputs, or outputs for the life safety system. This is not to say that this equipment is not important to the overall operation of the system, just that this equipment is not considered a “device” in the context of Class N. Equipment that does not meet the definition of a device cannot be specifically supervised but rather generally supervised as they are part of the supervised pathways that service the Class N devices themselves.

A.3.3.88 Double Doorway. Refer to Figure 17.7.6.6.4.3(A) for an illustration of detector location requirements for double doors.

A.3.3.94 Ember. Class A and Class D combustibles burn as embers under conditions where the flame typically associated with fire does not necessarily exist. This glowing combustion yields radiant emissions in parts of the radiant energy spectrum that are radically different from those parts affected by flaming combustion. Specialized detectors that are specifically designed to detect those emissions should be used in applications where this type of combustion is expected. In general, flame detectors are not intended for the detection of embers.

A.3.3.97 Emergency Communications System. The definition is not intended to include the emergency services communications systems as addressed in NFPA 1221, nor to address the public switched telephone network.

A.3.3.99 Emergency Communications System — Emergency Command Center. An emergency command center can also include the mass notification system control.

A.3.3.100 Emergency Control Function Interface Device. The emergency control function interface device is a listed relay or other listed appliance that is part of the fire alarm system. An example of an emergency control function interface device is the fire alarm control relay that removes power to a fan control unit.

A.3.3.101 Emergency Control Functions. Emergency control functions are meant to be observed functions, not equipment or devices. Examples of emergency control functions are fan control (operation or shutdown), smoke damper operation, elevator recall, elevator power shutdown, door holder release, shutter release, door unlocking, activation of exit marking devices, and so forth. Fans, elevators, smoke dampers, door holders, shutters, locked doors, or exit marking devices themselves are not emergency control functions.

A.3.3.103 Emergency Response Agency (ERA). An ERA includes any public, governmental, private, industrial, or military organization that engages in the operations specified in the definition. [1221, 2019]

A.3.3.104 Emergency Response Facility (ERF). Examples of ERFs include a fire station, a police station, an ambulance station, a rescue station, a ranger station, and similar facilities. [1221, 2019]

A.3.3.106 Endpoint (Class N). An endpoint device originates and/or terminates a communication stream and does not forward it to other devices.

An FACU, ACU, ECCU endpoint originates and/or terminates a communication stream with autonomy. If data is sent to or received from other locations, that communications stream forms a new path. The new path could even employ a different communications protocol and, where permitted, have a different pathway class designation as defined in Section 12.3.

The exception in 12.3.6(1) shows Class N communication paths do not require redundant paths when connected to a single endpoint device. However, a connection to an FACU, ACU, or ECCU must be redundant even when those elements are an endpoint on a Class N communication path, with the excepted allowance of 20 ft (6.1 m) inside a raceway or enclosure defined in 12.6.9.

A.3.3.107 Evacuation. Evacuation does not include the relocation of occupants within a building.

A.3.3.115 Fire Alarm Control Unit (FACU). In addition to the functions identified in the definition, a fire alarm control unit might have an integral operator interface, supply power to detection devices, notification appliances, transponder(s), or off-premises transmitter(s) or any combination of these. The control unit might also provide transfer of condition to relay or devices connected to the control unit. There can be multiple fire alarm control units in a fire alarm system.

A.3.3.115.2.1 Dedicated Function Fire Alarm Control Unit. A dedicated function fire alarm control unit could serve more than one emergency control function, for example a dedicated function fire alarm control unit could serve as a single control unit for sprinkler system monitoring and elevator recall. In that case, the control unit should be labeled as follows:

Sprinkler Waterflow AND Elevator Recall Control and Supervisory Control Unit

A.3.3.118.1 Combination System. Examples of non-fire systems are security, card access control, closed circuit television, sound reinforcement, background music, paging, sound masking, building automation, time, and attendance.

A.3.3.118.4 Protected Premises (Local) Fire Alarm System. A protected premises fire alarm system is any fire alarm system located at the protected premises. It can include any of the functions identified in Section 23.3. Where signals are transmitted to a communications center or supervising station, the protected premises fire alarm system also falls under the definition of one of the following systems: central station service alarm system, remote supervising station alarm system, proprietary supervising station alarm system, or auxiliary alarm system. The requirements that pertain to these systems apply in addition to the requirements for the protected premises fire alarm systems.

A.3.3.119 Fire Command Center. The fire command center should contain the following features as applicable to the specific facility:

- (1) Emergency voice/alarm communications system unit

- (2) Fire department communications unit
- (3) Fire detection and alarm system annunciator unit
- (4) Annunciator unit visually indicating the location of the elevators and whether they are operational
- (5) Status indicators and controls for air-handling systems
- (6) The required fire-fighter's control panel for smoke control systems installed in the building
- (7) Controls for unlocking stairway doors simultaneously
- (8) Sprinkler valve and waterflow detector display panels
- (9) Emergency and standby power status indicators
- (10) Telephone for fire department use with controlled access to the public telephone system
- (11) Fire pump status indicators
- (12) Schematic building plans indicating the typical floor plan and detailing the building core, means of egress, fire protection systems, fire-fighting equipment, and fire department access
- (13) Worktable
- (14) Generator supervision devices, manual start, and transfer features
- (15) Public address system
- (16) Other emergency systems identified in emergency response plan

A.3.3.135 Hearing Loss. The severity of hearing loss is measured by the degree of loudness, as measured in decibels, a sound must attain before being detected by an individual. Hearing loss can be ranked as mild, moderate, severe, or profound. It is quite common for someone to have more than one degree of hearing loss (e.g., mild sloping to severe). The following list shows the rankings and their corresponding decibel ranges:

- (1) Mild:
 - (a) For adults: between 25 and 40 dB
 - (b) For children: between 15 and 40 dB
- (2) Moderate: between 41 and 55 dB
- (3) Moderately severe: between 56 and 70 dB
- (4) Severe: between 71 and 90 dB
- (5) Profound: 90 dB or greater

NIOSH defines material hearing impairment as an average of the hearing threshold levels for both ears that exceeds 25 dB at 1000, 2000, 3000, and 4000 Hz.

The American Medical Association indicates that a person has suffered material impairment when testing reveals a 25 dB average hearing loss from audiometric zero at 500, 1000, 2000, and 3000 Hz. OSHA has recognized that this is the lowest level of hearing loss that constitutes any material hearing impairment.

A.3.3.143 Identified (as applied to equipment). Some examples of ways to determine suitability of equipment for a specific purpose, environment, or application include investigations by a qualified testing laboratory (listing and labeling), an inspection agency, or other organizations concerned with product evaluation. [70:100, Informational Note]

A.3.3.144 Immediately (as used in Chapter 26). Actions that are performed "immediately" should be performed within a maximum of 90 seconds from receipt of a signal.

A.3.3.145 Impairment. An impairment is a system component or function that is not working properly, which can result in the system or unit not functioning when required. This might be due to an intentional act, such as closing a valve or disabling an

initiating device. The impairment also might be caused by a deficiency in a piece of equipment or subsystem. An example of emergency impairment is physical damage to a control unit or wiring. Examples of a planned impairment include the addition of new devices or appliances or the reprogramming of system software.

A.3.3.146 In Writing. The definition of *in writing* should be applied to any documentation mandated by this Code whereby a statement or notification, or both, is required to be provided by the sender to a separate and distinct entity or to multiple entities, such as between an inspection, testing, and maintenance service provider and a building owner or between a supervising/central station provider and the authority having jurisdiction.

Such correspondence should be authorized and recognized by the sender as an official representation of their organization and clearly identifiable from the recipient's perspective as having been authorized by the sender. Examples of correspondence made *in writing* could include, but not be limited to, hard copy or digital notification that includes company letterhead or other type of company designation, authorized signatory or signatories either in digital form or on hard copy, or in an email signature block, or any combination thereof. Examples where such correspondence would be required could include, but not be limited to, test plans, inspection and testing reports, notification of deficiencies/corrections, change of supervising/central station providers, notification of recalled equipment, or suspected low audibility levels for alarm signaling.

The definition of *in writing* should not be applied to text messages, voice mails, notations on scratch paper, or any similar means of notification that fail to reflect the verifiable and authenticated nature of correspondence that is submitted *in writing*, as that term is defined by this Code.

A.3.3.148.2 Automatic Extinguishing System Supervisory Device. Examples of abnormal conditions include the following:

- (1) A control valve that has changed position, such as a normally open valve in the closed position.
- (2) Pressure levels that exceed or are less than needed, such as a dry pipe system having low air pressure.
- (3) Liquid agent levels that exceed or are less than needed, such as a foam concentrate tank having inadequate foam to meet design requirements.
- (4) Room temperatures below 40°F (4.4°C).
- (5) Loss of power to a fire pump.
- (6) A fire pump running.
- (7) High engine temperature.
- (8) Engine overspeed.

A.3.3.152 Intelligible. The term *intelligible* is intended to address only the communications channel and the acoustic environment as shown in Figure A.3.3.152. Intelligibility assumes that the talker or recorded voice message is in a language and using words known to the listener. It also assumes that the listener has normal hearing.

A.3.3.153.1.1 Emergency Control Function Interface. See Figure A.3.3.153.1.1.




FIGURE A.3.3.152 Voice Signal Path. (Source: K. Jacob, Bose® Professional Systems)




FIGURE A.3.3.153.1.1 Emergency Control Function Interface.

A.3.3.153.2 Fire Alarm Control Interface. Some mass notification systems' autonomous control units (ACUs) might not be listed to UL 864 for fire alarm service. Any component that is connected to the fire alarm system must be connected through a listed interface that will protect the functions of other systems should one system experience a failure. This can be through isolation modules, control relays, or other approved means that are listed for the intended use. As an example, failure of a stand-alone ACU should not affect any function of the FACU.

A.3.3.162 Local Operating Console (LOC). An LOC allows users within a building to activate prerecorded messages, deliver live voice messages, observe current status of the main autonomous control unit (ACU), or have similar such ACU operator functions at various locations within the building. An LOC serves a similar function as a remote fire alarm annunciator. However, there can be multiple LOC locations within a building, such as on each floor, at each main entry point, at the switchboard or receptionist's console, or as determined by a risk analysis.

A.3.3.168 Managed Facilities-Based Voice Network (MFVN). Managed facilities-based voice network service is functionally equivalent to traditional PSTN-based services provided by authorized common carriers (public utility telephone companies) with respect to dialing, dial plan, call completion, carriage of signals and protocols, and loop voltage treatment and provides all of the following features:

(1) A loop start telephone circuit service interface.

- (2) Pathway reliability that is assured by proactive management, operation, and maintenance by the MFVN provider.
- (3) 8 hours of standby power supply capacity for MFVN communications equipment either located at the protected premises or field deployed. Industry standards followed by the authorized common carriers (public utility telephone companies), and the other communications service providers that operate MFVNs, specifically engineer the selection of the size of the batteries, or other permanently located standby power source, in order to provide 8 hours of standby power with a reasonable degree of accuracy. Of course, over time, abnormal ambient conditions and battery aging can always have a potentially adverse effect on battery capacity. The MFVN field-deployed equipment typically monitors the condition of the standby battery and signals potential battery failure to permit the communications service provider to take appropriate action.
- (4) 24 hours of standby power supply capacity for MFVN communications equipment located at the communications service provider's central office.
- (5) Installation of network equipment at the protected premises with safeguards to prevent unauthorized access to the equipment and its connections.

When providing telephone service to a new customer, MFVN providers give notice to the telephone service subscriber of the need to have any connected alarm system tested by authorized

fire alarm service personnel in accordance with Chapter 14 to make certain that all signal transmission features have remained operational. These features include the proper functioning of line seizure and the successful transmission of signals to the supervising station. In this way, the MFVN providers assist their new customers in complying with a testing procedure similar to that outlined in 26.2.7 for changes to providers of supervising station service.

The evolution of the deployment of telephone service has moved beyond the sole use of metallic conductors connecting a telephone subscriber's premises with the nearest telephone service provider's control and routing point (wire center). In the last 25 years, telephone service providers have introduced a variety of technologies to transport multiple, simultaneous telephone calls over shared communication pathways. In order to facilitate the further development of the modernization of the telephone network, the authorized common carriers (public utility telephone companies) have transitioned their equipment into a managed facilities-based voice network (MFVN) capable of providing a variety of communications services in addition to the provision of traditional telephone service.

Similarly, the evolution of digital communications technology has permitted entities other than the authorized common carriers (public utility telephone companies) to deploy robust communications networks and offer a variety of communications services, including telephone service.

These alternate service providers fall into two broad categories. The first category includes those entities that have emulated the MFVN provided by the authorized common carriers. The second category includes those entities that offer telephone service using means that do not offer the rigorous quality assurance, operational stability, and consistent features provided by an MFVN.

The Code intends to only recognize the use of the telephone network transmission of alarm, supervisory, trouble, and other emergency signals by means of MFVNs.

For example, the Code intends to permit an MFVN to provide facilities-based telephone (voice) service that interfaces with the premises fire alarm or emergency signal control unit through a digital alarm communicator transmitter (DACT) using a loop start telephone circuit and signaling protocols fully compatible with and equivalent to those used in public switched telephone networks. The loop start telephone circuit and associated signaling can be provided through traditional copper wire telephone service (POTS — "plain old telephone service") or by means of equipment that emulates the loop start telephone circuit and associated signaling and then transmits the signals over a pathway using packet switched (IP) networks or other communications methods that are part of an MFVN.

Providers of MFVNs have disaster recovery plans to address both individual customer outages and widespread events such as tornados, ice storms, or other natural disasters, which include specific network power restoration procedures equivalent to those of traditional landline telephone services.

A.3.3.170 Manufacturer's Published Instructions. Manufacturer's applicable documentation can be subject to revision.

A.3.3.171 Mass Notification Priority Mode. Nonemergency mass notification activations are not intended to initiate this mode of operation.

A.3.3.172 Mass Notification System. A mass notification system can use intelligible voice communications, visual signals, text, graphics, tactile, or other communications methods. The system can be used to initiate evacuation or relocation or to provide information to occupants. The system can be intended for fire emergencies, weather emergencies, terrorist events, biological, chemical or nuclear emergencies, or any combination of these. The system can be automatic, manual, or both. Access to and control of the system can be from a single, on-site location or can include multiple command locations, including some remote from the area served. Systems can be wired, wireless, or some combination of the two.

A.3.3.176 Minimum Hearing Distance. In most cases, the minimum hearing distance is at a location where an occupant stands directly under or next to an audible notification appliance. What height should be used for the "ear"? For normal occupancy and use that distance might be easy to define. The average human height is about 68 in. (1.73 m) with the ear being about 62–63 in. (1.57–1.6 m) high. The designer might use 66 in. (1.68 m) as a reasonable selection. However, designers need to consider how the space will be used and whether the use and occupancy of the space might affect the minimum hearing distance. Consider an exercise facility where the audible notification appliances are installed on the perimeter walls at a height of 90 in. (2.29 m). An exercise machine, such as a stair climber, could elevate a person so that their ear is very close to the appliance.

Regardless of the designer's selection of a minimum hearing distance, it is possible, though not always "normal," for a person to get closer and to experience damaging sound levels. For example, someone on a ladder changing a light bulb or accessing high shelves could be significantly closer to an audible notification appliance than other users of the space. Should that possibility be considered when determining the minimum hearing distance? Other mitigation, such as training and personal protective equipment (PPE) (e.g., hearing protection) might be used to protect people in those instances.

The maximum allowable sound pressure level (110 dBA) is based on possible damage to human ears. Systems that expose other animals or life that might be damaged by sound pressure waves, might require additional consideration of loudness, frequency content, and sound patterns.

A.3.3.187 Nonrequired. There are situations where the applicable building or fire code does not require the installation of a fire alarm system or specific fire alarm system components, but the building owner wants to install a fire alarm system or component to meet site-specific needs or objectives. A building owner always has the option of installing protection that is above the minimum requirements of the Code. It is the intent of the Code that any fire alarm system, or fire alarm system components installed voluntarily by a building owner, meet the requirements of the applicable portions of the Code. However, it is not the intent of the Code that the installation of a nonrequired fire alarm system, or fire alarm system components, trigger requirements for the installation of additional fire alarm system components or features. For example, the installation of a fire alarm control unit and fire detectors to service a specific area, such as a computer room or flammable liquid storage room, does not trigger a requirement for audible or visual notification appliances, manual fire alarm boxes, or other fire alarm system features in other parts of the building.

A.3.3.189.1.2 Textual Audible Notification Appliance. An example of a textual audible notification appliance is an electrical acoustic transducer that reproduces a voice or tone signal, such as a loudspeaker.

A.3.3.189.3.1 Textual Visual Notification Appliance. Textual visual notification appliances provide temporary text, permanent text, or symbols and include, but are not limited to, annunciators, monitors, CRTs, displays, and printers.

A.3.3.193 Observation. Examples of observations could include, but are not limited to, manufacturer's suggested device replacement, executive software updates, corroded electrical component replacement, and other similar items not directly impacting a system's ability to complete its intended function at the point in time when the observation is made.

A.3.3.194 Occupiable. The term *occupiable* is used in this Code and in other governing laws, codes, or standards to determine areas that require certain features of a system. It is important for designers to understand that unless otherwise required, spaces that are not occupiable might not require or need coverage by initiating devices or occupant notification appliances. For example, most closets would not be considered to be occupiable. However, a space of the same size used as a file room would be considered occupiable.

A.3.3.196 Octave Band. Frequencies are generally reported based on a standard, preferred center frequency, f_c . The bandwidth of a particular octave band has a lower frequency, f_n , and an upper frequency, f_{n+1} . The relationships are as follows:

[A.3.3.196a]

$$f_{n+1} / f_n = 2^k$$

where:

$k = 1$ for octave bands

$k = 1/3$ for one-third octave bands

and

[A.3.3.196b]

$$f_c = f_n 2^{1/2}$$

For example, the 500 Hz octave band (center frequency) has a lower limit of 354 and an upper limit of 707 Hz. The octave band with a center frequency of 1000 Hz has a lower frequency of 707 Hz and an upper frequency of 1414 Hz.

A.3.3.203 Ownership. Inspection, testing, and maintenance is the responsibility of the property or building owner, or it can be transferred by contract. Systems installed, owned, or leased by a tenant are the responsibility of the tenant. The installing company should provide written notice of these responsibilities to the system user.

A.3.3.229.1 Auxiliary Alarm System. Alarms from an auxiliary alarm system are received at the communications center on the same equipment and by the same methods as alarms transmitted from public alarm boxes.

A.3.3.236 Qualified. *Qualified* might also mean that the person has knowledge of the installation, construction, or operation of apparatus and the hazards involved.

A.3.3.244 Radio Frequency. The present practicable limits of radio frequency (RF) are roughly 10 kHz to 100,000 MHz. Within this frequency range, electromagnetic waves can be detected and amplified as an electric current at the wave frequency. *Radio frequency* usually refers to the *RF* of the assigned channel. [1221, 2019]

A.3.3.252 Remote Access. Remote devices include but are not limited to laptop computers, cellular handheld devices, cloud-based systems, applications, and other similar equipment or software. Remote access communications are not intended to be used for supervising station alarm reporting system.

A.3.3.261 Response. Responses can be effected manually or automatically. One response to a signal might be to activate notification appliances or transmitters, which in turn generate additional signals. See A.3.3.65.

A.3.3.261.1 Alarm Response. Examples include activation of alarm notification appliances, elevator recall, smoke control measures, emergency responder dispatch, and deployment of resources in accordance with a risk analysis and the associated emergency response plan.

A.3.3.261.2 Pre-Alarm Response. Examples include the activation of appropriate notification appliances, dispatch of personnel, investigation of circumstances and problem resolution in accordance with a risk analysis and action plan, preparation for a potential alarm response, and so forth.

A.3.3.261.3 Supervisory Response. Examples include the activation of supervisory notification appliances, the shutdown of machines, fan shutdown or activation, dispatch of personnel, investigation of circumstances and problem resolution in accordance with a risk analysis and action plan, and so forth.

A.3.3.261.4 Trouble Response. Examples include the activation of trouble notification appliances, dispatch of service personnel, deployment of resources in accordance with an action plan, and so forth.

A.3.3.271 Shop Drawings. Shop drawings typically include the property location, scaled floor plans, equipment wiring details, typical equipment installation details, riser details, conduit/conductor size, and routing information needed to install a fire alarm and/or signaling system.

A.3.3.272 Signal. See A.3.3.65.

A.3.3.272.1 Alarm Signal. Examples of alarm signals include outputs of activated alarm initiating devices, the light and sound from activated alarm notification appliances, alarm data transmission to a supervising station, and so forth.

A.3.3.272.5 Fire Alarm Signal. Examples include outputs from activated fire alarm initiating devices (manual fire alarm box, automatic fire detector, waterflow switch, etc.), the light and sound from activated fire alarm notification appliances, fire alarm data transmission to a supervising station, and so forth.

A.3.3.272.6 Guard's Tour Supervisory Signal. The term *guard's tour supervisory signal*, associated with systems supporting guard's tour supervisory service, is a message indicating that a guard has actuated a guard's tour reporting station (not in itself an indication of a supervisory condition). Guard's tour supervisory signals are not a subset of the general category of supervisory signals as used in this Code.

A.3.3.272.7 Pre-Alarm Signal. Examples include outputs of analog initiating devices prior to reaching alarm levels, the light and sound from activated pre-alarm notification appliances, aspiration system outputs indicating smoke at levels below the listed alarm threshold, and so forth.

A.3.3.272.9 Supervisory Signal. Examples include activated supervisory signal-initiating device outputs, supervisory data transmissions to supervising stations, the light and sound from activated supervisory notification appliances, a delinquency signal indicating a guard's tour supervisory condition, and so forth.

The term *guard's tour supervisory signal*, associated with systems supporting guard's tour supervisory service, is a message indicating that a guard has activated a guard's tour reporting station (not in itself an indication of a supervisory condition). Guard's tour supervisory signals are not a subset of the general category of supervisory signals as used in this Code.

A.3.3.272.10 Trouble Signal. Examples include off-normal outputs from integrity monitoring circuits, the light and sound from activated trouble notification appliances, trouble data transmission to a supervising station, and so forth.

A.3.3.280 Sleeping Area. Bedrooms (or sleeping rooms) separated by other use areas, such as kitchens or living rooms (but not bathrooms), are considered separate sleeping areas.

A.3.3.285.2 Ionization Smoke Detection. Ionization smoke detection is more responsive to invisible particles (smaller than 1 micron in size) produced by most flaming fires. It is somewhat less responsive to the larger particles typical of most smoldering fires. Smoke detectors that use the ionization principle are usually of the spot type.

A.3.3.285.3 Photoelectric Light Obscuration Smoke Detection. The response of photoelectric light obscuration smoke detectors is usually not affected by the color of smoke.

Smoke detectors that use the light obscuration principle are usually of the line type. These detectors are commonly referred to as projected beam smoke detectors.

A.3.3.285.4 Photoelectric Light-Scattering Smoke Detection. Photoelectric light-scattering smoke detection is more responsive to the visible particles (larger than 1 micron in size) produced by most smoldering fires. It is somewhat less responsive to the smaller particles typical of most flaming fires. It is also less responsive to black smoke than to lighter colored smoke. Smoke detectors that use the light-scattering principle are usually of the spot type.

A.3.3.285.5 Video Image Smoke Detection (VISD). VISD is a software-based method of smoke detection that can analyze images for changes in features such as brightness, contrast, edge content, loss of detail, and motion. The detection equipment can consist of cameras producing digital or analog (converted to digital) video signals and processing unit(s) that maintain the software and interfaces to the fire alarm control unit.

A.3.3.291 Spark. The overwhelming majority of applications involving the detection of Class A and Class D combustibles with radiant energy-sensing detectors involve the transport of particulate solid materials through pneumatic conveyor ducts or mechanical conveyors. It is common in the industries that include such hazards to refer to a moving piece of burning

material as a *spark* and to systems for the detection of such fires as *spark detection systems*.

A.3.3.326 Unwanted Alarm. Unwanted alarms are any alarms that occur when there is no hazard condition present. These are sometimes also called false alarms. Because the term *false* has been used by many people to mean many different things, this Code is instead using the terms *unwanted*, *fault*, *nuisance*, *unintentional*, *unknown*, and *malicious* to categorize the different types of alarms. Unwanted alarms might be intentional, unintentional, or unknown. If they were caused intentionally, they might have been done by someone with the intent to cause disruption and should be classified as malicious. However, an unintentional alarm might occur when, for example, a child actuated a manual fire alarm box not knowing the consequences. Similarly, someone accidentally causing mechanical damage to an initiating device that results in an alarm is causing an unintentional alarm.

A.3.3.326.2 Nuisance Alarm. Nuisance alarms are unwanted alarms. Sometimes nuisance alarms might be called false alarms. In this Code, any unwanted alarm is considered false because they are not indicative of real hazards. Because the term *false* has been used by many people to mean many different things, this Code is instead using the terms *unwanted*, *nuisance*, and *malicious* to categorize the different types of alarms. They occur when some condition simulates a fire or other hazardous condition. For example, cigarette smoke can activate smoke detectors and smoke alarms. In that case, there might not be anything wrong with the smoke detector or smoke alarm — it is doing its job responding to the condition or stimulus that it was designed to detect. Another example would be a heat detector or heat alarm that activates when someone inadvertently points a hair dryer towards it. A malicious alarm occurs when someone intentionally activates the detector or alarm when there is no fire hazard. See the definitions of malicious, unintentional, unknown, and unwanted alarms.

A.3.3.328 Video Image Flame Detection (VIFD). Video image flame detection (VIFD) is a software-based method of flame detection that can be implemented by a range of video image analysis techniques. VIFD systems can analyze images for changes in features such as brightness, contrast, edge content, loss of detail, and motion. The detection equipment can consist of cameras producing digital or analog (converted to digital) video signals and processing unit(s) that maintain the software and interfaces to the fire alarm control unit.

A.3.3.336 Wireless Mesh Network (WMN) (as used in Chapter 26). Each node participates in routing by forwarding data for other nodes. The data hops from node to node until it reaches the receiving point. Which nodes forward data can be predetermined or determination can be made dynamically on the basis of network connectivity. Wireless mesh networks are often designed to self-form and self-heal. Wireless mesh networks can be implemented with various wireless technologies. (SIG-SSS)

A.3.3.339.2 Signaling Zone. A notification zone is the smallest discrete area used for any announcements or signaling. Depending on the emergency response plan, a signaling zone can encompass several notification zones. For example, in most high-rise buildings, each single floor (fire area) is a notification zone. Most emergency response plans call for the signaling zone to be the fire floor, floor above, and a floor below.

For example, the floors of a high rise that are playing the evacuation message and the “wait in place” message would be in the same notification zone, because they are activated simultaneously. The word “identical” clarifies that the notification zone is communicating a common message.

A.7.1.3 Unless otherwise identified, only the minimum documentation requirements of 7.2.1 apply. More stringent documentation requirements found in other chapters and other laws, codes, and standards, as well as project specifications, should identify any other documentation sections in this chapter that would be applicable.

A.7.2 It is not intended that all of the details outlined in Sections 7.3 through 7.5 be required for every project. In general, the more complex the system, the more stringent the requirements become for documentation. It is recognized that some projects would require only the minimum documentation listed in Section 7.2. Other projects might require more detailed documentation. Sections 7.3 through 7.5 provide menus of additional means of documenting a system. The intent is for other governing laws, codes, or standards; other parts of this Code; or project specifications or drawings to select the additional specific pieces of documentation from Sections 7.3 through 7.5.

A.7.2.1 In many cases, the installer might not have adequate record drawings or other completion documentation for the existing system. As an example, where a temporary school building is being installed, the fire alarm system subpanel in the temporary building should be fully documented, but the fire alarm system for the entire existing school might be so old that adequate documentation might not exist. In this example, documentation required in Section 7.2 should be completed only for the new subpanel and the interfaces to the existing school fire alarm system.

A.7.2.1(1) The purpose for a written narrative is to provide a description of the work to be performed and could be as simple as “Install additional three smoke detectors to provide coverage for newly installed meeting room.” However, it could be desirable to include why or by whose direction the work is being done, such as “at owner’s request,” “per specifications dated ...,” or “at the direction of” See also Section 23.3 for additional system feature documentation requirements.

A.7.2.1(12) Paragraph 26.6.2.5 allows for the following three communications pathway options when a supervising station fire alarm system is provided:

- (1) Performance-based technologies
- (2) Digital alarm communicator systems
- (3) Radio systems, which includes one-way private and two-way RF systems

Chapter 26 includes several requirements specific to each of these communications pathway alternatives. In order to verify the provided communication path(s), and any shared equipment, comply with Code requirements, the following are examples of information that should be submitted as the minimum documentation for a supervising station fire alarm system:

- (1) Performance-based technologies
 - (a) The type of performance-based transmitter(s) to be used such as IP communicators, cellular radios, and so forth

- (b) Whether communications with the supervising station will be via a single pathway or a multiple pathway
 - (c) An indication of the use, where applicable, of shared equipment such as routers, modems, and LANs within the protected premises
 - (d) Battery calculations for the shared equipment, which should meet the requirements of 26.6.3.13
- (2) Digital alarm communicator system
 - (a) The primary communications pathway, which should be a telephone line
 - (b) The secondary communications pathway, which should comply with 26.6.4.2.4
- (3) Radio system
 - (a) The type of radio system that will be used (private one-way or two-way RF)
 - (b) The secondary power provided for the radio transmitter

Where the transmitter equipment is located separately from the main fire alarm control unit, an indication of its protection in accordance with 10.4.4 should also be provided within the minimum documentation.

A.7.3.1 See Section 7.2 for the minimum documentation requirements.

A.7.3.2 Design (layout) documents should contain information related to the system that could include specifications, shop drawings, input/output matrix, battery calculations, notification appliance voltage drop calculations for visual notification appliances and loudspeakers, and product technical data sheets.

Design (layout) documents could include such items as preliminary plans issued as guidance and direction, risk analysis, emergency response plan, or a combination of these.

Deviations from requirements of governing laws, codes, standards, or preliminary plan requirements specified by an engineer should be clearly identified and documented as such.

Documentation of equivalency, where applicable, should be provided in accordance with Section 1.5 and be included with the record drawings.

It is the intent that existing systems that are altered should have design (layout) documents prepared that are applicable only to the portion(s) of the system being altered.

A.7.3.3 Preliminary plans such as those used for bidding, solicitation, or for obtaining permits could contain information as follows:

Performance criteria required in support of alternative means and methods for other codes, standards, or construction features should be clearly identified on the design (layout) documentation.

Such information should reference applicable waivers, appeals, variances, or similarly approved deviations from prescriptive criteria.

Preliminary documents could include the following:

- (1) Specifications and narrative applicable to the project
- (2) Interface requirements between systems such as fire alarm, mass notification, security, HVAC, smoke control, paging, background music, audio visual equipment,

elevators, access control, other fire protection systems, and so forth

- (3) Sequence of operation
- (4) Survivability of system circuits and equipment, when applicable
- (5) Notification zones, when applicable
- (6) Message content for voice systems
- (7) Means of system monitoring that is to be provided, when applicable
- (8) Codes and editions applicable to the system(s)
- (9) Special requirements of the owner, governing authority, or insurance carrier, when applicable
- (10) Voice delivery components beyond standard industry products required to achieve intelligibility

When devices are located (spaced) on preliminary drawings, the devices should be located (spaced) in accordance with standards, listings, and limitations of the equipment specified. When devices are not located (spaced) on the preliminary documents, a note should be included directing that the spacing should be per listing(s) and this Code.

When known, acoustic properties of spaces should be indicated on the preliminary design (layout) documents.

The architect/engineer preparing bid documents should not simply require a contractor to install a fire alarm system in accordance with codes, but rather outline the intended minimum performance criteria to be achieved in accordance with Section 7.3, with guidance from A.7.3.3.

A.7.3.4.1 See Section 7.2 for the minimum documentation requirements.

A.7.3.6 The Risk Analysis Checklist in Figure A.7.3.6 is not mandatory, but it can be used to initiate the thought process for identifying hazards in a facility.

A.7.3.7 When a system or component is installed in accordance with performance-based design criteria, such systems should be reviewed and acceptance tested by a design professional to verify that performance objectives are attained.

Due to unique design and construction challenges, fire protection concepts are often established on performance-based engineering practices. When such practices have been approved by the authority having jurisdiction, the engineer of record should sign off on the final installation documents to ensure that all conditions have been satisfied. Such engineering analysis could be beyond the qualifications of the code authority. As such, it is imperative that the engineer of record review and accept final concepts as accepted by the authority having jurisdiction.

A.7.3.9.1 Evaluation documentation can also include documentation such as that associated with performance-based alternatives and documentation related to equivalencies as well as any other special documentation that is specific to a particular system. Examples of where evaluations might be required are found in 23.4.3.1 and 24.5.24.2.

A.7.4.1 See Section 7.2 for the minimum documentation requirements.

A.7.4.2 It is important to note that shop drawings and particularly the word “sheets” do not necessarily mean physical paper sheets, but could be on electronic media.

A.7.4.6(2)(g) Designations should include an indication of where pathway survivability is being provided.

A.7.4.9 For an example of an input/output matrix of operation, see A.14.6.1.1.

A.7.5.1 See Section 7.2 for the minimum documentation requirements.

A.7.5.3.1(1) An owner’s manual should contain the following documentation:

- (1) A detailed narrative description of the system inputs, evacuation signaling, ancillary functions, annunciation, intended sequence of operations, expansion capability, application considerations, and limitations.
- (2) A written sequence of operation in matrix or narrative form.
- (3) Operator instructions for basic system operations, including alarm acknowledgment, system reset, interpretation of system output (LEDs, CRT display, and printout), operation of manual evacuation signaling and ancillary function controls, and change of printer paper.
- (4) A detailed description of routine maintenance and testing as required and recommended and as would be provided under a maintenance contract, including testing and maintenance instructions for each type of device installed. This information should include the following:
 - (a) Listing of the individual system components that require periodic testing and maintenance
 - (b) Step-by-step instructions detailing the requisite testing and maintenance procedures, and the intervals at which these procedures are to be performed, for each type of device installed
 - (c) A schedule that correlates the testing and maintenance procedures
- (5) A service directory, including a list of names and telephone numbers of those who provide service for the system.

A.7.5.5.2 For an example of an input/output matrix of operation, see A.14.6.1.1.

A.7.5.5.5 It is important that the documentation required by this section is available for technicians so they will be able to recognize variations of system configuration during acceptance, reacceptance, and periodic testing. It is also necessary for enforcement personnel in order to prevent confusion when they could otherwise misidentify an approved variation for being non-code compliant. This documentation is also necessary for those who might design additions or modifications.

A.7.5.6.1 It is the intent of this section to permit using forms other than Figure 7.8.2(a) through Figure 7.8.2(f) as long as they convey the same information.

RISK ANALYSIS CHECKLIST

Facility name: _____ Facility location: _____

Prepared by: _____ Date prepared: _____

Title and contact information: _____

ECS system type: _____

PART ONE: Identification of Assets or Operations at Risk

Use Part One of this checklist to identify the following assets or operations at risk at your facility

☐ People

- | | |
|--|--|
| ☐ Employees
☐ Visitors and guests
☐ Contractors working on site | ☐ Emergency responders
☐ Community surrounding the facility |
|--|--|

☐ Property

- | | |
|---|--|
| ☐ Physical property <ul style="list-style-type: none"> ☐ Corporate offices ☐ Manufacturing facilities ☐ Call center ☐ Distribution centers ☐ Data-processing center ☐ Research and development labs ☐ Property on the premises of others ☐ Vital papers, records, and drawings
☐ Intellectual property <ul style="list-style-type: none"> ☐ Copyright and patent infringement ☐ Trademark infringement ☐ Theft of intellectual property ☐ Theft of information | ☐ Utilities <ul style="list-style-type: none"> ☐ Telecommunications ☐ Electricity ☐ Water ☐ Gas ☐ Steam ☐ Heating/ventilation/air conditioning ☐ Pollution control ☐ Sewerage system ☐ Other critical infrastructure
☐ Computers and computer networks <ul style="list-style-type: none"> ☐ Software applications ☐ Electronic data
☐ Inventory <ul style="list-style-type: none"> ☐ Raw materials ☐ Finished product |
|---|--|

☐ Operations

- | | |
|---|--|
| ☐ Manufacturing processes
☐ Delivery of services
☐ Administrative support services | ☐ Research and development
☐ Supply chain |
|---|--|

☐ Environment

- | | |
|--|---------------------------------|
| ☐ Air
☐ Water | ☐ Ground |
|--|---------------------------------|

☐ Organization

- | | |
|---|--|
| ☐ Economic and financial condition
☐ Licenses, patents, or trademarks
☐ Reputation and image as well-managed company
☐ Contractual obligations | ☐ Community relationships
☐ Regional and national impact
☐ Regulatory compliance and relationships with vendors |
|---|--|

FIGURE A.7.3.6 Risk Analysis Checklist.

RISK ANALYSIS CHECKLIST (continued)

PART TWO: Determination of Facility Hazards

Use Part Two of this checklist to determine the potential hazards that might impact your facility.

☐ Natural Hazards—Geological

- | | |
|---|---|
| ☐ Earthquake
☐ Tsunami
☐ Volcano | ☐ Landslide, mudslide, subsidence
☐ Glacier, iceberg |
|---|---|

☐ Natural Hazards—Meteorological

- | | |
|--|---|
| ☐ Flood, flash flood, tidal surge
☐ Drought
☐ Windstorm, tropical cyclone, hurricane, tornado, water spout, dust/sand storm
☐ Extreme temperatures (heat, cold) | ☐ Lightning strikes
☐ Famine
☐ Geomagnetic storm
☐ Snow, ice, hail, sleet, avalanche |
|--|---|

☐ Natural Hazards—Biological

- | | |
|--|---|
| ☐ Diseases (pandemic) | ☐ Animal or insect infestation or damage |
|--|---|

☐ Human-Caused Accidental Events

- | | |
|--|---|
| ☐ Hazardous material (explosive, flammable liquid, flammable gas, flammable solid, oxidizer, poison, radiological, corrosive) spill or release
☐ Natural gas leak
☐ Nuclear power plant incident
☐ Hazmat incident off site
☐ Explosion/fire
☐ Wildfire (forest, range, urban, wildland, urban interface)
☐ Transportation accident (motor vehicle, railroad, watercraft, aircraft pipeline)
☐ Building/structure failure or collapse | ☐ Entrapment
☐ Mechanical breakdown
☐ Energy/power/utility failure
☐ Fuel/resource shortage
☐ Air/water pollution, contamination
☐ Water control structure/dam/levee failure
☐ Communications systems interruptions
☐ Financial issues, economic depression, inflation, financial system collapse
☐ Misinformation |
|--|---|

☐ Human-Caused Intentional Events

- | | |
|---|---|
| ☐ Terrorism (explosive, chemical, biological, radiological, nuclear, cyber)
☐ Sabotage or vandalism
☐ Civil disturbance, public unrest, mass hysteria, riot
☐ Enemy attack, war
☐ Insurrection
☐ Strike or labor dispute
☐ Demonstration
☐ Disinformation
☐ Criminal activity (vandalism, arson, theft, fraud, embezzlement, data theft)
☐ Electromagnetic pulse
☐ Physical or information security breach | ☐ Sniper incident
☐ Crime, theft, or robbery
☐ Product defect or contamination
☐ Harassment
☐ Arson
☐ Bomb threat
☐ Lost person
☐ Child abduction
☐ Kidnap
☐ Extortion
☐ Hostage incident
☐ Workplace violence |
|---|---|

☐ Technological-Caused Events

- | | |
|---|---|
| ☐ Telecommunications
☐ Central computer, mainframe, software, or application (internal/external) | ☐ Energy/power/utility
☐ Ancillary support equipment |
|---|---|

FIGURE A.7.3.6 Continued

A.7.5.6.2 Protected premises fire alarm systems are often installed under construction or remodeling contracts and subsequently connected to a supervising station alarm system under a separate contract. All contractors should complete the portions of the record of completion documentation for the portions of the connected systems for which they are responsible. Several partially completed documents might be accepted by the authority having jurisdiction provided that all portions of the connected systems are covered in the set of documents.

A.7.5.6.3 The requirements of Chapter 14 should be used to perform the installation wiring and operational acceptance tests required when completing the record of completion.

The record of completion form shall be permitted to be used to record decisions reached prior to installation regarding intended system type(s), circuit designations, device types, notification appliance type, power sources, and the means of transmission to the supervising station.

A.7.5.6.6.3 It is the intent that if an original or current record of completion is not available for the overall system, the installer would provide a new record of completion that addresses items discovered about the system. The installer will complete the respective sections related to the overall system that have been discovered under the current scope of work. It is not the intent of this section to require an in-depth evaluation of an existing system solely for the purpose of completing a system-wide record of completion.

A.7.5.8 This section is intended to provide a basis for the authority having jurisdiction to require third-party verification and certification that the authority having jurisdiction and the system owner can rely on to reasonably assure that the fire alarm system installation complies with the applicable requirements. Where the installation is an extension, modification, or reconfiguration of an existing system, the intent is that the verification be applicable only to the new work and that reacceptance testing be acceptable.

A.7.7.1.2 It is intended that archived records be allowed to be stored in electronic format as long as hard copies can be made from them when required.

A.7.7.2.3 The intent is that paper and/or electronic documents should not be stored inside the control unit because control units are not typically approved for the storage of combustible material.

Examples of system documents include the following:

- (1) Record drawings (as-builts)
- (2) Equipment technical data sheets
- (3) Alternative means and methods, variances, appeals, approvals, and so forth
- (4) Performance-based design documentation in accordance with 7.3.7
- (5) Risk analysis documentation in accordance with 7.3.6
- (6) Emergency response plan in accordance with 7.3.8
- (7) Evaluation documentation in accordance with 7.3.9
- (8) Software and firmware control documentation in accordance with 23.2.2

A.7.7.2.6 Documentation stored in electronic media can become obsolete, for example, 5.25 in. and 3.5 in. disks and tape drives are not supported by current technology. Updating the stored media to current technology concerns the programs used to operate them, and the computer or hardware used to

interface to the system installed. Thus, it is necessary to ensure that all components are still compatible with the installed system.

A.7.7.3.2 It is recognized that there are circumstances in which the security and protection of some system documents will require measures other than that prescribed in this Code. Since a common expectation of a mass notification system is to function during security and/or terrorist events, it could be crucial that system design be protected.

Where such conditions have been identified, the stakeholders should clearly identify what and how system documents should be maintained to satisfy the integrity of this section regarding reviews, future service, modifications, and system support.

Due to freedom of information laws allowing for public access to documents submitted to and retained by code officials, it could be necessary for secure documents to be reviewed by code officials at alternate locations. Such conditions should be identified by the stakeholders and discussed with the authorities having jurisdiction(s) in advance.

A.7.8.1.1 See Section 7.2 for the minimum documentation requirements.

A.7.8.2(1) Examples of completed record of completion forms are shown in Figure A.7.8.2(1)(a) through Figure A.7.8.2(1)(f).

In Figure 7.8.2(a), section 6, an example of a dual pathway is a circuit that is a continuous circuit connected to an FACU at two terminal locations, and an example of a separate pathway is a circuit that is only connected to the FACU at one terminal location.

A.7.8.2(2) Figure 7.8.2(g) through Figure 7.8.2(l) are sample forms intended to reflect the general information that should be provided as part of a system inspection and test report, but they are not intended to mandate a specific format for the report. A report format customized to the specific system configuration, devices, appliances, and system functions being tested meets the intent of the requirement.

In Figure 7.8.2(k), Section 2.1, an example of a single-voice-channel emergency communications system is a system that provides a single message or evacuation signal to multiple floors or areas at the same time. An example of a multiple-voice-channel emergency communications system is a system that can provide multiple messages or evacuation signals to multiple floors or areas at the same time.

A.10.3.1 Terms used by testing laboratories for equipment that is listed or labeled could include certified, approved, or listed.

In seismic hazard zones, the fire alarm designer should verify seismic certification requirements for control equipment with the AHJ.

A.10.3.3 This requirement does not apply to notification appliance circuits.

A.10.3.5(1) The requirement of 10.3.5(1) does not preclude transfer to secondary supply at less than 85 percent of nominal primary voltage, provided the requirements of 10.6.7 are met.

SYSTEM RECORD OF COMPLETION

*This form is to be completed by the system installation contractor at the time of system acceptance and approval.
It shall be permitted to modify this form as needed to provide a more complete and/or clear record.
Insert N/A in all unused lines.*

Attach additional sheets, data, or calculations as necessary to provide a complete record.

Form Completion Date: 2 November 2019 Supplemental Pages Attached: 0

1. PROPERTY INFORMATION

Name of property: World Storage and Transfer Headquarters
 Address: 27132 Santa Anita Boulevard, Hilo, HI
 Description of property: Business and Office Building
 Name of property representative: Joe Bago Donits
 Address: As above
 Phone: (743) 225-9768 Fax: (743) 225-9768 E-mail: jbago@WLS1.net

2. INSTALLATION, SERVICE, TESTING, AND MONITORING INFORMATION

Installation contractor: Sparkee's Electric
 Address: 1954 Nimitz Highway, Honolulu, HI 76542
 Phone: (978) 456-9876 Fax: (978) 456-9876 E-mail: shortcircuitguy@sparkee.net
 Service organization: None
 Address: _____
 Phone: _____ Fax: _____ E-mail: _____
 Testing organization: Jim's Protection, Inc.
 Address: 2300 Daly Boulevard, Austin, TX
 Phone: (407) 738-4587 Fax: (407) 738-4598 E-mail: testerjim@JPI.com
 Effective date for test and inspection contract: 25 January 2011
 Monitoring organization: Look the Other Way, Inc.
 Address: 995 Highway 35W, Minneapolis, MN
 Phone: (412) 456-9078 Fax: (412) 456-7272 E-mail: Look@otherway.com
 Account number: 56734598 Phone line 1: (212) 978-6576 Phone line 2: (212) 978-9978
 Means of transmission: IP
 Entity to which alarms are retransmitted: Honolulu FD Phone: (808) 455-5555

3. DOCUMENTATION

On-site location of the required record documents and site-specific software: Building Mgrs. Office Room 203

4. DESCRIPTION OF SYSTEM OR SERVICE

This is a: ☒ New system ☐ Modification to existing system Permit number: 11-907645
 NFPA 72 edition: 2019

4.1 Control Unit

Manufacturer: Halter Cabinet Model number: 1019-7647

4.2 Software and Firmware

Firmware revision number: 7.0 B Executive Rev 9.11

4.3 Alarm Verification

☒ This system does not incorporate alarm verification.

Number of devices subject to alarm verification: _____ Alarm verification set for _____ seconds

FIGURE A.7.8.2(1)(a) Example of Completed System Record of Completion.

SYSTEM RECORD OF COMPLETION (continued)**5. SYSTEM POWER****5.1 Control Unit****5.1.1 Primary Power**

Input voltage of control panel: 120 VAC Control panel amps: 7.3 Amps
 Overcurrent protection: Type: Breaker Amps: 20 Amps
 Branch circuit disconnecting means location: Breaker Panel — Room B-23 Number: 23

5.1.2 Secondary Power

Type of secondary power: Battery
 Location, if remote from the plant: Rear Yard
 Calculated capacity of secondary power to drive the system:
 In standby mode (hours): 24 In alarm mode (minutes): 15

5.2 Control Unit

- ☐ This system does not have power extender panels
☐ Power extender panels are listed on supplementary sheet A

6. CIRCUITS AND PATHWAYS

Pathway Type	Dual Pathway	Separate Pathway	Class	Survivability Level
Signaling Line		X	A	1
Device Power				
Initiating Device		X	B	1
Notification Appliance		X	B	1
Other (specify):				

7. REMOTE ANNUNCIATORS

Type	Location
Tabular	Front Lobby

8. INITIATING DEVICES

Type	Quantity	Addressable or Conventional	Alarm or Supervisory	Sensing Technology
Manual Pull Stations	12	Addressable	Alarm	
Smoke Detectors	8	Addressable	Alarm	Photoelectric
Duct Smoke Detectors				
Heat Detectors				
Gas Detectors	1	Conventional	Supervisory	
Carbon Monoxide Detectors				
Waterflow Switches	2	Conventional	Alarm	
Tamper Switches	4	Conventional	Supervisory	

FIGURE A.7.8.2(1)(a) Continued

SYSTEM RECORD OF COMPLETION (continued)**9. NOTIFICATION APPLIANCES**

Type	Quantity	Description	Connected to a Notification Appliance Circuit (NAC)	Connected to a Signaling Line Circuit (SLC)
Audible	18	Horns	✓	
Visual	24	Strobes	✓	
Combination Audible and Visual	6	Horns/Strobes	✓	

10. SYSTEM CONTROL FUNCTIONS

Type	Quantity
Hold-Open Door Releasing Devices	4
HVAC Shutdown	2
Fire/Smoke Dampers	
Door Unlocking	1
Elevator Recall	2
Elevator Shunt Trip	

11. INTERCONNECTED SYSTEMS

- ☐ This system does not have interconnected systems.
- ☐ Interconnected systems are listed on supplementary sheet _____.

12. CERTIFICATION AND APPROVALS**12.1 System Installation Contractor**

This system as specified herein has been installed according to all NFPA standards cited herein.

Signed: Harry Johnson Printed name: Harry Johnson Date: 11 November 2019
 Organization: Sparkee's Electric Title: Principal Phone: (987) 456-9876

12.2 System Operational Test

This system as specified herein has tested according to all NFPA standards cited herein.

Signed: Jim Riverbottom Printed name: Jim Riverbottom Date: 14 January 2011
 Organization: Jim's Protection, Inc. Title: President Phone: (407) 738-4583

12.3 Acceptance Test

Date and time of acceptance test: 0830 hrs. — 18 November 2019
 Installing contractor representative: Jim Johnson
 Testing contractor representative: Reginald O'Haraquest
 Property representative: Danny MacIntosh
 AHJ representative: Inspector DiDonato

FIGURE A.7.8.2(1)(a) Continued

EMERGENCY COMMUNICATIONS SYSTEMS SUPPLEMENTARY RECORD OF COMPLETION

This form is a supplement to the System Record of Completion. It includes systems and components specific to emergency communications systems.

This form is to be completed by the system installation contractor at the time of system acceptance and approval.

It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

Form Completion Date: 2 November 2019 Number of Supplemental Pages Attached: _____

1. PROPERTY INFORMATION

Name of property: World Storage and Transfer Headquarters

Address: 27132 Santa Anita Boulevard, Hilo, HI

2. DESCRIPTION OF SYSTEM OR SERVICE

☐ Fire alarm with in-building fire emergency voice alarm communication system (EVAC)

☐ Mass notification system

☒ Combination system, with the following components:

☐ Fire alarm ☐ EVACS ☒ MNS ☐ Two-way, in-building, emergency communications system

☐ Other (specify): _____

NFPA 72 edition: 2019 Additional description of system(s): _____

2.1 In-Building Fire Emergency Voice Alarm Communications System

Manufacturer: Halter Cabinet Model number: 1018-7648

Number of single voice alarm channels: 2 Number of multiple voice alarm channels: 0

Number of loudspeakers: 99 Number of loudspeaker circuits: 12

Location of amplification and sound processing equipment: Fire Control Room

Location of paging microphone stations:

Location 1: Fire Control Room

Location 2: Security Office

Location 3: _____

2.2 Mass Notification System

2.2.1 System Type:

☒ In-building MNS—combination

☐ In-building MNS ☐ Wide-area MNS ☐ Distributed recipient MNS

☐ Other (specify): _____

FIGURE A.7.8.2(1)(b) Example of Completed Emergency Communications System Supplementary Record of Completion.

EMERGENCY COMMUNICATIONS SYSTEMS SUPPLEMENTARY RECORD OF COMPLETION *(continued)*

2. DESCRIPTION OF SYSTEM OR SERVICE *(continued)*

2.2.2 System Features:

- ☒ Combination fire alarm/MNS ☐ MNS autonomous control unit ☐ Wide-area MNS to regional national alerting interface
☐ Local operating console (LOC) ☐ Distributed-recipient MNS (DRMNS) ☐ Wide-area MNS to DRMNS interface
☐ Wide-area MNS to high power loudspeaker array (HPLA) interface ☐ In-building MNS to wide-area MNS interface
☐ Other (specify): _____

2.2.3 MNS Local Operating Consoles

Location 1: Fire Control Room
 Location 2: Security Office
 Location 3: _____

2.2.4 High-Power Loudspeaker Arrays

Number of HPLA loudspeaker initiation zones: 0
 Location 1: _____
 Location 2: _____
 Location 3: _____

2.2.5 Mass Notification Devices

Combination fire alarm/MNS visual devices: 48 MNS-only visual devices: _____
 Textual signs: _____ Other (describe): _____
 Supervision class: _____

2.2.6 Special Hazard Notification

- ☒ This system does not have special suppression predischARGE notification.
☐ MNS systems DO NOT override notification appliances required to provide special suppression predischARGE notification.

3. TWO-WAY EMERGENCY COMMUNICATIONS SYSTEMS

3.1 Telephone System

Number of telephone jacks installed: 15 Number of warden stations installed: 3
 Number of telephone handsets stored on site: 6
 Type of telephone system installed: ☐ Electrically powered ☒ Sound powered

3.2 Area of Refuge Emergency Communications Systems

Number of stations: 0 Location of central control point: _____
 Days and hours when central control point is attended: _____
 Location of alternate control point: _____
 Days and hours when alternate control point is attended: _____

FIGURE A.7.8.2(1)(b) *Continued*

**EMERGENCY COMMUNICATIONS SYSTEMS
SUPPLEMENTARY RECORD OF COMPLETION (continued)**

3. TWO-WAY EMERGENCY COMMUNICATIONS SYSTEMS (continued)

3.3 Elevator Emergency Communications Systems

Number of elevators with stations: 2 Location of central control point: Fire Control Room

Days and hours when central control point is attended: 24

Location of alternate control point: None

Days and hours when alternate control point is attended: None

3.4 Other Two-Way Communications System

Describe: _____

4. CONTROL FUNCTIONS

This system actuates the following control functions specific to emergency communications systems:

Type	Quantity
Mass Notification Override of Alarm Signaling Systems or Appliances	1

See Main System Record of Completion for additional information, certifications, and approvals.

FIGURE A.7.8.2(1)(b) Continued

POWER SYSTEMS SUPPLEMENTARY RECORD OF COMPLETION

This form is a supplement to the System Record of Completion. It includes systems and components specific to power systems that incorporate generators, SEPSS systems, remote battery systems, or other complex power systems. This form is to be completed by the system installation contractor at the time of system acceptance and approval.

It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

Form Completion Date: 2 November 2019 Number of Supplemental Pages Attached: 0

1. PROPERTY INFORMATION

Name of property: World Storage and Transfer Headquarters

Address: 27132 Santa Anita Boulevard, Hilo, HI

2. SYSTEM POWER

2.1 Control Unit

2.1.1 Primary Power

Input voltage of control panel: 120 volt Control panel amps: 7.3

Overcurrent protection: Type: Circuit Breaker Amps: 20

Location (of primary supply panelboard): Main Electrical Room in Basement

Disconnecting means location: Panel E2 — Electric Room

2.1.2 Engine-Driven Generator

Location of generator: _____

Location of fuel storage: _____ Type of fuel: Diesel

2.1.3 Stored-Energy Emergency Power Supply Systems

Equipment powered by SEPSS system: None

Location of SEPSS system: _____

Calculated capacity of SEPSS batteries to drive the system components connected to it:

In standby mode (hours): _____ In alarm mode (minutes): _____

2.1.4 Batteries

Location: FACU Type: Gel Cell Nominal voltage: 24 Amp/hour rating: 16

Calculated capacity of batteries to drive the system:

In standby mode (hours): 24 In alarm mode (minutes): 15

2.2 In-Building Fire Emergency Voice Alarm Communications System or Mass Notification System

2.2.1 Primary Power

Input voltage of EVACS or MNS panel: 120 volt EVACS or MNS panel amps: 8.8

Overcurrent protection: Type: Circuit Breaker Amps: 20

Location (of primary supply panelboard): Main Electrical Room in Basement

Disconnecting means location: Panel E2 — Electric Room

FIGURE A.7.8.2(1)(c) Example of Completed Power Systems Supplementary Record of Completion.

POWER SYSTEMS SUPPLEMENTARY RECORD OF COMPLETION *(continued)*

2. SYSTEM POWER *(continued)*

2.2.2 Engine-Driven Generator

Location of generator: _____

Location of fuel storage: _____ Type of fuel: Diesel

2.2.3 Stored-Energy Emergency Power Supply Systems

Equipment powered by SEPSS system: None

Location of SEPSS system: N/A

Calculated capacity of SEPSS batteries to drive the system components connected to it:

In standby mode (hours): N/A In alarm mode (minutes): N/A

2.2.4 Batteries

Location: ECS Panel Type: Gel Cell Nominal voltage: 24 Amp/hour rating: 20

Calculated capacity of batteries to drive the system:

In standby mode (hours): 24 In alarm mode (minutes): 15

2.3 Notification Appliance Power Extender Panels

☐ This system does not have power extender panels.

2.3.1 Primary Power

Input voltage of power extender panel(s): 120 volt Power extender panel amps: 8

Overcurrent protection: Type: Circuit Breaker Amps: 20

Location (of primary supply panelboard): See Table

Disconnecting means location: _____

2.3.2 Engine Driven Generator

Location of generator: _____

Location of fuel storage: _____ Type of fuel: Diesel

2.3.3 Stored-Energy Emergency Power Supply Systems

Equipment powered by SEPSS system: None

Location of SEPSS system: _____

Calculated capacity of SEPSS batteries to drive the system components connected to it:

In standby mode (hours): _____ In alarm mode (minutes): _____

2.3.4 Batteries

Location: Power Panel Type: Gel Cell Nominal voltage: 24 Amp/hour rating: 12

Calculated capacity of batteries to drive the system:

In standby mode (hours): 24 In alarm mode (minutes): 15

See Main System Record of Completion for additional information, certifications, and approvals.

FIGURE A.7.8.2(1)(c) *Continued*

POWER SYSTEMS
SUPPLEMENTARY RECORD OF COMPLETION (continued)

2. SYSTEM POWER (continued)

2.4 Supervising Station Transmission Equipment

☒ This system does not use transmission equipment within the building powered by any other source than the alarm system control unit.

2.4.1 Primary Power

Input voltage of shared transmission equipment: 120 VAC

Shared transmission equipment panel amps: 73 amps

Overcurrent protection: Type: Breaker Amps: 20 amps

Location (of primary supply panelboard): Breaker Panel B-23

Disconnecting means location: Electric Room

2.4.2 Engine Driven Generator

Location of generator: _____

Location of fuel storage: _____ Type of fuel: _____

2.4.3 Stored-Energy Emergency Power Supply Systems

Equipment powered by SEPSS system: _____

Calculated capacity of SEPSS batteries to drive the system components connected to it:

In standby mode (hours): _____ In alarm mode (minutes): _____

2.4.4 Batteries

Location: FACU Type: Gel Nominal voltage: 12 Amp/hour rating: 16

Calculated capacity of batteries to drive the system:

In standby mode (hours): 24 In alarm mode (minutes): 15

See Main System Record of Completion for additional information, certifications, and approvals.

FIGURE A.7.8.2(1)(c) Continued

INTERCONNECTED SYSTEMS SUPPLEMENTARY RECORD OF COMPLETION

This form is a supplement to the System Record of Completion. It includes a list of types and locations of systems that are interconnected to the main system.

This form is to be completed by the system installation contractor at the time of system acceptance and approval.

It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

Form Completion Date: 2 November 2019 Number of Supplemental Pages Attached:

1. PROPERTY INFORMATION

Name of property: World Storage and Transfer Headquarters

Address: 27132 Santa Anita Boulevard, Hilo, HI

2. INTERCONNECTED SYSTEMS

Description	Location	Purpose
Fan Shutdown	Roof	Shut down fans on fire alarm activation
Elevator Recall	Elevator Room	Recall elevators in case of alarm on lobby smoke detectors

See Main System Record of Completion for additional information, certifications, and approvals.

FIGURE A.7.8.2(1)(e) Example of Completed Interconnected Systems Supplementary Record of Completion.

DEVIATIONS FROM ADOPTED CODES AND STANDARDS SUPPLEMENTARY RECORD OF COMPLETION

This form is a supplement to the System Record of Completion. It enables the designer and/or installer to document and justify deviations from accepted codes or standards.

This form is to be completed by the system installation contractor at the time of system acceptance and approval.

It shall be permitted to modify this form as needed to provide a more complete and/or clear record.

Insert N/A in all unused lines.

Form Completion Date: 2 November 2019

Number of Supplemental Pages Attached: _____

1. PROPERTY INFORMATION

Name of property: World Storage and Transfer Headquarters

Address: 27132 Santa Anita Boulevard, Hilo, HI

2. DEVIATIONS FROM ADOPTED CODES OR STANDARDS

Description	Purpose
Waterflow switch set to a 120-second trip	Issue has been identified that there are water surges during evening hours

See Main System Record of Completion for additional information, certifications, and approvals.

FIGURE A.7.8.2(1)(f) Example of Completed Deviations from Adopted Codes and Standards Supplementary Record of Completion.

A.10.4.1 Fire alarm specifications can include some or all of the following:

- (1) Address of the protected premises
- (2) Owner of the protected premises
- (3) Authority having jurisdiction
- (4) Applicable codes, standards, and other design criteria to which the system is required to comply
- (5) Type of building construction and occupancy
- (6) Fire department response point(s) and annunciator location(s)
- (7) Type of fire alarm system to be provided
- (8) Calculations (e.g., secondary supply and voltage drop calculations)
- (9) Type(s) of fire alarm initiating devices, supervisory alarm initiating devices, and evacuation notification appliances to be provided
- (10) Intended area(s) of coverage
- (11) Complete list of detection, signaling, and annunciator zones
- (12) Complete list of emergency control functions
- (13) Complete sequence of operations detailing all inputs and outputs

A.10.4.4 Switches and visible indicators referenced in 10.4.4 are those intended for use by the system owner and first responders. It is not the intent of the committee to require all control unit diagnostic indicators or configuration switches used by the installation/service personnel required to be installed within these limits. Control units that do not have such operator interface are not bound by this requirement; however, the installer should consider best practice for ease in serviceability.

A.10.4.5 The control units that are to be protected are those that provide notification of a fire to the occupants and responders. The term *control unit* does not include equipment such as annunciators and addressable devices. Requiring smoke detection at the transmitting equipment is intended to increase the probability that an alarm signal will be transmitted to a supervising station prior to that transmitting equipment being disabled due to the fire condition.

Where the area or room containing the control unit is provided with total smoke detection coverage, additional smoke detection is not required to protect the control unit. Where total smoke detection coverage is not provided, the Code intends that only one smoke detector is required at the control unit even when the area of the room would require more than one detector if installed according to the spacing rules in Chapter 17. The intent of selective coverage is to address the specific location of the equipment.

The location of the required detection should be in accordance with 17.7.4.2.1.

A.10.4.5.1 Subsection 10.4.5 permits the use of a heat detector if ambient conditions are not suitable for smoke detection. It is important to also evaluate whether the area is suitable for the control unit.

A.10.5.3 It is not the intent to require personnel performing simple inspections or operational tests of initiating devices to require factory training or special certification, provided such personnel can demonstrate knowledge in these areas.

A.10.5.3.1 The requirements for inspection personnel can vary depending on the type of inspection being performed.

The purpose for initial and reacceptance inspections is to ensure compliance with approved design documents and to ensure installation in accordance with this Code and other required installation standards. Therefore, the acceptance inspection should be performed by someone who is familiar with the specific requirements, the design documents, and the applicable codes and standards. This implies that acceptance inspections should be performed by the persons or entities responsible for the system design and by authorities having jurisdiction.

Once a system or a change to a system has been accepted, the inspection needs also change. The purpose for periodic inspections is to assure that obvious damages or changes that might affect the system operability are visually identified. Those persons performing periodic system inspections might or might not be familiar with all the specific system design goals and requirements. While many periodic inspections could uncover design faults, the intent of this Code is for such problems to be discovered at the acceptance inspection. The Code does not intend to require persons performing periodic inspections necessarily to be knowledgeable or qualified for inspecting and verifying the design of a system.

A.10.5.3.2 Testing personnel knowledge should include equipment selection, placement, and installation requirements of this Code and the manufacturer's published documentation.

A.10.5.3.4(1) Factory training and certification is intended to allow an individual to service equipment only for which he or she has specific brand and model training.

A.10.5.3.4(2) Nationally recognized fire alarm certification programs might include those programs offered by the International Municipal Signal Association (IMSA), National Institute for Certification in Engineering Technologies (NICET), and the Electronic Security Association (ESA). NOTE: These organizations and the products or services offered by them have not been independently verified by the NFPA, nor have the products or services been endorsed or certified by the NFPA or any of its technical committees.

A.10.5.3.4(3) Licenses and certifications offered at a state or local level are intended to recognize those individuals who have demonstrated a minimum level of technical competency in the area of fire alarm servicing.

A.10.5.3.5 This is not intended to require certification where it is not offered or required by the manufacturer.

A.10.5.5.1(2) An example of an organization providing alarm-monitoring-operator training is The Monitoring Association (TMA). Note that this reference is for informational purposes only, information concerning the product or service has been provided by the manufacturer or other outside sources, and the information concerning the product or service has not been independently verified nor has the product or service been endorsed or certified by the NFPA or any of its technical committees.

A.10.5.6.4.2(2) An example of an organization providing public emergency alarm reporting system certification is the International Municipal Signal Association. Note that this reference is for information purposes only. Information concerning the product or service has been provided by the manufacturer or other outside sources, and the information concerning the product or service has not been independently verified, nor

has the product or service been endorsed or certified by NFPA or any of its technical committees.

A.10.5.6.4.2(4) Factory training and certification are intended to allow individuals to service only the equipment for which they have specific brand and model training.

A.10.6.1 Exceptions exist in Chapter 23 for low-power wireless systems and in Chapter 29 for household low-power wireless systems and smoke alarms.

A.10.6.3.1 Paragraph 10.6.3.1 permits the use of an EPSS/SEPSS as the sole power source for a system. Using the EPSS/SEPSS option means that there is no primary and secondary supply. The EPSS/SEPSS serves both purposes, but from one supply point. Because of this, the risk of common mode failures should be considered because certain faults in the EPSS/SEPSS will leave the signaling system without any power.

A.10.6.4 Emergency power supply systems (EPSS) containing engine-driven generators are found in NFPA 110 and stored-energy emergency power supply systems (SEPSS) classifications are found in NFPA 111. Previous editions of *NFPA 72* referenced energy storage systems (ESS) and uninterruptible power supplies (UPS) systems. A UPS used for this purpose is an SEPSS. A UPS can also be included with an EPSS.

A.10.6.4.4 NFPA 855 provides requirements for mitigating the hazards associated with an SEPSS when the rated energy capacity of the SEPSS exceeds the values in NFPA 855, Section 1.3.

A.10.6.5.1.2 Multiple pieces of system equipment can be connected to a branch circuit, subject to the current capacity of the circuit. It is not intended that a branch circuit be limited to a single piece of equipment. It is not intended that the circuit supply power to other than system equipment. For example, a branch circuit could power both a fire alarm control unit and an NAC power supply, but it could not power both a fire alarm control unit and a sprinkler system air compressor.

A.10.6.5.2.2 The purpose of this requirement is to ensure that circuit disconnecting means for fire alarm and signaling systems are readily identifiable so that users will not mistakenly disconnect the power to the system or so that they can quickly disconnect power without having to search the electrical panel-board chart to identify the circuit. The intent of this requirement is not to require specific text for identification. Marking can include one of the following:

- (1) "FIRE ALARM" for fire alarm systems
- (2) "EMERGENCY COMMUNICATIONS" for emergency communications systems
- (3) "FIRE ALARM/EMERGENCY COMMUNICATIONS SYSTEM" for combination fire alarm and emergency communications systems
- (4) "CARBON MONOXIDE" for carbon monoxide detection systems

It would be acceptable to show the text using upper and/or lower case, such as "fire alarm," or "Fire Alarm," or "FIRE ALARM."

A.10.6.6 Where a computer system of any kind is used to receive and process alarm or supervisory signals, an EPSS/SEPSS, or a UPS listed to the requirements of an applicable standard such as UL 864, *Control Units and Accessories for Fire Alarm Systems*, with sufficient capacity to operate the system until the secondary supply is capable of operating the fire

alarm system might be required to prevent signal loss or a greater than 10-second signal delay.

EPSS/SEPSS equipment often contains an internal bypass arrangement to supply the load directly from the line. These internal bypass arrangements are a potential source of failure. EPSS/SEPSS equipment also requires periodic maintenance. It is, therefore, necessary to provide a means of promptly and safely bypassing and isolating the EPSS/SEPSS equipment from all power sources while maintaining continuity of power supply to the equipment normally supplied by the EPSS/SEPSS.

A.10.6.7.2 When a fire alarm system is used to alert occupants, the associated premises are generally evacuated during prolonged power outages. When this is not the case, as in emergency shelters or certain government facilities, additional secondary power should be required to address a more prolonged outage. These outages might be expected to result from weather or earthquake in locations subject to these events. Reasonable judgment should be employed when requiring additional secondary capacity.

When a fire alarm system is used to protect property, the associated premises might be vacant for prolonged periods (weekend, long holiday) or in very remote locations. When this is the case, and when the risk of loss is significant, additional secondary power should be required to address a more prolonged outage. These outages might be expected to result from weather or earthquake in locations subject to these events. Reasonable judgment should be employed when requiring additional secondary capacity.

A.10.6.7.2.14 Correction factors are intended to address normal aging and temperature effects on battery capacity. As a lead-acid battery ages, rated capacity will decrease to 80 percent, which is considered the end of service life. As a minimum, a correction factor of 1.25 should be applied for aging to ensure the battery can meet its current demand at the end of service life. At initial installation, lead-acid battery capacity can be as low as 90 percent and should gradually increase when it is subjected to several deep discharge/charging cycles or when it remains on float-charge for several weeks.

Battery calculations should include correction factors established for the battery technology to ensure that the required calculated amp-hour capacity remains available during the service life of the batteries and to compensate for changes in capacity where the batteries will be operated outside their nominal temperature range.

Temperature also affects lead-acid batteries. For additional information on lead-acid battery sizing considerations refer to IEEE 485, *Recommended Practice for Sizing Lead-Acid Batteries for Stationary Applications*.

Different battery technologies will require different correction factors.

A.10.6.7.2.15 For combination systems, such as a combination carbon monoxide and fire alarm system, where the carbon monoxide notification appliances are capable of being operated separately from the fire alarm system notification appliances, only the carbon monoxide notification appliances are required to operate for 12 hours.

A.10.6.7.3 The secondary power supply is not required to supply power to the fire alarm system through parallel distribution paths. Automatic transfer switches are commonly used to

allow secondary power to be supplied over the same distribution system as the primary power.

The generator does not need to be dedicated to the fire alarm system.

A.10.6.8.1 Examples include the following:

- (1) A building lighting power supply required for illumination in a required video image smoke detection means
- (2) A notification appliance circuit power supply located remotely
- (3) A power supply for transmitter required to transmit signals off premises
- (4) Power over ethernet (PoE), where provided for control units, circuit interfaces, or other equipment essential to system operation, and located remotely from the main control unit

A.10.6.9.2 Because digital alarm communicator systems establish communications channels between the protected premises and the central station via the public switched telephone network, the requirement to supervise circuits between the protected premises and the central station (*see* 12.6.1 and 12.6.2) is considered to be met if the communications channel is periodically tested in accordance with 26.6.4.2.5.

A.10.6.9.3 This requirement is intended to prevent all of the supervising station alarm systems in a given geographic area from transmitting simultaneous trouble signals (and overwhelming the associated supervising stations) in the event of a widespread power failure. A trouble signal is not intended to be transmitted if primary power is restored within the time delay.

A.10.6.10 The valve-regulated lead-acid (VRLA) battery type of rechargeable battery is currently used in protected premises applications.

This rechargeable-type battery is generally used in place of primary batteries in applications that have a relatively high current drain or that require the extended standby capability of much lower currents. The nominal voltage of a single starved electrolyte cell is 2 volts, and the battery is available in multiples of 2 volts (e.g., 2, 4, 6, 12). Batteries should be stored according to the battery manufacturer's published instructions. These batteries are often incorrectly referred to as "sealed lead-acid," "gel" or "maintenance-free batteries."

There are two technologies available. The most common type is referred to as "absorbed glass mat" or AGM. In this technology, the electrolyte is immobilized by being absorbed into fiberglass mats that surround the plates. Nearly all VRLA batteries in use in U.S. fire protection applications are AGM.

The second technology is referred to as gelled electrolyte. In this technology, the electrolyte is immobilized in a silica gel. This technology is predominately seen in European applications. While some manufacturers refer to the battery as a gel battery in the literature, this needs to be confirmed by the technician. Gel batteries require higher float voltages than AGM, and floating an AGM battery at gel voltages will shorten the battery life.

A.10.6.10.1.3 Examples of listing standards are UL 1989, *Standby Batteries*, and UL 2054, *Household and Commercial Batteries*.

A.10.6.10.3.4 The circuitry and methods for charging batteries of various types are to be evaluated by a nationally recognized testing laboratory to ensure they are appropriate for the purpose. During primary power use, batteries are trickle-charged if they are off-line and waiting to be put under load in the event of a loss of power.

Float-charged batteries are fully charged and connected across the output of the rectifiers to smooth the output and to serve as a standby source of power in the event of a loss of line power. Other charging methods are used to restore capacity to a battery after it has been utilized during a loss of primary power.

A.10.6.10.6 Manufacturers of fire alarm and emergency communications systems provide a means for supervising the battery charger's capability to properly charge the battery(ies). There typically is no means to test the battery charger for this trouble condition in the field.

A.10.7.3 Mass notification signals might, at times, be more important to the building or area occupants than the fire alarm signal. Stakeholders should perform a risk analysis in accordance with 24.3.12 to determine which, if any, messages should receive priority.

A.10.7.9 In addition, the override of circuits should be indicated at the control panel of each system to ensure signals are restored to normal.

A.10.10.4 Control unit signals can be audible, visual, or both for any particular function. Some older systems used only audible indicators that had to be coded for users to know what the signal meant. Where a control unit uses both audible and visual indicators, the purpose of the audible signal is to get someone's attention. In large system configurations, there might be multiple control units with audible signals. Also, there might be several different functions requiring an audible alert as a part of the whole signal. Thus, there could be several different audible signals. It is not the intent of this Code to have separate and distinct audible signals where clear visual distinction provides the user with the needed information. Visual signals, whether a lamp with a text label, an LCD screen, a computer monitor, or other textual visual appliances, are better forms of human interface.

A.10.10.5 A valve supervisory, a low-pressure switch, or another device intended to cause a supervisory signal when activated should not be connected in series with the end-of-line supervisory device of initiating device circuits, unless a distinctive signal, different from a trouble signal, is indicated.

A.10.11.1 Activation of an initiating device is usually the instant at which a complete digital signal is achieved at the device, such as a contact closure. For smoke detectors or other automatic initiating devices, which can involve signal processing and analysis of the signature of fire phenomena, activation means the instant when the signal analysis requirements are completed by the device or fire alarm control unit software.

A separate fire alarm control unit contemplates a network of fire alarm control units forming a single large system as defined in Section 23.8.

For some analog initiating devices, activation is the moment that the fire alarm control unit interprets that the signal from an initiating device has exceeded the alarm threshold programmed into the fire alarm control unit.

For smoke detectors working on a system with alarm verification, where the verification function is performed in the fire alarm control unit, the moment of activation of smoke detectors is sometimes determined by the fire alarm control unit.

It is not the intent of this paragraph to dictate the time frame for the local fire safety devices to complete their function, such as fan wind-down time, door closure time, or elevator travel time.

A.10.11.2 The intent of this requirement is to ensure that persons who are deaf or hard of hearing are alerted to seek additional information regarding an emergency situation. Persons who are deaf or hard of hearing are not always alerted by the loudspeakers that provide evacuation tones or voice instructions. It is intended that the loudspeakers and visual notification appliances located in the same area be activated together whenever tones, recorded voice instructions, or live voice instructions are being provided. (SIG-ECS)

A.10.11.4 The recommended coded signal designations for buildings that have four floors and multiple basements are provided in Table A.10.11.4.

A.10.11.6 Resetting of alarm signals should not require the simultaneous operation of multiple reset switches or the disconnection of any wiring or equipment to reset the alarm condition.

A.10.12 It is the intent that both visual and audible appliances are shut off when the notification appliance silence feature is activated on the fire alarm control unit.

Per the ADA, it is important not to provide conflicting signals for the hearing or visually impaired.

A.10.12.2 Where it is desired to deactivate the notification appliances for fire service operations inside the building and signal evacuated occupants that an alarm is still present, it is recommended that a separate non-silenceable notification zone be provided on the exterior of the building. The audible and visual notification appliances located at the building entrances could serve as a warning to prevent occupant re-entry.

A.10.15.9 The purpose of automatic trouble re-sound is to remind owners, or those responsible for the system, that the system remains in a fault condition. A secondary benefit is to possibly alert occupants of the building that the fire alarm system is in a fault condition.

A.10.15.10.7 In large, campus-style arrangements with proprietary supervising stations monitoring protected premises systems, and in other situations where off-premises monitoring achieves the desired result, the authority having jurisdiction is permitted to allow the reactivation to occur only at the supervising station. Approval by the authority having jurisdiction is

required so it can consider all fire safety issues and make a determination that there are procedures in place to ensure that the intent is met; in other words, someone is available to take action to correct the problem.

A.10.16.2 The operability of controlled mechanical equipment (e.g., smoke and fire dampers, elevator recall arrangements, and door holders) should be verified by periodic testing. Failure to test and properly maintain controlled mechanical equipment can result in operational failure during an emergency, with potential consequences up to and including loss of life.

A.10.18.1.2 The visible annunciation required by 10.18.1.2 must remain "on" even if other appliances are silenced, shut off, or disabled. Most often, a control unit will sound an audible signal and display a visual alert of an incoming signal. The audible signal is permitted to be deactivated, but the visual signal must remain active. Or, a system in a high-noise area might use high-power visual appliances for occupant alerting. Deactivating those signals, without resetting the system, is not permitted to deactivate the visual means required by 10.18.1.2.

A.10.18.3 The primary purpose of annunciation is to enable responding personnel to quickly and accurately determine the status of equipment or emergency control functions that might affect the safety of occupants.

A.10.18.5 Fire alarm system annunciation should, as a minimum, be sufficiently specific to identify a fire alarm signal in accordance with the following:

- (1) If a floor exceeds 22,500 ft² (2090 m²) in area, the floor should be subdivided into detection zones of 22,500 ft² (2090 m²) or less, consistent with the existing smoke and fire barriers on the floor.
- (2) If a floor exceeds 22,500 ft² (2090 m²) in area and is undivided by smoke or fire barriers, detection zoning should be determined on a case-by-case basis in consultation with the authority having jurisdiction.
- (3) Waterflow switches on sprinkler systems that serve multiple floors, areas exceeding 22,500 ft² (2090 m²), or areas inconsistent with the established detection system zoning should be annunciated individually.
- (4) In-duct smoke detectors on air-handling systems that serve multiple floors, areas exceeding 22,500 ft² (2090 m²), or areas inconsistent with the established detection system zoning should be annunciated individually.
- (5) If a floor area exceeds 22,500 ft² (2090 m²), additional zoning should be provided. The length of any zone should not exceed 300 ft (91 m) in any direction. If the building is provided with automatic sprinklers throughout, the area of the alarm zone should be permitted to coincide with the allowable area of the sprinkler zone.

A.10.18.6 *Emergency Services Interfaces.* Annunciators, information display systems, and controls for portions of a system provided for use by emergency service personnel should be designed, arranged, and located in accordance with the needs of the organizations intended to use the equipment.

A.10.19.1 Amplifiers generally require significant power regardless of load. To reduce the secondary power demand, there is no requirement to monitor the integrity of amplifiers during non-alarm operation on secondary power. This allows the amplifiers to be shut down while the system is operating on secondary power until an alarm occurs. When an alarm occurs,

Table A.10.11.4 Recommended Coded Signal Designations

Location	Coded Signal
Fourth floor	2-4
Third floor	2-3
Second floor	2-2
First floor	2-1
Basement	3-1
Sub-basement	3-2

monitoring of integrity must resume so that an operator is aware of current conditions and so that any backup amplifiers can be engaged.

Backup amplifying and evacuation signal-generating equipment is recommended with automatic transfer upon primary equipment failure to ensure prompt restoration of service in the event of equipment failure.

A.10.19.1.3 Manufacturers of fire alarm and emergency communications systems provide a means for supervising the tone-generating equipment capability to properly generate tones. There typically is no means to test the tone generator failure for this trouble condition in the field.

A.10.21 The term *impairments* encompasses a broad range of circumstances wherein a system or portion thereof is taken out of service for a variety of reasons. Systems are routinely impaired to allow hot work (e.g., open flame operations) to be performed in areas with automatic detection, construction, painting, and so forth, as well as to conduct normal system maintenance and testing. Impairments can be limited to specific initiating devices and/or functions (e.g., disconnecting the supervising station connection during system testing), or they can involve taking entire systems or portions of systems out of service. Section 10.21 is intended to help building owners control impairments of the system(s) in their building(s) and to ensure that systems are restored to full operation and/or returned to service afterward.

Additional requirements for impairments and out-of-service conditions are in 14.2.2.2.

A.10.21.4 It is important for the authority having jurisdiction, typically the local fire official, to be informed when systems have been out of service for more than 8 hours so that appropriate measures can be taken. The term *out of service* is meant to refer to the entire system or a substantial portion thereof.

A.10.21.5 The need for mitigating measures is typically determined on a case-by-case basis. This considers the building, occupancy type, nature and duration of impairment, building occupancy level during impairment period, active work being conducted on the fire alarm system during the impairment, condition of other fire protection systems and features (i.e., sprinklers, structural compartmentation, etc.), and hazards and assets at risk.

Appropriate mitigating measures range from simple occupant notification to full-time fire watch. Determining factors vary from testing-related impairments and maintenance activities during normal business through extensive impairments to high-value, high-hazard situations.

A.10.22 See 3.3.326 for the definitions of unwanted alarms.

A.11.1 Cybersecurity is not required for every system or application; it is only required when other sections of this Code, authorities, or regulations mandate that cybersecurity be incorporated into the system(s). Generally, there are greater cybersecurity concerns when systems are connected to external networks.

Cybersecurity recommendations are contained in Annex J.

A.12.2.1 In the 2007 edition of *NFPA 72*, initiating device circuit, signaling line circuit, and notification appliance circuit performance class/style tables were rooted in “copper” wiring methods. Fire alarm control units use new communications

technologies, such as Ethernet, fiber optics, and wireless, which do not fit in the “copper” wiring methods.

A.12.2.3.3 Fire alarm systems include fire detection and alarm notification, guard’s tour, sprinkler waterflow, and sprinkler supervisory systems. Circuits controlled and powered by the fire alarm system include circuits for the control of building systems safety functions, elevator capture, elevator shutdown, door release, smoke doors and damper control, fire doors and damper control, and fan shutdown, but only where these circuits are powered by and controlled by the fire alarm system. [70:760.1 Informational Note No. 1]

Class 1, 2, and 3 circuits are defined in Article 725 (of *NFPA 70*). [70:760.1 Informational Note No. 2]

A.12.2.3.4 It is important for the intended functionality of circuit integrity cable or electrical circuit protective systems to follow manufacturer’s installation instructions. An electrical circuit protective system has detailed installation requirements, and additional requirements can be found in the manufacturer’s installation instructions, *NFPA 70* or the listing organizations’ guide information.

A.12.2.3.5 In the event of an introduction of a fault and subsequent alarm condition, operational ability should be restored within 200 seconds, and the alarm condition received at the fire alarm control unit is to be within 10 seconds after the expiration of the 200 seconds. Any subsequent alarms initiated after the initial 200-second window should be actuated in accordance with 10.11.1.

A.12.2.4.3 Technologies that do not use metallic conductors (e.g., wireless or fiber optics) are not affected by ground connections.

A.12.3 The intent of the circuit designations is not to create a hierarchal ranking; rather it is to provide guidance on the levels of performance.

Users of the Chapter 12 designations should review whether there are other abnormal conditions not specified in Chapter 12 that the pathways need to annunciate and operate through for their application.

A.12.3.1 Fiber-optic or wireless pathways are examples of Class A circuitry not impaired by earth ground connection or short-circuits and therefore do not annunciate those conditions as a fault.

A.12.3.3 Class C is intended to describe technologies that supervise the communication pathway by polling or continuous communication “handshaking,” such as the following:

- (1) Fire alarm control unit or supervising station connections to a wired LAN, WAN, or Internet
- (2) Fire alarm control unit or supervising station connections to a wireless LAN, WAN, and Internet
- (3) Fire alarm control unit digital alarm communicator transmitter or supervising station digital alarm communicator receiver connections to the public switched telephone network

Individual pathway segments are not required to be monitored. Supervision is accomplished by end-to-end communications.

A.12.3.4 Class D is intended to describe pathways that are not supervised but have a fail-safe operation that performs the

intended function when the connection is lost. Examples of such pathways include the following:

- (1) Power to door holders where interruption of the power results in the door closing
- (2) Power to locking hardware that release upon an open circuit or fire alarm operation

A.12.3.5 Class E is intended to describe pathways that do not require supervision as described in Section 12.6.

A.12.3.6(1) The Class N pathway designation is added to specifically address the use of modern network infrastructure when used in fire alarm or signaling systems.

Class N networks can be specified for ancillary functions but are not required for supplemental reporting described in 23.12.4. [See Figure A.23.12.4.]

Ethernet network devices are addressable but with an important distinction from device addresses on a traditional SLC multi-drop loop. A device with an Ethernet address is, in most cases, a physical endpoint connected to a dedicated cable. Traditional SLC devices are all wired on the same communication line (in parallel), similar to an old party-line telephone system. By comparison, Ethernet's network switches direct each data packet to its intended recipient device like our modern phone systems.

Class N uses redundant paths as a means to compensate for Ethernet wiring that does not report a single connection to ground, a basic requirement of Class B. Thus, the physical separation of Class A and Class X, and equipment redundancy described in 12.3.7, is not inherently required of Class N. In other words, failure of a single switch is permitted to take down a Class N segment and is only required to report the loss of communication. Where redundant path segments are intended to have survivability similar to Class A or Class X, the physical separation requirements and overall equipment redundancy must be specified in addition to the Class N designation.

As a visual model, Class N could be likened to a redundant pathway backbone, allowed to have Class C branch paths to single endpoint devices. Therefore, every effort is made in this section to clearly distinguish the single endpoint device from the transport equipment required to have redundant paths.

Class N requires redundant, monitored pathway segments to and from a control unit(s) where any interruption in communications could potentially affect multiple endpoint devices. Typically, interconnected communications equipment such as Ethernet switches, wireless repeaters, or media converters are used in combination to create pathways. Chapter 12 describes the required behavior of Class N pathways. All equipment must meet the requirements of other chapters in *NFPA 72* (such as, but not limited to, requirements pertaining to secondary power supplies, equipment listings, and environment conditions).

Redundant pathways, isolated from ground, are actually common practice in robust Ethernet designs. Managed network switches commonly have specific uplink ports that are intended for load sharing and allow two parallel connections. For compliance with Class N, a trouble must be reported if either of these connections fails. [See Figure A.12.3.6(1)(a) and Figure A.12.3.6(1)(b).]

Class N pathways can use metallic conductor communications cable, such as a 100 ohm balanced twisted pair (e.g., Category 5E), including single-pair or multi-pair cable, or other

communications media, such as optical fiber cable or wireless transmission, or a combination of two or more such transport mediums.

Where a conductor-based media is used for Class N, the intention is not to monitor faults on individual conductors but rather to monitor the operational capability and performance of the pathway as a whole. Similar to Class C, end-to-end verification is used in Class N.

Primary and required redundant pathways are independently and continuously verified for their ability to support end-to-end communications to and from each endpoint device and its associated control equipment. Pathway segments that service more than one device must have at least one verified redundant pathway segment. Should any primary pathway segment fail, communication is supported by the redundant pathway segment(s). Failure of either a primary or redundant pathway will indicate a trouble.

Redundant pathway segments are generally independent and do not normally share media with the primary pathways. However, there are exceptions, such as different frequencies for wireless components or ring topologies. [See Figure A.12.3.6(5).]

A Class N network can be made more reliable with physically distinct pathway segments (i.e., an alternate conduit, or cable tray route, or wireless transmission frequency range, or a combination of distinct media). In addition to the required primary segments and redundant segments, a Class N pathway is permitted to have nonrequired segments. [See Figure A.12.3.6(1)(c).] Additional nonrequired pathway segments are allowed to be connected and not independently monitored for integrity as long as two paths are monitored to meet the redundancy requirement of Class N.

Traditionally, NFPA has used the word *device* for input components and the term *appliance* for components used in notification. With respect to Class N, the term *device* includes appliances and other intelligent, addressable components that perform a programmable input or output function. Examples of Class N devices include the following:

- (1) Input components such as alarm initiating modules switches and sensors
- (2) Output components such as output modules, Ethernet loudspeakers (i.e., IEEE 802.3 PoE loudspeakers), intelligent visual notification appliances (strobes), textual signage, and intelligent audio amplifiers

Transmission equipment components (e.g., media converters, Ethernet switches, patch panels, cross-connects) are connected to the Class N pathway merely to transport instructions between other equipment. As such, they are not considered devices with respect to Class N pathways.

The audio amplifier listed above is an example of an addressable device that can receive a digital audio input from the Class N pathway and then provide a notification appliance circuit (NAC) output with Class A, B, or X pathways. Other endpoint devices can similarly provide alternate class pathways for visual notification appliances (strobes) (NACs) or initiating devices (IDCs). From the perspective of the Class N pathway, communications terminate at this endpoint device. However, since these types of endpoints can support multiple notification appliance devices or initiating devices, path segments are subject to the redundant pathway requirement unless protec-

ted in an enclosure or raceway less than 20 ft (6 m) in length. (See 12.6.9.) [See Figure A.12.3.6(1)(c).]

Class N connections between control equipment are required to have redundant monitored pathway segments if a failure of a primary pathway segment in between control equipment could impair the operation of the control equipment. [See Figure A.12.3.6(1)(d).]

Class N is also permitted to include dual port devices that provide both transmission and input/output functions. Endpoint devices can have multiple connection ports and support dual pathway segment connections; thus the term *endpoint device* is not intended to prohibit more than one connection to a device. Even with dual connections, where other devices depend on the path, primary and redundant paths are required. But, where an endpoint device has two connection ports, and when a secondary nonrequired connection is added, there is no requirement to separately supervise the nonrequired redundant pathway segment. [See Figure A.12.3.6(1)(e).]

A.12.3.6(4) Operational conditions of the pathway include factors such as latency, throughput, response time, arrival rate, utilization, bandwidth, and loss. Life safety equipment connected to a Class N network actively monitors some or all of the pathway's operational conditions so that an improperly installed or configured pathway or a subsequently degraded pathway or segment is detected by the life safety equipment and repor-

ted as a trouble. The trouble condition is reported when operational conditions of the pathway(s) have deteriorated to the point where the equipment is no longer capable of meeting its minimum performance requirements, even if some level of communication to devices is still maintained. Performance requirements include the activation of an alarm within 10 seconds, the reporting of a trouble signal within 200 seconds, and delivery of audio messages with required intelligibility. End-to-end communications might be operational under system idle conditions, but in the event of an alarm, the increased load on a degraded pathway could cause a partial or complete failure to deliver required life safety signals. Such predictable failure must be actively detected and reported.

A.12.3.6(5) Devices with dual path connections are permitted to be connected in a daisy-chain of devices on a ring. Again, where Class N pathway segments support multiple devices, verified redundant pathway segment(s) are required. This can be accomplished with a ring topology, as long as each segment of the ring is verified as functional, and the failure of any one segment does not result in the loss of functionality of more than one device. In this arrangement, primary and redundant pathway segments share the same media, and provide two possible directions of communications in a ring topology [see Figure A.12.3.6(5)]. This daisy-chain configuration is also permitted between multiple control units that require verified primary and redundant pathway segments.




FIGURE A.12.3.6(1)(a) Class N Pathway Block Diagram – Example 1.




FIGURE A.12.3.6(1)(b) Class N Pathway Block Diagram – Example 2.




FIGURE A.12.3.6(1)(c) Class N Pathway to Endpoint with Multiple Devices.

A.12.3.8 A goal of 12.3.8 is to provide adequate separation between the outgoing and return cables. This separation is required to help ensure protection of the cables from physical damage. The recommended minimum separation to prevent physical damage is 12 in. (300 mm) where the cable is installed vertically and 48 in. (1.22 m) where the cable is installed horizontally.

Examples of physical pathways could include metallic conductors and optical fiber cables.

A.12.3.8.1(3) This exception would not permit an entire room of emergency control function interface devices controlled by the fire alarm system to be installed on a circuit where the feed and return legs are installed in the same raceway for rooms smaller than 1000 ft² (93 m²) in area.

Where a circuit enters a room that contains emergency control function interface devices (e.g., control modules/relays connected to and programmed to shut down HVAC units and other fire and life safety control functions), loss of both “legs” of this circuit could disable important fire and life safety control functions that might be essential for prevention of circulation of smoke or another required operation, such as elevator recall functions.

A.12.4 The intent of the pathway survivability designation is to provide options for the protection of the pathway circuits as shown in Table A.12.4 and not to create a hierarchical ranking. Other chapters within *NFPA 72* or other code-making jurisdictions can select the survivability option that best meets their needs.

A.12.4.3 Methods of survivability protection might alternate within a protected premises. For example, 2-hour fire-resistive cable might extend from a 2-hour fire-resistance-rated enclosure.

Fire alarm system notification appliances, control modules, jacks, and initiating devices are not capable of resisting attack by fire. Connecting these devices to circuits that require survivability and span multiple zones or floors will result in a circuit that is no longer survivable. For example, two-way, in-building communications system (fire fighter’s telephone) jacks that are






FIGURE A.12.3.6(1)(d) Class N Pathway Block Diagram with Multiple Control Units.



A nonrequired redundant cable to an endpoint device is permitted and does not require separate supervision.

FIGURE A.12.3.6(1)(e) Class N Pathway Block Diagram with Device with Dual Pathway Connection.

connected to a circuit serving multiple floors could be shorted by the fire. It is recommended that a Level 2 or Level 3 survivable circuit serving multiple zones or floors be installed as Class X or Class N or those circuits be designed to serve a single fire zone.



Communications continue from either direction in a ring topology.

FIGURE A.12.3.6(5) Class N Pathway Block Diagram with Daisy-Chained Devices with Dual Pathway Connection.

A.12.4.3(4) A performance-based alternative is needed because it is possible to construct a nonsprinklered, Type V(000) building that employs relocation or partial evacuation (e.g., a single-story ambulatory health care occupancy) that would not warrant either a 2-hour fire-resistive-rated enclosure or a 2-hour cable. Examples of performance alternatives that might be considered in a design for survivability are a strategic application of Class A, Class X, or Class N segments and also wireless communications pathways.

A.12.4.4 See A.12.4.3.

A.12.4.4(4) A performance-based alternative is needed because it is possible to construct a sprinklered single-story Type V(111) or multistory Type II(111) building that employs relocation or partial evacuation (e.g., a health care occupancy) that would not warrant either a 2-hour fire-resistive-rated enclosure or a 2-hour cable (a 1-hour enclosure would suffice). Examples of performance alternatives that might be considered in a design for survivability are a strategic application of Class A, Class X, or Class N segments and also wireless communications pathways.

A.12.4.5 As identified in A.12.4 and Table A.12.4, pathways are not ranked in a hierarchy of protection. As such, a Level 4 is not intended to be better than a Level 1. Rather, each provides a separate means of achieving an acceptable level of protection based on system performance and construction. Nonsprinklered buildings having less than 2-hour construction – such as a single-story nursing facility – might incorporate partial evacuation or relocation of occupants upon fire alarm signal activation. The provisions of a pathway survivability Level 4 might be appropriate for the fire alarm or signaling system installed in such facility. Figure A.24.3.14.4.6.3 provides examples of how a user might use various options within a multistory building to achieve an intended level of protection. These provisions might include 1-hour separations, separation by $\frac{1}{2}$ diagonal of the area, Class N or Class X pathways, fire-rated enclosures, or other means of protection. Additional explanatory material related to pathway survivability use is provided in A.24.3.14.4.2 through A.24.3.14.4.4, A.24.3.14.4.6.1 through A.24.3.14.4.6.4, A.24.3.14.9, and A.24.3.14.12.1.

A.12.5 Shared pathway designations propose a list of shared pathways, some of which are only allowable for nonrequired functions. Other sections of this Code determine which of the shared pathways are allowed to be used as paths for required fire alarm signaling. Refer to 23.8.2.6 for shared communications requirements.

A.12.5.1 In a Shared Pathway Level 0, common equipment can be used to establish life safety and non-life safety pathways.

A.12.5.2 In a Shared Pathway Level 1, common equipment can be used to establish life safety and non-life safety pathways.

A.12.5.3 In a Shared Pathway Level 2, common equipment can be used to establish life safety and non-life safety pathways.

A.12.5.4 In a Shared Pathway Level 3, life safety equipment is not shared with equipment of non-life safety systems.

A.12.6 The provision of a double loop or other multiple path conductor or circuit to avoid electrical monitoring is not acceptable.

A.12.6.8 This Code does not have jurisdiction over the monitoring integrity of conductors within equipment, devices, or appliances.

A.12.7 The nomenclature described in Section 12.7 can be found on drawings, specifications, and the actual installed circuits. Some examples of the nomenclature are X.2.3, A, B.3.

A.14.2.1.1 Initial and re-acceptance inspections are performed to ensure compliance with approved design documents whatever the quality or origin. This involves inspection to ensure that the correct equipment has been used and properly located and installed. Ensuring compliance helps to assure both operational reliability and mission reliability. This concept applies to any type of system, not just fire alarm or signaling systems. At this stage of a system's life, the responsibilities for such inspections rest with the designers of the systems and with the various applicable authorities having jurisdiction.

A.14.2.1.2 If a system is designed to meet a specific mission or set of goals, then operational testing will assure that the system has mission reliability. For example, during acceptance testing, the design ambient noise level might not be present. Authorities having jurisdiction and technicians should not be trying to achieve the +5/15 dB or +5/10 dB requirements at acceptance, as they might not know what the maximum average or peak noise levels are. They need only measure the system and determine if it meets the required design level. Therefore, the design level needs to be documented and communicated to them.

Acceptance and re-acceptance testing includes proper operation, and non-operation, of the fire alarm or signaling system's ability to properly interface to other systems. The best way to ensure a proper interface operation is to observe the actual operation of the interfaced system. However, exercising an emergency control function every time a related initiating device is actuated might not be desirable or practical, or in some cases might not be permitted. *NFPA 72* permits testing of the fire alarm or signaling system up to the end point connection to the interfaced system or emergency control function. Refer to A.14.4.3.2 Table 14.4.3.2 Item 24.

A.14.2.1.3 Visual inspections contribute to the assurance of operational and mission reliability but do not ensure either.

Table A.12.4 Performance Criteria Options for Pathway Survivability Levels

Required Performance Criteria	Pathway Survivability				
	Level 0 (12.4.1)	Level 1 (12.4.2)	Level 2 (12.4.3)	Level 3 (12.4.4)	Level 4 (12.4.5)
Per 12.2.3.3 and Section 12.4 of this Code, all pathways must comply with <i>NFPA 70</i> applicable requirements.	YES	YES	YES	YES	YES
Wiring methods permitted are installed in accordance with manufacturer's published instructions (12.2.3.3).	YES	YES	YES	YES	YES
Building is fully protected by an automatic sprinkler system in accordance with <i>NFPA 13</i> .	—	YES	—	YES	—
Any interconnecting conductors, cables, or other physical pathways are protected by metal raceways or metal armored cables.	—	YES	—	—	—
<i>One or more of the following are required:</i>					
(1) 1-hour fire-rated circuit integrity (CI) or fire-resistive cable					
(2) 1-hour fire-rated cable system [electrical circuit protective system(s)]	—	—	—	—	YES
(3) 1-hour fire-rated enclosure or protected area					
(4) Performance alternative approved by the AHJ					
<i>One or more of the following are required:</i>					
(1) 2-hour fire-rated circuit integrity (CI) or fire-resistive cable					
(2) 2-hour fire-rated cable system [electrical circuit protective system(s)]	—	—	YES	YES	—
(3) 2-hour fire-rated enclosure or protected area					
(4) Performance alternative approved by the AHJ					

A.14.2.1.4 Periodic testing of fire alarm and signaling systems is not necessarily done as a complete system test. *NFPA 72* requires parts of the systems to be tested at different frequencies. At any one particular test, only a fraction of the system can be tested. Periodic testing contributes to the assurance of operational and mission reliability but does not ensure either.

Periodic testing of the interface between a fire alarm or signaling system in some other system or emergency control function is permitted by *NFPA 72* to be performed without actually operating the interfaced system or function. Refer to A.14.4.3.2 Table 14.4.3.2 Item 24.

A.14.2.2.1.2 Testing should be performed in such a way that testing personnel can promptly respond to signals as they are initiated during testing and can ensure that devices are reporting with the correct locations and addresses, programming errors are not overlooked, ground faults are acknowledged promptly, and fire and trouble/supervisory signals are responded to immediately when signals are not related to the testing taking place.

A.14.2.3.1 See definition of *Ownership* in 3.3.203.

A.14.2.3.6 Service personnel should be able to do the following:

- (1) Understand the requirements contained in *NFPA 72* and the fire alarm requirements contained in *NFPA 70*
- (2) Understand basic job site safety laws and requirements
- (3) Apply troubleshooting techniques, and determine the cause of fire alarm system trouble conditions
- (4) Understand equipment specific requirements, such as programming, application, and compatibility
- (5) Read and interpret fire alarm system design documentation and manufacturer's inspection, testing, and maintenance guidelines
- (6) Properly use tools and test equipment required for testing and maintenance of fire alarm systems and their components
- (7) Properly apply the test methods required by *NFPA 72*

A.14.2.4 Prior to any scheduled inspection or testing, the service company should consult with the building or system owner or the owner's designated representative. Issues of advance notification in certain occupancies, including advance notification time, building posting, systems interruption and restoration, evacuation procedures, accommodation for evacuees, and other related issues, should be agreed upon by all parties prior to any inspection or testing.

A.14.2.7.1 As an example, testing of the elevator fire service and shutdown functions will usually require a coordinated multi-discipline effort with presence of qualified service personnel for the fire alarm system, the elevator system, and other building systems. The presence of inspection authorities might also be needed in some jurisdictions. The development of a test plan should be considered to ensure that the testing of these features is accomplished in a coordinated and timely manner. This plan should also ensure that all appropriate parties and personnel are present when needed, and that the testing requirements for both the fire alarm system and the elevator system are fulfilled. See Section 21.3 and Section 21.4 for specific elevator emergency control functions.

A.14.2.9 This section provides the option to adopt a performance-based inspection and testing method as an alternate means of compliance for Sections 14.3 and 14.4. The

prescriptive test and requirements contained in this Code are essentially qualitative. Equivalent or superior levels of performance can be demonstrated through quantitative performance-based analyses. This section provides a basis for implementing and monitoring a performance-based program acceptable under this option (provided that approval is obtained by the authority having jurisdiction). The concept of a performance-based inspection and testing program is to establish the requirements and frequencies at which inspection and testing must be performed to demonstrate an acceptable level of operational reliability. The goal is to balance the inspection and testing frequency with proven reliability of the system or component. The goal of a performance-based inspection program is also to adjust inspection and testing frequencies commensurate with historical documented equipment performance and desired reliability. Frequencies of inspection and testing under a performance-based program might be extended or reduced from the prescriptive inspection and testing requirements contained in this Code when continued inspection and testing has been documented indicating a higher or lower degree of reliability as compared to the authority having jurisdiction's expectations of performance. Additional program attributes should be considered when adjusting inspection and testing.

A fundamental requirement of a performance-based program is the continual monitoring of fire system/component failure rates and determining if they exceed the maximum allowable failure rates as agreed upon with the authority having jurisdiction. The process used to complete this review should be documented and be repeatable. Coupled with this ongoing review is a requirement for a formalized method of increasing or decreasing the frequency of inspection and testing when systems exhibit either a higher than expected failure rate or an increase in reliability as a result of a decrease in failures. A formal process for reviewing the failure rates and increasing or decreasing the frequency of inspection and testing must be well documented. Concurrence from the authority having jurisdiction on the process used to determine test frequencies should be obtained in advance of any alterations to the inspection and testing program. The frequency required for future inspections and tests might be reduced to the next inspection frequency and maintained there for a period equaling the initial data review or until the ongoing review indicates that the failure rate is no longer being exceeded — for example, going from an annual to a semiannual testing when the failure rate exceeds the authority having jurisdiction's expectations, or from annual to every 18 months when the failure trend indicates an increase in reliability.

See also *NFPA 551* for additional guidance.

A.14.2.10 The test plan is intended to clarify exactly what is to be tested and how it is to be tested. Testing of fire alarm and signaling systems is often done in a segmented fashion to accommodate the availability of testing or other personnel or to minimize the interruption of building operations. Where a building owner has contracted the performance of inspection, testing, and maintenance activities to outside entities, the test plan, what will and will not be tested, should be reviewed by those parties. Building operations can be affected by testing of the fire alarm or signaling system itself and by the operation of emergency control functions actuated by the fire alarm or signaling system. The boundary of the fire alarm or signaling system extends up to and includes the emergency control function interface device. The testing requirements prescribed in

NFPA 72 for fire alarm and signaling systems end at the emergency control function interface device. The purpose of the test plan is to document what devices will and will not actually be tested.

The testing of emergency control functions, releasing systems, or interfaced equipment is outside the scope of NFPA 72. Requirements for testing other systems are found in other governing laws, codes, or standards. Requirements for integrated testing of combined systems also fall under the authority of other governing laws, codes, standards, or authority having jurisdiction. NFPA 3 provides guidance for such testing. NFPA 3 recognizes the importance of the development of an integrated testing plan.

Further information on testing associated with emergency control functions can be found in Table 14.4.3.2, Item 24 and its related annex material in A.14.4.3.2.

A.14.3.1 Equipment performance can be affected by building modifications, occupancy changes, changes in environmental conditions, device location, physical obstructions, device orientation, physical damage, improper installation, degree of cleanliness, or other obvious problems that might not be indicated through electrical supervision.

The intent of 14.3.1 is to prevent an inspection being made at intervals exceeding those allowed by Table 14.3.1. Annual inspections should be made every 12 months; monthly inspections should be made every 30 days, and so forth. For example, it is not acceptable to conduct an annual inspection in January of year one, and December of year two (23 month frequency) just because Table 14.3.1 requires an inspection once each year.

A.14.3.2 In addition to safety considerations, other reasons for delaying fire alarm inspections include nationally or regionally declared disasters, such as pandemics, weather-related emergencies, or other governmentally recognized disruptions.

A.14.4.2 Reacceptance testing is performed to verify the proper operation of added or replaced devices, appliances, emergency control function devices, control units, and so forth. It is not the intent of the committee to unduly burden the system owner with increased costs for repeated testing of devices not directly affected by the replacement of devices with like devices.

For example, if a 2 amp fuse is replaced with another 2 amp fuse in the fire alarm control unit, verification of the circuit(s) served by the fused supply is required, but it would not be necessary to test 10 percent of initiating devices not directly affected by replacing the fuse. Likewise, it is not necessary to test all these initiating devices whenever a smoke detector is replaced with a like smoke detector.

When wiring changes are made to correct improperly supervised circuits, a test of the affected device or appliance is required, but not a test of 10 percent of initiating devices not directly affected.

A.14.4.3 Fire alarm system testing can be conducted using silent testing and the bypassing of emergency control functions. All input signals should be verified according to the system matrix of operation to ensure they create the appropriate outputs. Tests of audible notification appliances and emergency control functions should be conducted at the conclusion of satisfactory tests of all inputs.

The intent is to reduce the amount of time spent causing audible and visual occupant notification during tests in an occupied building. This reduction will help reduce the negative (cry wolf) impact on occupants caused by excessive operation of notification appliances. System printouts or history logs are an effective way of verifying the correct receipt of signals. However, many outputs such as occupant notification and emergency control functions are tested for correct operation, because logs do not necessarily verify operation of the system output. Operation of audible and visual notification appliances could be accomplished in a lump sum fashion after all inputs are proven correct by silent testing. All inputs tested in this manner must be proved to cause the appropriate signal by verifying alarm receipt at the controls as each device is actuated. Manufacturer-specific protocols such as "walk test" or "alarm bypass" are an acceptable means of testing under this section. Other methods of mitigating the negative impact include off-hours tests when the building is not occupied.

A.14.4.3.1 If the authority having jurisdiction strongly suspects significant deterioration or otherwise improper operation by a central station, a surprise inspection to test the operation of the central station should be made, but extreme caution should be exercised. This test is to be conducted without advising the central station. However, the communications center must be contacted when manual alarms, waterflow alarms, or automatic fire detection systems are tested so that the fire department will not respond. In addition, persons normally receiving calls for supervisory alarms should be notified when items such as gate valves and functions such as pump power are tested. Confirmation of the authenticity of the test procedure should be obtained and should be a matter for resolution between plant management and the central station.

A.14.4.3.2 Table 14.4.3.2 Item 9(4). Ohmic testing is a means to determine the state of health of a VRLA battery's cells by measuring some form of a cell's internal resistance. Typically, ohmic testing equipment uses one of three techniques — conductance, impedance, or resistance — to make these measurements.

In simplest technical terms, ohmic technology is based on Ohm's law, which expresses the relationship between volts, amperes, and ohms in an electrical circuit. Ohmic testing attempts to use voltage and current to determine the resistive characteristic of a battery's cells. As the cells in a battery age and start to lose capacity, the internal components of the battery are undergoing a degradation process. The degradation of these components (plates, grids, internal connection straps) within the battery's cells causes an increased resistance in the conduction paths of the cell, which in turn causes a change in the internal ohmic values. A measured increase in impedance or resistance, or a decrease in conductance, indicates the battery is losing its ability to produce the energy it was designed to deliver when called upon to support the connected loads.

The key to effective application of ohmic testing is the appropriate trending of test results over time compared to a baseline or reference value. Studies have demonstrated that an individual battery produces a unique ohmic "signature" and the use of ohmic testing equipment to trend changes in this signature from installation through the life of the battery is the most effective use of the technology. A program that involves ohmic testing on a regular interval to note changes in the battery is a good maintenance practice.

An ohmic baseline reference value is a benchmark value based on data collected from known good batteries. Reference values can be determined from site-specific measurement, or from testing a sample of new healthy batteries, or by using a generic baseline value to get started.

- (1) The best baseline is one established on the installed battery within three to six months after installation and trend accordingly using good record keeping. Ideally the individual ohmic value should be measured at installation and again after the battery has been on float charge for at least 72 hours in order for it to reach a high state of stabilization. These initial "site-specific" values should be recorded and permanently affixed to the battery as a baseline for subsequent tests over the life of the battery. The ohmic value will typically increase for conductance and decrease for resistance and impedance between the initial installation and after being on float-charge for 90 to 180 days (10 percent to 15 percent depending on battery type and size). Six months after installation measure and compare the ohmic readings to the readings taken at installation. Use whichever value is greater for conductance or lower for resistance and impedance as the baseline for that particular battery at that site going forward.
- (2) A sample of new healthy batteries in a fully charged state can be tested to obtain a baseline value representative of a new battery. A sample size of at least 30 batteries from one manufacturer with the same make, model, amp-hour rating, age (within 6 months), and manufacturing lot is recommended. Record the following information for the batteries:
 - (a) Battery manufacturer
 - (b) Model number
 - (c) Date of manufacture
 - (d) Manufacturing lot number (if available)
 - (e) Battery temperature
 - (f) Whether or not the battery has had a freshening charge
 - (g) Battery voltage
 - (h) Ohmic test value

Calculate the average ohmic value of the batteries. Do not include batteries that deviate more than 30 percent from the average because they could be outside of an acceptable range. Use the average value as a baseline starting point for this model battery.

- (3) A generic baseline value for a specific battery model can often be found by contacting the ohmic test equipment manufacturer or from the battery manufacturer. While it is important to note that the use of generic reference values might not be as accurate, it is still possible to identify grossly failed batteries and significant changes in battery condition by applying this method. Generic baseline values are typical averages to be used as general guidelines and should only be used when no other data is available. When testing older batteries for which no initial site-specific ohmic value is available, reference values can be obtained in the following ways:
 - (a) Contact the equipment or battery manufacturer for assistance.
 - (b) Consult your company documentation to see if reference values were created for the battery you are testing.

- (c) Using ohmic readings of recently installed batteries of the same manufacturer and model of the battery, manufacturer and model of the alarm panel/system, charging circuit, and temperature at time of measurements, calculate the average ohmic value of the best 8 to 10 batteries and use this value as a baseline reference.

As a battery ages and loses capacity, the internal ohmic values change. Although the change might not be perfectly consistent over all battery models and sizes, experience and extensive test data shows that a deviation of ohmic values from the established baseline by 30 percent or more for conductance and 40 percent or more for resistance or impedance indicates that the actual battery capacity has dropped to 80 percent or lower. (For lead-acid batteries, capacity drops off rapidly once the 80 percent capacity point is reached in the lifetime curve, so this is known as the "knee" of the capacity vs. lifetime curve). This 80 percent capacity is the level at which battery manufacturers recommend battery replacement. Figure A.14.4.3.2 illustrates an ohmic trend of a 5-year design life battery with an actual expected service life of 3 years. Note that while battery Unit #1 still has good ohmic readings, semiannual measurements show Unit #2 failing prematurely. For this case, it is desirable to replace both units at the same time. If one unit fails at 2½ years, it is likely the second unit will fail in one of the next semiannual tests. Full replacement ensures that all units will "float" together. One exception might be when a unit fails in the first year.

Ohmic testing can be a safe, simple, accurate, and reliable means of determining the state of health of VRLA batteries. It is important however to understand the following basic guidelines in order to maximize the benefits and avoid possible misleading test results:

- (1) Follow safety regulations: wear eye protection and remove metal jewelry, and so forth prior to working with batteries.
- (2) Conduct a visual inspection prior to testing. A cracked case, leaking terminal or post, or bulging battery should be replaced, not tested.
- (3) Temperature changes affect measured ohmic values and battery capacity. Ohmic measurements should be taken at 77°F (25°C) ±13°F (7°C).
- (4) For maximum accuracy and consistency, batteries should be tested when in a fully charged state.
- (5) Check the battery charging current prior to test. The charging current should be stable and be within the normal float current recommendations of the battery manufacturer for the battery model. If it is not, it is likely that the batteries have recently been discharged and a test is not appropriate until this float current stabilizes.
- (6) Whenever possible, ohmic readings should be taken each time with the same instrument, but as a minimum with the same model. Changing models will skew the data and require re-establishing the baseline.
- (7) When test equipment is provided with an alert, set the ohmic baseline and/or thresholds prior to beginning the test to provide an indication of any deviations from baseline.
- (8) It is essential to take ohmic measurements at the battery terminal or post. For consistency and accuracy, subse-

quent tests should always have probes or clamps placed at the same point while avoiding battery hardware such as bolt heads or washers. Connecting on the hardware will influence the readings and could cause replacement of a healthy battery.

- (9) Maintain good contact at the test point for the duration of the test. If the probe or clamp slips off during the test, an incorrect reading will result.
- (10) For batteries with fully insulated quick disconnect connectors, the battery should be taken offline by removing the quick disconnects from the battery terminals and then measuring and recording the internal ohmic value of the battery.
- (11) Do not condemn a battery based upon results of a single test without any trending data or an established baseline for that specific battery.
- (12) When one or more units in a battery falls outside the acceptable range from baseline, replace the entire string.
- (13) While testing online is the preferred method, it should be noted that the capability of ohmic meters varies. As such, the test equipment manufacturer might provide instructions to disconnect the battery and test offline. A battery tested online can display a different value than when tested offline due to the charger circuit and load being across the battery. Always test the same way, either online or offline, to have consistent and meaningful results. When ohmic testing is performed online, a change in current occurs due to the ohmic test set signal that could impact battery voltage readings. Because battery float voltage is directly tied to float current, the sum of the voltages of each battery cell/unit have to equal the charger float voltage of the battery string. If a load is applied from the ohmic test set that depresses one cell/unit, then the others have to rise somewhat to offset it. As ohmic testing progresses through the battery string, each cell/unit gets pulled down by the ohmic test set somewhat, and the charger must boost the string current to maintain the voltage, raising the voltage of the cells/units that have not yet been tested. For this reason, voltage readings should be taken with a voltmeter prior to performing ohmic testing online.

Table 14.4.3.2 Item 9(5). Battery capacity is determined by the mass of active material contained in the battery and is a measure of the battery's stored energy. The rated capacity of small VRLA batteries used in fire alarm or signaling system applications is typically measured in ampere-hours (Ah) where the ampere-hour rating is based on the battery's capability to provide a constant current at the nominal battery voltage for 20 hours. The rated capacity might vary from manufacturer to manufacturer.

The *actual* battery capacity during service life, often referred to as the state of charge (SOC), can vary significantly from *rated* capacity due to aging, charge and discharge cycles, temperature, and other factors. The unique failure modes of VRLA batteries due to aging and internal degradation are attributed for a high failure rate where the *actual* battery capacity has degraded to 80 percent of the manufacturer's *rated* capacity. As a result, battery manufacturers often recommend replacement much sooner than the rated design life for critical systems.

A test of battery capacity is designed to determine if the battery is capable of continuing to deliver the voltage level specified by the manufacturer. The results of a capacity test can

also be used to estimate where the battery is in its service life. A test of capacity is performed by applying a constant current load to the battery based on the manufacturer's published discharge rates until voltage falls to specified levels. Although discharging the battery for capacity testing concerns some, VRLA batteries are designed to handle numerous discharges within the limits established by the battery manufacturer.

The discharge rate selected for testing should be representative of the battery duty cycle. At shorter test times, the test duration has a greater effect on the capacity calculation. For example, a 1-minute difference in actual test time for a 5-minute discharge rate compared to a 3-hour discharge rate will result in a greater deviation of the calculated capacity. The battery is also operating less efficiently at shorter discharge rates and the effects of aging and degradation might not be as prevalent during shorter discharges.

Fire alarm or signaling system loading is typically insufficient for the practical application of a battery load test because the system load cannot be varied to maintain a constant current equal to the battery manufacturer's published discharge rates. The fixed load applied by the system will result in final voltage levels that are deceptively high. Battery sizing is also a factor. The calculated system loads for the battery duty cycle (e.g., 24 hours standby followed by 5 minutes in an alarm) will rarely align with published discharge rates necessary for load testing. In many applications where the battery size is large in comparison to the required system current, the system loading could be too small to accurately determine battery capacity. In these cases, a battery near failure could conceivably satisfy the low discharge rate applied by the fire alarm or signaling system.

In order to satisfy the load test requirements of Table 14.4.3.2, battery capacity testing can be performed in the following manner or in accordance with other methods such as those identified in IEEE 1188, *Recommended Practice for Maintenance, Testing, and Replacement of Valve-Regulated Lead-Acid (VRLA) Batteries for Stationary Applications*:

- (1) Referring to the battery manufacturer's specifications, determine the load current for the 3-hour battery rating to the selected end voltage, typically 1.67 volts per cell (10.2 volts for a 12-volt system or 20.4 volts for a 24-volt system).
- (2) Record the battery temperature at the negative terminal.
- (3) Disconnect the charger and connect a load bank to the battery terminals.
- (4) Apply the constant current specified for the 3-hour rate to the battery. Once the constant current is applied, continue the test until the battery terminal voltage decreases to the specified end voltage.
- (5) Stop the test when the selected end voltage is reached.
- (6) Record the actual test duration in minutes.
- (7) Disconnect the load bank and reconnect the charger.
- (8) Calculate percent battery capacity as follows:

$$\% \text{ Capacity} = [T_{\text{actual}} / (180 \times K_T)] \times 100$$

where:

T_{actual} = the test duration in minutes

K_T = the temperature correction factor for the actual battery temperature at the start of the test from Table A.14.4.3.2. Additional temperature correction factors can be obtained from IEEE 1188.

(9) Replace the battery if the battery capacity is less than or equal to 80 percent. Replace the battery at the next scheduled test interval if the battery capacity is less than 85 percent.

As a good practice, a new battery should be fully charged and then load tested following the battery manufacturer's recommendations prior to installation. A new fully charged battery should have a capacity of at least 90 percent.

Table 14.4.3.2, Item 17. Where the manufacturer publishes limits of accuracy for the operation of an initiating device, the test method should verify actuation is within the tolerances provided.

Table 14.4.3.2 Item 22(1) and 22(2). If, during the course of the periodic test of audible appliances, it is suspected that alarm sound levels could be lower than the required minimum, the system owner or the system owner's designated representative should be notified in writing. Such notification will allow the building owner or designated building representative to determine whether sound pressure level readings should be taken for the area(s) in question.

Table 14.4.3.2, Item 24. The extent of testing of a fire alarm or signaling system, including devices that were not tested, should be documented in accordance with the test plan in 14.2.10. *NFPA 72* does not require testing of an emergency control function, such as elevator recall, but does require testing of the emergency control function interface device, such as the relay powered by the fire alarm or signaling system. Where the emergency control function is not being tested concurrent with the fire alarm or signaling system testing, measurement of the emergency control function interface device output should be verified using the proper test devices. This might require reading or observing the condition of a relay, a voltage measurement, or the use of another type of test instrument. Once testing is complete, verification that any disabled or disconnected interface devices have been restored to normal is essential, and this verification should be documented in the testing results.

Testing of the emergency control functions themselves is outside of the scope of *NFPA 72*. A complete end-to-end test that demonstrates the performance of emergency control functions actuated by the fire alarm or signaling system might be required by some other governing laws, codes, or standards, or the authority having jurisdiction. In that situation, other applicable installation standards and design documents, not *NFPA 72*, would address testing and performance of the emergency control functions. *NFPA 4* provides requirements for integrated (end-to-end) system testing.

It is important to note that the appropriate *NFPA* standard would provide the acceptance criteria for the overall emergency control function operation requirements, including performance and test methods, while *NFPA 72* covers the required performance and testing of the emergency function interface device.

For instance, if an end-to-end test for a building with an engineered smoke control system is required by some other governing laws, codes, standards, or the authority having jurisdiction, the test protocol would have unique criteria for the smoke control system design, and a special inspector would be responsible for the overall operation and performance of the smoke control system in accordance with the appropriate standard (*NFPA 92* and *NFPA 101*) during the testing, includ-

ing measuring pressure differentials and ensuring proper fan and damper operation. Refer to the following extract from *NFPA 101* on smoke control:

9.3.2 System Design. The engineer of record shall clearly identify the intent of the system, the design method, the appropriateness of that method used, and the required means of inspecting, testing, and maintaining the system. [101: 9.3.2]

9.3.3 Acceptance Testing. Acceptance testing shall be performed by a special inspector in accordance with Section 9.13. [101: 9.3.3]

Even though the fire alarm or signaling system initiating device might actuate the smoke control system, the actual testing of the dampers and fan operation would be as required by the smoke control design and not part of the fire alarm or signaling system.

Other emergency control operation requirements might be as follows: For fan shutdown and smoke damper operation, the fan and damper operations would be in accordance with *NFPA 90A* and *NFPA 105* respectively, and those equipment operations would be verified by those responsible for HVAC systems in combination with the fire alarm system personnel. Guidance for elevator inspection and testing can be found in *ASME A.17.2, Guide for Inspection of Elevators, Escalators and Moving Walks*. For elevator systems, the recall function, elevator power shutdown, and hat illumination would be done with the elevator mechanics present during the test. This operational test is often accomplished during routine periodic fire alarm testing. For fire door holder and fire shutter release, it would be expected that the emergency control function operation of the doors/shutters would be verified in accordance with *NFPA 80* and *NFPA 101* during the test. In some cases, the door manufacturer representative might need to be present to reset the equipment.

A.14.4.4 It is suggested that the annual test be conducted in segments so that all devices are tested annually.

The intent of 14.4.4 is to prevent a test from being made at intervals exceeding those allowed by Table 14.4.3.2. Annual tests should be made every 12 months; monthly tests should be made every 30 days, and so forth. For example, it is not acceptable to conduct an annual test in January of year one, and December of year two (23-month frequency), just because Table 14.4.3.2 requires a test once each year. See the definition of *frequency* in 3.3.128 for minimum and maximum time between testing events.

A.14.4.4.1 In addition to safety considerations, other reasons for delaying fire alarm testing include nationally or regionally declared disasters, such as pandemics, weather-related emergencies, or other governmentally recognized disruptions.

A.14.4.4.3 Detectors that cause unwanted alarms should be tested at their lower listed range (or at 0.5 percent obscuration if unmarked or unknown). Detectors that actuate at less than this level should be replaced.

A.14.4.4.6 It is not intended to require testing the pathways at every device or circuit junctions.

A.14.4.5.3 It is intended that smoke alarms and connected appliances be considered as a "fire protection system" for the purpose of applying the responsibility provisions in 14.2.3.




FIGURE A.14.4.3.2 Example Ohmic Trend Analysis for a 24-Volt Battery Made Up of Two 12-Volt Units.

Table A.14.4.3.2 Temperature Correction Factors

Temperature		K_T
°F	(°C)	
65	18.3	0.92
66	18.9	0.927
67	19.4	0.935
68	20	0.942
69	20.6	0.948
70	21.1	0.955
71	21.7	0.96
72	22.2	0.97
73	22.8	0.975
74	23.4	0.98
75	23.9	0.985
76	24.5	0.99
77	25	1
78	25.6	1.002
79	26.1	1.007
80	26.7	1.011
81	27.2	1.017
82	27.8	1.023
83	28.3	1.03
84	28.9	1.035
85	29.4	1.04
86	30	1.045
87	30.6	1.05
88	31.1	1.055
89	31.6	1.06
90	32.2	1.065
95	35	1.09
100	37.8	1.112

A.14.4.5.4 Permanent occupants (whether renters or owners) of a dwelling unit should be provided with training and information sufficient to operate, inspect, test, and maintain their own alarms. The information should cover basic maintenance requirements, testing, and troubleshooting procedures, and contact information for further support. It is not intended that occupants be trained to a level similar to a factory technician or to qualify them to redesign, program, or extend their alarms without further training.

A.14.4.6.3 Permanent occupants (whether renters or owners) of a dwelling unit should be provided with training and information sufficient to operate, inspect, test, and maintain their own household alarm system. The information should cover basic maintenance requirements, testing and troubleshooting procedures, and contact information for further support. It is not intended that occupants be trained to a level similar to a factory technician or to qualify them to redesign, program, or extend their systems.

A.14.4.8.1.3 Permanent occupants (whether renters or owners) of a dwelling unit should be provided with training and information sufficient to operate, inspect, test, and maintain their own alarm systems. The training should cover basic maintenance requirements, testing and troubleshooting procedures, and contact information for further support. It is not intended that occupants be trained to a level similar to a factory technician or to qualify them to redesign, program, or extend their systems.

A.14.4.11 See Annex D, Speech Intelligibility.

A.14.6.1 For final determination of record retention, see 14.4.4.3 for sensitivity options.

A.14.6.1.1 One method used to define the required sequence of operations and to document the actual sequence of operations is an input/output matrix (see Figure A.14.6.1.1).

System Outputs

System Inputs

|--|

FIGURE A.14.6.1.1 Typical Input/Output Matrix.

A.14.6.1.2 With many software-based fire systems, a copy of the site-specific software is required to restore system operation if a catastrophic system failure should occur. Without a back-up copy readily available on site, recovery of system operation by authorized service personnel can be substantially delayed.

The intent of this requirement is to provide authorized service personnel with an on-site copy of the site-specific software. The on-site copy should provide a means to recover the last installed and tested version of the site-specific operation of the system. This typically would be an electronic copy of the source files required to load an external programming device with the site-specific data. This requirement does not extend to the system executive software, nor does it require that the external programmer software if required be stored on site.

It is intended that this copy of the software be an electronic version stored on a nonrewritable media containing all of the file(s) or data necessary to restore the system and not just a printed version of the operation stored on electronic media. One example of a nonrewritable medium is a CD-R.

A.17.1.1 Examples of initiating devices include, but are not limited to, fire detection devices, carbon monoxide or other gas detection devices, devices that detect the operation of fire suppression and extinguishing systems, waterflow detectors, pressure switches, manual fire alarm boxes, and other supervisory signal-initiating devices (including guard tour reporting)

used to ensure timely warning for the purposes of life safety and the protection of a building, a space, a structure, an area, or an object.

A.17.1.2 The initiating devices chapter does not specify requirements for having or using any particular type of initiating device for a particular application. The requirements to have certain initiating devices are found in other NFPA codes and standards, or in other governing laws, codes, or standards. In a few instances other parts of this Code might require some minimal complement of initiating devices. For example, 10.4.5 requires a smoke detector at control unit locations but does not require complete smoke detection of any particular area. Similarly, 23.8.5.1.2 requires at least one manual fire alarm box on any fire alarm system that is connected to a supervising station and that also employs automatic fire detectors or water-flow detection devices. Thus, a system that might be required solely for the purpose of monitoring a sprinkler system and sending a signal off premises would still require a smoke detector at any control unit locations as well as a single manual pull station.

A.17.3 Annex B, Engineering Guide for Automatic Fire Detector Spacing, provides a detailed design guide for the implementation of the performance-based design of fire alarm systems.

A.17.4.2.3 Situations exist where supplemental enclosures are necessary to protect the physical integrity of an initiating device. Protective enclosures should not interfere with the performance characteristics of the device. If the enclosure degrades the performance, methods should be detailed in the manufacturer's published instructions of the protection device that clearly identify the degradation. In some cases, adjustments to initiating device sensitivity or range of operation are necessary to ensure the objective and performance of the system.

A.17.4.6 The monitoring of circuit integrity relies on the interruption of the wiring continuity when the connection to the initiating device is lost. Terminals and leads, as illustrated in Figure A.17.4.6(a) and Figure A.17.4.6(b), monitor the presence of the device on the initiating device circuit.

A.17.4.7 Detectors have built-in status indicators that aid in identifying individual detectors with an active alarm or supervisory condition. These indicators should be readily visible to responding personnel unless other means are provided to aid in the purpose. Other methods can include means at the control panel to independently identify the detector's status along with the location of the detector and its purpose or it can include the addition of a remote alarm indicator.

A.17.4.7.1 Embossed plastic tape, pencil, ink, or crayon should not be considered to be a permanently attached placard.

A.17.4.7.2 Remote alarm and supervisory indicators should be located in an area where they are readily visible to responding personnel. Many times, they are located in the general vicinity of the concealed detector. Separate indicators for alarm and supervisory signals are not required so long as each condition can be independently identified (i.e., multicolor LED, or flashing LED vs steady LED).

A.17.4.8 Some applications that do not require full area protection do require detection to initiate action when specific objects or spaces are threatened by smoke or fire, such as at elevator landings that have ceilings in excess of 15 ft (4.6 m) and for protection of fire alarm control units. In high-ceiling areas, to achieve the desired initiation, such as for elevator recall and protection of fire alarm control units (FACUs), detection should be placed on the wall above and within 60 in. (1.52 m) from the top of the elevator door(s) or FACU. Multiple objects or a space can be protected by a single detector unit.

A.17.5.2 This requirement is based on the generally accepted principle that the ceiling jet is approximately 10 percent of the distance from the base of the fire to the ceiling. To this figure, an additional safety factor of 50 percent has been added. Performance-based methods are available to predict the impact of partitions on the flow of smoke to detectors and can be used to substantiate a less restrictive design criterion.

A.17.5.3 The requirement of 17.5.3 recognizes that there are several different types of detector coverage.






FIGURE A.17.4.6(a) Correct (and Incorrect) Wiring Methods.



Illustrates four-wire smoke detector employing a three-wire connecting arrangement. One side of power supply is connected to one side of initiating device circuit. Wire run broken at each connection to smoke detector to provide supervision.



Illustrates four-wire smoke detector employing a four-wire connecting arrangement. Incoming and outgoing leads or terminals for both initiating device and power supply connections. Wire run broken at each connection to provide supervision.

D = Detector

FIGURE A.17.4.6(b) Wiring Arrangements for Four-Wire Detectors.

A.17.5.3.1 The degree of detection coverage is generally a design issue. Usually the design of detection correlates with the smoke compartmentation of the building.

Vertical spaces such as stairways and elevator shafts are often difficult design challenges. For elevator shafts, Section 21.4 provides design criteria to achieve correlation with ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*.

Stairways can be equipped with smoke detection but the number and location are determined by the design of the stairway.

Generally at least one smoke detector should be located at the top of the stairway. Additional detectors should be located on additional floors to achieve design objectives.

A.17.5.3.1.4 Total coverage requires that a fire above the suspended ceiling be detected. Detector spacing and location for above ceiling spaces are addressed in 17.7.4.5.4. If that above-ceiling space is used as an air return plenum, this detection can be provided either by smoke detectors placed in accordance with 17.7.5.2 or where the air leaves the smoke compartment in accordance with 17.7.6.4.2.2.

A.17.5.3.2 If there are no detectors in the room or area of fire origin, the fire could exceed the design objectives before being detected by remotely located detectors. When coverage other than total coverage is required, partial coverage can be provided in common areas and work spaces such as corridors, lobbies, storage rooms, equipment rooms, and other tenantless spaces. The intent of selective coverage is to address a specific hazard only.

Where a specific area is to be protected, all points within that area should be within $0.7 \times$ the adjusted detector spacing for spot-type detectors as required by 17.6.3 and 17.7.4.2. Note that an area does not necessarily mean an entire room. It is possible to provide properly spaced detectors to provide detection for only part of a room. Similarly, the Code permits protection of a specific hazard. In that case, detectors within a radius of $0.7 \times$ the adjusted detector spacing from the hazard provide the required detection. An example of protection of specific risk is the smoke detector required by Section 21.3 to be within 21 ft (6.4 m) of an elevator, where elevator recall is required.

It should also be noted that fire detection by itself is not fire protection. Also, protection goals could be such that detection being provided for a specific area or hazard might require a form of total coverage for that particular area or hazard. That is, it might be necessary to provide detectors above suspended ceilings or in small closets and other ancillary spaces that are a part of, or an exposure to, the area or hazard being protected.

A.17.5.3.3 The requirement of 17.5.3.3 recognizes there will be instances where, for example, a facility owner would want to apply detection to meet certain performance goals and to address a particular hazard or need, but that detection is not required. Once installed, of course, acceptance testing, annual testing, and ongoing maintenance in accordance with this Code is expected. The intent of this section is to allow the use of a single detector, or multiple detectors provided for specific protection, with spacing to meet specific fire safety objectives as determined in accordance with 17.6.1.1 and 17.7.1.1.

A.17.6.1.1 The performance objective statement should describe the purpose of the detector placement and the inten-

ded response of the fire alarm control unit to the detector activation. This statement can include a narrative description of the required response time of the detectors, a narrative of the sequence of operations, a tabular list of programming requirements or some other method.

The performance objective of a fire detection system is usually expressed in terms of time and the size fire the system is intended to detect, measured in British thermal units per second (Btu/sec) or kilowatts (kW). Typically, the fire alarm system designer does not establish this criterion. It is usually obtained from the design documentation prepared by the designer responsible for the strategy of the structure as a whole. Where a prescriptive design is being provided, this requirement is fulfilled by stating in the design documentation that the design conforms to the prescriptive provisions of this Code.

A.17.6.1.3 In a performance-based design environment, the performance objectives for the fire alarm system are not established by the fire alarm system designer.

A fire protection strategy is developed to achieve those goals. General performance objectives are developed for the facility. These general objectives give rise to specific performance objectives for each fire protection system being employed in the facility. Consequently, the performance objectives and criteria for the fire alarm system are part of a much larger strategy that often relies on other fire protection features, working in concert with the fire alarm system to attain the overall fire protection goals for the facility.

In the performance-based design environment, the designer uses computational models to demonstrate that the spacing used for automatic fire detectors connected to the fire alarm system will achieve the objectives established by the system, by showing that the system meets the performance criteria established for the system in the design documentation. Consequently, it is imperative that the design objectives and performance criteria to which the system has been designed are clearly stated in the system documentation.

A.17.6.1.5 In order to predict the response of a heat detector using current fire modeling programs and currently published equations describing plume dynamics, two parameters must be known: operating temperature and response time index (RTI). The RTI is the quantification of the rate of heat transfer from the ceiling jet to the detector sensing element per unit of time, expressed as a function of ceiling jet temperature, ceiling jet velocity, and time. Spot-type heat detectors manufactured prior to July 1, 2008, were not required to be marked with an RTI.

A.17.6.2.3 Detectors should be selected to minimize this temperature difference in order to minimize response time. However, a heat detector with a temperature rating that is somewhat in excess of the highest normally expected ambient temperature is specified in order to avoid the possibility of premature operation of the heat detector to non-fire conditions. Heat-sensing fire detectors of a low temperature classification per Table 17.6.2.1 are intended only for installation in areas where the ambient temperature is controlled.

A.17.6.3.1.1 Maximum linear spacings on smooth ceilings for spot-type heat detectors are determined by full-scale fire tests. [See Figure A.17.6.3.1.1(c).] These tests assume that the detectors are to be installed in a pattern of one or more squares, each side of which equals the maximum spacing as determined in

the test, as illustrated in Figure A.17.6.3.1.1(a). The detector to be tested is placed at a corner of the square so that it is positioned at the farthest possible distance from the fire while remaining within the square. Thus, the distance from the detector to the fire is always the test spacing multiplied by 0.7 and can be calculated as shown in Table A.17.6.3.1.1. Figure A.17.6.3.1.1(b) illustrates the smooth ceiling spacing layout for line-type heat detectors.

Once the correct maximum test distance has been determined, it is valid to interchange the positions of the fire and the detector. The detector is now in the middle of the square, and the listing specifies that the detector is adequate to detect a fire that occurs anywhere within that square — even out to the farthest corner.

In laying out detector installations, designers work in terms of rectangles, as building areas are generally rectangular in shape. The pattern of heat spread from a fire source, however, is not rectangular in shape. On a smooth ceiling, heat spreads out in all directions in an ever-expanding circle. Thus, the coverage of a detector is not, in fact, a square, but rather a circle whose radius is the linear spacing multiplied by 0.7.

This is graphically illustrated in Figure A.17.6.3.1.1(d). With the detector at the center, by rotating the square, an infinite number of squares can be laid out, the corners of which create the plot of a circle whose radius is 0.7 times the listed spacing. The detector will cover any of these squares and, consequently, any point within the confines of the circle.

So far, this explanation has considered squares and circles. In practical applications, very few areas turn out to be exactly square, and circular areas are extremely rare. Designers deal generally with rectangles of odd dimensions and corners of rooms or areas formed by wall intercepts, where spacing to one wall is less than one-half the listed spacing. To simplify the rest of this explanation, the use of a detector with a listed spacing of 30 ft × 30 ft (9.1 m × 9.1 m) should be considered. The principles derived are equally applicable to other types.

Figure A.17.6.3.1.1(g) illustrates the derivation of this concept. In Figure A.17.6.3.1.1(g), a detector is placed in the center of a circle with a radius of 21 ft (0.7 × 30 ft) [6.4 m (0.7 × 9.1 m)]. A series of rectangles with one dimension less than the permitted maximum of 30 ft (9.1 m) is constructed within the circle. The following conclusions can be drawn:

- (1) As the smaller dimension decreases, the longer dimension can be increased beyond the linear maximum spacing of the detector with no loss in detection efficiency.
- (2) A single detector covers any area that fits within the circle. For a rectangle, a single, properly located detector should be permitted, provided the diagonal of the rectangle does not exceed the diameter of the circle.
- (3) Relative detector efficiency actually is increased, because the area coverage in square meters is always less than the 900 ft² (84 m²) permitted if the full 30 ft × 30 ft (9.1 m × 9.1 m) square were to be utilized. The principle illustrated here allows equal linear spacing between the detector and the fire, with no recognition for the effect of reflection from walls or partitions, which in narrow rooms or corridors is of additional benefit. For detectors that are not centered, the longer dimension should always be used in laying out the radius of coverage.

Areas so large that they exceed the rectangular dimensions given in Figure A.17.6.3.1.1(g) require additional detectors.

Often, proper placement of detectors can be facilitated by breaking down the area into multiple rectangles of the dimensions that fit most appropriately [see Figure A.17.6.3.1.1(e) and Figure A.17.6.3.1.1(f)]. For example, refer to Figure A.17.6.3.1.1(h). A corridor 10 ft (3.0 m) wide and up to 82 ft (25.0 m) long can be covered with two 30 ft (9.1 m) spot-type detectors. An area 40 ft (12.2 m) wide and up to 74 ft (22.6 m) long can be covered with four spot-type detectors. Irregular areas need more careful planning to make certain that no spot on the ceiling is more than 21 ft (6.4 m) away from a detector. These points can be determined by striking arcs from the remote corner. Where any part of the area lies beyond the circle with a radius of 0.7 times the listed spacings, additional detectors are required.

Figure A.17.6.3.1.1(h) illustrates smoke or heat detector spacing layouts in irregular areas.

A.17.6.3.1.3.1 Figure A.17.6.3.1.3.1 illustrates the proper mounting placement for detectors.

Table A.17.6.3.1.1 Test Spacing for Spot-Type Heat Detectors

Test Spacing		Maximum Test Distance from Fire to Detector (0.7D)	
ft	m	ft	m
50 × 50	15.2 × 15.2	35.0	10.7
40 × 40	12.2 × 12.2	28.0	8.5
30 × 30	9.1 × 9.1	21.0	6.4
25 × 25	7.6 × 7.6	17.5	5.3
20 × 20	6.1 × 6.1	14.0	4.3
15 × 15	4.6 × 4.6	10.5	3.2




FIGURE A.17.6.3.1.1(a) Spot-Type Heat Detectors.




FIGURE A.17.6.3.1.1(b) Line-Type Detectors — Spacing Layouts, Smooth Ceiling.




FIGURE A.17.6.3.1.1(c) Fire Test Layout.

A.17.6.3.2 In addition to the special requirements for heat detectors that are installed on ceilings with exposed joists, reduced spacing also could be required due to other structural characteristics of the protected area, such as possible drafts or other conditions that could affect detector operation.

See Figure A.17.6.3.2 for an example of reduced spacing for solid joist construction.






FIGURE A.17.6.3.1.1(d) Detector Covering any Square Laid Out in Confines of Circle in Which Radius Is 0.7 Times Listed Spacing.



Note: All measures are in feet.

FIGURE A.17.6.3.1.1(e) Typical Rectangles for Detector Curves of 15 ft to 50 ft.



Note: All measures are in meters.

FIGURE A.17.6.3.1.1(f) Typical Rectangles for Detector Curves of 4.6 m to 15.2 m.


A.17.6.3.3 The location and spacing of heat detectors should consider beam depth, ceiling height, beam spacing, and fire size.

If the ratio of beam depth (D) to ceiling height (H), (D/H), is greater than 0.10 and the ratio of beam spacing (W) to ceiling height (H), (W/H), is greater than 0.40, heat detectors should be located in each beam pocket.

If either the ratio of beam depth to ceiling height (D/H) is less than 0.10 or the ratio of beam spacing to ceiling height (W/H) is less than 0.40, heat detectors should be installed on the bottom of the beams.

A.17.6.3.4 Figure A.17.6.3.4(a) illustrates smoke or heat detector spacing for peaked-type sloped ceilings.

Figure A.17.6.3.4(b) illustrates smoke or heat detector spacing for shed-type sloped ceilings.



Note: Smoke detectors are not listed for spacing. Use manufacturer's coverage recommendations and this figure.

FIGURE A.17.6.3.1.1(g) Detector Spacing, Rectangular Areas.




FIGURE A.17.6.3.1.1(h) Smoke or Heat Detector Spacing Layout in Irregular Areas.




FIGURE A.17.6.3.1.3.1 Example of Proper Mounting for Heat Detectors.




FIGURE A.17.6.3.2 Detector Spacing Layout, Solid Joist Construction.

A.17.6.3.5.1 Both 17.6.3.5.1 and Table 17.6.3.5.1 are constructed to provide detector performance on higher ceilings [to 30 ft (9.1 m) high] that is essentially equivalent to that which would exist with detectors on a 10 ft (3.0 m) ceiling. Table 17.6.3.5.1 is only applicable to spot-type heat detectors.

The Fire Detection Institute Fire Test Report (*see K.1.2.17.1*) is used as a basis for Table 17.6.3.5.1. The report does not include data on integration-type detectors. Pending development of such data, the manufacturer's published instructions will provide guidance.

Table 17.6.3.5.1 provides for spacing modification to take into account different ceiling heights for generalized fire conditions. Information regarding a design method that allows the designer to take into account ceiling height, fire size, and ambient temperatures is provided in Annex B.

A.17.6.3.5.3 The width of uniform temperature of the plume when it impinges on the ceiling is approximately 0.4 times the




FIGURE A.17.6.3.4(a) Smoke or Heat Detector Spacing Layout, Sloped Ceilings (Peaked Type).




FIGURE A.17.6.3.4(b) Smoke or Heat Detector Spacing Layout, Sloped Ceilings (Shed Type).

height above the fire, so reducing spacing below this level will not increase response time. For example, a detector with a listed spacing of 15 ft (4.6 m) or 225 ft² (21 m²) need not be spaced closer than 12 ft (3.7 m) on a 30 ft (9.1 m) ceiling, even though Table 17.6.3.5.1 states that the spacing should be 0.34×15 ft (0.34×4.6 m), which equals 5.1 ft (1.6 m).

A.17.6.3.6 The linear space rating is the maximum allowable distance between heat detectors. The linear space rating is also a measure of the heat detector response time to a standard test fire where tested at the same distance. The higher the rating, the faster the response time. This Code recognizes only those heat detectors with ratings of 50 ft (15.2 m) or more.

A.17.7.1.1 The performance objective statement should describe the purpose of the detector placement and the intended response of the fire alarm control unit to the detector activation. This statement can include a narrative description of the required response time of the detectors, a narrative of the

sequence of operations, a tabular list of programming requirements, or some other method.

The performance objective of a fire detection system is usually expressed in terms of time and the size fire the system is intended to detect, measured in British thermal units per second (Btu/sec) or kilowatts (kW). Typically, the fire alarm system designer does not establish this criterion. It is usually obtained from the design documentation prepared by the designer responsible for the strategy of the structure as a whole. Where a prescriptive design is being provided, this requirement is fulfilled by stating in the design documentation that the design conforms to the prescriptive provisions of this Code.

A.17.7.1.2 The person designing an installation should keep in mind that, in order for a smoke detector to respond, the smoke has to travel from the point of origin to the detector. In evaluating any particular building or location, likely fire locations should be determined first. From each of these points of origin, paths of smoke travel should be determined. Wherever practicable, actual field tests should be conducted. The most desired locations for smoke detectors are the common points of intersection of smoke travel from fire locations throughout the building.

NOTE: This is one of the reasons that specific spacing is not assigned to smoke detectors by the testing laboratories.

A.17.7.1.3 In a performance-based design environment, the performance objectives for the fire alarm system are not established by the fire alarm system designer.

A fire protection strategy is developed to achieve those goals. General performance objectives are developed for the facility. These general objectives give rise to specific performance objectives for each fire protection system being employed in the facility. Consequently, the performance objectives and criteria for the fire alarm system are part of a much larger strategy that often relies on other fire protection features, working in concert with the fire alarm system to attain the overall fire protection goals for the facility.

In the performance-based design environment, the designer uses computational models to demonstrate that the spacing used for automatic fire detectors connected to the fire alarm system will achieve the objectives established by the system, by showing that the system meets the performance criteria established for the system in the design documentation. Consequently, it is imperative that the design objectives and performance criteria to which the system has been designed are clearly stated in the system documentation.

A.17.7.1.8 Product-listing standards include tests for temporary excursions beyond normal limits. In addition to temperature, humidity, and velocity variations, smoke detectors should operate reliably under such common environmental conditions as mechanical vibration, electrical interference, and other environmental influences. Tests for these conditions are also conducted by the testing laboratories in their listing program. In those cases in which environmental conditions approach the limits shown in Table A.17.7.1.8, the detector manufacturer's published instructions should be consulted for additional information and recommendations.

A.17.7.1.9 The velocities indicated in individual duct detector listings are based on applicable standards such as UL 268A, *Smoke Detectors for Duct Application*.

Table A.17.7.1.8 Environmental Conditions that Influence Smoke Detector Response

Detection Protection	Air Velocity >300 ft/min (>91.44 m/min)	Altitude >3000 ft (>914.4 m)	Humidity >93% RH	Temperature <32°F >100°F (<0°C >37.8°C)	Color of Smoke
Ion	X	X	X	X	O
Photo	O	O	X	X	X
Beam	O	O	X	X	O
Air sampling	O	O	X	X	O

X: Can affect detector response. O: Generally does not affect detector response.

Table A.17.7.1.10(a) Common Sources of Aerosols and Particulate Matter Moisture

Moisture	Humid outside air Humidifiers Live steam Showers Slop sink Steam tables Water spray
Combustion products and fumes	Chemical fumes Cleaning fluids Cooking equipment Curing Cutting, welding, and brazing Dryers Exhaust hoods Fireplaces Machining Ovens Paint spray
Atmospheric contaminants	Corrosive atmospheres Dust or lint Excessive tobacco smoke Heat treating Linen and bedding handling Pneumatic transport Sawing, drilling, and grinding Textile and agricultural processing
Engine exhaust	Diesel trucks and locomotives Engines not vented to the outside Gasoline forklift trucks
Heating element with abnormal conditions	Dust accumulations Improper exhaust Incomplete combustion

A.17.7.1.10 Smoke detectors can be affected by electrical and mechanical influences and by aerosols and particulate matter found in protected spaces. The location of detectors should be such that the influences of aerosols and particulate matter from sources such as those in Table A.17.7.1.10(a) are minimized. Similarly, the influences of electrical and mechanical factors shown in Table A.17.7.1.10(b) should be minimized. While it might not be possible to isolate environmental factors totally, an awareness of these factors during system layout and design favorably affects detector performance.

Table A.17.7.1.10(b) Sources of Electrical and Mechanical Influences on Smoke Detectors

Electrical Noise and Transients	Airflow
Vibration or shock	Gusts
Radiation	Excessive velocity
Radio frequency	
Intense light	
Lightning	
Electrostatic discharge	
Power supply	

A.17.7.1.11 Stratification of air in a room can hinder air containing smoke particles or gaseous combustion products from reaching ceiling-mounted smoke detectors or fire-gas detectors.

Stratification occurs when air containing smoke particles or gaseous combustion products is heated by smoldering or burning material and, becoming less dense than the surrounding cooler air, rises until it reaches a level at which there is no longer a difference in temperature between it and the surrounding air.

Stratification also can occur when evaporative coolers are used, because moisture introduced by these devices can condense on smoke, causing it to fall toward the floor. Therefore, to ensure rapid response, it might be necessary to install smoke detectors on sidewalls or at locations below the ceiling.

In installations where detection of smoldering or small fires is desired and where the possibility of stratification exists, consideration should be given to mounting a portion of the detectors below the ceiling. In high-ceiling areas, projected beam-type or air sampling-type detectors at different levels also should be considered. (See Figure A.17.7.1.11.)

A.17.7.2 Construction debris, dust (especially gypsum dust and the fines resulting from the sanding of drywall joint compounds), and aerosols can affect the sensitivity of smoke detectors and, in some instances, cause deleterious effects to the detector, thereby significantly reducing the expected life of the detector.

A.17.7.3 Throughout this Code, smoke detector sensitivity is referred to in terms of the percent obscuration required to alarm or produce a signal. Smoke detectors are tested using various smoke sources that have different characteristics (e.g., color, particle size, number of particles, particle shape). Unless otherwise specified, this Code, the manufacturers, and the listing agencies report and use the percent obscuration produced using a specific type of gray smoke. Actual detector response




FIGURE A.17.7.1.11 Smoke Detector Layout Accounting for Stratification.

will vary when the characteristics of the smoke reaching the detector are different from the smoke used in testing and reporting detector sensitivity.

A.17.7.3.1 The production sensitivity range should only be used as a benchmark for testing and should not be used as the sole basis for selection of devices. The percent per foot sensitivity marked on the smoke detector is derived from testing in a smoke chamber, usually referred to as the UL 268 Smoke Box. The measurements derived from this measurement apparatus are only valid in the context of the apparatus and cannot be used outside the context of the smoke box. The polychromatic light source employed in the smoke box results in measurements that are highly dependent upon smoke color and does not account for variations in light transmission as a function of wavelength that occurs as fuels and fire ventilation rates change or as smoke ages. Furthermore, the measurement apparatus uses a measurement of light obscuration by smoke to infer a measure of light reflectance when there is no correlation between these two optical characteristics.

A.17.7.4.1 Except in the case of smoldering, low-energy fires, all smoke detectors, regardless of the type of technology, usually rely on the plume and ceiling jet produced by the fire to transport the smoke upward and across the ceiling to the detector, sampling port, or projected sensing light beam. Once sufficient concentration is attained at the detector, sampling port, or sensing light beam location and, in the case of spot-type detectors, sufficient flow velocity is attained to overcome the flow resistance into the sensing chamber, the detector responds with an alarm signal. Detectors are usually mounted at the ceiling plane to take advantage of the flow provided by the plume and the ceiling jet. A hot, energetic fire produces large plume velocities and temperatures and hot, fast ceiling jets. This minimizes the time it takes for the smoke to travel to the detector. A smoldering fire produces little, if any, plume and no appreciable ceiling jet. Far more time elapses between ignition and detection under this circumstance.

A.17.7.4.2 In high-ceiling areas, such as atriums, where spot-type smoke detectors are not accessible for periodic maintenance

and testing, projected beam-type or air sampling-type detectors should be considered where access can be provided.

A.17.7.4.2.1 Refer to Figure A.17.7.4.2.1 for an example of proper mounting for detectors. Sidewall detectors mounted closer to the ceiling will respond faster.

A.17.7.4.2.2 Figure A.17.7.4.2.2 illustrates underfloor mounting installations.

A.17.7.4.2.3.1 The 30 ft (9.1 m) spacing is a guide for prescriptive designs. The use of such a spacing is based upon customary practice in the fire alarm community.

Where there are explicit performance objectives for the response of the smoke detection system, the performance-based design methods outlined in Annex B should be used.

For the purposes of this section, “nominal 30 ft (9.1 m)” should be determined to be 30 ft (9.1 m) $\pm$ 5 percent [$\pm$ 18 in. (460 mm)].

A.17.7.4.2.3.1(2) This is useful in calculating locations in corridors or irregular areas [see 17.6.3.1.1 and Figure A.17.6.3.1.1(h)]. For irregularly shaped areas, the spacing between detectors can be greater than the selected spacing, provided the maximum spacing from a detector to the farthest point of a sidewall or corner within its zone of protection is not greater than 0.7 times the selected spacing (0.7S).

A.17.7.4.2.4 Detectors are placed at reduced spacings at right angles to joists or beams in an attempt to ensure that detection time is equivalent to that which would be experienced on a flat ceiling. It takes longer for the combustion products (smoke or heat) to travel at right angles to beams or joists because of the phenomenon wherein a plume from a relatively hot fire with significant thermal lift tends to fill the pocket between each beam or joist before moving to the next beam or joist.

Though it is true that this phenomenon might not be significant in a small smoldering fire where there is only enough thermal lift to cause stratification at the bottom of the joists, reduced spacing is still recommended to ensure that detection time is equivalent to that which would exist on a flat ceiling, even in the case of a hotter type of fire.




FIGURE A.17.7.4.2.1 Example of Proper Mounting of Smoke Detectors.




FIGURE A.17.7.4.2.2 Mounting Installations Permitted (top) and Not Permitted (bottom).

A.17.7.4.2.4.2(3) The geometry and reservoir effect is a significant factor that contributes to the development of velocity, temperature, and smoke obscuration conditions at smoke detectors located on the ceiling in beam pocket areas or at the bottom of beams as smoke collected in the reservoir volume spills into adjacent pockets. The waffle- or pan-type ceiling created by beams or solid joists, although retarding the initial flow of smoke, results in increased optical density, temperature rise, and gas velocities comparable to unconfined smooth ceilings.

For waffle- or pan-type ceilings with beams or solid joists, an alternative smoke detector grid arrangement (such as a shifted grid), with detectors located to take advantage of the channeling effect due to the reservoirs created by the beam pockets, will improve detector response and might allow greater spacing. See Figure A.17.7.4.2.4.2(3)(a) and Figure A.17.7.4.2.4.2(3)(b) for an example of shifted grids. The alternative smoke detector grid arrangement and spacing should be justified by an engineering analysis comparing the alternative smoke detector grid arrangement with the performance of smoke detectors on a level ceiling of equal height using 30 ft (9.1 m) smoke detector spacing.

Figure A.17.7.4.2.4.2(3)(a) illustrates the reservoir and channeling effect that results from the deep beam configuration. The strongest gas flows occur in a direction perpendicular to the beam opposite the fire location. The weaker flow occurs in a directional 45 degrees off the beam grid; however, the reservoir effect accounts for higher concentrations of smoke eventually flowing from the strong area reservoirs into the weak area reservoirs.

Figure A.17.7.4.2.4.2(3)(b) is a generic example illustrating how a smoke detection grid using 30 ft (9.1 m) spacing can be

shifted to take advantage of the channeling and reservoir effect to optimize detection response. In the circle, the fire is split into four beam bays that must fill with smoke before appreciable flows occur into the next adjoining eight beam bays. This represents the worst case scenario for smoke to reach the detectors on the circle. The three other fire locations shown require the fire to initially fill only one or two bays before spilling to adjacent bays.

A.17.7.4.2.4.2(4) Corridor geometry is a significant factor that contributes to the development of velocity, temperature, and smoke obscuration conditions at smoke detectors located along a corridor. This is based on the fact that the ceiling jet is confined or constrained by the nearby walls without opportunity for entrainment of air. For corridors of approximately 15 ft (4.6 m) in width and for fires of approximately 100 kW or greater, modeling has demonstrated that the performance of smoke detectors in corridors with beams has been shown to be comparable to spot smoke detector spacing on an unconfined smooth ceiling surface.

A.17.7.4.2.4.3 A smoke detector should be placed within each beam channel. Computer modeling has shown that parallel beams (upslope) are very effective at channeling smoke, and smoke spillover is rarely detectable in adjacent parallel pockets.

A.17.7.4.2.4.4 Irregular area spacing guidance for level beam ceilings can be used. Computer modeling has shown that spot-type detectors should be located on the bottom of perpendicular beams.

A.17.7.4.2.4.5 Computer modeling has shown that spot-type detectors should be located on the bottom of perpendicular beams and should be aligned with the center of pocket, as shown, in Figure A.17.7.4.2.4.5.




FIGURE A.17.7.4.2.4.2(3)(a) Reservoir and Channeling Effect of Deep Beams.

A.17.7.4.3 Refer to Figure A.17.6.3.4(a).

A.17.7.4.4 Refer to Figure A.17.6.3.4(b).

A.17.7.4.6.1.1 For an air-sampling-type smoke detector, the sensitivity at the detector is not equal to sensitivity at the sampling port. Sampling port sensitivity is dependent on two main factors:

- (1) The number of sampling ports in the piping network
- (2) The set alarm sensitivity of the detector

The sensitivity at each sampling port of an air-sampling-type smoke detector should not exceed its listed port sensitivity.

A.17.7.4.6.2.6 Identification can include means such as marking or use of a configuration management program that identifies locations.

A.17.7.4.6.2.7 A benchmark test point should be provided at the furthest end of each pipe run, opposite the end of the air sampling-type smoke detector apparatus. This remote test point is intended to benchmark system performance at the time of initial commissioning and during routine test and inspection. The test point should be labeled to document benchmark system performance at the time of commissioning, using manufacturer-supplied labels intended for this purpose. Benchmark labels should be placed just above test points and be positioned so that they are visible without obstruction.

A.17.7.4.6.2.9 Where installed in areas having environmental conditions such as high temperature or humidity, radiation or corrosive atmospheres, all pipe network materials should be suitable for the specific environmental conditions anticipated.

A.17.7.4.6.3.1 Where the pipe network connects to the detector, refer to the manufacturer's published instructions for implementation of this connection.

A.17.7.4.6.3.3 Care should be exercised when attaching clamps to ensure that the pipe is not damaged and to allow for expansion and contraction of the pipe.




FIGURE A.17.7.4.2.4.2(3)(b) Shifted Smoke Detection Grid to Optimize Detection for Deep Beam Effects.




FIGURE A.17.7.4.2.4.5 Spot-Type Detector Spacing for Sloping Ceilings with Beam Pockets.


A.17.7.4.6.4.2 Electrical equipment cabinets are commonly ventilated vertically (bottom to top passive cooling) or horizontally (front to back passive cooling) or are fully enclosed with active internal cooling. For passively cooled applications, the sampling pipe can be located external to the cabinet with sampling ports directly in the main airflow of the exhaust vents or in the cabinet with the sampling port(s) located within 1 in. to 2 in. (25 mm to 50 mm) of the cabinet top. For fully enclosed cabinets, the sampling port is located in the cabinet within 1 in. to 2 in. (25 mm to 50 mm) from the cabinet top. In either case, the manufacturer's published installation instructions should be followed.

A.17.7.4.7 On smooth ceilings, a spacing of not more than 60 ft (18.3 m) between projected beams and not more than one-half that spacing between a projected beam and a *sidewall* (i.e., wall parallel to the beam travel) should be used as a guide. Other spacing should be determined based on ceiling height, airflow characteristics, and response requirements.

In some cases, the light beam projector is mounted on one end wall, with the light beam receiver or reflector mounted on the opposite wall. However, it is also permitted to suspend the projector and receiver/reflector from the ceiling at a distance from the end walls not exceeding one-quarter the selected spacing (S). (See Figure A.17.7.4.7.)

A.17.7.4.7.2 Projected beam smoke detection is often used in large open spaces with high ceilings where the use of spot-type detectors is impractical due to the problems of smoke stratification. In these spaces, there is questionable basis for the use of the prescriptive spacings presented in Section 17.7. However, beams can be installed such that, regardless of the fire origin, the plume will intersect at least one beam. To employ this strategy, the plume divergence is calculated as a function of the altitude at which the projected beam detectors are installed. The region of relatively uniform temperature and smoke density in a buoyant plume diverges at an angle of approximately 22 degrees, as shown in Figure A.17.7.4.7.2.

Another method involves assessing the smoke obstruction through the plume to determine the reduction in light from the receiver to the transmitter of the beam-type smoke detector to determine whether the detector might respond. ["Projected



S = Selected detector spacing

FIGURE A.17.7.4.7 Maximum Distance at Which Ceiling-Suspended Light Projector and Receiver/Reflector Can Be Positioned from End Wall Is One-Quarter Selected Spacing (S).

Beam Smoke Detectors — More Than Just a Substitute for Spot Detectors"; Fire Protection Engineering, Issue No. 23, Summer 2004, SFPE.]

A.17.7.4.7.8 Where the light path of a projected beam-type detector is abruptly interrupted or obscured, the unit should not initiate an alarm. It should give a trouble signal after verification of blockage.

A.17.7.5.1 Detectors should not be located in a direct airflow or closer than 36 in. (910 mm) from an air supply diffuser or return air opening. Supply or return sources larger than those commonly found in residential and small commercial establishments can require greater clearance to smoke detectors. Similarly, smoke detectors should be located farther away from high velocity air supplies. See B.4.9.

A.17.7.5.4 Smoke might not be drawn into the duct or plenums when the ventilating system is shut down. Furthermore, when the ventilating system is operating, the detector(s) can be less responsive to a fire condition in the room of fire origin due to dilution by clean air.

A.17.7.6 Refer to NFPA 101 for the definition of smoke compartment; NFPA 90A for the definition of duct systems; and NFPA 92, for the definition of smoke zone.

A.17.7.6.1 Smoke detectors located in an open area(s) should be used rather than duct-type detectors because of the dilution effect in air ducts. Active smoke management systems installed in accordance with NFPA 92 should be controlled by total coverage open area detection.

A.17.7.6.2 Dilution of smoke-laden air by clean air from other parts of the building or dilution by outside air intakes can allow high densities of smoke in a single room with no appreciable smoke in the air duct at the detector location. Smoke might not be drawn from open areas if air-conditioning systems or ventilating systems are shut down.

A.17.7.6.3 Smoke detectors can be applied in order to initiate control of smoke spread for the following purposes:

- (1) Prevention of the recirculation of dangerous quantities of smoke within a building
- (2) Selective operation of equipment to exhaust smoke from a building
- (3) Selective operation of equipment to pressurize smoke compartments




FIGURE A.17.7.4.7.2 The Plume Divergence of an Unconstrained Fire.

- (4) Operation of doors and dampers to close the openings in smoke compartments.

A.17.7.6.4.2 Smoke detectors are designed to sense the presence of particles of combustion, but depending on the sensing technology and other design factors, different detectors respond to different types of particles.

It is generally accepted that particle size distribution varies from sub-micron diameter particles predominant in the proximity of the flame of a flaming fire to particles one or more orders of magnitude larger, which are characteristic of smoke from a smoldering fire. The actual particle size distribution depends on a host of other variables, including the fuel and its physical make-up; the availability of oxygen, including air supply and fire-gas discharge; and other ambient conditions, especially humidity. Moreover, the particle size distribution is not constant, but as the fire gases cool, the sub-micron particles agglomerate and the very large ones precipitate. In other words, as smoke travels away from the fire source, the particle size distribution shows a relative decrease in smaller particles. Water vapor, which is abundantly present in most fires, when cooled sufficiently will condense to form fog particles — an effect frequently seen above tall chimneys. Because water condensation is basically clear in color, when it is mixed with other smoke particles, it can be expected to lighten the color of the mixture.

In almost every fire scenario in an air-handling system, the point of detection will be some distance from the fire source; therefore, the smoke will be cooler and more visible because of the growth of sub-micron particles into larger particles due to agglomeration and recombination. For these reasons, photo-electric detection technology has advantages over ionization detection technology in air duct system applications.

A.17.7.6.4.2.2 Detectors listed for the air velocity present can be permitted to be installed at the opening where the return air enters the common return air system. The detectors should be installed up to 12 in. (300 mm) in front of or behind the opening and spaced according to the following opening dimensions [see Figure A.17.7.6.4.2.2(a) through Figure A.17.7.6.4.2.2(c)]:

- (1) *Width.*
 - (a) Up to 36 in. (910 mm) — One detector centered in opening
 - (b) Up to 72 in. (1.83 m) — Two detectors located at the one-quarter points of the opening
 - (c) Over 72 in. (1.83 m) — One additional detector for each full 24 in. (610 mm) of opening
- (2) *Depth.* The number and spacing of the detector(s) in the depth (vertical) of the opening should be the same as those given for the width (horizontal) in A.17.7.6.4.2.2(1).
- (3) *Orientation.* Detectors should be oriented in the most favorable position for smoke entry with respect to the direction of airflow. The path of a projected beam-type detector across the return air openings should be considered equivalent in coverage to a row of individual detectors.

Additional duct smoke detection is not required where the air leaves each smoke compartment or in the duct system before the air enters the return air system in the return air of a smoke compartment provided with total (complete) smoke detection compliant with 17.5.3 because the addition of duct




FIGURE A.17.7.6.4.2.2(a) Location of Smoke Detector(s) in Return Air System Openings for Selective Operation of Equipment.




FIGURE A.17.7.6.4.2.2(b) Location of Smoke Detector(s) in Return Air Systems for Selective Operation of Equipment.

smoke detection would essentially not add any substantial detection benefit.

A.17.7.6.5.2 Where duct detectors are used to initiate the operation of smoke dampers, they should be located so that the detector is between the last inlet or outlet upstream of the damper and the first inlet or outlet downstream of the damper.

In order to obtain a representative sample, stratification and dead air space should be avoided. Such conditions could be caused by return duct openings, sharp turns, or connections, as well as by long, uninterrupted straight runs.




FIGURE A.17.7.6.4.2(c) Detector Location in Duct that Passes Through Smoke Compartments Not Served by Duct.

In return air systems, the requirements of 17.7.6.4.2.2 take precedence over these considerations. [See Figure A.17.7.6.5.2(a) and Figure A.17.7.6.5.2(b).]

Usually, it is necessary to manage smoke flow in buildings. Duct smoke detectors are used to shut down HVAC systems or initiate smoke management.

Filters have a serious effect on the performance of duct smoke detectors. The location of the detector relative to the filter and the source of smoke must be considered during the design process. Where smoke detectors are installed downstream from filters, they should be deemed to serve the purpose of providing an alarm indication of the occurrence of a fire in the HVAC unit (filters, belts, heat exchangers, etc.). These detectors usually serve the purpose of protecting building occupants from the smoke produced by an HVAC unit fire, or smoke ingress via the fresh air intake for the unit. They cannot be expected to serve the purpose of providing detection for the return side of the system.

Where return side detection is required, that requirement should be fulfilled with separate detectors from those monitoring the supply side. In order to be effective, return air duct smoke detectors should be located such that there are no filters between them and the source of the smoke.

Sampling tubes should be oriented to overcome thermal stratification due to buoyancy of the smoke in the upper half of the duct. This condition occurs where duct velocities are low, buoyancy exceeds flow inertia, or the detector is installed close to the fire compartment. A vertical orientation of sampling tubes overcomes the effects of differential buoyancy.

Where a detector is installed on a duct serving a single fire compartment, where the buoyancy exceeds the flow inertia of the air in the duct and the sampling tube cannot be oriented vertically, then the effects of thermal stratification can be minimized by locating the detector sampling tube in the upper half of the duct.

The thermal stratification is not a concern where the detector is installed far from the fire compartment or where the smoke is at or close to the average temperature in the duct.

A.17.7.6.6.4.1(C) If the depth of wall section above the door is 60 in. (1.52 m) or greater, additional detectors might be required as indicated by an engineering evaluation.




FIGURE A.17.7.6.5.2(a) Pendant-Mounted Air Duct Installation.




FIGURE A.17.7.6.5.2(b) Inlet Tube Orientation.

A.17.7.7.1.2 Airflow through holes in the rear of a smoke detector can interfere with smoke entry to the sensing chamber. Similarly, air from the conduit system can flow around the outside edges of the detector and interfere with smoke reaching the sensing chamber. Additionally, holes in the rear of a detector provide a means for entry of dust, dirt, and insects, each of which can adversely affect the detector's performance.

A.17.7.7.2 For the most effective detection of fire in high-rack storage areas, detectors should be located on the ceiling above each aisle and at intermediate levels in the racks. This is necessary to detect smoke that is trapped in the racks at an early stage of fire development when insufficient thermal energy is released to carry the smoke to the ceiling. Earliest detection of smoke is achieved by locating the intermediate level detectors adjacent to alternate pallet sections as shown in Figure A.17.7.7.2(a) and Figure A.17.7.7.2(b). The detector manufacturer's published instructions and engineering judgment should be followed for specific installations.

A projected beam-type detector can be permitted to be used in lieu of a single row of individual spot-type smoke detectors.




FIGURE A.17.7.7.2(a) Detector Location for Solid Storage (Closed Rack) in Which Transverse and Longitudinal Flue Spaces Are Irregular or Nonexistent, as for Slatted or Solid Shelved Storage.

Sampling ports of an air sampling-type detector can be permitted to be located above each aisle to provide coverage that is equivalent to the location of spot-type detectors. The manufacturer's published instructions and engineering judgment should be followed for the specific installation.

A.17.7.7.3.1 Detectors provided for the control of smoke spread are covered by the requirements of 17.7.6.

A.17.7.7.3.3 Smoke detector spacing depends on the movement of air within the room.

A.17.7.8.3 Facility owners and managers might desire to use cameras and their images for purposes other than smoke detection. The intent of this paragraph is not to prohibit additional uses, but to ensure the integrity of the life safety smoke detection mission of the equipment.

A.17.7.8.4 Video image smoke detection control and software should be protected from tampering by passwords, software keys, or other means of limiting access to authorized/qualified personnel. Component settings include any control or programming that might affect the operation of coverage of the detection. This includes, but is not limited to, camera focus, field of view, motion sensitivity settings, and change of




FIGURE A.17.7.7.2(b) Detector Location for Palletized Storage (Open Rack) or No Shelved Storage in Which Regular Transverse and Longitudinal Flue Spaces Are Maintained.

camera position. Any changes in component settings or ambient conditions that affect the design performance of the detector should initiate a trouble signal.

A.17.8.1 For the purpose of this Code, radiant energy includes the electromagnetic radiation emitted as a by-product of the combustion reaction, which obeys the laws of optics. This includes radiation in the ultraviolet, visible, and infrared portions of the spectrum emitted by flames or glowing embers. These portions of the spectrum are distinguished by wavelengths as shown in Table A.17.8.1.

Table A.17.8.1 Spectrum Wavelength Ranges

Radiant Energy	μm
Ultraviolet	0.1–0.35
Visible	0.36–0.75
Infrared	0.76–220

Conversion factors: 1.0 μm = 1000 nm = 10,000 Å.

A.17.8.2 Following are operating principles for two types of detectors:

- (1) *Flame Detectors.* Ultraviolet flame detectors typically use a vacuum photodiode Geiger-Muller tube to detect the ultraviolet radiation that is produced by a flame. The photodiode allows a burst of current to flow for each ultraviolet photon that hits the active area of the tube. When the number of current bursts per unit time reaches a predetermined level, the detector initiates an alarm. A single wavelength infrared flame detector uses one of several different photocell types to detect the infrared emissions in a single wavelength band that are produced by a flame. These detectors generally include provisions to minimize alarms from commonly occurring infrared sources such as incandescent lighting or sunlight. An ultraviolet/infrared (UV/IR) flame detector senses ultraviolet radiation with a vacuum photodiode tube and a selected wavelength of infrared radiation with a photocell and uses the combined signal to indicate a fire. These detectors need exposure to both types of radiation before an alarm signal can be initiated. A multiple wavelength infrared (IR/IR) flame detector senses radiation at two or more narrow bands of wavelengths in the infrared spectrum. These detectors electronically compare the emissions between the bands and initiate a signal where the relationship between the two bands indicates a fire.
- (2) *Spark/Ember Detectors.* A spark/ember-sensing detector usually uses a solid state photodiode or phototransistor to sense the radiant energy emitted by embers, typically between 0.5 microns and 2.0 microns in normally dark environments. These detectors can be made extremely sensitive (microwatts), and their response times can be made very short (microseconds).

A.17.8.2.1 The radiant energy from a flame or spark/ember is comprised of emissions in various bands of the ultraviolet, visible, and infrared portions of the spectrum. The relative quantities of radiation emitted in each part of the spectrum are determined by the fuel chemistry, the temperature, and the rate of combustion. The detector should be matched to the characteristics of the fire.

Almost all materials that participate in flaming combustion emit ultraviolet radiation to some degree during flaming combustion, whereas only carbon-containing fuels emit significant radiation at the 4.35 micron (carbon dioxide) band used by many detector types to detect a flame. (See Figure A.17.8.2.1.)

The radiant energy emitted from an ember is determined primarily by the fuel temperature (Planck's law emissions) and the emissivity of the fuel. Radiant energy from an ember is primarily infrared and, to a lesser degree, visible in wavelength. In general, embers do not emit ultraviolet energy in significant quantities (0.1 percent of total emissions) until the ember achieves temperatures of 3240°F (1727°C or 2000°K). In most cases, the emissions are included in the band of 0.8 microns to 2.0 microns, corresponding to temperatures of approximately 750°F to 1830°F (398°C to 1000°C).

Most radiant energy detectors have some form of qualification circuitry within them that uses time to help distinguish between spurious, transient signals and legitimate fire alarms. These circuits become very important where the anticipated fire scenario and the ability of the detector to respond to that anticipated fire are considered. For example, a detector that uses an integration circuit or a timing circuit to respond to the

flickering light from a fire might not respond well to a deflagration resulting from the ignition of accumulated combustible vapors and gases, or where the fire is a spark that is traveling up to 328 ft/sec (100 m/sec) past the detector. Under these circumstances, a detector that has a high-speed response capability is most appropriate. On the other hand, in applications where the development of the fire is slower, a detector that uses time for the confirmation of repetitive signals is appropriate. Consequently, the fire growth rate should be considered in selecting the detector. The detector performance should be selected to respond to the anticipated fire.

The radiant emissions are not the only criteria to be considered. The medium between the anticipated fire and the detector is also very important. Different wavelengths of radiant energy are absorbed with varying degrees of efficiency by materials that are suspended in the air or that accumulate on the optical surfaces of the detector. Generally, aerosols and surface deposits reduce the sensitivity of the detector. The detection technology used should take into account those normally occurring aerosols and surface deposits to minimize the reduction of system response between maintenance intervals. It should be noted that the smoke evolved from the combustion of middle and heavy fraction petroleum distillates is highly absorptive in the ultraviolet end of the spectrum. If using this type of detection, the system should be designed to minimize the effect of smoke interference on the response of the detection system.

The environment and ambient conditions anticipated in the area to be protected impact the choice of detector. All detectors have limitations on the range of ambient temperatures over which they will respond, consistent with their tested or approved sensitivities. The designer should make certain that the detector is compatible with the range of ambient temperatures anticipated in the area in which it is installed. In addition, rain, snow, and ice attenuate both ultraviolet and infrared radiation to varying degrees. Where anticipated, provisions should be made to protect the detector from accumulations of these materials on its optical surfaces.

A.17.8.2.2 Normal radiant emissions that are not from a fire can be present in the hazard area. When selecting a detector for an area, other potential sources of radiant emissions should be evaluated. Refer to A.17.8.2.1 for additional information.




FIGURE A.17.8.2.1 Spectrum of Typical Flame (Free-Burning Gasoline).

A.17.8.3.1.1 All optical detectors respond according to the following theoretical equation:

[A.17.8.3.1.1]

$$S = \frac{kP^{-e\zeta d}}{d^2}$$

where:

S = radiant power reaching the detector

k = proportionality constant for the detector

P = radiant power emitted by the fire

e = Napierian logarithm base (2.7183)

ζ = extinction coefficient of air

d = distance between the fire and the detector

The sensitivity (S) typically is measured in nanowatts. This equation yields a family of curves similar to the one shown in Figure A.17.8.3.1.1.

The curve defines the maximum distance at which the detector consistently detects a fire of defined size and fuel. Detectors should be employed only in the shaded area above the curve.

Under the best of conditions, with no atmospheric absorption, the radiant power reaching the detector is reduced by a factor of 4 if the distance between the detector and the fire is doubled. For the consumption of the atmospheric extinction, the exponential term zeta (ζ) is added to the equation. Zeta is a measure of the clarity of the air at the wavelength under consideration. Zeta is affected by humidity, dust, and any other contaminants in the air that are absorbent at the wavelength in question. Zeta generally has values between -0.001 and -0.1 for normal ambient air.




FIGURE A.17.8.3.1.1 Normalized Fire Size vs. Distance.

A.17.8.3.2.1 The following are types of application for which flame detectors are suitable:

- (1) High-ceiling, open-spaced buildings such as warehouses and aircraft hangars
- (2) Outdoor or semioutdoor areas where winds or drafts can prevent smoke from reaching a heat or smoke detector
- (3) Areas where rapidly developing flaming fires can occur, such as aircraft hangars, petrochemical production areas, storage and transfer areas, natural gas installations, paint shops, or solvent areas
- (4) Areas needing high fire risk machinery or installations, often coupled with an automatic gas extinguishing system
- (5) Environments that are unsuitable for other types of detectors

Some extraneous sources of radiant emissions that have been identified as interfering with the stability of flame detectors include the following:

- (1) Sunlight
- (2) Lightning
- (3) X-rays
- (4) Gamma rays
- (5) Cosmic rays
- (6) Ultraviolet radiation from arc welding
- (7) Electromagnetic interference (EMI, RFI)
- (8) Hot objects
- (9) Artificial lighting

A.17.8.3.2.3 The greater the angular displacement of the fire from the optical axis of the detector, the larger the fire must become before it is detected. This phenomenon establishes the field of view of the detector. Figure A.17.8.3.2.3 shows an example of the effective sensitivity versus angular displacement of a flame detector.

A.17.8.3.2.4 Virtually all radiant energy-sensing detectors exhibit some kind of fuel specificity. If burned at uniform rates [W (J/sec)], different fuels emit different levels of radiant power in the ultraviolet, visible, and infrared portions of the spectrum. Under free-burn conditions, a fire of given surface area but of different fuels burns at different rates [W (J/sec)] and emits varying levels of radiation in each of the major portions of the spectrum. Most radiant energy detectors designed to detect flame are qualified on the basis of a defined fire under specific conditions. If employing these detectors for fuels other than the defined fire, the designer should make certain that the appropriate adjustments to the maximum distance between the detector and the fire are made consistent with the fuel specificity of the detector.

A.17.8.3.2.6 This requirement has been satisfied by the following means:

- (1) Lens clarity monitoring and cleaning where a contaminated lens signal is rendered
- (2) Lens air purge

The need to clean detector windows can be reduced by the provision of air purge devices. These devices are not foolproof, however, and are not a replacement for regular inspection and testing. Radiant energy-sensing detectors should not be placed in protective housings (e.g., behind glass) to keep them clean, unless such housings are listed for the purpose. Some optical materials are absorptive at the wavelengths used by the detector.




FIGURE A.17.8.3.2.3 Normalized Sensitivity vs. Angular Displacement.

A.17.8.3.3.1 Spark/ember detectors are installed primarily to detect sparks and embers that could, if allowed to continue to burn, precipitate a much larger fire or explosion. Spark/ember detectors are typically mounted on some form of duct or conveyor; monitoring the fuel as it passes by. Usually, it is necessary to enclose the portion of the conveyor where the detectors are located, as these devices generally require a dark environment. Extraneous sources of radiant emissions that have been identified as interfering with the stability of spark/ember detectors include the following:

- (1) Ambient light
- (2) Electromagnetic interference (EMI, RFI)
- (3) Electrostatic discharge in the fuel stream

A.17.8.3.3.2 There is a minimum ignition power (watts) for all combustible dusts. If the spark or ember is incapable of delivering that quantity of power to the adjacent combustible material (dust), an expanding dust fire cannot occur. The minimum ignition power is determined by the fuel chemistry, fuel particle size, fuel concentration in air, and ambient conditions such as temperature and humidity.

A.17.8.3.3.4 As the distance between the fire and the detector increases, the radiant power reaching the detector decreases. Refer to A.17.8.3.1.1 for additional information.

A.17.8.3.3.5 The greater the angular displacement of the fire from the optical axis of the detector, the larger the fire must become before it is detected. This phenomenon establishes the field of view of the detector. Figure A.17.8.3.2.3 shows an example of the effective sensitivity versus angular displacement of a flame detector.

A.17.8.3.3.6 This requirement has been satisfied by the following means:

- (1) Lens clarity monitoring and cleaning where a contaminated lens signal is rendered
- (2) Lens air purge

A.17.8.5.3 Facility owners and managers might desire to use cameras and their images for purposes other than flame detection. The intent of this paragraph is not to prohibit additional uses, but to ensure the integrity of the life safety flame detection mission of the equipment.

A.17.8.5.4 Video image flame detection control and software should be protected from tampering by passwords, software

keys, or other means of limiting access to authorized/qualified personnel. Component settings include any control or programming that might affect the operation of coverage of the detection. This includes, but is not limited to, camera focus, field of view, motion sensitivity settings, and change of camera position. Any changes in component settings or ambient conditions that affect the design performance of the detector should initiate a trouble signal.

A.17.10.2.4 The engineering evaluation should include, but is not limited to, the following:

- (1) Structural features, size, and shape of the rooms and bays
- (2) Occupancy and uses of areas
- (3) Ceiling heights
- (4) Ceiling shape, surface, and obstructions
- (5) Ventilation
- (6) Ambient environment
- (7) Gas characteristics of the gases present
- (8) Configuration of the contents in the area to be protected
- (9) Response time(s)

A.17.11.2 Examples of such combustion effects are water vapor, ionized molecules, or other phenomena for which they are designed. The performance characteristics of the detector and the area into which it is to be installed should be evaluated to minimize nuisance alarms or conditions that would interfere with operation.

A.17.12.1 Additional documents such as NEMA SB-7, *Applications Guide for Carbon Monoxide Alarms and Detectors*, and the NFPA Fire Protection Research Foundation (FPRF) technical report, *Development of a Technical Basis for Carbon Monoxide Detector Siting*, can also be used as supplemental resources to help with risk assessment, siting, and application considerations.

A.17.12.1(1) Both permanent and temporary carbon-monoxide-producing devices need to be considered when locating carbon monoxide detectors. This includes accounting for all carbon-monoxide-producing appliances and equipment and temporary/mobile equipment, including vehicles, generators, machinery, engines, internal combustion engines, propane equipment, space heaters, engine-driven tools, grills, fire pits, systems used to generate hydrogen, fuel-burning equipment, and any other permanent and/or transient-type equipment and appliances that can be sources of carbon monoxide.

By placing carbon monoxide detectors close to all permanent as well as all temporary carbon-monoxide-producing sources, early detection of carbon monoxide is more likely to occur. Detectors should therefore be located as close as practicable to the carbon-monoxide-producing source, taking into account such factors as detector accessibility for inspection, testing, and maintenance; potential sources of detector damage or contamination; potential nuisance alarm sources; transient backdrafting spillage of flue gases during startup and operation; and ventilation supply and exhaust vents. For early detection, carbon monoxide detectors should be located on the ceiling over carbon-monoxide-producing sources. There is often some buoyancy of the heated combustion gases that can help carry the carbon monoxide to the detector.

Carbon monoxide detectors should also be considered throughout the room/space that contains the carbon-monoxide-producing source to help address either limited or no buoyancy of the carbon monoxide, adverse impacts by HVAC systems, as well as ambient airflows in the space that can

carry carbon monoxide away from the source rather than up to the ceiling directly over the source.

A.17.12.1(2) Carbon monoxide can follow flow paths from its original source to adjacent areas in the building, including moving horizontally and vertically throughout the space, building, and structure, and where carbon monoxide detectors should be located in these adjacent areas needs to be considered. Detector location and spacing should be based on an engineering evaluation that considers potential sources and migration of carbon monoxide, including through exhaust ductwork, HVAC equipment, openings in walls and floors, unprotected penetrations, and elevator shafts.

As some of the higher carbon monoxide concentrations are often at the source and within the exhaust ductwork and venting equipment, carbon monoxide detectors should be located along the exhaust path of any carbon-monoxide-producing equipment, appliances, and so forth, extending from the source of the carbon monoxide through the building to the termination of the exhaust at an exterior wall or roof. This should include detectors along any duct branch lines and interconnections to any ductwork and piping used in the exhaust system so carbon monoxide that might exist outside the exhaust path (due to leaks, damage, obstructions, rust, corrosion, etc.) can be detected.

The impact of HVAC systems should be taken into account when locating carbon monoxide detectors. HVAC systems can transport as well as mix and dilute carbon monoxide. Consideration should be given to the layout and operation of the HVAC system and whether the HVAC is constantly running or only runs for a portion of the time and, therefore, is not constantly distributing or mixing air in the building. When locating carbon monoxide detectors, other considerations include the presence and impact of closed doors and walls. These can compartmentalize areas within an individual HVAC zone or floor and prevent spread. Their presence can also allow carbon monoxide to accumulate more rapidly in given areas if doors are closed to contain it and not allow it to spread and dilute the concentration.

Carbon monoxide can potentially enter the building from an exterior source, such as through make-up air systems. Some of the external sources that should be considered when locating carbon monoxide detectors include adjacent structures, exterior systems, equipment such as vehicles and generators, and interconnections to underground spaces or parking garages.

A.17.12.1(3) Carbon monoxide detectors should be considered within each bedroom, dwelling unit, guest room, guest suite, and sleeping area, as well as the potential for multiple detectors in multiroom suites. Additional detectors in these spaces can provide more appropriate protection for people while awake or asleep.

A.17.12.1(4) Carbon monoxide detectors should also be located and installed as recommended by the manufacturer's published instructions, including those specific requirements for the spacing between detectors, minimum/maximum spacings to walls and obstructions, minimum/maximum height of a detector in a space, minimum/maximum distances to HVAC vents, reductions in spacing required for high ceilings, and other pertinent information required to help properly design, assess, and install detectors to achieve their intent of detecting carbon monoxide early on to warn occupants of a hazard.

A.17.12.3 At present there is no product performance listing for duct-mounted carbon monoxide detectors because there is no peer-reviewed research to determine what the alarm thresholds for duct-mounted carbon monoxide detectors should be. There are considerable differences between the operation of a spot-type carbon monoxide detector and a duct-mounted carbon monoxide detector. The environment in ducts can be very harsh and could impact the carbon monoxide detector's sensing element. Furthermore, in most buildings, there are periods when the HVAC system is not moving significant quantities of air from the compartments it serves. As a result, the carbon monoxide detection system cannot be designed to rely on the HVAC system operation for the transport of carbon monoxide to the carbon monoxide detectors.

A.17.13.1 Piping between the sprinkler system and a pressure actuated alarm-initiating device should be galvanized or of nonferrous metal or other approved corrosion-resistant material of not less than $\frac{3}{8}$ in. (9.5 mm) nominal pipe size.

A.17.13.2 The waterflow device or the combination of the waterflow devices and fire alarm system should be field configurable so that an alarm is initiated no more than 90 seconds after a sustained flow of at least 10 gpm (40 L/min).

Features that should be investigated to minimize alarm response time include the following:

- (1) Elimination of trapped air in the sprinkler system piping
- (2) Use of an excess pressure pump
- (3) Use of pressure drop alarm-initiating devices
- (4) A combination thereof

Care should be used when choosing waterflow alarm-initiating devices for hydraulically calculated looped systems and those systems using small orifice sprinklers. Such systems might incorporate a single point flow of significantly less than 10 gpm (40 L/min). In such cases, additional waterflow alarm-initiating devices or the use of pressure drop-type waterflow alarm-initiating devices might be necessary.

Care should be used when choosing waterflow alarm-initiating devices for sprinkler systems that use on-off sprinklers to ensure that an alarm is initiated in the event of a waterflow condition. On-off sprinklers open at a predetermined temperature and close when the temperature reaches a predetermined lower temperature. With certain types of fires, waterflow might occur in a series of short bursts of a duration of 10 seconds to 30 seconds each. An alarm-initiating device with retard might not detect waterflow under these conditions. An excess pressure system or a system that operates on pressure drop should be considered to facilitate waterflow detection on sprinkler systems that use on-off sprinklers.

Excess pressure systems can be used with or without alarm valves. The following is a description of one type of excess pressure system with an alarm valve.

An excess pressure system with an alarm valve consists of an excess pressure pump with pressure switches to control the operation of the pump. The inlet of the pump is connected to the supply side of the alarm valve, and the outlet is connected to the sprinkler system. The pump control pressure switch is of the differential type, maintaining the sprinkler system pressure above the main pressure by a constant amount. Another switch monitors low sprinkler system pressure to initiate a supervisory signal in the event of a failure of the pump or other malfunction. An additional pressure switch can be used to stop pump

operation in the event of a deficiency in water supply. Another pressure switch is connected to the alarm outlet of the alarm valve to initiate a waterflow alarm signal when waterflow exists. This type of system also inherently prevents false alarms due to water surges. The sprinkler retard chamber should be eliminated to enhance the detection capability of the system for short duration flows.

A.17.14 Alarm initiation can be accomplished by devices that detect the following:

- (1) Flow of water in foam systems
- (2) Pump activation
- (3) Differential pressure
- (4) Pressure (e.g., clean agent systems, carbon dioxide systems, and wet/dry chemical systems)
- (5) Mechanical operation of a release mechanism

A.17.15.8 Protective covers, also called pull station protectors can be installed over manually actuated alarm initiating devices to provide mechanical protection, environmental protection, and to reduce the likelihood of accidental or malicious activation. The protective covers must be listed to ensure that they do not hinder the operation of the pull stations and to ensure that they meet accessibility requirements for activation by persons with physical disabilities. The Code explicitly permits installing them over single- or double-action devices. When installed over a double-action device, the assembly effectively becomes a triple-action device. Some units include battery-operated audible warning signals that have been shown to deter malicious activations. To be effective, it is important that the regular staff or occupants be aware of the sound and investigate immediately in order to catch someone who might otherwise actuate the device without cause or to ensure that the device is actuated if there is a legitimate reason.

A.17.15.9.3 In environments where red paint or red plastic is not suitable, an alternative material, such as stainless steel, could be used as long as the box meets the requirements of 17.15.9.2.

A.17.15.9.5 It is not the intent of 17.15.9.5 to require manual fire alarm boxes to be attached to movable partitions or to equipment, nor to require the installation of permanent structures for mounting purposes only.

A.17.17.2.2.2 Some dry pipe and preaction sprinkler systems use lower air pressures in the range of 8 psi to 15 psi (0.5 bar to 1.0 bar), instead of the traditional 40 psi (2.7 bar). A plus or minus value of 10 psi (0.7 bar) is not appropriate for these systems and could result in dry pipe valve actuation prior to transmission of a low air pressure supervisory signal.

A.18.1 Notification appliances should be sufficient in quantity, audibility, intelligibility, and visibility so as to reliably convey the intended information to the intended personnel during an emergency.

Notification appliances in conventional commercial and industrial applications should be installed in accordance with the specific requirements of Sections 18.4 and 18.5.

The Code recognizes that it is not possible to identify specific criteria sufficient to ensure effective occupant notification in every conceivable application. If the specific criteria of Sections 18.4 and 18.5 are determined to be inadequate or inappropriate to provide the performance recommended,

approved alternative approaches or methods are permitted to be used.

Designers and AHJs are advised to consider alternative means in occupancies that have individuals with cognitive disabilities. In addition, persons responsible for evacuation planning should consider specific training for individuals with cognitive disabilities to familiarize them with audible and visual signals and what responses are necessary based on their capabilities and any alternative means used.

A.18.1.5 Chapter 18 establishes the means, methods, and performance requirements of notification appliances and systems. Chapter 18 does not require the installation of notification appliances or identify where notification signaling is required. Authorities having jurisdiction, other codes, other standards, and chapters of this Code require notification signaling and might specify areas or intended audiences.

For example, Chapter 10 requires audible and visible trouble signals at specific locations. A building or fire code might require audible and visual notification throughout all occupiable areas. In contrast, a building or fire code might require complete coverage with audible signaling, but might only require specific areas or spaces to have visual signaling. It is also possible that a referring code or standard might require compliance with mounting and notification appliance performance requirements without requiring complete notification signaling system performance. An example might be where an appliance is specifically located to provide information or notification to a person at a specific desk within a larger room.

A.18.3.3.2 The intent is to prohibit labeling that could give an incorrect message. Wording such as "Emergency" would be acceptable for labeling because it is generic enough not to cause confusion. Fire alarm systems are often used as emergency notification systems, and therefore attention should be given to this detail.

Combination audible and visual notification appliances are permitted to have multiple visual elements each labeled differently or not labeled at all.

A.18.3.4 Situations exist where supplemental enclosures are necessary to protect the physical integrity of a notification appliance. Protective enclosures should not interfere with the performance characteristics of the appliance. If the enclosure degrades the performance, methods should be detailed in the manufacturer's published instructions of the enclosure that clearly identify the degradation. For example, where the appliance signal is attenuated, it might be necessary to adjust the appliance spacings or appliance output.

A.18.3.6 For hardwired appliances, terminals or leads, as described in 18.3.6, are necessary to ensure that the wire run is broken and that the individual connections are made to the leads or other terminals for signaling and power.

A common terminal can be used for connection of incoming and outgoing wires. However, the design and construction of the terminal should not permit an uninsulated section of a single conductor to be looped around the terminal and to serve as two separate connections. For example, a notched clamping plate under a single securing screw is acceptable only if separate conductors of a notification circuit are intended to be inserted in each notch. [See Figure A.17.4.6(a).]

Another means to monitor the integrity of a connection is to establish communication between the appliance and the control unit. The integrity of the connection is verified by the presence of communication. Monitoring integrity in this fashion might not require multiple terminals or leads, as previously described.

It should be noted that monitoring the integrity of the installation conductors and their connection to an appliance does not guarantee the integrity of the appliance or that it is operational. Appliances can be damaged and become inoperable or a circuit can be overloaded, resulting in failure when the appliances are called upon to work. Presently, only testing can establish the integrity of an appliance.

A.18.3.7.1 Notification Appliances. The goal of a properly designed, installed, and maintained signaling system is to ensure that the notification appliances will operate at the required output (e.g., sound pressure level, candela output, synchronization, and so on) and durations during expected system operations.

A key component of a notification appliance is its power consumption. The designer must account for the minimum and maximum power specifications of an appliance. Product certification laboratory regulated-class 24 VDC appliances must operate at a low of 16 VDC and at a maximum of 33 VDC to ensure its output characteristics are correct. For example, too low of a voltage at the appliance might result in visual appliances losing synchronization or audible appliances having low or no output.

When designing direct-current NACs, the appliance nameplate (listed) voltage and current consumption values are used. This will be the maximum current over the voltage range of the product.

For audio NACs, the appliance voltage and wattage settings will provide a given sound output. This will typically be 25.2 or 70.7 VAC with a wattage tap and anticipated associated sound output level.

Power Sources. The type of power supply will impact the system design and operation. The system output, overcurrent protection methods, loading ratings/factors, inrush capabilities, and voltages should be evaluated. Some power supplies have their worst-case output condition at brownout, which is when the incoming AC mains are at their lowest value, just before the power supply transfers to battery power. The manufacturer's documentation and direction should be adhered to.

Control unit start terminal voltage is the lowest possible voltage applied to the notification appliance circuit in any condition of primary or secondary power.

Audio Circuits. Audio circuits, when active, use alternating current (ac). The method to calculate the line loss is based on the permitted electrical decibel loss (0.5 dB) and can be calculated with the following equations:

$$[A.18.3.7.1a]$$

$$\text{dB circuit loss} = (20 * \text{LOG}_{10}(\text{Load Impedance} / (\text{Load Impedance} + \text{Circuit Resistance})))$$

$$[A.18.3.7.1b]$$

$$\text{Load Impedance} = \text{Circuit Voltage}^2 / \text{Circuit Wattage}$$

An example of this dB circuit loss for a 70.7 Vrms system with a 16-watt connected load (19.2-watt calculated load) on 16 AWG stranded wire would work out to be as follows:

$$[A.18.3.7.1c]$$

$$-0.15738 = 20 * \text{LOG}_{10}(260.338 / (260.338 + 4.76))$$

Where the Load Impedance is calculated to be:

$$[A.18.3.7.1d]$$

$$260.338 = 70.7^2 / 19.2$$

To calculate wire length based on a given load, the following equation can be used:

$$[A.18.3.7.1e]$$

$$R_L = \frac{V^2}{P} = \text{Load Resistance (W)}$$

where:

R_L = Load resistance

V = Amplifier output voltage (V)

P = Power in load (W)

To solve for wire resistance, wire resistance (R_W) is converted to wire length as follows:

$$[A.18.3.7.1f]$$

$$D = \frac{R_W}{R_{/1000 \text{ ft pair}}} \times 1000$$

where:

D = Distance in feet

R_W = Maximum allowable wire resistance

$R_{/1000 \text{ ft pair}}$ = Wire resistance per 1000 ft pair

For a 0.5 dB loss calculation, the equation is:

$$[A.18.3.7.1g]$$

$$\text{Max length} = \frac{59.25 \times \text{Amplifier output}^2}{\text{Wire resistance} \times \text{Circuit load}}$$

where:

Amplifier = Signal level in Vrms supplied by the amplifier during the circuit

Wire resistance = Resistance rating of the wire per 1000 ft (300 m) pair

Circuit load = Total watts required by the audio circuit

For 25.2 Vrms systems, the maximum circuit length based on the wire resistance is as follows:

$$[A.18.3.7.1h]$$

$$\frac{59.25 \times 635}{(\text{Wire resistance} \times \text{Circuit load})}$$

For 70.7 Vrms systems, the maximum circuit length based on the wire resistance is as follows:

$$\frac{59.25 \times 4998}{(\text{Wire resistance} \times \text{Circuit load})} \quad [\text{A.18.3.7.1i}]$$

Field Control Modules. Some systems use field control modules (FCM) to control a NAC. FCMs are not a direct part of a control unit. These field-installed modules are typically addressable and provide electrical supervision of the NAC or might provide some control of the DC or AC power riser coming into or exiting the FCM. Any module or device that is in the power riser electrical path or that could impact the performance of the riser should be accounted for in the system design, installation, and testing. Other examples of FCMs include, but are not limited to, the following:

- (1) Relays
- (2) Coders
- (3) Supervision
- (4) Synchronization

For an FCM on a direct-current NAC, the following is the formula for the unit:

$$\text{Field Control Module Start Voltage (FCMSTV)} = \text{Riser Terminal Voltage} \pm \text{FCM Internal Circuitry Adjustment} \quad [\text{A.18.3.7.1j}]$$

For example:

$$17.4 \text{ V (FCMSTV)} = 18.1 \text{ V (FCM Riser Input Voltage)} - 0.7 \text{ (MVA)} \quad [\text{A.18.3.7.1k}]$$

For an FCM on an audio NAC, the dB insertion loss must be factored into the circuit total dB loss.

Voltage Drop Calculations. This is the key design factor. There are two acceptable methods as follows:

- (1) *End line loading (ELL).* This assumes that all the appliances are at the end of the circuit and are activated at one time. This is the most conservative method and is the recommended design method for all systems. ELL circuits are designed and tested based on the total circuit resistance and loss.
- (2) *Point-to-point (PTP).* This method requires that the designer know the exact wire distance between each and every appliance. If the installed values are different than the design values, the circuit might not work correctly. This method requires close coordination with the design and field work. PTP circuits are designed based on the individual segment and tested on total resistance and loss.

A.18.4.1.1 The Code does not require that all audible notification appliances within a building be of the same type. However, a mixture of different types of audible notification appliances within a space is not the desired method. Audible notification appliances that convey a similar audible signal are preferred. For example, a space that uses mechanical horns and bells might not be desirable. A space that is provided with mechanical horns and electronic horns with similar audible signal output is preferred.

However, the cost of replacing all existing appliances to match new appliances can impose substantial economic impact where other methods can be used to avoid occupant confusion of signals and signal content. Examples of other methods used to avoid confusion include, but are not limited to, training of occupants, signage, consistent use of temporal code signal pattern, and fire drills.

Hearing protection can attenuate both the ambient noise level and the audible signal. Specifications from hearing protection manufacturers might allow the effect of hearing protection devices to be evaluated. In spaces where hearing protection is worn due to high ambient noise conditions, visual notification appliances should be considered.

In addition, where hearing protection is worn due to high ambient noise conditions, the audible signal and ambient noise measurements can be analyzed and the audible signal can be adjusted to account for attenuation caused by the hearing protection devices.

A.18.4.1.2 The maximum sound pressure level permitted in a space is 110 dBA. In the 2007 edition, this was reduced from 120 dBA in previous editions. The change from 120 dBA to 110 dBA was made to coordinate with other laws, codes, and standards.

In addition to the danger of exposure to a high sound level, long-term exposure to lower levels could also be a problem when, for example, occupants must traverse long egress paths to exit or technicians test large systems over extended time periods.

This Code does not presume to know how long a person will be exposed to an audible notification system. The limit of 110 dBA has been set as a reasonable upper limit for the performance of a system. For workers who could be exposed to high sound levels over the course of a 40-year employment history, OSHA (Occupational, Health and Safety Administration) has established a maximum permitted dose before a hearing conservation program must be implemented. A worker exposed to 120 dBA for 7.5 minutes a day for 40 years might be in danger of suffering a hearing impairment. The OSHA regulation includes a formula to calculate a dose for situations where a person is exposed to different sound levels for different periods of time. The maximum permitted by the regulation is an 8-hour equivalent dose of 90 dBA. It is possible to calculate the dose a person experiences when traversing an egress path where the sound pressure level varies as he/she passes close to, then away from, audible appliances. Table A.18.4.1.2 depicts OSHA permissible noise exposures.

A.18.4.1.3 In determining maximum ambient sound levels, sound sources that should be considered include air-handling equipment and background music in a typical office environment, office cleaning equipment (vacuum cleaner), noisy children in a school auditorium, car engines in an auto shop, conveyor belts in a warehouse, and a running shower and fan in a hotel bathroom. Temporary or abnormal sound sources that can be excluded would include internal or external construction activities (i.e., office rearrangements and construction equipment).

A.18.4.1.5.1 Audibility of a fire or emergency signal might not be required in all rooms and spaces. For example, a system that is used for general occupant notification should not require audibility of the signal in closets and other spaces that are not

Table A.18.4.1.2 Permissible Noise Exposures

Duration (hr)	L_A (dBA)
8	90
6	92
4	95
3	97
2	100
1.5	102
1	105
0.5	110
0.25	115
0.125 (7.5 minutes)	120

Source: OSHA, 29 CFR 1910.5, Table G-16, Occupational Noise Exposure.

considered as occupiable spaces. However, a space of the same size used as a file room would be considered occupiable and should have coverage by notification appliances. Also, signaling intended only for staff or emergency forces might only have to be effective in very specific locations.

A.18.4.1.6 Because voice is composed of modulated tones, it is not valid to compare loudness measurements of tone signals with loudness measurements of voice signals. A voice signal that is subjectively judged to be equally as loud as a tone signal will actually produce a dB reading below that of the tone signal. The modulated tones of a voice signal can have the same or greater peak amplitude as that of a tone signal. However, because voice signals are modulated meters with fast or slow time, constants will show a lower dB or dBA reading.

A voice signal must have sufficient audibility to result in intelligible communication. Intelligibility modeling/measurements (subject based and instrument based) include audibility as well as many other factors when determining whether a voice signal is adequate or not adequate.

A.18.4.2.1 Section 10.10 requires that alarm signals be distinctive in sound from other signals and that this sound not be used for any other purpose. The use of the distinctive three-pulse temporal pattern signal required by 18.4.2.1 became effective July 1, 1996, for new systems installed after that date. It is not the intent to prohibit continued use of an existing consistent evacuation signaling scheme, subject to approval by the authority having jurisdiction. It is also not the intent that the distinct pattern be applied to visible appliances.

Prior to the 2013 edition, the use of the temporal code 3 distinctive evacuation signal was intended only where evacuation of the building was the intended response. In order to eliminate the need for additional signals to mean “relocate,” the signal is now permitted to be used where relocation or partial evacuation is the intended response. The simple result is people should not be in any area where the signal is sounding and that it is safe to be anywhere that signal is not sounding.

The temporal pattern can be produced by any audible notification appliance, as illustrated in Figure A.18.4.2.1(a) and Figure A.18.4.2.1(b).

A.18.4.2.2 The purpose of a minimum ring time is to assure that occupants have time to hear, understand, and act. When a signal stops, occupants might assume that no threat exists.




FIGURE A.18.4.2.1(a) Temporal Pattern Imposed on Signaling Appliances That Emit Continuous Signal While Energized.




FIGURE A.18.4.2.1(b) Temporal Pattern Imposed on Single-Stroke Bell or Chime.

Some jurisdictions might require longer ring times. Others might require visual appliances to continue to flash when audible signals have been silenced. Different jurisdictions and different buildings/areas require different emergency plans. Thus, the Code minimum ring time should be allowed to be different when approved by the AHJ. The Code specifically permits manual interruption. A jurisdiction might have an ordinance that does not allow owners/occupant to interrupt the signal, but would allow first responders to use the system as needed. In other cases, an approved emergency preparedness and emergency action plan might allow for manual interruption of the signal. The Code also has an allowance for MNS messages to interrupt the minimum ring time.

A.18.4.2.5 Coordination or synchronization of the audible signal within a notification zone is needed to preserve the temporal pattern. It is unlikely that the audible signal in one evacuation/notification zone will be heard in another at a level that will destroy the temporal pattern. Thus, it would not normally be necessary to provide coordination or synchronization for an entire system. Caution should be used in spaces such as atriums, where the sounds produced in one notification zone can be sufficient to cause confusion regarding the temporal pattern.

A.18.4.4 The typical average ambient sound level for the occupancies specified in Table A.18.4.4 are intended only for design guidance purposes. The typical average ambient sound levels specified should not be used in lieu of actual sound level measurements.

Sound levels can be significantly reduced due to distance and losses through building elements. Every time the distance from the source doubles, the sound level decreases by about 6 decibels (dB). Audible notification appliances are typically rated by manufacturers' and testing agencies at 10 ft (3 m) from the appliance. Subsequently, at a distance of 20 ft (6.1 m) from an audible appliance rated at 84 dBA, the sound level might be reduced to 78 dBA. At a closed door, the loss might be about 10 dB to 24 dB or more depending on construction. If the opening around the door is sealed, this might result in a loss of 22 dB to 34 dB or more.

Table A.18.4.4 Average Ambient Sound Level According to Location

Location	Average Ambient Sound Level (dBA)
Business occupancies	54
Educational occupancies	45
Industrial occupancies	88
Institutional occupancies	50
Mercantile occupancies	40
Mechanical rooms	91
Piers and water-surrounded structures	40
Places of assembly	60
Residential occupancies	35
Storage occupancies	30
Thoroughfares, high-density urban	70
Thoroughfares, medium-density urban	55
Thoroughfares, rural and suburban	40
Tower occupancies	35
Underground structures and windowless buildings	40
Vehicles and vessels	50

A.18.4.4.1 Audio levels are commonly measured using units of decibels, or $\frac{1}{10}$ Bell, abbreviated dB. When measured using a sound level meter, the operator can select either an A-weighted, B-weighted, or C-weighted measurement. The C-weighted measurement is nominally flat from 70 Hz to 4000 Hz, and the B-weighted measurement is nominally flat from 300 Hz to 4000 Hz. The A-weighted measurement filters the input signal to reduce the measurement sensitivity for frequencies to which the human ear is less sensitive and is relatively flat from 600 Hz to 7000 Hz. This results in a measurement that is weighted to simulate the segment of the audio spectrum that provides the most significant intelligibility components heard by the human ear. The units used for measurement are still dB, but the shorthand for specifying use of the A-weighted filter is typically dBA. The difference between any two sound levels measured on the same scale is always expressed in units of dB, not dBA.

The constantly changing nature of pressure waves, which are detected by ear, can be measured by electronic sound meters, and the resulting electronic waveforms can be processed and presented in a number of meaningful ways. Most simple sound level meters have a fast or slow time constant (125 ms and 1000 ms, respectively) to quickly average a sound signal and present a root mean square (RMS) level to the meter movement or display. This is the type of measurement used to determine the maximum sound level having a duration of at least 60 seconds. Note that Chapter 14 requires this measurement to be made using the FAST time setting on the meter. However, this quick average of impressed sound results in fast movements of the meter's output that are best seen when talking into the microphone; the meter quickly rises and falls with speech. However, when surveying the ambient sound levels to establish the increased level at which a notification appliance will properly function, the sound source needs to be averaged over a longer period of time. See 3.3.31, Average Ambient Sound Level. Moderately priced sound level meters have such a function, usually called L_{eq} or equivalent sound level. For example, an L_{eq} of speech in a quiet room would cause the meter

movement to rise gradually to a peak reading and slowly fall well after the speech is over. L_{eq} measurements are made over a specified time period and reported as $L_{eq,t}$ where t is the time period. For example, a measurement taken over 24 hours is reported as L_{eq24} .

L_{eq} readings can be misapplied in situations where the background ambient noises vary greatly during a 24-hour period. L_{eq} measurements should be taken over the period of occupancy. This is clarified by the definition of average ambient sound level (see 3.3.31). Note that average in this context is the integrated average at a particular measurement location, not the average of several readings taken at different locations. For example, it would be incorrect to take a reading in a quiet bathroom and average it with a reading taken near a noisy machine to get an average to use for the alarm signal design. The alarm would probably be excessively loud in the quiet bathroom and not loud enough near the noisy machine.

In areas where the background noise is generated by machinery and is fairly constant, a frequency analysis can be warranted. It might be found that the high sound levels are predominantly in one or two frequency bandwidths — often lower frequencies. Notification appliances producing sound in one or two other frequency bandwidths can adequately penetrate the background noise and provide notification. The system would still be designed to produce or have a sound level at the particular frequency or frequency bandwidth of at least 15 dB above the average ambient sound level or 5 dB above the maximum sound level having a duration of at least 60 seconds, whichever is greater.

In very high noise areas, such as theaters, dance halls, nightclubs, and machine shops, sound levels during occupied times can be 100 dBA and higher. Peak sounds might be 110 dBA or greater. At other occupied times, the sound level might be below 50 dBA. A system designed to have a sound level of at least 15 dB above the average ambient sound level or 5 dB above the maximum sound level having a duration of at least 60 seconds might result in a required sound pressure level in excess of the maximum of 110 dBA. A viable option is to reduce or eliminate the background noise. Professional theaters or other entertainment venues can have road show connection control units (see Section 520.50 of NFPA 70) to which troupes can connect their light and sound systems. These power sources can be controlled by the system. In less formal applications, such as many nightclubs, designated power circuits could be controlled. Diligence needs to be exercised to ensure that the controlled circuits are used.

Also, in occupancies such as machine shops or other production facilities, care must be exercised in the design to ensure that the removal of power to the noise source does not create some other hazard. As with other emergency control functions, control circuits and relays would be monitored for integrity in accordance with Chapter 10, Chapter 12, and Chapter 23.

Appropriate audible signaling in high ambient noise areas is often difficult. Areas such as automotive assembly areas, machining areas, paint spray areas, and so on, where the ambient noise is caused by the manufacturing process itself, require special consideration. Adding additional audible notification appliances that merely contribute to the already noisy environment might not be appropriate. Other alerting techniques such as visual notification appliances, for example, could be more effectively used.

Other codes, standards, laws, or regulations, and the authority having jurisdiction determine where a signal must be audible. This Code section describes the performance requirement needed for a signal to be considered reliably audible.

A.18.4.4.3 Elevator cars are not required to have audible appliances. If they are provided, they can be designed at the lower levels permitted for private mode signaling. Note that for a protected premises fire alarm system, 23.8.6.2.4 explicitly states that the signal is not required to operate in elevator cars. Similarly, for in-building fire emergency voice/alarm communications systems (EVACS), 24.4.8.5 permits audible appliances to be installed, but requires that the evacuation signal not operate in the elevators. This permits loudspeakers to be installed and used for manual communication to elevator occupants.

A.18.4.4.5.3 In facilities where an amplified sound system is used for music and other voice amplification, such as live performances in theaters, auditoriums, and so on, and there are audible notification appliances installed at the same area of the facility, a fire alarm control relay or interface should be provided to automatically shut down the amplified music or voice system upon activation of the audible notification appliances. This automatic shutdown of the nonemergency sound system should be performed to allow for the emergency fire alarm system signal to sound and be audible to the occupants of the facility.

A.18.4.5.1 See A.18.4.4.1 for additional information on sound measurements and weighting scales.

A.18.4.5.2 For example, in critical care patient areas, it is often desirable to not have an audible notification even at reduced private mode levels. Each case requires consideration by the governing authority. Another example would be high noise work areas where an audible signal needed to overcome background noise at one time of day would be excessively loud and potentially dangerous at another time of lower ambient noise. A sudden increase of more than 30 dB over 0.5 seconds is considered to cause sudden and potentially dangerous fright.

A.18.4.6.1 See A.18.4.4.1 for additional information on sound measurements and weighting scales.

Chapter 18 addresses notification appliances connected to and controlled by a fire alarm or emergency communications system. This chapter does not address dwelling-unit protection, such as smoke alarms, and their audible signal characteristics. Requirements for single- and multiple-station alarms and household fire alarm systems can be found in Chapter 29.

The intent of 18.4.6.1 is to require the use of the low-frequency signal in areas intended for sleeping and in areas that might reasonably be used for sleeping. Some of these rooms/areas include the following:

- (1) Hotel guest rooms
- (2) Common spaces of a hotel suite, such as living rooms, that have couches, beds, or sleeping furniture
- (3) Common spaces within dwelling units, such as living rooms or dens, that have couches, beds, or sleeping furniture
- (4) Areas and rooms with Murphy beds
- (5) Doctor/staff sleeping rooms
- (6) Nap rooms or sleeping areas in any occupancy

Sleeping areas that are provided with constant awake staff are not required to be provided with low-frequency audible

notification appliances. Paragraph 18.4.6.1 does not require low-frequency notification in hallways, lobbies, and other tenantless spaces.

It is not the intent of 18.4.6.1 to preclude appliances or devices that have been demonstrated through peer-reviewed research to awaken occupants with hearing loss as effectively as those using the frequency and amplitude specified in 18.4.6.1.

All notification appliances and notification systems should be listed for low-frequency operation.

For increased protection in the sleeping area, tactile notification in accordance with Section 18.10 might be an effective means of awakening those who have normal hearing, as well as those who are hearing impaired.

A.18.4.6.3 The intent of this section is to require the use of the low frequency signal in areas intended for sleeping and in areas that might reasonably be used for sleeping. For example, this section requires a low frequency audible signal in a bedroom of an apartment and also in the living room area of an apartment as it might have sleeping occupants. However, it would not be required to use the low frequency signal in the hallways, lobby, and other tenantless spaces. In hotels, the guest rooms would require use of the low frequency signals, but other spaces that might require audible signals could use any listed audible appliances regardless of the frequency content of the signal being produced. This chapter of the Code addresses notification appliances connected to and controlled by a fire alarm or emergency communications system. This chapter does not address dwelling unit protection such as smoke alarms and their audible signal characteristics. Requirements for single- and multiple-station alarms and household fire alarm systems can be found in Chapter 29.

It is not the intent of this section to preclude devices that have been demonstrated through peer-reviewed research to awaken occupants with hearing loss as effectively as those using the frequency and amplitude specified in this section.

Non-voice (e.g., horns) notification appliances should be listed as a "low frequency alarm" alarm appliance. Voice appliances and systems should be capable of 520 Hz $\pm$ 10 percent with the appropriate harmonics.

For increased protection in the sleeping area, tactile notification in accordance with Section 18.10 might be an effective means of awakening those who have normal hearing, as well as those who are hearing impaired.

A.18.4.6.3(2) For the purposes of awakening, the low frequency signal can be produced by a listed stand-alone appliance or by a listed system consisting of a recorded waveform delivered through an amplifier and loudspeaker.

A.18.4.7 This subsection permits a more rigorous analysis and design for audible signaling. Acoustic design practice and psychoacoustic research have long recognized that for a signal to be audible, it need only penetrate the background noise in a one-third or a one octave band. The averaging resulting from A-weighted analysis and design is a simplification that often results in systems being overdesigned. This overdesign is not dangerous but can be costly and is certainly not needed for effective system performance.

A.18.4.7.2 Noise at a lower frequency can mask a signal at an adjacent higher frequency. Thus, it is necessary to calculate the effective masked level of the noise in accordance with estab-

lished procedures. Figure A.18.4.7.2 shows an example of an octave band analysis of noise along with the calculated effective masked threshold and the proposed alarm signal.

A.18.4.8.1 The sound content of directional sounders is very different from that of the traditional fire alarm audible notification appliances. Traditional fire alarm audible notification appliances have a strong tonal content, usually centered near the 3 kHz region. Directional sounders use broadband frequency content, usually covering most of the human audible frequency range, 20 Hz to 20 kHz. Figure A.18.4.8.1(a) compares the frequency content of a traditional fire alarm audible notification appliance to a directional sounder. This figure shows that while the fire alarm audible notification appliance clearly dominates the 3 kHz and upper harmonics, the broadband content of the directional sounder is 20 dB to 30 dB in other frequency bands or ranges. The fire alarm has an overall A-weighted sound level greater than the directional sounder and will be perceived as being louder. However, since the directional sounder has a wide spectral range, the signal penetrates the fire alarm signal in several other frequency bands as permitted by 18.4.7.

There are three main types of information that allow the brain to identify the location of a sound. The first two are known as binaural cues because they make use of the fact that we have two ears, separated by the width of our head. A sound that emanates from either side of the mid-line will arrive first at the ear closer to it and will be loudest at the ear closer to it. At low frequencies the brain recognizes differences in the arrival time of sound between the ears (interaural time differences). At higher frequencies the salient signal is the loudness/intensity difference between the sounds at each ear (interaural intensity differences). Refer to Figure A.18.4.8.1(b). For single frequencies, these cues are spatially ambiguous.


The inherent ambiguity has been described as the “cone of confusion.” This arises from the fact that for any given frequency there are numerous spatial positions that generate

identical timing/intensity differences. These can be graphically represented in the form of a cone, the apex of which is at the level of the external ear. The cone of confusion is the main reason for our not being able to localize pure tones.

The final piece of sound localization information processed by the brain is the head-related transfer function (HRTF). The HRTF refers to the effect the external ear has on sound. As a result of passing over the bumps or convolutions of the pinna, the sound is modified so that some frequencies are attenuated and others are amplified. Refer to Figure A.18.4.8.1(c). Although there are certain generalities in the way the pinnae modify sound, the HRTF is unique to each individual. The role of the HRTF is particularly important when determining whether a sound is in front of or behind us. In this instance the timing and intensity differences are negligible, and there is consequently very little information available to the central nervous system on which to base this decision. To locate the direction of a sound source, the larger the frequency content to overcome the ambiguities inherent to single tones, the better the accuracy.


A.18.4.8.2 ITD: A difference in arrival times of waveform features (such as peaks and positive-going zero crossings) at the two ears is known as the interaural time difference, or ITD. The binaural physiology is capable of using phase information from ITD cues only at low frequencies below about 1500 Hz. However, the binaural system can successfully register an ITD that occurs at a high frequency such as 4000 Hz if the signal is modulated. The modulation, in turn, must have a rate that is less than about 1000 Hz.

ILD: Comparison between intensities in the left and right ears is known as the interaural level difference, or ILD. ILD cues exist physically only for frequencies above about 500 Hz. They become large and reliable for frequencies above 3000 Hz, making ILD cues most effective at high frequencies.



At the first octave band center frequency, the masked threshold of hearing, LT, Oct is equal to the noise level. For each subsequent center frequency, LT, Oct is the greater of either the noise level at that octave band, LN, Oct, or the masked threshold of the previous band less 7.5 dB.

FIGURE A.18.4.7.2 Threshold Masking Level Example.



* Measured at 10 ft in an anechoic room.

FIGURE A.18.4.8.1(a) Comparison of Frequency Content of a Traditional Fire Alarm Audible Notification Appliance to a Directional Sounder.




FIGURE A.18.4.8.1(b) Interaural Time and Intensity Differences of Sound.

ATF: The anatomical transfer function (ATF), also known as the head-related transfer function (HRTF), is used by listeners to resolve front-back confusion and to determine elevation. Waves that come from behind tend to be boosted in the 1000 Hz frequency region, whereas waves that come from the forward direction are boosted near 3000 Hz. The most dramatic effects occur above 4000 Hz.

These localization cues can be implemented simultaneously when the source signal is a broadband sound containing a range of low to high frequencies. For example, octave bands of 1 kHz (707 Hz–1414 Hz) for ITD, 4 kHz (2828 Hz–5856 Hz)

for ILD, and 8 kHz (5657 Hz–11,314 Hz) for ATF would fall within the effective frequency ranges required in 18.4.7.

Additional information on sound localization and auditory localization cues is contained in the following *Physics Today* article, “How We Localize Sound.”

The ability to pinpoint the location of a sound source is based on the physics of sound and the physiology of the human hearing mechanism. The brain processes a large amount of neural signals, some of which provide cues to the sound source's location. People are able to hear sound ranging from about 20 Hz to 20,000 Hz. Unfortunately, pure tones in this frequency range provide only limited localization information. The primary localization cues are provided by interaural time differences (ITDs) (lower frequencies), interaural intensity differences (IIDs) (mid to higher frequencies), and the head-related transfer function (HRTF) (higher frequencies). In enclosed spaces that can be somewhat reverberant, the precedence effect (PE) also provides directional information.

The interaural time difference (ITD) and interaural intensity difference (IID) are termed binaural cues because they depend on both ears separated by the width of the head. At lower frequencies (i.e., longer wavelength), the time delay between arriving sound signals is detectable. ITD is most evident in frequencies below about 500 Hz with clicks or short bursts of sound. At higher frequencies (i.e., shorter wavelength), the loudness/intensity differences between the ears is more noticeable because of partial shielding of the more distant ear by the head. IID is most evident for frequencies above 3000 Hz.

The head-related transfer function (HRTF) relies on the effect of the external ear on perceived sound. The HRTF describes the transforming effect of the head, torso, and external ear on sound as it travels from the sound source to the ear canals. The HRTF changes depending on sound source location, providing an additional localization cue. HRTF operates over a range of frequencies but seems to be most effective in the 5000 Hz to 10,000 Hz range. Combined with the listener's head motion, HRTF provides an independent localization method to complement ITD and IID capabilities.

The precedence effect (PE) is important for discriminating between the direct sound signal and reflected sound, a common situation within buildings. The ear is capable of discerning and fixating on the first sound received (i.e., line-of-sight direct signal) and disregarding later signals (i.e., reflected sound). The acoustical signal arriving first at the ears suppresses the ability to hear other signals (including reverberation) that arrive up to about 40 milliseconds after the initial signal.

All of the preceding cues are utilized simultaneously when the source signal is broadband sound containing a range of low and high frequencies, and when the sound arrives in bursts rather than as steady state sound. The combination of different cues provides reinforcement and redundancy of information to enhance the ability to locate the sound source. Broadband sound tends to eliminate potential ambiguities that occur for pure tone or narrowband sound sources.

Other types of sound patterns can be used as directional sounders that can be used for audible exit marking. Some scientific research has been performed to develop a directional sounder that utilizes a tonal sound different from the example




FIGURE A.18.4.8.1(c) Examples of Frequency-Dependent Attenuation for Sources in Front, Above, and Behind Listener.

above. As with the directional sound example presented above, the development of this alternative signal is similarly rooted in the vast research data that exists for sound localization and directional auditory cues.

An example of an alternative directional sound signal can be a sequence of two harmonic two-tone complexes. This sequence starts with a complex of low fundamental frequencies of 262 Hz and 330 Hz having duration of 200 ms. This sound is then followed by a 200 ms silence. Next the sequence continues with a second sound that is a complex of low fundamental frequencies of 330 Hz and 392 Hz having a duration of 200 ms. After another 200 ms silence, this whole pattern is repeated.

Localizability was ensured by the dense harmonic structure of the signal, with closely spaced harmonics up to 20 kHz. In addition sharp signal onsets were included to aid the detection of interaural time differences, thus increasing localizability.

A.18.4.8.5 Where directional sounders are used, they should not be located on only a single exit. They should be located at all of the identified exits in the building. This is to ensure that in an evacuation or relocation the occupants utilize all of the exits and areas of refuge, not just those that have directional sounders located near them. Some examples of exits would include the following:

- (1) Code-complying exterior doors and exit discharge
- (2) Code-complying exit passageway
- (3) Code-complying interior stairs, including smokeproof enclosures
- (4) Code-complying outside stairs
- (5) Code-complying ramps
- (6) Code-complying fire escapes
- (7) Code-complying horizontal exits

A.18.4.11 See Annex D, Speech Intelligibility.

A.18.4.11.1 See the definition of acoustically distinguishable space in 3.3.6.

A.18.4.11.3 For example, based on the system design the following locations might not require intelligibility. See also Annex D.

- (1) Private bathrooms, shower rooms, saunas, and similar rooms/areas
- (2) Mechanical, electrical, elevator equipment rooms, and similar rooms/areas
- (3) Elevator cars
- (4) Individual offices
- (5) Kitchens
- (6) Storage rooms
- (7) Closets
- (8) Rooms/areas where intelligibility cannot reasonably be predicted

A.18.4.11.4 ADS assignments should be a part of the original design process. See the discussion in A.3.3.6. The design drawings should be used to plan and show the limits of each ADS where there is more than one.

All areas that are intended to have audible occupant notification, whether by tone only or by voice should be designated as one or more ADSs. Drawings or a table listing all ADSs should be used to indicate which ADSs will require intelligible voice communications and those that will not. The same drawings or table could be used to list audibility requirements where tones are used and to list any forms of visual or other notification or communications methods being employed in the ADS.

A.18.5 The mounting height of the appliances affects the distribution pattern and level of illumination produced by an appliance on adjacent surfaces. It is this pattern, or effect, that provides occupant notification by visual appliances. If mounted too high, the pattern is larger but at a lower level of illumination (measured in lumens per square foot or foot-candles). If mounted too low, the illumination is greater (brighter) but the pattern is smaller and might not overlap correctly with that of adjacent appliances.

A qualified designer could choose to present calculations to an authority having jurisdiction showing that it is possible to use a mounting height greater than 96 in. (2.44 m) or less than 80 in. (2.03 m), provided that an equivalent level of illumination is achieved on the adjacent surfaces. This can be accomplished by using listed higher intensity appliances or closer spacing, or both.

Engineering calculations should be prepared by qualified persons and should be submitted to the authority having jurisdiction, showing how the proposed variation achieves the same or greater level of illumination provided by the prescriptive requirements of Section 18.5.

The calculations require knowledge of calculation methods for high-intensity visual notification appliances. In addition, the calculations require knowledge of the test standards used to evaluate and list the appliance.

A.18.5.1 There are two methods of visual signaling. These are methods in which notification of an emergency condition is conveyed by direct viewing of the illuminating appliance or by means of illumination of the surrounding area.

Visual notification appliances used in the public mode must be located and must be of a type, size, intensity, and number so that the operating effect of the appliance is seen by the intended viewers regardless of the viewer's orientation.

A.18.5.1.2 Visual notification appliances for fire or emergency signaling might not be required in all rooms or spaces. For example, a system that is used for general occupant notification should not require visual signaling in closets and other spaces that are not considered as occupiable areas. However, a space of the same size used as a file room could be considered occupiable and should have coverage by notification appliances. Also, signaling intended only for staff or emergency forces might only have to be effective in very specific locations.

A.18.5.2.2 Occupant notification by visual signaling is not required by *NFPA 72* except in high noise areas (*see 18.4.1.1*). Just as with audible occupant notification, the requirement to have such signaling originates from other governing laws, codes, or standards. Those other governing laws, codes, or standards specify the areas or spaces that require either audible, visual, or both types of occupant notification. *NFPA 72* then provides the standards for those systems.

A.18.5.3.3 Research indicates that equivalent indirect alerting is obtained between 0.1 milliseconds to 20 milliseconds. Testing above 20 milliseconds indicates that the effective candela must be increased to obtain equivalent alerting capability to that of shorter light pulse durations of 20 milliseconds or less. The effective candela rating should be increased by the value in Table A.18.5.3.3 to achieve equivalent alerting capability.

A.18.5.3.5 Effective intensity is the conventional method of equating the brightness of a flashing light to that of a steady-burning light as seen by a human observer. The units of effective intensity are expressed in candelas (or candlepower, which is equivalent to candelas). For example, a flashing light that has an effective intensity of 15 cd has the same apparent brightness to an observer as a 15 cd steady-burning light source.

Measurement of effective intensity is usually done in a laboratory using specialized photometric equipment. Accurate field measurement of effective intensity is not practical. Other units of measure for the intensity of flashing lights, such as peak

Table A.18.5.3.3 Visual Notification Appliance Rating Multipliers for Equivalent Alerting Capability

Rated Light Pulse Duration (milliseconds)	Rating Multiplier
20	1.00
25	1.22
30	1.43
35	1.64
40	1.83
45	2.02
50	2.20
55	2.37
60	2.54
65	2.70
70	2.85
75	3.00
80	3.14
85	3.28
90	3.41
95	3.54
100	3.67

candela or flash energy, do not correlate directly to effective intensity and are not used in this Code.

Visual notification appliances might be used to signal fire or other emergencies and might be intended to initiate evacuation, relocation, or some other behavior. Lights intended to initiate evacuation due to fire are required by the Code to be clear or white. Colored lights, such as amber/yellow lights, might be used in a combination system for any emergency (fire, bomb, chemical, weather, etc.) when the intent is for the signal recipient to seek additional information from other sources (voice, text displays, and so on).

Example Scenario 1: A building has a fire alarm system used for general evacuation. A separate mass notification system is used to provide voice instructions and information in the event of non-fire emergencies. The fire alarm system would have white/clear visual notification appliances intended to alert occupants of the need to evacuate. The mass notification system would have amber/yellow visual notification appliances that are intended to signal the need to get additional information from either audible voice announcements, text or graphical displays, or other information sources controlled or operated from the mass notification system. In the event that both systems are activated at the same time, the visual notification appliances should be synchronized per 18.5.5.7.2.

Example Scenario 2: A building has a mass notification system that provides information and instructions for a variety of emergency situations, including fire. Fire alarm initiation might be by a stand-alone fire detection system or might be an integral part of the mass notification system. In the event of an emergency, textual audible appliances are used to provide information. Visual signaling could be accomplished using one set of clear or colored visual notification appliances to indicate the need to get additional information. Visual textual information can be provided by text or graphic display or other visual information appliances. The content of the audible and visual messages will vary depending on the emergency.

A.18.5.3.7 It is not the intent to establish viewing and synchronization requirements for viewing locations outdoors. As an example, there is no need for Floor No. 1 to be synchronized with Floor No. 2 if there is no visual coupling as in an atrium.

Studies have shown that the effect of visual notification appliances on photosensitive epilepsy lessens with distance and viewing angle.

As long as the composite flash rate is no greater than that produced by two listed visual notification appliances as allowed by 18.5.5.7.2, compliance is achieved.

Example: A ballroom has multiple synchronized visual notification appliances operating during an emergency, the doors exiting the ballroom are opened, and the visual notification appliances outside in the lobby and corridor are also operating. The visual notification appliances in the corridor and lobby are synchronized with each other, but the visual notification appliances outside the ballroom are not synchronized with the visual notification appliances inside the ballroom. This would be an acceptable application because the composite flash rate does not exceed that allowed by 18.5.5.7.2.

A.18.5.4 The prescriptive requirements of Section 18.5 assume the use of appliances having very specific characteristics of light color, intensity, distribution, and so on. The appliance and application requirements are based on extensive research. However, the research was limited to typical residential and commercial applications such as school classrooms, offices, hallways, and hotel rooms. While these specific appliances and applications will likely work in other spaces, their use might not be the most effective solution and might not be as reliable as other visual notification methods.

For example, in large warehouse spaces and large distribution spaces such as super stores, it is possible to provide visual signaling using the appliances and applications of this chapter. However, mounting visual notification appliances at a height of 80 in. to 96 in. (2.03 m to 2.44 m) along aisles with rack storage subjects the visual notification appliances to frequent mechanical damage by forklift trucks and stock. Also, the number of appliances required would be very high. It might be possible to use other appliances and applications not specifically addressed by this chapter at this time. Alternative applications must be carefully engineered for reliability and function and would require permission of the authority having jurisdiction.

Tests of a system in large warehouse/super stores designed using the prescriptive approach of 18.5.5.7 showed that high ambient light levels resulted in both indirect and direct signaling effects. The signal-to-noise ratio produced by the operating visual notification appliances was low in many locations. However, with visual notification appliances located over the aisles or unobstructed by stock, indirect and some direct notification

was sometimes achieved. Direct notification occurs even when occupants do not look up toward the ceiling-mounted visual notification appliances due to the extended cone of vision shown in Figure A.18.5.4(a). The visual notification appliance intensity and spacing resulting from the prescriptive design was generally sufficient for occupant notification by a combination of direct and indirect signaling. Testing showed that the best performance was achieved where visual notification appliances were directly over aisles or where visual notification appliances in adjacent aisles were not obstructed by stock. The performance-based design method will almost always result in aisles not having a line of visual notification appliances in them, because the spacing of visual notification appliances can be greater than the spacing of aisles. Also, it is recognized that aisles might be relocated after installation of the system. Good design practice is to place visual notification appliances over aisles, especially those that are likely to remain unchanged such as main aisles, and over checkout areas. Where reorganization of aisles results in visual notification appliances not in or over an aisle, or where that is the base design, it is important to have a clear view from that aisle to a nearby visual notification appliance. See Figure A.18.5.4(b). Some spaces might have marginal visual notification appliance effect (direct or indirect). However, occupants in these large stores and storage occupancies move frequently and place themselves in a position where they receive notification via the visual notification appliances. In addition, complete synchronization of the visual notification appliances in the space produced a desirable effect.

Visual notification using the methods contained in 18.5.5.7 is achieved by indirect signaling. This means the viewer need not actually see the appliance, just the effect of the appliance. This can be achieved by producing minimum illumination on surfaces near the appliance, such as the floor, walls, and desks. There must be a sufficient change in illumination to be noticeable. The tables and charts in Section 18.5 specify a certain candela-effective light intensity for certain size spaces. The data were based on extensive research and testing. Appliances do not typically produce the same light intensity when measured off-axis. To ensure that the appliance produces the desired illumination (effect), it must have some distribution of light intensity to the areas surrounding the appliance. UL 1638, *Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories*, specifies the distribution of light shown to provide effective notification by indirect visual signaling.

A.18.5.5.1 The requirements for the location of appliances within a building or structure are intended to apply to visual notification appliances applied in accordance with 18.5.5.7, 18.5.5.8, and 18.5.5.10. The mounting and location of appliances installed using the performance-based alternative of 18.5.5.9 can be located differently, provided they meet the




FIGURE A.18.5.4(a) Extended Cone of Vision. (Source: R. P. Schifiliti Associates, Inc.)




FIGURE A.18.5.4(b) Visual Notification Appliances in Stores. (Source: R. P. Schifiliti Associates, Inc.)

intended performance requirements. Other appliances, such as graphic displays, video screens, and so on, should be located so that they meet their intended performance.

Where low ceiling heights or other conditions do not permit mounting at a minimum of 80 in. (2.03 m), visual notification appliances can be mounted at a lower height. However, lowering the mounting height reduces the area of coverage for that visual notification appliance. The performance-based methods of 18.5.5.9 can be used to determine the area of coverage. Visual notification appliance mounting height should not be lowered below the plane of normal human viewing [approximately 5 ft (1.5 m)] except where ceiling heights limit the mounting position.

The mounting height requirement of 80 in. to 96 in. (2.03 m to 2.44 m) does not address the possibility of conditions where ceiling heights are less than 80 in. (2.03 m). The range that is permitted [80 in. to 96 in. (2.03 m to 2.44 m)] ensures that visual notification appliances are not mounted too high, which would result in lower levels of illumination on surrounding walls and on the floor. The lower limit of the range ensures that a minimum percentage of the surrounding surfaces is illuminated and that the top of the illuminated pattern is at or above the plane of normal human viewing [approximately 5 ft (1.5 m)]. Wall mounting of visual notification appliances, which are listed only for wall mounting, can result in little or no illumination above the plane of the visual notification appliance. In the case of lower ceiling heights and mounting close to the ceiling, the level of illumination on the floor and surrounding walls is not reduced but the walls have a near 100 percent illuminated or “painted” area because the visual notification appliance is close to the ceiling. That is, there is little or no wall surface above the plane of the visual notification appliance that is not illuminated when the visual notification appliance is mounted close to the ceiling. Thus, when a visual notification appliance is mounted lower than the minimum [80 in. (2.03 m)] but still close to the ceiling, the only loss of signal is the smaller pattern produced on the horizontal plane (floor).

In the case where the only change is a lower mounting height due to a lower ceiling height, the room size covered by a visual notification appliance of a given value should be reduced

by twice the difference between the minimum mounting height of 80 in. (2.03 m) and the actual, lower mounting height. For example, if a 15 cd effective visual notification appliance that normally covers a 20 ft (6.1 m) square space is being used and the height of the space is 63 in. (1.6 m) and the visual notification appliance is mounted at 59 in. (1.5 m), the visual notification appliance can only cover a 16.5 ft (5.0 m) square space: $20\text{ ft} - 2(80\text{ in.} - 59\text{ in.})(1\text{ ft}/12\text{ in.}) = 16.5\text{ ft (5.0 m)}$.

The room size reduction assumes that the horizontal pattern on each side of the visual notification appliance is reduced by the same amount that the visual notification appliance height is reduced.

A.18.5.5.4 Visual notification appliances must be listed for either wall mounting or ceiling mounting. The effectiveness of ceiling-mounted appliances does not depend on them being mounted on a surface. Therefore, the Code permits them to be suspended below the ceiling using proper electrical installation methods. Appliances mounted parallel to the floor, whether on a ceiling or suspended, can sometimes significantly reduce installation costs and provide better coverage.

In convention spaces and areas with racking and shelving, wall-mounted appliances are frequently obstructed or subjected to mechanical damage. Ceiling mounting (or suspending) the appliances can prevent problems and increases the ability for the appliance to cover the floor area through direct and indirect signaling. See A.18.5.4.

A.18.5.5.5 Visual notification appliances must be listed for either wall mounting or ceiling mounting. The effectiveness of ceiling-mounted appliances does not depend on them being mounted on a surface. Therefore, the Code permits them to be suspended below the ceiling using proper electrical installation methods. Appliances mounted parallel to the floor, whether on a ceiling or suspended, can sometimes significantly reduce installation costs and provide better coverage.


In convention spaces and areas with racking and shelving, wall-mounted appliances are frequently obstructed or subjected to mechanical damage. Ceiling mounting (or suspending) the appliances can prevent problems and increases the ability for the appliance to cover the floor area through direct and indirect signaling. See A.18.5.4.

A.18.5.5.6 Obstructions to consider include, but are not limited to, light fixtures, duct work, structural elements, and video monitors. In corridors, it is the viewing of the appliance which is of concern. In rooms, it is the pattern of light produced on walls and floors that might be of concern.

A.18.5.5.7 The visual notification appliance intensities listed in Table 18.5.5.7.1(a) or Table 18.5.5.7.1(b), 18.5.5.8, or Table 18.5.5.10.3 or determined in accordance with the performance requirements of 18.5.5.9 are the minimum required intensities. It is acceptable to use a higher intensity visual notification appliance in lieu of the minimum required intensity.


Areas large enough to exceed the rectangular dimensions given in Figure A.18.5.5.7(a) through Figure A.18.5.5.7(c) require additional appliances. Often, proper placement of appliances can be facilitated by breaking down the area into multiple squares and dimensions that fit most appropriately [see Figure A.18.5.5.7(a) through Figure A.18.5.5.7(d)]. An area that is 40 ft (12.2 m) wide and 80 ft (24.4 m) long can be covered with two 60 cd appliances. Irregular areas and areas with dividers or partitions need more careful planning to make certain that at least one 15 cd appliance is installed for each 20 ft × 20 ft (6.1 m × 6.1 m) area and that light from the appliance is not blocked.

A.18.5.5.7.1 In rooms with an average ambient level greater than 500 lx, visual notification appliance spacing should be reduced by 30 percent (i.e., listed spacing × 0.7) or the



Note: Broken lines represent imaginary walls.

FIGURE A.18.5.5.7(a) Irregular Area Spacing.



Note: Broken lines represent imaginary walls.

FIGURE A.18.5.5.7(b) Spacing of Wall-Mounted Visual Notification Appliances in Rooms.




FIGURE A.18.5.5.7(c) Room Spacing Allocation — Correct.

required effective candela should be increased by 100 percent (i.e., effective candela × 2.0).

Ambient light levels have an effect on the proper candela ratings in indirect viewing of visual notification appliances. The amount of ambient light is normally from two sources: artificial lighting and natural light from outside.

In rooms or areas requiring artificial illumination, the ambient lux value for selecting candela values should be based on the maximum light intensity that the artificial light sources provide.

In rooms or areas that have natural outside light, the ambient lux value should be that of the maximum light level with the shades or curtains fully open during daylight hours and with the artificial lighting illuminated.




FIGURE A.18.5.5.7(d) Room Spacing Allocation — Incorrect.

Ambient light can be measured using a calibrated light meter in the approximate center of the room, 4 ft (1.2 m) above the floor, with the sensor facing upward. The light meter should measure light level from 0 to 10,000 lx with a precision accuracy of ± 5 percent.

For design purposes, typical ambient illumination for various locations and activities are shown in Table A.18.5.5.7.1 and can be used as a guide for the selection of appropriate visual signal intensity.

A.18.5.5.7.2(2) The field of view is based on the focusing capability of the human eye specified as 120 degrees in the *Illuminating Engineering Society (IES) Lighting Handbook Reference and Application*. The apex of this angle is the viewer's eye. In order to ensure compliance with the requirements of 18.5.5.7.2, this angle should be increased to approximately 135 degrees.

Testing has shown that high flash rates of high-intensity visual notification appliances can pose a potential risk of seizure to people with photosensitive epilepsy. To reduce this risk, more than two visual notification appliances are not permitted in any field of view unless their flashes are synchronized. This does not preclude synchronization of appliances that are not within the same field of view.

Table A.18.5.5.7.1 Typical Ambient Illumination for Various Locations

Locations	Illumination (lx)
Unoccupied rooms (only emergency lighting active)	100–150
Warehouses, homes, theaters, archives	150
Classrooms	250
Normal offices, study library, show rooms, laboratories	500
Supermarkets, mechanical workshops	750
Detailed work spaces, operating rooms	1000

Note: Table derived from "Recommended Light Levels," published by National Optical Astronomy Observatory.

A.18.5.5.7.6 This subsection is also intended to permit ceiling-mounted visual notification appliances to be suspended below the ceiling, provided the visual notification appliance height is not below the viewing plane for any ceiling height.

A.18.5.5.8 Because the occupants are usually alert and moving, and because their vision is focused by the narrowness of the space, corridor signaling is permitted to be by direct viewing of lower-intensity (15 cd) appliances. That is, the alerting is intended to be done by direct viewing of the visual notification appliance, not necessarily by its reflection off of surfaces (indirect viewing) as required for rooms in 18.5.5.7.

Note that it is acceptable to use 18.5.5.7 (Spacing in Rooms) to determine the number and location of visual notification appliances in corridors. If 18.5.5.7 is used, it is not necessary to have a corridor visual notification appliance within 15 ft (4.6 m) of the end of the corridor.

See Figure A.18.5.5.8 for corridor spacing for visual notification appliances.

A.18.5.5.8.5 Visual notification appliances in corridors are permitted to be mounted on walls or on ceilings in accordance with 18.5.5.8. Where there are more than two appliances in a field of view, they need to be synchronized.

Note that it is acceptable to use 18.5.5.7 (Spacing in Rooms) to determine the number and location of visual notification appliances in corridors. If 18.5.5.7 is used, it is not necessary to have a corridor visual notification appliance within 15 ft (4.5 m) of the end of the corridor. It is not the intent of this section to require visual notification appliances at or near every exit or exit access from a corridor.

A.18.5.5.9 A design that delivers a minimum illumination of 0.0375 lumens/ft² (footcandles) [0.4036 lumens/m² (lux)] to all occupiable spaces where visual notification is required is considered to meet the minimum light intensity requirements of 18.5.5.7.2(1). This level of illumination has been shown to




FIGURE A.18.5.5.8 Corridor Spacing for Visual Notification.

alert people by indirect viewing (e.g., reflected light) in a large variety of rooms with a wide range of ambient lighting conditions.

The illumination from a visual notification appliance at a particular distance is equal to the effective intensity of the appliance divided by the distance squared (the inverse square law). Table 18.5.5.7.1(a) and Table 18.5.5.7.1(b) are based on applying the inverse square law to provide an illumination of at least 0.0375 lumens/ft² (0.4037 lumens/m²) throughout each room size. For example, a 60 cd effective intensity appliance in a 40 ft × 40 ft (12.2 m × 12.2 m) room produces 0.0375 lumens/ft² (0.4037 lumens/m²) on the opposite wall 40 ft (12.2 m) away [$60 \div (40 \text{ ft})^2$ or $(60 \div (12.2 \text{ m})^2)$]. This same 60 cd effective intensity appliance produces 0.0375 lumens/ft² (0.4037 lumens/m²) on the adjacent wall 20 ft (6.1 m) away [$60 \times 25\% \div (20 \text{ ft})^2$ or $(60 \times 25\% \div (12.2 \text{ m})^2)$] where the minimum light output of the appliance at 90 degrees off-axis is 25 percent of rated output per UL 1638, *Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories*. Similarly, a 110 cd visual notification appliance will produce at least 0.0375 lumens/ft² (0.4037 lumens/m²) in a 54 ft × 54 ft (16.5 m × 16.5 m) room. Calculated intensities in Table 18.5.5.7.1(a) and Table 18.5.5.7.1(b) have been adjusted to standardize the intensity options of presently available products and take into account additional reflections in room corners and higher direct viewing probability when there is more than one appliance in a room.

The application of visual notification appliances in outdoor areas has not been tested and is not addressed in this Code. Visual notification appliances that are mounted outdoors should be listed for outdoor use (under UL 1638, for example) and should be located for direct viewing because reflected light will usually be greatly reduced.

A.18.5.5.10.3 The required intensity of a visual notification appliance used to alert sleeping persons is dependent on how close it is to the ceiling. A visual notification appliance that is within 24 in. (610 mm) of the ceiling might be partially obscured by smoke at the time it is called upon to operate. Therefore, the Code requires it to have a higher candela effective rating. The most common way to use the table is to decide first where the appliance will be located. Then, determine how far that is from the ceiling. If the distance is greater than or equal to 24 in. (610 mm), the appliance is permitted to have an output of 110 cd eff. If the distance from the appliance to the ceiling is less than 24 in. (610 mm), the appliance must have a rated output of at least 177 cd eff.

For example, if an appliance is to be wall mounted, the lens is required by 18.5.5.1 to be mounted not less than 80 in. (2.03 m) and not greater than 96 in. (2.44 m) above the finished floor. If it intended to be installed at 90 in. (2.29 m) and the ceiling height is 10 ft (3 m), the distance to the ceiling would be 30 in. (760 mm). Table 18.5.5.10.3 then indicates that the appliance must have a light output rated at 110 cd eff (or greater).

A second example might be an appliance that is part of a smoke detector base. Smoke detectors are required by Chapter 17 of this Code to be located either on the ceiling or on a wall, no more than 12 in. down from the ceiling to the top of the detector. Therefore, a visual notification appliance on a smoke detector base will be less than 24 in. (610 mm) from the ceiling. Table 18.5.5.10.3, then indicates that the appliance must have a light output rated at 177 cd eff (or greater).

Note that the requirement for increasing the intensity when mounted close to the ceiling applies only to visual notification appliances used in sleeping areas to awaken sleeping people. It is assumed that in nonsleeping situations, a visual notification appliance is not needed to alert someone if there is a developing smoke layer.

A.18.5.5.10.4 For sleeping areas, the use of visual notification appliances with other intensities at distances greater than 16 ft (4.9 m) has not been researched and is not addressed in this Code.

Visual notification is intended to be provided in sleeping areas at a distance not to exceed 16 ft (4.9 m) from the expected location of a pillow on a bed located within the room. The intent of the visual appliance is to wake a hearing-impaired individual who is sleeping. Individuals with hearing impairments might also sleep in other areas including the living room, family room, and den of a dwelling unit and living areas of guest rooms within a hotel or motel. Visual notification complying with 18.5.5.10.3 would be a benefit to an individual with a hearing impairment in any areas that might reasonably be used for sleeping.

A.18.6 Though the number of visual notification appliances might be reduced in private operating mode settings, visual notification appliances might still need to be considered in spaces occupied by the public or the hearing impaired or subject to other laws or codes.

A.18.8.1.2 The tone signal is used to evaluate the sound pressure level produced by loudspeaker appliances because of the fluctuating sound pressure level of voice or recorded messages.

A.18.9 Textual and graphical visual appliances are selected and installed to provide temporary text, permanent text, or symbols. Textual and graphical visual appliances are most commonly used in the private mode for fire alarm systems. The use of microprocessors with computer monitors and printers has resulted in the ability to provide detailed information in the form of text and graphics to persons charged with directing emergency response and evacuation. Textual and graphical visual appliances are also used in the public mode to communicate emergency response and evacuation information directly to the occupants or inhabitants of the area protected by the system. For both private mode and public mode signaling, text and graphic annunciators can provide information about pre-alarm, alarm, trouble, and supervisory conditions. Because textual and graphical visual appliances do not necessarily have the ability to alert, they should only be used to supplement audible or visual notification appliances.

Textual and graphical visual information should be of a size and visual quality that is easily read. Many factors influence the readability of textual visual appliances, including the following:

- (1) Size and color of the text or graphic
- (2) Distance from the point of observation
- (3) Observation time
- (4) Contrast
- (5) Background luminance
- (6) Lighting
- (7) Stray lighting (glare)
- (8) Shadows
- (9) Physiological factors

While many of these factors can be influenced by the equipment manufacturer and by the building designers, there is no readily available method to measure legibility.

A.18.9.4 Parts of this section on text characteristics are based on Section 703.5 of the updated accessibility guidelines in the U.S. Access Board's ADA-ABA-AG.

A.18.9.4.2 Signs are more legible for persons with low vision when characters contrast as much as possible with their background. Additional factors affecting the ease with which the text can be distinguished from its background include shadows cast by lighting sources, surface glare, and the uniformity of the text and its background colors and textures.

Stroke width-to-height ratios are an important part of character legibility and are affected by contrast. Ratios for light characters on a dark background and dark characters on a light background differ because light characters or symbols tend to spread or bleed into the adjacent dark background. To accommodate these differences, recommendations for symbol stroke width-to-character height ratios are as follows:

- (1) Positive image — Dark characters on a light background, ratio of 1:6 to 1:8
- (2) Negative image — Light characters on a dark background, ratio of 1:8 to 1:10

Source: Federal Aviation Administration (FAA) Human Factors Awareness Course available at <http://www.hf.faa.gov/webtraining/Intro/Intro1.htm>.

A.18.9.4.4 The use of all uppercase characters in messages should be avoided as it decreases legibility. The exception is one- or two-word commands or statements such as stop, go, or exit stair.

A.18.9.4.7 Paragraph 18.9.4.7 and the associated table does not apply to text and graphics displayed on desktop monitors. The Code does not list any specific sizing requirements for desktop monitors. However, 18.9.3 does require them to be clear and legible at the intended viewing distance. Other requirements in 18.9.4 such as contrast, sans serif fonts, and so forth should still apply to desktop displays. The specific requirements of Table 18.9.4.7 are taken directly from Section 703.5 of the updated accessibility guidelines in the U.S. Access Board's ADA-ABA-AG. The table has been reformatted to be consistent with other parts of NFPA 72.

A.18.9.4.8 The minimum height for textual and graphic visual appliances is given as 40 in. (1.02 m) above the ground or finished floor. However, the character or symbol sizes should be based on the height of the highest character or symbol displayed by the appliance.

A.18.10.2 Notification appliances are available for the deaf and hard of hearing. These appliances include, but are not limited to, supplemental tactical notification appliances. Such tactile notification appliances can be capable of awakening people. Tactile appliances can initiate in response to the activation of an audible smoke alarm, through hard wiring into the fire alarm system or by wireless methods.

Some tests show that visual notification appliances might not be effective in awakening some sleeping individuals during an emergency. Some tactile devices can be more effective in awakening individuals, regardless of hearing levels, from sleep.

A.21.1 Fire alarm systems, signaling systems, and emergency communications systems are often part of a large, integrated system serving a building or area. Figure A.21.1 shows examples of individual systems that might be part of an integrated system.

A fire alarm system might monitor the status of one of the other individual systems or provide a form of output to control another individual system, such as a smoke control system or an elevator controller.

In some cases, the fire alarm system shares information and control in two directions with another individual system. NFPA 72 covers only the fire alarm or signaling system in the circuits powered by it, not any part of the other individual systems.

See NFPA 3 and NFPA 4 for additional information on integrated systems.

A.21.2.1 The performance of automatic emergency control functions refers to their normal operation. For instance, it is all right to shut down elevator mainline power when the system has been designed to do so.

A.21.2.4 Emergency control function interface devices can be located far from the device to be actuated, such as air-handling units and exhaust fans located on the roof. The requirement for monitoring installation wiring for integrity only applies to the wiring between the fire alarm control unit and the emergency control function interface device. For example, it does not apply to the wiring between the emergency control function interface device and a motor stop/start control relay, or between the emergency control function interface device and the equipment to be controlled (e.g., air-handling units and exhaust fans). The location of the emergency control function interface device within 3 ft (910 mm) applies to the point of interface and not to remotely located equipment.




FIGURE A.21.1 Integrated Systems. (Source: R.P. Schifiliti Associates, Inc.)

Where Class D circuits are utilized to actuate emergency control functions (such as but not limited to door closers, AHU shutdown, and damper controls), the fire alarm control point is not required to be within 3 ft (910 mm) of the interface point to the system or device to be controlled. It is important to note that in some cases these control circuits are not part of the fire alarm system but rather part of the other systems performing the functions. See Figure A.3.3.153.1.1 for additional details.

A.21.3 The terms *machinery space*, *control space*, *machine room*, and *control room* are defined in *NFPA 70* and *ASME A17.1/CSA B44, Safety Code for Elevators and Escalators*.

A.21.3.2 In facilities without a building alarm system, dedicated function fire alarm control units are required by 21.3.2 for elevator recall in order that the elevator recall systems be monitored for integrity and have primary and secondary power meeting the requirements of this Code.

The fire alarm control unit used for this purpose should be located in an area that is normally occupied and should have audible and visible indicators to annunciate supervisory (elevator recall) and trouble conditions; however, no form of general occupant notification or evacuation signal is required or intended by 21.3.2.

A.21.3.5 Smoke detectors should not be installed in outdoor locations or locations that are open to the weather (such as unenclosed elevator lobbies in open parking structures), because such environments can exceed the parameters of the detector listing and can result in unwanted alarms. (See 21.3.10.)

A.21.3.7 Since it is permitted by *ASME A17.1/CSA B44, Safety Code for Elevators and Escalators*, to have access for fire alarm initiating devices installed inside elevator hoistways, the following are examples for proposed methods for providing such access (other methods could be acceptable if approved by the authority having jurisdiction):

- (1) Provide an access hatch door and associated protective guard for a spot type fire detector, where the fire detector is installed within the protective guard.
- (2) Provide an air sampling-type detector as specified in 17.7.4.6 installed outside the hoistway with its sampling tube installed to sample the air within the hoistway.
- (3) If heat detection is required, linear heat detectors with connection points located outside the hoistway or spot type heat detectors installed in accordance with A.21.3.7(1) are acceptable.
- (4) If a waterflow switch is provided per 21.3.3.2, install the waterflow switch outside the hoistway. The use of a time delay capability for this device is acceptable in order to ensure that water supply pressure fluctuations do not initiate unwanted Elevator Phase I Emergency Recall Operation.

A.21.3.8 This requirement applies to smoke and heat detectors installed in the hoistway. It is important to note that the hoistway includes the pit. The location of smoke or heat detectors will, most likely, require special consideration in order to provide the intended response of early detection of fire in the elevator pit. The location of these detectors will likely need to be below the lowest level of recall in order to provide an adequate response. Since there is no real ceiling at this location to allow installation using the spacing provisions of Chapter 17, the provisions of 17.7.4.1.3 and 17.4.8 should be

considered, which allows detectors to be placed closer to the hazard in a position where the detector can intercept the smoke or heat. Also refer to A.21.3.14.2(3).

A.21.3.9 It should be noted that smoke detectors installed in hoistways can be a source of nuisance activation. Therefore, hoistways need smoke detectors specifically intended for those types of spaces (environments).

A.21.3.10 The objective of elevator Phase I Emergency Recall Operation is to have the elevator automatically return to the recall level before fire can affect the safe operation of the elevator. This includes both the safe mechanical operation of the elevator, as well as the delivery of passengers to a safe lobby location. Where *ASME A17.1/CSA B44, Safety Code for Elevators and Escalators*, specifies the use of fire alarm initiating devices used to initiate Phase I Emergency Recall Operation, these devices are expected to provide the earliest response to situations that would require Phase I Emergency Recall Operations. The use of other automatic fire detection is only intended where smoke detection would not be appropriate due to the environment. Where ambient conditions prohibit the installation of smoke detectors, the selection and location of other automatic fire detection should be evaluated to ensure the best response is achieved. When heat detectors are used, consideration should be given to both detector temperature and time lag characteristics (Response Time Index). The consideration of a low temperature rating alone might not provide the earliest response. It should be noted that smoke detectors installed in hoistways can be a source of nuisance activation. Therefore, hoistways need smoke detectors specifically intended for those types of spaces (environments). Performance-based selection of specific automatic fire detection suitable for elevator hoistways can be based on Annex Bas acceptable to the authority having jurisdiction.

A.21.3.14.1 Refer to the definition of *Group Automatic Operation* in *ASME A17.1/CSA B44, Safety Code for Elevators and Escalators*.

In addition to performing elevator Phase I Emergency Recall Operation to the Designated Level, the elevator system, upon receiving the fire alarm system output specified in 21.3.14.1(1), 21.3.14.1(2), or 21.3.14.1(3), will also actuate the elevator car visual signal (fire fighter's hat) in accordance with *ASME A17.1/CSA B44, Safety Code for Elevators and Escalators*.

A.21.3.14.2 Refer to for the definition of *Group Automatic Operation* in *ASME A17.1/CSA B44, Safety Code for Elevators and Escalators*.

In addition to performing elevator Phase I Emergency Recall Operation to the Alternate Level, the elevator system, upon receiving the fire alarm system output specified in 21.3.14.2(1), 21.3.14.2(2), or 21.3.14.2(3) will also actuate the elevator car visual signal (fire fighter's hat) in accordance with *ASME A17.1/CSA B44, Safety Code for Elevators and Escalators*.

A.21.3.14.2(3) Where initiating devices are located in the elevator hoistway at or below the lowest level of recall, *ASME A17.1/CSA B44, Safety Code for Elevators and Escalators*, requires that the elevator be sent to the upper recall level. Note that the lowest level of recall could be the designated level or alternate level as determined by the local authority for the particular installation. Also note that the elevator hoistway, as defined in *ASME A17.1/CSA B44*, includes the elevator pit.

A.21.4.1 When determining desired performance, consideration should be given to the temperature and response time characteristics/index (RTI) of both the sprinkler and the heat detector to ensure that the heat detector will operate prior to the sprinkler, because a lower temperature rating alone might not provide earlier response.

A.21.4.2 The purpose of spacing heat detectors in close proximity to each sprinkler is to ensure the operation of the disconnecting means upon heat detection prior to the operation of any sprinkler installed in those locations. Spot-type heat detectors or linear heat detectors are acceptable.

A.21.4.3 Care should be taken to ensure that elevator power cannot be interrupted due to water pressure surges in the sprinkler system. The intent of the Code is to ensure that the switch and the system as a whole do not have the capability of introducing a time delay into the sequence. The use of a switch with a time delay mechanism set to zero does not meet the intent of the Code, because it is possible to introduce a time delay after the system has been accepted. This might occur in response to unwanted alarms caused by surges or water movement, rather than addressing the underlying cause of the surges or water movement (often due to air in the piping). Permanently disabling the delay in accordance with the manufacturer's printed instructions should be considered acceptable.

A.21.4.4 Figure A.21.4.4 illustrates one method of monitoring elevator shunt trip control power for integrity.




FIGURE A.21.4.4 Typical Method of Providing Elevator Power Shunt Trip Supervisory Signal.

A.21.5 The continuous monitoring of smoke and temperature is to allow the responding fire fighters to know when the tenability conditions at the floor elevator lobbies are changing. This can be accomplished at a minimum by monitoring elevator lobbies, machine rooms, control rooms, machinery spaces, or control spaces smoke detector(s) for the presence of smoke and a minimum of three ranges of temperature in the elevator lobbies, machine rooms, machinery spaces, or control rooms that provide full bodily access for fire fighters, as follows:

- (1) Normal $\leq 90^{\circ}\text{F}$ (32°C)
- (2) Monitoring (supervisory) between 90°F (32°C) and 135°F (57°C)
- (3) Unsafe (alarm) above 135°F (57°C)

Indications at the fire alarm control unit would typically be as follows:

For smoke:

- (1) No indication for normal
- (2) Red/alarm messaging or unsafe

For heat:

- (1) Green (no indication on fire alarm control unit) for a normal range
- (2) Amber/yellow/supervisory messaging for monitor range
- (3) Red/alarm messaging for unsafe

Note 1: Temperature monitoring should not be required in areas or locations not accessible to fire fighters, such as elevator control spaces and elevator machinery spaces located inside the elevator hoistway.

Note 2: If fire service access elevators or occupant evacuation elevators are provided in buildings not provided with a fire command center or emergency command center, such as low-rise buildings, the required annunciator(s) should be installed in another approved location as determined by the authority having jurisdiction.

In most cases, a separate annunciator would be recommended to provide an overall status of the elevator lobbies, machine rooms, or control rooms that provide full bodily access for fire fighters in the building.

The lowest temperature defined in Table 17.6.2.1, Temperature Classification and Color Code for Heat-Sensing Fire Detectors, is 100°F (38°C), so a thermostat or other approved heat sensor(s) should be used to monitor temperatures less than 100°F (38°C).

A.21.6 Refer to the applicable building code for application requirements and definitions related to occupant evacuation elevators (OEE). OEE are not required by code, and they will be provided for a relatively limited number of buildings, mainly office use high-rise buildings over 420 ft (128 m) in lieu of a required additional stairway as a building code exception. They could also be provided on a voluntary basis in other buildings due to ADA or mobility of occupants concerns. It is highly recommended that those involved with design and installation of these systems become familiar with available information such as ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*, Section 2.27, regarding occupant evacuation operation (OEO) and its nonmandatory Appendix V, "Building Features for Occupant Evacuation Operation." It will be imperative that a great amount of coordination and performance-based design be done between elevator and fire alarm system designers, installation contractors, and the authority having jurisdiction.

Figure A.21.6 demonstrates the basics of OEO. This is a simplified flowchart and is not intended to show all required inputs, outputs, or interfaces. This figure demonstrates some functions that are dictated by ASME A17.1/CSA B44 for reference only. Inclusion of elevator system operations in this figure is not intended to suggest that the fire alarm system is responsible for the feature.

A.21.6.2.1.1 The term *group automatic operation* is defined in ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*. Other terms such as *elevator group* or *group of elevators* are used in Section 26.6 to refer to those elevators sharing a common landing call operation. For instance, if an elevator landing call is registered on a particular floor, any elevator that could respond to that call would be considered in that elevator group. Elevators in an *elevator group* typically share a lobby, hoistway, and/or machine/control room or control space.

A.21.6.2.1.2 When OEO is actuated either manually or automatically, it is applicable to all elevators serving the floors of the elevator evacuation zone. However, when a single elevator or elevator group is placed on manual Elevator Phase I Emergency Recall Operation, OEO continues to operate for the

other elevator groups serving the elevator evacuation zone. Similarly, when a fire alarm initiating device(s) described in 21.3.14.1 and 21.3.14.2 is actuated, Elevator Phase I Emergency Recall Operation will cause recall only to the elevator group and not to all elevators in the elevator evacuation zone not associated with that group of recalled elevators. See also 21.6.2.8.

A.21.6.2.3.1 This signal to the elevator system is caused by the activation of a fire alarm initiating device other than that which is described in 21.3.14.1 and 21.3.14.2.

A.21.6.2.3.2 The elevator evacuation zone would typically be the floor of an active alarm plus two floors above and two floors below the floor with the active alarm for a total of five floors or as otherwise determined by the authority having jurisdiction.

A.21.6.2.3.3 The elevator discharge level is considered the same level as the designated level of elevator recall for an individual elevator or a group of elevators. More than a single elevator discharge level can exist in a building.




FIGURE A.21.6 Simplified Occupant Evacuation Operation (OEO) (Elevator system interface with the building fire alarm system based on ASME A17.1/CSA B44, Section 2.27.11, and NFPA 72, Section 21.6).

A.21.6.2.3.6 If there are different elevator discharge levels in the building, then separate signals from the fire alarm system should be sent to each elevator group serving the active alarm floors to allow for OEO operation of those elevators when the alarm is not at the elevator discharge level. The fire alarm system should not send signal(s) to the elevator system to initiate OEO for a group of elevators when the first active alarm is at the discharge level for that group. Subsequent active alarms at any levels should not cause the fire alarm system to send signal(s) to the elevator system to initiate OEO for that group of elevators. When the first active alarm is not on the discharge level, the fire alarm system should send signals to the elevator system to initiate OEO for that group of elevators and all subsequent active alarms, including at the elevator discharge level.

A.21.6.2.4 The manual selection means such as a switch or a push button for each floor is intended in lieu of automatic initiating devices that could be impaired or out of service and would otherwise have actuated to provide automatic initiation in accordance with 21.6.2.3. Manual fire alarm boxes are not included because they are typically actuated at locations remote from the fire. The manual selection means could also serve to evacuate the building or portions of the building for non-fire-related emergencies. The manual selection means is required to provide a maintained nonlatching output(s) from the fire alarm system to the elevator system to prevent the need for fire alarm system reset upon a wrong or unwanted manual selection of a floor(s).

A.21.6.2.5 The fire alarm system uses the floor identification to automatically establish an elevator evacuation zone for voice messaging purposes. The elevator system also uses the floor identification to determine the contiguous block of floors to be evacuated (elevator evacuation zone, see A.21.6.2.3.2). The elevator evacuation zone is updated to reflect changing conditions as indicated by the output signal(s). This information is sent to the elevator system and also used for occupant notification. The output signals from the fire alarm system can be in the form of contact closures or serial communications or other approved means. Coordination needs to be provided between the fire alarm system installer, the elevator system installer, and the authority having jurisdiction.

A.21.6.2.6 Prerecorded automatic voice messages provided by the in-building fire emergency voice/alarm communications system need to be coordinated with the variable message signs provided separately by the elevator system to all affected elevator lobbies and floors served by the elevator(s) operating in OEO so that occupants will understand what to expect and how to react. Additional visual information will be provided in each affected elevator lobby by the elevator system to further inform occupants of the status of the elevators. Refer also to 24.3.6 and associated Annex A material (Messages for One-Way Emergency Communications Systems) for additional information. It is important to note that all elevator lobbies served by elevator(s) operating in OEO, both within the elevator evacuation zone and on other floors outside that zone, will be considered as affected lobbies, and they will be provided with variable messages controlled by the elevator system. The fire alarm system will not provide automatic voice messages in the affected elevator lobbies, but rather it will provide automatic messages to all floors having those affected lobbies via audible appliances located outside those lobbies. The messages provided by the fire alarm system and the elevator system on the affected floors and lobbies must be coordinated so as not to

conflict with each other. It is especially important to address additional automatic or manual alarm actuation(s) and the impact on expanding the elevator evacuation zone and the corresponding voice messaging that has to adjust to the change. Table A.21.6.2.6 gives sample voice message content to be added to normal messaging (to be coordinated with the variable message display provided by the elevator contractor). Voice messaging is permitted to all other floor(s) in the building not in the elevator evacuation zone and not served by elevator(s) performing OEO in accordance with the facility emergency response plan approved by the authority having jurisdiction. For further information on voice messaging strategies refer to NIST Technical Note 1779, *General Guidance on Emergency Communication Strategies for Buildings* and *FPRF Elevator Messaging Strategies*.

A.21.6.2.6.3 This new message will require a signal(s) from the elevator system to the fire alarm system. This signal(s) will indicate to the fire alarm system that all elevators serving an elevator evacuation zone are not available due to Elevator Phase I Emergency Recall Operation or due to other elevator condition(s) such as inspection, operation, and malfunction.

A.21.6.2.6.4 The emergency voice/alarm communications system's loudspeaker(s) located in each OEE lobby are not permitted to transmit automatic voice messages since they could interrupt occupants using the required OEE elevator lobby two-way communication system. Therefore, manual paging zones are required for those loudspeakers by applicable building code(s). The specific zone selection will be performed from a fire alarm system paging panel located in the Fire Command Center. Since a very large number of individual paging zones could be required, it is permitted to group all OEE lobbies' loudspeakers per floor or vertically per elevator group as a single paging zone. The OEE lobby paging zone will be dedicated to loudspeakers that only serve OEE lobbies and will be separate from all other loudspeakers outside of an OEE lobby.

A.21.6.2.8 Suspension of OEO can occur when an individual elevator or group of elevators is recalled by fire fighters using key operated switch(es). It is important to recognize that OEO continues operation using the available elevator(s). The affected elevator(s) will return to OEO operation when fire fighters' emergency operation has been reset.

Table A.21.6.2.6 Sample Voice Message Content

Condition	Sample Voice Message
Specific block of floors being evacuated	"Elevators and stairs are available for evacuation."
Floors not in the elevator evacuation zone within an elevator group performing OEO	"Elevators are not available; they are temporarily dedicated to other floors."
On the discharge level	"Elevators are dedicated to evacuation. Do not enter elevator."
If some elevators have been recalled but other elevator(s) are still available	"Elevators and stairs are available for evacuation."
If all elevators serving a floor or elevator evacuation zone are recalled	"Elevators are out of service. Use stairs to evacuate."

A.21.6.2.9 Partial termination can occur when a particular group of elevators has been taken out of service because they have been recalled under automatic Elevator Phase I Emergency Recall Operation, but other elevator(s) in the elevator evacuation zone are still available for evacuation.

A.21.6.2.10 OEO will not actuate if no elevators are available. There are several instances where signals must be received from the elevator system. One of these is when the Elevator Phase I Emergency Recall key switch is used to manually initiate recall for all elevators. Another situation requiring a signal from the elevator system is when the elevator system cannot provide the intended operation. In this case the fire alarm system needs to know so it does not provide incorrect messaging to a floor(s). See also A.21.6.2.6.3.

A.21.7.2 This Code does not specifically require detection devices used to cause the operation of HVAC system smoke dampers, fire dampers, fan control, smoke doors, or fire doors to be connected to the fire alarm system.

A.21.10.1 Doors are commonly locked for various security reasons. Though doors are permitted to be locked to prevent ingress, doors are generally not permitted to be locked to restrict egress unless specifically permitted by governing laws, codes, and standards. Examples of special locking arrangements include delayed egress locking and access control locking. Approved locking requirements by governing laws, codes, and standards can vary extensively. For example, some might require all fire alarm initiating devices to immediately unlock electrically locked egress doors, while others might permit such doors to remain locked when a single manual fire alarm box is actuated. Some codes might also permit electrically locked doors to remain locked when a single smoke detector has actuated. These allowances are typically permitted only in sprinklered buildings and are generally used as additional safeguards to counter efforts to breach security, without compromising occupant safety.

A.21.10.3 A problem could exist when batteries are used as a secondary power source if a fire alarm control unit having 24 hours of standby operating power were to lose primary power and be operated for more than 24 hours from the secondary power source (batteries). It is possible that sufficient voltage would be available to keep the doors locked, but not enough voltage would be available to operate the fire alarm control unit to release the locks.

A.21.11 When a fire alarm evacuation signal actuates, the exit marking system will be actuated. In some cases, the activation might be sequenced to meet the fire safety plan of the property.

A.23.1.1 Chapter 23 is intended to cover alarm and signaling systems and their components, such as fire alarm, mass notification, carbon monoxide, and other signaling systems.

A.23.2.1 Systems can be installed for the purposes of life safety, property protection, or both. Evacuation or relocation is not a required output action for every system installed in accordance with Chapter 23.

A.23.2.2.1.1 Compatibility between software systems is necessary to ensure that the systems can communicate correctly and that the overall system can function as intended. Unfortunately, software that is compatible can become incompatible when the software is updated. Newer revisions of software might not maintain compatibility with older revisions. This paragraph

requires that the fire alarm software or firmware that interfaces with software or firmware in another system is compatible. An example might be a smoke control system that gets information from the fire alarm system. The term “required” indicates that this compatibility requirement is intended for required functions (e.g., smoke control) and not for supplemental functions that are not part of the required operation of the fire alarm system. An example of a supplemental function might be an RS-232 port that connects to a terminal emulator program used for maintenance purposes. The term “functionally” is intended to ensure that the intended functionality is maintained by the software. It is trying to avoid a situation where a change in software revision might still be compatible but changes the available functionality so that the two systems no longer perform the intended functions, even though the software communicates correctly.

A.23.2.2.1.2 Compatibility between systems will be documented in one or the other (or both) of the manufacturer’s installation documents for the compatible products and controlled by the listings agencies. This documentation will be referenced in the marking on the product. The documentation might be paper copy or electronic media (disk, website, etc.). When a software revision changes, the documentation can be consulted to ensure that it is still compatible with the software or firmware on the other side of the interface.

A.23.2.2.2 A commonly used method of protecting against unauthorized changes can be described as follows (in ascending levels of access):

- (1) *Access Level 1.* Access by persons who have a general responsibility for safety supervision, and who might be expected to investigate and initially respond to a fire alarm or trouble signal
- (2) *Access Level 2.* Access by persons who have a specific responsibility for safety, and who are trained to operate the control unit
- (3) *Access Level 3.* Access by persons who are trained and authorized to do the following:
 - (a) Reconfigure the site-specific data held within the control unit, or controlled by it
 - (b) Maintain the control unit in accordance with the manufacturer’s published instructions and data
- (4) *Access Level 4.* Access by persons who are trained and authorized either to repair the control unit or to alter its site-specific data or operating system program, thereby changing its basic mode of operation

A.23.3.1 Building codes provide requirements for systems such as sprinklers, fire alarm systems, standpipe systems, and so forth.

These requirements are based on the occupancy of a building. Inspection and testing verifies compliance to the code(s). Upon completion of all inspection and testing, the authority having jurisdiction will issue an occupancy permit, allowing people to utilize the building for its intended use.

Once the occupancy permits have been granted, these systems are not allowed to be removed or modified without the approval of the property or building or system owner or the owner’s designated representative. See 23.6.3.5.

This can create issues when there is not a clear understanding of the separation between the fire protection system and the tenant equipment. Class N shared pathways allow for Level

1 or Level 2 pathways to be shared with life safety and non-life safety equipment as long as the criteria outlined in 23.6.3 is met. The building system is allowed to leverage the tenant's equipment, and in this case the tenant is not allowed to remove or modify that equipment.

The use of Ethernet (wired or wireless) is an example where the tenant might have installed an Ethernet infrastructure that could easily be leveraged for the installation of additional fire alarm system capacity, but once that system is installed, tested, and inspected per the code, the IT team can no longer remove or modify the system without the approval of the property or building or system owner or the owner's designated representative.

A.23.3.2 Nonrequired fire alarm features are defined in 3.3.187. These are fire alarm systems or components that are not required by the building or fire codes and are installed voluntarily by a building owner to meet site-specific fire safety objectives. There is a need to properly document the nonrequired system and components. Nonrequired components must be operationally compatible in harmony with other required components and must not be detrimental to the overall system performance. It is for this reason that 23.3.2.1 mandates that nonrequired (voluntary) systems and components meet the applicable installation, testing, and maintenance requirements of this Code. It is not the intent of the Code to have the installation of nonrequired (voluntary) systems or components trigger a requirement for the installation of additional fire alarm components or features in the building. For example, if a building owner voluntarily installs a fire alarm control unit to transmit sprinkler waterflow signals to a central station, that does not trigger a requirement to install other fire alarm system components or features, such as manual fire alarm boxes, occupant notification, or electronic supervision of sprinkler control valves. See also A.17.5.3.3 and A.18.1.5.

Alternatively, supervision and power requirements are required to be taken into account for the nonrequired components/systems on the required fire alarm systems.

A.23.3.3.1 The following functions are included in Annex A to provide guidelines for utilizing building systems and equipment in addition to proprietary fire alarm equipment in order to provide life safety and property protection. Building functions that should be monitored, initiated, or controlled during a fire alarm condition include, but should not be limited to, the following:

- (1) Elevator operation consistent with ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*
- (2) Unlocking of stairwell and exit doors (*see NFPA 80 and NFPA 101*)
- (3) Release of fire and smoke dampers (*see NFPA 90A and NFPA 90B*)
- (4) Monitoring and initiating of automatic fire extinguishing system(s) or suppression system(s) and equipment in accordance with the applicable NFPA standard(s)

A.23.3.3.2 Examples of dedicated function fire alarm systems would include an elevator recall control and supervisory control unit, as addressed in 21.3.2, or a system used specifically to monitor sprinkler waterflow and supervisory functions.

A.23.4.2.2 The intent of this paragraph is to prevent situations where the signaling line circuit to a device is required to be one class of operation, while the power circuits, running in the

same raceways and subject to the same threats, are wired to a lower class of operation. This means that it is possible to have power wiring connected to a device that is of a different class than the signaling line or initiating device circuits. One example of where meeting the same minimum performance requirements would still allow different classes of wiring is where the performance requirements are based on distance or the number of devices attached to the wires. For example, if the signaling line circuit supplies 200 devices and the performance requirement is that not more than 10 devices be lost to a wiring fault, then the class of wiring on the signaling line circuit will be Class A, with isolators to protect against shorts. Where the power wires never supply more than 10 devices, the power wires could be wired as Class B.

A.23.6.1 The intent of 23.6.1 applies to both short-circuit faults and open-circuit faults.

Fire alarm and signaling system communications technologies have evolved to the point that SLCs are now the prevalent means of monitoring initiation devices, controlling output devices, and communicating between panels, annunciators, and controllers.

The extent of coverage of traditional IDCs is inherently limited based on the quantity of powered initiation devices or code limitations. Similarly, the extent and coverage of NACs also are limited by the power required to operate the devices. SLCs, unlike IDCs and NACs, have few limitations, and it is now common that a single SLC can monitor and control more than 250 devices. In addition, a single SLC can be the only pathway by which alarms are initiated, emergency control functions are controlled, and audible and visual notification appliances are actuated.

A total catastrophic failure of a fire alarm and life safety system due to a single open or short on an SLC can negate most, if not all, of this Code's requirements for specifying an acceptable minimum level of performance and reliability for the protection of life and property from fire.

Designers should carefully consider the potential that a single SLC short or open caused by a fire or inadvertent damage to the SLC could disable an entire SLC prior to the activation of an alarm condition along with the subsequent alarm signaling and emergency control functions.

With traditional IDCs and NACs, a single open, ground, or short fault on one circuit could not affect the performance of other IDCs, NACs, and emergency control circuits. As such, the occurrence of a single short or open could limit the extent of the failure to a particular zone or area.

One method for providing an acceptable level of performance and reliability of SLCs is to limit the potential catastrophic failure to one zone, in a way similar to how traditional IDCs and NACs have been and are now required to do.

A single zone could be designated in the following ways:

- (1) By floor where an SLC would not span multiple floors
- (2) By floor area, where a large floor would be split into multiple zones based on a maximum floor area size (e.g., 22,500 ft²)
- (3) By fire barrier or smoke barrier compartment boundaries, which an SLC would not cross
- (4) By maximum length or circuit, where an SLC would not be longer than a predetermined length (e.g., 300 ft)

See the definition of zone (3.3.339) and Figure A.23.6.1(a) through Figure A.23.6.1(d) for additional clarification.


Figure A.23.6.1(a) depicts a Class B SLC with four zones. Wiring of more zones would require one isolator for each additional zone. The isolator can be integrated into the device or a separate component. If a single short or open occurs beyond the isolators, only one zone will be affected.

Figure A.23.6.1(b) depicts a Class A SLC with four zones. Wiring of more zones would require one isolator for each additional zone. The isolator can be integrated into the device or a separate component. If a single short or open occurs, only one zone will be affected. If a single open occurs, no devices will be affected.

Figure A.23.6.1(c) depicts a hybrid Class A SLC loop with Class B SLC branches serving four zones that is designated as a Class B SLC. Wiring of more zones would require one isolator for each additional zone. The isolator can be integrated into the device or a separate component. If a single short occurs, only one zone will be affected. If a single open occurs, it might affect only one zone.


Figure A.23.6.1(d) depicts an incorrect Class B SLC configuration with four zones. If a single short or open occurs, one or more zones could be affected depending on the location of the single short.

A.23.6.1.3 The intent is to clarify that the requirement identified in 23.6.1 applies only to SLCs that connect to addressable devices and not to SLCs that interconnect fire alarm control units (FACU) or transponders.




Note: Paragraph 23.6.1.3(2) allows an un-isolated circuit in metallic raceway or other equivalently protected method that does not exceed 3 ft (0.9 m) in length.

FIGURE A.23.6.1(a) Class B Isolation Method.



Note: The two isolation modules shown at the FACU are not required if the panel SLC controller is internally isolated from shorts between outgoing and return termination points.

FIGURE A.23.6.1(b) Class A Isolation Method.



Note: The two isolation modules shown at the FACU are not required if the panel SLC controller is internally isolated from shorts between outgoing and return termination points.

FIGURE A.23.6.1(c) Hybrid Isolation Method.




FIGURE A.23.6.1(d) Incorrect Use of Isolators on an SLC.

A.23.6.1.3(3) In many cases, existing systems are partially modified with addressable devices being added as a part of the scope of work. In this case the SLC might not have been installed in a manner that could be easily modified to accommodate isolation modules and/or keep a single SLC loop confined to a single zone. This condition makes it clear that the requirements of SLC zones do not apply to existing systems that were not required to meet the zoning requirements of 23.6.1 when originally installed.

A.23.6.1.5 Possible scenarios in which a designer might choose to permit loss of more than one zone include a multi-story building with a small floor plan footprint where a limited number of addressable devices are located on the floor (e.g., one manual fire alarm box and two automatic fire detection devices). In this scenario, the designer might choose to include multiple floors of devices on the same signaling line circuit because the loss of such devices due to a single SLC short or open would disable a limited number of devices.

Another scenario could include buildings with a small vestibule at the top of a stair that exits onto the roof of a building. The vestibule might contain one manual fire alarm box and one or two automatic fire detection devices that could be connected to the signaling line circuit on the floor below and considered the same zone.

Designers providing documents for upgrades to an existing building where the control units and all fire alarm system devices are being replaced but some portion of the existing circuits are being reused might, because of constructability reasons, opt for combining zones and the associated risk of the loss of those devices due to a single SLC short or open.

The intent of 23.6.1.5 is not to impose an unnecessary burden on building owners with existing systems undergoing renovations, upgrades, or replacements. In these scenarios as

well as others, the designer would be required to provide a documented, performance-based design approach to justify why the loss of more than one zone is acceptable. Documentation must be composed in accordance with 23.6.2.4 and be submitted in accordance with 7.3.7.5.

A.23.6.2 Class N systems should mitigate risk that could be present when a zone or area is serviced by a single Class N device. However, 23.6.2 is not intended to automatically require the installation of twice as many (or more) Class N devices as compared to a design based on Class A, B, or X pathways. The risks inherent to Class N are different from the risks inherent to Class A, B, or X.

Class A and B pathways are permitted to lose devices in a zone (see Section 23.6) upon a multiple ground-fault pathway failure. Class A and B pathways require a single ground to be annunciated as a trouble signal. The requirement is to annunciate the first ground fault and alert the user so that the ground fault can be addressed before a possible second ground fault occurs. Note that a second ground fault is also annunciated at the systems operator interface because communication is lost.

Class X pathways are not permitted to lose devices in a zone (see Section 23.6) upon a multiple ground-fault pathway failure that results in a short circuit across the pathway. Class X pathways require a single ground to be annunciated as a trouble signal. The requirement is to annunciate the first ground fault and alert the user so that the ground fault can be addressed before a possible second ground fault occurs.

By contrast, Class N is not required to report a trouble condition at the occurrence of the first ground fault because it limits the loss to a single device if another ground occurs. A second ground fault in the Class N pathway, like Class A and B pathways, annunciates a trouble condition at the systems operator interface because communication is lost.

In summary, the potential risk of a loss of fire alarm function in an area must be considered in Class N network design. Multiple ground faults might cause such a loss in an area, especially after no one was alerted of a trouble condition at the first ground fault.

The term “device” in this context should be understood in conjunction with the definition of Device (Class N) 3.3.78 and the associated annex material A.3.3.78. An area is a separated space within a zone where initiating devices or notification appliances are required. Examples include an office, conference rooms, or temporary partitioned banquet rooms where alarm notification is required. Factors to consider when determining the need for multiple Class N devices within an area or zone include the following: whether the space is acoustically and/or visually isolated; specific audible and visual indication of trouble to the occupants in that area for a related ground-fault pathway failure of any device/appliance in that area; the pathways to devices in the area are not susceptible to ground faults such as fiber-optic or wireless pathways.

Also, multiple devices are not required when devices/appliances are connected by redundant pathways. For example, consider the dual port devices deployed as per A.12.3.6(5). For example, the failure of a sole Class N initiating device might delay or prevent the timely initiation of an alarm.

Depending on the facility and the risks for that occupancy, areas serviced by single devices, without redundant pathways,

that are susceptible to ground faults should be established by the system designer and approved by the authority having jurisdiction.

A.23.6.2.3 This requirement is to ensure that devices without redundant pathways are not used to terminate additional equipment such that a loss of the pathway would result in more than one device failure to communicate and operate as intended. This stipulation does not apply to dual port devices as described in A.12.3.6(5), because these devices support redundant pathways. A dual port device that is used to daisy-chain additional devices without a redundant pathway would be prohibited.

The term “device” in this context should be understood in conjunction with the definition of Device (Class N) 3.3.78 and the associated annex material A.3.3.78.

A network-based audio amplifier is an example of an addressable device that can receive a digital audio input from the Class N pathway and then provide a notification appliance circuit (NAC) output with Class A, B, or X pathways. Other endpoint devices can similarly provide alternate class pathways for visual notification appliances (strobes) (NACs) or initiating devices (IDCs). From the perspective of the Class N pathway, communications terminates at this endpoint device. However, since these types of endpoints can support multiple notification appliance devices or initiating devices, Class N path segments are still subject to the redundant pathway requirement unless protected in an enclosure or raceway less than 20 ft (6 m) in length. [See Figure A.12.3.6(1)(c).]

A.23.6.2.4 This clause is a consequence of the definition of Class N, which permits a single pathway to be used when only one device is served. [See 12.3.6(1).] This exception to the requirement of redundant pathways allows for the loss of operational capability to a single device. Unplugging, grounding, or cutting any single Ethernet cable or conductor cannot affect more than one Ethernet device and cannot affect additional devices, Ethernet or otherwise, in the system.

A.23.6.3.3 All shared pathways defined as Class N should be documented, including all equipment connected to the shared pathways, interconnecting methods identifying required redundant communication pathways, end points, techniques used for proper supervision, and possible risk due to shared pathway failures. As an example, for wired Ethernet, the designer might want to use cabling techniques identified in standards such as ISO/IEC 14763-3, *Informational technology — Implementation and operation of customer premises cabling — Part 3: Testing of optical fibre cabling*, to satisfy the requirements of the authority having jurisdiction.

A.23.6.3.3.1.2 Cable installations should be tested with appropriate field test measurement equipment in accordance with applicable standards such as TIA 526, *Standard Test Procedures for Fiber Optic Systems*, or other standards acceptable to the authority having jurisdiction. For example, testing requirements for Category 5 or higher balanced twisted-pair cabling should include the following:

- (1) Wire map (e.g., continuity, pairing)
- (2) Length
- (3) Insertion loss
- (4) NEXT loss
- (5) ACR-F (formerly called *ELFEXT*)
- (6) Propagation delay and delay skew
- (7) Return loss

- (8) Power sum near-end crosstalk (PSNEXT) loss
- (9) PSACR-F (formerly called *PSELFEXT*)

Testing requirements for fiber-optic cabling should include the following:

- (1) Attenuation
- (2) Optical bandwidth
- (3) Length

A.23.6.3.3.2 All ports need to be properly identified and labeled. For example, Class N switches should be permanently labeled “LIFE SAFETY EQUIPMENT – NO UNAUTHORIZED USE,” or plugs should be used to prevent access.

A.23.6.3.3.3.2 Life safety Class N network cabling, equipment, and infrastructure might include (but is not limited to) Ethernet switches, media converters, uninterruptible power supplies, separate life safety network dedicated branch circuit power, cabling cross connects, and both copper and optical fiber cabling.

A.23.6.3.5.1 Regular inspection, testing, and maintenance are conducted on life safety systems. In traditional systems a single certified entity was typically capable of servicing the fire alarm control unit, transport equipment, and/or wiring associated with it. Class N systems will often use modern network infrastructure that might fall outside the expertise of the life safety-certified entity, or other building systems could share the infrastructure used to create the Class N network. The property or building or system owner or the owner’s designated representative has responsibility to maintain a list of certified entities that are capable of servicing and maintaining the life safety system and the Class N network. This is what *NFPA 72* refers to as a *management organization*. For example, if the Class N network runs through Ethernet switches and routers, the premises IT infrastructure should be maintained by service personnel as referenced in 10.5.3.3.

A.23.6.3.5.2 During inspection, testing, or maintenance it could be necessary to temporarily disable or test part of a life safety system. The *management organization* is responsible to ensure that other affected entities are notified and action plans put in place to ensure appropriate life safety coverage is maintained and appropriate notification is given to other entities such as the fire or security monitoring services.

A.23.6.3.6.1 When shared pathway Level 1 or Level 2 is employed, care should be taken to ensure that the life safety system(s) traffic has priority over other systems sharing the Class N network to maintain the required bandwidth. Other systems might have unspecified or unpredictable bandwidth usage (such as a manually controlled security camera); therefore, the analysis should specify the method(s) used to ensure the required life safety bandwidth is maintained under all circumstances. The network design analysis should show this and be signed by the property or building or system owner or the owner’s designated representative responsible for the design for the authority having jurisdiction to review.

A.23.6.3.6.2 Primary and backup power should meet the requirements of *NFPA 72*. Life safety equipment and their connected equipment (Class N transport devices when not powered by the FACU) should utilize dedicated branch circuits for primary power. This is to prevent other loads from tripping a circuit breaker connected to the FACU and to prevent inadvertent disconnecting of primary power to the FACU.

The branch circuit disconnecting means (circuit breakers) should be clearly labeled and made only accessible to authorized personnel.

FACUs are required to have a secondary power source that must last for 24 hours of standby (nonalarm) power followed by either 5 (non-voice systems) or 15 (voice systems) minutes of alarm power. This is typically accomplished by backup batteries or by an emergency generator. All transport equipment not powered by the FACU has the same requirement. The analysis should document the calculation of all power requirements (standby and alarm) of the FACU and transport equipment to ensure that the system can meet this requirement. To meet this requirement, non-life safety systems could be disconnected from the secondary power source.

A.23.6.3.6.2(2) Where Class N networks incorporate power over communications cables, outputs are rated based on various systems. Section 725.144 of *NFPA 70* limits the number of 4-pair cables that can be bundled based on the current provided by the power source for these systems. The current rating marked on the power source equipment as required by 725.121(C) of *NFPA 70* for the outputs can be used to apply the requirements of 725.144 of *NFPA 70*.

One of the more common systems uses Power over Ethernet (PoE) technology standardized in IEEE 802.3bt, *IEEE Standard for Ethernet Amendment 2: Physical Layer and Management Parameters for Power over Ethernet over 4 pairs*. The information in Table A.23.6.3.6.2(2) shows allowable bundle sizes. It is derived from Table 725.144 of *NFPA 70* but temperature adjusted to 120°F (49°C) ambient as required by 10.3.5 of this Code.

Currently IEEE 802.3bt recognizes four PoE Types (Types 1 through 4). Each Type establishes a maximum power limit as supplied by the power sourcing equipment (PSE), commonly a PoE switch. Type 1 is limited to 15.4 W, Type 2 to 30 W, Type 3 to 60 W, and Type 4 to 90 W.

A.23.6.3.7.1 Maintenance is a critical aspect of fire alarm systems, and a plan needs to be in place to empower continued operation of the fire alarm system. Shared Class N pathways present a unique concern in that non-fire alarm technicians could perform maintenance or changes to the Class N equipment or pathways. For example, routine updates to software in the routers and switches or upgrades to address new non-fire alarm needs. This could result in outages of the portions of the fire alarm system or affect the subsequent operation of the fire alarm system. It is crucial that the maintenance plan address policy and procedure to monitor, maintain, and test per Chapter 14 and control change of the shared pathways to contribute to continued intended operation of the fire alarm system. For example, 14.4.2.5 states that changes to system executive software require a 10 percent functional test of the system, including typical network infrastructure such as routers and switches that now need consideration as part of the life safety network maintenance plan.

A.23.6.3.7.2 Written procedures should address who can access the Class N network; how the procedures will be implemented; the level of retesting of the system needed when software updates to the Class N network infrastructure such as routers and switches are made; and the effect of changes on system response times to ensure required time limits are maintained.

A.23.6.3.7.2(3) The planned impairment process is used to control change in the system and inform stakeholders. Any activities that can affect the performance of the network or impact conclusions of a risk analysis should be presented to the organization referred to in 23.6.3.5 for approval. The organization should have a name (e.g., Life Safety Network Management Group). All stakeholders who could be affected by network outages should have representation in the organization.

A committee made up of members of the organization should meet on a regular basis and report to the organization. All planned impairments should have 7 days' notice. An emergency impairment (one with less than 7 days' notice) should meet very stringent standards for urgency. Outages and repair operations are dealt with on a case by case basis with the fire marshal's office, and the Department of Public Safety is included based on the operational impact.

All proposed changes and outages are to be presented to the organization for authorization, scheduling, and coordination. Once a change has been authorized and scheduled, an impairment notification is issued notifying all affected users. If specific mitigation actions, such as fire watch, are required, they are to be included in the impairment notification.

Impairment notifications are issued through the fire marshal's office, the Department of Public Safety, the Power Outages Group, or other groups depending on the systems affected.

A "login banner" is a programmable option for network switches and routers. This banner is the first thing that comes up on the screen when you log into the equipment. Where practical, network equipment used in life safety systems should have a login banner to notify service personnel that the network is a part of an active life safety system and any impairment should be coordinated with the named organization.

A.23.6.3.8 Although this section outlines some specific criteria and/or limitations, each application should be based on recognized performance-based design practices and the emergency response plan developed for the specific facility. Here are the general categories of questions that might be presented to the stakeholders responsible for Class N shared network design decisions. The actual questions for each project must be tailored to the area, the building, the campus, and the culture of the user organization and the nature of how the network is being shared. The requirements for the life safety network should be evaluated with respect to the types of emergency events and emergency response plan. The potential impact of these events upon the life safety network also should be evaluated.

- (1) What types of emergency events could affect the life safety network (e.g., fire, security, safety, health, environmental, geological, meteorological, utility service disruption, or other types of events)?
- (2) What is the anticipated or expected severity of the emergency events, that is, how will they impact the facility and its functions? Are they expected to be extreme, severe, and so forth?
- (3) What is the certainty of the emergency event, that is, is it happening now, is it very likely to occur, is it likely to occur, is it possible that it will occur in the future, is it unlikely to occur, or is its occurrence unknown?

Table A.23.6.3.6.2(2) NFPA 70 Cable Bundle Table 725.144 Viewed from a PoE Type Perspective

	24 AWG: Number of 4-Pair Cables in a Bundle Corrected to 120°F (49°C), per Table 310.15(B)(1) of NFPA 70																	
	1–7			8–19			20–37			38–61			62–91			92–192		
	Temperature Rating			Temperature Rating			Temperature Rating			Temperature Rating			Temperature Rating			Temperature Rating		
IEEE 802.3bt Type Classification	60	75	90	60	75	90	60	75	90	60	75	90	60	75	90	60	75	90
Type 1	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Type 2	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Type 3	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes*	Yes	Yes	Yes*	Yes	Yes
Type 4	Yes	Yes	Yes	Yes	Yes	Yes	No	Yes	Yes	No	Yes	Yes	No	No	Yes	No	No	Yes
	23 AWG: Number of 4-Pair Cables in a Bundle Corrected to 120°F (49°C), per Table 310.15(B)(1) of NFPA 70																	
	1–7			8–19			20–37			38–61			62–91			92–192		
	Temperature Rating			Temperature Rating			Temperature Rating			Temperature Rating			Temperature Rating			Temperature Rating		
IEEE 802.3bt Type Classification	60	75	90	60	75	90	60	75	90	60	75	90	60	75	90	60	75	90
Type 1	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Type 2	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Type 3	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes*	Yes	Yes
Type 4	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	No	Yes	Yes	No	Yes	Yes	No	No	Yes
	22 AWG: Number of 4-Pair Cables in a Bundle Corrected to 120°F (49°C), per Table 310.15(B)(1) of NFPA 70																	
	1–7			8–19			20–37			38–61			62–91			92–192		
	Temperature Rating			Temperature Rating			Temperature Rating			Temperature Rating			Temperature Rating			Temperature Rating		
IEEE 802.3bt Type Classification	60	75	90	60	75	90	60	75	90	60	75	90	60	75	90	60	75	90
Type 1	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Type 2	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Type 3	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Type 4	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	No	Yes	Yes	No	Yes	Yes	No	Yes	Yes

Notes:

1. "Yes" indicates that the bundle size of the gauge and temperature cable is permitted for the IEEE Class in the leftmost column per NFPA 70. "No" designates bundle sizes that are not permitted.

2. IEEE 208.3bt: The PoE maximum permitted average current per conductor: Type 1: 175 mA, Type 2/3: 300 mA, Type 4: 433 mA.

*Section 725.144 (A) exception of NFPA 70 for currents of not more than 300 mA for conductors 24 AWG or greater is applied for Types 1, 2, and 3.

- (4) Natural hazards: What are the network risks to the implementation of the emergency response plan in response to natural hazard events? What are the types of emergency events that could be predicted to result from natural hazard events? For example, if flooding is possible in the surrounding area, how would a flood affect the life safety network while operating in its normal, monitored state? What would happen if a fire alarm occurred during a flood? How likely is it that a flood could damage the life safety network? What related events might impact the life safety network and equipment, such as a power outage?
- (5) Human caused: What are the network risks to the implementation of the emergency response plan in response to accidents or intentional acts? What are the types of emergency events that could be predicted from both within and outside the protected premises? What type of related

damage might be expected to impact the life safety network and equipment, such as explosions?

- (6) Technological caused: What are the network risks to the implementation of the emergency response plan in response to technologically caused events or failures and the types of emergency events that could be predicted to result from a technologically caused event both within and outside the protected premises. What type of related damage might be expected to impact the life safety network and equipment, such as a network attack?
- (7) Network maintenance risks: What are the network risks to the implementation of the emergency response plan in response to a degradation of network software performance (e.g., an unintended degradation of performance due to software updates) or a degradation of physical network performance or implementation (e.g., physical

damage, system modifications)? What types of emergency events could be predicted to result from a degradation of the life safety network? What type of related impairments might be expected to impact the components of the life safety network and equipment, such as environmental controls?

The questions suggested in items (1) through (7) are offered for consideration, and not all of them might be appropriate for every life safety network installation.

A.23.8.1.1 A system provided with an alarm verification feature as permitted by 23.8.5.4.1 is not considered a presignal system, since the delay in the signal produced is 60 seconds or less and requires no human intervention.

A.23.8.1.2.1.1(6) “Immediately actuated” means there are no delays imposed by the system other than the processing of the signal in accordance with 23.8.1.1.

A.23.8.1.2.1.2 The bypass means is intended to enable automatic or manual day, night, and weekend operation.

A.23.8.2 This Code addresses field installations that interconnect two or more listed control units, possibly from different manufacturers, that together fulfill the requirements of this Code.

Such an arrangement should preserve the reliability, adequacy, and integrity of all alarm, supervisory, and trouble signals and interconnecting circuits intended to be in accordance with the provisions of this Code.

Where interconnected control units are in separate buildings, consideration should be given to protecting the interconnecting wiring from electrical and radio frequency interference.

A.23.8.2.7.4 Where interconnected fire alarm control units have unsupervised form C contacts that change status during a trouble condition, annunciators installed at each control unit provide status indication.

A.23.8.2.11.1 Remote access is achieved by, but not limited to, the use of cellular technology, internet-based technology, or radio frequency technology. Paragraph 23.8.2.11 is intended to address the following activities: testing, maintenance, diagnostics, and software upgrade performed through remote access.

A.23.8.2.11.3(1) It is the intent to require two separate means of manually terminating the remote access connection with one of them being performed at the system control unit by a person on-site.

A.23.8.2.11.3(2) It is the intent that the remote connection be automatically terminated upon no activity or changes being performed for a period of one hour. The inactivity limitation of one hour is used as a reasonable time period.

A.23.8.2.11.4 Remote diagnostics involves queries of the system and does not involve changing the system.

A.23.8.2.11.4(1) It is the intent to require two separate means of manually terminating the remote access connection with one of them being performed at the system control unit by a person on-site.

A.23.8.2.11.4(2) It is the intent that the remote connection be automatically terminated upon no activity or changes being

performed for a period of one hour. The inactivity limitation of one hour is used as a reasonable time period.

A.23.8.2.11.5(1) It is the intent to require two separate means of manually terminating the remote access connection with one of them being performed at the system control unit by a person on-site.

A.23.8.2.11.5(2) It is the intent that the remote connection be automatically terminated upon no activity or changes being performed for a period of one hour. The inactivity limitation of one hour is used as a reasonable time period.

A.23.8.4.1 The provisions of 23.8.4.1 apply to types of equipment used in common for fire alarm systems, such as fire alarm, sprinkler supervisory, or guard's tour service, and for other systems, such as burglar alarm or coded paging systems, and to methods of circuit wiring common to both types of systems. The intent of connecting non-fire systems with the fire alarm system is often to cause the non-fire systems to react appropriately when signaled by the fire alarm system.

A.23.8.4.2.1 Buildings are advancing with technologies in HVAC, security, elevators, energy controls, and lighting. Building operators and designers expect to be able to integrate various building systems with human interfaces.

First responders are embracing new technologies, and the fire life safety systems have a lot of information to assist them in emergency response and also system evaluation.

For the first time, *NFPA 72* introduces the use of the common PC workstation technology having the UL listing for “shock and hazard” to be a part of the total building system without the UL 864 listing, which was a hindrance to the advancements in technologies.

A.23.8.4.2.2.2 When the BSIU is not available to control the fire alarm system, the FACU within the room must be able to perform all the necessary controls of the fire alarm system without relying on the BSIU.

A.23.8.4.4 For systems such as carbon monoxide detection, fire extinguisher electronic monitoring device, emergency communications (mass notification), or intrusion, much of the benefit of a combination system comes from being able to use common wiring. If the equipment in the combination system is of equivalent quality to fire alarm equipment, and the system monitors the wiring and equipment in the same way as fire alarm equipment, then sharing of wiring is permitted. If the equipment is not of equivalent quality, isolation between the systems would be required.

A.23.8.4.7 Examples of signal classification are provided in Table A.23.8.4.7. This is not all-inclusive or prescriptive but is meant to illustrate a potential classification scheme. Actual schemes might vary depending upon the emergency response plan and/or requirements of the authority having jurisdiction. Mass notification systems are allowed to take priority over the fire alarm audible notification message or signal. This is intended to allow the mass notification system to prioritize emergency signals on the basis of risk to building occupants. The designer should specify the desired operation, in particular, as to what should occur immediately after the mass notification message has completed.

Table A.23.8.4.7 Examples of Signal Classification

Life Safety	Property Protection	Trouble	Other
Fire alarm signals	Security signals	Battery fault	HVAC signals
Carbon monoxide alarm signals	Supervisory signals	AC power failure	Occupancy
Code blue signals	Access control	IDC faults	
Panic alarms		NAC faults	
Hazmat signals		SLC faults	
Severe weather warnings			
Flood alarms			
Mass notification signals			
Holdup alarm signals			

A.23.8.4.9.2 Response to carbon monoxide alarm signals could include, but not be limited to, any one of the following: immediate evacuation of occupants, immediate call to the fire department or other responding authorities, relocation of occupants to another portion of the building, investigation of the area identified, and/or opening of all doors and windows to the outside in the area identified.

A.23.8.4.10 See NFPA 10 for more information on portable fire extinguishers.

A.23.8.5.1.2 The manual means required by 23.8.5.1.2 is intended to provide a backup means to manually actuate the fire alarm system when the automatic fire detection system or waterflow devices are out of service due to maintenance and follow-up testing, or where human discovery of the fire precedes automatic sprinkler system or automatic detection system activation. The manual means is only intended for use by the system technician or the building owner and should be located by the sprinkler riser or fire alarm control unit.

During maintenance and follow-up testing, the manual fire alarm box required by 23.8.5.1.2 should be connected to a separate circuit that is not placed "on test" when the detection or sprinkler system is placed "on test." Aside from those instances where maintenance is needed, the manual fire alarm box required by this section is still subject to the periodic testing requirements outlined in Chapter 14.

A.23.8.5.3.2 Where power is supplied separately to the individual initiating device(s), multiple initiating circuits are not prohibited from being monitored for integrity by a single power supervision device.

A.23.8.5.4.1 The alarm verification feature should not be used as a substitute for proper detector location/applications or regular system maintenance. Alarm verification features are intended to reduce the frequency of false alarms caused by transient conditions. They are not intended to compensate for design errors or lack of maintenance.

A.23.8.5.4.6.3 Where a separate power source is provided for a duct smoke detector, consideration should be given to provide a secondary power source for the duct detector power source as a power failure to the duct detector will (or should) indicate a trouble condition on the fire panel. If the system is connected to an off-premises monitoring station, a trouble signal will be sent immediately upon power failure. This is in contrast to the intent and requirements to delay the off-premises reporting of primary power failures.

A.23.8.5.5 This Code does not specifically require a waterflow alarm initiating device to be connected to the building fire alarm system. Connection to the building fire alarm system would be determined by the requirements established by the authority having jurisdiction. See A.1.2.4.

A.23.8.5.5.3 Circuits connected to a signaling line circuit interface are initiating device circuits and are subject to these limitations.

A.23.8.5.6 This Code does not specifically require supervisory signal initiating devices to be connected to the building fire alarm system. Connections to the building fire alarm system would be determined by the requirements established by the authority having jurisdiction. See A.1.2.4. Some systems utilize nonelectrical methods to supervise conditions of the system such as chains on sprinkler control valves.

Supervisory signals are not intended to provide indication of design, installation, or functional defects in the supervised systems or system components and are not a substitute for regular testing of those systems in accordance with the applicable standard. Supervised conditions should include, but not be limited to, the following:

- (1) Control valves 1½ in. (38.1 mm) or larger
- (2) Pressure, including dry pipe system air, pressure tank air, preaction system supervisory air, steam for flooding systems, and public water
- (3) Water tanks, including water level and temperature
- (4) Building temperature, including areas such as valve closet and fire pump house
- (5) Electric fire pumps, including running (alarm or supervisory), power failure, and phase reversal
- (6) Engine-driven fire pumps, including running (alarm or supervisory), failure to start, controller off "automatic," and trouble (e.g., low oil, high temperature, overspeed)
- (7) Steam turbine fire pumps, including running (alarm or supervisory), steam pressure, and steam control valves

A.23.8.5.6.3 Circuits connected to a signaling line circuit interface are initiating device circuits and are subject to these limitations.

A.23.8.5.6.4 Some ball valves installed on air pressure lines connected to a pressure switch for dry pipe sprinkler systems or certain types of preaction sprinkler systems will cause the air pressure that is trapped in the line between the valve and the supervisory signal initiating device to bleed off when the valve is turned to isolate the initiating device. This will cause the initiating device to operate and signal the low air supervisory condition. The arrangement is permitted by other standards

and provides a fail-safe way to test a low air pressure signal without risking activation of the system.

A.23.8.5.8 See A.23.8.5.6.

A.23.8.6.2 The general purpose of the fire alarm audible and visual notification appliances is to alert occupants that there is a fire condition and for occupants to exit from the building.

Once the occupants are in the exit enclosures, high noise levels and light intensity from notification appliances could cause confusion and impede egress. There could be conditions that warrant the installation of notification appliances in exit passageways, but careful analysis is necessary to avoid impeding exiting from the building.

A.23.8.6.3.3 The building's emergency response plan might specify occupant notification only in the area(s) of initiation and at the control panel. Whole building evacuation might not be specified in the emergency response plan.

A.23.10.2 One or more of the following means might be considered acceptable to provide a level of survivability consistent with the intent of this requirement:

- (1) Installing a fire alarm system in a fully sprinklered building in accordance with NFPA 13
- (2) Routing notification appliance circuits separately
- (3) Using short-circuit fault-tolerant signaling line circuits for controlling evacuation signals

The requirement for notification appliances to operate in those notification zones that are not attacked by fire will also require that circuits and equipment that are common to more than one notification zone be designed and installed such that

the fire will not disable them. For instance, a signaling line circuit used to control notification appliances in multiple notification zones should be properly designed and installed so that one fire would not impair more than one notification zone. Power supply requirements of Chapter 10 apply to these systems. The secondary power supply requirements of that chapter meet the intent of these survivability requirements.

A.23.11.7 Automatic fire suppression systems referred to in 23.11.7 include, but are not limited to, preaction and deluge sprinkler systems, carbon dioxide systems, Halon systems, and dry chemical systems.

A.23.12.4 Off-premises logging of fire alarm data can be useful to preserve information in the face of fire or building failure to facilitate accurate reconstruction of the event. It can also be beneficial to send data off-premises to incident command personnel to enhance situational awareness and response decisions and to maintain safe and efficient operations. Figure A.23.12.4 shows an example of a network to accomplish these goals.

A.23.16 The term *wireless* has been replaced with the term *low-power radio* to eliminate potential confusion with other transmission media such as fiber optics.

Low-power radio devices are required to comply with the applicable low-power requirements of Title 47, Code of Federal Regulations, Part 15.

A.23.16.1 Equipment listed solely for dwelling unit use would not comply with this requirement.




FIGURE A.23.12.4 Supplemental Reporting Network.

A.23.16.2 This requirement is intended to limit the impact from the failure of a battery operated receiver/transmitter in a given space. This requirement is not intended to prevent a single device that contains multiple function elements, such as a combination carbon monoxide and smoke detector, a detector with an independently controllable sounder, a notification appliance with visible and audible elements, and so forth. This requirement is intended to limit the number of functional elements to one of each independent type. For example, two manual fire alarm boxes could not rely on a single battery.

A.23.16.3.1 This requirement is not intended to preclude verification and local test intervals prior to alarm transmission.

A.23.16.3.1.3 This requirement ensures that an alarm is received in the rare event that the RF channel experiences interference.

A.23.16.3.1.5 Trouble and supervisory signals are not required to latch. Self-restoring trouble and supervisory signals are acceptable.

A.24.1.2 An emergency communications system could target the general building, area, space, campus, or region.

A.24.3.1.1 In certain situations, it is important to provide a distributed sound level with minimal sound intensity variations to achieve an intelligible voice message. This differs from past fire alarm design practice that used fewer notification appliances but with each having greater sound pressure output levels. Nonemergency system design practice is to use more loudspeakers and less sound intensity from each loudspeaker. Besides improving intelligibility of the message, this approach minimizes annoyance to building occupants from the system and lessens the likelihood of tampering with the system by occupants because of loudspeakers being too loud. In other applications, such as outdoor signaling where reverberation is not a problem, intelligibility can be achieved by using fewer appliances or clusters of appliances covering larger areas.

Intelligibility is a complex function of the source audio, the acoustic response of the architectural features and materials of the immediate vicinity, and the dynamics created by the room's occupants. Refer to Annex D for more information on speech intelligibility and how it is predicted. Spacing loudspeakers closely can be an intelligibility-enhancing technique but can occasionally lead to opposite results when improperly designed. There are several techniques using directionality features that do not use closely spaced loudspeakers but rather use the room/space acoustic response in their favor.

A.24.3.1.2 In certain acoustically challenging areas, listed fire alarm loudspeakers might not be capable of producing an intelligible message. Non-fire alarm listed loudspeakers are permitted to be installed in these limited areas. A failure of a non-listed loudspeaker should not disrupt the operation of listed fire alarm loudspeakers and operation of the fire alarm or mass notification control equipment. Typically, a dedicated loudspeaker circuit and other audio components such as amplifiers could be necessary to meet this functionality.

A.24.3.2 Users who speak too softly, too loudly, or who hold a microphone too close, too far, or at an incorrect angle can introduce distortion or cause reduced intelligibility of the spoken message. The characteristics of the system microphone are important ergonomic factors that affect voice intelligibility. Some microphones need to be held close to the mouth, perhaps an inch or less. Others need to be three or four inches

away. How is the user to know what's ideal? A simple diagram next to the microphone can help. Some microphones are very directional and must be held flat in front of the mouth. These microphones are useful in small command centers, since they are less likely to pick up conversations off to the sides. On the other hand, microphones with a wider polar sensitivity are more forgiving for a user to hold comfortably while moving and doing other tasks. Their downside is that they will pick up extraneous noise in poorly designed command centers introduced into the microphone.

A.24.3.3 The requirements found in *NFPA 70* Article 708, should be considered for emergency communications systems that are installed in vital infrastructure facilities classified as a designated critical operations area (DCOA). This includes facilities that, if destroyed or incapacitated, would disrupt national security, the economy, public health or safety and where enhanced electrical infrastructure for continuity of operation has been deemed necessary by governmental authority.

A.24.3.4 The features for a nonrequired system should be established by the system designer on the basis of the goals and objectives intended by the system owner.

A.24.3.5.2 Dedicated in-building fire emergency voice/alarm communications systems are not required to monitor the integrity of the notification appliance circuits while active for emergency purposes. However, these circuits have to be monitored for integrity while active for non-emergency purposes. The building operator, system designer, and authority having jurisdiction should be aware that, in some situations, such a system could be subject to deliberate tampering. Tampering is usually attempted to reduce the output of a sound system that is in constant use, such as background music or a paging system, and that could be a source of annoyance to employees.

The likelihood of tampering can be reduced through proper consideration of loudspeaker accessibility and system operation.

Access can be reduced through the use of hidden or nonadjustable transformer taps (which can reduce playback levels), use of vandal-resistant listed loudspeakers, and placement in areas that are difficult to access, such as high ceilings (any ceiling higher than could be reached by standing on a desk or chair). Non-emergency operation of the system should always consider that an audio system that annoys an employee potentially reduces employee productivity and can also annoy the public in a commercial environment. Most motivations for tampering can be eliminated through appropriate use of the system and employee discipline. Access to amplification equipment and controls should be limited to those authorized to make adjustments to such equipment. It is common practice to install such equipment in a manner that allows adjustment of non-emergency audio signal levels while defaulting to a fixed, preset level of playback when operating in emergency mode. Under extreme circumstances, certain zones of a protected area might require a dedicated in-building fire emergency voice/alarm communications zone.

A.24.3.6.1 See Annex G.

A.24.3.6.2 See Annex G.

A.24.3.7 One-way emergency communications systems are intended to broadcast information, in an emergency, to personnel in one or more specified indoor or outdoor areas. It is intended that emergency messages be conveyed either by audi-

ble or visual textual means or both. This section does not apply to bells, horns, or other sounders and visual notification appliances, except where used in conjunction with the desired operation of emergency messages and signaling.

Two-way emergency communications systems are divided into two categories, those systems that are anticipated to be used by building occupants and those systems that are to be used by fire fighters, police, and other emergency services personnel. Two-way emergency communications systems are used both to exchange information and to communicate information, such as, but not limited to, instructions, acknowledgement of receipt of messages, condition of local environment, and condition of persons, and to give assurance that help is on its way.

NFPA 72 contains requirements that can impact the application of emergency communications systems. For instance, coordination of the functions of an emergency communications system with other systems that communicate audibly and/or visibly [such as fire alarm systems, security systems, public address (PA) systems] is essential in order to provide effective communication in an emergency situation. Conflicting or competing signals or messages from different systems could be very confusing to occupants and have a negative impact on the intended occupant response. Where independent systems using audible and/or visual notification are present, the emergency communications system needs to interface with those

systems to effect related control actions such as deactivating both audible and visual notification appliances. The use of a single integrated combination system might offer both economic and technical advantages. In any case, coordination between system functions is essential. The coordination of emergency communications systems with other systems should be considered part of the risk analysis for the emergency communications system. (See *Figure A.24.3.7*.)

Additional documents such as ANSI/NEMA SB-40, *Communications Systems for Life Safety in Schools*, can also be used as supplemental resources to provide help with risk assessment and application considerations.

A.24.3.7.1 Other codes reference *NFPA 72* with respect to the emergency voice alarm communications (EVAC) systems or design and installation requirements. If EVAC systems are required, they are also required to be listed per UL 864, *Control Units and Accessories for Fire Alarm Systems*. However, owners or designers might identify risks in addition to fire that might also require additional emergency communications systems such as in-building mass notification system (MNS), wide-area MNS, or distributed recipient MNS. If an MNS is included in the design, a risk analysis is required by 24.3.12. In consideration of the risk analysis, related design could include combinations of the emergency communications systems options presented in 24.3.7.1. For example, depending on the specifics of the facility under consideration, the design could include combination




FIGURE A.24.3.7 Emergency Communications Systems.

systems or other combinations of separate EVAC UL 864 and equipment listed per UL 2572, *Mass Notification Systems*, as long as these systems are interfaced in compliance with Chapter 24 and are approved by the AHJ.

Pathway survivability of one-way emergency communications systems is dictated by 24.3.14.4 through 24.3.14.6.

A.24.3.7.2 Pathway survivability of two-way emergency communications systems is dictated by 24.3.14.7 through 24.3.14.16.

A.24.3.8 The layers can be used in combination. In all cases, the system design needs to follow the risk analysis and be integrated into the emergency response plan. Research has shown that more than one layer has been used to be effective. Multiple layers provide an extra level of notification (a safety net). The overall MNS application is likely to exploit a number of public and individual systems or components that combine to produce a reliable and robust solution to achieve emergency notification objectives.

Layer 1 could consist of elements such as the following:

- (1) Emergency voice/alarm communications systems (EVACS)
- (2) In-building mass notification system (MNS)
- (3) One-way voice communication systems (PA)
- (4) Two-way voice communication systems
- (5) Visual notification appliances
- (6) Textual/digital signage/displays

Layer 2 could consist of elements such as the following:

- (1) Wide-area outdoor MNS
- (2) High power loudspeaker arrays (HPLAs)

Layer 3 could consist of elements such as the following:

- (1) Short message service (SMS)
- (2) Email
- (3) Computer pop-ups
- (4) Smartphone applications (apps)
- (5) Reverse 911/automated dialing

Layer 4 could consist of elements such as the following:

- (1) Radio broadcast (satellite, AM/FM)
- (2) Television broadcast (satellite, digital)
- (3) Location specific messages/notifications
- (4) Weather radios
- (5) Social networks

Also see *Optimizing Fire Alarm Notification for High Risk Groups* research project.

A.24.3.9 The design documents might include, but are not limited to, shop drawings, input/output matrix, battery calculations, notification appliance voltage drop and wattage calculations for visual notification appliances and loudspeakers, and product data sheets.

A.24.3.10 Fire emergency voice/alarm communications systems (EVACS) that are listed in accordance with UL 864, *Control Units and Accessories for Fire Alarm Systems*, can be used for MNS only if they are also listed in accordance with UL 2572, *Mass Notification Systems*. A control unit only listed in accordance with UL 2572 cannot be used as a fire alarm control unit.

A.24.3.12 There are many credible risk assessment methodologies that can be utilized and/or referenced in conducting the

risk assessment required in 24.3.12, some of which are listed as follows:

- (1) *CARVER — Target Analysis and Vulnerability Assessment Methodology*, Washington, DC: U.S. Department of Defense (see Field Manual 34-36, Special Operation Forces Intelligence and Electronics Warfare Operation, Sept. 30, 1991), www.defense.gov
- (2) *General Security Risk Assessment Guidelines*, Alexandria, VA: American Society for Industrial Security International, www.asisonline.org
- (3) *NFPA 1600*, Quincy, MA: National Fire Protection Association, www.nfpa.org
- (4) *NFPA 730*, Quincy, MA: National Fire Protection Association, www.nfpa.org
- (5) *Responsible Care Code*, Washington, DC: American Chemistry Council, www.americanchemistry.com
- (6) *AWWA J100, Risk and Resilience Management of Water & Wastewater Systems*, Denver, CO: American Water Works Association, www.awwa.org
- (7) *VAMCAP® Vulnerability Assessment Methodology for Critical Asset Protection*, Wilmington, DE: SafePlace Corporation, www.safeplace.com
- (8) *Vulnerability Assessment Methodologies*, Albuquerque, NM: Sandia National Laboratories, www.sandia.gov
- (9) *SFPE Engineering Guide to Fire Risk Assessment*, Gaithersburg, MD: Society of Fire Protection Engineers, www.sfpe.org

Refer to A.7.8.2(1) and Figure A.7.3.6 for a risk analysis checklist.

A.24.3.12.1 Although this chapter outlines some specific criteria and/or limitations, each application should be based on recognized performance-based design practices and the emergency response plan developed for the specific facility.

The risk analysis should identify which threats are significant enough that a mass notification system is required for an effective response. Significance of threats should be based on the likelihood of occurrence and the negative consequences if the threat does occur.

Here are the general categories of questions that might be presented to the senior manager responsible for mass notification decisions. The actual questions for each project must be tailored to the area, the building, the campus, and the culture of the user organization. Following is a brief description of potential content within the mass notification event questions:

- (1) What is the type of emergency event — that is, is it fire, security, safety, health, environmental, geological, meteorological, utility service disruption, or another type of event?
- (2) What is the urgency of the emergency event — that is, does it represent immediate danger, has it already occurred, is it expected to occur soon, is it expected to occur in the future, or is its occurrence unknown?
- (3) What is the anticipated or expected severity of the emergency event — that is, how will it impact our facility and its functions, is it expected to be extreme, severe, etc.?
- (4) What is the certainty of the emergency event — that is, is it happening now, is it very likely to occur, is it likely to occur, is it possible that it will occur in the future, is it unlikely to occur, or is its occurrence unknown?

- (5) What is the location of the event, or from what direction is the emergency event approaching — that is, has it or will it be approaching from the north, south, east, or west?
- (6) What zone or areas should receive the emergency message(s) — that is, is it a floor of a building, multiple floors of a building, the entire building, multiple buildings, a campus of buildings, an entire town or city, an entire state, an entire region of states, or an entire country?
- (7) What is the validity of the emergency event — that is, has the emergency event been investigated and/or confirmed?
- (8) What instructions should we send to our personnel — that is, should they evacuate the facility, should they shelter-in-place, should they shelter-in-place at a special location, should they proceed to a safe haven area, and other action oriented items?
- (9) Are there any special instructions, procedures, or special tasks that we need to remind personnel about or to accomplish — that is, close your office door, open your office door, stay away from windows, do not use elevators, and other information relating to personnel actions?

The questions suggested in items (1) through (9) are offered for consideration, and not all of them might be appropriate for every mass notification system installation. It is important to remember that when an emergency event occurs, the response must be immediate and deliberate. Therefore, there is no time for indecision. So the questions selected to reside in the emergency messaging decision tree illustrated in items (1) through (9) must be straightforward and as simple as possible. They must also be tailored to the specific organization, culture, site, and unique requirements of each local environment.

A.24.3.12.10 When a code requires a risk analysis for mass notification systems to determine the need for an MNS, the stakeholders can determine the extent and types of coverage and systems needed. It might be found that the minimum code requirements already include what is needed for the risk of a project and that nothing additional is required. An example could be a small school that has an EVAC system; that system might be sufficient for emergency communications based on the risk analysis prepared by the stakeholders and approved by the authority having jurisdiction.

A.24.3.13 The emergency response plan should include, but not be limited to, the following elements:

- (1) Emergency response team structure
- (2) Emergency response procedures, as follows:
 - (a) Building system related emergencies
 - (b) Human-related emergencies
 - (c) Terrorism-related emergencies
 - (d) Weather-related emergencies
- (3) Emergency response equipment and operations
- (4) Emergency response notification, as follows:
 - (a) Emergency message content
 - (b) Emergency notification approval process
 - (c) Emergency notification initiation process
- (5) Emergency response training and drills, as follows:
 - (a) Classroom training
 - (b) Table-top training
 - (c) Live drills

A.24.3.14.3 This section is not meant to preclude a performance-based pathway survivability approach. As with most performance-based approaches, documentation should be provided by the designer and maintained with system documentation for the life of the system. Written documentation of the approval from the authority having jurisdiction should also be maintained. A performance-based approach to pathway survivability could be equivalent to, less stringent than, or more stringent than the prescriptive approach in 24.3.14. Often a performance-based approach will result from a risk analysis.

This section is also not meant to preclude less stringent pathway survivability requirements supported by a risk analysis for those unique occupancies that employ emergency voice alarm/emergency communication systems for relocation or partial evacuation as part of their fire safety plan where relocation or partial evacuation could be readily superseded by total evacuation and where buildings are of a type other than Type I or Type II (222) construction where the pathway survivability performance requirement does not need to be for two hours. Examples include low-rise education and day-care occupancies, nursing homes, ambulatory health care occupancies, hotel and dormitory occupancies, and residential board and care occupancies.

Refer to Annex F for previous nomenclature and cross-reference.

A.24.3.14.4.2 The protection requirement would also apply to a signaling line circuit that extends from a master fire alarm control unit to another remote fire alarm control unit where notification appliance circuits might originate.

Refer to 24.4.8.6.6 for the specific requirements for the protection of fire alarm equipment.

A.24.3.14.4.3 The listing of 2-hour fire-rated cable systems [electrical circuit protective system(s)] requires it to be attached to a concrete wall or floor assembly constructed with a minimum of 2-hour rating or as otherwise identified by the UL FHIT systems assembly. In a fire event the wall or floor assembly could fail causing the pathway to fail. Two-hour fire-rated circuit integrity (CI) or fire-resistive cable is not required to be attached to a concrete assembly but is required to be supported per the manufacturer's installation instructions.

A.24.3.14.4.4 The listing of 1-hour fire-rated cable systems [electrical circuit protective system(s)] would likely require it to be attached to a wall or floor assembly that is constructed with a minimum of 1-hour rating. One-hour fire-rated circuit integrity (CI) or fire-resistive cable is not required to be attached to a concrete assembly but is required to be supported per the manufacturer's installation instructions.

A.24.3.14.4.6.1 Chapter 12 has specific requirements for separation of Class N and Class X circuits to prevent physical damage to allow the redundant pathway to remain operational. For systems designed for relocation and partial evacuation, communication must remain operational during a fire. Conductors must be separated by fire-rated floors and walls or distance in a sprinkler-protected building to be survivable during a fire. Specific circuit separation requirements are provided in 24.3.14.4.6.3 for the communication to remain operational when redundant separated pathways are installed.

A.24.3.14.4.6.2 Chapter 23 has specific requirements for SLC zones such as requiring equipment on different floors to be isolated so a single fault on the pathway does not impact more

than one notification zone. Rooms or enclosures required for protection of fire alarm equipment used for relocation and partial evacuation could contain equipment that serves multiple notification zones; therefore isolation would not be possible unless additional dedicated equipment and isolation for each notification zone is installed. Specific pathway survivability requirements for faults are provided in 24.3.14.4.6.4 when redundant separated pathways are installed.

A.24.3.14.4.6.3 In occupancies where relocation or partial evacuation is used, it is critical that the fire alarm system notification appliances remain operational in notification zones where the fire event is not occurring. Figure A.24.3.14.4.6.3 is a simplified riser diagram that illustrates how the communication and control circuits could be routed in a high-rise building. Building types (high-rise and institutional) where relocation or partial evacuation is used generally are required to be constructed with a 1-hour structural frame and floor assembly; therefore routing circuits on separate floors would allow the fire alarm notification appliances to remain operational.

When installing conductors in dissimilar protected areas in 24.3.14.4.6.3(2), it is important to confirm the walls of the room are constructed such that the rating extends from the top of the foundation or floor/ceiling assembly below to the underside of the floor or roof sheathing, slab, or deck above. If the rating is not continuous, additional protection of the fire alarm cable would be required to maintain protection of the cable. This could consist of fire-rated cables or conduit pathways. The rooms built with rated construction that provides the fire-rated separation would need to be constructed above and below each other to maintain the fire-rated separation. The rooms are not required to be located entirely directly above and below each other; however, fire alarm cable pathways would need to avoid being routed through the same rated enclosure.

A potential alternative to locating conductors in areas not separated by rated construction would be to install 1-hour fire-rated circuit integrity (CI) cable, fire-resistive cable, or a fire-rated cable system. This alternative to a Level 1 is covered by a Level 4 pathway survivability.

A.24.3.14.4.6.4 During a fire, insulation on fire alarm cabling can melt causing the conductors to touch causing a short circuit. Entire communication and control circuits can be impacted by a short fault on the circuit unless isolation is provided. Short-circuit isolation could be provided that is integral to the equipment or could be through a separate dedicated module that is installed between where the circuit enters the room or enclosure and the first component used to provide occupant notification. Refer to Figure A.24.3.14.4.6.3.

A.24.3.14.9 Although in some instances areas of refuge might be installed in buildings that use general evacuation and not relocation/partial evacuation, it is still crucial that people awaiting assistance can communicate with emergency responders to facilitate their evacuation. Thus, their evacuation time might be prolonged, and therefore the emergency communications systems should be capable of operating reliably during a fire incident. The requirement of 24.3.14.9 applies to any building regardless of whether it uses general evacuation, relocation, or partial evacuation.

A.24.3.14.12.1 During a fire, insulation on communication circuit cabling can melt causing the conductors to touch caus-

ing a short circuit. Entire communication and control circuits can be impacted by a short circuit or other fault on the circuit unless isolation is provided. Short-circuit isolation could be provided that is integral to the control equipment or could be through a separate dedicated module that is installed between where the circuit enters the room or enclosure and the first component used to provide the occupant communication. In order to meet the requirement that a single open, ground fault, or short-circuit fault cannot affect operation of the circuit, the use of a Class N or Class X pathway in accordance with Chapter 12 is required.

A.24.3.14.13 Stairway communications systems are required, for example, by the *International Building Code (IBC)* on every fifth floor in a building where the stairway doors are locked to prevent re-entry onto a floor. Under non-fire emergency conditions, people who become inadvertently locked into the stairway can request assistance if they are unable to navigate all the way down to the level of discharge where doors would be unlocked. The locked doors require remote unlocking capabilities from the fire command center (per IBC) so that during a fire emergency all stairway doors can be unlocked, eliminating the intended need for these communication stations to be used during a fire. Consequently, protecting the pathways for these systems from attack by fire is usually unnecessary.

A.24.3.14.14 Despite the intended use of these systems as noted in A.24.3.14.13, should they be deployed in a building where they are specifically intended to be used during fire emergency evacuations, partial evacuation, or relocation, then it is more appropriate to treat them as area of refuge two-way communications systems and to apply those pathway survivability requirements.

A.24.4 Where used, recorded voice messages for fire emergency alarm systems should be prepared in accordance with this Code by persons who are experienced with the operation of building fire emergency alarm systems and are knowledgeable of the building's construction, layout, and fire protection plan, including evacuation procedures. The proposed voice messages should be approved by the authority having jurisdiction prior to being implemented. Persons who record the messages for fire emergency alarm systems should be able to read and speak the language used for the message clearly, concisely, and without an accent that would have an adverse effect on intelligibility.

It is not the intention that in-building fire emergency voice/alarm communications service be limited to English-speaking populations. Emergency messages should be provided in the language of the predominant building population. If there is a possibility of isolated groups that do not speak the predominant language, multilingual messages should be provided. It is expected that small groups of transients unfamiliar with the predominant language will be picked up in the traffic flow in the event of an emergency and are not likely to be in an isolated situation.

A.24.4.2.1 Where an evacuation message is being provided, the three-pulse temporal signal specified in 18.4.2 should be provided unless otherwise dictated by the emergency response plan or authority having jurisdiction. This is regardless whether the cause of the evacuation is fire, carbon monoxide, gas leak, bomb threat, or any other emergency situation requiring evacuation of a building.




FIGURE A.24.3.14.4.6.3 Simplified Riser Diagram for a High-Rise Building with Relocation or Partial Evacuation.

A.24.4.2.2.2 Generally speaking, in a standard building configuration with normal ceiling height [8 ft to 12 ft (2.4 m to 3.7 m)], normal ceiling construction (e.g., drop acoustical ceiling tiles), standard wall configurations, and finishes and carpeted floors, ceiling-mounted loudspeakers should be installed in all normally occupiable spaces and in corridors spaced at a maximum of twice the ceiling height or as determined by a commercially available computer acoustical/loudspeaker modeling program. Where wall-mounted loudspeakers are used, manufacturer recommendations should be reviewed and/or computer modeling should be employed. One of the

goals of loudspeaker placement is to provide the shortest practical distance from the source (loudspeaker) to the recipient (person hearing the signal). In many applications, a combination of wall- and ceiling-mounted loudspeakers might be required. The audibility and intelligibility of the loudspeakers can be impacted by the tap/setting at which the loudspeaker is connected and should meet the audibility requirements of the Code while still having the message intelligible. Connecting to a high setting to meet the audibility requirements of the Code could distort the intelligibility of the signal.

In an ADS that is a non-acoustically challenging area, designing for audibility will typically result in an intelligible system provided minimum loudspeaker guidelines are followed. Areas typically considered to be non-acoustically challenging include traditional office environments, hotel guest rooms, dwelling units, and spaces with carpeting and furnishings.

Special attention must be given to acoustically challenging ADSs. Such areas might incorporate appreciable hard surfaces (e.g., glass, marble, tile, metal) or appreciably high ceilings (e.g., atriums, multiple ceiling heights). These conditions will require more stringent design guidelines to ensure intelligibility (e.g., a closer than normal loudspeaker spacing with lower taps). This can help reduce the effect of excessive reverberation and result in better intelligibility. In extreme cases there could be areas where intelligibility is not attainable, but this can be acceptable if there is an ADS within 30 ft (9.1 m) where the intelligibility of the system is deemed adequate.

In an ADS where the ambient noise level exceeds 85 dB it is acknowledged that intelligibility might not be attainable and, in such a case, an alternative means of notification will likely be required.

Design guidance is provided in the NEMA SB-50, *Emergency Communications Audio Intelligibility Applications Guide*.

A.24.4.4.2 The intent of this low frequency tone is to accommodate those with mild to severe hearing loss. See also 18.4.6, A.18.4.6.1, and A.29.5.10.2. The effective date listed in Chapter 18 for using a low frequency signal has not been allowed in 24.4.4 because voice systems are easily adapted to comply, whereas the requirements of 18.4.6 also apply to stand-alone tone signaling appliances.

A.24.4.4.3 Sleeping accommodations are provided in occupancies such as healthcare, detention and correction, and other occupancies where it would not be necessary to utilize a low frequency tone that awakens those sleeping. For example, in a hospital, the voice message is used to notify staff members who are already awake. The staff will then respond to the appropriate location in the hospital to carry out their duties that could include awakening and relocating patients who could be in danger. In addition, fire drills are required to be conducted on a regular basis and providing a low frequency tone could unnecessarily awaken patients, which would be detrimental to their care.

A.24.4.5.1 The choice of the location(s) for the in-building fire emergency voice/alarm communications control equipment should also take into consideration the ability of the fire alarm system to operate and function during any probable single event. Although *NFPA 72* does not regulate either building construction or contents, system designers should consider the potential for an event that could damage the equipment, including remotely located control devices, to disable the system or a portion thereof. Where practical, it is prudent to minimize unnecessary fire exposures of fire alarm control equipment through the use of fire-rated construction or enclosures, by limiting adjacent combustibles and ignition sources, or other appropriate means.

A.24.4.6.1 Loudspeakers located in the vicinity of the in-building fire emergency voice/alarm communications control equipment or MNS equipment should be arranged so they do not cause audio feedback when the system microphone is used. Loudspeakers installed in the area of two-way telephone

stations should be arranged so that the sound pressure level emitted does not preclude the effective use of the two-way telephone system. Circuits for loudspeakers and telephones should be separated, shielded, or otherwise arranged to prevent audio cross-talk between circuits.

A.24.4.7.1 Special suppression systems that are delivered through a total flooding or localized application include, but are not limited to, carbon dioxide, clean agents, halons, and other extinguishing agents. Special suppression systems require audible and visual warning alarms to provide personnel the opportunity to evacuate or to alert personnel not to enter the area of discharge that could be hazardous to life. A special suppression system discharge can be a life-threatening hazard for personnel who are not notified and, therefore, fail to react to the pre-discharge alarm. In such cases, pre-discharge and discharge alarms should be independent of the fire alarm loudspeakers that are used as part of the mass notification system. A special suppression system discharge could pose a greater threat to personnel that are located in the protected area, or that could enter the protected area, if the local signals were to be overridden and they did not receive the appropriate warning.

A.24.4.8 When a fire or other emergency occurs in a building, the usual goal is to evacuate the occupants or relocate them so that they are not exposed to hazardous conditions. The exception occurs in occupancies using stay-in-place/defend-in-place (SIP/DIP) [1] strategies. It might also be necessary to alert and provide information to trained staff responsible for assisting evacuation or relocation. Figure A.24.4.8 shows several key steps in a person's reaction and decision-making process [2].

Occupants rarely panic in fire situations [3,4]. The behavior that they adopt is based on the information they have, the perceived threat, and the decisions they make. The entire decision path is full of thought and decisions on the part of the occupant, all of which take time before leading to the development of adaptive behavior. In hindsight, the actions of many occupants in real fires are sometimes less than optimal. However, their decisions might have been the best choices given the information they had. Fire alarm systems that only use audible tones and/or flashing visual notification appliances impart only one bit of information: fire alarm. It has long been recognized that environments having complex egress situations or high hazard potentials require occupant notification systems that provide more than one bit of information [5]. To reduce the response time of the occupants and to effect the desired behavior, the message should contain several key elements [3,6].

The key elements include the following:

- (1) Tell occupants what has happened and where
- (2) Tell occupants what they should do
- (3) Tell occupants why they should do it

There does not seem to be any research that has tested actual message content to determine the best way to inform occupants. The problem is that each building and each fire is unique. Messaging is further complicated by the need to give different information to different people, depending on their location relative to the fire, their training, and their physical/mental capabilities.

Messages should use positive language and avoid negative instructions that could be misinterpreted due to unintelligible communications. For example, if you want people to leave an

area, say so: “A fire has been reported in the area. For your safety, use the stairs to evacuate the area immediately.” A bad example is: “The signal tone you have just heard indicated a report of an emergency. If your floor evacuation signal sounds after this message, do not use the elevator, walk to the nearest stairway and leave the floor. While the report is being verified, occupants on other floors should await further instructions.” This message is too long, ambiguous, and subject to misunderstanding if not heard clearly. The word “not” might not be heard clearly, or it might be heard to apply to the entire remaining sentence. Similarly, care should be used in selecting and clearly enunciating words such as “fifth” and “sixth,” which can sound the same if the system and environment lead to low intelligibility.

See A.24.3.6.1 for more information on methodology for improved message content, structure, and intelligibility. Refer to Annex D for more information on speech intelligibility and how it is predicted.

Content of the message should be predicated on the emergency response plan, the nature of the building and its occupants, the design of the fire alarm system, and testing of the occupant reaction to the message. Caution is advised that the fire alarm system operation and message actuation might be initiated by a manual pull station or detector remote from the fire.

[1] Schifiliti, R. P., “To Leave or Not to Leave — That is the Question!”, National Fire Protection Association, World Fire Safety Congress & Exposition, May 16, 2000, Denver, CO.

[2] Ramachandran, G., “Informative Fire Warning Systems,” *Fire Technology*, vol. 47, no. 1, February 1991, National Fire Protection Association, 66–81.

[3] Bryan, J., “Psychological Variables That May Affect Fire Alarm Design,” *Fire Protection Engineering*, Society of Fire Protection Engineers, Issue No. 11, Fall 2001.

[4] Proulx, G., “Cool Under Fire,” *Fire Protection Engineering*, Society of Fire Protection Engineers, Issue No. 16, Fall 2002.

[5] General Services Administration, Proceedings of the Reconvened International Conference on Fire Safety in High Rise Buildings, Washington, D.C., October 1971.

[6] Proulx, G., “Strategies for Ensuring Appropriate Occupant Response to Fire Alarm Signals,” National Research Council of Canada, Ottawa, Ontario, *Construction Technology Update*, No. 43, 1–6, December 2000.

A.24.4.8.3.1 Research finds that pauses before repeating emergency messages are more effective than repeating messages consecutively.

For example, Section 5.2.4.2 of NIST Technical Note 1779, *General Guidance on Emergency Communication Strategies for Buildings* (Kuligowski, 2013) [see G.2.2.1(11)(d)] recommends emergency messaging repetition. It also recommends that emergency messaging be repeated at intervals, rather than consecutively. “The second (or third message), provided some interval of time later, may catch a different population who were either busy or distracted during the time period when the first warning message was issued.” Paragraph 24.4.8.3.1 requires that EVAC messages used for fire emergency relocation or partial evacuation be repeated at least three times. Therefore, EVAC systems that transmit digitally stored audio messages are to be configured to meet these requirements. First responders




FIGURE A.24.4.8 Key Steps in Person's Reaction.

and other individuals required to make live fire-related relocation or partial evacuation messages must also be trained to repeat the entire message sequence, including the alert tone, at least three times. The interval for repeating the messages should be established in the emergency response plan.

A.24.4.8.3.2 Only first responders or other trained authorized emergency personnel should be able to intentionally and manually silence or reset the automatic prerecorded message sequence. This is required to ensure the safe evacuation or relocation of all occupants regardless of the time it takes to complete this task. It should not be permitted to allow for an automatic termination. The alert status of visual appliances should be maintained. However, since the duration of the alarm is indeterminate, audible alerts and messaging that are periodically suspended can contribute to an improved response by the occupants. Suspending the audible portion of the alarm can support a better community response to the instructions, especially in the case where the able-bodied are attempting to aid the infirm or emotionally challenged, or otherwise disabled occupants.

Approved alternative fire alarm notification schemes, such as a sequence that contains only a fixed number of repetitions of the prerecorded messages and associated alert tones, or as indicated in 24.4.8.3.2, should be permitted as long as the occupants are effectively notified and are provided instructions in a timely and safe manner in accordance with the emergency response plan.

Research from the National Research Council of Canada, *Occupant Behaviour and Evacuation*, found “In public buildings, such as airport terminals or sport centres, occupant training is not practical; for these, much of the responsibility for safety will rest with staff. Consequently, staff training is paramount. Occupants are very likely to look for staff members to obtain information; they are regarded as knowledgeable, they are expected to know the situation, the best course of action and the closest exit. Whether heard on a loudspeaker or seen in uniform or wearing a name tag, staff are likely to be listened to.”

The National Council on Disability publication, *Effective Emergency Management: Making Improvements for Communities and People with Disabilities*, found “People with disabilities should not be viewed as one more special interest group that drains resources from the common pool. Accommodating this large group often translates into being better equipped to serve all people. Anyone, at any moment, can incur a disability, particularly during emergencies.” (Kailes and Enders 2006, p. 13).

Further, Shields, Boyce, and Silcock (1997) note that “staff trained in emergency evacuation should provide guidance to people who are evacuating public facilities. Familiar and trusted staff can alert a significant portion of the public in such instances and ensure an efficient evacuation.” On the basis of census results, Morrow (1999, p. 5) argues that a “sizable segment” of any community’s population will need additional assistance during evacuation.

Fire-related emergency relocation instructions and nonevacuation messages are repeated a minimum of three times. For prerecorded messages, the actual number of times the message sequence plays is indeterminate, and the interval between each sequence playing is not defined by code, but rather intended to be defined in the emergency response plan. Paragraph 24.4.8.3.2 requires that the entire message sequence, including the tone, is again repeated after a pause. So if the tone and partial evacuation message is repeated three times as required by 24.4.8.3.1, then after pausing for an interval of at least 180 seconds (or alternative time periods that are established — see the following paragraph), the entire message sequence (including tone) is repeated again three times, followed by another pause, and so on.

Research shows (see Annex G: *Guidelines for Emergency Communication Strategies for Buildings and Campuses*) that effective messages should be repeated at intervals, not consecutively. In determining the alternative interval times, consider the following:

- (1) Too much time between message sequences could be misunderstood by occupants that the emergency has been resolved.
- (2) Too much time between message sequences could communicate insufficiently the sense of urgency that is intended.
- (3) Too little time between message sequences could impair the ability of occupants to comply with instructions, particularly for occupants that need assistance.
- (4) Too little time between message sequences could make it difficult for occupants to mark a change in the message contents if partial evacuation or relocation instructions are changed and re-issued.
- (5) On the loss of primary power, secondary power is required to support continuous notification for only 15 minutes. This time could be extended based on the period of repetition of automatic messages. Too little time between message sequences could exhaust power reserves before emergency first responders arrive, compromising their ability to manually transmit additional live evacuation or relocation messages.

A.24.4.8.4 Where a partial evacuation message is being provided, the three-pulse temporal signal specified in 18.4.2 should be provided unless otherwise dictated by the emergency response plan or authority having jurisdiction. This is regardless whether the cause of the evacuation is fire, carbon monox-

ide, gas leak, bomb threat, or any other emergency situation requiring partial evacuation of a building.

A.24.4.8.6.1 Along with the pathway survivability requirements, one or more of the following means could be considered acceptable to provide a level of survivability consistent with the intent of this requirement:

- (1) Routing notification appliance circuits separately
- (2) Using short-circuit, fault-tolerant signaling line circuits for controlling evacuation signals

The requirement for notification appliances to operate in those signaling zones that are not attacked by fire will also require that circuits and equipment that are common to more than one signaling zone be designed and installed such that the fire will not disable them. For instance, a signaling line circuit used to control notification appliances in multiple signaling zones should be properly designed and installed so that one fire would not impair the signaling line circuit, rendering the notification appliances serving more than one signaling zone inoperative.

A.24.4.8.6.3 Circuits are required to be protected as they pass through fire areas other than the one served. The purpose of this is to delay possible damage to the circuits from fires in areas other than those served by the circuits and to increase the likelihood that circuits serving areas remote from the original fire will have the opportunity to be actuated and serve their purpose. Circuits are considered protected when the pathway directly enters the notification zone from the rated room required by 24.4.8.6.6 and are not required to comply with the pathway survivability requirements in 24.3.14.4.

A.24.4.9.1 Paragraph 24.4.9.1 does not prohibit the provision of multiple notification appliance circuits within a notification zone.

A.24.5 This section covers the application, installation, location, performance, and maintenance of mass notification systems used for emergency purposes.

An in-building mass notification system is considered to be a system used to provide information and instructions to people in a building(s) or other space using intelligible voice communications and including visual signals, text, graphics, tactile, or other communication methods.

Mass notification systems can consist of fully independent systems with minimal or no interface with the building fire alarm system, systems that report trouble and supervisory signals through the fire alarm system, systems that share audible and visual notification circuits and appliances with the fire alarm system, or combination mass notification and fire alarm systems.

A.24.5.1 Although some minimum criteria are outlined for a particular feature, the feature might not be applicable for every project.

The information and instructions delivered by a mass notification system could be initiated manually by an operator or automatically by sensors or other systems and might be delivered to the target audience using prerecorded messages or live messages, or both, tailored to the situation and the audience.

Each mass notification system could be different, depending on the anticipated threat and the level of protection intended. As an example, a particular project might not require secure radio transmissions. As such, criteria for such would not apply. However, if the authority having jurisdiction or design professional has specified secure radio transmissions, the minimum applicable criteria within this document would be required. Deviation from these minimum criteria would require approval of the stakeholders.

Mass notification systems can consist of fully independent systems with minimal or no interface with the building fire alarm system, systems that report trouble and supervisory signals through the fire alarm system, systems that share audible and visual notification circuits and appliances with the fire alarm system, or combination mass notification and fire alarm systems.

A.24.5.1.2(6) Other systems could include wide-area mass notification, distributed recipient mass notification, and regional and national alerting.

A.24.5.2.1 Authorized personnel could include building occupants who can readily access and originate messages in emergency situations. Depending on the individual facility, use of the mass notification system to originate non-emergency messages could also be permitted. The selection of authorized personnel should be based on a risk assessment and the building emergency response plan.

A.24.5.2.2 Authorized personnel could initiate message signaling over the mass notification system from either an emergency command center or a secondary (backup) control station(s). In cases where clusters of facilities within the same geographical region exist, one or more regional control stations could initiate message signaling. The mass notification system could permit activation of messages originated by mobile sentries and roving patrols using wireless activation devices. Since it is common practice to allow mass notification systems to be utilized for “nonemergency” messages, the emergency command center should incorporate a clearly marked and easy to operate means to distinguish between emergency and non-emergency use. Comprehensive training and a fail-safe default to the emergency mode of operation should be employed to ensure that no actual emergency message gets transmitted as a nonemergency broadcast.

A.24.5.2.3 As a general practice, the number of message selection switches included as part of the operating controls should be limited, so that authorized personnel can utilize the system with only minimal familiarity. This, of course, could be a different matter on an industrial or college campus where trained individuals are likely to be very familiar with the operation and use of the system. In that case, more selection switches could be beneficial.

A.24.5.2.5 It is recognized that there can be benefit for users at the ACU to identify which specific location is currently in control. This can be indicated through visual means or through an audible location code. This can be especially useful for emergency responders utilizing the ACU to know which remote location is in control. If incorporated into a system, such features can be enabled or disabled by authorized personnel or as directed through the risk analysis.

A.24.5.2.10 During emergencies, building occupants should periodically receive an audible clue that the emergency notification

given by the mass notification system is still in effect. This also can help building occupants and emergency response personnel recognize that the mass notification system is overriding fire alarm notification appliances. The audible signal could consist of a simple signal such as a chirp of sufficient duration to be recognized by the usual building occupants and, typically, by occupants who are not hearing disabled.

A.24.5.3.1 The mass notification system could permit activation of messages originated by mobile sentries and roving patrols using wireless activation devices.

A.24.5.3.4 Generally, each separate building should be provided with a separate in-building mass notification system; however, some facilities (such as a campus-type high school with multiple separate buildings) might be more effectively served by a single in-building mass notification system. Alternately, a risk analysis could determine that a wide-area mass notification system provides the optimal capability for mass notification.

A.24.5.4.1 Alternate methods that achieve the desired statistical availability could be deemed acceptable in lieu of monitoring the integrity of circuits, signaling channels, or communication pathways where consistent with the risk analysis and emergency response plan.

An example of an alternate method could include an attendant monitored system, which is a device or system intended to be constantly operated and maintained by competent and experienced personnel either locally or from a remote station. ANSI/NEMA SB-40, *Communications Systems for Life Safety in Schools*, references “operational integrity” in relation to systems that are used regularly for routine purposes and suggests that such systems would be statistically more available due to a lower risk of falling into a state of disrepair. ANSI/NEMA SB-40 also addresses system readiness in relation to constant use, and recommends that, to the greatest extent possible, equipment used in emergency communication should be used daily in routine situations. Therefore, it is important to consider the level to which a system is constantly operated and the level of operator training when preparing a risk analysis. Based on the occupancy of the premise, the risk analysis, and the emergency response plan, the designer and authority having jurisdiction can more easily determine whether it is appropriate for loud-speaker circuits to utilize alternate methods for equivalency. Such a constantly operated system could be determined to achieve a statistically significant availability to satisfy an authority having jurisdiction.

A.24.5.7 The risk analysis should identify what emergency situations will take priority over the fire alarm evacuation signal. Should a tornado warning for the area take priority over an active fire in the building? Should a breach of security at the campus entry gate take priority over an active fire in the building? If a manual fire alarm pull box has been actuated, it might be a terrorist action to have people leave the building and walk into an exterior threat. In such a case, mass notification input is intended to override the fire alarm evacuation signals to redirect the occupants based on the conditions.

A.24.5.9.2 Devices such as gas or chemical sensors and detectors, weather alert signals, or other such signals can be desirable to connect to the mass notification system to provide a faster response to emergency conditions.

A.24.5.10 Refer to 24.5.2 for requirements related to operation of the system by authorized personnel. It is recognized that, based on the risk analysis, control equipment and circuits could need different levels of protection for different facilities. Access to the fire alarm/mass notification interface should be consistent with the action outlined in the emergency response plan. It could have been prior practice in some jurisdictions to locate the fire alarm control unit in the main lobby of a facility. However, it might not be appropriate to locate the mass notification system autonomous control unit within the lobby if the general public would have access to deactivate mass notification system components. Based on the risk analysis, it could be appropriate to locate the autonomous control unit within a secured room while providing local operating consoles for use by other authorized personnel.

A.24.5.12.1 Mass notification systems can include a system local operating console(s) for authorized occupants to readily access and originate messages in emergency and non-emergency situations. The quantity and location(s) of an LOC(s) should be determined by the risk analysis and the facilities emergency response plan.

A.24.5.13.1 The following is an example scheme for message prioritization, from highest (1) to lowest (5), for consideration during the risk analysis:

- (1) Live voice messages from personnel in the building should be the highest priority. If systems provide control locations that are usable by nonauthorized personnel, these controls should be disabled or overridden during emergency operations.
- (2) Automatic fire alarm messages/other high priority messages as determined by risk analysis criteria.
- (3) External messages originated by a wide-area mass notification system.
- (4) Message priority for emergency conditions such as severe weather warnings, gas leaks, chemical spills, and other hazardous conditions should be determined by risk analysis criteria and defined in the emergency response plan.
- (5) Non-emergency messages, such as general announcements and time function signaling (work breaks, class change, etc.), should have the lowest priority.

A.24.5.13.6(2) Unless the risk analysis determines otherwise, the fire alarm system should always be automatically returned to normal functionality. If the fire alarm system is automatically returned to normal functionality, the building emergency response plan should state that no user intervention is required. When manual intervention is required to return the fire alarm system to normal, specific instructions should be in place in the emergency response plan explaining how the fire alarm system notification appliances should be reactivated. These instructions should be located at the fire alarm and mass notification control units. Individuals responsible for manually returning the fire alarm system to normal should be properly trained in the procedure.

A.24.5.14 Control functions need to be accessible for those intended to use them. This requirement is not intended to require that the control enclosure be within the dimensions, but rather the respective buttons, latches, microphone, and other items the user will need to have within reach and view. Figure A.24.5.14(a) applies when the horizontal reach is less than 10 in. (254 mm). Figure A.24.5.14(b) applies when the horizontal reach is between 10 in. (254 mm) and 24 in. (610 mm).




FIGURE A.24.5.14(a) Horizontal Reach of Less Than 10 in. (254 mm).

A.24.5.18 Care in location and placement is critical to the survivability of the textual visual appliance and maximizing its effectiveness. Locate the textual visual appliance away from direct sunlight or direct local area lighting. Avoid locating the textual visual appliance near heating and air-conditioning ducts.

A.24.5.18.2 The requirement of 24.5.18.2 does not imply that multiple primary methods of visual appliances cannot exist in a common area. Both visual notification appliance and graphical or textual appliances are designated as primary where the authority having jurisdiction declares both to be required. When textual audible notification is required, consideration is warranted for high-noise areas and for a person who is deaf or hard of hearing being capable of clearly receiving instructions.

As mass notification systems are deployed, the more complex emergency management communication requirements that go beyond what can be indicated by a visual notification appliance and a tone are being addressed. The intelligibility requirements of an MNS/ECS are a direct reflection of this reality. However, for a person who is deaf or hard of hearing, no degree of intelligibility might be sufficient. Additionally, there are physical spaces where intelligibility is impossible or imprac-




FIGURE A.24.5.14(b) Horizontal Reach of 10 in. (254 mm) to 24 in. (610 mm).

tical to provide. In designating a primary visual notification appliance, it is easy to assume that a visual notification appliance is sufficient and all other visual notification is automatically supplemental.

However, where the risk analysis and an emergency response plan require the communication of MNS textual audible instructions for occupants, a visual notification appliance should not be considered a sufficient primary notification appliance where intelligibility cannot be achieved or where consideration for lone individuals or groups of individuals who are deaf or hard of hearing might prevent them from responding appropriately to emergency instructions.

A.24.5.20 The video display can be a video appliance used to facilitate mass notification. Information displayed could be video, graphic, text, or audio. Information can be transmitted over a video distribution network, MATV, or CATV system. These messages can be standardized or customized for specific applications or situations. Dynamic text elements can be derived from secure data or updated in real time, either locally or remotely. Messages can be controlled by authorities to update and alter content with manual overrides from authorized security, police, and so forth to ensure up-to-date and real-time information. The same can be accomplished with remote

control from an emergency command center. Examples of interfaces used for real-time control include USB, Ethernet, RS-232, and GPI.

A.24.5.22.1.3 Where automatic transmission is required to a supervising station, it should be performed in accordance with the emergency response plan. The purpose for disabling or overriding the fire alarm system notification appliances during simultaneous fire and mass notification events is so that occupants will not receive conflicting messages and fail to respond correctly. Fire alarm notification that should be overridden during a mass notification system activation could include audible notification appliances, visual notification appliances, textual notification appliances, and video notification appliances.

A.24.5.22.3.1 As part of the risk analysis and emergency response plan, consideration should be given to future interfacing in-building mass notification systems with a wide-area mass notification system if it does not presently exist. In-building mass notification systems should be designed to allow future interface with a wide-area mass notification system.

A.24.5.23.1 A combined system can include an autonomous control unit and fire alarm control unit supplied from different manufacturers or placed in separate equipment enclosures; however, the autonomous control unit and fire alarm control unit should be integrated in their controls and performance to meet the requirements of this Code.

A.24.5.24.2 When a professional-grade public address system, an engineered sound reinforcement system, or a pro-audio sound system does not meet all the performance requirements of Chapter 24, it can still be evaluated and documented with a risk analysis and permitted for use as an emergency communications system with the approval of the authority having jurisdiction. For example, consider a professional-grade public address system that includes outdoor-class loudspeakers not listed for fire. In the risk analysis, an argument could be made that the system is allowable for use during a non-fire-related evacuation of the structure, a lock-down or lock-out condition, or a reverse evacuation.

Another example could be an attendant monitored system, which is a device or system intended to be constantly operated and maintained by competent and experienced personnel either locally or from a remote station. Consider a professional-grade public address system, an engineered sound reinforcement system, or a pro-audio sound system that has a history of reliability, is used regularly by trained personnel, but does not support the monitoring for integrity requirements of *NFPA 72*. When coupled with appropriate equivalency information provided within the risk analysis, such a system could be deemed acceptable to an authority having jurisdiction for specific occupancies and uses.

The risk analysis should also consider the need for secondary power. Typically, public address systems, engineered sound reinforcement systems, and pro-audio sound systems do not include integrated secondary power. So, if the application requires secondary power, it would usually need to be provided through an alternate means such as backup generator or an ESS. For an ESS in particular, care should be taken to determine the required capacity to support a minimally acceptable operational period. See Section 10.6, Power Supplies, which highlights concerns and issues such as continuity, capacity, and various options.

A.24.6 Wide-area mass notification systems are generally installed to provide real-time information to outdoor areas. These systems are normally provided with, and operated from, two or more emergency command centers. Communications between emergency command centers and in-building mass notification systems is provided. Communications between the emergency command centers and regional or national command systems could also be provided. Wide-area mass notification systems are often those such as campus giant voice systems, military base public address systems, civil defense warning systems, large outdoor visual displays, and so forth.

A.24.6.2 A commonly used method of protecting against unauthorized changes using multiple levels of password protection can be described as follows (in ascending levels of access):

- (1) *Access Level 1.* Access by persons who have a general responsibility for safety supervision, and who might be expected to investigate and initially respond to an alarm or trouble signal.
- (2) *Access Level 2.* Access by persons who have a specific responsibility for safety, and who are trained to operate the control unit.
- (3) *Access Level 3.* Access by persons who are trained and authorized to take control over a given area of a site to allow local paging, which might be different from that of another area. Note: This might require a higher form of access to the local control.
- (4) *Access Level 4.* Access by persons that serve in a system administrator capacity and are authorized to make changes to the system and its associated software.

A.24.6.3 A wide-area mass notification system could have the capability to communicate with other notification systems on the site, such as the telephone alerting system, paging system, cell phone, pager, PDA activation, e-Blast, message scrolling, reverse 911, fax transmission, and highway advisory radio and sign control system (used for dynamic control of radio information and traffic signs for emergency information and traffic management).

A.24.6.5 High power loudspeaker arrays should be designed with directional characteristics that will minimize the distortion of voice signals by interface from other zones and will minimize the transmission of voice or tone signals into environmentally sensitive areas or off the site.

A.24.6.5.1(B) Refer to Annex D for more information on speech intelligibility and how it is predicted.

Normal weather conditions should be specified as appropriate for the geographic location.

In outdoor areas, such as in industrial areas with many multi-story buildings, the maximum distance of personnel from an outdoor loudspeaker often has to be significantly reduced to retain acceptable intelligibility of the voice message. Loudspeakers that provide directional capability should be used. These can be mounted on building exteriors if the loudspeakers do not radiate unacceptable levels of sound into the building on which they are mounted.

At some sites, it could be necessary to control the amount of sound that propagates in undesirable directions, such as into civilian communities adjacent to the site boundaries or into wildlife areas with protected or endangered animal species. Additionally, in some areas, it might be necessary to mount wide-area mass notification loudspeakers on the side of a build-

ing while simultaneously preventing an unacceptable increase in that building's interior noise levels.

A.24.6.5.4 At a minimum, the high power loudspeaker array controller should be located above known high water level during historic floods. In northern states, the high power loudspeaker array should be located above known snow levels. When selecting high power loudspeaker arrays, care should be taken to ensure the equipment is rated to operate between the high and low temperature range and other anticipated environmental conditions for the geographical location of installation. The system designer should inquire about this information as part of the risk analysis.

A.24.6.7.2 High power loudspeaker arrays should be mounted not to exceed the OSHA and FEMA Technical Bulletin, *Outdoor Warning Systems* Version 2.0, for occupational noise exposure limits or an absolute limit of 123 C-weighted decibels (dBC) as referenced in FEMA to anyone in the immediate vicinity of the appliances.

A.24.6.9 High power loudspeaker arrays and their supporting structures should have a minimum design wind speed of 100 miles/hr [161 km/hr (86.8 kn)]. The supporting structure should be sized to accommodate the static and dynamic loads produced by the sound systems and all attachments. Seismic loads are generally site specific.

A.24.7 Distributed recipient mass notification systems are enterprise-class systems for the management of, and mass distribution of, emergency notification messages within buildings, throughout installations, across entire geographical regions, or throughout a worldwide military command. Using distributed recipient mass notification systems, designated system operators would be able to rapidly and reliably inform appropriate personnel of homeland security levels (including chemical, biological, radiological, and nuclear threats; hazardous weather conditions; and many other critical events), possibly with near real-time response capability.

A distributed recipient mass notification system is meant to communicate to a wide range of targeted individuals and groups. These systems might use mass dialing systems, including reverse 911, email, SMS, or other directed communications methods to broadcast information. They might also use wired or wireless networks for one- or two-way communications and/or control between a building or area and an emergency services organization (information, command, and control).

Although classified as one-way ECS, distributed recipient mass notification systems could be capable of centrally tracking, in real time, all alerting activities for each individual recipient, including sending, receiving, and responding to alerts, and be able to generate reports based on tracked information. Distributed recipient mass notification systems could be able to provide ability to collect and report user responses to alerts, such as "I am safe," "I need assistance," and "I am not in affected area."

Distributed recipient mass notification systems could incorporate a predefined library of signals and messaging appropriate for, but not limited to, the following:

- (1) Presidential alert message
- (2) Homeland security levels
- (3) Terrorism threats, watches, or warnings
- (4) Evacuation routes
- (5) Emergency directives

- (6) Personnel recall requirements
- (7) Federal, DOD, police, fire, local, or installation-specific warning and notification requirements
- (8) Amber alerts

The distributed recipient mass notification system could be capable of monitoring emergency notifications from multiple data sources [such as Wireless Emergency Alert (WEA), National Weather Service, Emergency Managers Weather Information Network (EMWIN), Naval Meteorology and Oceanography (METOC), and others as determined locally] and automatically sending out notifications to designated facilities and personnel based on predefined rules.

A mass notification system could also be capable of reaching out to all online personnel by leveraging a highly secure, redundant, Web-based IP network architecture to manage the entire mass notification process. Agencies and organizations can create role-based uses such as operators, administrators, and recipients, based on their access rights across multiple facilities, campuses, and installations. System rules could be established to determine operator permissions and actions such as creating and activating scenarios, as well as the extent and geography of alerts and delivery systems and devices that should be used. Such a Web-based mass notification system would employ an open, standards-based architecture. The system could be integrated with existing user directories to support organizational hierarchy and emergency response groups. It could be structured to allow emergency criteria-based targeting of emergency alerts.

Additionally, this annex material provides information on ongoing development of system requirements for net-centric alerting systems (NCAS) that will be based on IP technologies. This annex is not mandatory, but is provided to stimulate development of suitable requirements and standards. Consequently, user suggestions and feedback on this annex are highly encouraged and requested. Methods to ensure reliability and robustness in off-normal or emergency conditions are of particular concern. The required amount of and method for isolating alerting functions from normal, non-alerting system functions needs development.

NCAS leverage the IP network infrastructure to instantly reach those personnel who have access to nearly any IP-connected devices [such as pop-up alerts on personal computers (PC), text messages to cellular telephones, electronic mail messages, and voice messages to voiceover-IP (VoIP) telephones and PCs]. Additionally, NCAS could be used to actuate, through a single user interface, other (IP based and non-IP based) alerting systems, such as wide-area alerting systems and traditional dial-up telephone alerting systems.

NCAS can be installed independently or at a central location. In a centrally managed NCAS configuration, personnel and facilities in the regional operations center's particular area of coverage could be alerted instantly by events, either from any individual installation, or centrally from the regional operations center. Using management tools, designated operators from each installation in the region could log in via a web browser and have complete access to their own portion of the NCAS. The regional operations center would retain the ability to centrally monitor and manage all portions of the system, including supervisory and trouble conditions of the different system components and integrated components.

The NCAS would incorporate a Web-based management and alert activation application through which all operators and administrators could gain access to the system's capabilities, based on the users' permissions and the defined access policy. Such a management application would incorporate management of the alert activation flow through all delivery methods, as well as end-user management, operators' permission and access, tracking and reporting, and all administrative aspects of the system.

Distributed recipient mass notification systems could interface and interoperate with other types of mass notification capabilities, including wide-area and in-building mass notification systems. During emergencies, systems operators should not need to send notifications using multiple alerting systems. The distributed recipient mass notification system, particularly NCAS, might be able to provide the capability to integrate user interfaces and consolidate access to multiple mass notification and alerting systems.

A.24.7.1 Distributed recipient mass notification systems could enable the management of the notification flow, including users' management, groups targeting, operators' permissions, access policies, predefined emergency scenarios, and response tracking and reporting.

A.24.7.2 Distributed recipient mass notification systems could be capable of sending alert messages in a prioritized method to target recipients according to the following:

- (1) Hierarchical organizational structure (as would be imported from an active directory)
- (2) Organizational roles
- (3) Specific distribution lists [e.g., hazardous materials (HAZMAT) response teams]
- (4) Specific distribution (e.g., person who is deaf or hard of hearing or others with disabilities that warrant prioritized notification)
- (5) Dynamic groups created through on-the-fly queries of the user directory
- (6) Geographical locations (e.g., entire bases, zones within bases)
- (7) IP addresses (required for targeting devices in specific physical locations)

Distributed recipient mass notification systems should provide mechanisms to update user and targeting data (e.g., user data import, integration with personnel directories, and self-user registration).

Distributed recipient mass notification systems could use a Web-based user interface, support locally designated standard network ports and protocols, and provide open interfaces to support interoperability, such as eXtensible markup language (XML) and common alerting protocol (CAP) based emergency messages. (*See OASIS Standard CAP-V1.2, OASIS Common Alerting Protocol, Version 1.2.*)

A.24.7.5 Distributed recipient mass notification systems would be capable of sending alert messages to end-users (recipients) via multiple delivery methods, including the following:

- (1) Audio-visual network alerts to desktops and laptops via desktop pop-up
- (2) Text alerts to mobile phones and pagers
- (3) Text alerts to electronic mail (e-mail) clients
- (4) Text alerts to social networks
- (5) Audio alerts to phones

- (6) Audio alerts to existing wide-area or building voice and or mass notification systems
- (7) Network alerts to any other IP-connected devices via standard XML and CAP protocols

The system could be extendable to support additional delivery methods in the future as this technology develops.

A.24.7.6 A distributed recipient mass notification system could support multiple server and multiple site configurations to achieve a “hot standby” failover configuration (i.e., no down time in case of failure in a single server), as well as to support higher load scenarios (e.g., more users). This could be accomplished with premises-based systems or hosted configurations.

Backup configuration can either be a net-centric system architecture located behind internet firewalls or hosted off-premises, outside the owner’s internet firewall utilizing a hosted software and hardware configuration operated and maintained by DRMNS provider(s), or incorporate features of both configurations.

A.24.8 Two-way, in-building emergency services communications systems are used by fire fighters, police, and other emergency services personnel. This does not preclude equipment outside of the protected premises.

A.24.8.6 Consideration should be given to the type of telephone handset that fire fighters use in areas where high ambient noise levels exist or areas where high noise levels could exist during a fire condition. Push-to-talk handsets, handsets that contain directional microphones, or handsets that contain other suitable noise-canceling features, can be used.

A.24.8.19 Two-way, in-building wired emergency services communications systems (i.e., fire fighters’ telephone systems) are intended to provide emergency service personnel and designated building occupants with a supervised, reliable communication system that is completely independent of other in-building communication systems. The survivability of two-way, in-building wired emergency services communications systems is paramount as they are intended for use during and throughout the duration of a fire or other emergency event. This kind of functionality requires that measures are taken to ensure that the system is designed, installed, and maintained in such a manner that they can survive and function under extreme conditions.

Pathway survivability of two-way emergency communications systems is dictated by 24.3.14.7 through 24.3.14.16.

A.24.9 The intent of these systems is to provide reliable radio communications for first responders within all buildings in their jurisdiction. The building codes now require these systems in lieu of fire fighter telephones.

NFPA 1221 is followed by 911 centers, dispatchers, and municipal radio operations centers. It is the best standard to follow for these systems.

Dedicated fire fighter telephone (FFT) systems were required in high-rise buildings to enable first responders to communicate within the building and to communicate primarily with the fire ground commander located at the fire command center. Although two-way radio communications enhancement systems were allowed in earlier years, the radio systems were not as reliable as they are today. In addition, because the FFTs were generally supplied by the manufacturers of the fire alarm systems, designers, authorities having jurisdiction,

and installers wrongly assumed the FFTs were required as part of the life safety system. [They were required if an emergency responder radio communications system (ERRCS) was not installed.] Today the opposite is true. Since 2009, the building and fire codes require the ERRCS, allowing the FFT only by permission of the authority having jurisdiction.

A.24.10 Generally, two-way emergency communications systems for rescue assistance include area of refuge two-way emergency communications systems, stairway communications systems, elevator landing communications systems, and occupant evacuation elevator lobby communications systems. All are members of the same system type fulfilling the same functions in different locations. These systems are required to be installed in different buildings by applicable building codes, and they are considered as life-safety emergency communication systems to be used by building occupants during fire and non-fire emergencies. Because they are similar and all are two-way emergency communications systems, it is appropriate that they are mandated by a common set of requirements. These systems are different in nature from the two emergency communications systems specified in 24.3.7.2(1) and 24.3.7.2(2) for fire fighter telephones and two-way radio communications enhancement systems that are meant to be used by fire fighters or other first responders or emergency personnel.

“Areas of refuge” are typically areas that have direct access to an exit, where people who are unable to use stairs can remain temporarily in safety to await further instructions or assistance during emergency evacuation or other emergency situations. It is, therefore, important that a method to communicate exists between that remote location and a constantly attended location either within the building or at an off-premises remote location where appropriate action for assistance can be initiated by trained personnel.

Stairway communications systems are typically provided in high-rise buildings between the fire command center and remote points located at not less than every fifth floor in stairways where the stairway doors are locked from the stair side to prevent building re-entry. It is important that a method to communicate exists between that remote location in the stairs and a constantly attended location either within the building or at an off-premises remote location so that appropriate action for assistance can be initiated.

Elevator car communications systems should not be confused with an elevator landing communications system, or an occupant evacuation elevator lobby communications system. The elevator car two-way communications system is installed in accordance with the requirements of ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*. Inspection and testing of elevator car two-way communications systems is performed in accordance with ASME A17.2, *Guide for Inspection of Elevators, Escalators, and Moving Walks*.

Area of refuge is not defined in NFPA 72; rather, as stipulated in 18.4.8.5, area of refuge is defined by the applicable building code or fire code. For example, the IBC identifies area of refuge as a place where occupants can wait who are unable to use a stairway. NFPA 101 provides a broader definition. Conversely, the term *area of rescue assistance* is more generic but is not defined in NFPA 72, NFPA 101, or the IBC.

A.24.10.3 The remote call stations are also known as *call boxes*. The master control station is the main operator control device for the system, which includes a visual display of the specific

active remote call station location(s). Large systems with numerous remote call stations might also include additional (sub) control unit(s) and multiple master control stations that could expand the overall capacity of the system. The secondary power supply is required in case of a loss of the primary power supply.

A.24.10.3.2 The central control point is typically the fire command center in high-rise buildings or any other approved location in low-rise or other buildings not provided with a fire command center.

A.24.10.3.3 Typically, the fire command center is not occupied during non-fire emergencies, and therefore the system should have dial-out capability to an off-premises constantly attended monitoring station. During fire emergencies, fire fighters will be in the fire command center, and they will be able to provide assistance and guidance to occupants in need.

A.24.10.6 To ensure a timely response to a call for assistance, the call is to be forwarded to an approved off-premises constantly attended location, such as a supervising station, 911 communications center, or other monitoring location. Typically, when the person in need is able to communicate, it is expected that the monitoring personnel can quickly establish the exact location of the building and the location within the building the call was made from and communicate this information to the emergency responders. However, if the person initiating the call is unable to provide the specific location within the building (or unable to communicate at all), the appropriate emergency responders will be dispatched to the specific building address. They should be able to locate the master control station at the building's central control point and establish the exact call location within the building on the master control station display.

All systems should have this capability, even if installed in a facility that currently has a constantly attended location, such that if that location was defunded in the future, the installed system would already have the capability to automatically forward off-premises.

A.24.10.7 One method by which a signal is transmitted to the off-premises monitoring station uses telephone connections in conjunction with caller ID to identify the phone number and a name associated with the building. The call is initially identified at the off-premises monitoring location via caller ID information (provided by the telephone service), a prerecorded message, or other approved means, prior to initiating the two-way communications. Information provided can be used to access a database of building addresses and other related information to aid emergency responders attending the location. The intention of this section is to ensure that off-premises monitoring personnel have instant access to the building address so that emergency responders can be immediately dispatched to the correct location.

A.24.10.9 Generally, the building code, specification engineer, or system designer will identify the proposed locations of the remote call stations, as well as the master control station. These locations should be submitted for approval by the authority having jurisdiction based on Chapter 7 requirements. Installation and other requirements found in Section 24.10 should be coordinated with the requirements of the building code in force.

A.24.10.14 Generally, area of refuge two-way emergency communications systems, stairway communications systems, elevator landing communications systems, and occupant evacuation elevator lobby communications systems are members of the same type of system. Since it is common to install these different systems in the same building, there is no prohibition against any combination of these systems being installed in a common building as a single amalgamated system with a single master control station and remotely located call stations.

A.24.10.15 If the microphone is to be used by authorized personnel, backup personnel should be assigned and trained on its proper usage.

A.24.11 An emergency communications system information, command, and control is intended to include wired or wireless networks for one- or two-way communications and/or control between a building or area and an emergency command center and could include an emergency services organization or public alarm reporting system. In a very basic configuration, a system and the receiving facility could be a supervising station system. However, there can be more complex systems that allow control of building systems and communications to building occupants from a remote location, including a municipal or other public alarm reporting command center or possibly even from a mobile command vehicle using secure communications.

A.24.11.1 For the purposes of this chapter, an emergency command center is considered to be a mass notification system facility(s), with communications and control equipment serving more than one building, where responsible authorities receive information from premises sources or systems, or from (higher level) regional or national sources or systems, and then disseminate appropriate information to a building, multiple buildings, outside campus areas, municipalities, or a combination of these in accordance with the emergency response plan established for the premises. A mass notification system could include at least one emergency command center with optional secondary/alternate emergency command centers.

A.24.11.1.1 The location of the emergency command center should be coordinated with the first responders. The primary emergency command center should be located at the command post, emergency operations center, or some such similar location. A redundant emergency command center, if required, should be located at a physically separate location, such as a police station, fire station, or similar facility.

Generally, the primary emergency command center should be housed in a building or portion of a building separated from the rest of the facility and having a 2-hour fire-resistive-rated separation.

The mass notification system might require activation of messages originated by mobile sentries and roving patrols using wireless activation devices. In cases where clusters of facilities within the same geographical region exist, one or more regional control stations might also exercise control.

A.24.11.1.4 The emergency command center should be staffed by qualified personnel who would monitor the system and take action appropriate to the emergency response plan established for the specific premises.

A.24.11.1.5 It is imperative that individuals expected to initiate or deliver emergency messages be properly trained in the expected operations. Individuals must be familiar with the equipment, its location, and functions if they will be expected to react properly in an emergency. In an emergency situation, people only react according to instinct or habit. If the individual has not had proper and repeated training over the emergency expectations, they could lack the proper instinct or habit.

Reading an employee manual is generally not an effective means of training for an emergency. To be effective, training must be reinforced with multiple means such as text, audio, visual, and, most importantly, hands-on experience. Regular drills allowing for delivery of live messages indicating an emergency condition is important. Many people have a very difficult time communicating clearly and effectively in an emergency situation when they are excited or fearful. If live messages are to be effective, they must be short, to the point, and in a calm tone conveying exactly what is expected. Screaming into the microphone, for instance, would not be appropriate. Actual message content will depend on the emergency response plan in place for the respective business and the response to an unfolding event. Situations such as an intruder in a building have become more common today and, as such, should be considered and planned for.

A.24.11.3 Different messages or signals could be prerecorded or live voice, tones, and so forth.

A.24.11.6 Text notification via wireless devices and desktop computer notification could be an effective means for delivering mass notification messages to multiple recipient groups. Supplementary wireless text messaging could be effective in reaching remote personnel. Desktop notification is particularly effective when more complex information must be conveyed, and it can be a cost-effective interim solution prior to, but not in lieu of, installing an in-building mass notification system.

A.24.12 The risk analysis forms the basis for the emergency response plan.

Ensuring accurate information dissemination to the right people, at the right place, and at the right time is essential to the mitigation of threat actions and consequences. Trained personnel are charged with making such decisions in real time. Quite often, the instructions provided to personnel in affected areas pertain to acting in specific defensive ways so as not to expose them to danger. A typical example is the case of a chemical or biological agent attack wherein the right response is to relocate to secure areas within the building while sealing doors and windows and shutting down air intakes, rather than to leave the building and be exposed to the attacking agent.

In cases of bomb threats, where specific information is available, directions for evacuation are to be given; these directions require more specificity than simply the instruction "Evacuate the building." In most cases, the evacuation route might depend on threat intelligence and is likely to be different from that specified in an emergency response plan. Most people can tell where the fire comes from but do not always know where the bomb is. Automatic evacuation of a building, a common procedure in cases of a fire, is to be avoided, since it might expose personnel to even greater danger.

One of the reasons for implementing a mass notification system is the threat of terrorism. Terrorism attacks tend to be

well organized and are often planned with details to inflict the widest degree of damage that is possible. The mass notification system must be designed to withstand various attack scenarios and survive even if some damage has already occurred.

Each design of a mass notification system should be specific to the nature and anticipated risks of each facility for which it is designed. Although this chapter outlines some specific criteria and/or limitations, each design should be based on recognized performance-based design practices.

The mass notification system should take into account various considerations, such as those indicated in this chapter. The particular design might or might not incorporate these provisions.

Considerations for developing a mass notification system are as follows:

- (1) Specific design for the facility
- (2) Account for anticipated risks
- (3) Use of live and/or prerecorded messaging
- (4) Interfacing with other building emergency communications systems
- (5) Interfacing with wide-area notification systems
- (6) Ability to control the HVAC and access control systems
- (7) Access to system components
- (8) Survivability of the system
- (9) Communication link redundancy and security
- (10) Redundancy and security of the emergency command center
- (11) Ability to customize and add to prerecorded message library
- (12) Messages should be tailored to the situation and audience
- (13) Scripted messages for live voice messages
- (14) Proper training of individuals that operate the system

A.24.12.2 The design professional(s) as part of the design team should be experienced in multiple areas considered essential for conducting the risk analysis and performance design based on the scope and size of the project. Areas of experience can include, but are not limited to, the following:

- (1) Applying recognized performance-based design concepts
- (2) Conducting hazard and operability studies
- (3) Technical aspects of fire alarm system design
- (4) Technical aspects of emergency communication systems
- (5) Security risks and/or terrorist threats
- (6) Building code requirements and limitations with respect to egress
- (7) Human response to emergency conditions
- (8) Development of emergency response plans
- (9) Other qualifications relative to the needs of the user/risk

The design professional(s) will often be a part of the engineering design team preparing project documents and specifications. However, the design professional can work for or be obtained by a qualified installation company. The design professional should be bound by professional licensing guidelines to ensure that the risk analysis is conducted in an objective manner based on user needs and not based on product or employment.

A.24.12.6.3 Communication and coordination between and among the various members of the design team is an important element to achieving the goals for performance of the system.

A.24.12.6.6 The *SFPE Engineering Guide to Performance-Based Fire Protection* provides guidance on the elements of a design brief.

A.26.1 Table A.26.1 provides a tool for users of the Code to easily and systematically look up requirements for protected premises, central station service, remote supervising station, and proprietary supervising station alarm systems.

A.26.1.1 Supervising station alarm systems include the equipment at the protected premises as well as the equipment at the supervising station itself. While the operational requirements relating to the signals sent off-premises fall under the scope of Chapter 26, the requirements of Chapter 23 also apply. For example, for protected premises fire alarm systems, refer to Figure A.26.1.1.

A.26.2.1.2 The term *immediately* in this context is intended to mean “without unreasonable delay.” Routine handling should take a maximum of 90 seconds from receipt of an alarm signal.

A.26.2.1.3(3) Events can be general alarm signals or other fire alarm signals not identified individually by point or zone.

A.26.2.2 The term *immediately* in this context is intended to mean “without unreasonable delay.” Routine handling should take a maximum of 90 seconds from receipt of an alarm signal or at the end of the verification time by the supervising station until the initiation of retransmission to the communications center.

A.26.2.2(1) It is recognized that individual fire departments will have a preference on whether verification is used in certain occupancies based on many variables such as department-specific staffing or response protocols, occupancy staffing, and occupancy risk. This section allows the fire authority to specifically select those occupancies where verification is allowed. It should be understood that the use of the alarm verification process could delay the response to the alarm by up to an additional 90 seconds.

A.26.2.2(4) The 90-second allowance for a supervising station to call the protected premises to verify the validity of the received alarm signal is in addition to the time allowed for the supervising station to initiate the retransmission to the communications center.

A.26.2.2(6) It is important to notify the communications center that an alarm signal was verified and that fire conditions exist at the protected premises or that some other type of an emergency exists. Fire departments typically have a substantially larger response for confirmed structure fires.

A.26.2.2(7) If an alarm signal cannot be reliably confirmed as a nuisance alarm, then it should be immediately retransmitted. This might include situations where no contact is made within the premises, or where the persons within the premises cannot verify the source of the alarm within the allowable 90 seconds, or other related scenarios.

A.26.2.2(8) When verification of a fire alarm signal results in a signal not being reported to the communications center, it is important that fire department personnel be made aware of the alarm and the reason for nondispatch so that problematic systems can be identified.

A.26.2.4.1.3 If a carbon monoxide detector cannot be reset in accordance with Chapter 14, it could indicate that carbon monoxide is still present in the premises. Until such time that carbon monoxide can be excluded as the source of the alarm, the assumption should be that carbon monoxide is present and appropriate life safety precautions should be followed.

A.26.2.5.2.2 Scheduled impairments include interruptions caused by construction or building damage. In addition, natural disasters can result in long-term system impairments that are not intended to require 24-hour reminders.

A.26.2.7 Changing where signals go from an existing to a new or different supervising station facility is sometimes done simply by changing a call-forward phone number. Or, within a supervising station, a new receiving computer and software can be constructed and lines changed over. Often, the account data are manually entered into the new system. Sometimes the data are transferred electronically. Errors can be made, causing the supervising station to get undefined alarms or incorrect account data, resulting in incorrect response by the supervising station. When such changes are made, the only viable way to ensure correct operation is to conduct an end-to-end test.

A.26.2.7.1 The phrase “notified in writing” can include any form of correspondence that can be verified upon request, such as a letter, fax, email or other means of documented transfer of information from one entity to another.

A.26.3.2 There are related types of contract service that often are provided from, or controlled by, a central station but that are neither anticipated by, nor consistent with, the provisions of 26.3.2. Although 26.3.2 does not preclude such arrangements, a central station company is expected to recognize, provide for, and preserve the reliability, adequacy, and integrity of those supervisory and alarm services intended to be in accordance with the provisions of 26.3.2.

Table A.26.1 Alarm System Performance Criteria

Attribute	Protected Premises Fire Alarm System	Central Station Service Alarm System	Remote Supervising Station Alarm System	Proprietary Supervising Station Alarm System
Applicability	All fire alarm systems	Supervising station service provided by a prime contractor. There is a subscriber (26.3.2, 26.3.3, and 26.3.4).	Where central station service is neither required nor elected, properties under various ownership monitored by a remote supervising station (26.5.1.1 and 26.5.1.2)	Supervising station monitoring contiguous or noncontiguous properties under one ownership and responsible to the owner of the protected property (26.4.2.1 and 26.4.2.2)
Listing	Equipment listed for the use intended (10.3)	Equipment listed for the use intended (10.3). Compliance documentation (26.3.4).	Equipment listed for use intended (10.3)	Equipment listed for use intended (10.3)
Design	According to Code by experienced persons (10.5.1)	According to Code by experienced persons (10.5.1)	According to Code by experienced persons (10.5.1)	According to Code by experienced persons (10.5.1)
Compatibility	Detector devices pulling power from initiating or signaling circuits listed for control unit (10.3.3)	Detector devices pulling power from initiating or signaling circuits listed for control unit (10.3.3)	Detector devices pulling power from initiating or signaling circuits listed for control unit (10.3.3)	Detector devices pulling power from initiating or signaling circuits listed for control unit (10.3.3)
Performance and limitations	85% and 110% of the nameplate rated input voltage, 32°F (0°C) and 120°F (49°C) ambient temperature, 85% relative humidity at 86°F (30°C) (10.3.5)	85% and 110% of the nameplate rated input voltage, 32°F (0°C) and 120°F (49°C) ambient temperature, 85% relative humidity at 86°F (30°C) (10.3.5)	85% and 110% of the nameplate rated input voltage, 32°F (0°C) and 120°F (49°C) ambient temperature, 85% relative humidity at 86°F (30°C) (10.3.5)	85% and 110% of the nameplate rated input voltage, 32°F (0°C) and 120°F (49°C) ambient temperature, 85% relative humidity at 86°F (30°C) (10.3.5)
Documentation	Authority having jurisdiction notified of new or changed specifications, wiring diagrams, battery calculations, floor plans. Statement from contractor that system meets manufacturer's published instructions and NFPA requirements (7.5.2). Record of completion (7.5.6). Results of evaluation required in 23.4.3.1 (23.4.3.3).	Authority having jurisdiction notified of new or changed specifications, wiring diagrams, battery calculations, floor plans. Statement from contractor that system meets manufacturer's published instructions and NFPA requirements (7.5.2). Record of completion (7.5.6). Results of evaluation required in 23.4.3.1 (23.4.3.3).	Authority having jurisdiction notified of new or changed specifications, wiring diagrams, battery calculations, floor plans. Statement from contractor that system meets manufacturer's published instructions and NFPA requirements (7.5.2). Record of completion (7.5.6). Results of evaluation required in 23.4.3.1 (23.4.3.3).	Authority having jurisdiction notified of new or changed specifications, wiring diagrams, battery calculations, floor plans. Statement from contractor that system meets manufacturer's published instructions and NFPA requirements (7.5.2). Record of completion (7.5.6). Results of evaluation required in 23.4.3.1 (23.4.3.3).
Supervising station facilities	None	UL 827-compliant for the supervising station and any subsidiary station (26.3.5.1 and 26.3.5.2)	Communications centers or other location acceptable to the authority having jurisdiction (26.5.3)	Fire-resistive, detached building or cut-off room not near or exposed to hazards. Access restricted, NFPA 10, 26-hour emergency lighting (26.4.3).

(continues)

Table A.26.1 *Continued*

Attribute	Protected Premises Fire Alarm System	Central Station Service Alarm System	Remote Supervising Station Alarm System	Proprietary Supervising Station Alarm System
Testing and maintenance	Chapter 14	Chapter 14. Pass code must be provided to place system into test mode (26.3.8.3.5.6).	Chapter 14	Chapter 14
Runner service	No	Yes Alarm — arrive at the protected premises within 2 hours where equipment needs to be reset. Guard's tour — 30 minutes. Supervisory — 2 hours. Trouble — 4 hours. (26.3.8)	No	Yes Alarm — arrive at the protected premises within 2 hours where equipment needs to be reset. Guard's tour — 30 minutes. Supervisory — 2 hours. Trouble — 4 hours. (26.4.6.1.6)
Operations and management requirements	None	Prime contractor provides all elements of central station service under a variety of contractual arrangements (26.3.3)	None	Supervising station is under same ownership and management responsibility as premises being supervised (26.4.2.1)
Staff	None	Minimum of two persons on duty at supervising station. Operation and supervision primary task (26.3.7).	Minimum of two persons on duty at supervising station at all times. Other duties permitted per the authority having jurisdiction (26.5.5).	Two operators of which one is permitted to be the runner. When runner is not in attendance at station, time between contact not to exceed 15 minutes. Primary duties are monitoring alarms and operations of station (26.4.5).
Monitor supervisory signals	Control unit and command center (10.14.1 and 10.14.2)	Control unit, command center, and central station (10.14.1 and 10.14.2)	Control unit, command center, and remote supervising station (10.14.1 and 10.14.2)	Control unit, command center, and proprietary supervising station (10.14.1 and 10.14.2)
Retransmission of signals	None	Alarm to public service communications center and subscriber. Supervisory, trouble, and guard service to designated personnel (26.3.8).	Alarm to public service communications center when monitored privately. Supervisory and trouble signals to owner's designated representative (26.5.6).	Alarm to public service communications center and plant brigade. Supervisory, trouble, and guard service to designated personnel (26.4.6.1.6).
Retransmission time	None	Alarm — immediate. Supervisory — immediate. Guard's tour supervisory — without unreasonable delay. Trouble — immediate. (26.3.8)	Alarm — immediate. Supervisory — immediate. Trouble — immediate. (26.5.6)	Alarm — immediate. Supervisory — immediate. Guard's tour supervisory — at once. Trouble — immediate. (26.4.6.1.6)
Records	Current year and 1 year after (7.7.1)	Complete records of all signals received must be retained for at least 1 year. Reports provided of signals received to authority having jurisdiction in a form it finds acceptable (26.3.9).	At least 1 year (26.5.8.1).	Complete records of all signals received shall be retained for at least 1 year. Reports provided of signals received to authority having jurisdiction in a form it finds acceptable (26.4.7).




FIGURE A.26.1.1 Supervising Station Alarm System.

A.26.3.4 The terms *certificated* and *placarded*, which appeared in previous editions of NFPA 72, were considered by some to be too specific to two listing organizations and were replaced with more generic wording. The concept of providing documentation to indicate ongoing compliance of an installed system continues to be reflected by the current language.

There are two distinct services offered by organizations that list fire alarm service provided by prime contractors and central stations. The first is the listing of these alarm services, which requires the companies to demonstrate they have the knowledge and ability to install, test, service, and maintain central station alarm systems and/or monitor and appropriately retransmit on receipt of various signals from protected premises alarm systems.

The second part of the service provided by listing organizations is the certification of individual protected premises fire alarm systems to bring the alarm systems under their ongoing audit inspection program or systematic follow-up program. Under this program, systems are certified by the listing organization, and documentation of this is to be provided, posted, and handled as described in 26.3.4 through 26.3.4.8. The method used to document compliance with this portion of the program varies among listing organizations and includes the issuance of certificates, placards, or other documentation.

There is nothing in this Code that requires all protected premises alarm systems monitored by a listed central station to be tested, maintained, serviced, monitored, and responded to in accordance with Section 26.3. This is often misunderstood by code users, owners, and AHJs, who think that merely specifying that these systems be monitored by a central station with a fire alarm listing gets them full central station service. Full compliance with central station alarm system requirements involves using alarm companies with fire alarm listings and having the listing organization certify the protected premises alarm system.

A.26.3.4.1 The documentation in this section should not be confused with the documentation required in Chapter 7, which is typically provided by the alarm company and covers the design, acceptance, and completion of new systems. Instead the documentation in this section is provided by the listing organization and could be in the form of a certificate, placard, or other document used by the listing organization.

A.26.3.4.2(2) The record of completion (*see Chapter 10*) can be used to fulfill this requirement.

A.26.3.4.5 It is the prime contractor's responsibility to remove all compliance markings (certification markings or placards) when a service contract goes into effect that conflicts in any way with the requirements of 26.3.4.

A.26.3.4.6 The prime contractor should be aware of statutes, public agency regulations, or certifications regarding alarm systems that might be binding on the subscriber. The prime contractor should identify for the subscriber which agencies could be an authority having jurisdiction and, if possible, advise the subscriber of any requirements or approvals being mandated by these agencies.

The subscriber has the responsibility for notifying the prime contractor of those private organizations that are being designated as an authority having jurisdiction. The subscriber also has the responsibility to notify the prime contractor of changes in the authority having jurisdiction, such as where there is a

change in insurance companies. Although the responsibility is primarily the subscriber's, the prime contractor should also take responsibility for seeking out these private authority(ies) having jurisdiction through the subscriber. The prime contractor is responsible for maintaining current records on the authority(ies) having jurisdiction for each protected premises.

The most prevalent public agency involved as an authority having jurisdiction with regard to alarm systems is the local fire department or fire prevention bureau. These are normally city or county agencies with statutory authority, and their approval of alarm system installations might be required. At the state level, the fire marshal's office is most likely to serve as the public regulatory agency.

The most prevalent private organizations involved as authorities having jurisdiction are insurance companies. Others include insurance rating bureaus, insurance brokers and agents, and private consultants. It is important to note that these organizations have no statutory authority and become authorities having jurisdiction only when designated by the subscriber.

With both public and private concerns to satisfy, it is not uncommon to find multiple authorities having jurisdiction involved with a particular protected premises. It is necessary to identify all authorities having jurisdiction in order to obtain all the necessary approvals for a central station alarm system installation.

The phrase "in writing" can include any form of correspondence that can be verified upon request, such as a letter, fax, email or other means of documented transfer of information from one entity to another.

A.26.3.6.6 Two telephone lines (numbers) at the central station connected to the public switched telephone network or a managed facilities-based voice network, each having its own telephone instrument connected, and two telephone lines (numbers) available at the communications center to which a central station operator can retransmit an alarm meet the intent of this requirement.

A.26.3.8.3.1(1) Nothing in this section is intended to prevent communication with the subscriber in less than 15 minutes from the receipt of the signal.

A.26.3.8.3.3 It is anticipated that the central station will first attempt to notify designated personnel at the protected premises. When such notification cannot be made, it might be appropriate to notify law enforcement or the fire department, or both. For example, if a valve supervisory signal is received where protected premises are not occupied, it is appropriate to notify the police.

A.26.3.8.3.3(1) The term immediately in this context is intended to mean "without unreasonable delay." Routine handling should take a maximum of 4 minutes from receipt of a supervisory signal by the central station until the initiation of communications with a person(s) designated by the subscriber.

A.26.3.8.3.4(1) The term immediately in this context is intended to mean "without unreasonable delay." Routine handling should take a maximum of 4 minutes from receipt of a trouble signal by the central station until initiation of the investigation by telephone.

A.26.3.8.3.5.3 The term immediately in this context is intended to mean “without unreasonable delay.” Routine handling should take a maximum of 4 minutes from receipt of a trouble signal by the central station until initiation of the investigation by telephone.

A.26.4.3.1 Consideration should be given to providing the following features for a proprietary supervising station location:

- (1) Fire resistive construction meeting the requirements of adopted building codes
- (2) Air handling systems isolated from common building systems

As a useful guide for determining the nature of the design and integrity necessary to achieve proper protection, the proprietary supervising station building or that portion of a building occupied by a proprietary supervising station should compare the construction, fire protection, restricted access, emergency lighting, and power facilities to the requirements stated in the latest edition of UL 827, *Central-Station Alarm Services*.

A.26.4.3.6 It is the intent of this Code that the operator within the proprietary supervising station should have a secure means of immediately retransmitting any signal indicative of a fire to the public fire department communications center. Automatic retransmission using an approved method installed in accordance with Sections 26.3 through 26.5, and Chapter 27 is the best method for proper retransmission. However, a manual means can be permitted to be used, consisting of either a manual connection following the requirements of Section 26.3, Section 26.5, and Chapter 27, or, for proprietary supervising stations serving only contiguous properties, a means in the form of a municipal fire alarm box installed within 50 ft (15.2 m) of the proprietary supervising station in accordance with Chapter 27 can be permitted.

A.26.4.4.1.3 Depending on a building's size and configuration, specific location information received by the proprietary supervising station could be warranted. This information could assist responding individuals by allowing them to respond directly to areas of the building where signals have been initiated. An example of a building where this might be beneficial might be a multi-floor building or one with a large building footprint. Signals from smaller buildings, such as a fast food restaurant or a gas station convenience store, would likely only need to be general in nature. It should be noted that this section does not specifically call for point identification, but the specific device location information provided by such a system would meet the requirements of the section.

A.26.4.4.3 Proprietary station procedures should include periodic review of nonrestored signals. One method for such a review could be by the use of equipment that would automatically redisplay the information.

A.26.4.6.1.3.3 Regardless of the type of retransmission facility used, telephone communications between the proprietary supervising station and the fire department should be available at all times and should not depend on a switchboard operator.

A.26.4.6.1.6.3(5) The phrase “written notice” can include any form of correspondence that can be verified upon request, such as a letter, fax, email or other means of documented transfer of information from one entity to another.

A.26.5.2.2(1) Chapter 14 permits the building owner or his designated representative to perform these services if they are qualified. In this situation, the documentation could be a declaration of qualification signed by the building owner. Multiple service providers are permitted.

A.26.5.3 As a minimum, the room or rooms containing the remote supervising station equipment should have a 1-hour fire rating, and the entire structure should be protected by an alarm system complying with Chapter 23.

As a useful guide for determining the nature of the design and integrity necessary to achieve proper protection, the remote supervising station building or that portion of a building occupied by a remote supervising station should compare the construction, fire protection, restricted access, emergency lighting, and power facilities to the requirements stated in the latest edition of UL 827, *Central-Station Alarm Services*.

If the remote supervising station is located within an emergency response agency (ERA), the ERA should consider meeting the requirements of Chapter 4 of NFPA 1221.

A.26.5.3.1.4 A listed central station might be considered an acceptable alternate location for receipt of fire alarm, supervisory, and trouble signals.

A.26.5.3.2 A listed central station might be considered an acceptable alternate location for receipt of trouble signals.

A.26.6.1 Refer to Table A.26.6.1 for communications methods.

A.26.6.2.2 It is not the intent of Section 26.6 to limit the use of listed equipment using alternate communications methods, provided these methods demonstrate performance characteristics that are equal to or superior to those technologies described in Section 26.6. Such demonstration of equivalency is to be evidenced by the equipment using the alternate communications methods meeting all the requirements of Chapter 10, including those that deal with such factors as reliability, monitoring for integrity, and listing. It is further expected that suitable proposals stating the requirements for such technology will be submitted for inclusion in subsequent editions of this Code.

A.26.6.2.4 The communications cloud is created by multiple telephone lines and multiple paths on the Internet. Under these circumstances, the requirements of Chapters 10 and 14, as required by 26.1.2, do not apply to devices comprising the communications cloud.

Table A.26.6.1 Communications Methods for Supervising Stations

Criteria	Performance-Based Technologies 26.6.3	Digital Alarm Communicator Systems 26.6.4	Two-Way Radio Frequency (RF) Multiplex Systems 26.6.5.1	One-Way Private Radio Alarm Systems 26.6.5.2
Federal Communications Commission (FCC) approval when applicable	Yes	Yes	Yes	Yes
Conform to <i>NFPA 70</i>	Yes	Yes	Yes	Yes
Monitoring for integrity of the transmission and communications channel	Monitor for integrity	Both the premises unit and the system unit monitor for integrity in a manner approved for the means of transmission employed. A single signal received on each incoming DACR line once every 6 hours.	Systems are periodically polled for end-to-end communications integrity.	Test signal from every transmitter once every 24 hours
Annunciate, at the supervising station, the degradation and restoration of the transmission or communications channel	Within 60 minutes for a single communication path and within 6 hours for multiple communication paths	Within 4 minutes using alternate phone line to report the trouble	Not exceed 90 seconds from the time of the actual failure	Only monitor the quality of signal received and indicate if the signal falls below minimum signal quality specified in Code
Redundant communication path where a portion of the transmission or communications channel cannot be monitored for integrity		Employ a combination of two separate transmission channels alternately tested at intervals not exceeding 6 hours	Redundant path not required — supervising station always indicates a communications failure	Minimum of two independent RF paths must be simultaneously employed
Interval testing of the backup path(s)		When two phone lines are used, test alternately every 6 hours. Testing for other back-up technologies, see 26.6.4.1.4(B).	Backup path not required	No requirement, because the quality of the signal is continuously monitored
Annunciation of communication failure or ability to communicate at the protected premises	Systems where the transmitter at the local premises unit detects a communication failure, the premises unit will annunciate the failure within 200 seconds of the failure	Indication of failure at premises due to line failure or failure to communicate after from 5 to 10 dialing attempts	Not required — always annunciated at the supervising station that initiates corrective action	Monitor the interconnection of the premises unit elements of transmitting equipment, and indicate a failure at the premises or transmit a trouble signal to the supervising station.
Time to restore signal-receiving, processing, display, and recording equipment	Where duplicate equipment not provided, spare hardware required so a repair can be effected within 30 minutes.	Spare digital alarm communicator receivers required for switchover to backup receiver in 30 seconds. One backup system unit for every five system units.	Where duplicate equipment not provided, spare hardware required so a repair can be effected within 30 minutes	Where duplicate equipment not provided, spare hardware required so a repair can be effected within 30 minutes
Loading capacities for system units and transmission and communications channels	512 independent alarm systems on a system unit with no backup. Unlimited if you can switch to a backup in 30 seconds.	See Table 26.6.4.2.2(D) for the maximum number of transmitters on a hunt group in a system unit	512 buildings and premises on a system unit with no backup. Unlimited if you can switch to a backup in 30 seconds.	512 buildings and premises on a system unit with no backup. Unlimited if you can switch to a backup in 30 seconds.
End-to-end communication time for an alarm	90 seconds from initiation of alarm until displayed to the operator and recorded on a medium from which the information can be retrieved	Off-hook to on-hook not to exceed 90 seconds per attempt. 10 attempts maximum. 900 seconds maximum for all attempts.	90 seconds from initiation until it is recorded	90% probability to receive an alarm in 90 seconds, 99% probability in 180 seconds, 99.999% probability in 450 seconds

(continues)

Table A.26.6.1 *Continued*

Criteria	Performance-Based Technologies 26.6.3	Digital Alarm Communicator Systems 26.6.4	Two-Way Radio Frequency (RF) Multiplex Systems 26.6.5.1	One-Way Private Radio Alarm Systems 26.6.5.2
Record and display rate of subsequent alarms at supervising station	Not slower than one every 10 additional seconds	Not addressed	When any number of subsequent alarms come in, record at a rate not slower than one every additional 10 seconds	When any number of subsequent alarms come in, record at a rate not slower than one every additional 10 seconds
Signal error detection and correction	Signal repetition, parity check, or some equivalent means of error detection and correction must be used.	Signal repetition, digital parity check, or some equivalent means of signal verification must be used.	Not addressed	Not addressed
Path sequence priority	No need for prioritization of paths. The requirement is that both paths are equivalent.	The first transmission attempt uses the primary channel.	Not addressed	Not addressed
Carrier diversity		Where long distance service (including WATS) is used, the second telephone number must be provided by a different long distance service provider where there are multiple providers.	Not addressed	Not addressed
Throughput probability		Demonstrate 90% probability of a system unit immediately answering a call or follow the loading in Table 26.6.4.2.2(D). One-way radio backup demonstrates 90% probability of transmission.	Not addressed	90% probability to receive an alarm in 90 seconds, 99% probability in 180 seconds, 99.999% in probability 450 seconds
Unique premises identifier	If a transmitter shares a transmission or communication channel with other transmitters, it must have a unique transmitter identifier.	Yes	Yes	Yes
Unique flaws	From time to time, unique flaws might be present in a communication system. Requirements must be written for unique flaws.	If call forwarding is used to communicate to the supervising station, verify the integrity of this feature every 4 hours.	None addressed	None addressed
Signal priority	If the communication method is shared with any other communication method, prioritizing alarm signals should be considered.	Chapter 10 on fundamentals requires that alarm signals take priority over supervisory signals unless there is sufficient repetition of the alarm signal to prevent the loss of an alarm signal.	Chapter 10 on fundamentals requires that alarm signals take priority over supervisory signals unless there is sufficient repetition of the alarm signal to prevent the loss of an alarm signal.	Chapter 10 on fundamentals requires that alarm signals take priority over supervisory signals unless there is sufficient repetition of the alarm signal to prevent the loss of an alarm signal.
Sharing communications equipment on premises	If the transmitter is sharing on-premises communications equipment, the shared equipment must be listed for the purpose (otherwise the transmitter must be installed ahead of the unlisted equipment).	Disconnect outgoing or incoming telephone call and prevent its use for outgoing telephone calls until signal transmission has been completed.	Not addressed	Not addressed

A.26.6.3 Certain legacy technologies (active multiplex, McCulloh, directly connected non-coded and private microwave) have been removed from the text of the document. Existing systems utilizing these technologies are acceptable, because all these technologies also comply with the general provisions of 26.6.3.

The object of 26.6.3 is not to give details of specific technologies but rather give basic operating parameters of the transmission supervision rates of technologies. The following list represents examples of current technologies that can be configured to meet the requirements and the intent of 26.6.3:

- (1) Transmitters using IP (Internet Protocol)
- (2) IP transmission over the public open Internet or over private IP facilities maintained by an organization for its own use
- (3) Transmitters using various (non-dialup) digital cellular technology

Wired IP Transmission. There are two types of wired IP transmission devices. One type connects the IP network directly to the fire alarm control unit (integrated IP or native IP). The second uses an intermediary module that can include the following:

- (1) IP dialer capture module
- (2) IP data capture module (such as RS-232, keypad bus, RS-485)
- (3) Relay contact monitoring module

Devices referred to as “IP dialer capture modules” (an IP communicator used with a DACT) are transmission devices that connect to the DACT output of the fire alarm control unit and convert the output data stream to IP (Internet protocol). As such, they are considered to use IP technology in their connection to the IP network. Therefore, they should be treated in this Code under the requirements of 26.6.3, performance-based technologies, and not under the requirements of 26.6.4, digital alarm communicator systems.

Digital Cellular. To accommodate an increase in the demand for mobile wireless communications as well as introducing new services over that same network, wireless voice communications no longer utilizes dedicated connections to pass voice band frequencies. In place of the voice band, the voice conversation is converted into a stream of bits and packaged within data packets that conform to messaging protocols. The packets are addressed to a destination point, delivered into the network, received by the destination point, and converted back into intelligible voice-grade messages. The message exchange through this wireless data network is done through well-known defined protocols such as “Global System for Mobile” communications (GSM) for voice communications as well as Code Division Multiple Access (CDMA) for both voice and data and General Packet Radio Service (GPRS) for mobile data services. These protocols have been developed to operate in an optimal way for the intended application. For example, GSM is used to efficiently establish voice-grade connections that deliver an appropriate level of intelligible voice quality, but might not be good enough to pass tones that represent data. Data transmission is better served by GPRS and CDMA where a connection into the wireless network is always available without having to “dial,” and large amounts of data can be efficiently transmitted. However, the data passed using GPRS or CDMA are not that of coded tones such as DTMF (Contact ID), but are computer-type messages similar to IP.

When using digital cellular, a DACT might or might not be used.

For example, the digital cellular device might be used to back up the DACT or, if properly supervised, be used as a stand-alone device. If used, the DACT is connected to a digital cellular radio device that connects to the cellular network by means of an antenna. The digital cellular radio device is constantly connecting to the wireless network and is always ready to attempt to transmit to a destination address without having to “dial” a number. The radio device recognizes that the alarm panel is attempting to place a call by the DACT’s “off-hook” signaling. The radio device accepts the DACT tone signaling, converts it into a packetized data stream, and sends the packets into the wireless network for delivery to a pre-assigned destination address.

A.26.6.3.5 When considering a fire alarm system utilizing a single communication path to the supervising station, consideration should be given to the risk exposure that results from the loss of that path for any period of time and for any reason. Some of these outages can be regular and predictable and others transitory.

One example of a single technology used to produce two paths is the use of a digital cellular premises unit communicating with two or more cell towers. In this case, the supervising station and the protected premises must be made aware if communications degrades to below two towers. Another example is the use of two different cellular carriers to produce the two paths. Similarly, in this case the supervising station and the protected must be made aware if communications degrades to one carrier.

A.26.6.3.12 Most communications equipment is not specifically listed for fire alarm applications, but is listed in accordance with applicable product standard for general communications equipment and is acceptable.

A.26.6.3.13.1 Shared equipment owned by or under the control of the subscriber should provide 24 hours of secondary standby power.

A.26.6.3.13.1.1 Shared equipment owned by or under the control of an approved managed facilities-based voice network provider should supply 8 hours of secondary power.

A.26.6.3.13.1.2 The requirement in 26.6.3.13.1.2 does not exempt first communications path transmitters and first communications path shared equipment necessary for the transmission of alarm, supervisory, trouble, and other signals located at the protected premises from the secondary power capacity requirements of 26.6.3.13. This section does not permit the communications paths to be considered multiple communication paths under 26.6.3.4.

A.26.6.4.1 A DACT can be used as a signaling interface from a fire alarm control unit to another means of signal transmission. Typically this is in either Ademco Contact ID or SIA format. In this case, the use of a DACT is not for the direct transmission of signals via a connection through a telephone line, but rather to another means of signal transport, because there are no phone lines utilized in the communication path. The other transmission means will then transmit the signal data via another listed means, which is found in 26.6.3 or 26.6.5.

A.26.6.4.2.1 Special care should be used when connecting a DACT to a digital service such as DSL or ADSL. Filters or other special equipment might be needed to communicate reliably.

A.26.6.4.2.3 To give the DACT the ability to disconnect an incoming call to the protected premises, telephone service should be of the type that provides for timed-release disconnect. In some telephone systems (step-by-step offices), timed-release disconnect is not provided.

A.26.6.4.2.3.3 A DACT can be programmed to originate calls to the DACR telephone lines (numbers) in any alternating sequence. The sequence can consist of single or multiple calls to one DACR telephone line (number), followed by transmissions on the alternate path or any combination thereof that is consistent with the minimum/maximum attempt requirements in 26.6.4.2.3.3.

A.26.6.4.2.4.2(6) Where two telephone lines (numbers) are used, care should be taken to assign the primary DACT telephone line (number) to a nonessential telephone line (number) at the protected premises so that the primary line used in the premises is not unnecessarily interrupted.

A.26.6.4.2.5(4) Where two telephone lines (numbers) are used, care should be taken to assign the primary DACT telephone line (number) to a nonessential telephone line (number) at the protected premises so that the primary line used in the premises is not unnecessarily interrupted.

A.26.6.4.2.5(8) Because call forwarding requires equipment at a telephone company central office that could occasionally interrupt the call forwarding feature, a signal should be initiated whereby the integrity of the forwarded telephone line (number) that is being called by DACTs is verified every 4 hours. This can be accomplished by a single DACT, either in service or used solely for verification, that automatically initiates and completes a transmission sequence to its associated DACR every 4 hours. A successful signal transmission sequence of any other type within the same 4-hour period should be considered sufficient to fulfill this requirement.

Call forwarding should not be confused with WATS or 800 service. The latter, differentiated from the former by dialing the 800 prefix, is a dedicated service used mainly for its toll-free feature; all calls are preprogrammed to terminate at a fixed telephone line (number) or to a dedicated line.

A.26.6.4.3.2.1 The timed-release disconnect considerations as outlined in A.26.6.4.2.3 apply to the telephone lines (numbers) connected to a DACR at the supervising station.

It might be necessary to consult with appropriate telephone service personnel to ensure that numbers assigned to the DACR can be individually accessed even where they are connected in rotary (a hunt group).

A.26.6.4.3.2.4 In determining system loading, Table 26.6.4.3.2.4 can be used, or it should be demonstrated that there is a 90 percent probability of incoming line availability. Table 26.6.4.3.2.4 is based on an average distribution of calls and an average connected time of 30 seconds per message. Therefore, where it is proposed to use Table 26.6.4.3.2.4 to determine system loading, if any factors are disclosed that could extend DACR connect time so as to increase the average connect time, the alternate method of determining system loading should be used. Higher (or possibly lower) loadings might be appropriate in some applications.

- (1) Some factors that could increase (or decrease) the capacity of a hunt group are as follows:
 - (a) Shorter (or longer) average message transmission time can influence hunt group capacity.
 - (b) The use of audio monitoring (listen-in) slow-scan video or other similar equipment can significantly increase the connected time for a signal and reduce effective hunt group capacity.
 - (c) The clustering of active burglar alarm signals can generate high peak loads at certain hours.
 - (d) Inappropriate scheduling of 6-hour test signals can generate excessive peak loads.
- (2) Demonstration of a 90 percent probability of incoming line availability can be accomplished by the following in-service monitoring of line activity:
 - (a) Incoming lines are assigned to telephone hunt groups. When a DACT calls the main number of a hunt group, it can connect to any currently available line in that hunt group.
 - (b) The receiver continuously monitors the "available" status of each line. A line is available when it is waiting for an incoming call. A line is unavailable for any of the following reasons:
 - i. Currently processing a call
 - ii. Line in trouble
 - iii. Audio monitoring (listen-in) in progress
 - iv. Any other condition that makes the line input unable to accept calls
 - (c) The receiver monitors the "available" status of the hunt group. A hunt group is available when any line in it is available.
 - (d) A message is emitted by the receiver when a hunt group is unavailable for more than 1 minute out of 10 minutes. This message references the hunt group and the degree of overload.

A.26.6.5.1.4 The intent of the plurality of control sites is to safeguard against damage caused by lightning and to minimize the effect of interference on the receipt of signals. The control sites can be co-located.

A.26.6.5.2 Originally the concept of one-way private radio was codified for a one-way system requiring at least two receiving towers or repeaters. Other similar systems have been developed that use this basic principle. Among them is the concept of the "mesh network" where a premises transmitter can access multiple nearby transmitters.

It is difficult to reliably test redundant paths on a mesh radio network without significant impact on the system and considerable efforts of time and personnel.

A remedy is to have the mesh network system equipment generate a report at the protected premises or supervising station showing redundant pathways. Additionally, the mesh system equipment at the protected premises and at the supervising station periodically determine the number of viable redundant paths and generate a trouble signal whenever the number falls below two paths, as is required by 26.6.5.2.

A.26.6.5.2.2 It is intended that each RAT communicate with two or more independently located RARSRs. The location of such RARSRs should be such that they do not share common facilities.

NOTE: All probability calculations required for the purposes of Chapter 17 should be made in accordance with established communications procedures, should assume the maximum channel loading parameters specified, and should further assume that 25 RATs are actively in alarm and are being received by each RARSR.

A.26.6.6.1 The signal information can be permitted to be provided in coded form. Records can be permitted to be used to interpret these codes.

A.26.6.6.2(4) Any signal that would dictate a different response, such as carbon monoxide alarms or mass notification alarms, should be individually identifiable so the appropriate response to the event can be initiated. There are more types of alarms and other signals that are being received at supervising stations and that require different responses by supervising station operators. These signals could be other than fire, but still life safety in nature, and must be uniquely identified because their signal is indicative of a different response.

A.26.6.6.3 An example of a critical assembly is an assembly in which a malfunction prevents the receipt and interpretation of signals by the supervising station operator.

A.26.6.6.4 In order to expedite repairs, it is recommended that spare modules, such as printed circuit boards, displays, or printers, be stocked at the supervising station.

A.26.6.6.5 For all forms of transmission, the maximum time to process an alarm signal should be 90 seconds. The maximum time to process a supervisory signal should be 4 minutes. The time to process an alarm or supervisory signal is defined as that time measured from receipt of a signal until retransmission or subscriber contact is initiated.

When the level of traffic in a supervising station system reaches a magnitude such that delayed response is possible, even if the loading tables or loading formulas of this Code are not exceeded, it is envisioned that it will be necessary to employ an enhanced method of processing.

For example, in a system where a single DACR instrument provided with fire and burglar alarm service is connected to multiple telephone lines, it is conceivable that, during certain periods of the day, fire alarm signals could be delayed by the security signaling traffic, such as opening and closing signals. Such an enhanced system would perform as follows, upon receipt of a signal:

- (1) Automatically process the signals, differentiating between those that require immediate response by supervising station personnel and those that need only be logged
- (2) Automatically provide relevant subscriber information to assist supervising station personnel in their response
- (3) Maintain a timed, unalterable log of the signals received and the response of supervising station personnel to such signals

A.27.1.7 Auxiliary alarm systems include the equipment at the protected premises as well as the equipment connecting it to the public emergency alarm reporting system. While the operational requirements relating to the signals sent off-premises fall under the scope of Chapter 27, the requirements of Chapter 23 also apply.

A.27.2.1 When choosing from available options to implement a public emergency alarm reporting system, the operating agency should consider which of the choices would facilitate

the maximum reliability of the system, where such a choice is not cost prohibitive.

A.27.2.3 Consideration should be given to the fact that devices could be installed in areas that are exposed to higher or lower temperatures, moisture, or other environmental conditions that could be more severe than ambient conditions found in a typical building. As an example, equipment could be installed inside a building in a boiler room, basement, attic, and so forth, where temperatures actually exceed ambient conditions outside the building. It is recommended that the authority having jurisdiction consider all possible installation locations and environmental conditions and that the equipment selected be designed to operate within the most extreme conditions to which it could be exposed.

A.27.4.3.3 Nonfederal radio frequencies are licensed by the Federal Communications Commission (FCC). Federal radio frequencies are assigned by the NTIA. Most frequencies available for FCC licensing require frequency coordination in order to limit interference from other users. Authorities having jurisdiction should use licensed, coordinated radio frequencies for wireless networks in order to minimize interference.

Outside of the United States similar regulatory bodies provide coordination and licensing such as Industry Canada.

A.27.5.2.5.1(1) Figure A.27.5.2.5.1(1) illustrates a Form 4A arrangement.

A.27.5.2.5.1(2) Figure A.27.5.2.5.1(2) illustrates a Form 4B arrangement.

A.27.5.3 Subsection 27.5.3 provides requirements for circumstances in which a municipality or government agency has situated a communications center at a location remote from the alarm processing equipment for the public emergency alarm reporting system. This might occur when the municipality or government agency has moved the communications center to combine services with other emergency dispatching, such as police emergency and medical services, or to combine with neighboring towns or cities (regionalization). In such cases, it might be impractical to relocate the alarm processing equipment.




FIGURE A.27.5.2.5.1(1) Form 4A.

A.27.5.5.1.1 Figure A.27.5.5.1.1 illustrates a Type A receiving network.

A.27.5.5.1.4 Figure A.27.5.5.1.4 illustrates the separate functional requirements and power source requirements for systems that function with wireless network repeater systems in accordance with 27.5.5.1.4.

A.27.5.5.3.3 See A.27.6.6.2.

A.27.6.1 There are three types of alarm boxes covered under Chapter 27. They are the publicly accessible box, auxiliary box, and master box.




FIGURE A.27.5.2.5.1(2) Form 4B.

Poling required for transpondence-type (two-way) systems only.




FIGURE A.27.5.5.1.1 Type A System Receiving Networks.

- (1) The publicly accessible box has a manual control that can be operated by the public. This type of alarm box is typically located outside on a pole or building and was previously called a street box. The box type was renamed because it is not necessarily located on or near a street.
- (2) An auxiliary box is part of an auxiliary alarm system and can be automatically activated either by initiating devices in limited applications or by a protected premises alarm system (Chapter 23). An auxiliary box can be located inside or outside a building.
- (3) The master box is a combination box that can be manually operated (publicly accessible) and automatically activated by the auxiliary alarm system (auxiliary box). The master box is typically located outside on a pole or building.

A.27.6.1.4 If the operating mechanism of a box creates sufficient sound to be heard by the user, the requirements are satisfied.

A.27.6.2 Publicly accessible alarm boxes were commonly referred to as “street boxes” in previous editions of the Code. Applications of these boxes are no longer limited to street locations.

A.27.6.2.1.6 Where the intent is for complete coverage, it should not be necessary to travel in excess of one block or 500 ft (150 m) to reach a box. In residential areas, it should not be necessary to travel in excess of two blocks or 800 ft (240 m) to reach a box.

A.27.6.2.1.10 The current supply for designating lights at boxes should be secured at lamp locations from the local electric utility company.




FIGURE A.27.5.5.1.4 Repeater Wireless Network/System.

Alternating-current power can be permitted to be superimposed on metallic fire alarm circuits for supplying designating lamps or for control or activation of equipment devices for fire alarm or other emergency signals, provided that the following conditions exist:

- (1) Voltage between any wire and ground or between one wire and any other wire of the system does not exceed 150 volts, and the total resultant current in any line circuit does not exceed $\frac{1}{4}$ ampere.
- (2) Components such as coupling capacitors, transformers, chokes, or coils are rated for 600-volt working voltage and have a breakdown voltage of at least twice the working voltage plus 1000 volts.
- (3) There is no interference with fire alarm service under any conditions.

A.27.6.2.1.11.2 Environmental and ambient conditions should be considered in the selection of the wiring method to be employed.

A.27.6.3.1.2 Environmental and ambient conditions should be considered in the selection of the wiring method to be employed.

A.27.6.3.1.3 Figure A.27.6.3.1.3 shows the interconnecting wiring that is intended to meet Level 2 survivability.

A.27.6.3.2.2.1 The local energy-type system [see Figure A.27.6.3.2.2.1(a) and Figure A.27.6.3.2.2.1(b)] is electrically isolated from the public emergency alarm reporting system and has its own power supply. The tripping of the transmitting device does not depend on the current in the system. In a wired circuit, receipt of the alarm by the communications center when the circuit is accidentally opened depends on the design of the transmitting device and the associated communications center equipment (i.e., whether or not the system is designed to receive alarms through manual or automatic ground operational facilities). In a radio box-type system, receipt of the alarm by the communications center depends on the proper operation of the radio transmitting and receiving equipment.

A.27.6.6.2 The transmission of an actual emergency-related message, initiated at the same time it is preselected for a test message, and, in turn, preempts said test message, must satisfy the intent of 27.6.6.2.

A.27.6.6.7 Examples of priority levels as follows:

- (1) Priority 1 — fire
- (2) Priority 2 — ECS
- (3) Priority 3 — medical
- (4) Priority 4 — supervisory
- (5) Priority 5 — monitored for integrity signals




FIGURE A.27.6.3.1.3 Interconnecting Wiring from Auxiliary Alarm System to Auxiliary Box or Master Box Installed in Rigid Metal Conduit, Intermediate Metal Conduit, or Electrical Metallic Tubing.




FIGURE A.27.6.3.2.2.1(a) Local Energy-Type Auxiliary Alarm System — Radio or Wired.




FIGURE A.27.6.3.2.2.1(b) Local Energy-Type Auxiliary Alarm System with Supply and Alarm Relay — Radio or Wired.

- (6) Priority 6 — tamper
- (7) Priority 7 — test

Additionally, within each signal category, additional priorities can be required such as Fire 1, Fire 2, Fire 3, and so forth.

A.27.7.1.6.2 There could be environmental conditions that necessitate the use of rigid nonmetallic conduit.

A.27.7.3 All requirements for circuit protection do not apply to coded radio reporting systems. These systems do not use metallic circuits.

A.27.8.1 The public emergency alarm reporting system infrastructure can be used to facilitate the operation of wide-area signaling, which might include voice, and which some communities now use for emergency notifications to the public.

A.29.1.1 This chapter provides a number of requirements related to fire warning equipment and carbon monoxide warning equipment that are deemed to be the practical and necessary minimum for average conditions at the present state of the art.

Chapter 29 does not attempt to cover all equipment, methods, and requirements that might be necessary or advantageous for the protection of lives and property from fire.

Smoke alarms in compliance with the 8th edition of UL 217, *Smoke Alarms*, and the 7th edition of UL 268, *Smoke Detectors for Fire Alarm Systems*, have passed a new performance test to help

reduce nuisance alarms from normal cooking. This end-product performance and listing requirement aligns with 29.11.3.4(6) of this Code. Smoke alarms complying with these UL standards will be listed “for resistance to common nuisance sources from cooking” and are suitable for installation at distances from cooking appliances outlined in this Code.

The technologies used in smoke alarms and detectors manufactured prior to the effective date of the new standards include ionization smoke detection and photoelectric smoke detection. These detection types are defined in 3.3.285.2 and 3.3.285.4 and are further explained in A.3.3.287.2 and A.3.3.287.4. Ionization smoke detection is more responsive to invisible particles produced by most flaming fires. Photoelectric smoke detection is more responsive to the visible particles produced by most smoldering fire.

A.29.1.2 An example of the applicable code within the NFPA set of codes and standards is NFPA 101. Other codes such as local building codes are other examples to be considered.

The requirements of Chapter 29 are intended to apply to installations in the following new and existing locations:

- (1) One- and two-family dwelling units
- (2) Sleeping rooms of lodging and rooming houses
- (3) Individual dwelling units of apartment buildings
- (4) Guest rooms, sleeping rooms, and living areas within guest suites of hotels and dormitories
- (5) Day-care homes
- (6) Residential board and care facilities
- (7) Other locations where applicable laws, codes, or standards specify a requirement for the installation of smoke alarms

A.29.1.4 Installations in manufactured homes are under the jurisdiction of the Department of Housing and Urban Development (HUD). The rules for installation are addressed in the Federal Manufactured Housing Construction Safety Standards (available at <https://www.hud.gov>).

A.29.2 *Fire Danger in the Home.* In 2009, fire was the third leading cause of unintentional injury deaths in the home and the sixth leading cause of unintentional injury deaths overall (*Injury Facts*, 2011, National Safety Council).

Seventy-nine percent of the fire fatalities in 2015 resulted from residential fires — 82.7 percent resulted from fires in one- and two-family dwellings, including manufactured homes; 15.5 percent were caused by apartment fires; and 1.7 percent resulted from fires in other residential occupancies (“Fire Loss in the United States during 2015,” Hylton J.G. Haynes, NFPA Fire Analysis and Research Division).

Approximately half (52 percent) of the home (dwellings and apartments) fire fatalities resulted from fires reported between 11:00 p.m. and 7:00 a.m., the common sleeping hours (“Home Structure Fires,” Marty Ahrens, NFPA Fire Analysis and Research Division, September 2016).

Almost three-quarters (71 percent) of all reported fire injuries occurred in the home, with more than one-half (73 percent) in one- and two-family dwelling units (including manufactured housing), and more than one-fifth (27 percent) apartments (“Fire Loss in the United States During 2015,” Hylton J.G. Haynes, NFPA Fire Analysis and Research Division).

It is estimated that each household will experience five (usually unreported) fires per lifetime and one in four fires

serious enough to report to a fire department per lifetime (“A Few Facts at the Household Level,” NFPA Fire Analysis Division, July 2009).

Fire Safety in the Home. NFPA 72 is intended to provide reasonable safety for persons in family living units. Reasonable fire safety can be produced through the following three-point program:

- (1) Minimizing fire hazards
- (2) Providing fire-warning equipment
- (3) Having and practicing an escape plan

Minimizing Fire Hazards. This Code cannot protect all persons at all times. For instance, the application of this Code might not provide protection against the following three traditional fatal fire scenarios:

- (1) Smoking in bed
- (2) Leaving children home alone
- (3) Cleaning with flammable liquids such as gasoline

However, Chapter 29 can lead to reasonable safety from fire when the three-point program is observed.

Fire-Warning Equipment. There are two types of fire to which household fire-warning equipment needs to respond. One is a rapidly developing, high-heat fire. The other is a slow, smoldering fire. Either can produce smoke and toxic gases.

Family Escape Plan. There is often very little time between the detection of a fire and the time it becomes deadly. This interval can be as little as 1 or 2 minutes. Thus, this Code requires detection means to give a family some advance warning of the development of conditions that become dangerous to life within a short period of time. Such warning, however, could be wasted unless the family has planned in advance for rapid exit from their residence. Therefore, in addition to the fire-warning equipment, this Code assumes that the residents have developed and practiced an exit plan.

Planning and practicing for fire conditions with a focus on rapid exit from the residence are important. Drills should be held so that all family members know the action to be taken. Each person should plan for the possibility that exit out of a bedroom window could be necessary. An exit out of the residence without the need to open a bedroom door is essential.

Household fires are especially dangerous at night when the occupants are asleep. Fires produce smoke and deadly gases that can overcome occupants while they are asleep. Furthermore, dense smoke reduces visibility. Most fire casualties are victims of smoke and gas inhalation rather than burns. To warn against a fire, Chapter 29 provides smoke detector (alarm) requirements in accordance with 29.8.1, and the associated annex recommends heat or smoke detectors (alarms) in all other major areas.

A.29.3.1 Terms used by testing laboratories for equipment that is listed or labeled under the definitions of this Code could include certified, approved, listed, recognized, and so forth.

A.29.3.3 This Code establishes minimum standards for the use of fire-warning equipment. The use of additional alarms or detectors over and above the minimum standard is encouraged. The use of additional devices can result in a combination of equipment (e.g., a combination of single- and multiple-station alarms or a combination of smoke alarms or smoke detectors that are part of a security/fire system and existing

multiple-station alarms). Though a combination is allowed, one type of equipment must independently meet the requirements of the Code. Compliance with the requirements of the Code cannot rely on the combination of the following fire-warning equipment:

- (1) Single-station alarms
- (2) Multiple-station alarms
- (3) Household fire alarm system (includes a security/fire system with smoke alarms or smoke detectors)

It is encouraged that the highest level of protection be used where possible. For example, if multiple-station alarms are added to an occupancy with compliant single-station alarms, the multiple-station alarms should be installed to replace all of the single-station alarms. Similarly, if a monitored household fire alarm system is added to a house that has compliant multiple-station alarms, monitored smoke alarms or smoke detectors should be installed to replace the multiple-station alarms or be installed to provide the same required coverage.

A.29.5.1 The use of the distinctive three-pulse temporal pattern fire alarm evacuation signal has been recommended by this Code since 1979. It has since been adopted as both an American National Standard [ANSI/ASA S3.41, *Audible Emergency Evacuation (E2) and Evacuation Signals with Relocation Instructions (ESRI)*] and an International Standard (ISO 8201, *Alarm systems — Audible emergency evacuation signal*).

These standards are available at

<https://webstore.ansi.org/>.

The standard fire alarm evacuation signal is a three-pulse temporal pattern using any appropriate sound. The pattern consists of the following in this order:

- (1) An “on” phase lasting 0.5 second ± 10 percent.
- (2) An “off” phase lasting 0.5 second ± 10 percent for three successive “on” periods.
- (3) An “off” phase lasting 1.5 seconds ± 10 percent [see Figure A.29.5.1(a) and Figure A.29.5.1(b)]. The signal should be repeated for a period appropriate for the purposes of evacuation of the building, but for not less than 180 seconds. A single-stroke bell or chime sounded at “on” intervals lasting 1 second ± 10 percent, with a 2-second ± 10 percent “off” interval after each third “on” stroke, is permitted [see Figure A.29.5.1(c)].

The minimum repetition time is permitted to be manually interrupted.

A.29.5.4 The four-pulse temporal (T4) pattern is illustrated in Figure A.29.5.4.




FIGURE A.29.5.1(a) Temporal Pattern Parameters.




FIGURE A.29.5.1(b) Temporal Pattern Imposed on Signaling Appliances That Emit Continuous Signal While Energized.




FIGURE A.29.5.1(c) Temporal Pattern Imposed on Single-Stroke Bell or Chime.

A.29.5.5 It is recommended that the voice notification message be intelligible, audible, and appropriate for the hazard. Care should be taken to avoid excessive silence during the message. Figure A.29.5.5(a) through Figure A.29.5.5(c) provide examples of acceptable combinations of the emergency evacuation signal and voice messages.

A.29.5.6 Temporal pattern parameters with voice allowance are shown in Figure A.29.5.6(a), Figure A.29.5.6(b), and Figure A.29.5.6(c).

A.29.5.8 Low frequency or tactile notification appliances such as bed shakers have been shown to be effective in waking those with normal hearing to profound hearing loss [CSE NIH report, 2005; Bruck and Thomas, 2009; Bruck, Thomas, and Ball, NFPA RF report, 2007].

A.29.5.10.1 As an example, governing laws, codes, or standards might require a certain number of accommodations be equipped for those with hearing loss or other disability.

A.29.5.10.1(2) It is not the intent of this section to preclude devices that have been demonstrated through peer-reviewed research to awaken occupants with hearing loss as effectively as those using the frequency and amplitude specified in this section.

A.29.5.10.2 Tactile notification appliances such as bed shakers have been shown to be effective in waking those with normal hearing to profound hearing loss [Ashley et al., 2005, UL 1971, 2018]. Tactile signaling has been studied and found to be an effective way to alert and notify sleeping persons. However, there are many variables that have not been tested that might affect the reliability of their performance. Some of the appliance variables include the mass of the appliance, frequency of vibration, and the throw or displacement of the vibrating mass. Occupant variables that might affect the reporting of test results and the effectiveness of the appliance include the person's age, how long a person has lived with their hearing loss, and what sleep stage the person is experiencing when the appliance operates. The type of mattress might also have an effect of the performance of certain tactile appliances. Mattress variables can include thickness, firmness, memory foam, pillow tops, water beds, air beds, and motion isolation mattresses.




FIGURE A.29.5.4 Four-Pulse Temporal Pattern.




FIGURE A.29.5.5(a) Temporal Pattern Parameters with Eight T3 Cycles Minimum with 10-Second Voice Allowance.

Users of tactile appliances should be cautioned to test how well they might sense the effect of the appliance.

The Code requires both visual notification appliances and tactile appliances. Visual notification appliances can awaken sleeping persons, provide verification that there is a fire alarm condition, and serve to alert persons when they are not in contact with a tactile appliance.

A.29.5.10.2(1) As an example, governing laws, codes, or standards might require a certain number of accommodations be equipped for those with hearing loss or other disability.

A.29.6.1 Working smoke alarms cut the risk of dying in reported home structure fires in half. Victims who are intimate with the fire or are incapable of taking action to escape might not benefit from the early warning. For these people, other strategies such as protection in-place or assisted escape or rescue would be necessary.

A.29.6.2 Family Escape Plan. There often is very little time between the detection of a fire and the time it becomes deadly. This interval can be as little as 1 or 2 minutes. Thus, this Code requires detection means to give a family some advance warning of the development of conditions that become dangerous to life within a short period of time. Such warning, however, could be wasted unless the family has planned in advance for rapid exit from their residence. Therefore, in addition to the fire-warning equipment, this Code requires exit plan information to be furnished.

Planning and practicing for fire conditions with a focus on rapid exit from the residence are important. Drills should be




FIGURE A.29.5.5(b) T3 Temporal Pattern Parameters with 1.5-Second Voice Allowance.

held so that all family members know the action to be taken. Each person should plan for the possibility that exit out of a bedroom window could be necessary. An exit out of the residence without the need to open a bedroom door is essential.

Special Provisions for the Disabled. For special circumstances where the life safety of an occupant(s) depends on prompt rescue by others, the fire-warning equipment should include means of prompt automatic notification to those who are to be depended on for rescue.

Alarm initiation — eight T3 cycles minimum. Optional voice allowed in any T3 cycle.								Two T3 cycles minimum — repeat as desired.		
T3 cycle with voice	T3 cycle with voice	T3 cycle with voice	T3 cycle with voice	T3 cycle with voice	T3 cycle with voice	T3 cycle with voice	T3 cycle with voice	Voice — 10-sec maximum	T3 cycle with voice	T3 cycle with voice
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)		(1)	(2)

FIGURE A.29.5.5(c) Temporal Pattern Parameters with 10-Second Voice Allowance in Any T3 Cycle.

Alarm initiation — Six T4 cycles (30 seconds minimum)						Two T4 cycles minimum — repeat as desired		
T4 cycle	T4 cycle	T4 cycle	T4 cycle	T4 cycle	T4 cycle	Voice — 10-seconds maximum	T4 cycle	T4 cycle
(1)	(2)	(3)	(4)	(5)	(6)		(1)	(2)

FIGURE A.29.5.6(a) Temporal Pattern Parameters with Six T4 Cycles with 10-second Voice Allowance.




FIGURE A.29.5.6(b) T4 Temporal Pattern Parameters with 1.5-second Voice Allowance.

Alarm initiation — Six T4 cycles minimum. Optional voice allowed in any T4 cycle.						Two T4 cycles minimum — repeat as desired		
T4 cycle with voice	T4 cycle with voice	T4 cycle with voice	T4 cycle with voice	T4 cycle with voice	T4 cycle with voice	Voice — 10-second maximum	T4 cycle with voice	T4 cycle with voice

FIGURE A.29.5.6(c) Temporal Pattern Parameters with 10-second Voice Allowance in Any T4 Cycle.

A.29.6.2.3 The normal path of egress does not include windows or other means of escape.

A.29.6.3 Assumptions — equipment is as follows:

- (1) Maintenance. Good fire protection requires that the equipment be maintained periodically. If the system owner or responsible party is unable to perform the required maintenance, a maintenance agreement should be considered.
- (2) Reliability of fire alarm systems. Fire alarm systems located in dwelling units and having all of the following features are considered to have a functional reliability of 95 percent:
 - (a) Utilizes a control unit
 - (b) Has at least two independent sources of operating power
 - (c) Monitors all initiating and notification circuits for integrity
 - (d) Transmits alarm signals to a constantly attended, remote monitoring location
 - (e) Is tested regularly by the homeowner and at least every 3 years by a qualified service technician
- (3) Reliability of fire alarm systems without remote monitoring or with wireless transmission. Fire alarm systems for dwelling units with all of the preceding features except (d) or systems that use low-power wireless transmission from initiating devices within the dwelling units are considered to have a functional reliability of 90 percent.
- (4) Reliability of other systems. Fire alarm systems for dwelling units comprised of interconnected smoke alarms where the interconnecting means is monitored for integrity are considered to have a functional reliability of 88 percent. If the interconnecting means is not supervised or the alarms are not interconnected, such systems are considered to have a functional reliability of 85 percent.

A.29.7 Hazardous concentrations of carbon monoxide can accumulate in a residence, generally from improperly operating heating appliances, insufficient make-up air into the residence or space, or blocked chimneys or vents. However, there are many other potential sources of carbon monoxide within a home, including, but not limited to, the following:

- (1) Malfunctioning fossil fuel-burning appliances
- (2) Wood stoves
- (3) Fireplaces
- (4) Idling automobiles in attached garages
- (5) Portable equipment such as gasoline-powered lawn and garden equipment and electric power generators
- (6) Barbecues

Carbon monoxide is odorless, tasteless, and colorless; therefore, its presence is undetectable by smell, taste, or sight. Carbon monoxide can be mixed and migrate throughout a residence through the HVAC system. Carbon monoxide alarms meeting the requirements of UL 2034, *Single and Multiple Station Carbon Monoxide Alarms*, carbon monoxide detectors meeting the requirements of UL 2075, *Safety Gas and Vapor Detectors and Sensors*, and installed in accordance with this standard should provide a significant level of protection against fatal carbon monoxide exposure.

The installation of additional carbon monoxide alarms could result in a higher degree of protection. Adding alarms to rooms where fuel-burning appliances are located could provide

earlier warning of carbon monoxide hazards caused by those sources. Additional alarms located in rooms normally closed off from the required alarms could increase the escape time, since the carbon monoxide concentration needed to force the carbon monoxide out of the closed rooms to the alarms would not be necessary. As a consequence, the installation of additional carbon monoxide alarms should be considered.

Carbon monoxide alarms or detectors are not substitutes for proper maintenance, inspection, and testing of fuel-burning equipment. Fuel-burning equipment and appliances should be used, maintained, tested, and inspected according to the manufacturers' instructions.

Carbon monoxide detectors/alarms are cross sensitive to hydrogen, an explosive gas that can be given off by recharging lead acid batteries. Where households include recharging stations (e.g., for golf carts), the alarm should be located away from the recharging location.

A.29.7.1.1 Where sleeping areas are separated and the audibility of the alarm or detector to occupants within each sleeping area could be seriously impaired, more than one unit could be needed.

At times, depending on conditions, the audibility of notification appliances could be seriously impaired when occupants are in the bedroom area. For instance, there might be a noisy window air conditioner or room humidifier generating an ambient noise level of 55 dBA or higher. The detection device alarms need to penetrate through the closed doors and be heard over the bedroom's noise levels with sufficient intensity to awaken sleeping occupants. Test data indicate that alarms with ratings of 85 dBA at 3 m (10 ft) that are installed outside the bedrooms can produce about 15 dBA over ambient noise levels of 55 dBA in the bedrooms. This sound pressure is likely to be sufficient to awaken the average sleeping person.

Alarms or detectors located remote from the bedroom area might not be loud enough to awaken the average person. In such cases, it is recommended that units be interconnected in such a way that the operation of the remotely located detector or alarm causes an alarm of sufficient intensity to penetrate the bedrooms. The interconnection can be accomplished by the following:

- (1) Installation of a system
- (2) Wiring together of multiple-station alarms
- (3) Use of line carrier or radio frequency transmitters/receivers
- (4) Adding supplemental notification appliances

A.29.7.1.2 The location for effective performance is not generally dependent on mounting height. The density of carbon monoxide is similar to that of air at room temperature, and carbon monoxide generally mixes readily with air.

A.29.8.1 All hostile fires in dwelling units generate smoke and heat. However, the results of full-scale experiments conducted over the last several decades in the United States, using typical fires in dwelling units, indicate that detectable quantities of smoke precede detectable levels of heat in nearly all cases (NBS GCR 75-51, *Detector Sensitivity and Siting Requirements for Dwellings*, 1975; NBS GCR 77-82, *Detector Sensitivity and Siting Requirements for Dwellings Phase 2*, 1977; and NIST Technical Note 1455-1, *Performance of Home Smoke Alarms, Analysis of the Response of Several Available Technologies in Residential Fire Settings*, 2008). In addition, slowly developing, smoldering fires can produce

smoke and toxic gases without a significant increase in the room's temperature. Again, the results of experiments indicate that detectable quantities of smoke precede the development of hazardous thermal atmospheres in nearly all cases.

For the preceding reasons, the required protection in this Code utilizes smoke alarms as the primary life safety equipment for providing a reasonable level of protection against fire.

The installation of additional alarms of either the smoke or heat type should result in a higher degree of protection. Adding alarms to rooms that are normally closed off from the required alarms increases the escape time because the fire does not need to build to the higher level necessary to force smoke out of the closed room to the required alarms. As a consequence, it is recommended that the householder consider the installation of additional fire protection devices. However, it should be understood that Chapter 29 does not require additional smoke alarms over and above those called for in 29.8.1. Refer to Figure A.29.8.1(a) through Figure A.29.8.1(d) where required smoke alarms are shown.

Where to Locate the Required Smoke Alarms. Fifty-three percent of home fire deaths were reported between 11:00 p.m. and 7:00 a.m. Persons in sleeping areas can be threatened by fires in the remainder of the unit; therefore, smoke alarms are best located in each bedroom and between the bedroom areas and the rest of the unit as shown in Figure A.29.8.1(b). In dwelling units with more than one bedroom area or with bedrooms on more than one floor, more than one smoke alarm is required, as shown in Figure A.29.8.1(c).

In addition to smoke alarms outside of the sleeping areas and in each bedroom, Chapter 29 requires the installation of a smoke alarm on each additional level of the dwelling unit, including the basement. These installations are shown in Figure A.29.8.1(d). The living area smoke alarm should be installed in the living room or near the stairway to the upper level, or in both locations. The basement smoke alarm should be installed in close proximity to the stairway leading to the floor above. Where installed on an open-joisted ceiling, the smoke alarm should be placed on the bottom of the joists. The smoke alarm should be positioned relative to the stairway so as to intercept smoke coming from a fire in the basement before the smoke enters the stairway.

Are More Smoke Alarms Desirable? The required number of smoke alarms might not provide reliable early warning protection for those areas separated by a door from the areas protected by the required smoke alarms. For this reason, the use of additional smoke alarms for those areas for increased protection is recommended. The additional areas include dining room, furnace room, utility room, and hallways not protected by the required smoke alarms. The installation of smoke alarms in kitchens, attics (finished or unfinished), or garages is not normally recommended, because these locations occasionally experience conditions that can result in improper operation.

A.29.8.1.1 Occupancies where smoke alarms are typically required include residential, residential board and care, or day-care home. The term *residential occupancy* is defined in 3.3.260 and includes one- and two-family dwellings; lodging or rooming houses; hotels, motels, and dormitories; and apartment buildings. The term *residential board and care occupancy* is defined in 3.3.259 and includes both small and large facilities. NFPA 101 specifies a small facility to be one with sleeping accommodations for not more than 16 residents. The term *day-*




FIGURE A.29.8.1(a) Split Level Arrangement.




FIGURE A.29.8.1(b) Smoke Alarm Should Be Located Between Sleeping Area and Rest of Dwelling Unit, as Well as in Each Bedroom.




FIGURE A.29.8.1(c) In Dwelling Units with More Than One Sleeping Area, Smoke Alarm Should Be Provided to Protect Each Sleeping Area in Addition to Smoke Alarms Required in Bedrooms.

care home, defined in 3.3.71, is a specific category of day-care occupancy. It should be noted that applicable laws, codes, or standards might include conditions that could impact the applicability of these requirements. The local authority should be consulted for specific details.

A.29.8.1.1(1) The term *sleeping room* applies to several occupancies including: one- and two-family dwellings; lodging or rooming houses; hotels, motels, and dormitories; apartment buildings; residential board and care facilities; and day-care homes. The term *guest room*, defined in 3.3.133, is an accommodation that includes sleeping facilities. It applies in the context of hotel and dormitory occupancies.

A.29.8.1.1(2) The term *dwelling unit* is defined in 3.3.90 and applies to one- and two-family dwellings and dwelling units of apartment buildings (including condominiums). The distance referenced for the location of the required smoke alarm should be measured on a horizontal projection of the ceiling and along the path of egress travel by an occupant.




FIGURE A.29.8.1(d) Smoke Alarm Should Be Located on Each Level in Addition to Each Bedroom.

A.29.8.1.1(5) The term *guest suite* is defined in 3.3.134, and the term *living area* is defined in 3.3.159.

A.29.8.1.3.1 The distance referenced for the spacing of smoke alarms should be measured on a horizontal projection of the ceiling. One smoke alarm per 500 ft² (46 m²) is evaluated by dividing the total interior square footage of floor area per level by 500 ft² (46 m²). The requirements do not preclude the installation of smoke alarms on walls in accordance with 29.11.3.3. Some building configurations, such as division of rooms and open foyers or great rooms, dictate that alarms be located so that they do not cover distinctly separate 500 ft² (46 m²) areas but rather provide overlapping coverage relative to this spacing requirement.

A.29.8.2.1.1 As of the 2007 edition of *NEPA 72*, the Code required the interconnection of alarms for both new and existing construction. The introduction of wireless interconnect smoke alarms allows installation of interconnect devices in existing construction without the need for ac wiring modifications that once were required to retrofit interconnected alarms. Work by the U.S. Consumer Product Safety Commission (CPSC) has concluded that interconnection of alarms is an important factor that can affect proper notification and life safety [1, 2]. The CPSC study shows that interconnected smoke alarms alerted residents to the fire more than twice as often as noninterconnected alarms. A Victoria University study [3] also emphasizes the need for interconnected alarms. The study indicates that interconnected smoke alarms in every room in every dwelling would lead to about 50 percent fewer fatalities.

- (1) Green, M. A., and Andres, C. "2004-2005 National Sample Survey of Unreported Residential Fires." CPSC, 2009.
- (2) Ahrens, M. "Factors in Smoke Alarm Performance." National Fire Protection Association. December 2009.
- (3) Thomas, I., and Bruck, D. "Smoke Alarms in Dwellings: Timely Activation and Effective Notification." Victoria University. June 2010.

A.29.8.2.2 One of the common problems associated with smoke alarms and detectors is the nuisance alarms that are usually triggered by products of combustion from cooking, smoking, or other household particulates. While an alarm for

such a condition is anticipated and tolerated by the occupant of a dwelling unit through routine living experience, the alarm is not permitted where it also sounds alarms in other dwelling units or in common use spaces. Nuisance alarms caused by cooking are a very common occurrence, and inspection authorities should be aware of the possible ramifications where the coverage is extended beyond the limits of the dwelling unit.

A.29.9.4(3) Restraining means are not intended to be used where the detector or alarm is designed to be plugged directly into a receptacle without a cord.

A.29.10.2 The UL listing for smoke alarms addresses two categories of these devices: one for applications where sensitivity testing is not required (UTGT), and one for applications where sensitivity testing is required (UTHA). Refer to the testing requirements for these devices in Chapter 14.

A.29.10.3.1 UL 2034, *Single and Multiple Station Carbon Monoxide Alarms*, includes a level below which the alarm should not respond.

A.29.10.4 The linear space rating is the maximum allowable distance between heat detectors. The linear space rating is also a measure of detector response time to a standard test fire when tested at the same distance. A higher rating corresponds to a faster response time. This Code recognizes only those heat detectors with ratings of 50 ft (15.2 m) or more.

A.29.10.4.2 A heat detector with a temperature rating somewhat in excess of the highest normally expected ambient temperature is specified in order to avoid the possibility of premature response of the heat detector to non-fire conditions.

Some areas or rooms of the dwelling unit can experience ambient temperatures considerably higher than those in the normally occupied living spaces. Examples are unfinished attics, the space near hot air registers, and some furnace rooms. This fact should be considered in the selection of the appropriate temperature rating for fixed-temperature heat detectors to be installed in these areas or rooms.

A.29.10.6.2 Listed household fire alarm systems have a means to allow users to cancel or abort an actuate fire alarm signal when they know it is an unwanted alarm.

A.29.10.7.8 Such input and output devices include, but are not limited to, relay modules, notification appliances, phone dialers, system control units, heat detectors, and manual fire alarm boxes.

A.29.10.8.2.4 Receiving units that stay in alarm for 30 seconds or 1 minute longer than the transmitting alarm would provide additional protection if the first alarm is damaged due to a very fast growing fire. The persisting alarm signal would provide additional notification to occupants. This option needs to be considered in light of the potential for the longer alarm signals on receiving smoke alarms being a potential nuisance to occupants during test and other nuisance alarm events.

A.29.10.9.1 *NEPA 72* does not require single- and multiple-station alarms and household alarm systems to send signals off-premises. However, if such supervision is elected by the owner or required by some other governing laws, codes, or standards, this section requires that it be done in accordance with other parts of this Code, except as noted.

A.29.10.9.2 Upon receipt of a carbon monoxide alarm signal, supervising station personnel should perform the following actions in the order listed:

- (1) Where required by the emergency response agency, immediately retransmit indication of the carbon monoxide alarm signal to the communications center.
- (2) The immediate retransmission should be permitted to be delayed by not more than 90 seconds where the jurisdiction permits the supervising station to first contact the protected premises to determine if the alarm was initiated by the activation of a test.
- (3) Contact the responsible party(s) in accordance with the notification plan.
- (4) Once contacted, the subscriber should be informed to take action in accordance with the manufacturer's published instructions, or where the manufacturer's published instructions are not available, the subscriber should be advised to take the following actions:
 - (a) Immediately move to fresh air, either outdoors or by an open door or window.
 - (b) Verify that all occupants are accounted for.
 - (c) Do not reenter the premises or move away from an open door or window until the emergency service responders have arrived, the premises have been aired out, and the alarm remains in its normal condition.

A.29.10.9.7 Where 29.10.9.7, which provides for screening alarm signals to minimize response to false alarms, is to be implemented, the following should be considered:

- (1) Was the verification call answered at the protected premises?
- (2) Did the respondent provide proper identification?
- (3) Is it necessary for the respondent to identify the cause of the alarm signal?
- (4) Should the public service fire communications center be notified and advised that an alarm signal was received, including the response to the verification call, when an authorized respondent states that fire service response is not desired?
- (5) Should the public service fire communications center be notified and advised that an alarm signal was received, including the response to the verification call, for all other situations, including both a hostile fire and no answer to the verification call?
- (6) What other actions should be required by a standard operating procedure?

A.29.10.10.1 All control units that use IP or cellular communication to transmit off-site or have devices that are connected wirelessly have an increased risk and should be designed for cybersecurity as determined by the manufacturer. The cybersecurity should comply with, but not be limited to, one of the following:

- (1) ANSI/ISA-62443, *Security for Industrial Automation and Control Systems Series*
- (2) NIST *Framework for Improving Critical Infrastructure Cybersecurity*
- (3) UL 2900-1, *Software Cybersecurity for Network-Connectable Products, Part 1: General Requirements*
- (4) UL 2900-2-3, *Software Cybersecurity for Network-Connectable Products, Part 2-3: Particular Requirements for Security and Life Safety Signaling Systems*
- (5) Other published cybersecurity standards

A.29.10.10.4 IP or cellular communication increases the risk of attack, damage, or unauthorized access to the alarm or connected network. Any alarm that uses this type of communication should be designed for cybersecurity as determined by the manufacturer. While no alarm that uses these communications can be impervious to attacks, the manufacturer should consider cybersecurity during the design process.

A.29.11.2.1 Once these limits have been exceeded, a household fire alarm and/or carbon monoxide detection system should be installed.

A.29.11.3 One of the most critical factors of any fire alarm system is the location of the fire detecting devices. This annex is not a technical study. It is an attempt to provide some fundamentals on fire-warning equipment location. For simplicity, only those types of alarms or detectors recognized by Chapter 29 (e.g., smoke and heat alarms or smoke and heat detectors) are discussed. Specific mounting locations of fire-warning equipment in unoccupied or architecturally unique areas (e.g., as in attics or in rooms with high ceilings) should be evaluated by a qualified professional.

The conclusions of the Kemano Fire Studies (2003) and FPRF Smoke Detector Spacing Requirements Report (2008) have determined revisions to smoke alarm and smoke detector mounting within 4 in. (100 mm) of a flat ceiling/wall corner are now acceptable. The studies have shown that acceptable detection performance does not depend on the 4 in. (100 mm) separation. Figure A.29.11.3 illustrates acceptable smoke alarm and smoke detector mounting locations.

A.29.11.3.1 Figure A.29.11.3.1 illustrates acceptable smoke alarm or smoke detector mounting locations for a peaked ceiling.

A.29.11.3.2 Figure A.29.11.3.2 illustrates acceptable smoke alarm or smoke detector mounting locations for a sloped ceiling.




FIGURE A.29.11.3 Example of Proper Mounting for Smoke Alarms and Smoke Detectors.

A.29.11.3.3 Figure A.29.11.3 illustrates acceptable smoke alarm or smoke detector mounting locations.

In those dwelling units employing radiant heating in the ceiling, the wall location is the recommended location. Radiant heating in the ceiling can create a hot air boundary layer along the ceiling surface, which can seriously restrict the movement of smoke and heat to a ceiling-mounted detector.

A.29.11.3.4(3) Smoke detectors and smoke alarms should be installed in those locations recommended by the manufacturer's published instructions, except in those cases where the space above the ceiling is open to the outside and little or no insulation is present over the ceiling. Such cases result in the ceiling being excessively cold in the winter or excessively hot in the summer. Where the ceiling is significantly different in temperature from the air space below, smoke and heat have difficulty reaching the ceiling and a detector that is located on that ceiling.

A.29.11.3.4(4) As per annex material located in A.29.8.1, it is not normally recommended that smoke alarms or smoke detectors be placed in kitchen spaces. This section of the code provides guidelines for safe installation if a need exists to install a smoke alarm or smoke detector in a residential kitchen space or cooking area.

Within this Code section, a fixed cooking appliance is any appliance that is intended to be permanently connected electrically to the wiring system or the fuel source. A stationary cooking appliance is any appliance that is intended to be fastened in place or located in a dedicated space, and is connected to the supply circuit or fuel source.




FIGURE A.29.11.3.1 Example of Proper Mounting for Alarms and Detectors with Peaked Ceilings.




FIGURE A.29.11.3.2 Example of Proper Mounting for Alarms and Detectors with Sloped Ceilings.

Smoke alarms and smoke detectors that are currently available to consumers are susceptible to particles released into the air during normal cooking procedures. If smoke alarms and smoke detectors are placed too close to the area where the cooking source originates, a high level of nuisance alarms can occur. Frequent nuisance alarms can result in an occupant disabling the smoke alarm or smoke detector.

Nuisance alarm studies show that commercially available residential smoke alarms and smoke detectors are susceptible to nuisance alarms when installed too close to cooking appliances. As the horizontal distance between the smoke alarm or smoke detectors and the cooking appliance increases, the frequency of nuisance alarms decreases. Smoke alarms or smoke detectors that use ionization smoke detection have been shown to be more susceptible to cooking nuisance alarms than those that use photoelectric smoke detection when the alarms or detectors are installed within 10 ft (3.0 m) along a horizontal smoke travel path from a cooking appliance. Smoke alarms or smoke detectors that use photoelectric smoke detection produce nuisance alarms when installed less than 10 ft (3.0 m) from a cooking appliance, though to a lesser degree.

The occurrence of the higher frequency of nuisance alarms observed in smoke alarms or smoke detectors that use ionization detection have been documented in the fire research data. Due to the differences in technology between ionization detection and photoelectric detection, the sensitivity typically used for ionization detection is much higher than that used for photoelectric detection. This sensitivity difference is a result of each type of the detection being required to satisfy UL 217 performance tests. Removing detection technology from consideration, the frequency of nuisance alarms is solely due to the sensitivity of the detection method used. Thus, both ionization and photoelectric detector technologies will produce nuisance alarms due to cooking, but currently available smoke alarms and smoke detectors that use ionization detection typically produce more cooking-related nuisance alarms.

The higher sensitivities of currently available smoke alarms and smoke detectors that use ionization detection do provide a benefit at the expense of a potentially higher rate of cooking-related nuisance alarms. Research has demonstrated that ionization detection will typically respond faster than photoelectric detection to flaming fires, providing earlier warning to occupants that might allow for quicker intervention or faster egress. In general, the installation of smoke alarms or smoke detectors that use ionization detection will result in increased fire safety at the risk of a higher frequency of nuisance alarms. The installation of smoke alarms or smoke detectors that use photoelectric detection will result in reduced fire safety for flaming fires and a reduced risk of nuisance alarms. Based on the trade-off between faster response to fires and the frequency of nuisance alarms, detectors that utilize both technologies (i.e., ionization, photoelectric, and a combination) are allowed to be installed between 10 ft (3.0 m) and 20 ft (6.1 m) along a horizontal flow path from a standard or fixed cooking appliance if the specific detector is equipped with an alarm silencing means or is of the photoelectric-type.

Nuisance alarm studies provide data on cooking nuisances that emanate from both fixed cooking appliances and stationary cooking appliances (e.g., stove, oven) as well as portable cooking appliances (e.g., toaster). Based on these studies, which demonstrate the potential of all cooking appliances to generate nuisance sources, a zone of exclusion has been speci-

fied surrounding each stationary or fixed cooking appliance. The purpose of this zone is to limit the installation of smoke alarms and detectors in areas where stationary, fixed, or portable cooking appliances will be located within the residential kitchen space such that potential nuisance alarms are minimized. The size of the zone of exclusion is specified to attempt to take into account the unknown and transitory locations of portable cooking appliances. This zone of exclusion is determined by measuring a 10 ft (3.0 m) radial distance from the closest edge of a stationary or fixed cooking appliance. The zone of exclusion is not intended to pass through walls or doorways. Figure A.29.11.3.4(4)(a) provides an example of the zone of exclusion in a generalized residential kitchen.

If other areas of this code require that a smoke alarm or smoke detector be placed within a horizontal flow path distance between 10 ft (3.0 m) and 20 ft (6.1 m) from a stationary or fixed cooking appliance, the following method should be used to determine the distance, and only photoelectric detection or smoke alarms/detectors with alarm silencing means can be installed in this area.

To install a smoke alarm or detector between 10 ft (3.0 m) and 20 ft (6.1 m) from the cooking appliance, an installer must first determine the 10 ft (3.0 m) area of exclusion. Once the area of exclusion is determined, an installer must then determine the horizontal flow distance. This is the horizontal distance along the ceiling from the closest edge of the cooking appliance to the smoke alarm or detector. The horizontal distance can consist of line segments due to impediments, such as interior partitions. Once an impediment is met, the measurement of the distance will then continue along the new horizontal path segment until the distance requirement is met or another impediment is encountered. Figure A.29.11.3.4(4)(b) provides an example for placement outside a kitchen in a nearby hallway. Figure A.29.11.3.4(4)(c) provides another example of appropriate placement outside of a kitchen in an adjacent room.

At a horizontal flow path distance of greater than 20 ft (6.1 m), any type of smoke alarm or smoke detector can be installed.

In rare cases, a residential dwelling can be of such size and configuration that an area of exclusion of 10 ft (3.0 m) from a stationary or fixed cooking appliance excludes the placement of a smoke alarm or smoke detector required by other areas of this Code. In these cases, a smoke alarm or smoke detector using photoelectric detection can be installed at least 72 in. (1.83 m) from the fixed or stationary cooking appliance. Figure A.29.11.3.4(4)(d) provides an example of this situation in practice where a smoke alarm or smoke detector is required outside of the sleeping area, but the space is in close proximity to the kitchen space.

In response to the above noted nuisance alarm studies, the 8th edition of UL 217, *Smoke Alarms*, and the 7th edition of UL 268, *Smoke Detectors for Fire Alarm Systems*, have added a new performance test to help reduce nuisance alarms from normal cooking. This end-product performance and listing requirement aligns with 29.11.3.4(6) of this Code. Smoke alarms complying with these UL standards will be listed "for resistance to common nuisance sources from cooking" and are suitable for installation at distances from cooking appliances outlined in this Code.




FIGURE A.29.11.3.4(4)(a) Example of Zone of Exclusion (gray area) Within Typical Residential Kitchen.

A.29.11.3.4(6) Studies indicate that smoke alarms and smoke detectors that use ionization detection, photoelectric detection, or a combination of ionization and photoelectric detection, are susceptible to nuisance alarms caused by steam. Some research has been done on the comparative response of these types of detection to steam. Steam particles, in general, are visible, reflect light easily, and are typically produced in a size range that has been shown to be more likely to actuate a photoelectric sensor (Dinaburg and Gottuk, 2015). Thus, it is required that smoke alarms and smoke detectors be installed greater than 36 in. (910 mm) from the bathroom door where possible. Increasing the distance between the smoke alarm or smoke detector and the bathroom door can reduce the frequency of nuisance alarms from bathroom steam. Frequent nuisance alarms can result in the occupant disabling the smoke alarm. Each incremental increase in separation, up to 10 ft (3.0 m), between the bathroom door and the smoke alarm or smoke detector is expected to reduce the frequency of nuisance alarms.

A.29.11.3.4(8) There are circumstances in which the placement of smoke alarms and detectors cannot physically meet the requirement to be 36 in. (910 mm) or further away from the tip of the fan blade. Consequently, there is an irreconcilable conflict in enforcing all siting requirements of this standard, so the requirement of 29.11.3.4(9) only applies where possible to allow compliance with this standard. A limited study (Gottuk and Gottuk 2015) has indicated that placing alarms closer than 36 in. (910 mm) is not expected to produce an unacceptable risk, and in some cases, could improve performance.

A.29.11.3.4(11) Figure A.29.11.3.4(11) illustrates acceptable smoke alarm or smoke detector mounting locations for tray-shaped ceilings.

A.29.11.4 While Chapter 29 does not require heat alarms or heat detectors as part of the basic protection scheme, it is recommended that the householder consider the use and placement of additional heat detectors for the same reasons presented under A.29.11.3. For example, additional heat alarms or heat detectors could be considered, but not limited to, the following areas: kitchen, dining room, attic (finished or




FIGURE A.29.11.3.4(4)(b) Example of Smoke Alarm or Smoke Detector Placement Between 10 ft (3.0 m) and 20 ft (6.1 m) Away in Hallway from Center of Stationary or Fixed Cooking Appliance.




FIGURE A.29.11.3.4(4)(c) Example of Smoke Alarm or Smoke Detector Placement Between 10 ft (3.0 m) and 20 ft (6.1 m) Away in Hallway from Center of Stationary or Fixed Cooking Appliance.

unfinished), furnace room, utility room, basement, and integral or attached garage.

The placement of the heat alarm or heat detector is critical where maximum speed of fire detection is desired. Thus, a logical location for a heat alarm or heat detector is the center of the ceiling. At this location, the heat alarm or heat detector is closest to all areas of the room.

A.29.11.4.1 Heat Alarm or Heat Detector Mounting — Dead Air Space. Heat from a fire rises to the ceiling, spreads out across the ceiling surface, and begins to bank down from the ceiling. The corner where the ceiling and the wall meet is an air space into which heat has difficulty penetrating. In most fires, this dead air space measures about 4 in. (100 mm) along the ceiling from the corner and about 4 in. (100 mm) down the wall as shown in Figure A.17.6.3.1.3.1. Heat alarm or heat detectors should not be placed in this dead air space.

A.29.11.4.2 Figure A.29.11.3.2 illustrates acceptable heat alarm or heat detector mounting locations for sloped ceilings.

A.29.11.4.4 Spacing of Detectors. Where a room is too large for protection by a single heat alarm or heat detector, multiple alarms or detectors should be used. It is important that they be properly located so all parts of the room are covered. (For further information on the spacing of detectors, see Chapter 17.)

Where the Distance Between Detectors Should Be Further Reduced. The distance between detectors is based on data obtained from the spread of heat across a smooth ceiling. Where the ceiling is not smooth, the placement of the heat alarm or heat detector should be tailored to the situation.

Figure A.17.6.3.1.3.1 illustrates acceptable heat alarms or heat detector mounting locations for smooth ceilings and side-walls.




FIGURE A.29.11.3.4(4)(d) Example of Exception Placement of Photoelectric Smoke Alarm or Smoke Detector at 72 in. (1.83 m) from Stationary or Fixed Cooking Appliance.

A.29.11.4.7 Refer to Figure A.29.11.4.7, where the distance between heat alarms or heat detectors should be further reduced.

For instance, with open wood joists, heat travels freely down the joist channels so that the maximum distance between the heat alarm or heat detectors [(50 ft) 15.2 m] can be used. However, heat has trouble spreading across the joists, so the distance in this direction should be one-half the distance allowed between detectors, as shown in Figure A.29.11.4.7, and the distance to the wall is reduced to 12.5 ft (3.8 m). Since one-half of 50 ft (15.2 m) is 25 ft (7.6 m), the distance between heat alarms or detectors across open wood joists should not exceed 25 ft (7.6 m), as shown in Figure A.29.11.4.7, and the distance to the wall is reduced [one-half of 25 ft (7.6 m)] to 12.5 ft (3.8 m). Paragraph 29.11.4.6 requires that a heat alarm or heat detectors be mounted on the bottom of the joists and not up in joist channels.

Walls, partitions, doorways, ceiling beams, and open joists interrupt the normal flow of heat, thus creating new areas to be protected.

In addition to the special requirements for heat detectors installed on ceilings with exposed joists, reduced spacing also might be required due to other structural characteristics of the protected area, possible drafts, or other conditions that could affect heat alarm or detector operation.

A.29.14.2.2(2) Actions that should be considered include opening windows and doors and evacuation. Also, the information should provide examples of organizations to be contacted for assistance.




FIGURE A.29.11.3.4(11) Locations Permitted for Smoke Alarms and Smoke Detectors on Tray-Shaped Ceilings.




FIGURE A.29.11.4.7 Open Joists, Attics, and Extra-High Ceilings are Some Areas that Require Special Knowledge for Installation.

Annex B Engineering Guide for Automatic Fire Detector Spacing

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

Users of Annex B should refer back to the text of NFPA 72 to familiarize themselves with the limitations of the design methods summarized herein.

Section B.2, and particularly B.2.2 and B.2.3, are largely based on the work of Custer and Meacham as found in "Performance-Based Fire Safety Engineering: An Introduction of Basic Concepts" (Meacham and Custer 1995) and Introduction to Performance-Based Fire Safety (Custer and Meacham 1997). [25]

The National Fire Protection Association and the Technical Committee on Initiating Devices for Fire Alarm Systems gratefully acknowledge the technical contributions of the Society of Fire Protection Engineers, Richard Custer, and Brian Meacham to performance-based design and this annex.

B.1 Introduction.

B.1.1 Scope. Annex B provides information intended to supplement Chapter 17. It includes a procedure for determining detector spacing based on the objectives set for the system, the size and growth rate of the design fire, the ceiling height, ambient temperature, and the response characteristics of the detectors. In addition to providing an engineering method for the design of detection systems using plume-dependent detectors, heat detectors, and smoke detectors, this annex also provides guidance on the use of radiant energy-sensing detectors.

B.1.2 General.

B.1.2.1 In the 1999 edition Annex B was revised in its entirety from previous editions. The correlations originally used to develop the tables and graphs for heat and smoke detector spacings in the earlier editions have been updated to be consistent with current research. These revisions correct the errors in the original correlations. In earlier editions, the tables and graphs were based on an assumed heat of combustion of 20,900 kJ/kg (8986 Btu/lb). The effective heat of combustion for common cellulosic materials is usually taken to be approximately 12,500 kJ/kg (5374 Btu/lb). The equations in this annex were produced using test data and data correlations for cellulosic (wood) fuels that have a total heat of combustion of about 12,500 kJ/kg (5374 Btu/lb).

B.1.2.2 In addition to the revisions undertaken in 1999, the concept of performance-based design was further expanded on. This included, to a large extent, additional material taken from the work of Custer and Meacham [25]. Since this time, the industry continues to develop additional codes, standards, and guides to further assist in undertaking a performance-based assessment. This includes the work of SFPE [40, 49], NFPA [50, 51, 52], and ICC [53].

B.1.2.3 For the purposes of this annex, the heat produced by a fire is manifested either as convective heat or radiant heat. It is assumed that conductive heat transfer is of little consequence during the early stages of the development of a fire, where this annex is relevant. A convective heat release rate fraction equal to 75 percent of the total heat release rate has been used in this annex. Users should refer to references 12 and 13 in K.1.2.19 for fuels or burning conditions that are substantially different from these conditions.

B.1.2.4 The design methods for plume-dependent fire detectors provided in this annex are based on full-scale fire tests funded by the Fire Detection Institute in which all fires were geometrically growing flaming fires. (See *Environments of Fire Detectors — Phase 1: Effect of Fire Size, Ceiling Height and Material; Measurements Vol. I and Analysis Vol. II* [10].)

B.1.2.5 The guidance applicable to smoke detectors is limited to a theoretical analysis based on the flaming fire test data and is not intended to address the detection of smoldering fires.

B.1.2.6 The design methods for plume-dependent fire detectors do not address the detection of steady-state fires.

B.1.2.7 The design methods for plume-dependent fire detectors used in this annex are only applicable when employed in the context of applications where the ceiling is smooth and level. They cannot be used for ceilings where there are beams, joists, or bays formed by beams and purlins. The research upon which the following methods have been based did not consider the effect of beams, joists, and bays in sufficient detail to justify the use of this annex to those applications.

B.1.3 Purpose.

B.1.3.1 The purpose of Annex B is to provide a performance basis for the location and spacing of fire detection-initiating devices. The sections for heat and smoke detectors provide an alternative design method to the prescriptive approach presented in Chapter 17 (i.e., based on their listed spacings). The section on radiant energy-sensing detectors elaborates on the performance-based criteria already existing in Chapter 17. A performance-based approach allows one to consider potential fire growth rates and fire signatures, the individual compartment characteristics, and damageability characteristics of the targets (e.g., occupants, equipment, contents, structures, and so on) in order to determine the location of a specific type of detector to meet the objectives established for the system.

B.1.3.2 Under the prescriptive approach, heat detectors are installed according to their listed spacing. The listed spacing is determined in a full-scale fire test room. The fire test room used for the determination of listed spacing for heat detectors has a ceiling height of 4.8 m (15 ft 9 in.). A steady-state, flammable liquid fire with a heat release rate of approximately 1137 kW (1200 Btu/sec), located 0.9 m (3 ft) above the floor, is used as the test fire. Special 71°C (160°F) test sprinklers are installed on a 3 m × 3 m (10 ft × 10 ft) spacing array such that the fire is in the center of the sprinkler array. The heat detectors being tested are installed in a square array with increasing spacing centered about the fire location. The elevation of the test fire is adjusted during the test to produce the temperature versus time curve at the test sprinkler heads to yield actuation of the heads in 2.0 minutes ±10 seconds. The largest heat detector spacing that achieves alarm before the actuation of the sprinkler heads in the test becomes the listed spacing for the heat detector. See Figure A.17.6.3.1.1(c). If the room dimensions, ambient conditions, and fire and response characteristics of the detector are different from above, the response of the heat detector must be expected to be different as well. Therefore, the use of an installed detector spacing that is different from the listed spacing might be warranted through the use of a performance-based approach if the conditions are as follows:

- (1) The design objectives are different from designing a system that operates at the same time as a sprinkler in the approval test.

- (2) Faster response of the device is desired.
- (3) A response of the device to a smaller fire than used in the approved test is required.
- (4) Accommodation to room geometry that is different from that used in the listing process.
- (5) Other special considerations, such as ambient temperature, air movement, ceiling height, or other obstruction, are different from or are not considered in the approval tests.
- (6) A fire other than a steady state 1137 kW (1200 Btu/sec) fire is contemplated.

B.1.3.3 The designer of fire alarm systems needs to be knowledgeable in the applicable areas associated with undertaking a performance-based design, including fire dynamics, performance-based design, detector response, and so forth, and apply these principles judiciously. In addition, the majority of jurisdictions consider the design of fire alarm systems as “engineering work.” They therefore require licensed engineers to perform such work. Other jurisdictions allow technologists to lay out fire alarm systems as long as they follow the appropriate prescriptive requirements. Designers who are using a performance-based design approach need to review the relevant engineering licensure laws in the jurisdictions in which they are practicing, as performance-based designs might very likely be deemed engineering and of the type that requires licensure of a professional engineer. The SFPE’s *Guidelines for Peer Review in the Fire Protection Design Process* [59] provides guidance to engineers who are asked to peer review this type of engineering design.

B.2 Performance-Based Approach to Designing and Analyzing Fire Detection Systems.

B.2.1 Overview. Subsection B.2.1 provides an overview of a systematic approach to conducting a performance-based design or analysis of a fire detection system. The approach has been outlined by Custer and Meacham and the SFPE *Engineering Guide to Performance Based Fire Protection* [40] and is summarized below in the context of design and analysis of fire detection systems. (Refer to Figure B.2.1.) This approach has been divided into two phases: defining goals and objectives and system design and evaluation.

B.2.2 Phase 1 — Defining Goals and Objectives.

B.2.2.1 Define Scope of Project.

B.2.2.1.1 The initial step of this approach is to identify information relative to the overall scope of work on the project, including characteristics of the building, design intent, design and construction team organization, constraints on design and project schedule, proposed building construction and features, relevant hazards, how the building functions, occupant characteristics, and so forth. Additional information that one might want to consider could also include characteristics of the fire departments, historic preservation, building management, and applicable regulations.

B.2.2.1.2 While defining the project’s scope, the designer will identify which of the three situations in Table B.2.2.1.2 best describes the project at hand (i.e., a performance-based analysis of an existing detection system in an existing building).

B.2.2.2 Identify Goals.

B.2.2.2.1 Fire protection assets are acquired in order to attain one or more of the following four goals:

- (1) To provide life safety (occupants, employees, fire fighters, and so forth)
- (2) To protect property and heritage (structure, contents, and so forth)
- (3) To provide for continuity of operations (protect stakeholder’s mission, operating capability, and so forth)
- (4) To limit the environmental impact of fire (toxic products, fire-fighting water run-off, and so forth)

B.2.2.2.2 Fire protection goals are like other goals in that they are generally easy to agree on, are qualitative, and are noncontroversial in nature. They express the desired overall outcome to be achieved, that is, to provide life safety to the building occupants.

B.2.2.2.3 When starting the performance-based process, the various parties — including the stakeholders (i.e., the architect, building owner, insurance carrier, building or fire officials, and so forth), the authority having jurisdiction, and the design engineer — work together to prioritize the basic fire protection goals. Prioritizing is based on the stakeholder’s objective and the building and occupancy involved. For example, life safety is a high priority in a hospital or stadium, while property protection might have an equally high priority in a large warehouse or historic building.

B.2.2.3 Identify Stakeholder’s Objectives.

B.2.2.3.1 Each stakeholder must explicitly state her or his objectives in terms of acceptable loss for the various goals previously stated.

B.2.2.3.2 Stakeholder objectives specify how much safety the stakeholder wants, needs, or can afford. “No loss of life within the room of origin” is a sample stakeholder objective or statement of the stakeholder’s maximum acceptable loss.

B.2.2.3.3 The stakeholder’s objectives are generally not stated in fire protection engineering terms.

B.2.2.3.4 Note that in a performance-based code environment, the Code will most likely define a performance objective or stakeholder objective.

B.2.2.4 Define Design Objectives.

B.2.2.4.1 The stakeholder’s objective must then be explicitly stated and quantified in fire protection engineering terms that describe how the objective will be achieved. This demands that the design objectives be expressed quantitatively. See Table B.2.2.4.1 (a) through Table B.2.2.4.1 (c).

B.2.2.4.2 The design objective provides a description of how the stakeholder’s objective will be achieved in general fire protection engineering terms prior to this description being quantified. The general objective is then reduced to explicit and quantitative fire protection engineering terms. The explicit fire protection engineering objectives provide a performance benchmark against which the predicted performance of a candidate design is evaluated.




FIGURE B.2.1 Overview of the Performance-Based Design Process. [25]

B.2.2.5 Define Performance Criteria.

B.2.2.5.1 Once the design objective has been established, specific, quantitatively expressed criteria that indicate attainment of the performance objective are developed.

B.2.2.5.2 Performance criteria provide a yardstick or threshold values that can measure a potential design's success in meeting stakeholder objectives and their associated design objectives. [25]

B.2.2.5.3 Quantification of the design objectives into performance criteria involves determination of the various fire-induced stresses that are a reflection of the stated loss objectives. Performance criteria can be expressed in various terms, including temperature, radiant flux, a rate of heat release, or concentration of a toxic or corrosive species that must not be exceeded.

B.2.2.5.4 Once the design performance criteria are established, appropriate safety factors are applied to obtain the

Table B.2.2.1.2 Design/Analysis Situation

Building Type	System Type	Design/Analysis
New	New	Design
Existing	New	Design
Existing	Existing	Analysis

working design criteria. The working design criteria reflect the performance that must be achieved by the detection system. This performance level must allow appropriate actions to be undertaken (e.g., actuate suppression systems, occupants' egress, notify fire department, and so forth) to meet the objectives. An acceptable fire detection system design provides the detection of the fire sufficiently early in its development to permit the other fire protection systems to meet or exceed the relevant performance criteria established for those systems.

Table B.2.2.4.1(a) Defining Goals and Objectives — Life Safety

Fire protection goal	Provide life safety
Stakeholder's objective	No loss of life within compartment of origin
Design objective	Maintain tenable conditions within the compartment of origin
Performance criteria	Maintain: Temperatures below $xx^{\circ}\text{C}$ ($^{\circ}\text{F}$) Visibility above yy m (ft) CO concentration below zz ppm for tt minutes

Table B.2.2.4.1(b) Defining Goals and Objectives — Property Protection

Fire protection goal	Provide protection of property
Stakeholder's objective	No fire damage outside compartment of origin
Design objective	Limit the spread of flame to the compartment of origin
Performance criteria	Maintain upper layer temperature below $xx^{\circ}\text{C}$ ($^{\circ}\text{F}$) and radiation level to the floor below yy kW/m^2 ($\text{Btu}/\text{sec}\cdot\text{ft}^2$) to prevent flashover

Table B.2.2.4.1(c) Defining Goals and Objectives — Continuity of Operations

Fire protection goal	Provide continuity of operations
Stakeholder's objective	Prevent any interruption to business operations in excess of 2 hours
Design objective	Limit the temperature and the concentration of HCl to within acceptable levels for continued operation of the equipment
Performance criteria	Provide detection such that operation of a gaseous suppression system will maintain temperatures below $xx^{\circ}\text{C}$ ($^{\circ}\text{F}$) and HCl levels below yy ppm

B.2.2.5.5 Throughout the process identified as Phase I and II, communication should be maintained with the authorities having jurisdiction (AHJs) to review and develop consensus on the approach being taken. It is recommended that this communication commence as early in the design process as possible. The AHJ should also be involved in the development of performance criteria. Often the acceptance of a performance-based design in lieu of a design based on a prescriptive approach relies on demonstrating equivalence. This is called the comparative method, where the designer demonstrates that the performance-based design responds at least as well as, if not better than, a system designed using a prescriptive approach.

B.2.3 Phase II — System Design and Evaluation.

B.2.3.1 Develop Fire Scenarios.

B.2.3.1.1 General.

B.2.3.1.1.1 A fire scenario defines the development of a fire and the spread of combustion products throughout a compartment or building. A fire scenario represents a set of fire conditions that are deemed a threat to a building and its occupants and/or contents, and, therefore, should be addressed in the design of the fire protection features of the structure. [25]

B.2.3.1.1.2 The process of developing a fire scenario is a combination of hazard analysis and risk analysis. The hazard analysis identifies potential ignition sources, fuels, and fire development. Risk is the probability of occurrence multiplied by the consequences of that occurrence. The risk analysis looks at the impact of the fire to the surroundings or target items.

B.2.3.1.1.3 The fire scenario should include a description of various conditions, including building characteristics, occupant characteristics, and fire characteristics. [25, 40]

B.2.3.1.2 Building Characteristics. Building characteristics include the following:

- (1) Configuration (area; ceiling height; ceiling configuration, such as flat, sloped beams; windows and doors, and thermodynamic properties)
- (2) Environment (ambient temperature, humidity, background noise, and so forth)
- (3) Equipment (heat-producing equipment, HVAC, manufacturing equipment, and so forth)
- (4) Functioning characteristics (occupied, during times, days, and so forth)
- (5) Target locations
- (6) Potential ignition sources
- (7) Aesthetic or historic preservation considerations

(Note target items — that is, areas associated with stakeholder objectives — along the expected route of spread for flame, heat, or other combustion products.)

B.2.3.1.3 Occupant Characteristics. Occupant characteristics include the following:

- (1) Alertness (sleeping, awake, and so forth)
- (2) Age
- (3) Mobility
- (4) Quantity and location within the building
- (5) Sex
- (6) Responsiveness
- (7) Familiarity with the building
- (8) Mental challenges

Human behavior plays a key role in life safety, as well as with the other fire safety goals. (*See SFPE Engineering Guide to Human Behavior in Fire.*) The possible actions that could be taken upon detecting a fire as well as how one reacts once they hear an alarm need to be considered. These actions can include alerting and rescuing other family members, gathering belongings, interpreting or verifying the message, shutting down processes. They should also include a look at how individuals respond on their own as well as in group situations.

Once these occupant characteristics and their behavior have been analyzed, one might also want to determine evacuation times. Numerous factors again need to be considered, including number of occupants, distribution throughout the build-

ing, pre-movement times, motivation, state of wakefulness, familiarity, capacity, and layout of the means of egress.

Due to the nature of human behavior, it is difficult to accurately quantify the movements and evacuation times of occupants from a building. Thus, particular attention should be given to assumptions and uncertainties assigned to these occupant characteristics.

B.2.3.1.4 Fire Characteristics.

B.2.3.1.4.1 Fire characteristics include the following:

- (1) Ignition sources — temperature, energy, time, and area of contact with potential fuels
- (2) Initial fuels
 - (a) *State.* Fuels can come in various states (i.e., solid, liquid, or gas). Each state can have very different combustion characteristics (i.e., a solid block of wood versus wood shavings versus wood dust)
 - (b) *Type and quantity of fuel.* A fire's development and duration depends also on what is burning. Cellulosic-based materials burn quite differently compared to plastics, or flammable liquids, in terms of producing different fire growth rates, heat release rates, and products of combustion.
 - (c) *Fuel configuration.* The geometrical arrangement of the fuel can also influence the fire growth rate and heat release rate. A wood block will burn very differently from a wood crib, as there is more surface area and ventilation, and radiation feedback between the combustible materials is increased.
 - (d) *Fuel location.* The location of the fuel (i.e., against wall, in corner, in open, against the ceiling) will influence the development of the fire. Fires in the corner of a room or against a wall will typically grow faster than a fire located in the center of a room.
 - (e) *Heat release rate.* The rate at which heat is released depends on the fuel's heat of combustion, the mass loss rate, the combustion efficiency, and the amount of incident heat flux. The mass loss rate also directly relates to the production rate of smoke, toxic gases, and other products of combustion.
 - (f) *Fire growth rate.* Fires grow at various rates that are dependent on type of fuel, configuration, and amount of ventilation. Some fires such as confined flammable liquid fires might not be growing fires as their burning area is fixed. These are referred to as steady state fires. The faster a fire develops, the faster the temperature rises, and the faster the products of combustion are produced.
 - (g) *Production rate of combustion products (smoke, CO, CO₂, etc.).* As the characteristics of various fuels vary, so will the type of quantity of materials generated during combustion. Species production rates can be estimated with species yields, which are representative of the mass of species produced per mass of fuel loss.
- (3) Secondary fuels — proximity to initial fuels; amount; distribution, ease of ignitability (*see initial fuels*); and extension potential (beyond compartment, structure, area, if outside)

B.2.3.1.4.2 An example of a fire scenario in a computer room might be as follows.

The computer room is 9.1 m × 6 m (30 ft × 20 ft) and 2.8 m (8 ft) high. It is occupied 12 hours a day, 5 days a week. The occupants are mobile and familiar with the building. There are no fixed fire suppression systems protecting this location. The fire department is capable of responding to the scene in 6 minutes, and an additional 15 minutes for fire ground evolution is needed.

Overheating of a resistor leads to the ignition of a printed circuit board and interconnecting cabling. This leads to a fire that quickly extends up into the above-ceiling space containing power and communications cabling. The burning of this cabling produces large quantities of dense, acrid smoke and corrosive products of combustion that spread throughout the computer suite. This causes the loss of essential computer and telecommunications services for 2 months.

B.2.3.2 Develop Design Fires.

B.2.3.2.1 General.

B.2.3.2.1.1 The design fire is the fire the system is intended to detect. When specifying a design fire, the specifics regarding the ignition, growth, steady-state output (if appropriate), and decay of the fire are expressed quantitatively.

There are numerous analysis techniques available to identify fire scenarios. These can typically fall into one of two categories: probabilistic or deterministic.

Probabilistic approaches typically relate to the statistical likelihood that ignition will occur, and the resultant outcome if a fire does occur. Probabilistic approaches could use the following as sources of data:

- (1) Fire statistics (ignition, first items ignited, and so on)
- (2) Past history
- (3) Hazard/failure analysis
- (4) Failure modes and effects analysis (FMEA)
- (5) Event trees
- (6) Fault trees
- (7) HAZOP studies
- (8) Cause-consequence analysis

Deterministic approaches use analysis or engineering judgment that is based on chemistry, physics, or correlations based on experimental data.

The selection of the design fire scenario and the supporting analysis techniques should be appropriate to the premise or processes. Inappropriate scenario selection or analysis can result in conservative designs that are not economical or designs with unacceptably high risks.

B.2.3.2.1.2 Fire development varies depending on the combustion characteristics of the fuel or fuels involved, the physical configuration of the fuels, the availability of combustion air, and the influences due to the compartment. Once a stable flame is attained, most fires grow in an accelerating pattern (*see Figure B.2.3.2.3.5*), reach a steady state characterized by a maximum heat release rate, and then enter into a decay period as the availability of either fuel or combustion air becomes limited. Fire growth and development are limited by factors such as quantity of fuel, arrangement of fuel, quantity of oxygen, and the effect of manual and automatic suppression systems.

For design fires with a smoldering period, very little data are available. The design engineer should, therefore, be careful in

specifying the duration of this period. The fire growth rate of flaming fires is determined by a variety of factors, including the following:

- (1) Type of fuel and ease of ignition
- (2) Fuel configuration and orientation
- (3) Location of secondary fuel packages
- (4) Proximity of fire to walls and corners
- (5) Ceiling height
- (6) Ventilation

It is important to note when using heat release data that the fuel burning as well as the compartment in which it is burning need to be considered together. A couch can produce sufficient heat to cause flashover in a small compartment, whereas this same couch placed in a large compartment with high ceilings can cause a limited fire and never reach flashover.

Several sources for developing design fires should be reviewed, including *SFPE Handbook of Fire Protection Engineering* [41]; *NFPA 101*; *NFPA 5000*; and *SFPE Engineering Guide to Performance Based Fire Protection* [40].

B.2.3.2.1.3 Designers might also need to consider fires that might be related to extreme events. These can either be fires used to trigger extreme events, or post-extreme-event-induced fires. If these are deemed credible, then designers should take these into consideration as design fires and also with respect to the overall reliability, redundancy, and robustness of the detection system to function during these types of events. [54]

B.2.3.2.2 Heat Release Rates.

B.2.3.2.2.1 Fires can be characterized by their rate of heat release, measured in terms of the number of kW (Btu/sec) of heat liberated. Typical maximum heat release rates (Q_m) for a number of different fuels and fuel configurations are provided in Table B.2.3.2.6.2(a) and Table B.2.3.2.6.2(c). The heat release rate of a fire can be described as a product of a heat release density and fire area using the following equation:

$$[B.2.3.2.2.1]$$

$$Q_m = qA$$

where:

Q_m = maximum or peak heat release rate [kW (Btu/sec)]

q = heat release rate density per unit floor area [kW/m² (Btu/sec-ft²)]

A = floor area of the fuel [m² (ft²)]

B.2.3.2.2.2 The following example is provided: A particular hazard analysis is to be based on a fire scenario involving a 3.05 m × 3.05 m (10 ft × 10 ft) stack of wood pallets stored 1.5 m (5 ft) high. Approximately what peak heat release rate can be expected?

From Table B.2.3.2.6.2(a), the heat release rate density (q) for 1.5 m (5 ft) high wood pallets is approximately 3745 kW/m² (330 Btu/sec-ft²).

The area is 3.05 m × 3.05 m (10 ft × 10 ft), or 9.29 m² (100 ft²). Using equation B.1 to determine the heat release rate yields the following:

$$3745 \times 9.29 = 34,791 \text{ kW } (330 \times 100 = 33,000 \text{ Btu/sec})$$

As indicated in the Table B.2.3.2.6.2(a), this fire generally produces a medium to fast fire growth rate, reaching 1055 kW (1000 Btu/sec) in approximately 90 to 190 seconds.

B.2.3.2.3 Fire Growth Rate.

B.2.3.2.3.1 Fires can also be defined by their growth rate or the time (t_g) it takes for the fire to reach a given heat release rate. Previous research [16] has shown that most fires grow exponentially and can be expressed by what is termed the "power law fire growth model":

$$[B.2.3.2.3.1]$$

$$Q \cong t^p$$

where:

Q = heat release rate (kW or Btu/sec)

t = time (seconds)

p = 2

B.2.3.2.3.2 In fire protection, fuel packages are often described as having a growth time (t_g). This is the time necessary after the ignition with a stable flame for the fuel package to attain a heat release rate of 1055 kW (1000 Btu/sec). The following equations describe the growth of design fires:

$$[B.2.3.2.3.2a]$$

$$Q = \frac{1055}{t_g^2} t^2 \quad (\text{for SI units})$$

or

$$[B.2.3.2.3.2b]$$

$$Q = \frac{1000}{t_g^2} t^2 \quad (\text{for inch-pound units})$$

and thus

$$[B.2.3.2.3.2c]$$

$$Q = \alpha t^2$$

where:

Q = heat release rate [kW or (Btu/sec)]

α = fire growth rate [1055/ t_g^2 (kW/sec²) or 1000/ t_g^2 (Btu/sec³)]

t_g = fire growth time to reach 1055 kW (1000 Btu/sec) after established burning

t = time after established burning occurs (seconds)

B.2.3.2.3.3 Table B.2.3.2.6.2(a) and Table B.2.3.2.6.2(e) provide values for t_g , the time necessary to reach a heat release rate of 1055 kW (1000 Btu/sec), for a variety of materials in various configurations.

B.2.3.2.3.4 Test data from 40 furniture calorimeter tests, as indicated in Table B.2.3.2.6.2(e), have been used to independently verify the power law fire growth model, $Q = \alpha t^2$. [14] For reference, the table contains the test numbers used in the original NIST reports.

The virtual time of origin (t_o) is the time at which a stable flame had appeared and the fires began to obey the power law

fire growth model. Prior to t_g , the fuels might have smoldered but did not burn vigorously with an open flame. The model curves are then predicted by the following equations:

[B.2.3.2.3.4a]

$$Q = \alpha(t - t_v)^2$$

and

[B.2.3.2.3.4b]

$$Q = \left(\frac{1055}{t_g^2} \right) (t - t_v)^2 \quad (\text{for SI units})$$

or

[B.2.3.2.3.4c]

$$Q = \left(\frac{1000}{t_g^2} \right) (t - t_v)^2 \quad (\text{for inch-pound units})$$

where:

Q = heat release rate [kW or (Btu/sec)]

α = fire growth rate [$1055/t_g^2$ (kW/sec²) or $1000/t_g^2$ (Btu/sec³)]

t_g = fire growth time to reach 1055 kW (1000 Btu/sec)

t = time after established burning occurs (seconds)

t_v = virtual time of origin (seconds)

B.2.3.2.3.5 Figure B.2.3.2.3.5 is an example of actual test data with a power law curve superimposed.

B.2.3.2.3.6 For purposes of this annex, fires are classified as being either slow-, medium-, or fast-developing from the time




FIGURE B.2.3.2.3.5 Test 38, Foam Sofa. (Courtesy of R. P. Schifiliti Associates, Inc.)

Table B.2.3.2.3.6 Power Law Heat Release Rates

Fire Growth Rate	Growth Time (t_g)	α (kW/sec ²)	α (Btu/sec ³)
Slow	$t_g \geq 400$ sec	$\alpha \leq 0.0066$	$\alpha \leq 0.0063$
Medium	$150 \leq t_g < 400$ sec	$0.0066 < \alpha \leq 0.0469$	$0.0063 < \alpha \leq 0.0445$
Fast	$t_g < 150$ sec	$\alpha > 0.0469$	$\alpha > 0.0445$

that established burning occurs until the fire reaches a heat release rate of 1055 kW (1000 Btu/sec). Table B.2.3.2.3.6 results from using B.2.3.2.3.2. [See also Table B.2.3.2.6.2(a).]

B.2.3.2.4 Flame Height.

B.2.3.2.4.1 There are a number of flame height to heat release rate correlations available that can be used to determine an appropriate design fire. The differences in the various correlations arise from the different data sets and curve-fitting methods used by the researchers. One such correlation is shown in Figure B.2.3.2.4.1. It indicates that flame height and fire heat release rate are directly related. [2] The lines in Figure B.2.3.2.4.1 were derived from the following equation:

[B.2.3.2.4.1a]

$$h_f = 0.182(kQ)^{2/5} \quad (\text{for SI units})$$

or

[B.2.3.2.4.1b]

$$h_f = 0.584(kQ)^{2/5} \quad (\text{for inch-pound units})$$

where:

h_f = flame height (m or ft)

k = wall effect factor

Q = heat release rate (kW or Btu/sec)

Where there are no nearby walls, use $k = 1$.

Where the fuel package is near a wall, use $k = 2$.

Where the fuel package is in a corner, use $k = 4$.

B.2.3.2.4.2 The following example is provided: What is the average flame height of a fire with a heat release rate of 1055 kW (1000 Btu/sec) located in the middle of a compartment?

From Figure B.2.3.2.4.1, find the heat release rate on the abscissa and read estimated flame height from the ordinate, or use equation B.2.3.2.4.1a or B.2.3.2.4.1b:

[B.2.3.2.4.2a]

$$h_f = 0.182(kQ)^{2/5} \quad (\text{for SI units}) \quad \text{or}$$

[B.2.3.2.4.2b]

$$h_f = 0.584(kQ)^{2/5} \quad (\text{for inch-pound units})$$




FIGURE B.2.3.2.4.1 Heat Release Rate vs. Flame Height.

[B.2.3.2.4.2c]

$$h_f = 0.182(1 \times 1055 \text{ kW})^{2/5} \text{ or}$$

[B.2.3.2.4.2d]

$$h_f = 0.584(1 \times 1000 \text{ Btu/sec})^{2/5} \text{ or}$$

[B.2.3.2.4.2e]

$$h_f = 2.8 \text{ m (9.25 ft)}$$

Another correlation has been derived by Drysdale [42]:

[B.2.3.2.4.2f]

$$I = 0.235Q^{2/5} - 1.02D$$

where:

I = the flame height (m)

Q = the convective heat release rate (kW)

D = the diameter of the fuel bed

These correlations will not produce the same prediction when used for exactly the same input data. There is inherent uncertainty in the calculated flame height due to the fact that the flaming combustion in the diffusion regime is a dynamic phenomenon. The designer should run multiple predictions with bounding values to address the inherent uncertainty of the correlations.

B.2.3.2.5 Selection of Critical Fire Size. Because all fire control means require a finite operation time, there is a critical difference between the time at which the fire must be detected and the time at which it achieves the magnitude of the design fire. Even though a fire has been detected, this does not mean that it stops growing. Fires typically grow exponentially until they become ventilation controlled, and limited by the availability of fuel, or until some type of fire suppression or extinguishment is commenced. Figure B.2.3.2.5 shows that there can be a significant increase in the heat release rate with only a small change in time due to the exponential growth rate of fire.

B.2.3.2.5.1 Once the design objectives and the design fire have been established, the designer will need to establish two points on the design fire curve: Q_{DO} and Q_{CR} .

B.2.3.2.5.2 Q_{DO} represents the heat release rate, or product release rate, which produces conditions representative of the design objective. This is the “design fire.” However, Q_{DO} does not represent the point in time at which detection is needed. Detection must occur sufficiently early in the development of the fire to allow for any intrinsic reaction time of the detection as well as the operation time for fire suppression or extinguishing systems. There will be delays in both detection of the fire as well as the response of equipment, or persons, to the alarm.

B.2.3.2.5.3 A critical fire size (Q_{CR}) is identified on the curve that accounts for the delays in detection and response. This point represents the maximum permissible fire size at which detection must occur that allows appropriate actions to be taken to keep the fire from exceeding the design objective (Q_{DO}).

B.2.3.2.5.4 Delays are inherent in both the detection system as well as in the response of the equipment or people that need to react once a fire is detected. Delays associated with the detection system include a lag in the transport of combustion products from the fire to the detector and response time lag of the detector, alarm verification time, processing time of the detector, and processing time of the control unit. Delays are also possible with an automatic fire extinguishing system(s) or suppression system(s). Delay can be introduced by alarm verification or crossed zone detection systems, filling and discharge times of preaction systems, delays in agent release required for occupant evacuation (e.g., CO₂ systems), and the time required to achieve extinguishment.




FIGURE B.2.3.2.5 Critical and Design Objective Heat Release Rates vs. Time.

B.2.3.2.5.5 Occupants do not always respond immediately to a fire alarm. The following must be accounted for when evaluating occupant safety issues:

- (1) Time expected for occupants to hear the alarm (due to sleeping or manufacturing equipment noise)
- (2) Time to decipher the message (e.g., voice alarm system)
- (3) Time to decide whether to leave (get dressed, gather belongings, call security)
- (4) Time to travel to an exit

B.2.3.2.5.6 Response of the fire department or fire brigade to a fire incident involves several different actions that need to occur sequentially before containment and extinguishment efforts of the fire can even begin. These actions should also be taken into account to properly design detection systems that meet the design objectives. These actions typically include the following:

- (1) Detection (detector delays, control unit delays, and so forth)
- (2) Notification to the monitoring station (remote, central station, proprietary, and so forth)
- (3) Notification of the fire department
- (4) Alarm handling time at the fire department
- (5) Turnout time at the station
- (6) Travel time to the incident
- (7) Access to the site
- (8) Set-up time on site
- (9) Access to building
- (10) Access to fire floor
- (11) Access to area of involvement
- (12) Application of extinguishant on the fire

B.2.3.2.5.7 Unless conditions that limit the availability of combustion air or fuel exist, neither the growth of the fire nor the resultant damage stop until fire suppression begins. The time needed to execute each step of the fire response sequence of actions must be quantified and documented. When designing a detection system, the sum of the time needed for each step in the response sequence (t_{delay}) must be subtracted from the time at which the fire attains the design objective (t_{DO}) in order to determine the latest time and fire size (Q_{CR}) in the fire development at which detection can occur and still achieve the system design objective.

B.2.3.2.5.8 The fire scenarios and design fires selected should include analysis of best and worst-case conditions and their likelihood of occurring. It is important to look at different conditions and situations and their effects on response.

B.2.3.2.6 Data Sources.

B.2.3.2.6.1 To produce a design fire curve, information is needed regarding the burning characteristics of the object(s) involved. Data can be obtained from either technical literature or by conducting small or large scale calorimeter tests.

B.2.3.2.6.2 Some information is contained in Figure B.2.3.2.6.2 and Table B.2.3.2.6.2(a) through Table B.2.3.2.6.2(e).

B.2.3.2.6.3 Graphs of heat release data from the 40 furniture calorimeter tests can be found in *Investigation of a New Sprinkler Sensitivity Approval Test: The Plunge Test* [8]. Best fit power law fire growth curves have been superimposed on the graphs. Data from these curves can be used with this guide to design or analyze fire detection systems that are intended to respond to

similar items burning under a flat ceiling. Table B.2.3.2.6.2(e) is a summary of the data.

B.2.3.2.6.4 In addition to heat release rate data, the original NIST reports [3] contain data on particulate conversion and radiation from the test specimens. These data can be used to determine the threshold fire size (heat release rate) at which tenability becomes endangered or the point at which additional fuel packages might become involved in the fire.

B.2.3.2.6.5 The *NFPA Fire Protection Handbook* [22], *SFPE Handbook of Fire Protection Engineering*, and *Upholstered Furniture Heat Release Rates Measured with a Furniture Calorimeter* [3] contain further information on heat release rates and fire growth rates.

B.2.3.2.6.6 Technical literature searches can be performed using a number of resources including FIREDOC, a document base of fire literature that is maintained by NIST.

B.2.3.2.6.7 A series of design fire curves are included as part of the "FASTLite" computer program available from NIST.

B.2.3.2.6.8 In addition, there are various organizations conducting tests and posting results of various test data on their websites, including the UK's British Research Establishment (BRE), Worcester Polytechnic Institute, and NIST's FAST-Data Fire Test Database.

B.2.3.3 Develop and Evaluate Candidate Fire Detection Systems.

B.2.3.3.1 Once the design objectives, the potential fire scenarios, and the room characteristics are well understood, the designer can select an appropriate detection strategy to detect the fire before its critical fire size (Q_{CR}) is reached. Important factors to consider include the type of detector, its sensitivity to expected fire signatures, its alarm threshold level and required duration at that threshold, expected installed location (e.g., distance from fire, or below ceiling), and freedom from nuisance response to expected ambient conditions. (See Chapter 17 and Annex A.)

B.2.3.3.1.1 The concept of wavelength is extremely important in selecting the proper detector for a particular application. There is a precise interrelation between the wavelength of light being emitted from a flame and the combustion chemistry producing the flame. Specific subatomic, atomic, and molecular events yield radiant energy of specific wavelengths. For example, ultraviolet photons are emitted as the result of the complete loss of electrons or very large changes in electron energy levels. During combustion, molecules are violently torn apart by the chemical reactivity of oxygen, and electrons are released in the process, recombining at drastically lower energy levels, thus giving rise to ultraviolet radiation. Visible radiation is generally the result of smaller changes in electron energy levels within the molecules of fuel, flame intermediates, and products of combustion. Infrared radiation comes from the vibration of molecules or parts of molecules when they are in the superheated state associated with combustion. Each chemical compound exhibits a group of wavelengths at which it is resonant. These wavelengths constitute the chemical's infrared spectrum, which is usually unique to that chemical.

This interrelationship between wavelength and combustion chemistry affects the relative performance of various types of detectors with respect to various fires.

Table B.2.3.2.6.2(a) Maximum Heat Release Rates — Warehouse Materials

Warehouse Materials	Growth Time (t_g) (sec)	Heat Release Density (q)		Classification
		kW/m ²	Btu/sec-ft ²	
1. Wood pallets, stack, 0.46 m (1½ ft) high (6%–12% moisture)	150–310	1,248	110	fast–medium
2. Wood pallets, stack, 1.52 m (5 ft) high (6%–12% moisture)	90–190	3,745	330	fast
3. Wood pallets, stack, 3.05 m (10 ft) high (6%–12% moisture)	80–110	6,810	600	fast
4. Wood pallets, stack, 4.88 m (16 ft) high (6%–12% moisture)	75–105	10,214	900	fast
5. Mail bags, filled, stored 1.52 m (5 ft) high	190	397	35	medium
6. Cartons, compartmented, stacked 4.57 m (15 ft) high	60	2,270	200	fast
7. Paper, vertical rolls, stacked 6.10 m (20 ft) high	15–28	—	—	*
8. Cotton (also PE, PE/cot, acrylic/nylon/PE), garments in 3.66 m (12 ft) high racks	20–42	—	—	*
9. Cartons on pallets, rack storage, 4.57 m–9.14 m (15 ft–30 ft) high	40–280	—	—	fast–medium
10. Paper products, densely packed in cartons, rack storage, 6.10 m (20 ft) high	470	—	—	slow
11. PE letter trays, filled, stacked 1.52 m (5 ft) high on cart	190	8,512	750	medium
12. PE trash barrels in cartons, stacked 4.57 m (15 ft) high	55	2,837	250	fast
13. FRP shower stalls in cartons, stacked 4.57 m (15 ft) high	85	1,248	110	fast
14. PE bottles, packed in item 6	85	6,242	550	fast
15. PE bottles in cartons, stacked 4.57 m (15 ft) high	75	1,929	170	fast
16. PE pallets, stacked 0.91 m (3 ft) high	130	—	—	fast
17. PE pallets, stacked 1.83 m–2.44 m (6 ft–8 ft) high	30–55	—	—	fast
18. PU mattress, single, horizontal	110	—	—	fast
19. PE insulation board, rigid foam, stacked 4.57 m (15 ft) high	8	1,929	170	*
20. PS jars, packed in item 6	55	13,619	1,200	fast
21. PS tubs nested in cartons, stacked 4.27 m (14 ft) high	105	5,107	450	fast
22. PS toy parts in cartons, stacked 4.57 m (15 ft) high	110	2,042	180	fast
23. PS insulation board, rigid, stacked 4.27 m (14 ft) high	7	3,291	290	*
24. PVC bottles, packed in item 6	9	3,405	300	*
25. PP tubs, packed in item 6	10	4,426	390	*
26. PP and PE film in rolls, stacked 4.27 m (14 ft) high	40	3,972	350	*
27. Distilled spirits in barrels, stacked 6.10 m (20 ft) high	23–40	—	—	*
28. Methyl alcohol	—	738	65	—
29. Gasoline	—	2,270	200	—
30. Kerosene	—	2,270	200	—
31. Diesel oil	—	2,043	180	—

PE: Polyethylene. PS: Polystyrene. PVC: Polyvinyl chloride. PP: Polypropylene. PU: Polyurethane. FRP: Fiberglass-reinforced polyester.

Note: The heat release rates per unit floor area are for fully involved combustibles, assuming 100 percent combustion efficiency. The growth times shown are those required to exceed 1000 Btu/sec heat release rate for developing fires, assuming 100 percent combustion efficiency.

*Fire growth rate exceeds design data.

Table B.2.3.2.6.2(b) Maximum Heat Release Rates from Fire Detection Institute Analysis

Materials	Approximate Values	
	kW	Btu/sec
Medium wastebasket with milk cartons	105	100
Large barrel with milk cartons	148	140
Upholstered chair with polyurethane foam	369	350
Latex foam mattress (heat at room door)	1265	1200
Furnished living room (heat at open door)	4217–8435	4000–8000

Table B.2.3.2.6.2(c) Unit Heat Release Rates for Fuels Burning in the Open

Commodity	Heat Release Rate	
	kW	Btu/sec
Flammable liquid pool	3291/m ²	290/ft ² of surface
Flammable liquid spray	557/Lpm	2000/gpm of flow
Pallet stack	3459/m	1000/ft of height
Wood or PMMA* (vertical)		
0.6 m (2 ft) height	104/m	30/ft of width
1.8 m (6 ft) height	242/m	70/ft of width
2.4 m (8 ft) height	623/m	180/ft of width
3.7 m (12 ft) height	1038/m	300/ft of width
Wood or PMMA*		
Top of horizontal surface	715/m ²	63/ft ² of surface
Solid polystyrene (vertical)		
0.6 m (2 ft) height	218/m	63/ft of width
1.8 m (6 ft) height	450/m	130/ft of width
2.4 m (8 ft) height	1384/m	400/ft of width
3.7 m (12 ft) height	2352/m	680/ft of width
Solid polystyrene (horizontal)	1362/m ²	120/ft ² of surface
Solid polypropylene (vertical)		
0.6 m (2 ft) height	218/m	63/ft of width
1.8 m (6 ft) height	346/m	100/ft of width
2.4 m (8 ft) height	969/m	280/ft of width
3.7 m (12 ft) height	1626/m	470/ft of width
Solid polypropylene (horizontal)	795/m ²	70/ft ² of surface

*Polymethyl methacrylate.

[92B: Table B.1, 1995.]

B.2.3.3.2 Reliability of the detection system and individual components should be computed and included in the selection and evaluation of the candidate fire detection system. A performance-based alternative design cannot be deemed performance-equivalent unless the alternative design provides comparable reliability to the prescriptive design it is intended to replace.

Reliability studies can be part of RAMS studies (i.e., reliability, availability, maintainability, and safety). RAMS is a tool that is used to manage dependability in “mission critical” systems. These are all factors that should be considered to ensure the system will continue to operate as designed, as well as provide ease of recommended maintenance and technician safety during maintenance.

The basis of RAMS is a systematic process, based on the system life cycle and tasks within it, that does the following:

- (1) Assists the client to specify system requirements, in terms of dependability, from a general mission statement to availability targets for systems, subsystems, and components (including software)
- (2) Assesses proposed designs, using formal RAMS techniques, to see how targets are met and where objectives are not achieved
- (3) Provides a means to make recommendations to designers and a system of hazard logging, to record and eventually “check off” identified necessary actions

The technical concepts of availability and reliability are based on a knowledge of and means to assess the following:

- (1) All possible system failure modes in the specified application environment
- (2) The probability (or rate) of occurrence of a system failure mode
- (3) The cause and effect of each failure mode on the functionality of the system
- (4) Efficient failure detection and location
- (5) The efficient restorability of the failed system
- (6) Economic maintenance over the required life cycle of the system
- (7) Human factors issues regarding safety during inspection, testing, and maintenance

B.2.3.3.3 Various methods are available to evaluate whether a candidate design will achieve the previously established performance criteria. Some methods are presented in Sections B.3, B.4, and B.5.

B.2.3.3.4 Candidate designs developed in the context of comparison evaluation might require comparing the response of the detection system designed using a performance-based approach to that of a prescriptive-based design. It could also be evaluated against acceptance criteria previously established with applicable stakeholders.

In addition to the preceding operational and response characteristics that need to be considered, there might be limitations set on the amount of disruption, visibility, or the impact the system will have on the space in which it is to be installed. This is particularly important in heritage-type buildings where one would want these to be as unobtrusive as possible, yet not require ripping down ornate ceilings to install.

B.2.3.4 Select and Document Final Design.

B.2.3.4.1 The last step in the process is the preparation of design documentation and equipment and installation specifications.

B.2.3.4.2 These documents should encompass the following information [25]:

- (1) Participants in the process — persons involved, their qualifications, function, responsibility, interest, and contributions.
- (2) Scope of work — purpose of conducting the analysis or design, part of the building evaluated, assumptions, and so forth.
- (3) Design approach — approach taken, where and why assumptions were made, and engineering tools and methodologies applied.
- (4) Project information — hazards, risks, construction type, materials, building use, layout, existing systems, occupant characteristics, and so forth.
- (5) Goals and objectives — agreed upon goals and objectives, how they were developed, who agreed to them and when.
- (6) Performance criteria — clearly identify performance criteria and related objective(s), including any safety, reliability, or uncertainty factors applied, and support for these factors where necessary.
- (7) Fire scenarios and design fires — description of fire scenarios used, bases for selecting and rejecting fire scenarios, assumptions, and restrictions.

Table B.2.3.2.6.2(d) Characteristics of Ignition Sources

	Typical Heat Output		Burn Time ^a (sec)	Maximum Flame Height		Flame Width		Maximum Heat Flux	
	W	Btu/sec		mm	in.	mm	in.	kW/m ²	Btu/sec · ft ²
Cigarette 1.1 g (not puffed, laid on solid surface)									
Bone dry	5	0.0047	1200	—	—	—	—	42	3.7
Conditioned to 50% relative humidity	5	0.0047	1200	—	—	—	—	35	3.1
Methenamine pill, 0.15 g (0.0053 oz)	45	0.043	90	—	—	—	—	4	0.35
Match, wooden, laid on solid surface	80	0.076	20–30	30	1.18	14	0.092	18–20	1.59–1.76
Wood cribs, BS 5852 Part 2									
No. 4 crib, 8.5 g (0.3 oz)	1,000	0.95	190	—	—	—	—	15 ^d	1.32
No. 5 crib, 17 g (0.6 oz)	1,900	1.80	200	—	—	—	—	17 ^d	1.50
No. 6 crib, 60 g (2.1 oz)	2,600	2.46	190	—	—	—	—	20 ^d	1.76
No. 7 crib, 126 g (4.4 oz)	6,400	6.07	350	—	—	—	—	25 ^d	2.20
Crumpled brown lunch bag, 6 g (0.21 oz)	1,200	1.14	80	—	—	—	—	—	—
Crumpled wax paper, 4.5 g (0.16 oz) (tight)	1,800	1.71	25	—	—	—	—	—	—
Crumpled wax paper, 4.5 g (0.16 oz) (loose)	5,300	5.03	20	—	—	—	—	—	—
Folded double-sheet newspaper, 22 g (0.78 oz) (bottom ignition)	4,000	3.79	100	—	—	—	—	—	—
Crumpled double-sheet newspaper, 22 g (0.78 oz) (top ignition)	7,400	7.02	40	—	—	—	—	—	—
Crumpled double-sheet newspaper, 22 g (0.78 oz) (bottom ignition)	17,000	16.12	20	—	—	—	—	—	—
Polyethylene wastebasket, 285 g (10.0 oz), filled with 12 milk cartons [390 g (13.8 oz)]	50,000	47.42	200 ^b	550	21.7	200	7.9	35 ^c	3.08
Plastic trash bags, filled with cellulosic trash [1.2–14 kg (42.3–49.3 oz)] ^c	120,000–350,000	113.81–331.96	200 ^b	—	—	—	—	—	—

Note: Based on Table B.5.3(b) of NFPA 92, 2012 edition.

^aTime duration of significant flaming.

^bTotal burn time in excess of 1800 seconds.

^cAs measured on simulation burner.

^dMeasured from 25 mm away.

^eResults vary greatly with packing density.

- (8) Design alternative(s) — describe design alternative(s) chosen, basis for selecting and rejecting design alternative(s), heat release rate, assumptions, and limitations. [This step should include the specific design objective (Q_{do}) and the critical heat release rate (Q_{cr}) used, comparison of results with the performance criteria and design objectives, and a discussion of the sensitivity of the selected design alternative to changes in the building use, contents, fire characteristics, occupants, and so forth.]
- (9) Engineering tools and methods used — description of engineering tools and methods used in the analysis or design, including appropriate references (literature, date, software version, and so forth), assumptions, limitations, engineering judgments, input data, validation data or procedures, and sensitivity analyses.
- (10) Drawings and specifications — detailed design and installation drawings and specification.
- (11) Test, inspection, and maintenance requirements (*see Chapter 14*).
- (12) Fire safety management concerns — allowed contents and materials in the space in order for the design to function properly, training, education, and so forth.
- (13) References — software documentation, technical literature, reports, technical data sheets, fire test results, and so forth.
- (14) Critical design assumptions — should include all assumptions that need to be maintained throughout the life cycle of the building so that the design functions as intended.
- (15) Critical design features — should include the design features and parameters that need to be maintained throughout the life of the building so that the design functions as intended.
- (16) Operations and maintenance manual — an operation and maintenance manual should be developed that clearly states the requirements for ensuring that the components of the performance-based design are correctly in place and functioning as designed. All subsystems should be identified, as well as their operation and interaction with the fire detection system. It should also include maintenance and testing frequencies, methods, and forms. The importance of testing interconnected systems should be detailed (i.e., elevator recall, suppression systems, HVAC shutdown, and so on).
- (17) Inspection, testing, maintenance, and commissioning — requirements for commissioning of systems and any special procedures or test methods — should be documented as well as inspection, testing, and maintenance procedures to address the design as well as any pertinent features or systems that need to be assessed.

Table B.2.3.2.6.2(e) Furniture Heat Release Rates [3, 14, 16]

Test No.	Item/Description/Mass	Growth Time (t_g) (sec)	Classification	Fire Growth Rate (α)		Virtual Time (t_v) (sec)	Maximum Heat Release Rates	
				kW/sec ²	Btu/sec ³		kW	Btu/sec
15	Metal wardrobe, 41.4 kg (91.3 lb) (total)	50	fast	0.4220	0.4002	10	750	711
18	Chair F33 (trial love seat), 29.2 kg (64.4 lb)	400	slow	0.0066	0.0063	140	950	901
19	Chair F21, 28.15 kg (62.01 lb) (initial)	175	medium	0.0344	0.0326	110	350	332
19	Chair F21, 28.15 kg (62.01 lb) (later)	50	fast	0.4220	0.4002	190	2000	1897
21	Metal wardrobe, 40.8 kg (90.0 lb) (total) (initial)	250	medium	0.0169	0.0160	10	250	237
21	Metal wardrobe, 40.8 kg (90.0 lb) (total) (average)	120	fast	0.0733	0.0695	60	250	237
21	Metal wardrobe, 40.8 kg (90.0 lb) (total) (later)	100	fast	0.1055	0.1001	30	140	133
22	Chair F24, 28.3 kg (62.4 lb)	350	medium	0.0086	0.0082	400	700	664
23	Chair F23, 31.2 kg (68.8 lb)	400	slow	0.0066	0.0063	100	700	664
24	Chair F22, 31.2 kg (68.8 lb)	2000	slow	0.0003	0.0003	150	300	285
25	Chair F26, 19.2 kg (42.3 lb)	200	medium	0.0264	0.0250	90	800	759
26	Chair F27, 29.0 kg (63.9 lb)	200	medium	0.0264	0.0250	360	900	854
27	Chair F29, 14.0 kg (30.9 lb)	100	fast	0.1055	0.1001	70	1850	1755
28	Chair F28, 29.2 kg (64.4 lb)	425	slow	0.0058	0.0055	90	700	664
29	Chair F25, 27.8 kg (61.3 lb) (later)	60	fast	0.2931	0.2780	175	700	664
29	Chair F25, 27.8 kg (61.3 lb) (initial)	100	fast	0.1055	0.1001	100	2000	1897
30	Chair F30, 25.2 kg (55.6 lb)	60	fast	0.2931	0.2780	70	950	901
31	Chair F31 (love seat), 39.6 kg (87.3 lb)	60	fast	0.2931	0.2780	145	2600	2466
37	Chair F31 (love seat), 40.4 kg (89.1 lb)	80	fast	0.1648	0.1563	100	2750	2608
38	Chair F32 (sofa), 51.5 kg (113.5 lb)	100	fast	0.1055	0.1001	50	3000	2845
39	½ in. plywood wardrobe with fabrics, 68.5 kg (151.0 lb)	35	*	0.8612	0.8168	20	3250	3083
40	½ in. plywood wardrobe with fabrics, 68.32 kg (150.6 lb)	35	*	0.8612	0.8168	40	3500	3320
41	⅓ in. plywood wardrobe with fabrics, 36.0 kg (79.4 lb)	40	*	0.6594	0.6254	40	6000	5691
42	⅛ in. plywood wardrobe with fire-retardant interior finish (initial growth)	70	fast	0.2153	0.2042	50	2000	1897
42	⅛ in. plywood wardrobe with fire-retardant interior finish (later growth)	30	*	1.1722	1.1118	100	5000	4742
43	Repeat of ½ in. plywood wardrobe, 67.62 kg (149.08 lb)	30	*	1.1722	1.1118	50	3000	2845
44	⅛ in. plywood wardrobe with fire-retardant latex paint, 37.26 kg (82.14 lb)	90	fast	0.1302	0.1235	30	2900	2751
45	Chair F21, 28.34 kg (62.48 lb)	100	*	0.1055	0.1001	120	2100	1992
46	Chair F21, 28.34 kg (62.48 lb)	45	*	0.5210	0.4941	130	2600	2466
47	Chair, adj. back metal frame, foam cushions, 20.82 kg (45.90 lb)	170	medium	0.0365	0.0346	30	250	237
48	Easy chair CO7, 11.52 kg (25.40 lb)	175	medium	0.0344	0.0326	90	950	901
49	Easy chair F34, 15.68 kg (34.57 lb)	200	medium	0.0264	0.0250	50	200	190
50	Chair, metal frame, minimum cushion, 16.52 kg (36.42 lb)	200	medium	0.0264	0.0250	120	3000	2845
51	Chair, molded fiberglass, no cushion, 5.28 kg (11.64 lb)	120	fast	0.0733	0.0695	20	35	33

(continues)

Table B.2.3.2.6.2(e) *Continued*

Test No.	Item/Description/Mass	Growth Time (t_g) (sec)	Classification	Fire Growth Rate (α)		Virtual Time (t_v) (sec)	Maximum Heat Release Rates	
				kW/sec ²	Btu/sec ³		kW	Btu/sec
52	Molded plastic patient chair, 11.26 kg (24.82 lb)	275	medium	0.0140	0.0133	2090	700	664
53	Chair, metal frame, padded seat and back, 15.54 kg (34.26 lb)	350	medium	0.0086	0.0082	50	280	266
54	Love seat, metal frame, foam cushions, 27.26 kg (60.10 lb)	500	slow	0.0042	0.0040	210	300	285
56	Chair, wood frame, latex foam cushions, 11.2 kg (24.69 lb)	500	slow	0.0042	0.0040	50	85	81
57	Love seat, wood frame, foam cushions, 54.6 kg (120.37 lb)	350	medium	0.0086	0.0082	500	1000	949
61	Wardrobe, $\frac{3}{4}$ in. particleboard, 120.33 kg (265.28 lb)	150	medium	0.0469	0.0445	0	1200	1138
62	Bookcase, plywood with aluminum frame, 30.39 kg (67.00 lb)	65	fast	0.2497	0.2368	40	25	24
64	Easy chair, molded flexible urethane frame, 15.98 kg (35.23 lb)	1000	slow	0.0011	0.0010	750	450	427
66	Easy chair, 23.02 kg (50.75 lb)	76	fast	0.1827	0.1733	3700	600	569
67	Mattress and box spring, 62.36 kg (137.48 lb) (later)	350	medium	0.0086	0.0082	400	500	474
67	Mattress and box spring, 62.36 kg (137.48 lb) (initial)	1100	slow	0.0009	0.0009	90	400	379

Note: For tests 19, 21, 29, 42, and 67, different power law curves were used to model the initial and the latter realms of burning. In examples such as these, engineers should choose the fire growth parameter that best describes the realm of burning to which the detection system is being designed to respond.

*Fire growth exceeds design data.

B.2.3.5 Management. It is important to ensure that the systems are designed, installed, commissioned, maintained, and tested on regular intervals as indicated in Chapter 14. In addition, the person conducting the testing and inspections should be aware of the background of the design and the need to evaluate not only the detector and whether it operates but also be aware of changing conditions including the following:

- (1) Changes in hazard being protected
- (2) Location of the hazard changes
- (3) Other hazards introduced into the area
- (4) Ambient environment
- (5) Invalidity of any of the design assumptions

B.3 Evaluation of Heat Detection System Performance.

B.3.1 General. Section B.3 provides a method for determining the application spacing for both fixed-temperature heat detectors (including sprinklers) and rate-of-rise heat detectors. This method is valid only for use when detectors are to be placed on a large, flat ceiling. It predicts detector response to a geometrically growing flaming fire at a specific fire size. This method takes into account the effects of ceiling height, radial distance between the detector and the fire, threshold fire size [critical heat release rate (Q_{CR})], rate of fire development, and detector response time index. For fixed-temperature detectors, the ambient temperature and the temperature rating of the detector are also considered. This method also allows for the adjustment of the application spacing for fixed-temperature heat detectors to account for variations in ambient temperature (T_a) from standard test conditions.




FIGURE B.2.3.2.6.2 Power Law Heat Release Rates.

B.3.1.1 This method can also be used to estimate the fire size at which detection will occur, given an existing array of listed heat detectors installed at a known spacing, ceiling height, and ambient conditions.

B.3.1.2 The effect of rate of fire growth and fire size of a flaming fire, as well as the effect of ceiling height on the spacing and response of smoke detectors, can also be determined using this method.

B.3.1.3 The methodology contained herein uses theories of fire development, fire plume dynamics, and detector perform-

ance. These are considered the major factors influencing detector response. This methodology does not address several lesser phenomena that, in general, are considered unlikely to have a significant influence. A discussion of ceiling drag, heat loss to the ceiling, radiation to the detector from a fire, re-radiation of heat from a detector to its surroundings, and the heat of fusion of eutectic materials in fusible elements of heat detectors and their possible limitations on the design method are provided in References 4, 11, 16, and 18 in K.1.2.19.

B.3.1.4 The methodology in Section B.3 does not address the effects of ceiling projections, such as beams and joists, on detector response. While it has been shown that these components of a ceiling have a significant effect on the response of heat detectors, research has not yet resulted in a simplified method for quantifying this effect. The prescriptive adjustments to detector spacing in Chapter 17 should be applied to application spacings derived from this methodology. Computational fluid dynamics (CFD) programs are available and can assist in analyzing the fire and development and spread of heat and smoke, as well as the potential effects of varying ceiling configurations and characteristics including sloped and beamed ceilings.

B.3.2 Considerations Regarding Input Data.

B.3.2.1 Required Data. The data listed in B.3.2.1.1 and B.3.2.1.2 are necessary in order to use the methods in this annex for either design or analysis.

B.3.2.1.1 Design. Data required to determine design include the following:

- (1) Ceiling height or clearance above fuel (H)
- (2) Threshold fire size at which response must occur (Q_d) or the time to detector response (t_d)
- (3) Response time index (RTI) for the detector (heat detectors only) or its listed spacing
- (4) Ambient temperature (T_a)
- (5) Detector operating temperature (T_i) (heat detectors only)
- (6) Rate of temperature change set point for rate-of-rise heat detectors (T_r/min)
- (7) Fire growth rate (α) or the fire growth time (t_g)

B.3.2.1.2 Analysis. Data required to determine analysis include the following:

- (1) Ceiling height or clearance above fuel (H)
- (2) Response time index (RTI) for the detector (heat detectors only) or its listed spacing
- (3) Actual installed spacing (S) of the existing detectors
- (4) Ambient temperature (T_a)
- (5) Detector operating temperature (T_i) (heat detectors only)
- (6) Rate of temperature change set point for rate-of-rise heat detectors (T_r/min)
- (7) Fire growth rate (α) or the fire growth time (t_g)

B.3.2.2 Ambient Temperature Considerations.

B.3.2.2.1 The maximum ambient temperature expected to occur at the ceiling will directly affect the choice of temperature rating for a fixed-temperature heat detector application. However, the minimum ambient temperature likely to be present at the ceiling is also very important. When ambient temperature at the ceiling decreases, more heat from a fire is needed to bring the air surrounding the detector's sensing element up to its rated (operating) temperature. This results in

slower response when the ambient temperature is lower. In the case of a fire that is growing over time, lower ambient temperatures result in a larger fire size at the time of detection.

B.3.2.2.2 Therefore, selection of the minimum ambient temperature has a significant effect on the calculations. The designer should decide what temperature to use for these calculations and document why that temperature was chosen. Because the response time of a given detector to a given fire is dependent only on the detector's time constant and the temperature difference between ambient and the detector rating, the use of the lowest anticipated ambient temperature for the space results in the most conservative design. For unheated spaces, a review of historical weather data would be appropriate. However, such data might show extremely low temperatures that occur relatively infrequently, such as every 100 years. Depending on actual design considerations, it might be more appropriate to use an average minimum ambient temperature. In any case, a sensitivity analysis should be performed to determine the effect of changing the ambient temperature on the design results.

B.3.2.2.3 In a room or work area that has central heating, the minimum ambient temperature would usually be about 20°C (68°F). On the other hand, certain warehouse occupancies might be heated only enough to prevent water pipes from freezing and, in this case, the minimum ambient temperature can be considered to be 2°C (35°F), even though, during many months of the year, the actual ambient temperature can be much higher.

B.3.2.3 Ceiling Height Considerations.

B.3.2.3.1 A detector ordinarily operates sooner if it is nearer to the fire. Where ceiling heights exceed 4.9 m (16 ft), ceiling height is the dominant factor in the detection system response.

B.3.2.3.2 As flaming combustion commences, a buoyant plume forms. The plume is comprised of the heated gases and smoke rising from the fire. The plume assumes the general shape of an inverted cone. The smoke concentration and temperature within the cone varies inversely as a variable exponential function of the distance from the source. This effect is very significant in the early stages of a fire, because the angle of the cone is wide. As a fire intensifies, the angle of the cone narrows and the significance of the effect of height is lessened.

B.3.2.3.3 As the ceiling height increases, a larger-size fire is necessary to actuate the same detector in the same length of time. In view of this, it is very important that the designer consider the size of the fire and rate of heat release that might develop before detection is ultimately obtained.

B.3.2.3.4 The procedures presented in B.3.2.3 are based on analysis of data for ceiling heights up to 9.1 m (30 ft). No data were analyzed for ceiling heights greater than 9.1 m (30 ft). In spaces where the ceiling heights exceed this limit, B.3.2.3 offers no guidance. [40]

B.3.2.3.5 The relationships presented here are based on the difference between the ceiling height and the height of the fuel item involved in the fire. It is recommended that the designer assume the fire is at floor level and use the actual distance from floor to ceiling for the calculations. This will yield a design that is conservative, and actual detector response can be expected to exceed the needed speed of response in those cases where the fire begins above floor level.

B.3.2.3.6 Where the designer desires to consider the height of the potential fuel in the room, the distance between the base of the fuel and the ceiling should be used in place of the ceiling height. This design option is appropriate only if the minimum height of the potential fuel is always constant and the concept is approved by the authority having jurisdiction.

B.3.2.4 Operating Temperature.

B.3.2.4.1 The operating temperature, or rate of temperature change, of the detector required for response is obtained from the manufacturer's data and is determined during the listing process.

B.3.2.4.2 The difference between the rated temperature of a fixed-temperature detector (T_s) and the maximum ambient-temperature (T_a) at the ceiling should be as small as possible. However, to reduce unwanted alarms, the difference between operating temperature and the maximum ambient temperature should be not less than 11°C (20°F). (See Chapter 17.)

B.3.2.4.3 If using combination detectors incorporating both fixed temperature and rate-of-rise heat detection principles to detect a geometrically growing fire, the data contained herein for rate-of-rise detectors should be used in selecting an installed spacing, because the rate-of-rise principle controls the response. The fixed-temperature set point is determined from the maximum anticipated ambient temperature.

B.3.2.5 Time Constant and Response Time Index (RTI). The flow of heat from the ceiling jet into a heat detector sensing element is not instantaneous. It occurs over a period of time. A measure of the speed with which heat transfer occurs, the thermal response coefficient is needed to accurately predict heat detector response. This is currently called the detector time constant (τ_0). The time constant is a measure of the detector's sensitivity. The sensitivity of a heat detector, τ_0 or RTI, should be determined by validated test. Research by FM Global [43,44,45] has shown that such a correlation exists and has resulted in a test method to determine RTI. This test method is documented in FM Approval Standard 3210, *Heat Detectors for Automatic Fire Alarm Signaling*. Heat detectors should be listed with their RTI so that heat detector spacing can be appropriately determined for various objectives and applications. For older or existing detectors, given the detector's listed spacing and the detector's rated temperature (T_s), Table B.3.2.5, developed in part by Heskestad and Delichatsios [10], can be used to find the detector time constant.

B.3.2.6 Fire Growth Rate.

B.3.2.6.1 Fire growth varies depending on the combustion characteristics and the physical configuration of the fuels involved. After ignition, most fires grow in an accelerating pattern. Information regarding the fire growth rate for various fuels has been provided previously in this annex.

B.3.2.6.2 If the heat release history for a particular fire is known, the α or t_g can be calculated using curve fitting techniques for implementation into the method detailed herein. [16]

B.3.2.6.3 In most cases, the exact fuel(s) and growth rates will not be known. Engineering judgment should therefore be used to select α or t_g that is expected to approximate the fire. Sensitivity analysis should also be performed to determine the effect on response from changes in the expected fire growth rate. In some analyses the effect on response will be negligible. Other cases might show that a more thorough analysis of potential fuels and fire scenarios is necessary.

B.3.2.7 Threshold Fire Size. The user should refer to B.2.3.1 and B.2.3.2 regarding discussions on determining threshold fire sizes (Q_{FD} and Q_{CR}) to meet the design objectives.

B.3.3 Heat Detector Spacing.

B.3.3.1 Fixed-Temperature Heat Detector Spacing. The following method can be used to determine the response of fixed-temperature heat detectors for designing or analyzing heat detection systems.

B.3.3.1.1 The objective of designing a detection system is to determine the spacing of detectors required to respond to a given set of conditions and goals. To achieve the objectives, detector response must occur when the fire reaches a critical heat release rate, or in a specified time.

B.3.3.1.2 When analyzing an existing detection system, the designer is looking to determine the size of the fire at the time that the detector responds.

B.3.3.2 Theoretical Background. [26, 28] The design and analysis methods contained in Annex B are the joint result of extensive experimental work and of mathematical modeling of the heat and mass transfer processes involved. The original method was developed by Heskestad and Delichatsios [9, 10], Beyler [4], and Schifflit [16]. It was recently updated by Marrion [28] to reflect changes in the original correlations as discussed in work by Heskestad and Delichatsios [11] and

Table B.3.2.5 Time Constants (τ_0) for Any Listed Heat Detector [at a reference velocity of 1.5 m/sec (5 ft/sec)]

Listed Spacing		Underwriters Laboratories Inc.						Factory Mutual Research Corporation (All Temperatures)
m	ft	53.3°C (128°F)	57.2°C (135°F)	62.8°C (145°F)	71.1°C (160°F)	76.7°C (170°F)	91.1°C (196°F)	
3.05	10	400	330	262	195	160	97	196
4.57	15	250	190	156	110	89	45	110
6.10	20	165	135	105	70	52	17	70
7.62	25	124	100	78	48	32	—	48
9.14	30	95	80	61	36	22	—	36
12.19	40	71	57	41	18	—	—	—
15.24	50	59	44	30	—	—	—	—
21.34	70	36	24	9	—	—	—	—

Notes: (1) These time constants are based on an analysis [10] of the Underwriters Laboratories Inc. and Factory Mutual listing test procedures. (2) These time constants can be converted to response time index (RTI) values by using the equation $RTI = \tau_0 (5.0 \text{ ft/sec})^{1/2}$. (See also B.3.3.)

Marrion [27]. Additional research has been conducted by FM Global [43, 44, 45]. Paragraph B.3.3.2 outlines methods and data correlations used to model the heat transfer to a heat detector, as well as velocity and temperature correlations for growing fires at the location of the detector. Only the general principles are described here. More detailed information is available in References 4, 9, 10, 16, and 28 in K.1.2.19.

B.3.3.3 Heat Detector Correlations. The heat transfer to a detector can be described by the following equation:

$$Q_{\text{total}} = Q_{\text{cond}} + Q_{\text{conv}} + Q_{\text{rad}} \quad [\text{B.3.3.3}]$$

where:

Q_{total} = total heat transfer to a detector (kW or Btu/sec)
 Q_{cond} = conductive heat transfer
 Q_{conv} = convective heat transfer
 Q_{rad} = radiative heat transfer

B.3.3.3.1 Because detection typically occurs during the initial stages of a fire, the radiant heat transfer component (Q_{rad}) can be considered negligible. In addition, because the heat-sensing elements of most of the heat detectors are thermally isolated from the rest of the detection unit, as well as from the ceiling, it can be assumed that the conductive portion of the heat release rate (Q_{cond}) is also negligible, especially when compared to the convective heat transfer rate. Because the majority of the heat transfer to the detection element is via convection, the following equation can be used to calculate the total heat transfer:

$$Q = Q_{\text{conv}} = H_c A (T_g - T_d) \quad [\text{B.3.3.3.1}]$$

where:

Q_{conv} = convective heat transfer (kW or Btu/sec)
 H_c = convective heat transfer coefficient for the detector (kW/m²·°C or Btu/ft²·sec·°F)
 A = surface area of the detector's element (m² or ft²)
 T_g = temperature of fire gases at the detector (°C or °F)
 T_d = temperature rating, or set point, of the detector (°C or °F)

B.3.3.3.2 Assuming the detection element can be treated as a lumped mass (m) (kg or lbm), its temperature change can be defined as follows:

$$\frac{dT_d}{dt} = \frac{Q}{mc} \quad [\text{B.3.3.3.2}]$$

where:

dT_d/dt = change in temperature of detection element (deg/sec)
 Q = heat release rate (kW or Btu/sec)
 m = detector element's mass (kg or lbm)
 c = detector element's specific heat (kJ/kg·°C or Btu/lbm·°F)

B.3.3.3.3 By inserting Equation B.3.3.3.2 into Equation B.3.3.3.1, the change in temperature of the detection element over time is expressed in Equation B.3.3.3.3.

$$\frac{dT_d}{dt} = \frac{H_c A (T_g - T_d)}{mc} \quad [\text{B.3.3.3.3}]$$

Note that the variables are identified in Section B.7.

B.3.3.3.4 The use of a time constant (τ) was proposed by Heskestad and Smith [8] in order to define the convective heat transfer to a specific detector's heat-sensing element. This time constant is a function of the mass, specific heat, convective heat transfer coefficient, and area of the element and can be expressed as follows:

$$\tau = \frac{mc}{H_c A} \quad [\text{B.3.3.3.4}]$$

where:

m = detector element's mass (kg or lbm)
 c = detector element's specific heat (kJ/kg·°C or Btu/lbm·°F)
 H_c = convective heat transfer coefficient for the detector (kW/m²·°C or Btu/ft²·sec·°F)
 A = surface area of the detector's element (m² or ft²)
 τ = detector time constant (seconds)

B.3.3.3.5 As seen in the equation B.3.3.3.4, τ is a measure of the detector's sensitivity. By increasing the mass of the detection element, the time constant, and thus the response time, increases.

B.3.3.3.6 Substituting into equation B.3.3.3.3 produces the following:

$$\frac{dT_d}{dt} = \frac{T_g - T_d}{\tau} \quad [\text{B.3.3.3.6}]$$

Note that the variables are identified in Section B.7.

B.3.3.3.7 Research has shown [24] that the convective heat transfer coefficient for sprinklers and heat detection elements is similar to that of spheres, cylinders, and so forth, and is thus approximately proportional to the square root of the velocity of the gases passing the detector. As the mass, thermal capacity, and area of the detection element remain constant, the following relationship can be expressed as the response time index (RTI) for an individual detector:

$$\tau u^{1/2} \sim \tau_0 u_0^{1/2} = \text{RTI} \quad [\text{B.3.3.3.7}]$$

where:

τ = detector time constant (seconds)
 u = velocity of fire gases (m/sec or ft/sec)
 u_0 = instantaneous velocity of fire gases (m/sec or ft/sec)
RTI = response time index

B.3.3.3.8 If τ_0 is measured at a given reference velocity (u_0), τ can be determined for any other gas velocity (u) for that detector. A plunge test is the easiest way to measure τ_0 . It has also been related to the listed spacing of a detector through a calculation. Table B.3.2.5 presents results from these calculations [10]. The RTI value can then be obtained by multiplying τ_0 values by $u_0^{1/2}$.

B.3.3.3.9 It has become customary to refer to the time constant using a reference velocity of $u_0 = 1.5$ m/sec (5 ft/sec). For example, where $u_0 = 1.5$ m/sec (5 ft/sec), a τ_0 of 30 seconds corresponds to an RTI of $36 \text{ sec}^{1/2}/\text{m}^{1/2}$ (or $67 \text{ sec}^{1/2}/\text{ft}^{1/2}$). On the other hand, a detector that has an RTI of $36 \text{ sec}^{1/2}/\text{m}^{1/2}$ (or $67 \text{ sec}^{1/2}/\text{ft}^{1/2}$) would have a τ_0 of 23.7 seconds, if measured in an air velocity of 2.4 m/sec (8 ft/sec).

B.3.3.3.10 The following equation can therefore be used to calculate the heat transfer to the detection element and thus determine its temperature from its local fire-induced environment:

[B.3.3.3.10]

$$\frac{dT_d}{dt} = \frac{u^{1/2}(T_g - T_d)}{\text{RTI}}$$

Note that the variables are identified in Section B.7.

B.3.3.4 Temperature and Velocity Correlations. [26, 28] In order to predict the operation of any detector, it is necessary to characterize the local environment created by the fire at the location of the detector. For a heat detector, the important variables are the temperature and velocity of the gases at the detector. Through a program of full-scale tests and the use of mathematical modeling techniques, general expressions for temperature and velocity at a detector location have been developed by Heskestad and Delichatsios (*refer to references 4, 9, 10, and 16 in K.1.2.19*). These expressions are valid for fires that grow according to the following power law relationship:

[B.3.3.4]

$$Q = \alpha t^p$$

where:

Q = theoretical convective fire heat release rate (kW or Btu/sec)

α = fire growth rate (kW/sec² or Btu/sec³)

t = time (seconds)

p = positive exponent

Several other ceiling jet correlations [41] have been developed over the years that the designer should also review as to their applicability to the particular design case. Sensitivity analyses should also be conducted with the analysis.

B.3.3.4.1 Relationships have been developed by Heskestad and Delichatsios [9] for temperature and velocity of fire gases in a ceiling jet. These have been expressed as follows [26]:

[B.3.3.4.1a]

$$U_p^* = \frac{u}{A^{1/(3+p)} u^{1/(3+p)} H^{(p-1)/(3+p)}} = f\left(t_p^*, \frac{r}{H}\right)$$

[B.3.3.4.1b]

$$\Delta T_p^* = g\left(t_p^*, \frac{r}{H}\right) = \frac{\Delta T}{A^{2/(3+p)} \left(\frac{T_g}{g}\right) \alpha^{2/(3+p)} H^{-(5-p)/(3+p)}}$$

where:

[B.3.3.4.1c]

$$t_p^* = \frac{t}{A^{-1/(3+p)} \alpha^{-1/(3+p)} H^{1/(3+p)}}$$

and

[B.3.3.4.1d]

$$A = \frac{g}{C_p T_g \rho_0}$$

Note that the variables are identified in Section B.7.

B.3.3.4.2 Using the correlations in B.3.3.4.1, Heskestad and Delichatsios [9], and with later updates from another paper by Heskestad [11], the following correlations were presented for fires that had heat release rates that grew according to the power law equation, with $p = 2$. As previously discussed [10, 18], the $p = 2$ power law fire growth model can be used to model the heat release rate of a wide range of fuels. These fires are therefore referred to as *t-squared* fires.

[B.3.3.4.2a]

$$t_{2f}^* = 0.861 \left(1 + \frac{r}{H}\right)$$

[B.3.3.4.2b]

$$\Delta T_2^* = 0 \quad \text{for } t_2^* < t_{2f}^*$$

[B.3.3.4.2c]

$$\Delta T_2^* = \left(\frac{t_2^* - t_{2f}^*}{0.146 + 0.242r/H} \right)^{4/3} \quad \text{for } t_2^* \geq t_{2f}^*$$

[B.3.3.4.2d]

$$\frac{u_2^*}{(\Delta T_2^*)^{1/2}} = 0.59 \left(\frac{r}{H} \right)^{-0.63}$$

Note that the variables are identified in Section B.7.

B.3.3.4.3 Work by Beyler [4] determined that the temperature and velocity correlations in B.3.3.4.2 could be substituted into the heat transfer equation for the detector and integrated. His analytical solution is as follows:

$$T_d(t) - T_d(0) = \left(\frac{\Delta T}{\Delta T_2^*} \right) \Delta T_2^* \left[\frac{1 - (1 - e^{-Y})}{Y} \right] \quad [\text{B.3.3.4.3a}]$$

$$\frac{dT_d(t)}{dt} = \frac{\left(\frac{4}{3} \right) \left(\frac{\Delta T}{\Delta T_2^*} \right) (\Delta T_2^*)^{1/4} (1 - e^{-Y})}{\left(\frac{t}{t_2^*} \right) D} \quad [\text{B.3.3.4.3b}]$$

where:

$$Y = \left(\frac{3}{4} \right) \left(\frac{u}{u_2^*} \right)^{1/2} \left(\frac{u_2^*}{\Delta T_2^{*1/2}} \right)^{1/2} \left(\frac{\Delta T_2^*}{RTI} \right) \left(\frac{t}{t_2^*} \right) D \quad [\text{B.3.3.4.3c}]$$

and

$$D = 0.146 + 0.242r/H \quad [\text{B.3.3.4.3d}]$$

Note that the variables are identified in Section B.7.

B.3.3.4.4 The steps involved in solving these equations for either a design or analysis situation are presented in Figure B.3.3.4.4 [28].

B.3.3.5 Limitations. [26]

B.3.3.5.1 If velocity and temperature of the fire gases flowing past a detector cannot be accurately determined, errors will be introduced when calculating the response of a detector. The graphs presented by Heskestad and Delichatsios indicate the errors in the calculated fire-gas temperatures and velocities [10]. A detailed analysis of these errors is beyond the scope of this annex; however, some discussion is warranted. In using the method presented in B.3.3.2, the user should be aware of the limitations of these correlations, as outlined in Reference 26. The designer should also refer back to the original reports.

Graphs of actual and calculated data show that errors in T_2^* can be as high as 50 percent, although generally there appears to be much better agreement. The maximum errors occur at r/H values of about 0.37. All other plots of actual and calculated data, for various r/H , show much smaller errors. In terms of the actual change in temperature over ambient, the maximum errors are on the order of 5°C to 10°C (9°F to 18°F). The larger errors occur with faster fires and lower ceilings.

At $r/H = 0.37$, the errors are conservative when the equations are used in a design problem. That is, the equations predicted lower temperatures. Plots of data for other values of r/H indicate that the equations predict slightly higher temperatures.

Errors in fire-gas velocities are related to errors in temperatures. The equations show that the velocity of the fire gases is proportional to the square root of the change in temperatures of the fire gases. In terms of heat transfer to a detector, the detector's change in temperature is proportional to the change in gas temperature and the square root of the fire-gas velocity. Hence, the expected errors bear the same relationships.

Based on the discussion in this section, errors in predicted temperatures and velocities of fire gases will be greatest for fast fires and low ceilings. Sample calculations simulating these conditions show errors in calculated detector spacings on the order of plus or minus one meter, or less.

B.3.3.5.2 The procedures presented in this annex are based on an analysis of test data for ceiling heights up to 9.1 m (30 ft). No data were analyzed for ceilings greater than 9.1 m (30 ft). The reader should refer to Reference 40 for additional insight.

B.3.3.6 Design Examples.

B.3.3.6.1 Define Project Scope. A fire detection system is to be designed for installation in an unsprinklered warehouse building. The building has a large, flat ceiling that is approximately 4 m (13.1 ft) high. The ambient temperature inside is normally 10°C (50°F). The municipal fire service has indicated that it can begin putting water on the fire within 5.25 minutes of receiving the alarm.

B.3.3.6.2 Identify Goals. Provide protection of property.

B.3.3.6.3 Define Stakeholder's Objective. No fire spread from initial fuel package.

B.3.3.6.4 Define Design Objective. Prevent radiant ignition of adjacent fuel package.

B.3.3.6.5 Develop Performance Criteria. After discussions with the plant fire brigade with regard to their capability and analyzing the radiant energy levels necessary to ignite adjacent fuel packages, it was determined that the fire should be detected and suppression activities started prior to its reaching 10,000 kW (9478 Btu/sec).

B.3.3.6.6 Develop Fire Scenarios and the Design Fire. Evaluation of the potential contents to be warehoused identified the areas where wood pallets are stored to be one of the highest fire hazards.

Fire Detection Design and Analysis Worksheet [28]

Design Example

1.	Determine ambient temperature (T_a) ceiling height or height above fuel (H).	$T_a = \text{_____}^\circ\text{C} + 273 = \text{_____}\text{ K}$ $H = \text{_____}\text{ m}$
2.	Determine the fire growth characteristic (α or t_g) for the expected design fire.	$\alpha = \text{_____}\text{ kW/sec}^2$ $t_g = \text{_____}\text{ sec}$
3a.	Define the characteristics of the detectors.	$T_s = \text{_____}^\circ\text{C} + 273 = \text{_____}\text{ K}$ $\text{RTI} = \text{_____}\text{ m}^{1/2}\text{sec}^{1/2}$ $\frac{dT_d}{dt} = \text{_____}^\circ\text{C/min}$ $\tau_0 = \text{_____}\text{ sec}$
3b.	<i>Design</i> — Establish system goals (t_{CR} or Q_{CR}) and make a first estimate of the distance (r) from the fire to the detector.	$t_{CR} = \text{_____}\text{ sec}$ $r = \text{_____}\text{ m}$ $Q_{CR} = \text{_____}\text{ kW}$
3b.	<i>Analysis</i> — Determine spacing of existing detectors and make a first estimate of the response time or the fire size at detector response ($Q = \alpha t^2$).	$r = \text{_____} * 1.41 = \text{_____} = S\text{ (m)}$ $Q = \text{_____}\text{ kW}$ $t_d = \text{_____}\text{ sec}$
4.	Using equation B.3.3.4.2a, calculate the non-dimensional time (t_{2f}^*) at which the initial heat front reaches the detector.	$t_{2f}^* = 0.861 \left(1 + \frac{r}{H} \right)$ $t_{2f}^* = \text{_____}$
5.	Calculate the factor A defined by the relationship for A in equation B.3.3.4.1d.	$A = \frac{g}{C_p T_a \rho_o}$ $A = \text{_____}$
6.	Use the required response time (t_{CR}) along with the relationship for t_p^* in equation B.3.3.4.1c and $p = 2$ to calculate the corresponding value of t_2^* .	$t_2^* = \frac{t_{CR}}{A^{-1/(3+p)} \alpha^{-1/(3+p)} H^{4/(3+p)}}$ $t_2^* = \text{_____}$
7.	If $t_2^* > t_{2f}^*$, continue to step 8. If not, try a new detector position (r) and return to step 4.	
8.	Calculate the ratio $\frac{u}{u_2^*}$ using the relationship for U_p^* in equation B.3.3.4.1a.	$\frac{u}{u_2^*} = A^{1/(3+p)} \alpha^{1/(3+p)} H^{(p-1)/(3+p)}$ $\frac{u}{u_2^*} = \text{_____}$
9.	Calculate the ratio $\frac{\Delta T}{\Delta T_2^*}$ using the relationship for ΔT_p^* in equation B.3.3.4.1b.	$\frac{\Delta T}{\Delta T_2^*} = A^{2/(3+p)} (T_a/g) \alpha^{2/(3+p)} H^{-(5-p)/(3+p)}$ $\frac{\Delta T}{\Delta T_2^*} = \text{_____}$
10.	Use the relationship for ΔT_2^* in equation B.3.3.4.2c to calculate ΔT_2^* .	$\Delta T_2^* = \left[\frac{t_2^* - t_{2f}^*}{(0.146 + 0.242r/H)} \right]^{4/3}$ $\Delta T_2^* = \text{_____}$
11.	Use the relationship for $\frac{u}{(\Delta T_2^*)^{1/2}}$ in equation B.3.3.4.2d to calculate the ratio $\frac{u_2^*}{(\Delta T_2^*)^{1/2}}$.	$\frac{u_2^*}{(\Delta T_2^*)^{1/2}} = 0.59 \left(\frac{r}{H} \right)^{-0.63}$ $\frac{u_2^*}{(\Delta T_2^*)^{1/2}} = \text{_____}$
12.	Use the relationships for Y and D in equations B.3.3.4.3c and B.3.3.4.3d to calculate Y .	$Y = \left(\frac{3}{4} \right) \left(\frac{u}{u_2^*} \right)^{1/2} \left[\frac{u_2^*}{(\Delta T_2^*)^{1/2}} \right]^{1/2} \left(\frac{\Delta T_2^*}{\text{RTI}} \right) \left(\frac{t}{t_2^*} \right) D$ $Y = \text{_____}$
13.	<i>Fixed Temperature HD</i> — Use the relationship for $T_d(t) - T_d(0)$ in equation B.3.3.4.3a to calculate the resulting temperature of the detector $T_d(t)$.	$T_d(t) = \left(\frac{\Delta T}{\Delta T_2^*} \right) \Delta T_2^* \left[1 - \frac{(1-e^{-Y})}{Y} \right] + T_d(0)$ $T_d(t) = \text{_____}$
14.	<i>Rate of Rise HD</i> — Use the relationship for $\frac{dT_d(t)}{dt}$ in equation B.3.3.4.3b.	$\frac{dT_d}{dt} = \left[\left(\frac{4}{3} \right) \left(\frac{\Delta T}{\Delta T_2^*} \right) (\Delta T_2^*)^{1/4} \frac{(1-e^{-Y})}{[(t/t_2^*)D]} \right] dt$ $\frac{dT_d}{dt} = \text{_____}$
15.	If: 1. $T_d > T_s$ 2. $T_d < T_s$ 3. $T_d = T_s$	Repeat Procedure Using Design 1. a larger r 2. a smaller r 3. $s = 1.41 \times r = \text{_____}\text{ m}$ Analysis 1. a larger t_f 2. a smaller t_f 3. $t_f = \text{_____}\text{ sec}$

FIGURE B.3.3.4.4 Fire Detection Design and Analysis Worksheet. [28]

B.3.3.6.6.1 The fire scenario involving the ignition of a stack of wood pallets will therefore be evaluated. The pallets are stored 0.5 m (1.5 ft) high. Fire test data [see Table B.2.3.2.6.2(a)] indicate that this type of fire follows the t^2 power law equation with a t_g equal to approximately 150 to 310 seconds. To be conservative, the faster fire growth rate will be used. Thus, using Equation B.3.3.4,

$$Q = \alpha t^p$$

$$1055 \text{ kW} = (\alpha \text{ kW/sec}^2)(150 \text{ sec})^2$$

$$\alpha = 0.047 \text{ kW/sec}^2$$

or

$$Q = \alpha t^p$$

$$1000 \text{ Btu/sec} = (\alpha \text{ Btu/sec}^3)(150 \text{ sec})^2$$

$$\alpha = 0.044 \text{ Btu/sec}^3$$

Note that the variables are identified in Section B.7.

B.3.3.6.6.2 Using the power law growth equation with $p = 2$, the time after open flaming until the fire grows to 10,000 kW (9478 Btu/sec) can be calculated as follows:

$$Q = \left(\frac{1055}{t_g^2} \right) t_{DO}^2 = \alpha t^2 \quad (\text{for SI units})$$

or

$$Q = \left(\frac{1000}{t_g^2} \right) t_{DO}^2 = \alpha t^2 \quad (\text{for inch-pound units})$$

$$t_{DO} = 461 \text{ seconds}$$

Note that the variables are identified in Section B.7.

B.3.3.6.6.3 The critical heat release rate and time to detection can therefore be calculated as follows, assuming t_{respond} equals the 5.25 minutes necessary for the fire brigade to respond to the alarm and begin discharging water:

$$t_{CR} = t_{DO} - t_{\text{respond}}$$

$$t_{CR} = 461 - 315 = 146 \text{ seconds}$$

and thus

$$Q_{CR} = \alpha t_{CR}^2$$

$$Q_{CR} = 1000 \text{ kW (948 Btu/sec)}$$

Note that the variables are identified in Section B.7.

B.3.3.7 Develop Candidate Designs.

B.3.3.7.1 Fixed-temperature heat detectors have been selected for installation in the warehouse with a 57°C (135°F) operating temperature and a UL-listed spacing of 9.1 m (30 ft). From Table B.3.2.5, the time constant is determined to be 80 seconds when referenced to a gas velocity of 1.5 m/sec (5 ft/sec). When used with Equation B.3.3.7, the detector's RTI can be calculated as follows:

$$RTI = \tau_0 u_0^{1/2}$$

$$RTI = 98 \text{ m}^{1/2} \text{ sec}^{1/2}$$

or

$$RTI = 179 \text{ ft}^{1/2} \text{ sec}^{1/2}$$

B.3.3.7.2 To begin calculations, it will be necessary to make a first guess at the required detector spacing. For this example, a first estimate of 4.7 m (15.3 ft) is used. This correlates to a radial distance of 3.3 m (10.8 ft).

B.3.3.8 Evaluate Candidate Designs. These values can then be entered into the design and analysis worksheet shown in Figure B.3.3.8 in order to evaluate the candidate design.

B.3.3.8.1 After 146 seconds, when the fire has grown to 1000 kW (948 Btu/sec) and at a radial distance of 3.3 m (10.8 ft) from the center of the fire, the detector temperature is calculated to be 57°C (135°F). This is the detector actuation temperature. If the calculated temperature of the detector were higher than the actuation temperature, the radial distance could be increased. The calculation would then be repeated until the calculated detector temperature is approximately equal to the actuation temperature.

B.3.3.8.2 The last step is to use the final calculated value of r with the equation relating spacing to radial distance. This will determine the maximum installed detector spacing that will result in detector response within the established goals.

$$S = 9^{1/2} r$$

$$S = 4.7 \text{ m (15.3 ft)}$$

where:

S = spacing of detectors

r = radial distance from fire plume axis (m or ft)

Fire Detection Design and Analysis Worksheet [28]

Design Example

1.	Determine ambient temperature (T_a) ceiling height or height above fuel (H).	$T_a = 10$ °C + 273 = <u>283</u> K $H = 4$ m
2.	Determine the fire growth characteristic (α or t_g) for the expected design fire.	$\alpha = 0.047$ kW/sec ² $t_g = 150$ sec
3a.	Define the characteristics of the detectors.	$T_s = 57$ °C + 273 = <u>330</u> K RTI = <u>98</u> m ^{1/2} sec ^{1/2} $\frac{dT_d}{dt} =$ °C/min $\tau_0 =$ sec
3b.	<i>Design</i> — Establish system goals (t_{CR} or Q_{CR}) and make a first estimate of the distance (r) from the fire to the detector.	$t_{CR} = 146$ sec $r = 3.3$ m $Q_{CR} = 1000$ kW
3b.	<i>Analysis</i> — Determine spacing of existing detectors and make a first estimate of the response time or the fire size at detector response ($Q = \alpha t^2$).	$r =$ *1.41 = <u> </u> = S (m) $Q =$ kW $t_d =$ sec
4.	Using equation B.3.3.4.2a, calculate the non-dimensional time (t_{2f}^*) at which the initial heat front reaches the detector.	$t_{2f}^* = 0.861 \left(1 + \frac{r}{H}\right)$ $t_{2f}^* = 1.57$
5.	Calculate the factor A defined by the relationship for A in equation B.3.3.4.1d.	$A = \frac{g}{C_p T_a \rho_a}$ $A = 0.030$
6.	Use the required response time (t_{CR}) along with the relationship for t_p^* in equation B.3.3.4.1c and $p = 2$ to calculate the corresponding value of t_2^* .	$t_2^* = \frac{t_{CR}}{A^{-1/(3+p)} \alpha^{-1/(3+p)} H^{4/(3+p)}}$ $t_2^* = 12.98$
7.	If $t_2^* > t_{2f}^*$, continue to step 8. If not, try a new detector position (r) and return to step 4.	
8.	Calculate the ratio $\frac{u}{u_2^*}$ using the relationship for U_p in equation B.3.3.4.1a.	$\frac{u}{u_2^*} = A^{1/(3+p)} \alpha^{1/(3+p)} H^{(p-1)/(3+p)}$ $\frac{u}{u_2^*} = 0.356$
9.	Calculate the ratio $\frac{\Delta T}{\Delta T_2^*}$ using the relationship for ΔT_p in equation B.3.3.4.1b.	$\frac{\Delta T}{\Delta T_2^*} = A^{2/(3+p)} (T_a/g) \alpha^{2/(3+p)} H^{-(5-p)/(3+p)}$ $\frac{\Delta T}{\Delta T_2^*} = 0.913$
10.	Use the relationship for ΔT_2^* in equation B.3.3.4.2c to calculate ΔT_2^* .	$\Delta T_2^* = \left[\frac{t_2^* - t_{2f}^*}{(0.146 + 0.242r/H)} \right]^{4/3}$ $\Delta T_2^* = 105.89$
11.	Use the relationship for $\frac{u_2^*}{(\Delta T_2^*)^{1/2}}$ in equation B.3.3.4.2d to calculate the ratio $\frac{u_2^*}{(\Delta T_2^*)^{1/2}}$.	$\frac{u_2^*}{(\Delta T_2^*)^{1/2}} = 0.59 \left(\frac{r}{H} \right)^{-0.63}$ $\frac{u_2^*}{(\Delta T_2^*)^{1/2}} = 0.66$
12.	Use the relationships for Y and D in equations B.3.3.4.3c and B.3.3.4.3d to calculate Y .	$Y = \left(\frac{3}{4} \right) \left(\frac{u}{u_2^*} \right)^{1/2} \left[\frac{u_2^*}{(\Delta T_2^*)^{1/2}} \right]^{1/2} \left(\frac{\Delta T_2^*}{RTI} \right) \left(\frac{t}{t_2^*} \right) D$ $Y = 1.533$
13.	<i>Fixed Temperature HD</i> — Use the relationship for $T_d(t) - T_d(0)$ in equation B.3.3.4.3a to calculate the resulting temperature of the detector $T_d(t)$.	$T_d(t) = \left(\frac{\Delta T}{\Delta T_2^*} \right) \Delta T_2^* \left[1 - \frac{(1-e^{-Y})}{Y} \right] + T_d(0)$ $T_d(t) = 57.25$
14.	<i>Rate of Rise HD</i> — Use the relationship for $\frac{dT_d(t)}{dt}$ in equation B.3.3.4.3b.	$dT_d = \left[\left(\frac{4}{3} \right) \left(\frac{\Delta T}{\Delta T_2^*} \right) (\Delta T_2^*)^{1/4} \frac{(1-e^{-Y})}{[(t/t_2^*)D]} \right] dt$ $dT_d =$
15.	If: 1. $T_d > T_s$ 2. $T_d < T_s$ 3. $T_d = T_s$	Repeat Procedure Using Design 1. a larger r 2. a smaller r 3. $s = 1.41 \times r = 4.7$ m Analysis 1. a larger t_p 2. a smaller t_p 3. $t_p =$ sec

FIGURE B.3.3.8 Fire Detection Design and Analysis Worksheet [28] — Design Example.

B.3.3.8.3 The following example of analysis is provided.

B.3.3.8.3.1 The following example shows how an existing heat detection system or a proposed design can be analyzed to determine the response time or fire size at response. The scenario that was analyzed in the previous example will be used again, with the exception that the warehouse building has existing heat detectors. The fire, building, and detectors have the same characteristics as the previous example with the exception of spacing. The detectors are spaced evenly on the ceiling at 9.1 m (30 ft) intervals.

B.3.3.8.3.2 The following equation is used to determine the maximum radial distance from the fire axis to a detector:

$$S = 1.414r \quad [\text{B.3.3.8.3.2a}]$$

or

$$r = \frac{S}{1.414} \quad [\text{B.3.3.8.3.2b}]$$

$$r = 6.5 \text{ m (21.2 ft)}$$

where:

S = spacing of detectors

r = radial distance from fire plume axis (m or ft)

B.3.3.8.3.3 Next, the response time of the detector or the fire size at response is estimated. In the preceding design, the fire grew to 1000 kW (948 Btu/sec) in 146 seconds when the detector located at a distance of 3.3 m (10.8 ft) responded. As the radial distance in this example is larger, a slower response time and thus a larger fire size at response is expected. A first approximation at the response time is made at 3 minutes. The corresponding fire size is found using the power law fire growth equation B.3.3.4 with $p = 2$ and α from B.3.3.6.6.1:

$$Q = \alpha t^p \quad [\text{B.3.3.8.3.3a}]$$

$$Q = (0.047 \text{ kW/sec}^2)(180 \text{ sec})^2$$

$$Q = 1523 \text{ kW}$$

or

$$Q = (0.044 \text{ Btu/sec}^3)(180 \text{ sec})^2 \quad [\text{B.3.3.8.3.3b}]$$

$$Q = 1426 \text{ Btu/sec}$$

B.3.3.8.3.4 These data can be incorporated into the fire detection design and analysis worksheet shown in Figure B.3.3.8.3.4 in order to carry out the remainder of the calculations.

B.3.3.8.3.5 Using a radial distance of 6.5 m (21 ft) from the axis of this fire, the temperature of the detector is calculated to

be 41°C (106°F) after 3 minutes of exposure. The detector actuation temperature is 57°C (135°F). Thus, the detector response time is more than the estimated 3 minutes. If the calculated temperature were more than the actuation temperature, then a smaller t would be used. As in the previous example, calculations should be repeated varying the time to response until the calculated detector temperature is approximately equal to the actuation temperature. For this example, the response time is estimated to be 213 seconds. This corresponds to a fire size at response of 2132 kW (2022 Btu/sec).

B.3.3.8.4 The preceding examples assume that the fire continues to follow the t -squared fire growth relationship up to detector activation. These calculations do not check whether this will happen, nor do they show how the detector temperature varies once the fire stops following the power law relationship. The user should therefore determine that there will be sufficient fuel, since the preceding correlations do not perform this analysis. If there is not a sufficient amount of fuel, then there is the possibility that the heat release rate curve will flatten out or decline before the heat release rate needed for actuation is reached.

B.3.3.8.5 Table B.3.3.8.5(a) through Table B.3.3.8.5(k) provide a comparison of heat release rates, response times, and spacings when variables characteristic of the fires, detectors, and room are changed from the analysis example.

B.3.3.9 Rate-of-Rise Heat Detector Spacing.

B.3.3.9.1 The preceding procedure can be used to estimate the response of rate-of-rise heat detectors for either design or analysis purposes. In this case, it is necessary to assume that the heat detector response can be modeled using a lumped mass heat transfer model.

B.3.3.9.2 In step 3 of Figure B.3.3.4.4, Figure B.3.3.8, and Figure B.3.3.8.3.4, the user must determine the rate of temperature rise (dT_d/dt) at which the detector will respond from the manufacturer's data. [Note that listed rate-of-rise heat detectors are designed to actuate at a nominal rate of temperature rise of 8°C (15°F) per minute.] The user must use the relationship for $dT_d(t)/dt$ in Equation B.3.3.4.3b instead of the relationship for $T_d(t) - T_d(0)$ in Equation B.3.3.4.3a in order to calculate the rate of change of the detector temperature. This value is then compared to the rate of change at which the chosen detector is designed to respond.

NOTE: The assumption that heat transfer to a detector can be modeled as a lumped mass might not hold for rate-of-rise heat detectors. This is due to the operating principle of this type of detector, in that most rate-of-rise detectors operate when the expansion of air in a chamber expands at a rate faster than it can vent through an opening. To accurately model the response of a rate-of-rise detector would require modeling the heat transfer from the detector body to the air in the chamber, as well as the air venting through the hole.

B.3.3.10 Rate Compensation-Type Heat Detectors. Rate-compensated detectors are not specifically covered by Annex B. However, a conservative approach to predicting their performance is to use the fixed-temperature heat detector guidance contained herein.

Fire Detection Design and Analysis Worksheet [28]

Design Analysis 2

1.	Determine ambient temperature (T_a) ceiling height or height above fuel (H).	$T_a = 10$ °C + 273 = 283 K $H = 4$ m
2.	Determine the fire growth characteristic (α or t_g) for the expected design fire.	$\alpha = 0.047$ kW/sec ² $t_g = 150$ sec
3a.	Define the characteristics of the detectors.	$T_s = 57$ °C + 273 = 330 K $RTI = 98$ m ^{1/2} sec ^{1/2} $\frac{dT_d}{dt} =$ °C/min $\tau_0 =$ sec
3b.	<i>Design</i> — Establish system goals (t_{CR} or Q_{CR}) and make a first estimate of the distance (r) from the fire to the detector.	$t_{CR} =$ sec $r =$ m $Q_{CR} =$ kW
3b.	<i>Analysis</i> — Determine spacing of existing detectors and make a first estimate of the response time or the fire size at detector response ($Q = \alpha t^2$).	$r = 6.5$ * 1.41 = 9.2 = S (m) $Q = 1,523$ kW $t_d = 180$ sec
4.	Using equation B.3.3.4.2a, calculate the non-dimensional time (t_{2f}^*) at which the initial heat front reaches the detector.	$t_{2f}^* = 0.861 \left(1 + \frac{r}{H}\right)$ $t_{2f}^* = 2.26$
5.	Calculate the factor A defined by the relationship for A in equation B.3.3.4.1d.	$A = \frac{g}{C_p T_a \rho_o}$ $A = 0.030$
6.	Use the required response time (t_{CR}) along with the relationship for t_p^* in equation B.3.3.4.1c and $p = 2$ to calculate the corresponding value of t_2^* .	$t_2^* = \frac{t_{CR}}{A^{-1/(3+p)} \alpha^{-1/(3+p)} H^{4/(3+p)}}$ $t_2^* = 16$
7.	If $t_2^* > t_{2f}^*$, continue to step 8. If not, try a new detector position (r) and return to step 4.	
8.	Calculate the ratio $\frac{u}{u_2^*}$ using the relationship for U_p^* in equation B.3.3.4.1a.	$\frac{u}{u_2^*} = A^{1/(3+p)} \alpha^{1/(3+p)} H^{(p-1)/(3+p)}$ $\frac{u}{u_2^*} = 0.356$
9.	Calculate the ratio $\frac{\Delta T}{\Delta T_2^*}$ using the relationship for ΔT_p^* in equation B.3.3.4.1b.	$\frac{\Delta T}{\Delta T_2^*} = A^{2/(3+p)} (T_a/g) \alpha^{2/(3+p)} H^{-(5-p)/(3+p)}$ $\frac{\Delta T}{\Delta T_2^*} = 0.913$
10.	Use the relationship for ΔT_2^* in equation B.3.3.4.2c to calculate ΔT_2^* .	$\Delta T_2^* = \left[\frac{t_2^* - t_{2f}^*}{(0.146 + 0.242r/H)} \right]^{4/3}$ $\Delta T_2^* = 75.01$
11.	Use the relationship for $\frac{u_2^*}{(\Delta T_2^*)^{1/2}}$ in equation B.3.3.4.2d to calculate the ratio $\frac{u_2^*}{(\Delta T_2^*)^{1/2}}$.	$\frac{u_2^*}{(\Delta T_2^*)^{1/2}} = 0.59 \left(\frac{r}{H} \right)^{-0.63}$ $\frac{u_2^*}{(\Delta T_2^*)^{1/2}} = 0.435$
12.	Use the relationships for Y and D in equations B.3.3.4.3c and B.3.3.4.3d to calculate Y .	$Y = \left(\frac{3}{4} \right) \left(\frac{u}{u_2^*} \right)^{1/2} \left[\frac{u_2^*}{(\Delta T_2^*)^{1/2}} \right]^{1/2} \left(\frac{\Delta T_2^*}{RTI} \right) \left(\frac{t}{t_2^*} \right) D$ $Y = 1.37$
13.	<i>Fixed Temperature HD</i> — Use the relationship for $T_d(t) - T_d(0)$ in equation B.3.3.4.3a to calculate the resulting temperature of the detector $T_d(t)$.	$T_d(t) = \left(\frac{\Delta T}{\Delta T_2^*} \right) \Delta T_2^* \left[1 - \frac{(1 - e^{-Y})}{Y} \right] + T_d(0)$ $T_d(t) = 41$
14.	<i>Rate of Rise HD</i> — Use the relationship for $\frac{dT_d(t)}{dt}$ in equation B.3.3.4.3b.	$dT_d = \left[\left(\frac{4}{3} \right) \left(\frac{\Delta T}{\Delta T_2^*} \right) (\Delta T_2^*)^{1/4} \frac{(1 - e^{-Y})}{[(t/t_2^*)D]} \right] dt$ $dT_d =$
15.	If: 1. $T_d > T_s$ 2. $T_d < T_s$ 3. $T_d = T_s$	Repeat Procedure Using Design 1. a larger r 2. a smaller r 3. $s = 1.41 \times r =$ m Analysis 1. a larger t_r 2. a smaller t_r 3. $t_r =$ sec

FIGURE B.3.3.8.3.4 Fire Detection Design and Analysis Worksheet [28] — Analysis Example 2.

Table B.3.3.8.5(a) Operating Temperature Versus Heat Transfer Rate [S = 9.1 m (30 ft)]

Operating Temperature		Heat Release Rate/ Response Time	
°C	°F	kW/sec	Btu/sec/sec
57	135	2132/213	2022/213
74	165	2798/244	2654/244
93	200	3554/275	3371/275

Table B.3.3.8.5(b) Operating Temperature Versus Spacing [Qd = 1000 kW (948 Btu/sec)]

Operating Temperature		Spacing	
°C	°F	m	ft
57	135	4.7	15.4
74	165	3.5	11.5
93	200	2.5	8.2

Table B.3.3.8.5(c) RTI Versus Heat Release Rate [S = 9.1 m (30 ft)]

RTI		Heat Release Rate/ Response Time	
m ^{1/2} sec ^{1/2}	ft ^{1/2} sec ^{1/2}	kW/sec	Btu/sec/sec
50	93	1609/185	1526/185
150	280	2640/237	2504/237
300	560	3898/288	3697/288

Table B.3.3.8.5(d) RTI Versus Spacing [Qd = 1000 kW (948 Btu/sec)]

RTI		Spacing	
m ^{1/2} sec ^{1/2}	ft ^{1/2} sec ^{1/2}	m	ft
50	93	6.1	20.0
150	280	3.7	12.1
300	560	2.3	7.6

Table B.3.3.8.5(e) Ambient Temperature Versus Heat Release Rate [S = 9.1 m (30 ft)]

Ambient Temperature		Heat Release Rate/ Response Time	
°C	°F	kW/sec	Btu/sec/sec
0	32	2552/233	2420/233
20	68	1751/193	1661/193
38	100	1058/150	1004/150

Table B.3.3.8.5(f) Ambient Temperature Versus Spacing [Qd = 1000 kW (948 Btu/sec)]

Ambient Temperature		Spacing	
°C	°F	m	ft
0	32	3.8	12.5
20	68	5.7	18.7
38	100	8.8	28.9

Table B.3.3.8.5(g) Ceiling Height Versus Heat Release Rate [S = 9.1 m (30 ft)]

Ceiling Height		Heat Release Rate/ Response Time	
m	ft	kW/sec	Btu/sec/sec
2.4	8	1787/195	1695/195
4.9	16	2358/224	2237/224
7.3	24	3056/255	2899/255

Table B.3.3.8.5(h) Ceiling Height Versus Spacing [Qd = 1000 kW (948 Btu/sec)]

Ceiling Height		Spacing	
m	ft	m	ft
2.4	8	5.8	19.0
4.9	16	4.0	13.1
7.3	24	2.1	6.9

Table B.3.3.8.5(i) Detector Spacing Versus Heat Release Rate [S = 9.1 m (30 ft)]

Detector Spacing		Heat Release Rate/ Response Time	
m	ft	kW/sec	Btu/sec/sec
4.6	15	1000/146	949/146
9.1	30	2132/213	2022/213
15.2	50	4146/297	3932/297

Table B.3.3.8.5(j) Fire Growth Rate Versus Heat Release Rate [S = 9.1 m (30 ft)]

Heat Release Rate/ Response Time		
Fire Growth Rate	kW/sec	Btu/sec/sec
Slow $t_g = 400$ sec	1250/435	1186/435
Medium $t_g = 250$ sec	1582/306	1499/306
Fast $t_g = 100$ sec	2769/162	2626/162

Table B.3.3.8.5(k) Fire Growth Rate Versus Spacing
[$Q_d = 1000 \text{ kW}$ (948 Btu/sec)]

Fire Growth Rate	Spacing	
	m	ft
Slow, $t_g = 400 \text{ sec}$	8.2	26.9
Medium, $t_g = 250 \text{ sec}$	6.5	21.3
Fast, $t_g = 100 \text{ sec}$	3.7	12.1

B.4 Smoke Detector Spacing for Flaming Fires.

B.4.1 Introduction.

B.4.1.1 The listing investigation for smoke detectors does not yield a “listed spacing” as it does for heat detectors. Instead, the manufacturers recommend a spacing. Because the largest spacing that can be evaluated in the full-scale fire test room is 7.6 m (25 ft), it has become common practice to recommend 9.1 m (30 ft) spacing for smoke detectors when they are installed on flat, smooth ceilings. Reductions in smoke detector spacing are made empirically to address factors that can affect response, including ceiling height, beamed or joisted ceilings, and areas that have high rates of air movement.

B.4.1.2 The placement of smoke detectors, however, should be based on an understanding of fire plume and ceiling jet flows, smoke production rates, particulate changes due to aging, and the operating characteristics of the particular detector being used. The heat detector spacing information presented in Section B.3 is based on knowledge of plume and jet flows. An understanding of smoke production and aging lags considerably behind an understanding of heat production. In addition, the operating characteristics of smoke detectors in specific fire environments are not often measured or made generally available for other than a very few number of combustible materials. Therefore, the existing knowledge base precludes the development of complete engineering design information for smoke detector location and spacing.

B.4.1.3 In design applications where predicting the response of smoke detectors is not critical, the spacing criteria presented in Chapter 17 should provide sufficient information to design a very basic smoke detection system. However, if the goals and objectives established for the detection system require detector response within a certain amount of time, optical density, heat release rate, or temperature rise, then additional analysis might be needed. For these situations, information regarding the expected fire characteristics (fuel and its fire growth rate), transport characteristics, detector characteristics, and compartment characteristics is required. The following information regarding smoke detector response and various performance-based approaches to evaluating smoke detector response is therefore provided.

B.4.2 Response Characteristics of Smoke Detectors. To determine whether a smoke detector will respond to a given Q_{OR} , a number of factors need to be evaluated. These factors include smoke characteristics, smoke transport, and detector characteristics.

B.4.3 Smoke Characteristics.

B.4.3.1 Smoke characteristics are a function of the fuel composition, the mode of combustion (smoldering or flaming), and the amount of mixing with the ambient air (dilu-

tion). These factors are important for determining the characteristics of the products of combustion, such as particle size, distribution, composition, concentration, refractive index, and so on. The significance of these features with regard to smoke detector response is well documented. [29, 30]

B.4.3.2 Whether smoke detectors detect by sensing scattered light, loss of light transmission (light extinction), or reduction of ion current, they are particle detectors. Thus, particle concentration, size, color, size distribution, and so forth, affect each sensing technology differently. It is generally accepted that a flaming, well-ventilated, energetic fire produces smoke having a larger proportion of the sub-micron diameter particulates as opposed to a smoldering fire that produces smoke with a predominance of large, super-micron particulates. It is also known that as the smoke cools, the smaller particles agglomerate, forming larger ones as they age, and are carried away from the fire source. More research is necessary to provide sufficient data to allow the prediction of smoke characteristics at the source, as well as during transport. Furthermore, response models must be developed that can predict the response of a particular detector to different kinds of smoke as well as smoke that has aged during the flow from the fire to the detector location.

B.4.4 Transport Considerations.

B.4.4.1 All smoke detection relies on the plume and ceiling jet flows to transport the smoke from the locus of the fire to the detector. Various considerations must be addressed during this transport time, including changes to the characteristics of the smoke that occur with time and distance from the source, and transport time of smoke from the source to the detector.

B.4.4.2 The smoke characteristic changes that occur during transport relate mainly to the particle size distribution. Particle size changes during transport occur mainly as a result of sedimentation and agglomeration.

B.4.4.3 Transport time is a function of the characteristics of the travel path from the source to the detector. Important characteristics that should be considered include ceiling height and configuration (e.g., sloped, beamed), intervening barriers such as doors and beams, as well as dilution and buoyancy effects such as stratification that might delay or prevent smoke in being transported to the detector.

B.4.4.4 In smoldering fires, thermal energy provides a force for transporting smoke particles to the smoke sensor. However, usually in the context of smoke detection, the rate of energy (heat) release is small and the rate of growth of the fire is slow. Consequently, other factors such as ambient airflow from HVAC systems, differential solar heating of the structure, and wind cooling of the structure can have a dominant influence on the transport of smoke particles to the smoke sensor when low-output fires are considered.

B.4.4.5 In the early stages of development of a growing fire, the same interior environmental effects, including ambient airflow from HVAC systems, differential solar heating of the structure, and wind cooling of the structure, can have a dominant influence on the transport of smoke. This is particularly important in spaces having high ceilings. Greater thermal energy release from the fire is necessary to overcome these interior environmental effects. Because the fire must attain a sufficiently high level of heat release before it can overcome the interior environmental airflows and drive the smoke to the

ceiling-mounted detectors, the use of closer spacing of smoke detectors on the ceiling might not significantly improve the response of the detectors to the fire. Therefore, when considering ceiling height alone, smoke detector spacing closer than 9.1 m (30 ft) might not be warranted, except in instances where an engineering analysis indicates additional benefit will result. Other construction characteristics also should be considered. (Refer to the appropriate sections of Chapter 17 dealing with smoke detectors and their use for the control of smoke spread.)

B.4.5 Smoke Dilution. Smoke dilution causes a reduction in the quantity of smoke per unit of air volume of smoke reaching the detector. Dilution typically occurs either by entrainment of air in the plume or the ceiling jet or by effects of HVAC systems. Forced ventilation systems with high air change rates typically cause the most concern, particularly in the early stages of fire development, when smoke production rate and plume velocity are both low. Airflows from supply as well as return vents can create defined air movement patterns within a compartment, which can either keep smoke away from detectors that are located outside of these paths or can inhibit smoke from entering a detector that is located directly in the airflow path. [26]

There currently are no quantitative methods for estimating either smoke dilution or airflow effects on locating smoke detectors. These factors should therefore be considered qualitatively. The designer should understand that the effects of airflow become larger as the fire size at detection (Q_{CR}) gets smaller. Depending on the application, the designer might find it useful to obtain airflow and velocity profiles within the room or to even conduct small-scale smoke tests under various conditions to assist in the design of the system.

B.4.6 Stratification.

B.4.6.1 The potential for the stratification of smoke is another concern in designing and analyzing the response of detectors. This is of particular concern with the detection of low-energy fires and fires in compartments with high ceilings.

B.4.6.2 The upward movement of smoke in the plume depends on the smoke being buoyant relative to the surrounding air. Stratification occurs when the smoke or hot gases flowing from the fire fail to ascend to the smoke detectors mounted at a particular level (usually on the ceiling) above the fire due to the loss of buoyancy. This phenomenon occurs due to the continuous entrainment of cooler air into the fire plume as it rises, resulting in cooling of the smoke and fire plume gases. The cooling of the plume results in a reduction in buoyancy. Eventually the plume cools to a point where its temperature equals that of the surrounding air and its buoyancy diminishes to zero. Once this point of equilibrium is reached, the smoke will cease its upward flow and form a layer, maintaining its height above the fire, regardless of the ceiling height, unless and until sufficient additional thermal energy is provided from the fire to raise the layer due to its increased buoyancy. The maximum height to which plume fluid (smoke) will ascend, especially early in the development of a fire, depends on the convective heat release rate of the fire and the ambient temperature in the compartment.

B.4.6.3 Because warm air rises, there will usually be a temperature gradient in the compartment. Of particular interest are those cases where the temperature of the air in the upper portion of the compartment is greater than at the lower level before the ignition. This can occur as a result of solar load

where ceilings contain glazing materials. Computational methods are available to assess the potential for intermediate stratification for the following two cases, depicted in Figure B.4.6.3(a).

Case 1. The temperature of the ambient is relatively constant up to a height above which there is a layer of warm air at uniform temperature. This situation can occur if the upper portion of a mall, atrium, or other large space is unoccupied and the air is left unconditioned.

Case 2. The ambient interior air of the compartment has a constant and uniform temperature gradient (temperature change per unit height) from floor to ceiling. This case is generally encountered in industrial and storage facilities that are normally unoccupied.

The analysis of intermediate stratification is presented in Figure B.4.6.3(b). Plume centerline temperatures from two fires, 1000 kW (948 Btu/sec) and 2000 kW (1896 Btu/sec), are graphed based on estimates from correlations presented in this section. In Case 1, a step function is assumed to indicate a $30^{\circ}\text{C}/\text{m}$ ($16.5^{\circ}\text{F}/\text{ft}$) change in temperature 15 m (49.2 ft) above the floor due to the upper portion of the atrium being unconditioned. For Case 2, a temperature gradient of $1.5^{\circ}\text{C}/\text{m}$ ($0.82^{\circ}\text{F}/\text{ft}$) is arbitrarily assumed in an atrium that has a ceiling height of 20 m (65.6 ft).

B.4.6.3.1 Step Function Temperature Gradient Spaces. If the interior air temperature exhibits a discrete change at some elevation above the floor, the potential for stratification can be assessed by applying the plume centerline temperature correlation. If the plume centerline temperature is equal to the ambient temperature, the plume is no longer buoyant, loses its




FIGURE B.4.6.3(a) Pre-Fire Temperature Profiles.




FIGURE B.4.6.3(b) Indoor Air and Plume Temperature Profiles with Potential for Intermediate Stratification.

upward momentum, and stratifies at that height. The plume centerline temperature can be calculated by using the following equation:

$$T_i = 25 Q^{2/3} z^{-5/3} + 20 \quad (\text{for SI units}) \quad [\text{B.4.6.3.1a}]$$

$$T_i = 316 Q^{2/3} z^{-5/3} + 70 \quad (\text{for inch-pound units}) \quad [\text{B.4.6.3.1b}]$$

where:

T_i = plume centerline temperature ($^{\circ}\text{C}$ or $^{\circ}\text{F}$)

Q = convective portion of fire heat release rate (kW or Btu/sec)

z = height above the top of the fuel package involved (m or ft)

B.4.6.3.2 Linear Temperature Gradient Spaces. To determine whether or not the rising smoke or heat from an axisymmetric fire plume will stratify below detectors, the following equation can be applied where the ambient temperature increases linearly with increasing elevation:

$$Z_m = 5.54 Q^{1/4} \left(\frac{\Delta T_0}{dZ} \right)^{-3/8} \quad (\text{for SI units}) \quad [\text{B.4.6.3.2a}]$$

or

$$Z_m = 14.7 Q^{1/4} \left(\frac{\Delta T_0}{dZ} \right)^{-3/8} \quad (\text{for inch-pound units}) \quad [\text{B.4.6.3.2b}]$$

where:

Z_m = maximum height of smoke rise above the fire surface (m or ft)

ΔT_0 = difference between the ambient temperature at the location of detectors and the ambient temperature at the level of the fire surface ($^{\circ}\text{C}$ or $^{\circ}\text{F}$)

Q = convective portion of the heat release rate (kW or Btu/sec)

B.4.6.3.2.1 The convective portion of the heat release rate (Q) can be estimated as 70 percent of the heat release rate.

B.4.6.3.2.2 As an alternative to using the noted expression to directly calculate the maximum height to which the smoke or heat will rise, Figure B.4.6.3.2.2 can be used to determine Z_m for given fires. Where Z_m , as calculated or determined graphically, is greater than the installed height of detectors, smoke or heat from a rising fire plume is predicted to reach the detectors. Where the compared values of Z_m and the installed height of detectors are comparable heights, the prediction that smoke or heat will reach the detectors might not be a reliable expectation.

B.4.6.3.2.3 Assuming the ambient temperature varies linearly with the height, the minimum Q required to overcome the ambient temperature difference and drive the smoke to the




FIGURE B.4.6.3.2.2 Temperature Change and Maximum Height of Smoke Rise for Given Fire Sizes.

ceiling ($Z_m = H$) can be determined from the following equation:

$$Q = 0.0018 H^{5/2} \Delta T_0^{3/2} \quad (\text{for SI units}) \quad [\text{B.4.6.3.2.3a}]$$

or

$$Q = 2.39 \times 10^{-5} H^{5/2} \Delta T_0^{3/2} \quad (\text{for inch-pound units}) \quad [\text{B.4.6.3.2.3b}]$$

Note that the variables are identified in Section B.7.

B.4.6.3.2.4 The theoretical basis for the stratification calculation is based on the works of Morton, Taylor, and Turner [15] and Heskestad [9]. For further information regarding the derivation of the expression defining Z_m , the user is referred to the work of Klotz and Milke [13] and NFPA 92.

B.4.7 Detector Characteristics.

B.4.7.1 General. Once smoke is transported to the detector, additional factors become important in determining whether response will occur. These include the aerodynamic characteristics of the detector and the type of sensor within the detector. The aerodynamics of the detector relate to how easily smoke can pass through the detector housing and enter the sensor portion of the unit. Additionally, the location of the entry portion to the sensor with respect to the velocity profile of the ceiling jet is also an important factor. Finally, different sensing methods and algorithms will respond differently, depending on the smoke characteristics (e.g., smoke color, particle size, optical density, and so forth). Within the family of photoelectric devices, there will be variations depending on the wavelengths of light and the scattering angles employed. Paragraphs B.4.7.2 through B.4.7.5 discuss some of these issues and various calculation methods.

B.4.7.2 Resistance to Smoke Entry.

B.4.7.2.1 All spot-type smoke detectors require smoke to enter the detection chamber in order to be sensed. This requires additional factors to be taken into consideration when attempt-

ing to estimate smoke detector response, as smoke entry into the detection chamber can be affected in several ways, for example, insect screens, sensing chamber configuration, and location of the detector with respect to the ceiling.

B.4.7.2.2 In trying to quantify this, Heskestad [32] developed the idea of smoke detector lag to explain the difference in optical density outside (D_{uo}) versus inside (D_{ui}) of a detector when the detector actuates. It was demonstrated that this difference could be explained by the use of a correction factor D_{uc} using the following relationship:

[B.4.7.2.2]

$$D_{uc} = \frac{L \frac{d(D_{uo})}{dt}}{V}$$

where:

L = characteristic length for a given detector design, represents the ease of smoke entry into the sensing chamber

$d(D_{uo})/dt$ = rate of increase of optical density outside the detector

V = velocity of the smoke at the detector

B.4.7.2.3 Various studies regarding this correlation have provided additional insight regarding smoke entry and associated lags [33, 34, 34a, 34b, 34c, 34d, 34e]; however, the difficulty in quantifying L for different detectors and relating it to spacing requirements can have limited usefulness, and the concept of critical velocity (u_c) could be more applicable. [21]

B.4.7.3 Critical Velocity. A smoke detector's critical velocity refers to the minimum velocity of the smoke necessary to enter the sensing chamber to cause an alarm without significant delays due to smoke entry lag. Alarms can occur at velocities less than the critical velocity value, but their response can be delayed or require greater smoke concentrations than would normally be necessary. Flow across a detector causes a pressure differential between the upstream and downstream sides of the detector. This pressure differential is the principal driving force for the smoke entering the unit.

Experimental work has indicated that the critical velocity is approximately 0.15 m/sec (0.49 ft/sec) for the ionization detectors tested in one particular study. [21] Once velocities were reduced below this level, the smoke concentration level outside the detector before an alarm condition increased dramatically when compared to smoke concentration levels when the velocity was above the critical value. Another study found that measured velocities at the time of alarm for ionization and photoelectric detectors in full-scale flaming fire tests generally supported this velocity value, with a mean value of 0.13 m/sec (0.43 ft/sec) and a standard deviation of 0.07 m/sec (0.23 ft/sec) [46]. Estimating the critical velocity can therefore be useful for design and analysis.

It is interesting to note that this critical velocity value (0.15 m/sec or 0.49 ft/sec) is close to that at which a smoke detector must respond in the UL smoke detector sensitivity chamber in order to become listed. [35] The location in the ceiling jet where this velocity occurs for a given fire and ceiling height might therefore be considered as a first approximation for locating detectors. This again assumes a horizontal, smooth ceiling. Care should also be taken when using this correlation,

such that consideration is given to potential effects of coagulation and agglomeration, and settling of the smoke within the ceiling jet as it moves away from the fire source and loses its buoyancy. The velocity for smoke entry might be present, but the concentration of smoke might not be sufficient to actuate the detector.

B.4.7.4 Response to Smoke Color. Smoke detectors that use an optical means to detect smoke respond differently to smokes of different colors.

B.4.7.4.1 Manufacturers currently provide limited information regarding the response of smoke detectors in their specifications as well as in the information contained on the labels on the backs of the detectors. This response information indicates only their nominal response values with respect to gray smoke, not to black, and is often provided with a response range instead of an exact response value. This range is in accordance with UL 268, *Smoke Detectors for Fire Alarm Systems*.

B.4.7.4.2 The response ranges allowable by UL for gray smoke are shown in Table B.4.7.4.2. Older editions of UL 268 contained response ranges for black smoke and are also shown for comparison.

B.4.7.4.3 Detectors respond at different optical density levels to different fuels and different types of smoke. Examples of this are shown in Table B.4.7.4.3, which contains values of optical density at response recommended by Heskestad and Delichatsios [10] based on their test.

Note the large variations in response not only to materials producing relatively the same color of smoke but also to smoke of different color, which is much more pronounced. Also note that there was variation in the optical density at response values for a given material in the test conducted by Heskestad and Delichatsios, which is not shown in Table B.4.7.4.3. The values cited in Table B.4.7.4.3 are provided as an example of the variation in optical density at response, but these values are not necessarily appropriate for all analyses. For example, the results presented for polyurethane and PVC involved relatively large, rapidly developing fires, and fires with smaller growth rates could result in smaller values of optical density at response [10]. More information on the variation of optical density at response is available from Geiman and Gottuk [48] and Geiman [46].

B.4.7.5 Optical Density and Temperature. During a flaming fire, smoke detector response is affected by ceiling height and the size and rate of fire growth in much the same way as heat detector response. The thermal energy of the flaming fire transports smoke particles to the sensing chamber just as it does heat to a heat sensor. While the relationship between the amount of smoke and the amount of heat produced by a fire is highly dependent on the fuel and the way it is burning, research has shown that the relationship between temperature and the optical density of smoke remains somewhat constant

Table B.4.7.4.2 UL 268 Smoke Detector Test Acceptance Criteria for Different Colored Smoke [35]

Color of Smoke	Acceptable Response Range	
	%/m	%/ft
Gray	1.6–12.5	0.5–4.0
Black	5.0–29.2	1.5–10.0

Table B.4.7.4.3 Values of Optical Density at Response for Flaming Fires [18]

Material	Optical Density at Response				Relative Smoke Color
	$D_w(\text{m}^{-1})$		$D_w(\text{ft}^{-1})$		
	Ionization	Photoelectric	Ionization	Photoelectric	
Wood crib	0.016	0.049	0.005	0.015	Light
Cotton fabric	0.002	0.026	0.0005	0.008	Light
Polyurethane foam	0.164	0.164	0.05	0.05	Dark
PVC	0.328	0.328	0.1	0.1	Dark
Variation			200:1	12.5:1	

Table B.4.7.5.1 Ratio of Optical Density to Temperature Rise

Material	$D_w/\Delta T [(\text{m}^\circ\text{C})^{-1}]$		$D_w/\Delta T [(\text{ft}^\circ\text{F})^{-1}]$		Maximum: Minimum
	Representative Value	Value Range	Representative Value	Value Range	
Wood (sugar pine, 5% moist)	1.20E-03	8.9E-4–3.2E-3	2.00E-04	1.5E-5–5.5E-4	3.7:1
Cotton (unbleached muslin fabric)	5.9E-4/1.2E-3	3.0E-4–1.8E-3	1.0E-04/2.0E-4	5.0E-5–3.0E-4	6:1
Paper (in trash can)	1.80E-03	Data not available	3.00E-04	Data not available	—
Polyurethane foam	2.40E-03	1.2E-2–3.2E-2	4.00E-04	2.0E-3–5.5E-3	2.8:1
Polyester fiber (bed pillow)	1.80E-02	Data not available	5.0E-3/1.0E-2	Data not available	—
PVC (wire insulation)	3.0E-2/5.9E-2	5.9E-3–5.9E-2	3.00E-03	1.0E-3–1.0E-2	10:1
Foam rubber PU (sofa cushion)	7.70E-02	Data not available	1.30E-02	Data not available	—
Average	2.10E-02	3.0E-4–7.7E-2	3.60E-03	5.0E-05–1.3E-2	260:1

within the fire plume and on the ceiling in the proximity of the plume.

B.4.7.5.1 These results were based on the work by Heskestad and Delichatsios [10] and are indicated in Table B.4.7.5.1. Note that for a given fuel, the optical density to temperature rise ratio between the maximum and minimum levels is 10 or less.

B.4.7.5.2 In situations where the optical density at detector response is known and is independent of particle size distribution, the detector response can be approximated as a function of the heat release rate of the burning fuel, the fire growth rate, and the ceiling height, assuming that the preceding correlation exists.

B.4.7.5.3 When Appendix C of NFPA 72E [58] was first published in 1984, a 13°C (20°F) temperature rise was used to indicate detector response. Schifiliti and Pucci [18] have combined some of the data from Heskestad and Delichatsios [10] to produce Table B.4.7.5.3 showing the temperature rise at detector response. Note that the temperature rise associated with detector response varies significantly depending on the detector type and fuel.

Also note that the values in Table B.4.7.5.3 are not based on temperature measurements taken at the detector response times, but were calculated by Heskestad and Delichatsios [10] from their recommended values of optical density at response (Table B.4.7.4.3) and their recommended ratios of optical density to temperature rise (Table B.4.7.5.1).

Several experimental studies have cited temperature rises at detection as low as 1°C to 3°C (1.8°F to 5.4°F). Of particular note, Geiman [46] found that for flaming fires, 80 percent of

Table B.4.7.5.3 Temperature Rise for Detector Response [18]

Material	Ionization Temperature Rise		Scattering Temperature Rise	
	°C	°F	°C	°F
Wood	13.9	25	41.7	75
Cotton	1.7	3	27.8	50
Polyurethane	7.2	13	7.2	13
PVC	7.2	13	7.2	13
Average	7.8	14	21.1	38

the ionization detectors examined in full-scale smoke detection tests alarmed at measured temperature rises less than or equal to 3°C (5.4°F).

B.4.8 Methods for Estimating Smoke Detector Response.

B.4.8.1 General. There are various methods to estimate smoke detector response. Research is still needed in this area to reflect smoke production, transport to the detector, response of the detector, and performance metrics of the smoke detector. Designers should be aware of the advantages and disadvantages, as well as limitations, of these methods and undertake sensitivity analyses and use of multiple methods where applicable.

B.4.8.1.1 Method 1 — Optical Density Versus Temperature.

B.4.8.1.2 The following example is intended to determine whether an existing fire detection system can detect a fire in part of a warehouse used to store wardrobes in sufficient time to prevent radiant ignition of adjacent wardrobes. The area

under review has a large, flat ceiling, 5 m (16.5 ft) high. The ambient temperature within the compartment is 20°C (68°F). The compartment is not sprinklered. The wardrobes are constructed mainly of particleboard. The detectors are ionization-type smoke detectors spaced 6.1 m (20 ft) on center. The design objective is to keep the maximum heat release rate (Q_{DO}) below 2 MW (1897 Btu/sec) in order to ensure that radiant ignition of the wardrobes in the adjacent aisle will not occur. There is an on-site fire brigade that can respond to and begin discharging water on the fire within 90 seconds of receiving the alarm. It can be assumed that there are no other delays between the time the detector reaches its operating threshold and the time to notification of the fire brigade. Given this information, would the existing system be sufficient?

B.4.8.1.3 The following assumptions are made for this example:

[B.4.8.1.3]

$$\alpha = 0.047 \text{ kW/sec}^2 \text{ (0.044 Btu/sec}^3\text{)}$$

$$RTI = 25 \text{ m}^{1/2}\text{sec}^{1/2} \text{ (45 ft}^{1/2}\text{sec}^{1/2}\text{)}$$

Temperature rise for response = 14°C (25°F)

Refer to Table B.4.7.5.3 for temperature rise to response of an ionization smoke detector for a wood fire.

B.4.8.1.4 Using the power law equation, the design objective response time is calculated as follows:

[B.4.8.1.4a]

$$Q_{DO} = \alpha t_{DO}^2$$

$$2000 \text{ kW} = 0.047 \text{ kW/sec}^2 (t_{DO}^2)$$

$$t_{DO} = 210 \text{ sec}$$

or

[B.4.8.1.4b]

$$1897 \text{ Btu/sec} = 0.044 \text{ Btu/sec}^3 (t_{DO}^2)$$

$$t_{DO} = 210 \text{ sec}$$

B.4.8.1.5 Next, subtract the time for the fire brigade to respond to determine what time after ignition that detection should occur. Note that a 30-second safety factor has been added to the fire brigade's response time.

[B.4.8.1.5]

$$t_{CR} = 210 \text{ sec} - 120 \text{ sec} = 90 \text{ sec}$$

B.4.8.1.6 Then calculate the critical heat release rate at which detection should occur as follows:

[B.4.8.1.6a]

$$Q_{CR} = \alpha t_{CR}^2$$

[B.4.8.1.6b]

$$Q_{CR} = 0.047 \text{ kW/sec}^2 (90 \text{ sec})^2 = 380 \text{ kW}$$

or

$$Q_{CR} = 0.044 \text{ Btu/sec}^3 (90 \text{ sec})^2 = 360 \text{ Btu/sec}$$

B.4.8.1.7 Using the numbers in the fire detection design and analysis worksheet at 90 seconds into the fire when the heat release rate is 380 kW (360 Btu/sec), the temperature rise at the detector is calculated to be approximately 17°C (30.6°F). This, therefore, might be a reasonable approximation to show that the detector might respond.

B.4.8.2 Method 2 — Mass Optical Density.

B.4.8.2.1 Data regarding smoke characteristics for given fuels can be used as another method to evaluate detector response.

B.4.8.2.2 The following example is provided.

The design objective established for this scenario is to detect the smoke from a flaming 400 g (1.0 lb) polyurethane chair cushion in less than 2 minutes. The chair is placed in a compartment that is 40 m² (431 ft²). The ceiling height is 3.0 m (10 ft). It has been determined that the burning rate of the cushion is a steady rate of 50 g/min (0.09 lb/min). Determine whether the design objective will be met.

B.4.8.2.3 The total mass loss of the cushion due to combustion at 2 minutes is 100 g (0.22 lb). Therefore, the optical density in the room produced by the burning cushion can be calculated from the following equation: [5]

[B.4.8.2.3]

$$D = \frac{D_m M}{V_c}$$

where:

D_m = mass optical density (m²/g) [26]

M = mass (g)

V_c = volume of the compartment

$$D = [(0.22 \text{ m}^2/\text{g})(100 \text{ g})] / (40 \text{ m}^2)(3 \text{ m}) = 0.183 \text{ m}^{-1}$$

or where:

D_m = mass optical density (ft²/lb) [26]

M = mass (lb)

V_c = volume of the compartment

$$D = [(1075 \text{ ft}^2/\text{lb})(0.22 \text{ lb})] / (431 \text{ ft}^2)(9.8 \text{ ft}) = 0.056 \text{ ft}^{-1}$$

B.4.8.2.4 If it is assumed that the detector responds at an optical density of 0.15 m⁻¹ (0.046 ft⁻¹), the maximum black smoke optical density allowed in a previous edition of the UL 268 sensitivity test [35], it can be assumed that the detector will respond within 2 minutes.

B.4.8.2.5 It should be noted that this method presents a very simplified approach, and that various assumptions would need to be made including that the smoke is confined to the room, is well mixed, can reach the ceiling, and can enter the detector.

B.4.8.2.6 The preceding estimation assumes that the smoke is evenly distributed throughout the entire compartment volume. This is rarely the case but establishes a very conservative limit. For design purposes, one can model the smoke layer as a cylindrical volume centered about the fire plume having a depth equivalent to the ceiling jet thickness or some multiple of it. Refer to Figure B.4.8.2.6.

The volume of the cylinder can now be used as the solution volume:

$$D = \frac{D_m M}{V_c} \quad [\text{B.4.8.2.6a}]$$

is used with the substitution of

$$V_c = \pi r^2 h \quad [\text{B.4.8.2.6b}]$$

To obtain the maximum radius from the fire plume centerline at which detector response is expected, the nominal 0.14 m^{-1} optical density criterion is substituted into the relation and an explicit relation for r is obtained,

$$r = \left(\frac{D_m M}{0.14 \pi h} \right)^{1/2} \quad [\text{B.4.8.2.6c}]$$

Note that the results of this calculation are highly dependent upon the assumed layer thickness, h . The designer must carefully document the value used for the ceiling jet thickness for this reason. This method does not assume any minimum velocity across the detector, nor does it provide for any delay due to smoke entry. Finally, it assumes uniform smoke concentration throughout the solution volume. Failure to use prudently selected values for ceiling jet thickness and use of this relation outside the limitations imposed by the assumptions can lead to invalid designs.

B.4.8.2.7 The mass optical density method also enables the designer to analyze existing systems. When we accept the assumption that smoke detectors listed by UL will respond at an optical density of 0.14 m^{-1} , we can write the relation:




FIGURE B.4.8.2.6 Smoke Layer Volume Model.

$$D_A = 0.14 = \frac{D_m M}{V_c} \quad [\text{B.4.8.2.7a}]$$

and thus

$$M = D_A \pi r^2 h / D_m \quad [\text{B.4.8.2.7b}]$$

for a cylindrical solution volume.

Since $H(t) = M \Delta H_c$ and $H(t) = (\alpha t^3)/3$, we can write the relation

$$M = \frac{(\alpha t^3)}{3 \Delta H_c} \quad [\text{B.4.8.2.7c}]$$

Substituting, this leads to the relation

$$\frac{(\alpha t^3)}{3 \Delta H_c} = \frac{D_A \pi r^2 h}{D_m} \quad [\text{B.4.8.2.7d}]$$

This relation is reorganized to be explicit in t ,

$$t = \left(\frac{3 D_A \pi r^2 h \Delta H_c}{\alpha D_m} \right)^{1/3} \quad [\text{B.4.8.2.7e}]$$

This time estimate must be corrected for the lag time produced by the resistance to smoke entry of the detector. Currently, this time delay, which is a function of detector design and ceiling jet velocity, is not quantified in the listing process. Consequently, the designer must make an estimate of the time delay due to smoke entry, t_e . Thus, the response time estimate becomes:

$$t = \left(\frac{3 D_A \pi r^2 h \Delta H_c}{\alpha D_m} \right)^{1/3} + t_e \quad [\text{B.4.8.2.7f}]$$

This relation predicts the time at which the mass optical density attains the detector alarm threshold in the solution volume derived from the detector spacing and an assumed ceiling jet thickness. Again, the results of this calculation are highly dependent upon the assumed ceiling jet layer thickness. However, once time, t , is known, if the fire can be characterized as a t -square fire, the fire size can be calculated from the relation

$$Q = \alpha t^2 \quad [\text{B.4.8.2.7g}]$$

Consequently, substitution of this relation into the preceding relation yields the final analytical relation for the heat release rate at alarm, Q_a :

[B.4.8.2.7h]

$$Q_a = \alpha \left[\left(\frac{3D_A \pi r^2 h \Delta H_c}{\alpha D_m} \right)^{1/3} + t_e \right]^2$$

This relation provides an estimate of detector response subject to the assumptions and values selected or the relevant parameters. The estimate can be no better than the data used to generate it.

B.4.8.3 Critical Velocity Method. Research shows that a minimum critical velocity is necessary before smoke can enter the sensing chamber of the smoke detector. (See B.4.7.3.) This method assumes that, if this critical velocity has been attained, sufficient smoke concentration is in the ceiling jet gas flow to produce an alarm signal. Ceiling jet velocity correlations exist for steady-state fires, not t -square fires. However, a t -square fire can be modeled as a succession of steady-state fires for slow and medium growth rate fires. In the UL smoke box test, the minimum flow velocity at the detector is 0.152 m/sec (30 ft/minute). The correlation

[B.4.8.3a]

$$\frac{0.195(Q^{1/3} H^{1/2})}{r^{5/6}} \quad \text{for } r/h \geq 0.15$$

is used. U_c is set to equal 0.152 m/sec. With this substitution the relation becomes:

[B.4.8.3b]

$$r = (1.28 Q^{1/3} H^{1/2})^{6/5}$$

This relation is solved to obtain the maximum distance between the fire plume centerline and the detector at which the critical jet velocity is expected to be obtained for the given convective heat release rate and ceiling height.

B.4.9 Effects of HVAC Systems. The requirement to address the effects of HVAC systems on the performance of smoke detectors was historically reduced to a “3-foot rule.” However, research conducted under the auspices of the Fire Protection Research Foundation showed that such a simple rule was not adequate in many cases.

Theoretically, the effect of HVAC flows on the performance of smoke detectors can be implemented by calculating the flow velocity and smoke concentration at the detector as a function of fire growth and HVAC operating parameters. With complex ceilings this often requires the use of computational fluid dynamics models running in computers. One such model is FDS, developed and supported by NIST.

However, for simple, planar ceilings at heights customarily encountered in conventional construction, the effects of HVAC system can be estimated using a simplified calculation derived from well-known correlations to identify where a problem is likely. These simple calculations are not a substitute for a fully

modeled scenario, but they provide the advantage of being easily executed in a short time frame.

Ceiling-mounted HVAC system supply and return registers are designed to produce specific airflow patterns. The exact shape of the velocity and flow volume profiles is determined by the physical design of the register. A commercially available register might exhibit a flow profile as shown in Figure B.4.9.

This section considers two cases. The first is where the ceiling jet is being acted upon by an HVAC system supply. The second is where the ceiling jet is being acted upon by an HVAC system return. Each case is considered in its bounding value condition to provide a worst-case estimate of the resulting velocity at the detector.

In the first case, the flow of air from the ceiling supply can divert, impede, and dilute the ceiling jet flow, retarding detector response. This effect can be estimated using a one-dimensional vector analysis of the velocity produced by the HVAC system versus that produced by the fire. The velocity profile produced by the HVAC supply register is determined by the design of the register and the flow volume supplied to it. The velocity at the detector produced by the fire is an artifact of the ceiling jet. The sum of these two velocities versus the minimum velocity for response can be used to determine if sufficient ceiling jet velocity exists at the detector to initiate an alarm.

In the second case, the HVAC return pulls air up from lower elevations in the compartment, diluting the smoke density in the ceiling jet in the vicinity of the HVAC return. This case is much more difficult to evaluate because it implies a flow volume analysis to determine when the flow to ceiling-mounted HVAC returns will distort the concentration profile of the ceiling jet to the point that it adversely affects detector response. Unfortunately, the listings of smoke detectors do not include an explicit measurable value for detector sensitivity in terms that can relate to the design fire.

B.4.9.1 Effects of HVAC Ceiling Supply Registers. This method makes use of the finding that there is a critical minimum velocity necessary for reliable smoke detector response. The use of the 30 ft/min (0.15 m/sec) flow velocity in the UL 268 and 217 smoke detector sensitivity test for spot-type smoke detectors has led to the evolution of spot-type smoke detectors that are optimized for that flow velocity. In listing investigations, it has been learned that when the ceiling jet velocity is less than the nominal 30 ft/min (0.15 m/sec) commercially available, listed spot-type smoke detector, performance begins to suffer. (See B.4.7.3.)

For the prediction of spot-type smoke detector response we assume that the ceiling jet velocity at the detector must exceed this critical velocity, 0.15 m/sec (30 ft/min), at the detector.




FIGURE B.4.9 Typical HVAC Flow Patterns in Mercantile and Business Occupancies.

The flow from an HVAC system supply register also produces a flow velocity. When a fire occurs in a room equipped with ceiling-mounted HVAC system supply, the velocity at the detector is the vector sum of the velocity due to the HVAC system supply and the fire ceiling jet.

To estimate the resultant flow velocity at a smoke detector, the flow velocity from the ceiling supply is determined as a function of register design, flow volume, and distance from the supply register. The velocity produced by the ceiling jet is calculated as a function of distance from the fire plume. The worst-case limit condition is where the detector location is where the ceiling jet flow is directly opposite in direction to the flow from the HVAC supply register. Consequently, it is assumed that the ceiling jet is flowing in the opposite direction of the flow from the ceiling register.

The flow of air into a compartment via the HVAC system can be estimated by the flow volume and a flow factor that is related to the flow characteristics of the supply register. See Figure B.4.9.1(a) for an example of such characteristics.

The manufacturer of the ceiling supply register provides a velocity diagram that depicts flow velocity as a function of flow volume for each register it produces. In the U.S., these diagrams generally use conventional feet per minute (FPM) and cubic feet per minute (CFM) units. Since fire protection engineering correlations are generally expressed in metric units, it is necessary to convert the flow volume and flow velocity from the HVAC system to metric units. Replacing CFM with flow volume per unit time this relation becomes:

$$v_r = k(V)/d^2 \text{ m/sec} \quad [\text{B.4.9.1a}]$$

where:

v_r = is the velocity due to the register

The ceiling jet velocity can be modeled with the relation for critical velocity developed by Alpert.

$$v_d = 0.195(Q^{1/3}H^{1/2})/r^{5/6} \text{ m/sec} \quad [\text{B.4.9.1b}]$$

The flow at the detector is the sum of the velocity from the ceiling jet and the ceiling supply register. Since the worst-case scenario is where the fire is located such that the flow of the ceiling jet is directly opposed to the flow from the HVAC supply register, this scenario forms the basis for the analysis as shown in Figure B.4.9.1(b).

The velocity from the ceiling jet is derived from Alpert's correlations.

$$v_d = 0.195(Q^{1/3}H^{1/2})/r^{5/6} \quad [\text{B.4.9.1c}]$$

where:

v_d = ceiling jet velocity at the detector

Q = convective heat release, $0.65 \dot{Q}$

H = ceiling height

r = radius, distance between plume centerline and the detector

All in metric units.

In the case of opposing flows, the resultant velocity at the detector is the ceiling jet velocity minus the velocity due to the flow from the HVAC supply. The relation becomes:

$$v_d = 0.195(Q^{1/3}H^{1/2})/r^{5/6} - k(V)/d^2 \quad [\text{B.4.9.1d}]$$

Smoke detector response can be expected to be consistent with its listing when the value of v_d is greater than or equal to 0.15 m/sec. Thus the relation becomes:

$$0.15 \text{ m/sec} \leq 0.195(Q^{1/3}H^{1/2})/r^{5/6} - k(CFM)/d^2 \quad [\text{B.4.9.1e}]$$

If the right-hand side of the equation B.4.10.1e exceeds the left, the airflow from the HVAC register should not be sufficient to reduce the ceiling jet flow from the fire plume to the point where response by a smoke detector would not be expected. On the other hand, if the calculated resultant velocity is less than the 0.15 m/sec threshold, adjustments should be made to the design to locate the smoke detector where there will be sufficient ceiling jet velocity to predict alarm response.

B.4.9.2 Effects of HVAC Returns. When detectors are in close proximity to ceiling-mounted HVAC return grilles, the flow of air upward toward the return grille tends to dilute and cool the ceiling jet. This tends to retard the response of detectors. Unfortunately the geometry is more complex in this case. The ceiling jet is moving horizontally across the ceiling while the flow toward a ceiling-mounted return grille is essentially moving vertically.

Most ceiling return grilles usually exhibit a flow velocity profile that is roughly hemispherical in shape, centered on the duct centerline. Figure B.4.9.2 illustrates this flow velocity profile.




FIGURE B.4.9.1(a) Typical HVAC Velocity Versus Flow Volume Diagram that Might be Used to Describe Operation of Supply Register.

As the radial distance from the HVAC return increases, the velocity drops off quite rapidly, proportional to 4π times the square of the increase in distance. The relative velocity contributions could be again used to calculate the relative effect, but in this case an explicit sensitivity parameter that relates to the design fire is not available. Percent per foot obscuration cannot be reliably used.

However, the bounding value, worst-case scenario is where the upward velocity is modeled as if it is flowing directly opposite to that of the ceiling jet. This reduces to the same analysis as for the ceiling supply.

These calculations do NOT replace CFD modeling. They are limited only for level ceilings of heights normally encountered in commercial construction. In that limited context they can be used to predict smoke detector performance.

B.5 Radiant Energy Detection.

B.5.1 General.

B.5.1.1 Electromagnetic Radiation. Electromagnetic radiation is emitted over a broad range of the spectrum during the combustion process. The portion of the spectrum in which radiant energy-sensing detectors operate has been divided into three bands: ultraviolet (UV), visible, or infrared (IR). These wavelengths are defined with the following wavelength ranges: [3]

- (1) Ultraviolet 0.1–0.35 microns
- (2) Visible 0.35–0.75 microns
- (3) Infrared 0.75–220 microns




FIGURE B.4.9.1(b) Ceiling Jet Flow in Opposition to Flow from HVAC System.




FIGURE B.4.9.2 Velocity Profile for Ceiling-Mounted Return Grille.

B.5.1.2 Wavelength. These wavelength ranges correspond to the quantum-mechanical interaction between matter and energy. Photonic interactions with matter can be characterized by wavelength as shown in Table B.5.1.2.

Table B.5.1.2 Wavelength Ranges

Wavelength	Photonic Interaction
$\lambda < 50 \text{ micron}$	Gross molecular translations
$50 \text{ }\mu\text{m} < \lambda < 1.0 \text{ }\mu\text{m}$	Molecular vibrations and rotations
$1.0 \text{ }\mu\text{m} < \lambda < 0.05 \text{ }\mu\text{m}$	Valence electron bond vibrations
$0.3 \text{ }\mu\text{m} < \lambda < 0.05 \text{ }\mu\text{m}$	Electron stripping and recombinations

B.5.1.3 Photon Transfer. When a fuel molecule is oxidized in the combustion process, the combustion intermediate molecule must lose energy to become a stable molecular species. This energy is emitted as a photon with a unique wavelength determined by the following equation:

[B.5.1.3]

$$e = \frac{hc}{\lambda}$$

where:
 e = energy (joules)
 h = Planck's constant (6.63E-23 joule-sec)
 c = speed of light (m/sec)
 λ = wavelength (microns)

[1.0 joule = 5.0345E+18(λ), where λ is measured in microns.]

B.5.1.4 Type of Detector. The choice of the type of radiant energy-sensing detector to use is determined by the type of emissions that are expected from the fire radiator.

B.5.1.4.1 Fuels that produce a flame, a stream of combustible or flammable gases involved in the combustion reaction with a gaseous oxidizer, radiate quantum emissions. These fuels include flammable gases, flammable liquids, combustible liquids, and solids that are burning with a flame.

B.5.1.4.2 Fuels that are oxidized in the solid phase or radiators that are emitting due to their internal temperature (sparks and embers) radiate Planckian emissions. These fuels include carbonaceous fuels such as coal, charcoal, wood, and cellulosic fibers that are burning without an established flame, as well as metals that have been heated due to mechanical impacts and friction.

B.5.1.4.3 Almost all combustion events produce Planckian emissions, emissions that are the result of the thermal energy in the fuel mass. Therefore, spark/ember detectors that are designed to detect these emissions are not fuel specific. Flame detectors detect quantum emissions that are the result of changes in molecular structure and energy state in the gas phase. These emissions are uniquely associated with particular molecular structures. This can result in a flame detector that is very fuel specific.

B.5.1.5 Effects of Ambient. The choice of radiant energy-sensing detector is also limited by the effect of ambient condi-

tions. The design must take into account the radiant energy absorption of the atmosphere, presence of non-fire-related radiation sources that might cause nuisance alarms, the electromagnetic energy of the spark, ember, or fire to be detected, the distance from the fire source to the sensor, and characteristics of the sensor.

B.5.1.5.1 Ambient Non-Fire Radiators. Most ambients contain non-fire radiators that can emit at wavelengths used by radiant energy-sensing detectors for fire detection. The designer should make a thorough evaluation of the ambient to identify radiators that have the potential for producing unwarranted alarm response from radiant energy-sensing detectors. Since radiant energy-sensing detectors use electronic components that can act as antennas, the evaluation should include radio band, microwave, infrared, visible, and ultraviolet sources.

B.5.1.5.2 Ambient Radiant Absorbance. The medium through which radiant energy passes from fire source to detector has a finite transmittance. Transmittance is usually quantified by its reciprocal, absorbance. Absorbance by atmospheric species varies with wavelength. Gaseous species absorb at the same wavelengths that they emit. Particulate species can transmit, reflect, or absorb radiant emission, and the proportion that is absorbed is expressed as the reciprocal of its emissivity, ϵ .

B.5.1.5.3 Contamination of Optical Surfaces. Radiant energy can be absorbed or reflected by materials contaminating the optical surfaces of radiant energy-sensing detectors. The designer should evaluate the potential for surface contamination and implement provisions for keeping these surfaces clean. Extreme caution must be employed when considering the use of surrogate windows. Common glass, acrylic, and other glazing materials are opaque at the wavelengths used by most flame detectors and some spark/ember detectors. Placing a window between the detector and the hazard area that has not been listed by a nationally recognized testing laboratory (NRTL) for use with the detector in question is a violation of the detector listing and will usually result in a system that is incapable of detecting a fire in the hazard area.

B.5.1.5.4 Design Factors. These factors are important for several reasons. First, a radiation sensor is primarily a line-of-sight device, and must "see" the fire source. If there are other radiation sources in the area, or if atmospheric conditions are such that a large fraction of the radiation could be absorbed in the atmosphere, the type, location, and spacing of the sensors could be affected. In addition, the sensors react to specific wavelengths, and the fuel must emit radiation in the sensor's bandwidth. For example, an infrared detection device with a single sensor tuned to 4.3 microns (the CO₂ emission peak) cannot be expected to detect a non-carbon-based fire. Furthermore, the sensor needs to be able to respond reliably within the required time, especially when activating an explosion suppression system or similar fast-response extinguishing or control system.

B.5.1.6 Detector Response Model. The response of radiant energy-sensing detectors is modeled with a modified inverse square relationship as shown in the following equation [5]:

[B.5.1.6]

$$S = \frac{kPe^{-\zeta d}}{d^2}$$

where:

S = radiant power reaching the detector (W or Btu/sec) sufficient to produce alarm response

k = proportionality constant for the detector

P = radiant power emitted by the fire (W or Btu/sec)

ζ = extinction coefficient of air at detector operating wavelengths

d = distance between the fire and the detector (m or ft)

This relationship models the fire as a point source radiator, of uniform radiant output per steradian, some distance (d) from the detector. This relationship also models the effect of absorbance by the air between the fire and the detector as being a uniform extinction function. The designer must verify that these modeling assumptions are valid for the application in question.

B.5.2 Design of Flame Detection Systems.

B.5.2.1 Detector Sensitivity. Flame detector sensitivity is traditionally quantified as the distance at which the unit can detect a fire of given size. The fire most commonly used by the NRTLs in North America is a 0.9 m² (1.0 ft²) fire fueled with regular grade, unleaded gasoline. Some special-purpose detectors are evaluated using 150 mm (6 in.) diameter fires fueled with isopropanol.

B.5.2.1.1 This means of sensitivity determination does not take into account that flames can best be modeled as an optically dense radiator in which radiant emissions radiated from the far side of the flame toward the detector are re-absorbed by the flame. Consequently, the radiated power from a flame is not proportional to the area of the fire but to the flame silhouette, and hence to the height and width of the fire.

B.5.2.1.2 Because flame detectors detect the radiant emissions produced during the formation of flame intermediates and products, the radiant intensity produced by a flame at a given wavelength is proportional to the relative concentration of the specific intermediate or product in the flame and that portion of the total heat release rate of the fire resulting from the formation of that specific intermediate or product. This means that the response of a detector can vary widely as different fuels are used to produce a fire of the same surface area and flame width.

B.5.2.1.3 Many flame detectors are designed to detect specific products such as water (2.5 microns) and CO₂ (4.35 microns). These detectors cannot be used for fires that do not produce these products as a result of the combustion process.

B.5.2.1.4 Many flame detectors use time variance of the radiant emissions of a flame to distinguish between non-fire radiators and a flame. Where a deflagration hazard exists, the designer must determine the sample time period for such flame detectors and how such detectors will operate in the event of a deflagration of fuel vapor or fuel gases.

B.5.2.2 Design Fire. Using the process outlined in Section B.2, determine the fire size (kW or Btu/sec) at which detection must be achieved.

B.5.2.2.1 Compute the surface area the design fire is expected to occupy from the correlations in Table B.2.3.2.6.2(a) or other sources. Use the flame height correlation to determine the height of the flame plume:

[B.5.2.2.1a]

$$h_f = 0.182(kQ)^{2/5} \quad (\text{for SI units})$$

or

[B.5.2.2.1b]

$$h_f = 0.584(kQ)^{2/5} \quad (\text{for inch-pound units})$$

where:

 h_f = flame height (m or ft) Q = heat release rate (kW or Btu/sec)

k = wall effect factor. Where there are no nearby walls, use $k = 1$; where the fuel package is near a wall, use $k = 2$; where the fuel package is in a corner, use $k = 4$

Determine the minimum anticipated flame area width (w_f). Where flammable or combustible liquids are the fuel load and are unconfined, model the fuel as a circular pool. Compute the radiating area (A_r) using the following equation:

[B.5.2.2.1c]

$$A_r = \frac{1}{2h_f w_f}$$

where:

 A_r = radiating area (m² or ft²) h_f = flame height (m or ft) w_f = flame width (m or ft)

B.5.2.2.2 The radiant power output of the fire to the detector can be approximated as being proportional to the radiating area (A_r) of the flame:

[B.5.2.2.2]

$$P = cA_r$$

where:

 A_r = radiating area (m² or ft²) c = power per unit area proportionality constant P = radiated power (W or Btu/sec)

B.5.2.2.3 Calculate Detector Sensitivity. Using Equation B.5.2.2.1a or B.5.2.2.1b compute the radiating area of the test fire used by the NRTL in the listing process (A_r). The radiant power output of the test fire to the detector in the listing process is proportional to the radiating area (A_r) of the listing test flame.

B.5.2.2.4 Calculate Detector Response to Design Fire. Because the sensitivity of a flame detector is fixed during the manufacturing process, the following is the relationship that determines the radiant power reaching the detector sufficient to produce an alarm response:

[B.5.2.4a]

$$S = \frac{kcA_r e^{-\zeta d}}{d^2}$$

where:

 S = radiant power reaching the detector (W or Btu/sec) sufficient to produce alarm response k = proportionality constant for the detector A_r = radiant area of the listing test fire (m² or ft²) ζ = extinction coefficient of air at detector operating wavelengths d = distance between the fire and the detector during the listing fire test (m or ft) c = emitted power per unit flame radiating area correlation

Because the sensitivity of the detector is constant over the range of ambients for which it is listed:

[B.5.2.4b]

$$S = \frac{kcA_r e^{-\zeta d}}{d^2}$$

where:

 S = radiant power reaching the detector (W or Btu/sec) sufficient to produce alarm response k = proportionality constant for the detector c = emitted power per unit flame radiating area correlation A_r = radiant area of the design fire (m² or ft²) ζ = extinction coefficient of air at detector operating wavelengths d' = distance between the design fire and the detector (m or ft)

Therefore, use the following equation to determine the following:

[B.5.2.4c]

$$\frac{kcA_r e^{-\zeta d}}{d^2} = \frac{kcA_r e^{-\zeta d'}}{d'^2}$$

To solve for d' use the following equation:

[B.5.2.4d]

$$\left(\frac{d^2 A_r e^{-\zeta d}}{A_r e^{-\zeta d'}} \right)^{1/2} = d'$$

This relation is solved iteratively for d' , the distance at which the detector can detect the design fire.

B.5.2.5 Correction for Angular Displacement.

B.5.2.5.1 Most flame detectors exhibit a loss of sensitivity as the fire is displaced from the optical axis of the detector. This correction to the detector sensitivity is shown as a polar graph in Figure A.17.8.3.2.3.

B.5.2.5.2 When the correction for angular displacement is expressed as a reduction of normalized detection distance, the correction is made to detection distance (d').

B.5.2.5.3 When the correction for angular displacement is expressed as a normalized sensitivity (fire size increment), the correction must be made to A_r prior to calculating response distance (d').

B.5.2.6 Corrections for Fuel. Most flame detectors exhibit some level of fuel specificity. Some manufacturers provide "fuel

factors" that relate detector response performance to a fire of one fuel to the response performance of a benchmark fuel. Other manufacturers provide performance criteria for a list of specific fuels. Unless the manufacturer's published instructions, bearing the listing mark, contain explicit instructions for the application of the detector for fuels other than those used in the listing process, the unit cannot be deemed listed for use in hazard areas containing fuels different from those employed in the listing process.

B.5.2.6.1 When the fuel factor correction is expressed as a detection distance reduction, the correction should be applied after the detection distance has been computed.

B.5.2.6.2 When the fuel factor correction is expressed as a function of normalized fire size, the correction must be made prior to calculating detection distance.

B.5.2.7 Atmospheric Extinction Factors.

B.5.2.7.1 Because the atmosphere is not infinitely transmittent at any wavelength, all flame detectors are affected by atmospheric absorption to some degree. The effect of atmospheric extinction on the performance of flame detectors is determined to some degree by the wavelengths used for sensing and the detector electronic architecture. Values for the atmospheric extinction coefficient (ζ) should be obtained from the detector manufacturer's published instructions.

B.5.2.7.2 The numerical value of ζ can be determined experimentally for any flame detector. The detector must be tested with two different sized test fires to determine the distance at which each of the fires can be detected by the detector in question. The larger the difference between the sizes of the flaming fires, the more precise the determination of ζ . Ideally, one test fire would be approximately 4 times the heat release rate (surface area) of the other. The data are then used in the relation:

[B.5.2.7.2]

$$\zeta = \frac{\ln \left[(d_1^2 A_2) / (d_2^2 A_1) \right]}{d_2 - d_1}$$

where:

"1" = subscripts referring to the first test fire

"2" = subscripts referring to the second test fire

d = maximum distance between the flame detector and the fire at which the fire is detected

A = the radiating area of the test fire as determined per B.5.2.2.1

This relation allows the designer to determine the value of ζ for detectors that are already installed or for those that were evaluated for listing before the inclusion of the requirement for the publishing of ζ appeared in ANSI/FM Approval Standard 3260, *Radiant Energy-Sensing Fire Detectors for Automatic Fire Alarm Signaling*.

B.5.3 Design of Spark/Ember Detection Systems.

B.5.3.1 Design Fire. Using the process outlined in Section B.2, determine the fire size (kW or Btu/sec) at which detection must be achieved.

B.5.3.1.1 The quantification of the fire is generally derived from the energy investment per unit time sufficient to propagate combustion of the combustible particulate solids in the fuel stream. Because energy per unit time is power, expressed in watts, the fire size criterion is generally expressed in watts or milliwatts.

B.5.3.1.2 The radiant emissions, integrated over all wavelengths, from a non-ideal Planckian radiator is expressed with the following form of the Stefan-Boltzmann equation:

[B.5.3.1.2]

$$P = \epsilon A \sigma T^4$$

where:

P = radiant power (W or Btu/sec)

ϵ = emissivity, a material property expressed as a fraction between 0 and 1.0

A = area of radiator (m^2 or ft^2)

σ = Stefan-Boltzmann constant $5.67E-8 \text{ W}/m^2K^4$

T = temperature (K or R)

B.5.3.1.3 This models the spark or ember as a point source radiator.

B.5.3.2 Fire Environment. Spark/ember detectors are usually used on pneumatic conveyance system ducts to monitor combustible particulate solids as they flow past the detector(s). This environment puts large concentrations of combustible particulate solids between the fire and the detector. A value for ζ must be computed for the monitored environment. The simplifying assumption that absorbance at visible levels is equal to or greater than that at infrared wavelengths yields conservative designs and is used.

B.5.3.3 Calculate Detector Response to Design Fire. Because the sensitivity of a spark/ember detector is fixed during the manufacturing process,

[B.5.3.3a]

$$S = \frac{k P e^{-\zeta d}}{d^2}$$

where:

S = radiant power reaching the detector (W or Btu/sec) sufficient to produce alarm response

k = proportionality constant for the detector

P = radiant power emitted by test spark (W or Btu/sec)

ζ = extinction coefficient of air at detector operating wavelengths

d = distance between the fire and the detector during the listing fire test (m^2 or ft^2)

Because the sensitivity of the detector is constant over the range of ambients for which it is listed,

$$S = \frac{kP'e^{-\zeta d'}}{d'^2} \quad [\text{B.5.3.3b}]$$

where:

S = radiant power reaching the detector (W or Btu/sec) sufficient to produce alarm response

k = proportionality constant for the detector

P' = radiant power from the design fire (W or Btu/sec)

ζ = the extinction coefficient of air at detector operating wavelengths

d' = the distance between the design fire and the detector (m^2 or ft^2)

Therefore, use the following equation to solve for

$$\frac{kPe^{-\zeta d}}{d^2} = \frac{kP'e^{-\zeta d'}}{d'^2} \quad [\text{B.5.3.3c}]$$

To solve for d' ,

$$d' = \left(\frac{d^2 P' e^{-\zeta d'}}{P e^{-\zeta d}} \right)^{1/2} \quad [\text{B.5.3.3d}]$$

This relation is solved iteratively for d' , the distance at which the detector can detect the design fire.

B.5.3.4 Correction for Angular Displacement.

B.5.3.4.1 Most spark/ember detectors exhibit a loss of sensitivity as the fire is displaced from the optical axis of the detector. This correction to the detector sensitivity is shown as a polar graph in Figure A.17.8.3.2.3.

B.5.3.4.2 When the correction for angular displacement is expressed as a reduction of normalized detection distance, the correction is made to detection distance (d').

B.5.3.4.3 When the correction for angular displacement is expressed as a normalized sensitivity (fire size increment), the correction must be made to P' prior to calculating response distance (d').

B.5.3.5 Corrections for Fuel. Because spark/ember detectors respond to Planckian emission in the near infrared portion of the spectrum, corrections for fuels are rarely necessary.

B.6 Computer Fire Models. Several special application computer models are available to assist in the design and analysis of both heat detectors (e.g., fixed-temperature, rate-of-rise, sprinklers, fusible links) and smoke detectors. These computer models typically run on personal computers and are available from the NIST website at: <http://fire.nist.gov>. The *SFPE Engineering Guide: Guidelines for Substantiating a Fire Model for a Given Application* [60] provides guidance to the engineer on how to select a fire model.

B.6.1 DETACT — T². DETACT — T² (DETECTOR ACTuation — time squared) calculates the actuation time of heat detectors (fixed-temperature and rate-of-rise) and sprinklers to user-specified fires that grow with the square of time. DETACT — T² assumes the detector is located in a large compartment with an unconfined ceiling, where there is no accumulation of hot gases at the ceiling. Thus, heating of the detector is only from the flow of hot gases along the ceiling. Input data include H , τ_0 , RTI, T_s , S , and α . The program calculates the heat release rate at detector activation, as well as the time to activation.

B.6.2 DETACT — QS. DETACT — QS (DETECTOR ACTuation — quasi-steady) calculates the actuation time of heat detectors and sprinklers in response to fires that grow according to a user-defined fire. DETACT — QS assumes the detector is located in a large compartment with unconfined ceilings, where there is no accumulation of hot gases at the ceiling. Thus, heating of the detector is only from the flow of hot gases along the ceiling. Input data include H , τ_0 , RTI, T_s , the distance of the detector from the fire's axis, and heat release rates at user-specified times. The program calculates the heat release rate at detector activation, the time to activation, and the ceiling jet temperature.

DETECT — QS can also be found in HAZARD I, FIREFORM, FPETOOL. A comprehensive evaluation of DETACT QS can be found in the *SFPE Engineering Guide: Evaluation of the Computer Fire Model DETACT QS*. This guide provides information on the theoretical basis, mathematical robustness, sensitivity of output to input, and an evaluation of the predictive ability of the model.

B.6.3 LAVENT. LAVENT (Link Actuated VENT) calculates the actuation time of sprinklers and fusible link-actuated ceiling vents in compartment fires with draft curtains. Inputs include the ambient temperature, compartment size, thermophysical properties of the ceiling, fire location, size and growth rate, ceiling vent area and location, RTI, and temperature rating of the fusible links. Outputs of the model include the temperatures and release times of the links, the areas of the vents that have opened, the radial temperature distribution at the ceiling, and the temperature and height of the upper layer.

B.6.4 JET is a single-compartment, two-zone computer model. It has been designed to calculate the centerline temperature of the plume, the ceiling jet temperature, and the ceiling jet velocity. JET can model ceiling-mounted fusible links, as well as link-actuated ceiling vents. JET evolved from the model platform used for LAVENT and contains many of the same features. Some of the major differences between them include the ceiling jet temperature and velocity algorithms, the fusible link algorithm, and the use of a variable radiative fraction. [57]

B.6.5 References.

- (1) Alpert, R. "Ceiling Jets," *Fire Technology*, Aug. 1972.
- (2) "Evaluating Unsprinklered Fire Hazards," *SFPE Technology Report* 83-2.
- (3) Babrauskas, V., Lawson, J. R., Walton, W. D., and Twilley, W. H. "Upholstered Furniture Heat Release Rates Measured with a Furniture Calorimeter," (NBSIR 82-2604) (Dec. 1982). National Institute of Standards and Technology (formerly National Bureau of Standards), Center for Fire Research, Gaithersburg, MD 20889.

- (4) Beyler, C. "A Design Method for Flaming Fire Detection," *Fire Technology*, Vol. 20, No. 4, Nov. 1984.
- (5) Hurley, M. J., Chapter 40, *SFPE Handbook of Fire Protection Engineering*, 5th edition, by Schifiliti, R.P., Custer, R.L.P. and Meacham, B.J., 2016.
- (6) Evans, D. D. and Stroup, D. W. "Methods to Calculate Response Time of Heat and Smoke Detectors Installed Below Large Unobstructed Ceilings," (NBSIR 85-3167) (Feb. 1985, issued Jul. 1986). National Institute of Standards and Technology (formerly National Bureau of Standards), Center for Fire Research, Gaithersburg, MD 20889.
- (7) Heskestad, G. "Characterization of Smoke Entry and Response for Products-of-Combustion Detectors" Proceedings, 7th International Conference on Problems of Automatic Fire Detection, Rheinisch-Westfälischen Technischen Hochschule Aachen (Mar. 1975).
- (8) Heskestad, G. "Investigation of a New Sprinkler Sensitivity Approval Test: The Plunge Test," FMRC Tech. Report 22485, Factory Mutual Research Corporation, 1151 Providence Turnpike, Norwood, MA 02062.
- (9) Heskestad, G. and Delichatsios, M. A. "The Initial Convective Flow in Fire: Seventeenth Symposium on Combustion," The Combustion Institute, Pittsburgh, PA (1979).
- (10) Heskestad, G. and Delichatsios, M. A. "Environments of Fire Detectors — Phase 1: Effect of Fire Size, Ceiling Height and Material," Measurements Vol. I (NBS-GCR-77-86), Analysis Vol. II (NBS-GCR-77-95). National Technical Information Service (NTIS), Springfield, VA 22151.
- (11) Heskestad, G. and Delichatsios, M. A. "Update: The Initial Convective Flow in Fire," *Fire Safety Journal*, Vol. 15, No. 5, 1989.
- (12) International Organization for Standardization, *Audible Emergency Evacuation Signal*, ISO 8201, 1987.
- (13) Klotz, J. and Milke, J. "Principles of Smoke Management," American Society of Heating, Refrigerating and Air Conditioning Engineers, Atlanta, GA, 2002.
- (14) Lawson, J. R., Walton, W. D., and Twilley, W. H. "Fire Performance of Furnishings as Measured in the NBS Furniture Calorimeter, Part 1," (NBSIR 83-2787) (Aug. 1983). National Institute of Standards and Technology (formerly National Bureau of Standards), Center for Fire Research, Gaithersburg, MD 20889.
- (15) Morton, B. R., Taylor, Sir Geoffrey, and Turner, J. S. "Turbulent Gravitational Convection from Maintained and Instantaneous Sources," *Proc. Royal Society A*, 234, 1–23, 1956.
- (16) Schifiliti, R. "Use of Fire Plume Theory in the Design and Analysis of Fire Detector and Sprinkler Response," Master's Thesis, Worcester Polytechnic Institute, Center for Firesafety Studies, Worcester, MA, 1986.
- (17) Title 47, Code of Federal Regulations, Communications Act of 1934 Amended.
- (18) Schifiliti, R. and Pucci, W. "Fire Detection Modelling, State of the Art," 6 May, 1996 sponsored by the Fire Detection Institute, Bloomfield, CT.
- (19) Forney, G., Bukowski, R., Davis, W. "Field Modelling: Effects of Flat Beamed Ceilings on Detector and Sprinkler Response," Technical Report, Year 1. International Fire Detection Research Project, Fire Protection Research Foundation, Quincy, MA, October, 1993.
- (20) Davis, W., Forney, G., Bukowski, R. "Field Modelling: Simulating the Effect of Sloped Beamed Ceilings on Detector and Sprinkler Response," Year 1. International Fire Detection Research Project Technical Report, Fire Protection Research Foundation, Quincy, MA, October, 1994.
- (21) Brozowski, E. "A Preliminary Approach to Siting Smoke Detectors Based on Design Fire Size and Detector Aerosol Entry Lag Time," Master's Thesis, Worcester Polytechnic, Worcester, MA, 1989.
- (22) Cote, A. *NFPA Fire Protection Handbook*, 20th edition, National Fire Protection Association, Quincy, MA, 2008.
- (23) Tewarson, A., "Generation of Heat and Chemical Compounds in Fires," *SFPE Handbook of Fire Protection Engineering*, Second Edition, NFPA and SFPE, 1995.
- (24) Hollman, J. P. *Heat Transfer*, McGraw-Hill, New York, 1976.
- (25) Custer, R. L. P., and Meacham, B. "Introduction to Performance Based Fire Safety," SFPE, 1997.
- (26) Schifiliti, R. P., Meacham B., Custer, R. L. P. "Design of Detection Systems," *SFPE Handbook of Fire Protection Engineering*.
- (27) Marrion, C. "Correction Factors for the Heat of Combustion in NFPA 72," Appendix B, Fire Protection Engineering, SFPE, 1998.
- (28) Marrion, C. "Designing and Analyzing the Response of Detection Systems: An Update to Previous Correlations," 1988.
- (29) Custer, R. and Bright, R. "Fire Detection: The State-of-the-Art," NBS Tech. Note 839, National Bureau of Standards, Washington, 1974.
- (30) Meacham, Brian J. "Characterization of Smoke from Burning Materials for the Evaluation of Light Scattering-Type Smoke Detector Response," MS Thesis, WPI Center for Firesafety Studies, Worcester, MA, 1991.
- (31) Delichatsios, M. A. "Categorization of Cable Flammability, Detection of Smoldering, and Flaming Cable Fires," Interim Report, Factory Mutual Research Corporation, Norwood, MA, NP-1630, Nov. 1980.
- (32) Heskestad, G. FMRC Serial Number 21017, Factory Mutual Research Corp., Norwood, MA, 1974.
- (33) Marrion, C. E. "Lag Time Modeling and Effects of Ceiling Jet Velocity on the Placement of Optical Smoke Detectors," MS Thesis, WPI Center for Firesafety Studies, Worcester, MA, 1989.
- (34) Kokkala, M. et al. "Measurements of the Characteristic Lengths of Smoke Detectors," *Fire Technology*, Vol. 28, No. 2, National Fire Protection Association, Quincy, MA, 1992.
- (34a) Yamauchi et al. "A Calculation Method for Predicting Heat and Smoke Detector's Response."
- (34b) Cleary et al. "Particulate Entry Lag in Spot Type Smoke Detectors," IAFSS Proceedings, Boston, MA 2000.
- (34c) Keski-Rahkonen, "Revisiting Modeling of Fluid Penetration into Smoke Detectors," AUBE 2001.

(34d) Bjoerkman et al. "Determination of Dynamic Model Parameters of Smoke Detectors," *Fire Safety Journal*, No. 37, pp. 395–407, 2002.

(34e) Keski-Rahkonen, "A New Model for Time Lag of Smoke Detectors," International Collaborative Project to Evaluate Fire Models for Nuclear Power Plant Application, Gaithersburg, MD May 2002.

(35) UL 268, *Standard for Smoke Detectors for Fire Alarm Signaling Systems*, Underwriters Laboratories, Inc., Northbrook, IL, 2009.

(36) Deal, Scott. "Technical Reference Guide for FPEtool Version 3.2," NISTIR 5486, National Institute for Standards and Technology, U.S. Department of Commerce, Gaithersburg, MD, Aug. 1994.

(37) Mowrer, F. W. "Lag Times Associated with Detection and Suppression," *Fire Technology*, Vol. 26, No. 3, pp. 244–265, 1990.

(38) Newman, J. S. "Principles for Fire Detection," *Fire Technology*, Vol. 24, No. 2, pp. 116–127, 1988.

(39) Custer, R., Meacham, B., Wood, C. "Performance Based Design Techniques for Detection and Special Suppression Applications," Proceedings of the SFPE Engineering Seminars on Advances in Detection and Suppression Technology, 1994.

(40) SFPE *Engineering Guide to Performance Based Fire Protection*, 2nd edition, SFPE, Gaithersburg, MD, 2007.

(41) SFPE *Handbook of Fire Protection Engineering*, Fifth Edition, SFPE, Gaithersburg, MD, 2016.

(42) Drysdale, Dougal, *An Introduction to Fire Dynamics*, John Wiley & Sons, New York, NY, 1998, ISBN 0 471 90613 1, Second Edition.

(43) Nam S., Donovan L.P. and Kim S.G., Establishing Heat Detectors Thermal Sensitivity Through Bench Scale Tests; *Fire Safety Journal*, Volume 39, Number 3, 191–215; April 2004.

(44) Nam S., Thermal Response Coefficient TRC of Heat Detectors and Its Field Applications, Fire Detection and Research Applications Symposium, NFPA Research Foundation, January 2003.

(45) Nam S., Performance-Based Heat Detector Spacing, Interflam 2004, pp. 883–892.

(46) Geiman, J. A., "Evaluation of Smoke Detector Response Estimation Methods," Master of Science Thesis, University of Maryland, College Park, MD, December 2003.

(47) [Reference removed.]

(48) Geiman, J. A., and Gottuck, D.T., "Alarm Thresholds for Smoke Detector Modeling," *Fire Safety Science — Proceeding of the Seventh International Symposium*, 2003, pp. 197–208.

(49) *The SFPE Code Official's Guide to Performance-based Design Review and Analysis of Buildings*, Society of Fire Protection Engineers, Bethesda, MD, 2004.

(50) NFPA 101, *Life Safety Code*, National Fire Protection Association, Quincy, MA, 2009.

(51) NFPA 909, *Code for the Protection of Cultural Resource Properties — Museums, Libraries, and Places of Worship*, National Fire Protection Association, Quincy, MA, 2010.

(52) NFPA 914, *Code for Fire Protection of Historic Structures*, National Fire Protection Association, Quincy, MA, 2010.

(53) Performance-based Building Design Concepts, International Code Council, Washington DC, 2004.

(54) *Extreme Event Mitigation In Buildings — Analysis and Design*, Meacham, National Fire Protection Association, Quincy MA, 2006.

(55) Geiman, Gottuk, and Milke, "Evaluation of Smoke Detector Response Estimation Methods: Optical Density, Temperature Rise and Velocity at Alarm," *Journal of Fire Protection Engineering*, 2006.

(56) Su et al., "Kemano Fire Studies — Part 1: Response of Residential Smoke Alarms," Research Report 108, NRCC, April 2003.

(57) Davis, W., The Zone Model Jet, "A Model for the Prediction of Detector Activation and Gas Temperature in the Presence of a Smoke Layer," NISTIR 6324, NIST, May 1999.

(58) NFPA 72E, *Standard for Automatic Fire Detectors*, 1984 edition.

(59) *Guidelines for Peer Review in the Fire Protection Design Process*, Society of Fire Protection Engineers, 2009.

(60) *SFPE Engineering Guide: Guidelines for Substantiating a Fire Model for a Given Application*, Society of Fire Protection Engineers, Gaithersburg, MD, 2011.

B.7 Nomenclature. The nomenclature used in Annex B is defined in Table B.7.

Table B.7 Nomenclature

α	= fire growth rate (kW/sec ² or Btu/sec ³)
A	= area (m ² or ft ²)
A_0	= $g / (C_p T_a \rho)$ [m ³ / (sec ² kJ) or ft ⁴ / (sec ² Btu)]
A_r	= radiating area (m ² or ft ²)
A_t	= radiating area of test fire
C	= specific heat of detector element (kJ/kg·°C or Btu/lbm·°F)
c	= speed of light (m/sec or ft/sec)
C_p	= specific heat of air [kJ / (kg K) or Btu/lbm R (1.040 kJ/kg K)]
D_m	= mass optical density (m ² /g or ft ² /lb)
d	= distance between fire and radiant energy-sensing detector
d'	= distance between fire and detector
$d(Du)/dt$	= rate of increase of optical density outside the detector
D	= $0.146 + 0.242\tau/H$
Δt	= change in time (seconds)
ΔT	= increase above ambient in temperature of gas surrounding a detector (°C or °F)
Δt_d	= increase above ambient in temperature of a detector (°C or °F)
Δt_p	= change in reduced gas temperature
e	= energy (joules or Btu)
f	= functional relationship
g	= gravitational constant (9.81 m/sec ² or 32 ft/sec ²)

(continues)

Table B.7 Continued

h	= Planck's constant (6.63E-23 joule-sec)
H	= ceiling height or height above fire (m or ft)
H_c	= convective heat transfer coefficient (kW/m ² ·°C or Btu/ft ² ·sec·°F)
ΔH_c	= heat of combustion (kJ/mol)
h_f	= flame height (m or ft)
H_f	= heat of formation (kJ/mol)
L	= characteristic length for a given detector design
k	= detector constant, dimensionless
m	= mass (kg or lbm)
p	= positive exponent
P	= radiant power (watts or Btu/sec)
q	= heat release rate density per unit floor area (watts/m ² or Btu/sec·ft ²)
Q	= heat release rate (kW or Btu/sec)
Q_c	= convection portion of fire heat release rate (kW or Btu/sec)
Q_{cond}	= heat transferred by conduction (kW or Btu/sec)
Q_{conv}	= heat transferred by convection (kW or Btu/sec)
Q_c	= threshold fire size at which response must occur
Q_{rad}	= heat transferred by radiation (kW or Btu/sec)
Q_{total}	= total heat transfer (kW or Btu/sec)
Q_{CR}	= critical heat release rate (kW or Btu/sec)
Q_{DO}	= design heat release rate (kW or Btu/sec)
Q_m	= maximum heat release rate (kW or Btu/sec)
Q_p	= predicted heat release rate (kW or Btu/sec)
Q_T	= threshold heat release rate at response (kW or Btu/sec)
r	= radial distance from fire plume axis (m or ft)
ρ_0	= density of ambient air [kg/m ³ or lb/ft ³ (1.1 kg/m ³)]
RTI	= response time index (m ^{1/2} sec ^{1/2} or ft ^{1/2} sec ^{1/2})
S	= spacing of detectors or sprinkler heads (m or ft)
S	= radiant energy
t_{DO}	= time at which the design objective heat release rate (Q_{DO}) is reached (seconds)
t_{CR}	= time at which the critical heat release rate (Q_{CR}) is reached (seconds)
t	= time (seconds)
t_c	= critical time — time at which fire would reach a heat release rate of 1055 kW (1000 Btu/sec) (seconds)

(continues)

Table B.7 Continued

t_d	= time to detector response
t_g	= fire growth time to reach 1055 kW (1000 Btu/sec) (seconds)
t_r	= response time (seconds)
t_{respond}	= time available, or needed, for response to an alarm condition (seconds)
t_v	= virtual time of origin (seconds)
t_{2f}	= arrival time of heat front (for $p = 2$ power law fire) at a point r/H (seconds)
t_{2f}^*	= reduced arrival time of heat front (for $p = 2$ power law fire) at a point r/H (seconds)
t^*	= reduced time
T_p	= temperature (°C or °F)
T_a	= ambient temperature (°C or °F)
T_c	= plume centerline temperature (°C or °F)
T_d	= detector temperature (°C or °F)
T_g	= temperature of fire gases (°C or °F)
T_s	= rated operating temperature of a detector or sprinkler (°C or °F)
u_0	= instantaneous velocity of fire gases (m/sec or ft/sec)
u	= velocity (m/sec or ft/sec)
u_c	= critical velocity
U_p	= reduced gas velocity
V	= velocity of smoke at detector
w_f	= flame width (m or ft)
Y	= defined in equation B.27
z	= height above top of fuel package involved (m or ft)
λ	= wavelength (microns)
Z_m	= maximum height of smoke rise above fire surface (m or ft)
τ	= detector time constant mc/HA (seconds)
τ_0	= detector time constant measured at reference velocity u_0 (seconds)
ϵ	= emissivity, a material property expressed as a fraction between 0 and 1.0

Annex C System Performance and Design Guide

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

C.1 Scope. The requirements of the protected premises chapter (Chapter 23) provide for minimum levels of protection for fire alarm systems to protect life and property, regardless of the building characteristics, contents, or use. This System Performance and Design Guide provides additional considerations for users of the NFAC when planning, designing, and installing protected premises fire alarm systems for buildings that might be unusual in scale, mission, use, symbolism, or other critical or high-profile characteristics.

This guidance suggests potential system characteristics to enhanced system performance for protection of life, mission, and property in high-profile and other critical buildings, including signaling path integrity, redundancies, survivability, backup fire control stations, nonerasable logs, multiple information stations, and the benefits of networked and peer-to-peer configurations.

C.2 Building Scale. The size of a building to be protected influences fire alarm system operating characteristics, control functions, circuit integrity, annunciation, and other factors for protection of life, property, or the mission of the building.

C.2.1 Fire Service Response Location(s).

C.2.1.1 Location(s). Determine the fire service response location(s) by inquiry to the responding fire department (and building operating personnel, if appropriate).

C.2.1.2 Quantity. The fire service might desire more than one response location. Building operators might desire redundancies for security or operations under emergency conditions.

C.2.1.3 Functions. The primary response location is the normally expected location of the fire command center. In general, the fire command center provides information and control functions for the entire building. One or more redundant or abbreviated fire command centers might be desired for security or operations under emergency conditions.

C.2.1.3.1 Information. Nonprimary response locations might be intended to provide annunciation equipment to provide information for the entire building, or for a portion of the building associated with the response location.

C.2.1.3.2 Control. Nonprimary response locations might be intended to provide a partial or complete fire command center or emergency command center to provide control functions for the entire building, or for a portion of the building associated with the response location.

C.2.2 System Operational Characteristics.

C.2.2.1 On-Premises Response. Determine an emergency response plan considering the requirements of NFAC, local codes and regulations, the availability and responsibility of building operating personnel, and the mobility of occupants.

C.2.2.1.1 Investigation. Building security or operating personnel should investigate every alarm signal, and the emergency response plan might include investigation of initial alarm signals prior to activating a general alarm or the evacuation or relocation of occupants.

C.2.2.1.2 Communication. Determine appropriate methods to provide alarm information, and instructions when required, to building security and operating personnel, supervisory and management personnel, and building occupants. Consider the need for predetermined messages, single- or multiple-channel communications systems, and coordination of communications system coverage and zoning with building subdivisions, including smoke compartments and automatic suppression system coverage and zoning. Consider the need for multiple languages in emergency communications.

C.2.2.1.3 Evacuation/Relocation. Determine the extent to which the emergency egress plan is based on total evacuation, relocation and partial evacuation, areas of rescue assistance and/or defending in place.

C.2.2.1.4 Survivability. Consider means to harden the fire notification circuits/paths to attack by fire for a period of time necessary to notify building operating personnel and occupants of a fire emergency and/or provide instructions if appropriate.

C.2.2.1.5 Control. Fire alarm system control units can be arranged to actuate other building systems and to condition passive fire barriers to enhance fire safety in the building.

C.2.2.1.6 Building Systems. Consider activation or release of building systems and elements including, but not limited to, closing fire/smoke doors and dampers, recall of elevators, unlocking stairway doors, activating smoke control systems and or shut-down fans to prevent recirculation of smoke.

C.2.2.1.7 Fire Scene Operations. Compartmentation, water supply, fire fighter access, and communication links are important for manual fire-fighting operations. Fire alarm system monitoring, reporting, display, and control functions that enhance the maintenance and operation of these elements that enhance fire scene operations should be considered in the design, installation, and maintenance of protected premises fire alarm systems. An example would be a flashing visual notification appliance over the fire department connection.

C.2.2.2 External Response.

C.2.2.2.1 Resources Available. Determine the availability and responsibility of fire service resources. An example of the use of this information might be determining how to stage evacuation.

C.2.2.2.2 Time Required. Consider the time required for fire service response to the building. Consider travel time at various times of day and seasons of year.

C.2.2.2.3 Notification. Determine one or more acceptable means of automatic and manual notification of the fire service to initiate response to the building. Consider the extent of information that might be transmitted to the responding fire service to enhance response to the building and to provide incident information prior to its arrival.

C.2.2.2.4 Evacuation/Relocation. Consider system operational characteristics that might enhance coordination of control and direction to building operating personnel and occupants. Consider means of control and shift in control of evacuation or relocation direction from building operating personnel to fire service command.

C.2.2.2.5 Knowledge of Premises. Harmonize system operating characteristics to pre-incident planning with fire service and building operating and security personnel.

C.2.2.2.6 Communications and Control. Provide for fire-fighter communications through dedicated two-way fire-fighter communication systems, or consider a means to provide enhanced operation of fire service radio communications in the protected premises.

C.3 Premises Mission/Use/Property Protection. The loss of use or mission of a facility to the effects of accidental fire can have a very significant impact on the community or organization served by the facility. In such a case, it is appropriate to enhance functional characteristics of the protected premises system. Considerations include the following:

- (1) Criticality/Mission Continuity
 - (a) Community — Loss of operations of the facility might affect the community beyond the facility. Consider the sensitivity of fire detection and the effectiveness of alarm processing, emergency response, and fire suppression to minimize effects on the community served due to facility impairment by fire.
 - (b) Operations
 - i. On-premises — Fire might result in business interruption or reduced effectiveness.
 - ii. Elsewhere — Services provided by the facility to remote locations might cease or be reduced.
- (2) Life Safety
 - (a) Evacuation/Relocation — Size, distribution, and mobility of the occupant population should be considered with knowledge of facility emergency planning and availability of emergency response resources to determine the extent to which people movement might be managed during a fire incident.
 - (b) Defend-In-Place — A protected premises system might be used to actuate facility fire safety elements necessary to defend occupants in place or to enhance rescue assistance.
- (3) Property
 - (a) Value — Cost, availability, and time required to reestablish facility contents should be considered when determining the sensitivity of fire detection and the effectiveness of alarm processing, emergency response, and fire suppression.
 - (b) Replacement — Availability and time required to replace damaged facility contents should be considered when determining the sensitivity of fire detection and the effectiveness of alarm processing, emergency response and fire suppression.
 - (c) Redundancy — Duplication of facility contents in separate locations might reduce the need for sensitivity of fire detection or other property protection system capabilities.

C.4 Protected Premises Signaling System Features.

C.4.1 Event Logs. Computer processor-based systems are capable of assembling logs of system events by date and time, including alarm history. Such logs are an important resource in assessing system performance or malfunctions and in understanding or reconstructing a fire event after the fact. It is imperative that such logs are preserved and protected against deletion until it is affirmed that no further need for a log

exists. Caution is recommended to secure system history logs when system software changes are made.

C.4.2 Network Configuration. Systems that use digital means to transfer signal information might provide benefits in economy of installation and distribution of information to multiple locations to enable rigorous alarm processing and response. Transmission of digital alarm information to remote locations might assist responding personnel by providing incident information prior to arrival at the location of the fire.

C.4.3 Peer to Peer Data Communication. Systems that duplicate the operating and history data bases in multiple network control units provide redundant monitoring and control points on a system that can enhance the reliability of the system and the operation of the system during emergency or degraded conditions.

Annex D Speech Intelligibility

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

Users of Annex D should refer back to the text of NFPA 72 to familiarize themselves with the specific requirements for the planning, design, installation, and testing of voice communications systems.

D.1 Introduction.

D.1.1 This annex is intended to provide guidance on the planning, design, installation, and testing of voice communication systems. The majority of this annex contains recommendations for testing of the intelligibility of voice systems.

D.1.2 As with most systems, proper system performance is related to good planning, design, installation, and maintenance. Similarly, test results are a valuable feedback mechanism for persons planning, designing, and installing systems.

D.1.3 This annex describes when, where, and how to test for speech intelligibility. It is also not the intent of this test protocol to describe how to interpret results or how to correct systems or environments that contribute to poor speech intelligibility.

D.1.4 For occupancies that do not yet exist, the designer should have an understanding of the acoustic characteristics of the architectural design, as well as the acoustic performance properties of available loudspeakers. Architecturally, this includes the physical size and shape of the space, as well as the acoustic properties of the walls, floors, ceilings, and interior furnishings. A proper design analysis can sometimes reveal that an intelligible system is not achievable unless some features of the architectural design are changed. The designer should be prepared to defend such conclusions and, if necessary, refuse to certify the installation of such a system. While “hand calculations” and experience work well for simpler installations, more complex designs are frequently better and more cost-effectively analyzed using one of a number of readily available computer-based design programs.

D.1.5 The designer and the authority having jurisdiction should both be aware that the acoustic performance parameters of the chosen loudspeakers, as well as their placement in the structure, play a major role in determining how many appliances are necessary for adequate intelligibility. The numerical count of appliances for a given design and protected space cannot, by itself, be used to determine the adequacy of the

design. Sometimes, the acoustic problems of certain placement constraints can be satisfactorily overcome through the careful selection of loudspeakers with the requisite performance characteristics, rather than by increasing their number.

D.2 Fundamentals of Test Protocol.

D.2.1 Measurement Method.

D.2.1.1 STI/STIPA.

D.2.1.1.1 Where the method for measuring speech intelligibility is the Speech Transmission Index (STI), this test protocol should be followed.

D.2.1.1.2 There are several methods that measure the STI. One method common to the emergency communications system industry uses a test signal referred to as STIPA — STI-Public Address.

D.2.1.2 Other Methods. Where the method for measuring speech intelligibility is the Phonetically Balanced Word test (PB), Modified Rhyme Test (MRT), or Speech Intelligibility Index (SII) method, the same methods for determining measurement locations should be used.

D.2.2 References.

D.2.2.1 IEC 60268-16, *Sound system equipment — Part 16: Objective rating of speech intelligibility by speech transmission index*, International Electrotechnical Commission, Geneva, Switz., 2011.

D.2.2.2 ISO 7240-19, *Fire Detection and Alarm Systems — Part 19: Design, Installation, Commissioning and Service of Sound Systems for Emergency Purposes*, International Organization for Standardization, Geneva, Switz., 1st edition, 15 Aug 2007.

D.2.2.3 NEMA Standards Publication SB 50, *Emergency Communications Audio Intelligibility Applications Guide*, National Electrical Manufacturers Association, Rosslyn VA, 2014.

D.2.3 Terminology.

D.2.3.1 Acoustically Distinguishable Space (ADS).

D.2.3.1.1 An acoustically distinguishable space (ADS) can be an emergency communication system notification zone, or subdivision thereof, that can be an enclosed or otherwise physically defined space, or that can be distinguished from other spaces because of different acoustical, environmental, or use characteristics such as reverberation time and ambient sound pressure level. The ADS might have acoustical design features that are conducive for voice intelligibility, or it might be a space where voice intelligibility could be difficult or impossible to achieve.

D.2.3.1.2 All parts of a building or area intended to have occupant notification are subdivided into ADSs as defined. Some ADSs might be designated to have voice communications capability and require that those communications be intelligible. Other spaces might not require voice intelligibility or might not be capable of reliable voice intelligibility. Each is still referred to as an ADS.

D.2.3.1.3 In smaller areas, such as those under 400 ft² (40 m²), walls alone will define the ADS. In larger areas, other factors might have to be considered. In spaces that might be subdivided by temporary or movable partitions, such as ballrooms and meeting rooms, each individual configuration should be considered a separate ADS. Physical characteristics such as a change in ceiling height of more than 20 percent or change in

acoustical finish, such as carpet in one area and tile in another, would require those areas to be treated as separate ADSs. In larger areas there might be noise sources that require a section to be treated as a separate ADS. Any significant change in ambient sound pressure level or frequency might necessitate an area be considered a separate ADS.

D.2.3.1.4 In areas of 85 dBA or greater ambient sound pressure level, meeting the pass/fail criteria for intelligibility might not be possible and other means of communication might be necessary. So, for example, the space immediately surrounding a printing press or other high noise machine might be designated as a separate ADS and the design might call for some form of effective notification but not necessarily require the ability to have intelligible voice communication. The aisles or operator's control stations might be separate ADSs where intelligible voice communication might be desired.

D.2.3.1.5 Significant differences in furnishings, for example, an area with tables, desks, or low dividers adjacent to an area with high shelving, would require separate consideration. The entire desk area could be a single acoustic zone whereas each area between shelving could be a unique zone. Essentially, any noteworthy change in the acoustical environment within an area will mandate consideration of that portion of the area to be treated as an acoustic zone. Hallways and stairwells will typically be considered as individual acoustic zones.

D.2.3.1.6 Spaces confined by walls with carpeting and acoustical ceilings can be deemed to be one ADS. An ADS should be an area of consistent size and material. A change of materials from carpet to hard tile, the existence of sound sources such as decorative waterfalls, large expanses of glass, and changes in ceiling height are all factors that might separate one ADS from another.

D.2.3.1.7 Each ADS might require different components and design features to achieve intelligible voice communication. For example, two ADSs with similar acoustical treatments and noise levels might have different ceiling heights. The ADS with the lower ceiling height might require more ceiling-mounted loudspeakers to ensure that all listeners are in a direct sound field. See Figure D.2.3.1.7. Other ADSs might benefit from the use of alternate loudspeaker technologies such as line arrays to achieve intelligibility.

D.2.3.1.8 An ADS that differs from another because of the frequency and level of ambient sound pressure level might require the use of loudspeakers and system components that have a wider frequency bandwidth than conventional emergency communications equipment. However, designers should not use higher bandwidth loudspeakers in all locations unless needed to overcome certain acoustic and ambient conditions. This is because the higher bandwidth appliance will require more energy to perform properly. This increases amplifier and wire size and power supply requirements.

D.2.3.1.9 In some spaces it might be impractical to achieve intelligibility, and in such a case alternatives to voice evacuation might be required within such areas.

D.2.3.1.10 There might be some areas of a facility where there are several spaces of the same approximate size and with the same acoustic properties. For example, there might be an office space with multiple individual offices, each with one loudspeaker. If one or two are satisfactorily tested, there is no need to test all of them for speech intelligibility.




FIGURE D.2.3.1.7 Illustration Demonstrating Effect of Ceiling Height. (Source: R. P. Schifiliti Associates, Inc.)

D.2.3.2 Audibility Test. Measurement of the sound pressure level of a tone signal in accordance with the requirements of NFPA 72.

D.2.3.3 Intelligibility Test. A test method used to predict how well speech is understood by a listener.

D.2.3.4 Occupied Ambient Sound Pressure Level. The period of time when the building involved in the test is occupied and is reasonably close to having maximum background noise. For example, this might involve the operation of HVAC equipment, an industrial process, or a maximum number of occupants such as might occur in a place of public assembly.

D.2.3.5 STI or STIPA Test Signal.

D.2.3.5.1 A special audio signal that is played over the emergency communications system being tested.

D.2.3.5.2 Instruments that measure STI using a STIPA signal use a special signal that consists of signals in seven octave bands. The sound in each octave band is modulated using two (separate) modulation frequencies. The STI and STIPA have been standardized in IEC 60268. However, at the present time, the implementation of the measurement software and correlations with the test signal can differ between instrument manufacturers. Therefore, until there is further standardization, only the test signal recommended by the instrument manufacturer should be used with their instrument. Although the STIPA test signals can sound similar, there might be speed or other differences that affect results if one manufacturer's test signal is used with another manufacturer's instrument.

D.2.3.6 Talkbox. An instrument usually consisting of a high quality audio loudspeaker and a CD player or other method used to play an STI or STIPA test signal.

D.2.3.7 Unoccupied Ambient Sound Pressure Level. The period of time when the primary occupants of the facility are not present, or when ambient sound pressure level is not at its highest level.

D.2.4 Acceptability Criteria.

D.2.4.1 The intelligibility of an emergency communication system is considered acceptable if at least 90 percent of the measurement locations within each ADS have a measured STI of not less than 0.45 (0.65 CIS) and an average STI of not less than 0.50 STI (0.70 CIS).

D.2.4.2 Speech intelligibility is not a physical quantity like meters, feet, amperes, volts, or even decibels. It is a benchmark

of the degree to which we understand spoken language, and as such is a complex phenomenon affected by many variables (see Jacob, K. and Tyson, T., "Computer-Based Prediction of Speech Intelligibility for Mass Notification Systems"). There are two basic categories of intelligibility testing: (1) subject- (human-) based testing and (2) instrument-based test methods. Test methods that use human subjects are only statistical predictions of how well speech might be understood at any other time for any other group of listeners. Several subject-based test methods have been extensively researched, tested for reliability, and standardized. Examples include the Phonetically Balanced (PB) word scores (256 words or 1000 words) and Modified Rhyme Test (MRT). (See ANSI/ASA S3.2, *Method for Measuring the Intelligibility of Speech Over Communications Systems*.)

D.2.4.3 Subject based test methods can gauge how much of the spoken information is correctly understood by a person or group of persons for that particular test. When properly done, that resulting value is a prediction of how much of the spoken word will be correctly understood by others at some other time. Therefore, the results of speech intelligibility testing are usually described as predictions, not measurements. However, most users of the instruments refer to the results as measurements, not as predictions. Since the use of portable instruments is the more common method in the alarm and emergency communications industries, in this document the results will be referred to as measurements to avoid confusion. However, in scientific and general acoustic literature, readers can see the measured values correctly referred to as predictions.

D.2.4.4 Several instrument based methods for predicting speech intelligibility have been extensively researched and tested for accuracy and repeatability, and the methods have been standardized, most notably the Speech Intelligibility Index (SII) (formerly the Articulation Index, AI), Speech Transmission Index (STI), and Speech Transmission Index for Public Address (STIPA) [Ref: IEC 60268-16, *Sound system equipment — Part 16: Objective rating of speech intelligibility by speech transmission index*, 2003. Ref: ANSI/ASA S3.5, *Methods for Calculation of the Speech Intelligibility Index*, 1997 (R2017)]. Accuracy is how close the meter corresponds to actual human test results. Thus, even though an instrument is used, the results are subjective in that they correlate with how humans perceive the quality of speech.

D.2.4.5 Each of the established methods for measuring speech intelligibility has its own scale. The common intelligibility scale (CIS) was developed in 1995 to show the relationship between the different methods and to permit codes and standards to require a certain level of performance while permitting any of

the accepted measurement methods to be employed (*see Barnett, P. W. and Knight, A.D., "The Common Intelligibility Scale"*). The speech transmission index (STI) is widely used and has been implemented in portable equipment using a modified method called STIPA (STI public address). For this reason, the performance metrics cited in this document use units of STI with units of CIS in parentheses. The relationship between the two is: $CIS = 1 + \log(STI)$. Relationships between other methods can be found in the literature (*see ISO 7240-16, Fire detection and alarm systems — Part 16: Sound system control and indicating equipment*).

D.2.4.6 If an ADS is small enough to only require one measurement location (*see D.3.7 for the recommendation for measurement point spacing*), the result should be 0.50 STI (0.70 CIS) or more for the ADS to pass the requirement for speech intelligibility. This is based on the requirement for an average of 0.50 STI (0.70 CIS) or more in that ADS. Therefore, a single measurement of 0.45 STI (0.65 CIS) would not be considered acceptable, because that one measurement would be below the minimum required average of 0.50 STI (0.70 CIS) in that ADS.

D.2.4.7 If the value at that one measurement location were less than 0.50 STI (0.70 CIS), additional measurements could be taken at that same single measurement location. As with simple sound pressure level measurements, intelligibility measurements at any point will vary. If the average of all the measurements at that location were 0.50 STI (0.70 CIS) or more, the ADS would pass the requirement for speech intelligibility.

D.2.4.8 Some ADSs might require multiple measurement points due to their larger size. (*See D.3.7 for the recommendation for measurement point spacing.*) However, even in a small ADS where one measurement point would be permitted, a designer might intend that multiple measurements be made because of conditions that might result in specific points having intelligibility scores below the minimum. Where an ADS has multiple measurement locations, the requirement is that at least 90 percent of the measurement locations have values not less than 0.45 STI (0.65 CIS) and that all measurement points average to 0.50 STI (0.70 CIS) or greater.

D.2.4.9 The use of an average intelligibility score as a part of the requirement permits a wider range of measured values within an ADS than would a simple minimum requirement. A range of permitted values is not appropriate since there is no need for an upper limit for intelligibility — perfect intelligibility is certainly acceptable.

D.2.4.10 The requirement that only 90 percent of the measured points in the ADS meet the minimum and that the average for the entire ADS be 0.50 STI (0.70 CIS) or greater recognizes that in any space, with any system and any set of acoustic conditions, there can be points where the intelligibility score might be below the minimum. *See also the discussion in D.2.3.1 on the definition of an ADS and how some ADSs might be designated to not require speech intelligibility at all.* For example, in a room that is otherwise similar from an acoustics standpoint, the space around a loud machine might be one ADS while the rest of the room is a separate ADS. The ADS surrounding the machine might be designed to have some form of occupant notification but not to have intelligible voice communications. This type of ADS designation permits the remainder of the room to be scored without being penalized by the fact that intelligible communication near some loud sound sources might not be possible.

D.2.4.11 The intelligibility performance requirement cited herein intentionally uses two decimal points. Portable instruments that use the STIPA method for measuring the Speech Transmission Index (STI) generally have a precision on the order of 0.02 to 0.03 (*Ref: Sander J. van Wijngaarden and Jan A. Verhave, Past Present and Future of the Speech Transmission Index, Chapter 9, Measurement and Prediction of Speech Intelligibility in Traffic Tunnels Using the STI, p113, TNO Human Factors, The Netherlands, 2002*). Other methods that measure STI can have a greater measurement precision. Other measurement methods, such as Modified Rhyme Test (MRT), Phonetically Balanced Word (PB) lists, and Speech Intelligibility Index (SII), also have levels of precision in the hundredths when properly conducted and scored. However, there might be slight variations in measured values between any two meters or between any two persons taking measurements with the same instrument, or between any two listener panels when using subject based test methods. This is true for any measurement method or instrument, including simple scales for measuring length or mass.

D.2.4.12 Measurements should be made and recorded using two decimal places. Averages can be calculated to three decimal points and rounded. The calculated average value should be rounded to the nearest five-hundredths (0.05) to reflect possible measurement errors and the intent of the requirement (*Ref: Mapp, P., "Systematic & Common Errors in Sound System STI and Intelligibility Measurements," Convention Paper 6271, Audio Engineering Society, 117th Convention, San Fran, CA, 28–31 Oct 2004. Ref: Peter Mapp, Past Present and Future of the Speech Transmission Index, Chapter 8, Practical Application of STI to Assessing Public Address and Emergency Sound Systems, TNO Human Factors, The Netherlands, 2002*). For example, averages of 0.47–0.525 STI would all be rounded to report an average of 0.50 STI (0.70 CIS). The minimum value permitted for all but 10 percent of the measurement locations in an ADS should be 0.45 STI (0.65 CIS) or greater. For example, values of 0.44 STI are below the minimum; they are not rounded up to 0.45 STI.

D.2.5 Limitations of Test Method.

D.2.5.1 Equipment designed in accordance with UL 864 and fire alarm loudspeakers designed in accordance with UL 1480 are only tested for and only required to produce frequencies of 400 to 4000 Hz. Speech, however, includes a wider range of frequencies. Speech intelligibility measurements using STI and STIPA include octave band measurements that range from 125 Hz to 8000 Hz. STI results are most dependent on the 2000, 1000, 500, and 4000 Hz octave bands (in order of weighting) and to a lesser extent the 8000 and 250 Hz octave bands and to an even lesser extent, the 125 Hz band (again, in order of weighting).

D.2.5.2 While the lower and higher octave bands in STI calculations are weighted much less than the others, under certain acoustic conditions, systems that do not produce the highs and the lows can produce speech intelligibility that is less than desired. This does not imply that all systems should use equipment capable of greater bandwidth sound reproduction. While the larger frequency response will probably sound better and be more intelligible to a listener, it might not be necessary for the minimum desired performance. The use of equipment with higher bandwidth will require an increase in power supplies, amplifiers, and wire sizes to drive the loudspeaker appliances.

D.2.5.3 Areas of high ambient sound pressure levels (“noise”) might be incapable of meeting the acceptability criteria in D.2.4.

D.2.5.4 In areas where the ambient sound pressure level exceeds 90 dBA, satisfactory speech intelligibility is difficult to achieve with conventional communications equipment and design practice. A better system design might include alternate communications methods, such as signs and displays, or might involve providing occupant notification but not voice alarm communication at that location.

D.2.5.5 Impulse sounds made during measurements can impact measurement accuracy or cause instrument error.

D.2.5.6 Impulse sounds such as accidentally tapping the meter microphone, or a nearby door slamming can cause a measurement error. Some meters will display an error message. If an impulse sound occurs during the measurement, consider taking another measurement to check the results. This process is analogous to ignoring temporary sound sources, as permitted by *NFPA 72* when taking sound pressure level measurements.

D.2.5.7 Natural variation in ambient sound pressure level levels can affect the results.

D.2.6 General Requirements.

D.2.6.1 The qualified staff should be identified on the system design documents. Acceptable evidence of qualifications or certification should be provided when requested by the authority having jurisdiction. Qualified personnel should include, but not be limited to, one or more of the following:

- (1) Personnel who are factory trained and certified for fire alarm system design of the specific type and brand of system addressed by this test protocol
- (2) Personnel who are certified by a nationally recognized certification organization acceptable to the authority having jurisdiction
- (3) Personnel who are registered, licensed, or certified by a state or local authority

D.2.6.2 All necessary precautions should be taken with the facility owner to work with appropriately qualified staff when handling or performing any function with the emergency communications system control unit.

D.2.6.3 Testing impairment and record keeping requirements of *NFPA 72*, Chapter 14 should apply.

D.2.6.4 Test measurements and other documentation should be maintained as required by the authority having jurisdiction.

D.2.6.5 Impairment management procedures of *NFPA 72*, Section 10.21 should be followed.

D.2.6.6 Test Participants. The test participants should include representatives of the following: building owners, the organizations responsible for the fire alarm or emergency communications system design and installation, system equipment supplier and/or manufacturer, and the authority having jurisdiction.

D.3 Pre-Planning.

D.3.1 Facility Occupancy and Use.

D.3.1.1 Occupancy/Use Types. Prior to testing, the pre-planning effort should identify the occupancy or use type to better minimize disruption to the facility occupants during the test.

D.3.1.2 Normal Operational Time Periods. Prior to testing, pre-planning efforts should identify the operational time periods when the occupied ambient sound pressure level and the unoccupied ambient sound pressure level are most likely to occur.

D.3.1.3 Testing Before Building Furnishing Completion. It might be necessary to perform testing to permit partial use before the building is in its final acoustic configuration. The results of intelligibility testing at this stage can differ from the final performance of the system. It might be necessary to work with the authority having jurisdiction to develop a testing plan. For example, until acoustical treatments such as carpeting, ceiling tiles, and other furnishings are in place, the system can be partially tested to meet audibility requirements but not necessarily intelligibility requirements. Other test plans or mitigating procedures might be permitted.

D.3.1.4 Facility Construction and Condition. Construction in the facility to be tested should be completed for areas that will be subject to intelligibility testing. This specifically requires that the command center and all locations of system microphones to be tested should be completed. Any location of remote system microphones not tested during this time should be noted, and said locations should be fully tested with positive results within 90 days of area occupancy or as required by the authority having jurisdiction. Also, all building systems such as environmental conditioning systems should be completed and operational, as they both produce noise and provide acoustic noise travel paths. In addition, all floor treatments and any acoustical wall or ceiling treatments should be in place.

D.3.1.5 System Under Test Status. The system under test should be completed for all areas where intelligibility testing will be done.

D.3.1.6 System Under Test Power. System under test should be on permanent primary power source as defined in *NFPA 72*.

D.3.1.7 System Under Test Secondary Power. Secondary power, where required and/or provided for the system under test, should be fully functional. If batteries are used for this purpose, batteries should be fully charged for a minimum of 48 hours prior to the commencement of any testing.

D.3.2 Emergency Communications Equipment.

D.3.2.1 As discussed in D.2.3.1, not all ADSs will require or be capable of intelligible voice communications. It is the designer's job to define areas that will have voice communication versus those that might have tone-only signaling, as well as which spaces will have visual notification appliances (strobes), textual signage, or other forms of notification and/or communication. This document intends that “notification” mean any form of notification, not just voice communication, whether audible, visual, or using some other human sense.

D.3.2.2 There might be applications where not all spaces will require intelligible voice signaling (Ref: *NFPA 72*, 2007, Section A.7.4.1.4). For example, in a residential occupancy such as an apartment, the authority having jurisdiction and the designer might agree to a system that achieves the required audibility throughout but does not result in intelligible voice signaling in the bedrooms. The system would be sufficient to awaken and alert. However, intelligibility might not be achieved in the bedrooms with the doors closed and the sounder in the adjacent hallway or room. In some cases this can require that messages repeat a sufficient number of times to ensure that

occupants can reach a location where the system is sufficiently intelligible to be understood. Systems that use tone signaling in some areas and voice signaling in other areas would not require voice intelligibility in those areas only covered by the tone.

D.3.2.3 Emergency Communications System Control Unit.

The system under test for the emergency communications system should be located and identified prior to testing, and its operation features necessary for the testing clarified. Personnel who are authorized to access and service the control unit are necessary for the testing and should be included within the team performing the tests. If necessary, notification to locations beyond the facility that is being tested (e.g., fire department or a supervising station) should be notified of the tests, and if appropriate, their automatic notification feature disabled. Upon completion of the tests the emergency communications system should be returned to its normal operating condition.

D.3.2.4 Test Set-up. The function and operation of the emergency communication system control unit should be reviewed with personnel authorized to access and operate this equipment. Information should be acquired on the functioning of the voice notification portion of the system, and whether it has zone capabilities that will allow minimal disruption to building occupants by testing each zone individually. The test plan should also specify whether other functions of the system, such as elevator recall and air handler control, will be disabled during the testing of the emergency communications system.

D.3.2.5 System Under Test Calibration. The complete system under test audio path should be fully calibrated in accordance with manufacturer's published instructions. On systems with adjustable technology, if manufacturer's published instructions are not provided, the alternate calibration procedure offered below can be employed to calibrate the system under test.

D.3.2.5.1 Alternate Calibration Procedure.

D.3.2.5.1.1 This calibration is to be performed with the system under test on normal AC power, then checked with the system on secondary power (if so equipped).

D.3.2.5.1.2 The system under test amplifier output or the circuit being calibrated should have a minimum of a 1-watt load during the calibration process.

D.3.2.5.1.3 Perform pre-test occupant and remote monitoring station notification requirements specified in *NFPA 72*, Chapter 14.

D.3.2.5.1.4 Introduce a 1 kHz sine-wave tone (± 100 Hz) at 90 dBA-fast 4" (4 in.) to the system microphone on-axis, perpendicular to the face of the microphone.

D.3.2.5.1.5 Place the system under test into manual paging mode (microphone "live" and connected to amplifier circuitry with notification appliance circuits active).

D.3.2.5.1.6 Using a 4-digit accuracy RMS meter, set on AC scale, set the output of the System Under Test audio notification appliance circuits to between 24 and 26 Vrms for 25.2 volt systems or between 69 and 71 Vrms for 70.7 volt systems.

D.3.2.5.1.7 Once system under test manual paging mode has been calibrated, prerecorded tone (if so equipped) should then be tested by playing it through the system under test to ensure that there is no more than a 3 dBA difference between manual paging using the system microphone and the prerecor-

ded message. The dBA measurement should be made using an integrating/averaging meter and averaged over approximately 10 seconds of voice announcement to compensate for voice amplitude modulation.

D.3.2.5.1.8 On a system under test with more than one emergency paging microphone and/or prerecorded message units, the primary units should be calibrated, then secondary units tested to ensure that they produce signals throughout the system under test at the same amplitude as the primary units.

D.3.3 Plans and Specifications.

D.3.3.1 The approved plans and specifications for the system should be used to plan and document the tests.

D.3.3.2 Testing is best accomplished using large scale plans showing all notification appliances.

D.3.3.3 The plans should show the different system notification zones.

D.3.3.4 The type and location of the notification appliances used in the emergency communication system should be identified prior to testing.

D.3.3.5 Notification appliance symbols should differentiate the type of appliance where more than one type is used.

D.3.3.6 Notification appliance symbols should include the design wattage for each loudspeaker appliance.

D.3.3.7 The plans should show the ambient sound pressure levels used as a basis for the system design.

D.3.4 Estimating a Design's Speech Intelligibility. There are occasions in which a space might not be available to take test measurements in prior to the design being completed. Calculation methods for speech intelligibility are available so that a design can be assessed before actual installation. The calculations use basic physical parameters of the space and the system arrives at a speech intelligibility estimate. (*See K.1.2.19.*) The results of the calculation methods can be converted to STI using the CIS described in D.2.4.5.

D.3.5 Assignment of Acoustically Distinguishable Spaces.

D.3.5.1 ADSs should be assigned prior to the test, and be subject to review by all test participants.

D.3.5.2 ADS assignments should be a part of the original design process. See the discussion in D.2.3.1.

D.3.5.3 The design drawings should be used to plan and show the limits of each ADS where there is more than one.

D.3.5.4 All areas that are intended to have audible occupant notification, whether by tone only or by voice are to be designated as one or more ADSs. See D.2.3.1.

D.3.5.5 The drawings or a table listing all ADSs should be used to indicate which ADSs will require intelligible voice communications and which will not. The same drawings or table could be used to list audibility requirements where tones are used and to list any forms of visual or other notification or communications methods being employed in the ADS.

D.3.5.6 ADS layouts that differ from the original, approved design documents should be approved by the authority having jurisdiction.

D.3.6 Spaces Not Requiring Testing.

D.3.6.1 Buildings and areas of buildings that are not acoustically challenging such as traditional office environments, hotel guest rooms, dwelling units, and spaces with carpeting and furnishings generally meet intelligibility levels if the audibility levels are consistent with the requirements of *NFPA 72*. Performing intelligibility testing might not be necessary in these areas. Areas of a typical building that can be acoustically challenging could include vehicle parking levels and large lobby areas with hard floors and wall surfaces, stairs, and other spaces with high reverberation. Intelligibility meeting the requirements in this document can be difficult to achieve throughout these spaces. Specialized sound system design procedures, principles, and equipment might be necessary to achieve speech intelligibility in high noise areas or areas with challenging acoustics. Alternatively, intelligibility could be provided near exits and within specific areas (elevator lobby of a parking level) where occupants can obtain clear instructions after being alerted. This is done, in part, by the proper planning and designation of ADSs.

D.3.6.2 Factors that influence the decision to measure or not measure speech intelligibility include those in D.3.6.2.1 through D.3.6.2.3.

D.3.6.2.1 Possible reasons not to test speech intelligibility include the following:

- (1) Distance from the listener to loudspeaker is less than 30 ft (9.1 m) in the room (assuming proper audibility and low reverberation)
- (2) Ambient sound level is less than 50 dBA and the average SPL of the voice message is 10–15 dBA greater than the ambient sound level
- (3) No appreciable hard surfaces (e.g., glass, marble, tile, metal)
- (4) No appreciable high ceilings (i.e., ceiling height equals loudspeaker spacing at a ratio of 1:1 optimal or 1:2 max)

D.3.6.2.2 It might be acceptable to only spot test intelligibility. One possible reason for spot sample testing is where the space has been acoustically designed by individuals having skills sufficient to properly design a voice/alarm system for the occupancy to be protected (e.g., space has been designed using commercially available computer modeling software acceptable to the authority having jurisdiction).

D.3.6.2.3 Possible reasons to test include the following:

- (1) Appreciable hard surfaces (e.g., glass, marble, tile, metal)
- (2) Appreciable high ceilings (e.g., atriums, multiple ceiling heights)

D.3.6.3 In situations where there are several ADSs that have the exact same physical and system configuration, it might be possible to test only a representative sample and then just check the others to confirm system and appliance operation — for example, hotel rooms with similar layouts or offices of similar size and furnishings where each has a loudspeaker appliance. In these cases there would be no expected difference in system intelligibility. The only possible problem would be one where an appliance was not operational or tapped at the incorrect wattage. These problems would be apparent by a basic “listening” test.

D.3.6.4 Not all ADSs will require speech intelligibility testing. Some areas might be designed for notification, but not for voice communication. Notification can be accomplished by

tone-only signaling or by a pre-alert tone preceding a voice message. See D.3.5.5.

D.3.6.5 By definition, an ADS is relatively uniform in acoustic characteristics. However, speech intelligibility will vary at different points within an ADS depending primarily on distance to noise sources and distance to loudspeaker appliances. Generally, in smaller spaces up to about 40 ft × 40 ft (12.2 m × 12.2 m), one measurement location will be sufficient. The location should not be directly in front of a wall mounted loudspeaker or directly under a ceiling mounted loudspeaker. Neither should it be in the far corner right next to walls or windows. Generally, try to stay about 5 to 10 ft (1.5 to 3.0 m) away from vertical surfaces that reflect sound. In larger spaces, a grid of about 40 ft × 40 ft (12.2 m × 12.2 m) can be used as a starting guide, then adjusted for the locations of machines and other obstructions and for loudspeaker appliance locations. See D.2.4 for additional discussion on measuring points and the averaging of results in an ADS.

D.3.6.6 Of the ADSs that do require intelligible voice communications, some will require speech intelligibility testing and others might only require audibility testing.

D.3.6.7 Testing of intelligibility might not be required in buildings and areas of buildings that are not acoustically challenging and that meet the audibility requirements of *NFPA 72*. Spaces that are not considered to be acoustically challenging include traditional office environments, hotel guest rooms, spaces with carpeting and furnishings that reduce reverberation, and other, smaller spaces where a loudspeaker appliance is installed in the space.

D.3.7 Measurement Points Within ADS.

D.3.7.1 Measurements should be taken at an elevation of 5 ft (1.5 m) or at any other elevation deemed appropriate based on occupancy (e.g., elevated walkways, child-height, sitting height, work area height, etc.) or test instrument instructions.

D.3.7.2 The number and location of measurement points in each ADS should be planned and based on the area and volume of the space and the loudspeaker appliance location within the space. The location of noise sources, egress paths, and the locations of personnel in the space should also be considered.

D.3.7.3 Testing when the area is occupied and when the ambient sound level is at or near its expected maximum is preferred because it is easier. However, it does involve playing of a test signal through the emergency communications system for the duration of the test. When testing using the STIPA signal, the signal is a continuous noise signal. Other methods that measure STI use a swept tone that should be repeated for each measurement location. The alternate procedure is to test and save the STI measurement data during unoccupied times, measure and save the unoccupied sound level, and then take and save sound level measurements during occupied times. The three data sets are combined by software to calculate the corrected STI for the area. Testing using this method requires three measurements at each measurement location, but does not subject occupants to constant test signals. The choice of testing occupied versus unoccupied for intelligibility is the same as for audibility testing of tone signaling systems and is based on convenience versus disruption of normal use of the space. However, unlike audibility testing, intelligibility testing is less likely to contribute to the Cry Wolf Syndrome because the

test signal is not the same as the evacuation tone, which would be sounded throughout testing of a tone signaling system. [Ref: Schifiliti, Robert P., "Fire Alarm Testing Strategies Can Improve Occupant Response and Reduce the "Cry Wolf" Syndrome," NEMA Supplement in Fire Protection Engineering, Society of Fire Protection Engineers, Bethesda, MD 20814, Fall 2003.] and [Ref: Breznitz, S., *Cry Wolf: The Psychology of False Alarms*, Lawrence Erlbaum Associates, Hillsdale, NJ, February 1984.]

D.3.7.4 If multiple measurement points are required within an ADS, they should be separated by about 40 ft (12.2 m).

D.3.7.5 No more than one third of the measurement points within an ADS should be on the axis of a loudspeaker.

D.3.7.6 See D.2.4 for the requirements for averaging the results at different measurement points within an ADS.

D.3.7.7 Measurement points should be shown on plans or otherwise described in a way that permits future testing at the same locations.

D.3.8 Test Method — Occupied versus Unoccupied.

D.3.8.1 It is possible to conduct STI measurements when the area is occupied or when it is not occupied. In this document "occupied" versus "unoccupied" is intended to be consistent with the definitions in D.2.3 for occupied ambient sound pressure level and for unoccupied ambient sound pressure level.

D.3.8.2 The preferred procedure is to conduct the STI/STIPA test in the presence of the occupied ambient sound pressure level. See D.6.4.

D.3.8.3 Where the test method is measuring the STI using the STIPA test signal, the STIPA test signal can be played through the system and the STI can be measured and the data saved by the test instrument when the area is either not occupied or when the background ambient conditions are not the occupied ambient sound pressure level. It is also necessary to measure and save the unoccupied ambient sound level at each measurement location. Then, during occupied times, take and save ambient sound level measurements. The three data sets are combined by software to calculate the corrected STI for the area. See D.6.5.6.

D.4 Test Equipment Calibration for Testing Using STIPA Test Signal.

D.4.1 General.

D.4.1.1 The calibration of the STI test instrument is done in accordance with this section using a talkbox or in accordance with manufacturer's published instructions.

D.4.1.2 The Intelligibility Test System consists of a talkbox and STIPA test meter (analyzer) all from one manufacturer. Units from other manufacturers should not be interchanged unless said units have been tested by a recognized testing laboratory for compatibility (*see D.2.3.5.2*).

D.4.1.3 Prior to performing any intelligibility testing or intelligibility system calibration, verify that the test meter's microphone, talkbox, and analyzer are within calibration date as listed on the unit's calibration tag.

D.4.1.4 All audio test equipment, including ANSI Type 2 sound pressure level meters required by *NFPA 72* for audibility testing, require regular calibration to known, traceable standards. The portable meters used to measure STI using the STIPA

test signal should meet or exceed ANSI Type 2 meter requirements. In addition, the STIPA test signal and the meter algorithm for measuring the received signal and calculating the modulation transfer function to arrive at the STI should be tested by a certifying laboratory for accuracy to the IEC standard for STI.

D.4.2 Calibration Procedure.

D.4.2.1 The following procedures should be performed at the commencement and conclusion of intelligibility testing. If the following procedure differs from that recommended by the manufacturer of the test equipment, follow their calibration test procedure.

D.4.2.2 Perform calibration procedures in a quiet room (45 dBA or less) without any extraneous sounds or any talking, music, etc.

D.4.2.3 Start STIPA test tone as instructed by the manufacturer.

D.4.2.4 Apply power to the talkbox and then actuate the STIPA test signal.

D.4.2.5 Turn on the analyzer and set it to SPL A fast measurement mode.

D.4.2.6 Place the analyzer's microphone approximately 1 in., on axis, from the talkbox. Do not place the analyzer microphone against any hard surface — this can lead to induced noise and affect the calibration.

D.4.2.7 Adjust the talkbox volume so that the STI analyzer's reading is approximately 92 dBA.

D.4.2.8 Keeping the analyzer in approximately the same position, measure the STI. Note that some meters display STI measurements using the CIS scale while some can display results in either STI or CIS units. See D.2.4 for an explanation of the CIS scale.

D.4.2.9 The equipment is working properly if the reading is greater than 0.91 STI or 0.96 CIS. Up to three tests can be performed. If the system does not pass after three tests, it should be returned to the manufacturer for repair or recalibration.

D.5 Talkbox Set-up.

D.5.1 Input Test Signal.

D.5.1.1 The input test signal should be configured to produce the proper level by utilizing either the microphone input method or the direct input injection method.

D.5.1.2 Most emergency communications systems have microphones for manual voice communication and should be tested using the microphone test method. Systems that do not have microphones and that only play prerecorded voice announcements can be tested using the direct input injection method.

D.5.1.3 By putting the STI or STIPA test signal into the system via the system microphone, the ECS system is being tested from end to end. If an ECS system has the test signal prerecorded in its hardware, playback of that test signal would not be testing the microphone and the part that feeds the microphone signal into the system.

D.5.1.4 Direct Input Injection Method for Test Signals.

D.5.1.4.1 With this method the STI or STIPA test signals are prerecorded in the emergency communications system hardware in the same way as the prerecorded voice messages and at the same input levels. Alternately, the test signal can input to the system via input jacks or terminals.

D.5.1.4.2 The input level of the test signal should be tested by the ECS listing agency as being the same as the prerecorded voice levels or should be calibrated using the ECS equipment manufacturer's published instructions.

D.5.1.4.3 For ECS systems that permit voice messages to be custom recorded, the equivalent sound level (*see A.18.4.4.1*) L_{eq} of the recorded voice over a period of 10 seconds or the length of the voice message should be measured and should be within 3 dB of the prerecorded STI or STIPA test signal to ensure that it is at the correct level.

D.5.1.4.4 Field measurements of the STI are made using the procedure in Section D.5.

D.5.1.5 Microphone Input Method for Test Signals.

D.5.1.5.1 With this method a recording of the STI or STIPA test signals are played into the system microphone using a talkbox.

D.5.1.5.2 The talkbox is set up and calibrated per D.5.2, and field measurements of the STI are made using the procedure in Section D.6.

D.5.2 Calibrating the Input Test Signal for Microphone Input Method.

D.5.2.1 Of the two methods for setting the test signal input to the system microphone, the method that sets the level to match that of a person speaking into the microphone is the one required by IEC 60268-16, *Sound system equipment — Part 16: Objective rating of speech intelligibility by speech transmission index*, the standard that defines STI and STIPA.

D.5.2.2 In theory, the two methods for setting up the talkbox should result in the talkbox being set at approximately the same sound level. The ECS should be designed and configured so that input to the microphone results in the same output level that any prerecorded announcements would produce.

D.5.2.3 General.

D.5.2.3.1 There are two methods for setting the level of the STI or STIPA test signal at the input microphone.

D.5.2.3.2 Method 1 sets the volume of the input test signal so that the dBA output in the area under test is the same as that for a prerecorded message.

D.5.2.3.3 Method 2 sets the volume of the input test signal to match that of speech level under normal conditions.

D.5.2.3.4 The room where the talkbox and system under test microphone are located should be quiet.

D.5.2.3.5 An emergency command center or fire command center will not be free of noise during an actual emergency. However, for testing purposes, the room should be relatively free of extraneous noises that could affect the results. The purpose of the tests is to establish the baseline capability of the system and acoustic environment to support intelligible communications. Good design practice for an emergency

command center is to isolate the space so that only emergency command personnel have access. In addition, the location of the microphone for manual input should be such that background discussions and noise are minimized.

D.5.2.3.6 Set up the talkbox in accordance with the manufacturer's published instructions.

D.5.2.4 Method 1 — Matching Recorded Message Level.

D.5.2.4.1 The intent of this method is to set the talkbox or audio source input level into the emergency communications system microphone so that the output at a location in the area under test is the same as the level of prerecorded messages played by the system.

D.5.2.4.2 The sound pressure level produced by the talkbox while playing the STI or STIPA test signal should be matched with the sound pressure level of the prerecorded voice message.

D.5.2.4.3 Two people will be needed to perform the calibration procedure. One person needs to be present at the talkbox while the other person needs to operate the analyzer at a typical location in the facility.

D.5.2.4.4 At a typical location in the facility, position the analyzer so its microphone is approximately 5 ft (1.5 m) above the finished floor.

D.5.2.4.5 Set the analyzer (meter) to measure sound pressure level, A-weighted, fast.

D.5.2.4.6 Actuate the prerecorded voice message from the ECS.

D.5.2.4.7 The decibel reading at the analyzer will be somewhat erratic due to the nature of speech signals.

D.5.2.4.8 Record the highest dB reading the system produces.

D.5.2.4.9 Do not move the analyzer from the test location.

D.5.2.4.10 Turn off the prerecorded voice message.

D.5.2.4.11 Place the microphone of the emergency communications system at a distance from the talkbox as recommended by the microphone or ECS manufacturer.

D.5.2.4.12 Start the talkbox STI or STIPA test signal.

D.5.2.4.13 Adjust the talkbox sound level until the field measurement of the test signal is ± 3 dB of the level generated when the prerecorded voice message was played and measured. This setting should not change for the remainder of the testing.

D.5.2.4.14 Begin field testing in accordance with Section D.6.

D.5.2.5 Method 2 — Matching Speech Level.

D.5.2.5.1 The intent of this method is to set the talkbox or audio source input level to the emergency communications system microphone to match that of an average person speaking into the microphone.

D.5.2.5.2 Set the analyzer (meter) to measure sound pressure level, A-weighted, fast.

D.5.2.5.3 Start the STI or STIPA test signal and hold the meter at a distance of 39.4 in. (1.0 m) on-axis from the talkbox or audio source.

D.5.2.5.4 Set the talkbox volume (level) so that the meter registers 65 dBA at a distance of 39.4 in. (1.0 m). This setting should not change for the remainder of the testing.

D.5.2.5.5 The distance from the microphone to the talkbox should be documented so that future tests can be set up consistently. Most microphone manufacturers or ECS equipment manufacturers will state a recommended distance for a person to hold the microphone when talking. Some microphone use chin guards or some physical means to help users know when they are holding the microphone at the correct distance. If the manufacturer has not recommended a talking distance, 4 in. (100 mm) is recommended as a guide.

D.5.2.5.6 Place the microphone of the emergency communications system at a distance from the talkbox as recommended by the microphone or ECS manufacturer.

D.5.2.5.7 A level of 60 dBA at one meter is required by IEC 60268-16, *Sound system equipment — Part 16: Objective rating of speech intelligibility by speech transmission index*, the standard that defines STI and STIPA and is considered a normal speech level. While 60 dBA at 1 m is documented as “normal” speech, in areas where there is background noise, the Lombard effect causes a person to talk at an elevated volume. For this document, the committee chose to use 65 dBA as more representative of speech levels during emergency situations. It is recommended that at least one field STI measurement be made at both 60 dBA and 70 dBA at one meter talking level to test the effects of elevated voice level.

D.5.2.5.8 Sound pressure level increases 6 dB whenever the distance is halved. So, the test could be set up so that the talkbox level achieves $65 + 6 = 71$ dBA at a distance of 19.7 in. (0.50 m). Table D.5.2.5.8 shows different dB levels at distances that would be equivalent to 65 dBA at 39.4 in. (1.0 m).

D.5.2.5.9 Begin field testing in accordance with Section D.6.

D.6 STI/STIPA Test Procedure.

D.6.1 General. This test procedure permits testing during either occupied conditions or during unoccupied conditions. See D.3.8.

D.6.2 Power. The system under test should be tested on secondary power for a minimum of 15 minutes and then on primary power for the remainder of the testing.

D.6.3 System Operation. Where two ADSs are adjacent to each other and not separated by physical barriers that significantly prevent noise penetration from one ADS to another, the notification appliances in both ADSs should be operating during the testing. It is acceptable for intelligibility testing to

silence or disable other notification zones that would not potentially interfere with each other. However, regular testing per *NFPA 72* would require that all circuits be operated simultaneously at one point to ensure proper operation and to verify power requirements.

D.6.4 Occupied Testing.

D.6.4.1 Testing should be done during a period of time when the area is occupied and is reasonably close to having maximum background noise.

D.6.4.2 Set up the talkbox in accordance with Section D.4 and start the STI or STIPA test signal.

D.6.4.3 At each measurement point in each ADS measure the STI.

D.6.4.4 Document the results on plans or forms in a way that accurately describes the measurement point and that permits future testing at the same locations.

D.6.5 Unoccupied Testing.

D.6.5.1 General. Testing of speech intelligibility in the presence of the occupied ambient sound pressure level is the preferred method. However, for various reasons, including disruption of normal work, it might be desirable to only do “silent” testing during occupied periods and to do testing with the STI or STIPA test signal during unoccupied or less occupied conditions.

D.6.5.2 Number of Tests. This test method requires three different measurements at each measurement point, typically made during two site visits. The data for each measurement is saved in a format in accordance with the instrument manufacturer’s requirements. The three data files are then post-processed to arrive at the final corrected STI.

D.6.5.3 Occupied Ambient Sound Pressure Level Measurement.

D.6.5.3.1 At each measurement point in each ADS measure the occupied ambient sound pressure level.

D.6.5.3.2 Save the measurement data in accordance with the instrument manufacturer’s requirements to permit post-processing of the data.

D.6.5.3.3 Document the results on plans or forms in a way that accurately describes the measurement point and that permits future testing at the same locations.

D.6.5.4 Unoccupied Ambient Sound Pressure Level Measurement.

D.6.5.4.1 At each measurement point in each ADS measure the unoccupied ambient sound pressure level.

D.6.5.4.2 Save the measurement data in accordance with the instrument manufacturer’s requirements to permit post-processing of the data.

D.6.5.4.3 Document the results on plans or forms in a way that accurately describes the measurement point and that permits future testing at the same locations.

D.6.5.5 Unoccupied STI Measurement.

D.6.5.5.1 Set up the talkbox in accordance with Section D.4 and start the STI or STIPA test signal.

Table D.5.2.5.8 Audibility Equivalent to 65 dBA at 1-m Distance

L_p			L_p			L_p		
r (in.)	r (m)	(dB)	r (in.)	r (m)	(dB)	r (in.)	r (m)	(dB)
0.1	0	117	4	0.10	85	11	0.28	76
0.2	0.01	111	5	0.13	83	12	0.30	75
0.5	0.01	103	6	0.15	81	20	0.50	71
1.0	0.03	97	7	0.18	80	24	0.61	69
1.5	0.04	93	8	0.20	79	39.37	1.00	65
2.0	0.05	91	9	0.23	78	78.8	2.00	59
3.0	0.08	87	10	0.25	77			

D.6.5.5.2 At each measurement point in each ADS measure the uncorrected STI.

D.6.5.5.3 Save the measurement data in accordance with the instrument manufacturer's requirements to permit post-processing of the data.

D.6.5.5.4 Document the results on plans or forms in a way that accurately describes the measurement point and that permits future testing at the same locations.

D.6.5.6 Post-Processing.

D.6.5.6.1 The corrected STI is arrived at by post-processing of the occupied ambient sound pressure level measurement, the unoccupied ambient sound pressure level measurement, and the unoccupied STI measurement. In effect, the measured STI (uncorrected) is being corrected by adding in the effects of the actual expected (occupied) ambient sound pressure level.

D.6.5.6.2 The post-processing procedure or software provided by the instrument manufacturer should be used to calculate the final corrected STI for each measurement point.

D.6.5.6.3 Document the results on plans or forms in a way that accurately describes the measurement point and that permits future testing at the same locations.

D.6.5.6.4 Documentation of the final results for each point should include the results of all three measurements and the final corrected STI value. The manufacturer's software revision should also be included in the results documentation.

D.7 Post Test Procedures.

D.7.1 Test Closure. Upon completion of all testing, the emergency communications system should be returned to its normal operating condition.

D.7.2 Results.

D.7.2.1 It is also not the intent of this test protocol to describe how to interpret results or how to correct systems or environments that contribute to poor speech intelligibility. However, depending on the instrument used, it might be possible to have data retained by the instrument to determine possible causes and their effects on STI results. Consult with the instrument manufacturer to determine if the instrument has the capability to display or save the intermediate STI modulation indices and octave band measurement results and for instructions on how to interpret those data.

D.7.2.2 For each ADS, summarize the results in accordance with the performance requirements of D.2.4.

D.7.2.3 For an ADS that had multiple measurement points or that had multiple measurements at only one measurement point, calculate the average per D.2.4 and list the average and the minimum measurement per D.2.4 in the results summary.

D.7.3 Documentation.

D.7.3.1 The test results should be fully documented and provided to the building owner, the emergency communications system contractor, the system designer, the authority having jurisdiction, and any other individual or organization deemed appropriate.

D.7.3.2 In addition to the requirements for test documentation contained in *NFPA 72*, Chapter 10, the test results should include:

- (1) Building location and related descriptive facility information
- (2) Names, titles, and contact information for individuals involved in test
- (3) Dates and times of tests
- (4) A list of testing instruments, including manufacturer's name, model, serial number, and date of most recent calibration
- (5) Technical description of emergency communications system
- (6) Identification of ADSs
- (7) Locations of specific measurement points (in a list or on a set of drawings)
- (8) Site definition of ambient sound pressure levels
- (9) STI/STIPA measurements at each measurement point
- (10) Final corrected STI/STIPA values where the post-processing procedure is used
- (11) Indication of whether or not the test met the pass/fail criteria
- (12) Record of system restoration
- (13) Any additional information to assist with future evaluation of system performance

D.7.3.3 If appropriate, the plans and specifications addressed in D.3.3 should be updated based on the results of the test.

Annex E Sample Ordinance Adopting NFPA 72

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

E.1 The following sample ordinance is provided to assist a jurisdiction in the adoption of this Code and is not part of this Code.

ORDINANCE NO. _____

An ordinance of the [jurisdiction] adopting the 2022 edition of *NFPA 72, National Fire Alarm and Signaling Code*, and documents listed in Chapter 2 of that Code; prescribing regulations governing conditions hazardous to life and property from fire or explosion; providing for the issuance of permits and collection of fees; repealing Ordinance No. _____ of the [jurisdiction] and all other ordinances and parts of ordinances in conflict therewith; providing a penalty; providing a severability clause; and providing for publication; and providing an effective date.

BE IT ORDAINED BY THE [governing body] OF THE [jurisdiction]:

SECTION 1 That the *NFPA 72, National Fire Alarm and Signaling Code*, and documents adopted by Chapter 2, three (3) copies of which are on file and are open to inspection by the public in the office of the [jurisdiction's keeper of records] of the [jurisdiction], are hereby adopted and incorporated into this ordinance as fully as if set out at length herein, and from the date on which this ordinance shall take effect, the provisions thereof shall be controlling within the limits of the [jurisdiction]. The same are hereby adopted as the Code of the [jurisdiction] for the purpose of prescribing regulations governing conditions hazardous to life and property from fire or explosion and providing for issuance of permits and collection of fees.

SECTION 2 Any person who shall violate any provision of this code or standard hereby adopted or fail to comply there-

with; or who shall violate or fail to comply with any order made thereunder; or who shall build in violation of any detailed statement of specifications or plans submitted and approved thereunder; or fail to operate in accordance with any certificate or permit issued thereunder; and from which no appeal has been taken; or who shall fail to comply with such an order as affirmed or modified by a court of competent jurisdiction, within the time fixed herein, shall severally for each and every such violation and noncompliance, respectively, be guilty of a misdemeanor, punishable by a fine of not less than \$ _____ nor more than \$ _____ or by imprisonment for not less than _____ days nor more than _____ days or by both such fine and imprisonment. The imposition of one penalty for any violation shall not excuse the violation or permit it to continue; and all such persons shall be required to correct or remedy such violations or defects within a reasonable time; and when not otherwise specified the application of the above penalty shall not be held to prevent the enforced removal of prohibited conditions. Each day that prohibited conditions are maintained shall constitute a separate offense.

SECTION 3 Additions, insertions, and changes — that the 2022 edition of *NFPA 72, National Fire Alarm and Signaling Code*, is amended and changed in the following respects:

List Amendments

SECTION 4 That ordinance No. _____ of [jurisdiction] entitled [fill in the title of the ordinance or ordinances in effect at the present time] and all other ordinances or parts of ordinances in conflict herewith are hereby repealed.

SECTION 5 That if any section, subsection, sentence, clause, or phrase of this ordinance is, for any reason, held to be invalid or unconstitutional, such decision shall not affect the validity or constitutionality of the remaining portions of this ordinance. The [governing body] hereby declares that it would have passed this ordinance, and each section, subsection, clause, or phrase hereof, irrespective of the fact that any one or more sections, subsections, sentences, clauses, and phrases be declared unconstitutional.

SECTION 6 That the [jurisdiction's keeper of records] is hereby ordered and directed to cause this ordinance to be published.

[NOTE: An additional provision might be required to direct the number of times the ordinance is to be published and to specify that it is to be in a newspaper in general circulation. Posting may also be required.]

SECTION 7 That this ordinance and the rules, regulations, provisions, requirements, orders, and matters established and adopted hereby shall take effect and be in full force and effect [time period] from and after the date of its final passage and adoption.

Annex F Wiring Diagrams and Guide for Testing Fire Alarm Circuits

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

Annex F provides guidance for testing of the various classes of circuits identified in Chapter 12 of this edition of NFPA 72. Earlier editions of NFPA 72 have used different designations for these circuits. Designations found in previous editions (located in Annex C of NFPA 72, 2007 edition or earlier) can be compared with these corresponding diagrams.

F.1 General. Circuit class designations in this edition of the Code are Class A, B, C, D, E, N, and X. Definitions can be found in Chapter 12. Additionally, special circuits unique to supervising stations are designated as Types 4, 5, 6, and 7, and definitions can be found in Chapter 26.

The wiring diagrams depicted in Figure F.2.1.1 through Figure F.3.14(k) are representative of typical circuits encountered in the field and are not intended to be all-inclusive.

The noted symbols are as indicated in NFPA 170.

An individual point-identifying (i.e., addressable) fire alarm initiating device operates on a signaling line circuit and is designated as a Class A, Class B, or Class X initiating device circuit. All fire alarm circuits must test free of grounds because metallic conductors will cause failure of the circuit when a second ground condition occurs on the same power source.

Nonmetallic circuit paths, such as low-power radio and optical fiber cable, might still be designated as Class A, B, or X if they meet the other performance requirements of those pathways.

The following initiating device circuits are illustrative of either alarm or supervisory signaling. Alarm-initiating devices and supervisory initiating devices are not permitted to have identical annunciation at the fire alarm control unit.

Directly connected system smoke detectors, commonly referred to as two-wire detectors, should be listed as being electrically and functionally compatible with the fire alarm control unit and the specific subunit or module to which they are connected. If the detectors and the units or modules are not compatible, it is possible that, during an alarm condition, the detector's visible indicator will illuminate, but no change of state to the alarm condition will occur at the fire alarm control unit. Incompatibility can also prevent proper system operation at extremes of operating voltage, temperature, and other environmental conditions.

Where two or more two-wire detectors with integral relays are connected to a single initiating device circuit, and their relay contacts are used to control essential building functions (e.g., fan shutdown, elevator recall), it should be clearly noted that the circuit might be capable of supplying only enough energy to support one detector/relay combination in an alarm mode. If control of more than one building function is required, each detector/relay combination used to control separate functions should be connected to separate initiating device circuits, or they should be connected to an initiating device circuit that provides adequate power to allow all the detectors connected to the circuit to be in the alarm mode simultaneously. During acceptance and reacceptance testing, this feature should always be tested and verified.

A loudspeaker is an alarm notification appliance, and, if used as shown in the diagrams in Section F.2, the principle of operation and supervision is the same as for other audible alarm notification appliances (e.g., bells and horns).

The testing of supervised remote relays is to be conducted in the same manner as for notification appliances.

F.2 Wiring Diagrams and Testing. When testing circuits, the correct wiring size, insulation type, and conductor fill should be verified in accordance with the requirements of NFPA 70.

F.2.1 Testing Nonpowered, Hard-Wired Class A, B, or C Initiating Device Circuits. Disconnect conductor at device or control unit, then reconnect. Temporarily connect a ground to either leg of conductors, then remove ground. Both operations should indicate audible and visual trouble with subsequent restoration at control unit.

F.2.1.1 Hard-Wired Alarm Initiating or Supervisory Initiating Devices. Hard-wired alarm initiating devices (e.g., manual station or valve supervisory switch), by their intended function, initiate alarm upon a conductor-to-conductor short. See Figure F.2.1.1.

F.2.2 Nonpowered Class A Circuits. Disconnect a conductor at a device at midpoint in the circuit. Operate a device on either side of the device with the disconnected conductor. Reset fire alarm control unit and reconnect conductor. Repeat test with a ground applied to either conductor in place of the disconnected conductor. Both operations should indicate audible and visual trouble, then alarm or supervisory indication with subsequent restoration.

F.2.3 Circuit-Powered (Two-Wire) Smoke Detectors for Class A or B Initiating Device Circuits. Remove smoke detector where installed with plug-in base or disconnect conductor from fire alarm control unit beyond first device. Actuate smoke detector per manufacturer's published instructions between fire alarm control unit and circuit break. Restore detector or circuit, or both. Fire alarm control unit should indicate trouble when fault occurs and alarm when detectors are actuated between the break and the fire alarm control unit. See Figure F.2.3.




FIGURE F.2.1.1 Nonpowered Alarm Initiating or Supervisory Initiating Devices Connected to Hard-Wired and Class B Initiating Device Circuits.




FIGURE F.2.3 Circuit-Powered (Two-Wire) Smoke Detectors for Class A or B Initiating Device Circuits.

F.2.4 Circuit-Powered (Two-Wire) Smoke Detectors for Class A Initiating Device Circuits. Disconnect conductor at a smoke detector or remove where installed with a plug-in base at midpoint in the circuit. Operate a device on either side of the device with the fault. Reset control unit and reconnect conductor or detector. Repeat test with a ground applied to either conductor in place of the disconnected conductor or removed device. Both operations should indicate audible and visual trouble, then alarm indication with subsequent restoration. See Figure F.2.4.

F.2.5 Combination Alarm Initiating Device and Notification Appliance Circuits. Disconnect a conductor either at indicating or initiating device. Actuate initiating device between the fault and the fire alarm control unit. Actuate additional smoke detectors between the device first actuated and the fire alarm control unit. Restore circuit, initiating devices, and fire alarm control unit. Confirm that all notification appliances on the circuit operate from the fire alarm control unit up to the fault and that all smoke detectors tested and their associated ancillary functions, if any, operate. See Figure F.2.5.

F.2.6 Combination Alarm Initiating Device and Notification Appliance Circuits Arranged for Operation with Single Open or Ground Fault. Testing of the circuit is similar to that described in F.2.5. Confirm that all notification appliances operate on either side of fault. See Figure F.2.6.




FIGURE F.2.4 Circuit-Powered (Two-Wire) Smoke Detectors for Class A Initiating Device Circuits.




FIGURE F.2.5 Combination Alarm Initiating Device and Notification Appliance Circuits.




FIGURE F.2.6 Combination Alarm Initiating Device and Notification Appliance Circuits Arranged for Operation with Single Open or Ground Fault.

F.2.7 Class A or B Circuits with Four-Wire Smoke Detectors and End-of-Line Power Supervision Relay. Testing of the circuit is similar to that described in F.2.3 and F.2.4. Disconnect a leg of the power supply circuit beyond the first device on the circuit. Actuate initiating device between the fault and the fire alarm control unit. Restore circuits, initiating devices, and fire alarm control unit. Audible and visual trouble should indicate at the fire alarm control unit where either the initiating or power circuit is faulted. All initiating devices between the circuit fault and the fire alarm control unit should actuate. In addition, removal of a smoke detector from a plug-in-type base can also break the power supply circuit. Where circuits contain various powered and nonpowered devices on the same initiating circuit, verify that the nonpowered devices beyond the power circuit fault can still initiate an alarm. A return loop should be brought back to the last powered device and the power supervisory relay to incorporate into the end-of-line device. See Figure F.2.7.

F.2.8 Class B Initiating Device Circuits with Four-Wire Smoke Detectors That Include Integral Individual Supervision Relays. Testing of the circuit is similar to that described in F.2.3 with the addition of a power circuit. See Figure F.2.8.

F.2.9 Alarm Notification Appliances Connected Class B (Two-Wire) Circuits. Testing of the notification appliances connected as Class B is similar to that described in F.2.3. See Figure F.2.9.

F.2.10 Alarm Notification Appliances Connected to Class A (Four-Wire) Circuits. Testing of the notification appliances connected as Class A is similar to that described in F.2.4. See Figure F.2.10.

F.2.11 System with Supervised Audible Notification Appliance Circuit and Unsupervised Visual Notification Appliance Circuit. Testing of the notification appliances connected to Class B is similar to that described in F.2.4. See Figure F.2.11.

F.2.12 System with Supervised Audible and Visual Notification Appliance Circuits. Testing of the notification appliances connected to Class B is similar to that described in F.2.4. See Figure F.2.12.

F.2.13 Series Notification Appliance Circuit That No Longer Meets Requirements of NFPA 72. An open fault in the circuit wiring should cause a trouble condition. See Figure F.2.13.

F.2.14 Supervised Series Supervisory Initiating Circuit with Sprinkler Supervisory Valve Switches Connected That No Longer Meets Requirements of NFPA 72. An open fault in the circuit wiring or operation of the valve switch (or any supervisory signal device) should cause a trouble condition. The classification of this circuit is now designated as Class D because the intended operation is performed. When the circuit fails, the indication at the fire control unit is the same as if the supervisory switch were to open. Fire alarm initiating devices, including supervisory inputs, are no longer allowed to annunciate as trouble conditions. See Figure F.2.14.

F.2.15 Initiating Device Circuit with Parallel Waterflow Alarm Switches and Series Supervisory Valve Switch That No Longer Meets Requirements of NFPA 72. An open fault in the circuit wiring or operation of the valve switch should cause a trouble signal. See Figure F.2.15.




FIGURE F.2.7 Class B Circuits with Four-Wire Smoke Detectors and End-of-Line Power Supervision Relay.




FIGURE F.2.8 Class B Initiating Device Circuits with Four-Wire Smoke Detectors That Include Integral Individual Supervision Relays.




FIGURE F.2.9 Alarm Notification Appliances Connected to Class B (Two-Wire) Circuits.




FIGURE F.2.10 Alarm Notification Appliances Connected to Class A (Four-Wire) Circuits.




FIGURE F.2.11 Supervised Audible Notification Appliance Circuit and Unsupervised Visual Notification Appliance Circuit.

F.2.16 System Connected to Municipal Fire Alarm Master Box Circuit. Disconnect a leg of municipal circuit at master box. Verify alarm sent to public communications center. Disconnect leg of auxiliary circuit. Verify trouble condition on control unit. Restore circuits. Actuate control unit and send alarm signal to communications center. Verify control unit in trouble condition until master box reset. See Figure F.2.16.

F.2.17 Auxiliary Circuit Connected to Municipal Fire Alarm Master Box. For operation with a master box, an open or ground fault (where ground detection is provided) on the circuit should result in a trouble condition at the fire alarm control unit. A trouble signal at the fire alarm control unit should persist until the master box is reset. For operation with




FIGURE F.2.12 Supervised Audible and Visual Notification Appliance Circuits.




FIGURE F.2.13 Series Notification Appliance Circuit.




FIGURE F.2.14 Supervised Series Supervisory Initiating Circuit with Sprinkler Supervisory Valve Switches Connected.




FIGURE F.2.15 Initiating Device Circuit with Parallel Waterflow Alarm Switches and Series Supervisory Valve Switch.




FIGURE F.2.16 System Connected to Municipal Fire Alarm Master Box Circuit.

a shunt trip master box, an open fault in the auxiliary circuit should cause an alarm on the municipal system. See Figure F.2.17.

F.3 Circuit Classes. Some testing laboratories and authorities having jurisdiction permitted systems to be classified as Class X by the application of two circuits operating in tandem. An example of this is to take two series circuits, Class B, and operate them in tandem. The logic was that if a condition occurs on one of the circuits, the other series circuit remained operative.

To understand the principles of the circuit, alarm receipt capability should be performed on a single circuit, and the Class type, based on the performance, should be indicated on the record of completion.

F.3.1 Style 0.5. This signaling circuit operates as a series circuit in performance. This is identical to the historical series audible signaling circuits. Any type of break or ground in one of the conductors, or the internal of the multiple interface device, and the total circuit is rendered inoperative.

To test and verify this type of circuit, either a conductor should be lifted or an earth ground should be placed on a conductor or a terminal point where the signaling circuit attaches to the multiplex interface device.

F.3.2 Style 0.5(a) (Class B) Series That No Longer Meets Requirements of NFPA 72. Style 0.5(a) functions so that, when a box is operated, the supervisory contacts open, making the succeeding devices nonoperative while the operating box sends a coded signal. Any alarms occurring in any successive devices will not be received at the receiving station during this period. See Figure F.3.2.

F.3.3 Style 0.5(b) Shunt That No Longer Meets Requirements of NFPA 72. The contact closures when the device is operated (and remains closed) to shunt out the remainder of the system until the code is complete. See Figure F.3.3.

F.3.4 Style 0.5(c) Positive Supervised Successive That No Longer Meets Requirements of NFPA 72. An open or ground fault on the circuit should cause a trouble condition at the control unit. See Figure F.3.4.




FIGURE F.2.17 Auxiliary Circuit Connected to Municipal Fire Alarm Master Box.




FIGURE F.3.2 Style 0.5(a) Series.

F.3.5 Style 1.0 That No Longer Meets Requirements of NFPA 72. This is a series circuit identical to the diagram for Style 0.5, except that the fire alarm system hardware has enhanced performance. [See Figure F.3.5(a) and Figure F.3.5(b).] A single earth ground can be placed on a conductor or multiplex interface device, and the circuit and hardware will still have alarm operability.

If a conductor break or an internal fault occurs in the pathway of the circuit conductors, the entire circuit becomes inoperative.

To verify alarm receipt capability and the resulting trouble signal, place an earth ground on one of the conductors or at the point where the signaling circuit attaches to the multiplex interface device. One of the transmitters or an initiating device should then be placed into alarm.

F.3.6 Typical McCulloh Loop. This is the central station McCulloh redundant-type circuit and has alarm receipt capability on either side of a single break. See Figure F.3.6.

F.3.6.1 To test, lift one of the conductors and operate a transmitter or initiating device on each side of the break. This activity should be repeated for each conductor.

F.3.6.2 Place an earth ground on a conductor and operate a single transmitter or initiating device to verify alarm receipt capability and trouble condition for each conductor.

F.3.6.3 Repeat the instructions of F.3.6.1 and F.3.6.2 at the same time, verify alarm receipt capability, and verify that a trouble condition results.

F.3.7 Class B (Formerly Style 3.0). This is a parallel circuit in which multiplex interface devices transmit signal and operating power over the same conductors. (See Figure F.3.7.) The multiplex interface devices might be operable up to the point of a single break. Verify by lifting a conductor and causing an alarm condition on one of the units between the central alarm unit and the break. Either lift a conductor to verify the trouble condition or place an earth ground on the conductors. Test for all the valuations shown on the signaling table.




FIGURE F.3.3 Style 0.5(b) Shunt.




FIGURE F.3.4 Style 0.5(c) Positive Supervised Successive.

On ground-fault testing, verify alarm receipt capability by actuating a multiplex interface initiating device or a transmitter.

F.3.8 Style 3.5 That No Longer Meets Requirements of NFPA 72. Follow the instructions for Class B (formerly Style 3.0) and verify the trouble conditions by either lifting a conductor or placing a ground on the conductor. See Figure F.3.8.




FIGURE F.3.5(a) Style 1.0 (Class B).




FIGURE F.3.5(b) Typical Transmitter Layout.




FIGURE F.3.6 Typical McCulloh Loop.




FIGURE F.3.7 Class B (Formerly Style 3.0).




FIGURE F.3.8 Style 3.5.

F.3.9 Class B (Formerly Style 4.0). Follow the instructions for Class B (formerly Style 3.0) and include a loss of carrier where the signal is being used. See Figure F.3.9.

F.3.10 Style 4.5 That No Longer Meets Requirements of NFPA 72. Follow the instructions for Style 3.5. Verify alarm receipt capability while lifting a conductor by actuating a multiple interface device or transmitter on each side of the break. See Figure F.3.10.

F.3.11 Class A (Formerly Style 5.0). Verify the alarm receipt capability and trouble annunciation by lifting a conductor and actuating a multiplex interfacing device or a transmitter on each side of the break.

F.3.11.1 Ground Test on Class A (Formerly Style 5.0) Circuit. For the earth ground verification, place an earth ground and certify alarm receipt capability and trouble annunciation by actuating a single multiplex interfacing device or a transmitter. See Figure F.3.11.1.




FIGURE F.3.9 Class B (Formerly Style 4.0).




FIGURE F.3.10 Style 4.5 (Class B).




FIGURE F.3.11.1 Class A (Formerly Style 5.0).

F.3.12 Class A (Formerly Style 6.0). Follow the instructions from F.3.11. Verify the trouble annunciation for the various combinations. See Figure F.3.12.

F.3.13 Class A with Circuit Isolators. For the portions of the circuits electrically located between the monitoring points of circuit isolators, follow the instructions for a Class X circuit. It should be clearly noted that the alarm receipt capability for remaining portions of the circuit protection isolators is not the capability of the entire circuit but is permitted with enhanced system capabilities. See Figure F.3.13.

F.3.14 Class X (Formerly Style 7.0). Follow the instructions for testing of Class A (formerly Style 6.0) for alarm receipt capability and trouble annunciation. See Figure F.3.14(a) through Figure F.3.14(k).

NOTE: Some manufacturers of this type of equipment have isolators as part of the base assembly. Therefore, in the field, this component might not be readily observable without the assistance of the manufacturer's representative.




FIGURE F.3.12 Style 6.0 (Class A).




FIGURE F.3.13 Class A with Circuit Isolators.





FIGURE F.3.14(a) Class X (Formerly Style 7.0).



CU = Wireless control unit
(with power supply and standby power)
R = Wireless repeater
(with power supply and standby power)
D = Wireless initiating, indicating, and control device
(either primary battery or primary standby battery)

FIGURE E.3.14(b) Low-Power Radio (Wireless) Fire Alarm System.




FIGURE E.3.14(c) Two-Way RF Multiplex Systems.




FIGURE E.3.14(d) One-Way Radio Alarm System.




FIGURE E.3.14(e) One-Way Radio Alarm System (Type 6 and Type 7).






FIGURE E.3.14(f) Style 4 Fiber Network.



Style 4 fiber network where the control unit has a two-way path communications capability. A single break separates the system into two LANs, both with Style 4 capabilities.

CC = Control center
FACU = Fire alarm control unit


FIGURE E.3.14(g) Style 4 Fiber Network (Single Break).



Style 4 fiber network where the control unit has a two-way path communications capability. A double break isolates the control units and the control center in this case. There is one LAN and one isolated control unit operating on its own. Control center is isolated completely with no communications with the network.

CC = Control center
FACU = Fire alarm control unit


FIGURE F.3.14(h) Style 4 Fiber Network (Double Break).



Style 7 fiber network where the control unit has a two-way path communications capability with the two breaks now breaking into two LANs, both functioning as independent networks with the same Style 7 capabilities.

CC = Control center
FACU = Fire alarm control unit


FIGURE F.3.14(i) Style 7 Fiber Network (Two LANs).



Style 7 fiber network where the control unit has a two-way path communications capability, with one break. System remains as one LAN and meets Style 7.

CC = Control center
FACU = Fire alarm control unit

FIGURE F.3.14(j) Style 7 Fiber Network (One LAN).



Style 7 fiber network where the control unit has a two-way path communications capability.

CC = Control center
FACU = Fire alarm control unit

FIGURE F.3.14(k) Style 7 Fiber Network.

Annex G Guidelines for Emergency Communication Strategies for Buildings and Campuses

This annex is not part of the requirements of this NFPA document but is included for informational purposes only.

G.1 The material in this annex is based on the National Institute of Standards and Technology (NIST) and Fire Protection Research Foundation research *Guidance Document: Emergency Communication Strategies for Buildings*, by Erica Kuligowski, Ph.D. and H. Omori, 2014, as adapted by the NFPA ECS TC.

The purpose of this annex is to provide guidance to system designers, building managers, and/or building emergency personnel responsible for emergency communication on how to create and disseminate messages using basic communication modes (audible and/or visual technology). The guidance provided here is taken directly from a report published by the National Institute of Standards and Technology, which was based on a review of 162 literature sources from a variety of social science and engineering disciplines (Kuligowski et al. 2012) and the prioritization of the specific findings extracted from each literature source.

This document first presents guidance on how to create and disseminate emergency information in the face of rapid-onset disasters¹ — providing guidance on the dissemination of alert signals, the creation of the warning message, the formatting of messages for both visual and audible means, and the dissemination of the warning message. This document then provides examples of emergency messages (i.e., message templates) for five different types of emergency scenarios. These message templates can be altered to fit the needs of your occupants, as well as the type of emergency that has occurred and type of technology used to disseminate the alerts/messages.

G.2 Guidance on Emergency Communication Strategies. This section provides guidance for managers, emergency personnel, alarm system manufacturers, codes/standards committees, or others responsible for emergency communication on the ways in which alerts and warning messages should be created, formatted, and disseminated. The guidance is divided into two main parts: guidance on alerts and guidance on warning messages. Although these two parts often get confused, it is important to distinguish between the purpose of an alert and a warning message.

An *alert* is meant to grab peoples' attention, notifying them that an emergency is taking place and that there is important information, which will be provided to them. The purpose of a *warning message* is to give that important information to occupants.

Guidance on the construction and dissemination of both alerts and warnings is provided here.

G.2.1 Alerts. It is imperative to disseminate an alert to let occupants know that a warning message will follow. Regardless of whether the warning message is provided audibly, visually, or via tactile means, an alert is necessary to gain people's attention and should be provided separately from the warning message. An effective alert should include the following characteristics:

- (1) Alerts should be significantly different from ambient sounds.
- (2) Buildings should reduce background noise when initiating audible alerts.
- (3) Flashing, rather than static lights, preferably one standard color for all buildings, can be used to gain attention to visual warning messages.

- (4) There are additional methods to alert occupants to an emergency: disruption of routine activities, tactile methods, social networks, and face-to-face.
- (5) An alert signal should be accompanied by a clear, consistent, concise, and candid warning message.
- (6) If selected, an alert should be tested for its success in getting occupants' attention in the event of an emergency and used as part of building- or campus-wide training.

G.2.2 Warnings. Warning messages should provide information to the occupants on the state of the emergency and what they are supposed to do in response to this emergency. The warning message should come after an alert signal is given and can be provided via visual or audible means. However, before such guidance on message format for visual and audible messages can be provided, it is vital to provide guidance on the content of the warning message itself.

G.2.2.1 The Message. Regardless of the method used to disseminate the warning message, there are certain characteristics that are required of an effective warning message. These are included here:

- (1) Message Content.
 - (a) A warning message should contain five important topics to ensure that occupants have sufficient information to respond.
 - i. Who is providing the message? (i.e., the source of the message)
 - ii. What should people do? (i.e., what actions occupants should take in response to the emergency and, if necessary, how to take these actions)
 - iii. When do people need to act? (In rapid-onset events, the "when" is likely to be "immediately.")
 - iv. Where is the emergency taking place? (i.e., who needs to act and who does not)
 - v. Why do people need to act? (including a description of the hazard and its dangers/consequences)
 - (b) The source of the message should be someone who is perceived as credible by the occupants
 - (c) Building managers, campus managers, and emergency personnel should understand the affected population and, from this understanding, develop a database of possible trusted sources (as well as backup sources).
- (2) Message Structure.
 - (a) Message order for short messages (e.g., 90-characters) should be the following:
 - i. Source
 - ii. Guidance on what people should do
 - iii. Hazard (why)
 - iv. Location (where)
 - v. Time.
 - (b) Message order for longer messages should be the following:
 - i. Source
 - ii. Hazard
 - iii. Location
 - iv. Guidance
 - v. Time

- (c) Numbered lists can help to chronologically organize multiple steps in a process
- (d) For limited message length, message writers could draft the message in a bulleted form; each of the five topics in the warning should be separated as its own bullet point
- (e) Distinct audiences should be addressed separately in the message (or in multiple messages)
- (3) Message Language (or Wording).
 - (a) Messages should be written using short, simple words, omitting unnecessary words or phrases.
 - (b) Messages should be written using active voice, present tense, avoiding hidden verbs.
 - (c) Messages should be written using short, simple, and clear sentences, avoiding double negatives and exceptions to exceptions; main ideas should be placed before exceptions and conditions.
 - (d) Emergency messages should be written at a sixth grade reading level or lower. An emergency message can be evaluated for its reading level using computer software and/or a simple calculation.
 - (e) Emergency messages should be written without the use of jargon and false cognates.
 - (f) Emergency messages should be provided in the language of the predominant affected populace. If there is a possibility of isolated groups that do not speak the predominant language, multilingual messages should be provided. It is expected that small groups of transients unfamiliar with the predominant language will be picked up in the traffic flow in the event of an emergency and are not likely to be in an isolated situation.
- (4) Multiple Messages.
 - (a) Building managers, campus managers, and emergency personnel should anticipate the need to write more than one emergency message throughout a disaster, including feedback messages or updates.
 - (b) In update messages, occupants should be told why the information has changed, to ensure that the new message is viewed as credible.
 - (c) Provide feedback messages after a “non-event” to inform occupants that the alert signal and warning system operated and worked as planned and the reasons why the event did not occur.
 - (d) Building managers, campus managers, and emergency personnel should test emergency messages with the affected population.
- (5) Visual Warnings.
 - (a) Messages that are displayed visually will have different capabilities and limitations than those disseminated audibly. Message creators should consider different factors and make different types of decisions based upon the dissemination method. The first consideration is the type of visual technology that will be used to disseminate the messages, which can include textual visual displays, SMS text messages, computer pop-ups, email, Internet websites, news (TV broadcast), or streaming broadcast over the web. Depending upon the technology chosen to display visual warning messages, guidance is provided here on message displays to enable occupants to see or notice the displayed warning, understand the warning, perceive warning credibility and risk, and respond appropriately.
- (6) Noticing and Reading the Warning.
 - (a) Place the emergency sign in a location where people will notice it and be able to read it from their original (pre-emergency) location.
 - (b) Signs will be reliably conspicuous within 15 degrees of the direct line of sight.
 - (c) Text is easier to read when written with a mixture of upper and lower case letters rather than the use of all capitals.
 - (d) The recommended relationship for older adults with lower visual acuity is $D = 100 * h$, providing a more conservative result, and ensuring that a larger population will be able to read the emergency message.
 - (e) A stroke-to-width ratio of the letters is suggested as 1:5 (generally), with a ratio of 1:7 suggested for lighter letters on a darker background.
 - (f) Building managers, campus managers, or emergency personnel should consult the ADA Standards for Accessible Design (U.S. Department of Justice 2010) for additional requirements on signage.
 - (g) Contrast between the text and the background should be at least 30 percent, although recommended values could be as high as 60 percent.
 - (h) The use of pictorials (in lieu of or in addition to text) can also bring attention to the sign.
 - (i) Message providers should ensure that emergency information is not blocked by other signs or information.
- (7) Comprehending, Believing, and Personalizing the Warning.
 - (a) Printed text should accompany symbols or pictorials used in visual warnings; a minimum number of words should be used to accompany graphics.
 - (b) Diagrams that display a series of sequential steps are more successful for comprehension of a process than one single graphic.
 - (c) A color-contrasted word or statement should be used for text that should be read first and/or be perceived as more urgent than the rest, unless color is used for other reasons (e.g. bilingual text).
 - (d) A warning message can increase in perceived credibility and risk if occupants are shown that others are also responding.
 - (e) Simultaneously displayed text (discrete messages) is preferred rather than a sequentially displayed message.
 - (f) Simultaneously displayed text can also be used for bilingual messages, especially if care is taken to differentiate the text of one language from the text of the other language.
 - (g) Limit the use of flashing words on visual message displays.
- (8) Audible Warnings.
 - (a) There are specific warning technologies that only (or primarily) affect the aural sense, including public address systems (voice notification systems), automated voice dialing, satellite/AM/FM radio broadcasts, satellite/off-air television broadcasts, and tone alert radios. Whereas visual technologies

- can limit message length, audible warnings are often limited only by the attention capabilities of the audience. In other words, an audible message can play for long periods of time with these technology types, and the message creator and source must be careful to provide all important information in an appropriate length of time.
- (b) In this section, guidance will be given for methods to increase the likelihood that an individual will perceive, or hear, the message. Following this, guidance will be provided that can increase comprehension of the message for audible messages, as well as the ways in which to increase credibility and risk assessment of the event when the warning is presented audibly.
- (9) Perception.
- (a) Other, non-alert/warning voices in the background should be reduced or eliminated.
 - (b) Any voice announcements should also be accompanied by simultaneous visual text.
- (10) Comprehending, Believing, and Personalizing the Warning.
- (a) Letters are more difficult to identify in speech than numbers, which are more difficult than colors.
 - (b) People making announcements (or other message sources) should not be heavily accented and should speak with a rate of approximately 175 words per minute.
 - (c) Audible warnings can be delivered using a live voice, dynamic voice (generated by text-to-speech software), or using prerecorded voice.
 - (d) The live voice and dynamic voice methods provide the benefit of messages that can be updated with new information while also conveying an appropriate level of urgency, if necessary.
 - (e) Dynamic and prerecorded voice methods provide the benefits of easily repeating the played messages for longer periods of time and not relying on the voice announcer training or stress level while delivering the message.
 - (f) For the voice itself, best results will vary, depending on the specific location — for example, in outdoor applications, it has been shown that a male voice will provide better intelligibility, as the naturally lower frequency of the male voice travels better. Inversely, in an interior application, where the background ambient noise is typically in the same lower frequencies, a female voice tends to penetrate better, as it is more distinct from the ambient.
 - (g) Urgency measures should be used selectively to emphasize the more dangerous, immediate, life-threatening situations (since overuse can lead to non-response in future disasters).
- (11) Dissemination of the Warning Message.
- (a) Use multiple channels to disseminate the warning message, including visual, audible, and tactile means.
 - (b) A warning message should be repeated at least once, with some research advocating for message repetition of at least three times.
 - (c) Messages should be stated in full, and then repeated in full, rather than repeating statements within the same message.

- (d) Warning messages should be repeated at intervals, rather than consecutively.
- (e) Warning messages should be disseminated as early as possible.
- (f) Face-to-face communication should accompany other audible or visual technologies.
- (g) Messages should be disseminated using a combination of both push and pull technologies.
- (h) Push communication² is most important to use for alert signals as well as initial warning messages.

G.3 Emergency Message Templates. Rapid-onset emergencies often come with little warning and can have a major impact on communities. In order to provide clear, effective instructions for a threatened population, it is important to create message templates ahead of time for a variety of different emergencies.

This section provides examples of message templates for five types of emergency, using various forms of emergency communication technology. All bracketed text can be altered and replaced with text that better suits the needs of the occupants, emergency scenario, emergency response strategies, and the technology being used. Please see Kuligowski and Omori (2014) for more information on the process associated with the development of these templates. Each template follows the guidance presented in this document.

G.3.1 Scenario 1 — Fire in a building, partial evacuation strategy, building-wide public address announcements. Scenario 1 is a fire located on the 10th floor of a 20-story building. Individuals are unable to use elevators in this scenario, except for those who are unable to negotiate the stairs, in which case building staff or fire fighters will assist them using the freight elevator(s).

Protective actions: Occupants on floors 9, 10, and 11 are told to evacuate to the 8th floor (two floors below the fire floor). All other occupants are provided with a message to remain on their floor. Therefore, in this scenario, two different types of messages are required to be provided simultaneously to occupants, depending upon the floor on which they are located: one message will be disseminated to floors 9, 10, and 11, while a different message will be disseminated simultaneously to all other floors.

Technology used to disseminate the message: The building-wide public address system, which is capable of providing different messages to different floors (using a live voice or a dynamic voice).

G.3.1.1 Message Templates for Scenario 1:

- (1) Building-wide announcement to Floors 9, 10, and 11: "Attention [floors 9, 10, and 11]. This is your [Building Safety Officer, Joe Smith]. A fire has been reported on the [10th floor] of the building. Everyone on the [9th, 10th, and 11th floors] should move to the [8th floor] to be protected from heat and smoke, since heat and smoke can creep into nearby floors during a fire. Use the stairs immediately. Do not use the elevators. Those who need help getting to the 8th floor, please wait inside the stairwell [or go to the freight elevator lobby]."
- (2) Building-wide announcement to all other floors: "Attention. This is your [Building Safety Officer, Joe Smith]. A fire has been reported on the [10th floor] of the building. Please wait on your floor. At this time, you are safer remaining on your floor than leaving the building, because this building is designed to confine the fire [e.g.,

locally or to the 10th floor only]. Do not use the elevators for any reason. We will give you further instructions, if the situation changes.”

G.3.2 Scenario 2 — Fire in a building, full evacuation strategy, building-wide public address announcement, and cell phone text message. Scenario 2 is a fire located on the second floor of a 20-story building in which smoke is traveling up the building’s air-conditioning/venting system, causing the need for a full-building evacuation. Individuals are unable to use elevators in this scenario, except for those who are unable to negotiate the stairs, in which case building staff or fire fighters will assist them using the freight elevator(s).

Protective actions: Occupants on all floors are requested to evacuate the building, known as a full-building evacuation.

Technologies used to disseminate the message: The building-wide public address system, which is capable of providing different messages to different floors (using a live voice or a dynamic voice). Also, a 90-character text message alert to cell phone users in the building.

G.3.2.1 Message Templates for Scenario 2:

- (1) Building-wide public address system: “Attention. This is [Chief Smith from the Springfield Fire Department]. A fire has been reported on the [second floor] of the building. Everyone must leave the building now to avoid contact with the fire’s heat and smoke. Go NOW to your closest stair and leave the building. People who cannot use the stairs should go to the freight elevator lobby for help.”
- (2) Cell phone text message (90 characters): “Evacuate building now. It is on fire. Go to freight elevator if you need help.”

Note: A description of the hazard (a more detailed “why” statement) is not included in this message due to character limits. Also, the source is not listed. It is possible that the source will already be identified in the “From” or “FRM” line of the text message. If message contents are limited, there is always the option to send a follow-up text message that provides more information or that continues the previous message. Also remember that some phones (i.e., non-smart phones) could display longer text messages in reverse chronological order.

G.3.3 Scenario 3 — Tornado imminent on a college campus, campus-wide audible messaging system, and Twitter message. Scenario 3 is a tornado imminent on a college campus.

Protective actions: The individuals on the college campus are instructed to “shelter in place.” Additionally, the National Weather Service provides examples of protective actions (included below):

Example 1: “TAKE COVER NOW. FOR YOUR PROTECTION MOVE TO AN INTERIOR ROOM ON THE LOWEST FLOOR OF A STURDY BUILDING.”

Example 2: “TAKE COVER NOW. MOVE TO AN INTERIOR ROOM ON THE LOWEST FLOOR OF A STURDY BUILDING. AVOID WINDOWS. IF IN A MOBILE HOME...A VEHICLE OR OUTDOORS...MOVE TO THE CLOSEST SUBSTANTIAL SHELTER AND PROTECT YOURSELF FROM FLYING DEBRIS.”

Example 3: “THE SAFEST PLACE TO BE DURING A TORNADO IS IN A BASEMENT. GET UNDER A WORKBENCH OR OTHER PIECE OF STURDY FURNITURE. IF NO

BASEMENT IS AVAILABLE...SEEK SHELTER ON THE LOWEST FLOOR OF THE BUILDING IN AN INTERIOR HALLWAY OR ROOM SUCH AS A CLOSET. USE BLANKETS OR PILLOWS TO COVER YOUR BODY AND ALWAYS STAY AWAY FROM WINDOWS.”

IF IN MOBILE HOMES OR VEHICLES...EVACUATE THEM AND GET INSIDE A SUBSTANTIAL SHELTER. IF NO SHELTER IS AVAILABLE...LIE FLAT IN THE NEAREST DITCH OR OTHER LOW SPOT AND COVER YOUR HEAD WITH YOUR HANDS.”

(Examples found here: <http://www.nws.noaa.gov/view/valid-prods.php?prod=TOR>)

Technologies used to disseminate the message: A campus-wide siren system with audible messaging capabilities. Also, a 140-character Twitter³ message should be disseminated as well for this emergency.

G.3.3.1 Message Templates for Scenario 3:

- (1) Campus-wide audible messaging system): *Alert tone precedes message* [siren]. “This is [Joan Smith, Chief of Campus Police]. A tornado has been sighted on the ground at [20th Street and Mockingbird Lane]. The tornado is strong and is moving toward the college campus at high speeds (with winds over 160 mph). High winds and large, flying debris can flatten a building in a storm of this magnitude. Take shelter now. Get inside now, go to the lowest level, and get away from windows. Stay there until further instructions.”
- (2) Twitter message (140 characters): “Take shelter inside a building NOW. Go to the lowest level, get away from windows. Strong tornado near campus.” [Include hashtag in 140 characters.]

Note: The source of the message is not included in this Twitter message since the source will be evident from the Twitter message layout.

G.3.4 Scenario 4 — Chemical spill in a building, building-wide public address announcements, and building-wide email messages. Scenario 4 is a chemical spill in a 40-story office building. The event was an accident and occurred on the 1st floor of the building. There is the possibility of the chemical negatively affecting individuals on the lower floors of the building. Individuals are unable to use elevators in this scenario. For those who are unable to negotiate the stairs, only one freight elevator will be used with fire-fighter assistance.

Protective actions: Occupants are advised to perform different actions based upon the floor on which they are located. First, occupants on the first floor are advised to evacuate the building. At the same time, occupants on floors 2 through 10 are advised to travel to locations higher in the building — preferably to floors 20 through 30. Concurrently, occupants on floors 11 and above are advised to remain in place. Therefore, in this scenario, three different types of messages are required to be provided simultaneously to occupants, depending upon the floor on which they are located: one message will be disseminated to the first floor, one message will be disseminated to floors 2 through 10, and a third message will be disseminated to all other floors.

Technologies used to disseminate the message: The building public address system, which is capable of providing different message to different floors (using a live voice or a dynamic voice). Additionally, an email message (through the company’s email

system) should be disseminated to employees on floors 2 through 10 to relocate to a higher floor. [Note: Do not worry about an email to other employees, although in an actual emergency, that would be necessary.]

G.3.4.1

- (1) Building-wide public address system: [first floor occupants] “This is your [Building Manager, Joe Smith]. A dangerous chemical has spilled on the first floor. The chemical makes it difficult to see and can cause trouble breathing. Evacuate immediately.”
- (2) Building-wide public address system: [floors 2 through 10] “This is your [Building Manager, Joe Smith]. A dangerous chemical has spilled on the first floor. The chemical makes it difficult to see and can cause trouble breathing. Immediately use the stairs to relocate to the [20th through 30th floors], and then wait for further instructions. If you can’t use the stairs on your own, go to the freight elevator and wait for help. Relocate now.”
- (3) Building-wide public address system: [floors 11 and above] “This is your [Building Manager, Joe Smith]. A dangerous chemical has spilled on the first floor. The chemical makes it difficult to see and can cause trouble breathing. People on [floors 1 through 10] are being evacuated. Please stay on your floor. You are safer remaining where you are than if you try to leave the building. The chemical will not reach people on floors 11 and above. You would possibly be exposed to the chemical if you tried to leave the building. Do not use the elevators for any reason. We will give you further instructions if the situation changes.”

Note: Provide emails with the same messages as listed above.

G.3.5 Scenario 5 — Violent event in an airport, airport-wide visual messaging screens, and cell phone text message. The fifth scenario is a violent event. Specially, the emergency involves an active shooter that has been identified in a major U.S. airport.

Example protective action: Occupants should evacuate the airport through all accessible doors, including doors from the gate waiting areas onto the tarmac area.

Technologies used to disseminate the message (along with example character limits that can be typical for these types of technologies): A 90-character text message alert to individuals’ phones within the airport. Also, airport-wide visual messaging screens (limit message to 60 words or less) can be used to alert individuals in terminals where the shooter is NOT located.

G.3.5.1 Message Templates for Scenario 5:

- (1) Airport-wide visual messaging screens: “This is Los Angeles Police. Evacuate the terminal NOW. Follow directions from airport security. Shots have been fired near Gate 22.”
- (2) Cell phone text message (90 characters): “Leave NOW. Follow airport security. **Shots fired!** Police report: Shooter in Terminal A.”

Note: A description of the hazard (a more detailed “why” statement) is not included in this message due to character limits. If message contents are limited, there is always the option to send a follow-up text message that provides more information or that continues the previous message. Also remember that some phones (i.e., non-smart phones) could display longer text messages in reverse chronological order.

G.4 Future Direction. The purpose of this report is to provide guidance to system designers, building managers, and building emergency personnel responsible for emergency communication on how to create and disseminate effective messages using basic communication modes (audible vs. visual technology), as well as examples of emergency messages (message templates) for five different types of emergency scenarios. START (2013) contains additional message templates for similar types of rapid-onset events for both limited- and unlimited-character length dissemination technologies. Additionally, Kuligowski and Omori (2014) provide guidance on how to test the effectiveness of these messages.

As with any document, there are gaps in the research that hinder the ability to provide guidance on certain topics, including message length and repetition. This guidance document focuses specifically on textual message creation, creating room for additional guidance on the development and testing of visual symbols that could be used instead of, or in addition to, textual emergency messages. In the future, as research gaps are addressed, additional editions of this document would be useful to enhance the findings and guidance provided here.

G.5 References. Kuligowski, E.D., S.M.V. Gwynne, K.M. Butler, B.L. Hoskins, and C.R. Sandler, 2012. *Developing Emergency Communication Strategies for Buildings*. Technical Note 1733, National Institute of Standards and Technology: Gaithersburg, MD.

Kuligowski, E.D. and Omori, H., 2014. *General Guidance on Emergency Communication Strategies for Buildings, 2nd Edition*. NIST Technical Note 1827, National Institute of Standards and Technology: Gaithersburg, MD.

U.S. Department of Justice, September 2010. 2010 *ADA Standards for Accessible Design*. Washington, DC: DOJ. http://www.ada.gov/2010ADASTandards_index.htm.

START (National Consortium for the Study of Terrorism and Responses to Terrorism), 2013. *Task 2.9: Phase II Interim Report on Results from Experiments, Think-out-Louds, and Focus Groups*. University of Maryland, College Park: College Park, MD.

G.6 Footnotes.

¹ Rapid-onset emergencies are those emergencies that occur with no or almost no (in the case of minutes) notice, rather than slow-onset events (i.e., emergencies in which the occurrence is known hours or even days in advance). These different emergency types require different sets of emergency messages and dissemination techniques to allow building occupants to receive information in a timely manner, resulting in efficient and safer public response.

² Push technologies are those that do not require individuals to take extra effort to receive the alert or warning message (e.g., public address systems or text messages), whereas pull technologies require the individual to seek additional information to acquire the alert/message (e.g., Internet websites).

³ Certain commercial entities, equipment, or materials are identified in this document in order to describe an experimental procedure or concept adequately. Such identification is not intended to imply recommendation or endorsement by the National Institute of Standards and Technology, nor is it intended to imply that the entities, materials, or equipment identified are necessarily the best available for the purpose.

Annex H Carbon Monoxide

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

H.1 Dangers of Carbon Monoxide. Carbon monoxide is an odorless, tasteless, colorless gas produced by incomplete combustion. Solid, liquid, or gaseous fuels can each, under certain conditions, produce lethal concentrations in the home. (See Table H.1 and Figure H.1.)

The values in Table H.1 are approximate values for healthy adults. Children, the elderly, and persons with preexisting physical conditions might be more susceptible to the effects of carbon monoxide exposure. Continued exposure after unconsciousness can cause death. The dangers of carbon monoxide exposure depend on a number of variables, such as the occupant's health, activity level, time of exposure, and initial carboxyhemoglobin (COHb) level. Due to these variables, Table H.1 and Figure H.1 are to be used as general guidelines and might not appear quantitatively consistent.

The following equation for determining the estimated percent of COHb in the blood is from "A proposal for evaluating human exposure to carbon monoxide contamination in military vehicles," by Steinberg and Nielson and "Considerations for the physiological variables that determine the blood carboxyhemoglobin concentration in man" by Coburn, Forster, and Kane.

[H.1]

$$\% \text{COHb}_t = \% \text{COHb}_0 \left[e^{-(t/2908B)} \right] + 218 \left[1 - e^{-(t/2908B)} \right] \times \left(0.0003 + \frac{\text{ppm CO}}{1316} \right)$$

where:

% COHb_t = percentage of COHb at time *t*

% COHb₀ = percentage of COHb in the blood at time 0

t = time (minutes)

B = 0.0404 (work effort)

ppm CO = parts per million carbon monoxide

H.2 Information for Emergency Responders. *Guideline Summary.* How public emergency response organizations respond to carbon monoxide incident calls is essential for the safety of the building occupants and the emergency responders. One reference that can be helpful to emergency responders is the Consumer Product Safety Commission (CPSC) *Responding to Residential Carbon Monoxide Incidents: Guidelines for Fire and Other Emergency First Response Personnel*. This guide is designed to help emergency responders act quickly and effectively when responding to a carbon monoxide incident, and it provides the following:

- (1) Guidelines for dispatchers handling calls
- (2) Incident reporting forms to help emergency responders identify the elevated source of carbon monoxide, the level of care needed by occupants, and when it is safe for occupants to return to the building
- (3) Advice and actions to give building occupants

The CPSC guide is available for download at <https://www.cpsc.gov/s3fs-public/coguide.pdf>.

Table H.1 Symptoms of Carbon Monoxide Exposure Based on Concentration

Concentration (ppm CO)	Symptoms
50	No adverse effects with 8 hours of exposure
200	Mild headache after 2–3 hours of exposure
400	Headache and nausea after 1–2 hours of exposure
800	Headache, nausea, and dizziness after 45 minutes of exposure; collapse and unconsciousness after 2 hours of exposure
1,000	Loss of consciousness after 1 hour of exposure
1,600	Headache, nausea, and dizziness after 20 minutes of exposure
3,200	Headache, nausea, and dizziness after 5–10 minutes of exposure; collapse and unconsciousness after 30 minutes of exposure
6,400	Headache and dizziness after 1–2 minutes of exposure; unconsciousness and danger of death after 10–15 minutes of exposure
12,800 (1.28% by volume)	Immediate physiological effects; unconsciousness and danger of death after 1–3 minutes of exposure




FIGURE H.1 Carbon Monoxide Concentration (ppm CO) Versus Time (Minutes).

Annex I Color-Coded Tagging Program

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

To assist with the enforcement and application of NFPA 72, some authorities having jurisdiction (AHJs) adopt color-coded system status tagging programs. The purpose of these programs varies, but the typical goal is to provide a readily accessible means of determining the status of a system following its most current inspection or test.

While NFPA 72 does not mandate system status tagging, it is desirable that a certain level of consistency exist between programs. With that in mind, AHJs using a color-coded system status tagging program should consider the tagging information provided in this annex.

I.1 Fire Alarm System Installation, Maintenance, and Service Tagging. After successful completion of acceptance testing approved by the AHJ or periodic inspection or testing, the recommendations in I.1.1 through I.1.5 should apply to fire alarm systems, except household fire alarm systems installed in accordance with Chapter 29.

I.1.1 Installation Tagging.

I.1.1.1 After the completion of an installation of new fire alarm equipment or a new system, or the extension, alteration, or modification to a fire alarm system already in place, an installation label should be affixed to the inside of the control unit cover. The tag should not cover or conceal installation or wiring instructions, testing laboratory listings, or control unit displays. If the system has no control unit, the tag should be placed in a permanent location.

I.1.1.2 The installation tag should be in accordance with the following recommendations:

- (1) Installation tags should be white with black lettering.
- (2) Installation tags should be approximately 3 in. (70 mm) high and approximately 3 in. (70 mm) wide and should have an adhesive on the back.
- (3) Installation tags should contain the following information:
 - (a) **DO NOT REMOVE BY ORDER OF THE AUTHORITY HAVING JURISDICTION** (all capital letters in at least 10-point boldface type)
 - (b) **INSTALLATION RECORD** (all capital letters in at least 10-point boldface type)
 - (c) The registered firm's name, address, and telephone number and the certification number of the firm performing the installation
 - (d) The installation date, the technician's signature (a stamped signature is not recommended to be permitted) and certification number
 - (e) The name and certification number (if applicable) of the fire alarm system designer who designed the system

An example of an installation tag is shown in Figure I.1.1.2.

I.1.2 Service Tagging.

I.1.2.1 After any service, to certify that the service performed complies with requirements of this code, a fire alarm service tag should be completed in detail and affixed to the inside or outside of the control unit cover. The tag should not cover or conceal installation or wiring instructions, testing laboratory listings, or control unit displays. If the system has no control unit, the tag should be placed in a permanent location.

DO NOT REMOVE BY ORDER OF THE AUTHORITY HAVING JURISDICTION (for life of system) Fire detection and fire alarm devices or system INSTALLATION RECORD (post inside control unit or at permanent location) <i>Registered Firm's Name</i> <i>Street Address</i> <i>City, State, Zip</i> <i>Phone Number - Cert. Number</i>		
Installation Date	Technician Signature	Cert. #
Fire alarm system designer (printed name) or professional engineer's name and license number copied from record drawings used to install the system.		

Color: Black text on white background.

FIGURE I.1.1.2 Installation Tag Example.

I.1.2.2 The service tag should be in accordance with the following recommendations:

- (1) The service tag should be white in color with printed black lettering.
- (2) The service tag should be approximately 3 in. (70 mm) high and 3 in. (70 mm) wide and should have an adhesive on the back that allows for tag removal.
- (3) Approximately ½ in. (13 mm) of the adhesive on the top back of the tag should be used to attach the tag over the previous service tag to permit viewing of the previous tag and the maintaining of a brief history.
- (4) Service tags should contain the following information:
 - (a) **DO NOT REMOVE BY ORDER OF THE AUTHORITY HAVING JURISDICTION** (all capital letters in at least 10-point boldface type)
 - (b) **SERVICE RECORD** (all capital letters in at least 10-point boldface type)
 - (c) The registered firm's name, address, and telephone number and the license number of the firm performing the service
 - (d) The date of service performed, the technician's signature (a stamped signature is not recommended to be permitted) and certification number
 - (e) A list of services performed
 - (f) The type of service performed, either general service or the correction of conditions that resulted in a red tag or yellow tag

An example of an installation tag is shown in Figure I.1.2.2.

I.1.2.3 If the service performed corrects all conditions noted on a yellow tag or red tag, the color and date of the tag should be marked on the service tag and the respective yellow tag or red tag removed in accordance with I.1.4.4 or I.1.5.4.

I.1.2.4 If, during any service, deficiencies are noted, the system is inoperable, has a fault condition, or is impaired from normal operation, both of the following should apply:

DO NOT REMOVE BY ORDER OF THE AUTHORITY HAVING JURISDICTION (for at least two years) SERVICE RECORD <i>Registered Firm's Name</i> <i>Street Address</i> <i>City, State, Zip</i> <i>Phone Number - License Number</i>		
Date	Technician Signature	Cert. #
List Services: _____		
Performed ☐ General service listed above Corrected ☐ RED TAG dated _____ Corrected ☐ YELLOW TAG dated _____		

Color: Black text on white background.

FIGURE I.1.2.2 Service Tag Example.

- (1) The system owner or the owner's designated representative and the local AHJ should be notified of the condition.
- (2) The servicing personnel should attach, in addition to the service tag, the appropriate yellow tag or red tag, following the procedures in I.1.4 or I.1.5.

I.1.2.5 Service tags should remain in place for a period of 2 years from the date of service.

I.1.3 Inspection and Testing Tagging.

I.1.3.1 After the inspection and testing of a fire alarm system, a fire alarm inspection and testing tag should be completed in detail and affixed to either the inside or outside of the control unit cover. The tag should not cover or conceal installation or wiring instructions, testing laboratory listings, or control unit displays. If the system has no control unit, the tag should be placed in a permanent location.

I.1.3.2 The inspection and testing tag should be in accordance with the following recommendations:

- (1) The inspection and testing tag should be blue with printed black lettering.
- (2) The inspection and testing tag should be approximately 3 in. (70 mm) high and 3 in. (70 mm) wide and should have an adhesive on the back that allows for tag removal.
- (3) Approximately a ½ in. (13 mm) of the adhesive on the top back of the tag should be used to attach the tag over the previous inspection and testing tag to permit viewing of the previous tag and the maintaining of a brief history.
- (4) Inspection and testing tags should contain the following information:
 - (a) **DO NOT REMOVE BY ORDER OF THE AUTHORITY HAVING JURISDICTION** (all capital letters in at least 10-point boldface type)

**DO NOT REMOVE BY ORDER OF
THE AUTHORITY HAVING JURISDICTION**
(until all conditions are corrected)
**SYSTEM DEFICIENCY(IES) REQUIRES CORRECTIVE
ACTION**

Registered Firm's Name
Street Address
City, State, Zip
Phone Number - License Number

Date	Technician Signature	Cert. #
------	----------------------	---------

List Conditions: _____

REPORT STATUS TO OWNER AND AHJ
(in writing within five business days)

Color: Black text on yellow background.

FIGURE I.1.4.2 Yellow Tag Example.

I.1.5.2 The red tag should be in accordance with the following recommendations:

- (1) Red tags should be approximately 3 in. (70 mm) high and 3 in. (70 mm) wide and should have an adhesive on the back that allows for tag removal.
- (2) Tags should be red with printed black lettering.
- (3) Red tags should contain the following information:
 - (a) **DO NOT REMOVE BY ORDER OF THE AUTHORITY HAVING JURISDICTION** (all in capital letters, at least 10-point boldface type)
 - (b) Status of the system to be marked as inoperable or impaired or fault
 - (c) The registered firm's name, address, and telephone number and the license number of the firm attaching the red tag
 - (d) The date the tag was attached, the technician's signature (a stamped signature is not recommended to be permitted) and certification number
 - (e) List of conditions resulting in the red tag

An example of a red tag is shown in Figure I.1.5.2.

I.1.5.3 Immediately after attaching a red tag, the inspection, testing, or service personnel should notify the system owner or the owner's designated representative and the AHJ of all impairments in accordance with the following:

- (1) If the system is inoperable, by immediate direct oral communication and in writing within one business day of the attachment of the red tag
- (2) If the system has a fault condition or is impaired from normal operation, in writing within three business days of the attachment of the red tag

**DO NOT REMOVE BY ORDER OF
THE AUTHORITY HAVING JURISDICTION**
(until all conditions are corrected)

System ☐ **INOPERABLE** ☐ **IMPAIRED** ☐ **FAULT**

Registered Firm's Name
Street Address
City, State, Zip
Phone Number - License Number

Date	Technician Signature	Cert. #
------	----------------------	---------

List Conditions: _____

REPORT INOPERABLE TO OWNER AND AHJ
(orally immediately and in writing within next business day)
REPORT ALL OTHER TO OWNER AND AHJ
(in writing within three business days)

Color: Black text on red background.

FIGURE I.1.5.2 Red Tag Example.

I.1.5.4 Red tags should remain in place until the conditions are corrected and a service tag is attached certifying that the corrections were made in accordance with I.1.2.1.

I.1.5.4.1 The red tag should be removed only by an inspection, testing, or service personnel qualified in accordance with 10.5.3 or the AHJ.

I.1.5.4.2 The AHJ should be notified in writing within five business days of the removal of the red tag.

Annex J Guidelines for Cybersecurity

This annex is not a part of the requirements of this NFPA document but is included for informational purposes only.

J.1 Introduction. NFPA 72 contains requirements for fire alarm and emergency communications systems that can be impacted by cybersecurity threats. Coordination of cybersecurity frameworks to protect the functions of systems is essential in order to prevent unwanted impacts on the system. Where the system would need to interface with the internet or other systems, it would make sense to provide a secure firewall or gateway. In any case, protection from cybersecurity threats is essential.

The Technical Committee has determined that, in lieu of establishing requirements in Chapter 11 on cybersecurity at this time, it is appropriate to provide such guidance and framework in this annex. This allows the industry and the public the ability to gain experience with cybersecurity measures and provide constructive feedback for future editions of this Code.

J.2 Cybersecurity Provisions. Where cybersecurity provisions are required, manufacturers, system designers, system installers, inspection personnel, testing personnel, and service technicians involved in the design, installation, testing, and maintenance of cybersecurity provisions should provide cybersecurity measures as outlined in this annex.

J.3 Cybersecurity Standards. Systems should be designed, installed, and maintained in accordance with one or more of the following cybersecurity standards:

- (1) ANSI/ISA/IEC-62443-4-2, *Security for Industrial Automation and Control Systems, Part 4-2: Technical Security Requirements for IACS Components*
- (2) NISTIR 8259, *Foundational Cybersecurity Activities for IoT Device Manufacturers*
- (3) NIST Framework for Improving Critical Infrastructure Cybersecurity
- (4) UL 2900-2-3, *Software Cybersecurity for Network-Connectable Products Part 2-3: Particular Requirements for Security and Life Signaling Systems*
- (5) Other standard(s) or published documents acceptable to the authority having jurisdiction

J.4 Evidence of Compliance. Evidence of cybersecurity compliance should include one or more of the following:

- (1) Certification of compliance by a nationally recognized test laboratory
- (2) Manufacturer certification for the specific type and brand of system provided
- (3) An assessment or certification program acceptable to the authority having jurisdiction

J.5 Documentation. All system-related documentation associated with the use of the selected standard(s) is included as part of the system documentation required by Chapter 7.

J.6 Cybersecurity Certificate Maintenance.

J.6.1 Certificate Validation. Where a system is provided with a cybersecurity certificate document as evidence of compliance, the validity of the certificate should be checked annually.

J.6.2 Cybersecurity Software Revisions. Software changes made only for cybersecurity purposes to firewalls or barrier gateways should not require the functional test of the system that is otherwise required by 14.4.2.4 and 14.4.2.5 where all the following are true:

- (1) The changes do not affect the function of the executive or site-specific software.
- (2) The integrity of the software update installed in the firewall or barrier gateway is verified to ensure complete and intact software delivery.
- (3) The software is digitally signed by the manufacturer.
- (4) The digital signature of the software is verified prior to execution by the system or system components using secure signing keys.

Figure J.6.2 depicts system typical firewall/gateway operation. Such functionality is not mandated but when deployed might take the form of physical hardware, firmware, or a combination of both. The firewall/gateway might be physically integrated into the control unit as shown in the integrated control unit graphic, or a separate device/service that interacts with the control unit as shown in the nonintegrated control unit. If the firewall/gateway is segmented from the executive firmware and site-specific software and if security software changes to the firewall/gateway are made, these changes should not require system retesting. If changes are made in a firewall/gateway that is not segmented from the executive firmware and site-specific software, the system should be retested.

J.6.3 Remote Software Changes. Software changes to systems or system components made only for cybersecurity purposes




FIGURE J.6.2 System Typical Firewall/Gateway Operation.

should be permitted to be made by remote access in accordance with Chapter 23.

Annex K Informational References

K.1 Referenced Publications. The documents or portions thereof listed in this annex are referenced within the informational sections of this Code and are not part of the requirements of this document unless also listed in Chapter 2 for other reasons.

K.1.1 NFPA Publications. National Fire Protection Association, 1 Batterymarch Park, Quincy, MA 02169-7471.

NFPA 3, *Standard for Commissioning of Fire Protection and Life Safety Systems*, 2021 edition.

NFPA 4, *Standard for Integrated Fire Protection and Life Safety System Testing*, 2021 edition.

NFPA 10, *Standard for Portable Fire Extinguishers*, 2022 edition.

NFPA 13, *Standard for the Installation of Sprinkler Systems*, 2022 edition.

NFPA 70®, *National Electrical Code®*, 2020 edition.

NFPA 72E, *Standard for Automatic Fire Detectors*, 1984 edition.

NFPA 80, *Standard for Fire Doors and Other Opening Protectives*, 2022 edition.

NFPA 90A, *Standard for the Installation of Air-Conditioning and Ventilating Systems*, 2021 edition.

NFPA 90B, *Standard for the Installation of Warm Air Heating and Air-Conditioning Systems*, 2021 edition.

NFPA 92, *Standard for Smoke Control Systems*, 2021 edition.

NFPA 101®, *Life Safety Code®*, 2021 edition.

NFPA 105, *Standard for Smoke Door Assemblies and Other Opening Protectives*, 2022 edition.

NFPA 111, *Standard on Stored Electrical Energy Emergency and Standby Power Systems*, 2022 edition.

NFPA 170, *Standard for Fire Safety and Emergency Symbols*, 2021 edition.

NFPA 551, *Guide for the Evaluation of Fire Risk Assessments*, 2019 edition.

NFPA 730, *Guide for Premises Security*, 2020 edition.

NFPA 855, *Standard for the Installation of Stationary Energy Storage Systems*, 2020 edition.

NFPA 909, *Code for the Protection of Cultural Resource Properties — Museums, Libraries, and Places of Worship*, 2021 edition.

NFPA 914, *Code for Fire Protection of Historic Structures*, 2019 edition.

NFPA 1221, *Standard for the Installation, Maintenance, and Use of Emergency Services Communications Systems*, 2019 edition.

NFPA 1600®, *Standard on Continuity, Emergency, and Crisis Management*, 2019 edition.

NFPA 5000®, *Building Construction and Safety Code®*, 2021 edition.

Fire Protection Research Foundation, *Elevator Messaging Strategies*, 2011.

Fire Protection Research Foundation, *Optimizing Fire Alarm Notification for High Risk Groups*, 2007.

Fire Protection Research Foundation (FPRF) Report, *Development of Technical Basis for Carbon Monoxide Detector Siting*, prepared by C. Beyler and D. Gottuk, 2007.

K.1.2 Other Publications.

K.1.2.1 ASA Publications. Acoustical Society of America, 35 Pinelawn Road, Suite 114 E, Melville, NY 11747-3177.

ANSI/ASA S3.2, *Method for Measuring the Intelligibility of Speech Over Communications Systems*, 2009 (R2014).

ANSI/ASA S3.41, *Audible Emergency Evacuation (E2) and Evacuation Signals with Relocation Instructions (ESRI)*, 2015.

K.1.2.2 ASME Publications. American Society of Mechanical Engineers, Two Park Avenue, New York, NY 10016-5990.

ASME A17.1/CSA B44, *Safety Code for Elevators and Escalators*, 2019.

ASME A.17.2, *Guide for Inspection of Elevators, Escalators, and Moving Walks*, 2017.

K.1.2.3 FEMA Publications. Federal Emergency Management Agency, U.S. Department of Homeland Security, 500 C Street, SW, Washington, DC 20024.

FEMA Technical Bulletin, *Outdoor Warning Systems*, Version 2.0, January 2006.

K.1.2.4 FM Approvals LLC. FM Approvals LLC, 1151 Boston-Providence Turnpike, P.O. Box 9102, Norwood, MA 02062.

FM Approval Standard 3210, *Heat Detectors for Automatic Fire Alarm Signaling*, 2018.

ANSI/FM Approval Standard 3260, *Radiant Energy-Sensing Fire Detectors for Automatic Fire Alarm Signaling*, 2018.

K.1.2.5 IEC Publications. International Electrotechnical Commission, 3 rue de Varembe, P.O. Box 131, CH-1211 Geneva 20, Switzerland. IEC documents are available through ANSI.

IEC 60268-16, *Sound system equipment — Part 16: Objective rating of speech intelligibility by speech transmission index*, 2011.

Keating, John P. and Loftus, Elizabeth F., "People Care in Fire Emergencies — Psychological Aspects, 1975," SFPE, 1975.

K.1.2.6 IEEE Standards Association Publications. IEEE, 3 Park Avenue, New York, NY 10016-5997.

IEEE 485, *Recommended Practice for Sizing Lead-Acid Batteries for Stationary Applications*, 2010.

IEEE 1188, *Recommended Practice for Maintenance, Testing, and Replacement of Valve-Regulated Lead-Acid (VRLA) Batteries for Stationary Applications*, 2005 (R2010).

IEEE 802.3, *Standard for Information Technology — Telecommunications and Information Exchange Between Systems — Local and Metropolitan Area Networks — Specific Requirements — Part 3*, 2006.

IEEE 802.3bt™, *IEEE Standard for Ethernet, Amendment 2: Physical Layer and Management Parameters for Power over Ethernet over 4 pairs*, 2018.

K.1.2.7 IES Publications. Illuminating Engineering Society of North America, 120 Wall Street, 17th floor, New York, NY 10005.

Lighting Handbook Reference and Application, 2011.

K.1.2.8 ISA Publications. International Society of Automation, 67 T.W. Alexander Drive, PO Box 12277, Research Triangle Park, NC 27709.

ANSI/ISA 62443, *Security for Industrial Automation and Control Systems Series*, 2019.

ANSI /ISA/IEC-62443-4-2, *Security for Industrial Automation and Control Systems, Part 4-2: Technical Security Requirements for IACS Components*, 2019.

K.1.2.9 ISO Publications. International Organization for Standardization, ISO Central Secretariat, BIBC II, Chemin de Blandonnet 8, CP 401, 1214 Vernier, Geneva, Switzerland.

ISO 7240-19, *Fire detection and alarm systems — Part 19: Design, installation, commissioning, and service of sound systems for emergency purposes*, 2007 (R2018).

ISO 8201, *Alarm systems — Audible emergency evacuation signal*, 2017.

ISO/IEC 14763-3, *Informational technology — Implementation and operation of customer premises cabling — Part 3: Testing of optical fibre cabling*, 2014.

K.1.2.10 NEMA Publications. National Electrical Manufacturers Association, 1300 North 17th Street, Suite 900, Arlington, VA 22209.

NEMA SB-7, *Applications Guide for Carbon Monoxide Alarms and Detectors*, 2018.

ANSI/NEMA SB-40, *Communications Systems for Life Safety in Schools*, 2015.

NEMA SB-50, *Emergency Communications Audio Intelligibility Applications Guide*, 2014.

K.1.2.11 NIST Publications. National Institute of Standards and Technology, 100 Bureau Drive, Stop 1070, Gaithersburg, MD 20899-1070.

Kuligowski, Erica D., NIST Technical Note 1779, *General Guidance on Emergency Communications Strategies for Buildings*, February 2013.

NIST Framework for Improving Critical Infrastructure Cybersecurity Version 1.1, 2018.

NISTIR 8259, *Foundational Cybersecurity Activities for IoT Device Manufacturers*, 2020.

Stone, William C., NISTIR 6055, *Electromagnetic Signal Attenuation in Construction Materials*, 1997.

K.1.2.12 OASIS Publications. Organization for the Advancement of Structured Information Standards (OASIS), 25 Corporate Drive, Suite 103, Burlington, MA 01803.

OASIS Standard CAP-V1.2, *OASIS Common Alerting Protocol*, Version 1.2.

K.1.2.13 SFPE Publications. Society of Fire Protection Engineers, 9711 Washingtonian Blvd., Suite 380, Gaithersburg, MD 20878.

SFPE Engineering Guide: Evaluation of the Computer Fire Model DETACT QS, 2002.

SFPE Engineering Guide to Fire Risk Assessment, 2006.

SFPE Engineering Guide to Human Behavior in Fire, 2019.

SFPE Engineering Guide to Performance-Based Fire Protection, 2nd edition, 2007.

SFPE Handbook of Fire Protection Engineering, 5th edition, 2016.

“Projected Beam Smoke Detectors — More Than Just a Substitute for Spot Detectors”; *Fire Protection Engineering*, Issue No. 23, Summer 2004, SFPE.

K.1.2.14 TIA Publications. Telecommunications Industry Association, 1320 North Courthouse Road, Suite 200, Arlington, VA 22201.

TIA-526, *Standard Test Procedures for Fiber Optic Systems*, September 1992.

K.1.2.15 UL Publications. Underwriters Laboratories Inc., 333 Pfingsten Road, Northbrook, IL 60062-2096.

UL 217, *Smoke Alarms*, 8th edition, 2015, revised 2016.

UL 268, *Smoke Detectors for Fire Alarm Systems*, 7th edition, 2016.

UL 268A, *Smoke Detectors for Duct Application*, 2008, revised 2016.

UL 827, *Central-Station Alarm Services*, 2014, revised 2019.

UL 864, *Control Units and Accessories for Fire Alarm Systems*, 2014, revised 2018.

UL 1638, *Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories*, 2016.

UL 1778, *Uninterruptible Power Source*, 2017.

UL 1971, *Signaling Devices for the Hearing Impaired*, 2002, revised 2018.

UL 1989, *Standby Batteries*, 2018.

UL 2034, *Single and Multiple Station Carbon Monoxide Alarms*, 2017, revised 2018.

UL 2054, *Household and Commercial Batteries*, 2004.

UL 2075, *Safety Gas and Vapor Detectors and Sensors*, 2013, revised 2017.

UL 2572, *Mass Notification Systems*, 2018.

UL 2900, *Software Cybersecurity for Network-Connectable Products*, 2017.

UL 2900-1, *Standard for Software Cybersecurity for Network-Connectable Products, Part 1: General Requirements*, 2017.

UL 2900-2-3, *Standard for Software Cybersecurity for Network-Connectable Products, Part 2-3: Particular Requirements for Security and Life Safety Signaling Systems*, 2020.

K.1.2.16 US Government Publications. US Government Publishing Office, 732 North Capitol Street, NW, Washington, DC 20401-0001.

ADA-ABA-AG, *Americans with Disabilities Act and Architectural Barriers Act Accessibility Guidelines*, 2010.

Federal Aviation Administration (FAA) Human Factors Awareness Course, <http://www.hf.faa.gov/webtraining/Intro/Intro1.htm>.

42 U.S.C. 5401-5426, “Manufactured Home Construction and Safety Standards.”

NIST Technical Note 1455-1, *Performance of Home Smoke Alarms, Analysis of the Response of Several Available Technologies in Residential Fire Settings*, February 2008.

Title 24, Code of Federal Regulations, Parts 3280, 3282, 3284, 3285, 3286, 3288, and 3800.

Title 29, Code of Federal Regulations, Part 1910.5.

Title 47, Code of Federal Regulations, Part 15, “Radio Frequency Devices.”

K.1.2.17 References Associated with Annex A.

K.1.2.17.1 Reference to A.17.6.3.5.1.

Schifiliti, R. and Pucci, W. “Fire Detection Modelling, State of the Art,” 6 May 1996 sponsored by the Fire Detection Institute, Bloomfield, CT.

K.1.2.17.2 Reference to A.18.4.8.2.

“How We Localize Sound,” *Physics Today*, Volume 52, Issue 11, Page 24 (November 1999).

K.1.2.17.3 Reference to A.18.5.5.7.1.

"Recommended Light Levels," National Optical Astronomy Observatory, www.noao.edu.

K.1.2.17.4 Reference to A.24.3.8.

Bruck, D., Thomas, I., and Ball M., *Optimizing Fire Alarm Notification for High Risk Groups Research Project — Waking effectiveness of alarms (auditory, visual and tactile) for the alcohol impaired*, Report to the Fire Protection Research Foundation, June 2007.

K.1.2.17.5 References to A.24.3.12.

(1) CARVER — *Target Analysis and Vulnerability Assessment Methodology*, Washington, DC: U.S. Department of Defense (see Field Manual 34-36, Special Operation Forces Intelligence and Electronics Warfare Operation, Sept. 30, 1991), www.defense.gov.

(2) *General Security Risk Assessment Guidelines*, Alexandria, VA: American Society for Industrial Security International, www.asisonline.org.

(3) NFPA 1600®, *Standard on Continuity, Emergency, and Crisis Management*, National Fire Protection Association, Quincy, MA, 2019 edition.

(4) NFPA 730, *Guide for Premises Security*, National Fire Protection Association, Quincy, MA, 2020 edition.

(5) *Responsible Care Code*, Washington, DC: American Chemistry Council, www.americanchemistry.com.

(6) AWWA J100, *Risk and Resilience Management of Water & Wastewater Systems*, American Water Works Association, Denver, CO, 2010, www.awwa.org.

(7) VAMCAI® *Vulnerability Assessment Methodology for Critical Asset Protection*, Wilmington, DE: SafePlace Corporation, www.safeplace.com.

(8) *Vulnerability Assessment Methodologies*, Albuquerque, NM: Sandia National Laboratories, www.sandia.gov.

(9) *SFPE Engineering Guide to Fire Risk Assessment*, Society of Fire Protection Engineers, Gaithersburg, MD, 2006, www.sfpe.org.

K.1.2.17.6 Reference to A.24.3.14.13.

International Building Code (IBC), International Code Council, Falls Church, VA, 2018.

K.1.2.17.7 References to A.24.4.8.

(1) Schifiliti, R.P., "To Leave or Not to Leave — That is the Question!", National Fire Protection Association, World Fire Safety Congress & Exposition, May 16, 2000, Denver, CO.

(2) Ramachandran, G., "Informative Fire Warning Systems," *Fire Technology*, Volume 47, Number 1, February 1991, National Fire Protection Association, 66–81.

(3) J. Bryan, "Psychological Variables That May Affect Fire Alarm Design," *Fire Protection Engineering*, Society of Fire Protection Engineers, Issue No. 11, Fall 2001.

(4) Proulx, G., "Cool Under Fire," *Fire Protection Engineering*, Society of Fire Protection Engineers, Issue No. 16, Fall 2002.

(5) General Services Administration, Proceedings of the Reconvened International Conference on Fire Safety in High Rise Buildings, Washington, D.C., October 1971.

(6) Proulx, G., "Strategies for Ensuring Appropriate Occupant Response to Fire Alarm Signals," National Research Council of Canada, Ottawa, Ontario, *Construction Technology Update*, No. 43, 1–6, December 2000.

K.1.2.17.8 References to A.24.4.8.3.2.

Kailes, J.I. and Enders, A., "Moving Beyond "Special Needs": A Function Based Framework for Emergency Management and Planning," *Journal of Disability Policy Studies*, SAGE Publications, March 2007.

Morrow, B.H., "Identifying and Mapping Community Vulnerability," *Disasters*, 23(1), 1–18, 1999.

Proulx, G., *Occupant Behaviour and Evacuation*, National Research Council of Canada, Ottawa, Ontario, 2001.

Shields, T.J., Boyce, K.E., and Silcock, G.W.H., *Client Report: Unannounced Evacuation of Marks & Spencer, Sprucefield Store*, Fire Safety Engineering Research and Technology Centre, University of Ulster, Northern Ireland, 1997.

K.1.2.17.9 References to A.29.2.

"A Few Facts at the Household Level," NFPA Fire Analysis Division, *Fire Journal*, July 2009.

Ahrens, M., "Home Structure Fires," NFPA Fire Analysis and Research Division, September 2016.

Haynes, Hylton J.G., "Fire Loss in the United States during 2015," NFPA Fire Analysis and Research Division, September 2016.

Injury Facts, National Safety Council, Itasca, IL, 2011.

K.1.2.17.10 References to A.29.5.8.

Bruck, D. and Thomas, I., "Smoke alarms for sleeping adults who are hard-of-hearing: comparison of auditory, visual, and tactile signals," *Ear and Hearing*, 30(1), February 2009, pp. 73–80.

Bruck, D., Thomas, I., and Ball, M., "Optimizing Fire Alarm Notification for High Risk Groups Research Project — Waking effectiveness of alarms (auditory, visual and tactile) for the alcohol impaired," Report to the Fire Protection Research Foundation, June 2007.

Roby, R., "Smoke Detector Alert for the Deaf," Phase II SBIR, Final Report, NIH Grant No. 2R44 DC004254-2, May 27, 2005.

K.1.2.17.11 References to A.29.8.1.

NBS GCR 75-51, *Detector Sensitivity and Siting Requirements for Dwellings*, 1975.

NBS GCR 77-82, *Detector Sensitivity and Siting Requirements for Dwellings Phase 2*, 1977.

NIST Technical Note 1455-1, *Performance of Home Smoke Detectors Analysis of the Response of Several Available Technologies in a Residential Setting*, 2007.

K.1.2.17.12 References to A.29.8.2.1.1.

Green, M. A. and Andres, C., "2004–2005 National Sample Survey of Unreported Residential Fires," CPSC, 2009.

Ahrens, M., "Factors in Smoke Alarm Performance," National Fire Protection Association, December 2009.

Thomas, I. and Bruck, D., "Smoke Alarms in Dwellings: Timely Activation and Effective Notification," Victoria University, June 2010.

K.1.2.17.13 References to A.29.11.3.

Kemano Fire Studies Part 1 of Residential Smoke Alarms, National Research Council Canada, April 2003.

Spacing Requirements for Complex Beamed and Sloped Ceilings Report, The Fire Protection Research Foundation, NFPA, April 2008.

K.1.2.17.14 References to A.29.11.3.4(6).

Dinaburg, J. and Gottuk, D.T., "Smoke Alarm Nuisance Source Characterization: Experimental Results — Final Report," Fire Protection Research Foundation, 1 Batterymarch Park, Quincy, MA, 2015.

K.1.2.17.15 References to A.29.11.3.4(8).

Gottuk, E.D. and Gottuk, D.T., "The Effect of Ceiling Fans on Smoke Alarm Performance," NFPA Research Foundation SUPDET Symposium presentation, 2015.

K.1.2.18 Other Publications — Related to Carbon Monoxide Provisions.

Ashley, E., DuBois, J., "Waking Effectiveness of Audible, Visual, and Vibratory Emergency Alarms Across All Hearing Levels," Fire Suppression and Detection Research Symposium, Orlando, FL 2005.

Coburn, R. F., Forster, R. E., and Kane, P. G., "Considerations for the physiological variables that determine the blood carboxyhemoglobin concentration in man," *Journal of Clinical Investigation*, 1965, November; 44(11):1899–1910.

Fire Protection Research Foundation (FPRF) Report, Development of Technical Basis for Carbon Monoxide Detector Siting, prepared by C. Beyler and D. Gottuk, 2007.

Report of research on emergency signaling devices for use by the hearing impaired (Subject 1971), Underwriters Laboratories, 1991 (Superseded; referenced for historical purposes).

Steinberg, S., and Nielson, G. D., "A proposal for evaluating human exposure to carbon monoxide contamination in military vehicles," AMCMS Code 672716.H700011, March 1977.

Title 47, Code of Federal Regulations, Part 15.

K.1.2.19 References Associated with Annex B.

(1) Alpert, R. "Ceiling Jets," *Fire Technology*, August 1972.

(2) "Evaluating Unsprinklered Fire Hazards," *SFPE Technology Report* 83-2.

(3) Babrauskas, V., Lawson, J. R., Walton, W. D., and Twilley, W. H. "Upholstered Furniture Heat Release Rates Measured with a Furniture Calorimeter," (NBSIR 82-2604) (Dec. 1982). National Institute of Standards and Technology (formerly

National Bureau of Standards), Center for Fire Research, Gaithersburg, MD 20889.

(4) Beyler, C. "A Design Method for Flaming Fire Detection," *Fire Technology*, Vol. 20, No. 4, November 1984.

(5) Hurley, M. J., ed., Chapter 40, *SFPE Handbook of Fire Protection Engineering*, by R. Schifiliti, R. Custer, and B. Meacham, 2016.

(6) Evans, D. D. and Stroup, D. W. "Methods to Calculate Response Time of Heat and Smoke Detectors Installed Below Large Unobstructed Ceilings," (NBSIR 85-3167) (Feb. 1985, issued Jul. 1986). National Institute of Standards and Technology (formerly National Bureau of Standards), Center for Fire Research, Gaithersburg, MD 20889.

(7) Heskestad, G. "Characterization of Smoke Entry and Response for Products-of-Combustion Detectors" Proceedings, 7th International Conference on Problems of Automatic Fire Detection, Rheinisch-Westfälischen Technischen Hochschule Aachen (March 1975).

(8) Heskestad, G. "Investigation of a New Sprinkler Sensitivity Approval Test: The Plunge Test," FMRC Tech. Report 22485, Factory Mutual Research Corporation, 1151 Providence Turnpike, Norwood, MA 02062.

(9) Heskestad, G. and Delichatsios, M. A. "The Initial Convective Flow in Fire: Seventeenth Symposium on Combustion," The Combustion Institute, Pittsburgh, PA (1979).

(10) Heskestad, G. and Delichatsios, M. A. "Environments of Fire Detectors — Phase I: Effect of Fire Size, Ceiling Height and Material," Measurements Vol. I (NBS-GCR-77-86), Analysis Vol. II (NBS-GCR-77-95). National Technical Information Service (NTIS), Springfield, VA 22151.

(11) Heskestad, G. and Delichatsios, M. A. "Update: The Initial Convective Flow in Fire," *Fire Safety Journal*, Vol. 15, No. 5, 1989.

(12) International Organization for Standardization, *Alarm systems — Audible Emergency Evacuation Signal*, ISO 8201, 2017.

(13) Klotz, J. and Milke, J. "Principles of Smoke Management," American Society of Heating, Refrigerating and Air Conditioning Engineers, Atlanta, GA, 2002.

(14) Lawson, J. R., Walton, W. D., and Twilley, W. H. "Fire Performance of Furnishings as Measured in the NBS Furniture Calorimeter, Part 1," (NBSIR 83-2787) (Aug. 1983). National Institute of Standards and Technology (formerly National Bureau of Standards), Center for Fire Research, Gaithersburg, MD 20889.

(15) Morton, B. R., Taylor, Sir Geoffrey, and Turner, J. S. "Turbulent Gravitational Convection from Maintained and Instantaneous Sources," *Proc. Royal Society A*, 234, 1–23, 1956.

(16) Schifiliti, R. "Use of Fire Plume Theory in the Design and Analysis of Fire Detector and Sprinkler Response," Master's Thesis, Worcester Polytechnic Institute, Center for Firesafety Studies, Worcester, MA, 1986.

(17) Title 47, Code of Federal Regulations, Communications Act of 1934 Amended.

(18) Schifiliti, R. and Pucci, W. "Fire Detection Modelling, State of the Art," 6 May, 1996 sponsored by the Fire Detection Institute, Bloomfield, CT.

- (19) Forney, G., Bukowski, R., Davis, W. "Field Modelling: Effects of Flat Beamed Ceilings on Detector and Sprinkler Response," Technical Report, Year 1. International Fire Detection Research Project, National Fire Protection Research Foundation, Quincy, MA. October, 1993.
- (20) Davis, W., Forney, G., Bukowski, R. "Field Modelling: Simulating the Effect of Sloped Beamed Ceilings on Detector and Sprinkler Response," Year 1. International Fire Detection Research Project Technical Report, National Fire Protection Research Foundation, Quincy, MA. October, 1994.
- (21) Brozovski, E. "A Preliminary Approach to Siting Smoke Detectors Based on Design Fire Size and Detector Aerosol Entry Lag Time," Master's Thesis, Worcester Polytechnic, Worcester, MA, 1989.
- (22) Cote, A. *NFPA Fire Protection Handbook*, 20th edition, National Fire Protection Association, Quincy, MA, 2008.
- (23) Tewarson, A., "Generation of Heat and Chemical Compounds in Fires," *SFPE Handbook of Fire Protection Engineering*, Second Edition, NFPA and SFPE, 1995.
- (24) Hollman, J. P. *Heat Transfer*, McGraw-Hill, New York, 1976.
- (25) Custer, R. L. P., and Meacham, B. "Introduction to Performance Based Fire Safety," SFPE, 1997.
- (26) Schifiliti, R. P., Meacham B., Custer, R. L. P. "Design of Detection Systems," *SFPE Handbook of Fire Protection Engineering*.
- (27) Marrion, C. "Correction Factors for the Heat of Combustion in NFPA 72," Appendix B, Fire Protection Engineering, SFPE, 1998.
- (28) Marrion, C. "Designing and Analyzing the Response of Detection Systems: An Update to Previous Correlations," 1988.
- (29) Custer, R. and Bright, R. "Fire Detection: The State-of-the-Art," NBS Tech. Note 839, National Bureau of Standards, Washington, 1974.
- (30) Meacham, Brian J. "Characterization of Smoke from Burning Materials for the Evaluation of Light Scattering-Type Smoke Detector Response," MS Thesis, WPI Center for Firesafety Studies, Worcester, MA, 1991.
- (31) Delichatsios, M. A. "Categorization of Cable Flammability, Detection of Smoldering, and Flaming Cable Fires," Interim Report, Factory Mutual Research Corporation, Norwood, MA, NP-1630, November 1980.
- (32) Heskestad, G. FMRC Serial Number 21017, Factory Mutual Research Corp., Norwood, MA, 1974.
- (33) Marrion, C. E. "Lag Time Modeling and Effects of Ceiling Jet Velocity on the Placement of Optical Smoke Detectors," MS Thesis, WPI Center for Firesafety Studies, Worcester, MA, 1989.
- (34) Kokkala, M. et al. "Measurements of the Characteristic Lengths of Smoke Detectors," *Fire Technology*, Vol. 28, No. 2, National Fire Protection Association, Quincy, MA, 1992.
- (34a) Yamauchi et al. "A Calculation Method for Predicting Heat and Smoke Detector's Response."
- (34b) Cleary et al. "Particulate Entry Lag in Spot Type Smoke Detectors," IAFSS Proceedings, Boston, MA 2000.
- (34c) Keski-Rahkonen, "Revisiting Modeling of Fluid Penetration into Smoke Detectors," AUBE 2001.
- (34d) Bjoerkman et al. "Determination of Dynamic Model Parameters of Smoke Detectors," *Fire Safety Journal*, No 37, pp. 395-407, 2002.
- (34e) Keski-Rahkonen, "A New Model for Time Lag of Smoke Detectors," International Collaborative Project to Evaluate Fire Models for Nuclear Power Plant Application, Gaithersburg, MD, May 2002.
- (35) UL 268, *Standard for Smoke Detectors for Fire Alarm Systems*, Underwriters Laboratories, Inc., Northbrook, IL, 2009.
- (36) Deal, Scott. "Technical Reference Guide for FPEtool Version 3.2," NISTIR 5486, National Institute for Standards and Technology, U.S. Department of Commerce, Gaithersburg, MD, Aug. 1994.
- (37) Mowrer, F. W. "Lag Times Associated with Detection and Suppression," *Fire Technology*, Vol. 26, No. 3, pp. 244-265, 1990.
- (38) Newman, J. S. "Principles for Fire Detection," *Fire Technology*, Vol. 24, No. 2, pp. 116-127, 1988.
- (39) Custer, R., Meacham, B., Wood, C. "Performance Based Design Techniques for Detection and Special Suppression Applications," Proceedings of the SFPE Engineering Seminars on Advances in Detection and Suppression Technology, 1994.
- (40) *SFPE Engineering Guide to Performance Based Fire Protection*, 2nd edition, 2007, SFPE, Gaithersburg, MD.
- (41) *SFPE Handbook of Fire Protection Engineering*, 5th edition, SFPE, Gaithersburg, MD, 2016.
- (42) Drysdale, Dougal, *An Introduction to Fire Dynamics*, John Wiley & Sons, New York, NY, 1998, ISBN 0 471 90613 1, 2nd edition.
- (43) Nam S., Donovan L.P. and Kim S.G., Establishing Heat Detectors Thermal Sensitivity Through Bench Scale Tests, *Fire Safety Journal*, Volume 39, Number 3, 191-215, April 2004.
- (44) Nam S., Thermal Response Coefficient TRC of Heat Detectors and Its Field Applications, Fire Detection and Research Applications Symposium, NFP Research Foundation, January 2003.
- (45) Nam S., Performance-Based Heat Detector Spacing, Interflam 2004, pp 883-892.
- (46) Geiman, J. A., "Evaluation of Smoke Detector Response Estimation Methods," Master of Science Thesis, University of Maryland, College Park, MD, December 2003.
- (47) [Reference removed.]
- (48) Geiman, J.A., and Gottuck, D.T., "Alarm Thresholds for Smoke Detector Modeling," *Fire Safety Science — Proceeding of the Seventh International Symposium*, 2003, pp. 197-208.
- (49) *The SFPE Code Official's Guide to Performance-based Design Review and Analysis of Buildings*, Society of Fire Protection Engineers, Bethesda, MD, 2004.
- (50) NFPA 101, *Life Safety Code*, National Fire Protection Association, Quincy, MA, 2009.

(51) NFPA 909, *Code for the Protection of Cultural Resource Properties — Museums, Libraries, and Places of Worship*, National Fire Protection Association, Quincy, MA, 2010.

(52) NFPA 914, *Code for Fire Protection of Historic Structures*, National Fire Protection Association, Quincy, MA, 2010.

(53) Performance-based Building Design Concepts, International Code Council, Washington DC, 2004.

(54) *Extreme Event Mitigation In Buildings — Analysis and Design*, Meacham, National Fire Protection Association, Quincy, MA, 2006.

(55) Geiman, Gottuk, and Milke, "Evaluation of Smoke Detector Response Estimation Methods: Optical Density, Temperature Rise and Velocity at Alarm," *Journal of Fire Protection Engineering*, 2006.

(56) Su et al., "Kemano Fire Studies — Part 1: Response of Residential Smoke Alarms," Research Report 108, NRCC, April 2003.

(57) Davis, W., The Zone Model Jet, "A Model for the Prediction of Detector Activation and Gas Temperature in the Presence of a Smoke Layer," NISTIR 6324, NIST, May 1999.

(58) *SFPE Engineering Guide to Human Behavior in Fire*, 2019.

(59) *Guidelines for Peer Review in the Fire Protection Design Process*, Society of Fire Protection Engineers, Gaithersburg, MD, 2009.

(60) *SFPE Engineering Guide: Guidelines for Substantiating a Fire Model for a Given Application*, Society of Fire Protection Engineers, Gaithersburg, MD, 2011.

K.1.2.20 References Associated with Annex D.

(1) Jacob, K. & Tyson, T., "Computer-Based Prediction of Speech Intelligibility for Mass Notification Systems," SUPDET 2008, Fire Protection Research Foundation, March 2008.

(2) IEC 60268-16, "Sound system equipment — Part 16: Objective rating of speech intelligibility by speech transmission index," 2011.

(3) ANSI/ASA S3.5, *Methods for Calculation of the Speech Intelligibility Index*, Acoustical Society of America, 35 Pinelawn Road, Suite 114 E, Melville, NY 11747-3177, 1997 (R2017).

(4) Barnett, P.W. and Knight, A.D., "The Common Intelligibility Scale," *Proceedings of the Institute of Acoustics*, Vol. 17, Part 7, 1995.

(5) ISO 7240-16, *Fire detection and alarm systems — Part 16: Sound system control and indicating equipment*, International Organization for Standardization, ISO Central Secretariat, BIBC II, Chemin de Blandonnet 8, CP 401, 1214 Vernier, Geneva, Switzerland, 2007.

(6) Sander J. van Wijngaarden and Jan A. Verhave, Past Present and Future of the Speech Transmission Index, Chapter 9, Measurement and Prediction of Speech Intelligibility in Traffic Tunnels Using the STI, p113, TNO Human Factors, The Netherlands, 2002.

(7) Mapp, P., "Systematic & Common Errors in Sound System STI and Intelligibility Measurements," Convention Paper 6271, Audio Engineering Society, 117th Convention, San Fran, CA, 28–31 October 2004.

(8) Peter Mapp, Past Present and Future of the Speech Transmission Index, Chapter 8, Practical Application of STI to Assessing Public Address and Emergency Sound Systems, TNO Human Factors, The Netherlands, 2002.

(9) UL 1480, *Speakers for Fire Alarm and Signaling Systems, Including Accessories*, 2016.

(10) Schifiliti, Robert P., "Fire Alarm Testing Strategies Can Improve Occupant Response and Reduce the 'Cry Wolf' Syndrome," NEMA Supplement in *Fire Protection Engineering*, Society of Fire Protection Engineers, Bethesda, MD, 2003.

(11) Breznitz, S., *Cry Wolf: The Psychology of False Alarms*, Lawrence Erlbaum Associates, Hillsdale, NJ, 1984.

K.1.2.21 References Associated with Annex G.

Kuligowski, E.D., S.M.V. Gwynne, K.M. Butler, B.L. Hoskins, and C.R. Sandler, *Developing Emergency Communication Strategies for Buildings*, NIST Technical Note 1733, National Institute of Standards and Technology, Gaithersburg, MD, 2012.

Kuligowski, E.D. and Omori, H., *General Guidance on Emergency Communication Strategies for Buildings*, NIST Technical Note 1827, National Institute of Standards and Technology, Gaithersburg, MD, 2nd Edition, 2014.

START (National Consortium for the Study of Terrorism and Responses to Terrorism), 2013. Task 2.9: Phase II Interim Report on Results from Experiments, Think-out-Louds, and Focus Groups. University of Maryland, College Park: College Park, MD.

2010 *ADA Standards for Accessible Design*, U.S. Department of Justice, Washington, DC, September 2010 (http://www.ada.gov/2010ADASTandards_index.htm).

K.1.2.22 References Associated with Annex H.

U.S. Consumer Product Safety Commission, *Responding to Residential Carbon Monoxide Incidents: Guidelines for Fire and Other Emergency Response Personnel*, Washington, DC, July 2002, <http://www.cpsc.gov/s3fs-public/coguide.pdf>.

K.2 Informational References. The following documents or portions thereof are listed here as informational resources only. They are not a part of the requirements of this document.

K.2.1 ASTM Publications. ASTM International, 100 Barr Harbor Drive, P.O. Box C700, West Conshohocken, PA 19428-2959.

ASTM E2292, *Standard Guide for Field Investigation of Carbon Monoxide Poisoning Incidents*, 2014.

K.2.2 EPRI Publications. Electric Power Research Institute, 3420 Hillview Avenue, Palo Alto, CA 94304.

Technical Report 1002925, *Stationary Battery Monitoring by Internal Ohmic Measurement*, 2002.

Technical Report 1006757, *Stationary Battery Guide; Design, Application, and Maintenance*, 2002.

K.2.3 IMSA Publications. International Municipal Signal Association, 165 East Union Street, Newark, NY 14513-0539.

IMSA Official Wire and Cable Specifications Manual, 2012.

K.2.4 NFPA Publications. National Fire Protection Association, 1 Batterymarch Park, Quincy, MA 02169-7471.

NFPA 1192, *Standard on Recreational Vehicles*, 2021 edition.

K.2.5 UL Publications. Underwriters Laboratories Inc., 333 Pfingsten Road, Northbrook, IL 60062-2096.

UL 1973, *Batteries for Use in Light Electric Rail (LER) Applications and Stationary Applications*, 1st edition, 2013, revised 2016.

UL 2054, *Household and Commercial Batteries*, 2nd edition, 2004, revised 2011.

UL 2075, *Gas and Vapor Detectors and Sensors*, 2013, revised 2017.

UL 9540, *Outline of Investigation for Energy Storage Systems and Equipment*, 1st edition, 2016.

K.2.6 Other Publications.

Keating, John P. and Loftus, Elizabeth F., "People Care in Fire Emergencies — Psychological Aspects, 1975," SFPE, 1975.

Stone, W. Electromagnetic Attenuation in Construction Materials, National Institute of Standards and Technology, NISTIR 6055, 1997.

K.3 References for Extracts in Informational Sections.

NFPA 70®, *National Electrical Code*®, 2020 edition.

NFPA 92B, *Smoke Management Systems in Malls, Atria, and Large Spaces*, 1995 edition (withdrawn).

NFPA 101®, *Life Safety Code*®, 2021 edition.

NFPA 1221, *Standard for the Installation, Maintenance, and Use of Emergency Services Communications Systems*, 2019 edition.

Index

Copyright © 2021 National Fire Protection Association. All Rights Reserved.

The copyright in this index is separate and distinct from the copyright in the document that it indexes. The licensing provisions set forth for the document are not applicable to this index. This index may not be reproduced in whole or in part by any means without the express written permission of NFPA.

-A-

- Abnormal (off-normal) condition**, 10.3.4, 10.8.1, 12.2.2, 23.3.3.1(3), 23.5 to 23.7, 24.5.2.2, 24.6.11.2, 24.10.4, 27.6.1.2, A.12.3
Definition, 3.3.65.1
- Accessible, readily (readily accessible)**, 10.6.10.5, 10.18.3.1, 27.6.2.1.1, A.24.5.2.1, A.24.5.12.1
Definition, 3.3.3
- Accessible (as applied to equipment)**
Definition, 3.3.1
- Accessible (as applied to wiring methods)**
Definition, 3.3.2
- Accessible spaces (as applied to detection coverage)**
Definition, 3.3.4
- Acknowledge**, 10.11.8.2, 10.14.6.2, 23.8.1.2.1.1, 26.3.6.6.2, 26.3.8.3.5.2, 26.4.4.2.1.1, 26.4.4.2.2.1(B), 26.4.4.2.2.3, 26.4.4.2.2.4, 26.4.4.3, 26.6.4.2.5, 26.6.6.5, A.26.4.4.3, A.26.6.6.5
Definition, 3.3.5
- Acoustically distinguishable space (ADS)**, 18.4.11, 24.4.2.2.2, 24.5.3.2, A.18.4.11, A.24.4.2.2.2, D.2.3.1, D.3.5
Definition, 3.3.6, A.3.3.6
- Active multiplex systems**, A.26.6.3
Definition, 3.3.7
Testing, Table 14.4.3.2
- Addressable devices**
Circuits, notification appliances, 23.8.6.4
Definition, 3.3.8
- Adoption of code**
Requirements, 1.7
Sample ordinance, Annex E
- Adverse conditions**, 26.6.5.1.4, 26.6.5.1.6, 26.6.5.2.7, A.26.6.5.1.4
Definition, 3.3.9
- Aerial construction**, 27.7.1.2.2, 27.7.1.4, 27.7.3.6, 27.7.3.9 to 27.7.3.12
- Air ducts**, *see* Ducts, detectors in
- Air sampling-type detectors**, 17.7.4.6, 17.7.7.3.3.3, A.17.7.4.6.1.1 to A.17.7.4.6.4.2
Definition, 3.3.77.1
Inspection, Table 14.3.1
Test methods, Table 14.4.3.2
- Air stratification**, *see* Stratification
- Alarm**
Carbon monoxide, *see* Carbon monoxide alarms
Definition, 3.3.11
- Alarm boxes**, 27.4.2.4, 27.6, A.26.4.3.6, A.27.6.1 to A.27.6.6.7; *see also* Auxiliary alarm systems
Auxiliary, 27.4.2.4(2)
Definition, 3.3.12.1
Inspections, Table 14.3.1
Testing, Table 14.4.3.2
Wireless network boxes, 27.4.3.8(2)
- Coded, *see* Coded
- Inspections, Table 14.3.1
- Manual, 10.4.6.3, 17.15, 23.3.3.1(1), 23.8.5.1.2, 27.4.2.4, 27.4.3.8, A.17.15.8 to A.17.15.9.5, A.23.8.5.1.2
- Auxiliary fire alarm systems, application of, Table 27.6.3.2.2.3
- Definition, 3.3.12.3, A.3.3.12.3
- Inspections, Table 14.3.1
- Location, 17.15.6, 17.15.9.2, 17.15.9.4 to 17.15.9.6, A.17.15.9.5
- Mass notification system, 24.5.9.4 to 24.5.9.6
- Mounting, 17.15.4, 17.15.5, 17.15.9.6
- Signal initiation, 23.3.3.1(1), 23.8.5.2, 26.2.1.1
- Testing, Table 14.4.3.2
- Master, 27.4.2.4(3), 27.6.4
Definition, 3.3.12.4
Inspections, Table 14.3.1
Testing, Table 14.4.3.2, F.2.16, F.2.17
Wireless network boxes, 27.4.3.8(3)
- Municipal (street box)
Definition, 3.3.181
- Publicly accessible, 27.4.2.4(1), 27.6.2, A.27.6.2
Definition, 3.3.12.5
Inspections, Table 14.3.1
Location, 27.6.2.1.6, 27.6.2.1.7, 27.6.2.1.10, A.27.6.2.1.6, A.27.6.2.1.10
Power supplies, 27.6.6.9 to 27.6.6.13
Testing, Table 14.4.3.2
Wired network boxes, 27.6.5
Wireless network boxes, 27.4.3.8(1), 27.6.6, A.27.6.6.2, A.27.6.6.7
- Alarm condition**, 10.8.2, 21.3.4, 21.7.6, 21.10.6, 23.8.2.7, A.23.8.2.7.4
Definition, 3.3.65.1.1, A.3.3.65.1.1
- Alarm repeater systems**, 27.5.3.4, 27.5.5.3.4.1, 27.5.5.3.5, 29.10.8.1.1(4), A.26.6.5.2, A.27.5.5.1.4; *see also* Radio alarm repeater station receiver (RARSR); Repeater station; Wireless repeater
Definition, 3.3.13
- Alarm responses**, 10.9.1
Definition, 3.3.261.1, A.3.3.261.1
- Alarm service (definition)**, 3.3.14
- Alarm signals**, 10.7 to 10.15, A.10.7.3 to A.10.15.10.7; *see also* Fire alarm signals; Supervisory signals; Trouble signals
Central station service, 26.3.8.3.1, A.26.3.8.3.1(1)
Coded, 10.14.4
Content, 26.2.3
Control units, interconnected, 23.8.2.7.1
Deactivation, 10.11.8, 10.12, 24.5.13.5, 24.5.25.1, A.10.12
Definition, 3.3.272.1, A.3.3.272.1
Distinctive, *see* Distinctive signals
Ducts, detectors in, 21.7.4
Elevator system, output signals to, 21.6.2.5, A.21.6.2.5

- Emergency communications systems, 24.11.3, A.24.11.3
- End-to-end communication time, 12.3.3, 12.3.6, 26.6.3.8, A.12.3.3, A.12.3.6(1) to A.12.3.6(5), Table A.26.6.1
- Household signaling systems, 29.10.9.6, 29.10.9.7, A.29.10.9.7
- Low-power radio (wireless) systems, 23.16.3, A.23.16.3.1
- Off-premises, 23.3.3.1(12), 23.12, A.23.12.4
- Positive alarm sequence, *see* Positive alarm sequence
- Power supervisory devices, operation of, 10.6.9.4
- Proprietary supervising system, 26.4.4.1 to 26.4.4.4, 26.4.6.1.6.1, A.26.4.4.1.3, A.26.4.4.3
- Public emergency alarm reporting systems, 27.5.2.2.2
- Remote supervising station system, 26.5.1.3, 26.5.1.4, 26.5.1.5.2, 26.5.3.1, 26.5.4, 26.5.6.3.1, 26.5.7, 26.5.8.1, A.26.5.3.1.4
- Response to, 10.9.1
- Secondary power, operation on, 10.6.7.1.1, 26.6.3.13, A.26.6.3.13.1
- Supervising station alarm systems, 26.2.1, 26.6.1.2, 26.6.3.8, 26.6.3.11, 26.6.3.14, A.26.2.1.2, A.26.2.1.3(3)
- Wireless, 27.4.3.4, 27.5.5.1.3
- Alarm systems**, *see* Fire alarm systems; In-building fire emergency voice/alarm communications systems (EVACS); In-building mass notification systems; Public emergency alarm reporting systems; Supervising station alarm systems
- Alarm verification features**, Table 14.4.3.2, 23.8.5.4.1, 23.8.5.4.3(3), 26.2.2, A.23.8.5.4.1, A.26.2.2
 - Definition, 3.3.17
- Alert tone**, 18.4.1.5, 24.6.1.3, A.18.4.1.5.1, G.2.1
 - Definition, 3.3.18
- Amplifiers**, 10.19.1, Table 14.4.3.2, A.10.19.1
- Analog initiating devices (sensor)**
 - Definition, 3.3.148.1
- Ancillary functions**
 - Definition, 3.3.20, A.3.3.20
 - Emergency communications systems, 24.3.5, A.24.3.5.2
- Annunciation**, 10.18, A.10.18.3, A.10.18.5, F.1
 - Combination systems, 23.8.4.4.3, 23.8.4.5.2
 - Control units, interconnected, 23.8.2.7.1 to 23.8.2.7.4, A.23.8.2.7.4
 - Of elevator status, 21.5, A.21.5
 - Protected premises fire alarm systems, 23.8.5.8.1, 23.8.5.10.2, 23.8.5.10.3
 - Supervising station communication methods, Table A.26.6.1
 - Visible zone indication, 10.18.4
 - Alarm, 10.18.1
 - Supervisory and trouble, 10.18.2
 - Zones, 10.18.5, A.10.18.5
- Annunciators**, *see also* Remote annunciators
 - Access and location, 10.18.3, A.10.18.3
 - Control units, interconnected, 23.8.2.7.4, A.23.8.2.7.4
 - Definition, 3.3.21
 - Inspection, Table 14.3.1
 - Testing, Table 14.4.3.2
- Apartment buildings**, A.29.1.2, A.29.8.1.1; *see also* Household signaling systems
 - Definition, 3.3.22
- Application of code**, 1.3
- Approved (definition)**, 3.2.1, A.3.2.1
- Area of refuge emergency communications systems**, 24.3.7.2(3), 24.3.14.9, 24.10, 24.11.1.2(3), A.24.3.14.9, A.24.10
- As-built drawings**, *see* Record drawings
- Audible notification appliances**, 18.4, A.18.4.1.1 to A.18.4.11.4; *see also* Emergency voice/alarm communications; Exit marking audible notification appliances
 - Alarm signal deactivation (silencing), 10.11.8.2, 10.12.2, 24.5.13.5, 24.5.25.1, A.10.12.2
 - Area of refuge, stairway, and elevator communication systems, 24.10.12
 - Audibility, 18.4.1.1 to 18.4.1.4, 18.4.4.1, 18.4.5.1, A.18.4.1.1 to A.18.4.1.3, A.18.4.4.1, A.18.4.5.1, D.2.3.2
 - Carbon monoxide alarm signals, 18.4.3, 29.10.7.3, 29.10.7.4, 29.10.7.6, 29.10.7.7
 - Change of status signals, 26.6.6.5(1)
 - Definition, 3.3.189.1
 - Distinctive signals, *see* Distinctive signals
 - Documentation, 7.2.1(10)
 - Emergency voice/alarm communications, 24.4.8.6, A.24.4.8.6.1, A.24.4.8.6.3
 - Evacuation signals, 18.4.2, 29.5.1, A.18.4.2.1, A.18.4.2.5, A.29.5.1
 - Hearing loss, for persons with, 29.5.10.1
 - Household signaling systems, 29.5.1, 29.5.5 to 29.5.7, 29.5.10.1, 29.8.2.2, 29.10.7.3, 29.10.7.4, 29.10.7.6, 29.10.7.7, A.29.5.1, A.29.5.5, A.29.5.6, A.29.5.10.1, A.29.8.2.2
 - Trouble signals, 29.9.2, 29.9.5, 29.9.7, 29.10.6.5
 - Inspections, Table 14.3.1
 - Location of appliances, 18.4.9, 18.4.10
 - Mass notification systems, 24.5.2.10, A.24.5.2.10
 - Nameplates, 18.3.2.1, 18.3.2.2
 - Narrow band tone signaling for exceeding masked thresholds, 18.4.7, A.18.4.7
 - Private mode, 18.4.4.3, 18.4.4.4, 18.4.5, A.18.4.5.1, A.18.4.5.2
 - Proprietary supervising systems, 26.4.4.2.1.1
 - Public emergency alarm reporting systems
 - Alarm receiving equipment, 27.5.2.2.5.1, 27.5.2.2.6, 27.5.2.4.2 to 27.5.2.4.5, 27.5.2.5.7, 27.5.4.2.3, 27.5.4.3.2, 27.5.5.3.7, 27.5.5.3.8
 - Auxiliary fire alarm systems, 27.6.3.2.3.11
 - Wired network systems, 27.5.4.4.4
 - Public mode, 18.4.4, A.18.4.4
 - Remote supervising station systems, 26.5.1.4, 26.5.1.5, 26.5.4.1
 - Sleeping areas, 18.4.6, A.18.4.6.1 to A.18.4.6.3(2)
 - Supervisory signals, 10.14.1, 10.14.2.1, 10.14.5, 10.14.6.1, 10.14.6.2
 - Testing, Table 14.4.3.2, A.14.4.3.2, F.2.11, F.2.12
 - Textual appliances, Table 14.4.3.2, 18.8, A.18.8.1.2
 - Definition, 3.3.189.1.2, A.3.3.189.1.2
 - Trouble signals, 10.15.3 to 10.15.9, 10.15.10.4, Table 14.4.3.2, A.10.15.9
 - Household signaling systems, 29.9.2, 29.9.5, 29.9.7, 29.10.6.5
- Authority having jurisdiction (definition)**, 3.2.2, A.3.2.2
- Automatic drift compensation**, 23.8.5.4.2
- Automatic extinguishing systems**, *see* Extinguishing systems
- Automatic extinguishing system supervisory devices**, 17.17.2.2.2, 23.3.3.1(2), 23.8.5.6, 23.8.5.8 to 23.5.10, A.17.17.2.2.2, A.23.8.5.6, A.23.8.5.8
 - Definition, 3.3.148.2, A.3.3.148.2
- Automatic fire detectors**, *see also* Fire-gas detectors; Heat detectors; Radiant energy-sensing fire detectors; Smoke detectors

Combination, B.3.2.4.3
 Definition, 3.3.77.5, A.3.3.77.5
 Definition, 3.3.77.2, A.3.3.77.2
 Fire extinguishing or suppression system operation (definition), 3.3.77.3
 Initiating devices, Table 27.6.3.2.2.3
 Manual fire box, available, 23.8.5.1.2, A.23.8.5.1.2
 Other types, 17.11, A.17.11.2
 Definition, 3.3.77.15
 Sensitivity testing, 14.4.4.3
 Signal disposition, 26.2.1.1
 Spacing, Annex B
 Two fire detectors, operation of, 23.8.5.4.3 to 23.8.5.4.5
Automatic fire extinguishing or suppression system operation (definition), 3.3.77.3
Autonomous control unit (ACU), *see* Control units
Auxiliary alarm boxes, *see* Alarm boxes
Auxiliary alarm systems, 27.6.3, A.27.6.3.1.2 to A.27.6.3.2.2.1
 Definition, 3.3.229.1, A.3.3.229.1
 Interfaces with public alarm systems, 27.6.3.2.2.2
 Types of systems, 27.6.3.2.2, A.27.6.3.2.2.1 (1) to A.27.6.3.2.2.1
Average ambient sound level, 18.4.1.1, 18.4.4.1, 18.4.4.5.1, 18.4.5.1, A.18.4.1.1, A.18.4.4.1, A.18.4.5.1
 Definition, 3.3.31, A.3.3.31

-B-

Backbone, A.12.3.6(1)
 Definition, 3.3.32, A.3.3.32
Batteries, 10.6.10, A.10.6.10
 Box, 27.6.6.9 to 27.6.6.13
 Capacity (definition), 3.3.33.1
 Charger, 10.6.10.3, 10.6.11.7, A.10.6.10.3.4
 Definition, 3.3.33.2
 Metering, 10.6.10.5
 Monitoring integrity of, 10.6.10.6
 Charging, 10.6.10.3, A.10.6.10.3.4
 Definition, 3.3.33, A.3.3.33
 Engine-driven generators, 10.6.11.7
 Float charge, 27.5.2.6.4, 27.5.2.6.5, 27.5.2.8, A.10.6.7.2.14, A.10.6.10.3.4, A.14.4.3.2
 Definition, 3.3.33.2.1
 Fully charged, 10.6.10.3.1, 10.6.10.3.2, Table 14.4.3.2, A.10.6.10.3.4, A.14.4.3.2, D.3.1.7
 Definition, 3.3.33.2.2
 Household signaling systems, 29.9.1, 29.9.2, 29.9.4(7), 29.9.5, 29.9.7
 Inspections, Table 14.3.1
 Load test (definition), 3.3.33.3
 Location, 10.6.10.2
 Low-power radio (wireless) system power, 23.16.2, A.23.16.2
 Primary (dry cell), Table 14.3.1, 23.16.2, 29.9.1, A.23.16.2
 Definition, 3.3.215
 Public emergency alarm reporting systems, 27.5.2.5.1 to 27.5.2.5.4, 27.5.2.8, 27.5.4.3.1, 27.6.6.9 to 27.6.6.13, A.27.5.2.5.1(1), A.27.5.2.5.1(2)
 Rechargeable, 29.9.3, 29.9.5, 29.9.8
 Definition, 3.3.33.5
 Replacement, 14.4.5.9

Secondary power source, 10.6.6.3.1, 10.6.7.2.14, 10.6.7.3.1, 10.6.7.4.1, 29.9.1, 29.9.3, 29.9.4(7), A.10.6.7.2.14, A.10.6.7.2.15
 State of charge (SOC) (definition), 3.3.33.2.3
 Testing, Table 14.4.3.2, A.14.4.3.2
 Trickle charge (definition), 3.3.33.2.4
 Unit (multi-cell) (definition), 3.3.43.3
 Valve-regulated lead acid (VRLA), Table 14.3.1, Table 14.4.3.2, A.10.6.10, A.14.4.3.2

Beam construction (ceiling)

Definition, 3.3.42.1
 Detector location, 17.6.3.3.2
 Detector spacing, 17.6.3.3.1, 17.7.4.2.4, 29.11.4.6, A.17.7.4.2.4

Box alarms, *see* Alarm boxes

Box batteries, 27.6.6.9 to 27.6.6.13

Box circuits, 27.5.2.5.1, 27.5.2.5.6.2, 27.5.4.1, 27.5.4.2.1, 27.5.4.2.2, 27.5.4.4, 27.7.2.2

Building, *see also* In-building mass notification systems

Emergency radio communication system in, 14.4.10
 Wiring inside, 27.7.1.2.3, 27.7.1.6, A.27.7.1.6.2

Building fire alarm command center, 10.14.1(2)

Building fire alarm systems, 23.3.3.1, A.23.3.3.1; *see also* In-building mass notification systems; Protected premises (local) alarm and signaling systems

Definition, 3.3.118.4.1

Building system information units (BSIU)

Control units, located with, 23.8.4.2.2.1 to 23.8.4.2.2.3, A.23.8.4.2.2.2
 Definition, 3.3.36
 Emergency communications systems, 24.3.11

Burglar alarm systems, 26.6.4.3.2.5

-C-

Cables

Aerial construction, 27.7.1.2.2, 27.7.1.4
 Fiber-optic, 12.2.3.1, Table 14.3.1, Table 14.4.3.2, 27.4.2.1.1, A.27.7.1.6.2, A.27.7.3
 Inside buildings, 27.7.1.2.3, 27.7.1.6, A.27.7.1.6.2
 Leads down poles, 27.7.1.5
 Public cable plant, *see* Wired network, public fire alarm reporting system
 Underground, 27.7.1.2.2, 27.7.1.3

Call forwarding equipment, 26.6.4.2.5(8), Table A.26.6.1, A.26.6.4.2.5(8)

Carbon monoxide, Annex H

Dangers of, H.1
 Emergency responders, information for, H.2

Carbon monoxide alarms, 14.4.5.7, 29.1.2, 29.3.3, 29.7, 29.10.3, A.29.1.2, A.29.3.1, A.29.3.3, A.29.7

Definition, 3.3.11.1
 Markings, 29.14.1.2
 Power supplies, 29.9, A.29.9.4(3)

Carbon monoxide alarm signals, 10.7.5, 10.10.3, 18.4.3, 23.8.4.9, 29.5.4, 29.5.6, 29.10.7.3, 29.10.7.4, A.23.8.4.9.2, A.29.5.4, A.29.5.6

Definition, 3.3.272.2
 Priority of, 29.10.7.7
 Secondary power supply, use of, 29.9.5
 Supervising station alarm systems, 26.2.4, A.26.2.4.1.3

- Carbon monoxide detection systems**, 1.3.1(2), 14.4.5.7, 14.4.6.5, 17.12, A.17.12.1(1), A.17.12.1(2)
 - Combination systems, Table 14.3.1, Table 14.4.3.2, 14.4.5.8, 23.8.4.9, 29.10.7, A.23.8.4.9.2, A.29.10.7.8
 - Definition, 3.3.37.1
 - Definition, 3.3.37
 - Detectors (definition), 3.3.77.4
 - Emergency control function interface, HVAC system, 21.7.6
 - Household systems, Table 14.4.3.2, Chap. 29
 - Combination systems, 29.10.7, A.29.10.7.8
 - Definition, 3.3.37.2
 - Testing, 14.4.8, 29.10.6.11, A.14.4.8.1.3
 - Installation, 17.12.1, 17.12.6, 17.12.8, 29.3.2, 29.3.3, A.17.12.1(1), A.17.12.1(2), A.29.3.3
 - Location of detectors, 17.12.1, 17.12.3 to 17.12.5, A.17.12.1(1)
 - Markings, 29.14.1.2
 - Notification appliance deactivation, 10.13
 - Power supplies, 29.9, A.29.9.4(3)
 - Protected premises alarm and signaling systems, 23.3.3.1, 23.8.3, 23.8.6.1.2, 23.8.6.1.3, 23.9.2, 23.15.6, A.23.3.3.1
 - Secondary power supply, 10.6.7.2.15, 10.6.7.2.16
 - Servicing of, 26.2.4.1.3, 26.2.4.2.2, A.26.2.4.1.3
- Carrier (definition)**, 3.3.38
- Carrier system (definition)**, 3.3.39
- Ceiling height**
 - Definition, 3.3.41
 - Fire development and, B.3.2.3
- Ceilings**, *see also* Level ceilings; Sloping ceilings; Sloping peaked-type ceiling; Sloping shed-type ceiling; Smooth ceilings
 - Ambient ceiling temperature, Table 17.6.2.1, 17.6.2.3, A.17.6.2.3
 - Definition, 3.3.40, A.3.3.40
 - Detector location and spacing on, 17.6.3, 17.7.4, 29.8.1.3.1, 29.8.1.3.2, 29.11.3.1 to 29.11.3.4, 29.11.4, A.17.6.3.1.1 to A.17.6.3.6, A.17.7.4.2 to A.17.7.4.7.8, A.29.8.1.3.1, A.29.11.3.1 to A.29.11.3.4(11), A.29.11.4
 - High, 17.6.3.5, A.17.6.3.5.1, A.17.6.3.5.3
 - Open grid, 17.5.3.1.3
 - Shapes of (definition), 3.3.270
 - Stratification below, *see* Stratification
 - Suspended, 17.7.4.5
 - Visual notification appliances located on, 18.5.5.4, 18.5.5.5, Table 18.5.5.7.1(b), 18.5.5.7.6 to 18.5.5.7.8, A.18.5.5.4, A.18.5.5.5.6
- Ceiling surfaces**, *see also* Beam construction (ceiling); Smooth ceilings; Solid joist construction (ceiling)
 - Girder (definition), 3.3.42.2
- Cells**, *see also* Batteries
 - Absorbed glass mat (AGM), A.10.6.10
 - Definition, 3.3.43.2.1
 - Definition, 3.3.43
 - Gelled electrolyte (gell cell), A.10.6.10
 - Definition, 3.3.43.2.2
 - Primary (dry)
 - Definition, 3.3.43.1
 - Starved electrolyte, A.10.6.10
 - Definition, 3.3.43.2
 - Unit (multi-cell)
 - Definition, 3.3.43.3
- Valve-regulated lead acid (VRLA)
 - Definition, 3.3.43.4, A.3.3.43.4
- Central station**, *see* Central supervising station
- Central station alarm system**, *see* Central station service alarm systems
- Central station service**, 26.3, A.26.3.2 to A.26.3.8.3.5.3
 - Contract requirements, 26.3.3
 - Definition, 3.3.303.1
 - Documentation, 7.5.9
 - Indication of, 26.3.4, A.26.3.4
- Central station service alarm systems**, 26.3, Table A.26.1, A.26.3.2 to A.26.3.8.3.5.3
 - Definition, 3.3.302.1
 - Disposition of signals, 26.3.8.3, A.26.3.8.3.1(1) to A.26.3.8.3.5.3
 - Guard's signal, 26.3.8.3.2
 - Personnel, 26.3.7
 - Presignal feature, 23.8.1.1.2(1)
 - Procedures, 26.3.8, A.26.3.8.3.1(1) to A.26.3.8.3.5.3
 - Protected premises fire alarm systems, 23.12.1
 - Record keeping and reporting, 26.3.8.3.5.1, 26.3.9
 - Remote signals received by, 26.5.3.1.3
 - Testing and maintenance, 14.2.3.5, 14.4.7, 26.3.8.3.5.1, 26.3.9.2, 26.3.10
 - Two-way radio frequency (RF) systems, supervision of, 26.6.5.1.6.3
- Central supervising station**
 - Definition, 3.3.301.1
 - Equipment, 26.3.6, A.26.3.6.6
 - Facilities, 26.3.5
 - Household signaling systems, 29.10.9.6
 - Inspection, 14.4.3.1, A.14.4.3.1
 - Pathway survivability, emergency communications systems, 24.3.14.15
 - Presignal feature, use of, 23.8.1.1.2(1)
- Certification of personnel**, 10.5.1.3, 10.5.1.6, 10.5.2.3, 10.5.2.5, 10.5.3.4, 10.5.3.5.1, 10.5.4.4, 10.5.5.1, 10.5.5.2, 10.5.6.4.2, A.10.5.3, A.10.5.3.4(1) to A.10.5.3.4(3), A.10.5.5.1(2), A.10.5.6.4.2(2), A.10.5.6.4.2(4)
- Channels**, *see also* Communications channels; Transmission channels
 - Definition, 3.3.50
 - Radio (definition), 3.3.50.2, A.3.3.50.2: *see also* Radio frequency
- Circuit conductors**, 27.7.1.1
- Circuit interface**, *see* Interface; Interface equipment
- Circuits**, Chap. 12; *see also* Communications circuits; Paths (pathways)
 - Branch circuits, 10.6.5.1, 10.6.5.2.1, 10.6.5.3, 10.6.7.3.1(2), 10.6.7.4.1, 29.9.4, A.10.6.5.1.2, A.23.6.3.3.2, A.23.6.3.6.2
 - Class, 23.4.3, F.1, F.3
 - Combination household signaling systems, 29.10.7.6
 - Definition, 3.3.51
 - Designations, 23.4.2, A.23.4.2.2
 - Disconnecting means, 10.6.5.2, 10.6.5.4, 21.4.1, 21.4.3, 21.4.4, A.10.6.5.2.2, A.21.4.1, A.21.4.3, A.21.4.4
 - Elevator shutdown, control circuits for, 21.4.4, 21.4.5, A.21.4.4
 - Ground connections, 12.2.4, A.12.2.4.3
 - Identification and accessibility, 10.6.5.2, A.10.6.5.2.2
 - Identification nomenclature, 12.7, A.12.7

- Integrity, 12.6, Table 14.4.3.2, 24.5.25.2(3), A.12.6
- Notification appliance, *see* Notification appliance circuits
- Protected premises fire alarm systems, 23.4.2, 23.4.3, 27.2.4, A.23.4.2.2
- Protection, 10.6.5.3, 23.8.5.11, 27.7.3, A.27.7.3
- Public emergency alarm reporting systems
 - Alarm receiving equipment, 27.5.2.2.2, 27.5.2.2.3.1, 27.5.2.2.3.2, 27.5.2.3, 27.5.2.5, 27.5.4.1, A.27.5.2.5.1(1), A.27.5.2.5.1(2)
 - Box, *see* Box circuits
 - Protection, circuit, 27.7.3, A.27.7.3
 - Public cable plant, 27.7, A.27.7.1.6.2, A.27.7.3
 - Signal transmission facilities, 27.7.2
- Remote supervising station system, 26.5.1.5.2
- Signaling lines, 23.4.2, 23.8.2.6, A.23.4.2.2
- Status changes, display and recording of, 26.6.6.1, A.26.6.6.1
- Testing, Table 14.4.3.2, 14.4.7, Annex F
- Wiring diagrams, Annex F
- Cloud chamber smoke detection (definition), 3.3.285.1**
- Code**
 - Adoption requirements, 1.7
 - Definition, 3.2.3, A.3.2.3
 - Deviations from adopted code record of completion, Fig. 7.8.2(f), Fig. A.7.8.2(1)(f)
 - Sample ordinance, Annex E
- Coded**
 - Alarm signals, 10.11.4, 10.11.5, 10.14.4, A.10.11.4
 - Definition, 3.3.54, A.3.3.54
 - Retransmission procedures, 26.4.6.1.3.3, A.26.4.6.1.3.3
 - Supervisory signals, 10.14.3, 10.14.4
- Combination carbon monoxide detection systems, *see* Carbon monoxide detection systems**
- Combination detectors, 14.4.5.8, 17.7.7.1.1, 17.9.1, 17.9.2, B.3.2.4.3**
 - Definition, 3.3.77.5, A.3.3.77.5
 - Testing, Table 14.4.3.2, F.2.5, F.2.6
- Combination emergency communications systems, *see* Emergency communications systems—combination**
- Combination fire alarm and guard's tour box, 17.15.3**
 - Definition, 3.3.12.2
- Combination fire alarm systems, 21.2.3, 23.3.3.1(13), 23.8.2.1 to 23.8.2.8, 23.8.4, 29.10.7, A.23.8.2.7.4, A.23.8.4.1 to A.23.8.4.10, A.29.10.7.8**
 - Definition, 3.3.118.1, A.3.3.118.1
 - Inspections, Table 14.3.1
 - Testing, Table 14.4.3.2
- Command center, emergency, *see* Emergency communications systems—emergency command center**
- Common talk mode, *see* Talk mode**
- Communications center**
 - Alarm boxes, transmission from, *see* Alarm boxes
 - Alarm processing equipment, 27.5, A.27.5.2.5.1(1), A.27.5.2.5.1(2)
 - Alarm signal verification, 26.2.2, A.26.2.2
 - Circuit protection, 27.7.3, A.27.7.3
 - Definition, 3.3.60, A.3.3.60
 - Indicator of signal transmitted to, 27.6.1.4, A.27.6.1.4
 - Power supply messages, transmission of, 27.6.6.10.5, 27.6.6.10.6, 27.6.6.11.4.1, 27.6.6.11.5, 27.6.6.13.2.1
 - Public emergency alarm reporting systems wireless network, 27.4.3.6
 - Remote supervising stations, transmission from, 26.5.3.1.1
 - Retransmission to, 26.2.1.2, 26.2.1.3, 26.3.2(3), 26.3.6.6, 26.3.8.3.1(1), 26.4.6.1.3.3, 26.5.1.3, 26.5.4.4, 26.5.6.3.1(1), 27.5.2.1.2, 27.5.2.1.3, 29.10.8.1.1(4), Table A.26.1, A.26.2.1.2, A.26.2.1.3(3), A.26.3.6.6, A.26.3.8.3.1(1)
- Communications channels, 26.4.6.1.3, A.26.4.6.1.3.3**
 - Definition, 3.3.50.1
- Communications circuits**
 - Definition, 3.3.62
 - Emergency voice/alarm communications, 24.4.8.6, A.24.4.8.6.1, A.24.4.8.6.3
 - In-building mass notification systems, 24.5.4, A.24.5.4.1
 - Pathway survivability, 24.3.14, A.24.3.14.3, A.24.3.14.9
- Communications cloud (definition), 3.3.63**
- Compatibility, 10.3.3, 23.2.2.1.2, A.10.3.3, A.23.2.2.1.2, Table A.26.1, E.1**
- Completion, records of, *see* Records**
- Completion documentation, 7.5, A.7.5.1 to A.7.5.8**
- Computer systems**
 - Alarms and supervisory signals, 26.2.8, 26.3.6.3
 - Communications center, 27.5.2.9
 - Control, 23.2.2, A.23.2.2.1.1 to A.23.2.2.2
 - Distributed recipient mass notification systems, A.24.7.5
- Condition, *see also* Abnormal (off-normal) condition; Alarm condition; Normal condition; Supervisory condition; Trouble condition**
 - Definition, 3.3.65, A.3.3.65
 - Pre-alarm, 10.8.2.1
 - Definition, 3.3.65.1.2, A.3.3.65.1.2
- Conductors**
 - Circuit, 27.7.1.1
 - Testing, Table 14.4.3.2
- Constantly attended, 23.8.1.1.2, 23.8.6.1.3, 24.3.5.2, 24.10.3.3, 24.10.6, A.24.10**
 - Definition, 3.3.66
- Contiguous property, 26.4.2.2**
 - Definition, 3.3.221.1
- Control circuits, 10.17, 21.2.4, A.21.2.4**
- Control equipment, *see also* Local operating console (LOC)**
 - Definition, 3.3.68
 - Elevators, A.21.4.4
 - Emergency voice/alarm communications systems, 24.4.5, A.24.4.5.1
 - Household signaling systems, A.29.10.7.8
 - In-building mass notification systems, 24.5.2.3 to 24.5.2.10, 24.5.12, A.24.5.2.3 to A.24.5.2.10, A.24.5.12.1
 - Inspections, Table 14.3.1
 - Software and firmware control, 23.2.2, A.23.2.2.1.1 to A.23.2.2.2
 - Testing, 14.4.2.1 to 14.4.2.3, Table 14.4.3.2
- Control units, *see also* Fire alarm control units (FACU)-**
 - Area of refuge, stairway, and elevator communications systems, 24.10.3 to 24.10.5, 24.10.9, A.24.10.3 to A.24.10.6
 - Audible signals on, 10.10.4, 10.11.8.1, 10.11.8.2, A.10.10.4
 - Autonomous control unit (ACU), 24.5.1.2(1), 24.5.11
 - Definition, 3.3.69.1, A.3.3.69.1

- Carbon monoxide detection systems, 29.7, A.29.7
 - Definition, 3.3.69
 - Diagrams, 7.4.7
 - Elevators, 21.4.5, 21.4.6, A.21.4.4
 - Emergency communications control unit (ECCU), 24.3.10, 24.11.2, A.24.3.10
 - Definition, 3.3.69.2
 - Household signaling systems, 29.10.6, A.29.10.6.2
 - In-building mass notification systems, 24.5.1.2(1), 24.5.1.3, 24.5.8
 - Testing, Table 14.4.3.2
 - Visible signals on, 10.11.8.1, 10.11.8.2
 - Wireless (definition), 3.3.69.4; *see also* Radio alarm system (RAS)
 - Control valves**, 17.1.7.1
 - Converters**, 27.5.2.6
 - Corridors, visual notification appliances located on**, 18.5.5.8, A.18.5.5.6
 - Coverage, detector**, 17.5.3, A.17.5.3
 - Cybersecurity**, Chap. 11, Annex J
 - Definition, 3.3.70
 - Performance, 29.10.10
- D-**
- DACR**, *see* Digital alarm communicator receiver (DACR)
 - DACS**, *see* Digital alarm communicator system (DACS)
 - DACT**, *see* Digital alarm communicator transmitter (DACT)
 - Dampers, smoke and fire**, 21.7.2, A.21.7.2
 - DARR**, *see* Digital alarm radio receiver (DARR)
 - DARS**, *see* Digital alarm radio system (DARS)
 - DART**, *see* Digital alarm radio transmitter (DART)
 - Day-care homes**, A.29.1.2, A.29.8.1.1; *see also* Household signaling systems
 - Definition, 3.3.71
 - Dedicated fire alarm control units**, *see* Fire alarm control units (FACU)
 - Dedicated function fire alarm system**, *see* Fire alarm systems
 - Deficiencies**, 14.2.2.3
 - Definition, 3.3.74
 - Tagging system, color-coded, I.1.4, I.1.5
 - Definitions**, Chap. 3
 - Delinquency signal**, 23.14.4, 23.14.7, 26.6.6.2, A.26.6.6.2(4)
 - Definition, 3.3.272.3
 - Design, fire alarm systems**, 10.4, A.10.4.1 to A.10.4.5, Table A.26.1, Annex B
 - Documentation, 7.3, A.7.3.1 to A.7.3.9.1
 - Emergency communications systems, 24.3.9, 24.4.2.2.1, 24.4.8.6.1, 24.5.3.2, 24.5.22.3.2, 24.6.9, 24.9, A.24.3.9, A.24.4.8.6.1, A.24.6.9
 - Performance-based, *see* Performance-based design
 - Protected premises alarm systems, 23.4.1, Annex C
 - Public emergency alarm reporting systems, 27.2.1, A.27.2.1, A.27.2.3
 - Smoke detectors, 17.7.1.1 to 17.7.1.3, A.17.7.1.1 to A.17.7.1.3
 - Design professional (definition)**, 3.3.76, A.3.3.76
 - Detection**
 - Abnormal condition, 10.8.1
 - Alarm condition, 10.8.2
 - Normal condition, 10.8.2.4
 - Pre-alarm condition, 10.8.2.1
 - Supervisory condition, 10.8.2.2
 - Trouble condition, 10.8.2.3
 - Detection devices**, 23.8.5.4, A.23.8.5.4.1
 - Detectors**, *see also* Automatic fire detectors; Carbon monoxide detection systems; Combination detectors; Heat detectors; Multi-criteria detectors; Multi-sensor detectors; Smoke detectors
 - Definition, 3.3.77
 - Design documentation, 7.3.5
 - In ducts, *see* Ducts, detectors in
 - Inspection, Table 14.3.1
 - Positive alarm sequence, use of, 23.8.1.2, A.23.8.1.2.1.1(6), A.23.8.1.2.1.2
 - Device (Class N)**, 21.2.6, 23.6.2, 23.8.2.6.3, A.12.3.6(1), A.12.3.6(5), A.23.6.2
 - Definition, 3.3.78, A.3.3.78
 - Digital alarm communicator receiver (DACR)**, 26.6.4.2.2, 26.6.4.2.5(8), 26.6.4.3, Table A.26.6.1, A.26.6.4.2.3.3, A.26.6.4.2.5(8), A.26.6.4.3.2.1, A.26.6.4.3.2.4
 - Change of status signals, 26.6.6.5(5)
 - Definition, 3.3.79
 - Equipment, 26.6.4.3.1
 - Testing, Table 14.4.3.2
 - Transmission channel, 26.6.4.3.2, A.26.6.4.3.2.1, A.26.6.4.3.2.4
 - Digital alarm communicator system (DACS)**, 26.6.4, Table A.26.6.1
 - Definition, 3.3.80
 - Power supplies, 10.6.9.2, A.10.6.9.2
 - Digital alarm communicator transmitter (DACT)**, 26.6.4.1, A.26.6.4.2.1 to A.26.6.4.2.5(8)
 - Definition, 3.3.81
 - Household signaling systems, 29.10.9.10.1 to 29.10.9.10.4
 - Inspection, Table 14.3.1
 - Power failure indication, 10.6.9.1.2
 - Testing, Table 14.4.3.2
 - Transmission channels, 26.6.4.2.4, A.26.6.4.2.4.2(6)
 - Transmission means, 26.6.4.2.4, 26.6.4.2.5, A.26.6.3, A.26.6.4.2.4.2(6), A.26.6.4.2.5(4), A.26.6.4.2.5(8)
 - Digital alarm radio receiver (DARR)**
 - Definition, 3.3.82
 - Testing, Table 14.4.3.2
 - Digital alarm radio system (DARS)**, *see also* Digital alarm radio receiver (DARR); Digital alarm radio transmitter (DART)
 - Definition, 3.3.83
 - Digital alarm radio transmitter (DART)**
 - Definition, 3.3.84
 - Inspection, Table 14.3.1
 - Testing, Table 14.4.3.2
 - Digital cellular**, A.26.6.3
 - Display**, 26.4.4.2.2.1, 26.4.4.2.2.2, 26.4.4.2.2.4, 26.4.4.3, 26.4.4.4, A.26.4.4.3
 - Definition, 3.3.85
 - Transmission requirements, 26.6.6, A.26.6.6.1 to A.26.6.6.5
 - Distinctive signals**, 10.10, 23.8.4.7, 29.10.6.7, 29.10.7.3, 29.10.7.4, A.10.10.4, A.23.8.4.7
 - Audible notification appliances, 18.4.2, A.18.4.2.1, A.18.4.2.5
 - Evacuation, 18.4.2, A.18.4.2.1, A.18.4.2.5
 - Distributed recipient mass notification system**, *see* One-way emergency communications systems

Documentation, Chap. 7, 10.20, Table A.26.1; *see also* Emergency response plan; Records

- Central station service, 26.3.3.2, 26.3.4.1 to 26.3.4.4, A.26.3.4.1, A.26.3.4.2(2)
- Completion, 7.5, A.7.5.1 to A.7.5.8; *see also* Records of completion
- Cybersecurity, J.5
- Design (layout), 7.3, 24.3.9, A.7.3.1 to A.7.3.9.1, A.24.3.9
- Emergency communications systems, 24.4.8.1, 24.5.2.2, 24.13, A.24.5.2.2
- Forms, 7.8, A.7.8.1.1 to A.7.8.2(2)
- Masked thresholds, exceeding, 18.4.7.4
- Minimum required, 7.2, A.7.1.3, A.7.2
- Personnel qualifications, 10.5.1.3, 10.5.4.4
- Public address system, 24.5.2.4, A.24.5.2.4
- Remote supervising station systems, 26.5.2, A.26.5.2.2(1)
- Of revisions, 7.5.6.6, A.7.5.6.6.3
- Sequence of operations, 7.2.1(4), 7.4.9, 7.5.5.2, A.7.4.9, A.7.5.5.2
- Shop drawings, 7.4, A.7.4.1 to A.7.4.9
- Testing, inspection, and maintenance, 7.2.1(17), 7.6, 7.7.1.1, 7.8.2, 14.2.5, 14.6, 26.3.9.2, A.7.8.2(1), A.7.8.2(2), A.14.6.1
- Test signals, 26.3.8.3.5.1
- Voice systems, intelligibility of, D.7.3

Door release service, 17.7.6.3.3, 17.7.6.6, 21.9, 23.15.3

Doors, *see also* Double doorway

- Electrically locked, 21.10, A.21.10.1, A.21.10.3
- Fire and smoke, 21.7.2, A.21.7.2

Door unlocking devices, 23.15.4, 24.11.1.2(7)

Dormitories, A.29.1.2, A.29.8.1.1; *see also* Household signaling systems

- Definition, 3.3.87

Double doorway, 17.7.6.6.4.3, 17.7.6.6.4.4, 17.7.6.6.5.1

- Definition, 3.3.88, A.3.3.88

Downlink (definition), 3.3.89

Drawings, record, *see* Record drawings

Dry pipe sprinkler systems, 17.17.2.2.2, A.17.17.2.2.2

Ducts, detectors in, 17.7.1.9, 17.7.5.4, 17.7.5.5, 17.7.6.2.1, 17.7.6.3.1, 17.7.6.3.4, 17.7.6.4.2, 17.7.6.5, 21.7.4, A.17.7.1.9, A.17.7.5.4, A.17.7.6.2, A.17.7.6.4.2

- Air sampling-type smoke detector, 17.7.4.6.4.1
- Inspection, Table 14.3.1
- Signal initiation, 23.8.5.4.6, A.23.8.5.4.6.3
- Testing, Table 14.4.3.2

Dwelling units, *see also* Household signaling systems; One- and two-family dwellings

- Definition, 3.3.90
- Detection, required, 29.8.1, A.29.8.1
- Fire alarm signals, 29.8.2.2, A.29.8.2.2
- Low-power radio (wireless) systems, 29.10.8, A.29.10.8.2.4
- Protected premises alarm systems interconnected, 23.8.3

-E-

Effective masked threshold, 18.4.7, A.18.4.7

- Definition, 3.3.91

Electrical cabinet, air sampling-type detectors for, 17.7.4.6.4.2, A.17.7.4.6.4.2

Electrical conductivity heat detectors (definition), 3.3.77.6

Electrically locked doors, 21.10, A.21.10.1, A.21.10.3

Electromechanical releasing device, Table 14.3.1, Table 14.4.3.2

- Definition, 3.3.93

Elevators, 21.2.2, 23.15.1

- Audible alarm notification appliances, 18.4.4.3
- Emergency communications systems, 24.3.7.2(5), 24.3.14.10, 24.4.8.5, 24.10, 24.11.1.2(4), A.24.10
- Fire service access, 21.5, A.21.5
- Hoistways, 21.3.3.1, 21.3.3.2, 21.3.6 to 21.3.8, 21.3.14.1(3), 21.3.14.2(3), A.21.3.7, A.21.3.8, A.21.3.14.2(3)
- Notification appliances in, 23.8.6.2, A.23.8.6.2
- Occupant evacuation, 21.6, 24.3.7.2(6), 24.4.8.5, 24.10, A.21.5, A.21.6, A.24.10
- Phase 1 emergency recall operation, 21.3, 23.8.5.1.3, A.21.3
- Shutdown, 21.4, A.21.4.1 to A.21.4.4

Ember, B.5.1.4.2, B.5.3.1.3

- Definition, 3.3.94, A.3.3.94

Ember detectors, 17.8, A.17.8.1 to A.17.8.5.4

- Definition, 3.3.77.22, A.3.3.77.22
- Spacing, 17.8.3.3, A.17.8.3.3.1 to A.17.8.3.3.6
- System design, B.5.3

Ember detector sensitivity, B.5.3.3, B.5.3.4.1

- Definition, 3.3.293

Emergency command center, *see* Emergency communications systems—emergency command center

Emergency communications control unit (ECCU), *see* Control units

Emergency communications equipment, Table 14.4.3.2, D.3.2

Emergency communications systems, Chap. 24; *see also* One-way emergency communications systems; Two-way emergency communications systems

- Ancillary functions, 24.3.5, A.24.3.5.2
- Classification, 1.3.2, 24.3.7, A.24.3.7
- Definition, 3.3.97, A.3.3.97
- Emergency control functions, interface with, Chap. 21
- Information, command, and control, 24.11, A.24.11
- Mass notification systems, 24.12, A.24.12.6.3, A.24.12.6.6
- Messages, creation and dissemination of, Annex G
- Microphone use, 24.3.2
- Nonrequired (voluntary) systems, 24.3.4, A.24.3.4
- Pathway survivability, 24.3.14, A.24.3.14.3, A.24.3.14.9
- Power supplies, 10.6, A.10.6.1 to A.10.6.10.3.4
- Public emergency alarm reporting systems, connection to, 27.8, A.27.8.1
- Record of completion, Fig. 7.8.2(b), Fig. A.7.8.2(1)(b)
- Record of inspection and testing, Figs. 7.8.2(k)
- Required systems, 24.3.3, A.24.3.3
- Stairway communication systems, 24.10, A.24.10

Emergency communications systems—combination, 24.5.1.11, 24.5.11.5, 24.5.11.6, 24.5.23, 24.5.25, A.24.5.23.1

- Definition, 3.3.98

Emergency communications systems—emergency command center, 10.14.1(3), 24.11, A.24.11

- Definition, 3.3.99, A.3.3.99
- Loudspeakers, use of, 24.3.5.2(1)
- Mass notification system, 24.5.8, A.24.5.2.2
- Secondary power system, 10.6.7.2.8
- Wide-area mass notification systems, 24.6.4

Emergency control function interface devices, 21.2.4 to 21.2.6, 21.2.8 to 21.2.10, 23.8.2.6.1, A.21.2.4

- Definition, 3.3.100, A.3.3.100

- Emergency control function interfaces**, Chap. 21, 24.5.22.2; *see also* Emergency control function interface devices
- Definition, 3.3.153.1.1, A.3.3.153.1.1
- Emergency control functions**, 14.2.7, Table 14.4.3.2, 23.3.3.1(5), 23.8.2.6.1, 23.8.5.4.4, 23.15, A.14.2.7.1
- Definition, 3.3.101, A.3.3.101
 - Interfaces, *see* Emergency control function interfaces
 - Status indicators, 10.16, A.10.16.2
- Emergency lighting, proprietary supervising station**, 26.4.3.4
- Emergency monitoring locations**, 26.2.10
- Emergency response agency (ERA)**, A.26.5.3, A.29.10.9.2
- Definition, 3.3.103, A.3.3.103
- Emergency response facility (ERF)**, 27.5.2.2.4, 27.5.4.1.6.2, 27.5.5.1.2.1, 27.5.5.1.2.3, 27.7.3.6; *see also* Emergency communications systems—emergency command center
- Definition, 3.3.104, A.3.3.104
- Emergency response plan**, 24.3.12.10, 24.3.13, A.24.3.13
- Definition, 3.3.105
 - Documentation, 7.3.8
 - Emergency command center, 24.11.1.3, 24.11.1.4, 24.11.2.1, 24.11.3, 24.11.4.2, 24.11.6, A.24.11.1.4, A.24.11.3, A.24.11.6
 - Mass notification systems
 - In-building, 24.5.1.7, 24.5.2.2, 24.5.8, 24.5.9.1, 24.5.9.3, 24.5.10, 24.5.13.1 to 24.5.13.4, 24.5.13.6, 24.5.22.1.3(5), 24.5.24.2, A.24.5.2.2, A.24.5.10, A.24.5.13.1, A.24.5.13.6(2), A.24.5.24.2
 - Wide-area, 24.6.1.2, 24.6.1.3, 24.6.5.3
- Emergency service communications center**, *see* Communications center
- Emergency voice/alarm communications**, 23.3.3.1(7), 23.9, A.24.3.10; *see also* In-building fire emergency voice/alarm communications systems (EVACS); Intelligibility
- Inspection, Table 14.3.1
 - Live voice, 14.4.11, 23.9.3, 24.3.1, 24.4.5.7, 24.5.2.2, 24.5.2.8, 24.5.13.2, 24.6.1, A.14.4.11, A.24.3.1.1, A.24.3.1.2, A.24.5.2.2
 - Localized messaging, 24.5.3.1, A.24.5.3.1
 - Manual controls, 24.4.5.6
 - Prerecorded (digital) voice and tone fire alarm systems, 14.4.11, 23.10, A.14.4.11, A.23.10.2
 - Secondary power system, 10.6.7.2.3
 - Tampering with, A.24.3.5.2
- Endpoint (Class N)**, 12.3.6, 12.3.8, A.12.3.6(1) to A.12.3.6(5), A.12.3.8
- Definition, 3.3.106, A.3.3.106
- Energy storage systems (ESS)**, 10.6.6.3.1, 10.6.6.3.2, A.10.6.4
- Testing, Table 14.4.3.2
- Enforcement**
- Requirements, 1.7
- Engine-driven generators**, 10.6.4.2, 10.6.5.1.1, 10.6.7.3.1, 10.6.7.4.1, 10.6.7.4.2, 10.6.9.1.6, 10.6.11
- Public emergency alarm reporting systems, 27.5.2.7
 - Testing, Table 14.4.3.2
- Engineering guide for automatic fire detector spacing**, Annex B
- Equivalency to code**, 1.5
- Error detection/correction**, 26.6.3.11
- Escape route**, 29.6.2, A.29.6.2
- Evacuation**, 23.8.6.1.1, 23.10.2, A.23.8.6.2, A.23.10.2, C.2.2.1.3
- Definition, 3.3.107, A.3.3.107
- Distinctive signals, 10.10.7
 - Occupant evacuation elevators, *see* Elevators
 - Partial, 24.4.8, A.24.4.8
 - Positive alarm sequence, use of, 23.8.1.2.1.1, A.23.8.1.2.1.1(6)
 - Voice, 23.9, 24.4.2, A.24.4.2.2.2
 - Elevators, 21.6.2.3.3, 21.6.2.6.1 to 21.6.2.6.4, A.21.6.2.3.3, A.21.6.2.6.3, A.21.6.2.6.4
 - In-building emergency voice/alarm communication systems, 24.4.8.2, A.24.4.8
 - Tone preceding and following, 24.3.6.3
- Evacuation signals**, 18.4.1.5, 23.8.6.2.3, 23.8.6.2.4, 24.4.1.2, 24.4.8.5.1, 29.5.1, A.18.4.1.5.1, A.29.2, A.29.5.1; *see also* Fire alarm/evacuation signal tone generator
- Control units, interconnected, 23.8.2.7.1
 - Definition, 3.3.272.4
 - Distinctive, 18.4.2, A.18.4.2.1, A.18.4.2.5
- Evaluation documentation**, 7.3.9, A.7.3.9.1
- Executive software**, 14.4.2.5
- Definition, 3.3.288.1
- Exit marking audible notification appliances**, 18.4.1.7, 18.4.8, 21.11, 23.15.5, A.18.4.8.1 to A.18.4.8.5, A.21.11
- Definition, 3.3.189.1.1
 - Inspections, Table 14.3.1
 - Testing, Table 14.4.3.2
- Exit plan**, 29.6.2, A.29.6.2
- Exits**
- Door release service, 17.7.6.3.3, 17.7.6.6, 23.15.3
 - Door unlocking devices for, 23.15.4
 - Emergency communications systems, 24.4.8.5.1, 24.4.8.5.2
 - Notification appliances, exit stair enclosures/exit passageways, 23.8.6.2, A.23.8.6.2
- Extinguishers, portable fire**, 26.4.3.3
- Electronic monitoring devices, 17.16, 23.8.4.10, A.23.8.4.10
 - Definition, 3.3.120
- Extinguishing systems**, *see also* Waterflow alarms
- Abnormal conditions, monitoring of, 23.3.3.1(3)
 - Automatic operation detectors, 17.13, 17.14, A.17.13.1, A.17.13.2, A.17.14
 - Definition, 3.3.77.3
 - Initiating devices and release service, 23.3.3.1(4), 23.8.5.4.4, 23.8.5.7, 23.8.5.10, 23.11, 26.2.1.1, A.23.11.7
 - Auxiliary fire alarm systems, Table 27.6.3.2.2.3
 - Inspection, Table 14.3.1
 - Supervisory devices, *see* Automatic extinguishing system supervisory devices
 - Testing, 14.2.6, Table 14.4.3.2
 - Special suppression systems, predischARGE notification for, 24.4.7.1, A.24.4.7.1
 - Supervisory devices and signal initiation, *see* Automatic extinguishing system supervisory devices

-F-

FACP, *see* Fire alarm control units (FACU)

False alarms, *see* Unwanted alarms

Fan, high volume low speed (HVLS), 21.8

- Definition, 3.3.139

Fan control, 21.7.2, 21.8, A.21.7.2

Federal Communications Commission, 26.6.2.4.1, 27.4.3.2, Table A.26.6.1

Fiber optic cables, *see* Cables

Field of view (definition), 3.3.113

Fire alarm and guard's tour box, combination, 17.15.3

Definition, 3.3.12.2

Fire alarm boxes, *see* Alarm boxes

Fire alarm control interface (FACI), *see* Interface

Fire alarm control units (FACU), 10.14.1(1), 21.2.5, 21.2.6, A.10.4.4, A.10.4.5, F.1

Building system information units, located with, 23.8.4.2.2.1 to 23.8.4.2.2.3, A.23.8.4.2.2.2

Dedicated function, 21.3.2, 23.8.5.5.1, 23.8.5.6.1, A.21.3.2

Definition, 3.3.115.2.1, A.3.3.115.2.1

Definition, 3.3.115, A.3.3.115

Elevators, 21.3.1, 21.3.2, 21.3.14, 21.4.5, 21.4.6, A.21.3.2, A.21.3.14.1 to A.21.3.14.2(3)

Exits, unlocking of, 21.10.3, A.21.10.3

Household signaling systems, 29.10.6.7 to 29.10.6.10, 29.14.1.3

In-building mass notification systems, 24.5.1.3, 24.5.13.7

Inspections, Table 14.3.1

Master, 10.6.8.2, 10.6.8.3, 24.10.3 to 24.10.6, 24.10.9 to 24.10.11, 26.6.2.1, A.24.10.3, A.24.10.6, A.24.10.9

Definition, 3.3.115.1

Protected premises (local), 23.8.5.4.2, 23.8.5.8.1, 26.4.2.3, 26.4.6.1.3.1, 26.6.6.1, A.26.6.6.1, C.2.2.1.5

Dedicated function, *see* subhead: Dedicated function

Definition, 3.3.115.2

Positive alarm sequence, acknowledgment of, 23.8.1.2.1.1, A.23.8.1.2.1.1(6)

Releasing service, 23.8.5.10

Definition, 3.3.115.2.2

System requirements, 23.8.2, A.23.8.2

Real-time data, transmission of, 23.12.4.1

Software and firmware control, 23.2.2, A.23.2.2.1.1 to A.23.2.2.2

Testing, 14.4.4.2, F.2.1 to F.2.5, F.2.7

Trouble signals, transmission of, 23.12.3

Fire alarm/evacuation signal tone generator, 10.19.1, Table 14.4.3.2, 23.10, 24.4.4, A.10.19.1, A.23.10.2, A.24.4.4.2, A.24.4.4.3; *see also* Alert tone

Definition, 3.3.116

Fire alarm signals, 10.11, A.10.11.1 to A.10.11.6; *see also* Alarm signals; Fire alarm/evacuation signal tone generator

Combination systems, 29.10.7.2 to 29.10.7.4, 29.10.7.6, 29.10.7.7

Definition, 3.3.272.5, A.3.3.272.5

Distinctive signals, 10.10.1, 10.10.2

Initiation, *see* Alarm boxes; Initiating devices

Keypad signal, activation of, 29.10.9.9

Presignal feature, 23.8.1.1, A.23.8.1.1

Priority of, 10.7.2, 24.5.1.7, 24.5.13.4, 29.10.7.2, 29.10.7.7, A.24.5.7

Secondary power supply, use of, 29.9.5

Fire alarm systems, *see also* Inspections; Maintenance; Testing

Ancillary functions, 24.3.5, A.24.3.5.2

Central station, *see* Central station service alarm systems

Classification, 1.3.1

Combination, 23.3.3.1(13), 23.8.2.1 to 12.8.2.8, 23.8.4, A.23.8.2.7.4, A.23.8.4.1 to A.23.8.4.10

Definition, 3.3.118.1, A.3.3.118.1

Compatibility, 10.3.3, A.10.3.3, Table A.26.1

Dedicated function systems, 23.3.3.2, A.23.3.3.2

Definition, 3.3.118.4.2

Definition, 3.3.118

Design, *see* Design, fire alarm systems

Documentation, *see* Records

Emergency control functions, interface with, Chap. 21

Fundamentals, Chap. 10

Household, *see* Household signaling systems

Initiating device, connection to, 17.4.6, A.17.4.6

Installation, 10.5.2, 29.3.2, 29.3.3, 29.6.3, 29.11, A.29.3.3, A.29.6.3, A.29.11.2.1 to A.29.11.4.7

Interfaces, *see* Interface equipment

Municipal (definition), 3.3.118.3

Notification appliances, *see* Notification appliances

Power supply, *see* Power supplies

Protected premises, *see* Protected premises (local) alarm and signaling systems

Fire command center, *see also* Emergency communications systems —emergency command center

Definition, 3.3.119, A.3.3.119

Fire doors, 21.7.2, A.21.7.2

Fire emergency voice/alarm communications system, *see* Emergency communications systems

Fire extinguisher electronic monitoring devices, 17.16, 23.8.4.10, A.23.8.4.10

Definition, 3.3.120

Firefighter's Smoke Control Station (FCFS), 21.7.7, 24.11.1.2(7)

Fire-gas detectors, Table 14.4.3.2

Definition, 3.3.77.7

Fire growth, B.2.3.1.4.1, B.2.3.2.1.2, B.2.3.2.3, B.3.2.6

Fire models

Computer, B.6

Detector response, B.5.1.6

Fire pumps

Monitoring, 23.8.5.9.1, 23.8.5.9.2

Signal initiation, 23.8.5.9

Fire service access elevators, 21.5, A.21.5

Fire service communications center, *see* Communications center

Fire wardens, 24.8.4, 24.8.13

Definition, 3.3.121

Fire warning equipment, 29.2.1, 29.3.2; *see also* Heat detectors; Household signaling systems; Smoke detectors

Definition, 3.3.122

Evacuation signals, 29.5.1, A.29.5.1

Fixed-temperature detectors, 14.4.4.5, 14.6.2.2, 17.6.2.1, 17.6.2.2.1.1, 17.6.2.3.1, 17.7.7.1.1, 29.10.4.2, A.29.10.4.2

Definition, 3.3.77.8, A.3.3.77.8

Spacing, B.3.2.4.2, B.3.2.4.3, B.3.3.1

Test methods, Table 14.4.3.2

Flame, B.5.1.4.1, B.5.2.1.1

Definition, 3.3.125

Flame detectors, 17.8, A.17.8.1 to A.17.8.5.4

Definition, 3.3.77.9, A.3.3.77.9

Spacing, 17.8.3.2, A.17.8.3.2.1 to A.17.8.3.2.6

System design, B.5.2

Video image flame detection, *see* Video image flame detection (VIFD)

Flame detector sensitivity, B.5.2.1, B.5.2.3, B.5.2.4

Definition, 3.3.127

Floor plan drawings, 7.4.5

Follow-up program, 26.3.4, A.26.3.4

Frequency

- Annual (definition), 3.3.128.5
- Definition, 3.3.128
- Monthly (definition), 3.3.128.2
- Quarterly (definition), 3.3.128.3
- Semiannual (definition), 3.3.128.4
- Weekly (definition), 3.3.128.1

Fuel, 10.6.11.6

-G-

Gas detectors, 7.3.5.4, 17.10, A.17.10.2.4

Definition, 3.3.77.10

Gateway, 23.8.2.6.2

Definition, 3.3.129

Generators, *see* Engine-driven generators

Girders, ceiling (definition), 3.3.42.2

Guard's tour

- Equipment inspection, Table 14.3.1
- Equipment testing, Table 14.4.3.2
- Supervisory service, 23.3.3.1(10), 23.13
- Suppressed signal system, 23.14, 26.6.4.3.2.5

Guard's tour box and fire alarm system, combination, 17.15.3

Definition, 3.3.12.2

Guard's tour reporting stations, 23.13

Definition, 3.3.131

Guard's tour supervisory signal, 26.3.8.3.2, 26.4.6.1.6.2

Definition, 3.3.272.6, A.3.3.272.6

Guest rooms, 29.8.1.1, A.29.1.2, A.29.8.1.1(1) to A.29.8.1.1(5)

Definition, 3.3.133

Guest suites, 29.8.1.1(5), A.29.1.2, A.29.8.1.1(5)

Definition, 3.3.134

-H-

Hearing loss

- Definition, 3.3.135, A.3.3.135
- Notification appliances for persons with, 29.5.9, 29.5.10, A.24.4.4.2, A.29.5.10.1 to A.29.5.10.2(1)
- Profound
 - Definition, 3.3.135.1
 - Notification appliances for persons with, 29.5.10.2, A.24.4.4.2, A.29.5.10.2

Heat alarms, 29.8.2.1.1, A.29.8.2.1.1

Definition, 3.3.136

Installation, 29.1.2, 29.11.4, A.29.1.2, A.29.11.4

Interconnection of, 29.11.2, A.29.11.2.1

Mechanically powered, single-station, 29.5.3, A.29.8.2.1.1

Definition, 3.3.136.1

Performance of, 29.10.4, A.29.10.4

Power supplies, household fire alarm systems, 29.9, A.29.9.4(3)

Testing, 29.10.5

Heat detectors, 10.4.5, 17.5, 17.6, A.10.4.5, A.17.5.2 to A.17.5.3.3, A.17.6.1.1 to A.17.6.3.6

Color coding, 17.6.2.2.1

Correlations, B.3.3.3, B.3.3.4

Coverage, 17.5.3, A.17.5.3

Definition, 3.3.77.11

Design documentation, 7.3.5.1

Electrical conductivity (definition), 3.3.77.6

Elevators, 21.4.1, 21.4.2, A.21.4.1, A.21.4.2

Inspection, testing, and maintenance, Table 14.3.1, Table 14.4.3.2, 14.4.4.5, 14.6.2.2

Installation, 17.4.3 to 17.4.8, 29.3.3, 29.11.4, A.17.4.6 to A.17.4.8, A.29.3.3, A.29.11.4, B.1.3.2

Location, 17.6.3, 29.3.3, 29.11.4, A.17.6.3.1.1 to A.17.6.3.6, A.29.3.3, A.29.11.4

Performance, 29.10.1, 29.10.4, A.29.10.4, B.3

Self-diagnostic, 29.10.1

Spacing, *see* Spacing

Temperature classification, 17.6.2.1, Table 17.6.2.1

Theoretical considerations, B.3.3.2

Heating, ventilating, and air conditioning (HVAC) systems, 17.7.5, 17.7.7.3.4, 17.12.9.1, 21.7, 23.15.2, A.17.7.5.4, A.21.7.2, B.4.9

High air movement areas, 17.7.7.3, Fig. 17.7.7.3.3.2

High power loudspeaker array (HPLA), 24.6.5 to 24.6.9, A.24.6.7.2, A.24.6.9

Definition, 3.3.138

Secondary power system, 10.6.7.2.6

High-rack storage, 17.7.7.2, A.17.7.6.2

High volume low speed (HVLS) fan, 21.8

Definition, 3.3.139

Hold-up alarms, 10.7.8

Hotels, A.29.1.2, A.29.8.1.1, D.3.6.1, D.3.6.3, D.3.6.7; *see also* Household signaling systems

Definition, 3.3.140

Household carbon monoxide detection systems, *see* Carbon monoxide detection systems

Household signaling systems, 17.1.5, Chap. 29; *see also* Carbon monoxide detection systems

Assumptions, 29.6, A.29.6.1 to A.29.6.3

Equipment, 29.6.3, A.29.6.3

Escape route, 29.6.2, A.29.6.2

Occupants, 29.6.1, A.29.6.1

Basic requirements, 29.3, A.29.3.3

Combination system, 29.10.7, A.29.10.7.8

Definition, 3.3.118.2

Detection, 29.8, A.29.8.1 to A.29.8.2.2; *see also* Heat detectors; Smoke detectors

Equipment

Installation, 29.11.5

Performance, 29.10, A.29.10.2 to A.29.10.9.7

Inspection, testing, and maintenance, Figs. 7.8.2(m), 14.4.6, 29.6.3, 29.13, A.14.4.6.3, A.29.6.3

Installation, 29.11, A.29.11.2.1 to A.29.11.4.7

Markings and instructions, 29.14, A.29.14.2.2(2)

Notification appliances, *see* Notification appliances

Occupant notification, required, 29.8.2, A.29.8.2.1.1, A.29.8.2.2

Optional functions, 29.12

Power supplies, 29.9, A.29.9.4(3)

Remote annunciation, 29.4

Waterflow alarm connected to, 29.10.7.8.4

Hunt groups, 26.6.4.3.2.2, 26.6.4.3.2.4, Table A.26.6.1, A.26.6.4.3.2.1, A.26.6.4.3.2.4

Definition, 3.3.142

Loading capacities, 26.6.4.3.2.4, A.26.6.4.3.2.4

-I-**Identified (as applied to equipment)**

Definition, 3.3.143, A.3.3.143

Immediately (definition), 3.3.144, A.3.3.144**Impairments,** 10.21, 14.2.2.2, 24.5.5, A.10.21

Definition, 3.3.145, A.3.3.145

In-building fire emergency voice/alarm communications systems (EVACS), 23.3.3.1(7), 23.9, 24.4, A.24.4; *see also*

Emergency voice/alarm communications; Intelligibility

Definition, 3.3.97.1.2

Elevators, occupant evacuation, 21.6.2.3.3, 21.6.2.6, 21.6.2.8, 21.6.2.9.2, A.21.6.2.3.3, A.21.6.2.6, A.21.6.2.8

Monitoring, 10.19, A.10.19.1

Voice evacuation messages, 24.4.2, A.24.4.2.2.2

In-building mass notification systems, 23.8.6, 24.5, A.23.8.6.2, A.23.8.6.3.3, A.24.5; *see also* In-building fire emergency voice/alarm communications systems (EVACS)

Autonomous control unit, 24.5.11

Definition, 3.3.97.1.3

Elevators, occupant evacuation, 21.6.2.3.3, A.21.6.2.3.3

Emergency response plan, 24.5.1.7, 24.5.10, A.24.5.10

Impairments, 24.5.5

Initiating devices, 24.5.9, A.24.5.9.2

Initiation indication, 24.5.8

Inspection, testing, and maintenance, Table 14.3.1, Table 14.4.3.2, 24.5.6

Interfaces, 24.5.10, 24.5.22, 24.5.25, 24.6.13.3, A.24.5.10, A.24.5.22.1.3, A.24.5.22.3.1

Local operating console, *see* Local operating console (LOC)

Notification appliances, 24.5.16 to 24.5.21, A.24.5.18 to A.24.5.20

Notification coverage, 24.5.3, A.24.5.3.1, A.24.5.3.4

Pathway survivability, 24.3.14.4, 24.3.14.5

Priority of signals, 24.5.1.7

Public address systems, 24.5.24, 24.5.25, A.24.5.24.2

Risk analysis for, *see* Risk analysis

Secondary power system, 10.6.7.2.9, 10.6.7.2.10

System operation, 24.5.2, A.24.5.2.1 to A.24.5.2.10

System priorities, 24.5.7, A.24.5.7

Voice messages, 24.5.1.6, 24.5.13, A.24.5.13.1, A.24.5.13.6(2)

Volume control, 24.5.15

Wide area mass notification systems, *see* One-way emergency communications systems**Initiating device circuits,** 23.4.2, 23.8.5.5.3, 23.8.5.6.3, A.23.4.2.2, A.23.8.5.5.3, A.23.8.5.6.3, F.1

Definition, 3.3.149

Faults, 10.11.7

Performance/capacities, 23.5

Testing, Table 14.4.3.2, A.14.4.3.2, F.2.1 to F.2.8, F.2.14, F.2.15

Initiating devices, 10.12.5, Chap. 17, 23.3.3.1(2), A.17.1.1; *see also* Automatic fire detectorsAutomatic extinguishing system supervisory devices, *see* Automatic extinguishing system supervisory devices

Auxiliary fire alarm systems, 27.6.3.2.2.3, 27.6.3.2.3.13

Definition, 3.3.148

Elevator recall for fire fighters' service, 21.3, A.21.3

Elevators, occupant evacuation, 21.6.2.1, 21.6.2.3, 21.6.2.5, A.21.6.2.1.1, A.21.6.2.3.1 to A.21.6.2.3.6, A.21.6.2.5

Elevator shutdown, 21.4, A.21.4.1 to A.21.4.4

Extinguishing system operation, detection of, 17.13, A.17.13.1, A.17.13.2

Fire alarm system, connection to, 17.4.6, A.17.4.6

General requirements, 17.4, A.17.4.2.3 to A.17.4.7

Household signaling systems, 29.10.6.7

In-building mass notification systems, 24.5.1.2(5), 24.5.1.6, 24.5.9, A.24.5.9.2

Inspection, Table 14.3.1

Installation, 10.4.6, 17.4, 21.3.6 to 21.3.10, A.17.4.2.3 to A.17.4.7, A.21.3.8 to A.21.3.10

Manual initiation, *see* Alarm boxes

Performance-based design, 17.3, A.17.3

Protected premises alarm systems, 23.4.2, 23.8.1.2.1.1, 23.8.5, A.23.4.2.2, A.23.8.1.2.1.1(6), A.23.8.5.1.2 to A.23.8.5.8, C.2.2.2.3

Record of inspection and testing, Figs. 7.8.2(i)

Signal disposition, 26.2.1.1

Status changes, display and recording of, 26.6.6.1, A.26.6.6.1

Supervisory signals, *see* Supervisory signal initiating devices

Testing, 14.4.2.1, 14.4.2.2, 14.4.2.4(2), Table 14.4.3.2, A.14.4.3.2

Waterflow alarms, *see* Waterflow alarms**Inspection personnel,** *see* Personnel**Inspections,** 10.3.2, 14.1 to 14.3, A.14.2.1.1 to A.14.3.1

Documentation and records, 7.2.1(17), 7.6, 7.8.2, Figs. 7.8.2(g) to (m), 14.6.2, A.7.8.2(1), A.7.8.2(2)

Emergency communications systems, 24.3.5.3, 24.5.6, 24.11.7

Frequency, 14.3.1 to 14.3.3, Table 14.3.1, 14.4.5.2, A.14.3.1

Household signaling systems, 14.4.6, A.14.4.6.3

Personnel, 10.5.3, 14.2.3.6, A.10.5.3, A.14.2.3.6

Definition, 3.3.208.1

Public emergency alarm reporting systems, 27.3.4

Smoke alarms, 14.4.5.1 to 14.4.5.4, A.14.4.5.3, A.14.4.5.4

Supervising station alarm systems, 26.5.2, 26.5.9, A.26.5.2.2(1)

Tagging, color-coded, I.1.3

Visual, 14.3.1, Table 14.3.1, 14.3.5, A.14.3.1

Installation, 1.1.1, 1.2.3, 10.3.2, 10.4, A.10.4.1 to A.10.4.5

Alarm boxes, publicly accessible, 27.6.2.1.11, A.27.6.2.1.11.2

Carbon monoxide detection systems, 17.12.1, 17.12.6, 17.12.8, 29.3.2, 29.3.3, A.17.12.1(1), A.17.12.1(2), A.29.3.3

Circuits and pathways, 12.2.3, A.12.2.3.3 to A.12.2.3.5

Cybersecurity, 11.1, A.11.1

Documentation, 7.4, 7.5.2, 7.5.8, 14.6.1.1, 24.3.9.2, A.7.4.1 to A.7.4.9, A.7.5.8

Emergency communications systems, 24.1.1, 24.2.2, 24.3.9.2, 24.5.1, 24.9, A.24.5.1

Fire alarm systems, 10.5.2, 29.3.2, 29.3.3, 29.6.3, 29.11, A.29.1.1, A.29.3.3, A.29.6.3, A.29.11.2.1 to A.29.11.4.7

Heat detectors, 29.11.4, A.29.11.4, B.1.3.2

Household signaling systems, 14.4.6.4, 29.1.1, A.29.1.1

In-building mass notification systems, 24.5.1.4

Initiating devices, 17.4.3 to 17.4.8, A.17.4.6 to A.17.4.8

Inspections, 14.2.1.1, 14.3.4, A.14.2.1.1

Notification appliances, visual, 18.5.5.8.1

Protected premises alarm systems, 23.1.1, 23.4.1, A.23.1.1

Public emergency alarm reporting systems, 27.1.1, 27.1.2, 27.2.1, A.27.2.1, A.27.2.3

Smoke detectors, *see* Smoke detectors

Supervising station alarm systems, 26.1, 26.5.1.2, A.26.1

Tagging, color-coded, I.1.1

Instructions

- Household signaling systems, 29.14, A.29.14.2.2(2)
- Manufacturer's published, *see* Manufacturer's published instructions

Integrity, Table 14.4.3.2

- Circuits, 12.6, Table 14.4.3.2, 24.5.25.2(3), A.12.6
- Combination fire alarm systems, 23.8.4.4.1(1), 23.8.4.4.2, 23.8.4.5.1
- DACT transmission means, 26.6.4.2.5(7)
- Emergency voice/alarm communications systems, 10.19, 24.3.5.2(2), A.10.19.1, A.24.3.5.2
- Fire alarm system communications to other systems, 21.2.8, 21.2.11
- Household signaling systems, 29.10.6.7, 29.10.8.1.1, 29.11.2.3
- Mass notification systems, Table 14.3.1, Table 14.4.3.2
- Power supplies, 10.6.3.4, 10.6.9, A.10.6.9.2, A.10.6.9.3
- Protected premises fire alarm systems, 23.4, 23.8.5.11.4, A.23.4.2.2

- Interconnection, 23.8.3.4

- Low-power radio (wireless) systems, 23.16.4

- Signaling paths, 23.4.3.2, 27.2.4

- Suppression systems, 23.8.5.7.2

- Tone-generating equipment, 10.19.1, A.10.19.1

- Publicly accessible auxiliary boxes, 27.6.3.2.3.15(A)

- Remote alarm receiving equipment, 27.5.3.5

- Supervising station fire alarm system transmission technology, 26.6.3.2, Table A.26.6.1

- Wireless reporting systems, 27.4.3.4, 27.5.5.3, A.27.5.5.3.3

Intelligibility, 18.4.1.6, 18.4.11, 21.2.11(1), 24.3.1, 24.4.2.2.1, 24.6.5.1, A.18.4.1.6, A.18.4.11, A.24.3.1.1, A.24.3.1.2, A.24.6.5.1(B), Annex D

- Definition, 3.3.151

Intelligible (definition), 3.3.152, A.3.3.152**Interconnections**, *see also* Paths (pathways)

- Household signaling systems, 29.8.2.1.1, 29.10.6.7, 29.10.7.6, A.29.8.2.1.1

- In-building mass notification systems, 24.5.1.1

- Metallic, 27.7, A.27.7.1.6.2, A.27.7.3

- Notification appliances, 18.1.7

- Protected premises alarm systems, 23.8.3

- Record of completion, Fig. 7.8.2(e), Fig. A.7.8.2(1)(e)

- Smoke detectors, 29.11.2, A.29.11.2.1

- Status changes, display and recording of, 26.6.6.1, A.26.6.6.1

Interface**Circuit**

- Definition, 3.3.153.1

- Emergency control function interface, *see* Emergency control function interfaces

- Signaling line, Table 14.4.3.2

- Definition, 3.3.153.1.2

- Testing, 14.4.4.4

- Emergency communications systems/public alarm reporting systems, 27.8.2

- Emergency control function, *see* Emergency control function interfaces

- Fire alarm control interface (FACI), 24.5.1.2(3), 24.5.22.1, A.24.5.22.1.3

- Definition, 3.3.153.2, A.3.3.153.2

- Software and firmware, 23.2.2.1.1, A.23.2.2.1.1

- Fire alarm/mass notification, 24.5.10, A.24.5.10

- In-building mass notification systems, 24.5.1.2(3), 24.5.1.2(6), 24.5.22, 24.5.25, A.24.5.1.2(6), A.24.5.22.1.3, A.24.5.22.3.1

- Inspection, testing, and maintenance, Figs. 7.8.2(l), 14.2.7, Table 14.4.3.2, 14.4.4.4, A.14.2.7.1

- Public address system, 24.5.25

- Wide area mass notification system, 24.6.11, 24.6.13.3

Interface equipment

- Auxiliary and public fire alarm systems, 27.6.3.2.2.2

- Inspection, Table 14.3.1

- Testing, Table 14.4.3.2, 14.4.4.4

Internet protocol, A.26.6.3**Inverters**, 27.5.2.5.1, 27.5.2.6, A.27.5.2.5.1(1), A.27.5.2.5.1(2)**In-writing (definition)**, 3.3.146, A.3.3.146**Ionization smoke detection**, B.4.7.1, B.4.7.3, B.4.8.1.2

- Definition, 3.3.285.2, A.3.3.285.2

-L-**Labeled (definition)**, 3.2.4**Leg facility**, 26.4.4.5.2

- Definition, 3.3.155

Level ceilings, 17.7.4.2.4.2, 17.7.4.7.5, A.17.7.4.2.4.2(3), A.17.7.4.2.4.2(4)

- Definition, 3.3.40.1

Life safety network, 21.2.11

- Definition, 3.3.157

Line-type detectors, 17.6.3.1.3.2, 17.6.3.5.2

- Definition, 3.3.77.12, A.3.3.77.12

Listed

- Definition, 3.2.5, A.3.2.5

- Detectors, 17.5.1, 17.6.1.4, 17.7.1.9, A.17.7.1.8, A.17.7.1.9

- Carbon monoxide, 17.12.2, 17.12.7

- Equipment, 10.3.1, 10.3.3, 23.8.4.4.1(4), A.10.3.3

- Household signaling systems, 29.3.1, A.29.6.3

- Mass notification system control units, 24.3.10, A.24.3.10

- Notification appliances, 18.3.1, 24.5.1.3, 24.5.9.2 to 24.5.9.4, A.24.5.9.2

- Speakers, 24.3.1.2, A.24.3.1.2

- Supervising station alarm systems, Table A.26.1

Living areas, 29.8.1.1(5), 29.8.1.1(6), 29.8.1.2, A.29.1.2, A.29.8.1.1(5)

- Definition, 3.3.159

Loading capacities

- Definition, 3.3.160

- Digital alarm communicator receiver (DACR) hunt groups, 26.6.4.3.2.4, A.26.6.4.3.2.4

- One-way private radio alarm systems, 26.6.5.2.6

- Supervising station communication methods, Table A.26.6.1

- System unit, 26.6.3.7

- Two-way radio frequency (RF) multiplex systems, 26.6.5.1.5, Table 26.6.5.1.5.2

Local energy type auxiliary fire alarm system, 27.6.3.2.2.1(1), A.27.6.3.2.2.1

- Definition, 3.3.229.1.1

Local operating console (LOC), 24.5.1.2(2), 24.5.1.10, 24.5.2.5, 24.5.11.3, 24.5.12, A.24.5.2.5, A.24.5.12.1

- Definition, 3.3.162, A.3.3.162

- Mounting of controls, 24.5.14, A.24.5.14

Locked doors, electrically, 21.10, A.21.10.1, A.21.10.3

Lodging or rooming houses, A.29.1.2, A.29.8.1.1; *see also* Household signaling systems

Definition, 3.3.163

Loop start telephone circuit, 26.6.4.2.1.2

Definition, 3.3.309.1

Loss of power

Definition, 3.3.164

Trouble signals, 10.6.9.1.1, 10.15.2

Loudspeakers, 18.8.1, 23.8.4.6, 24.4.2.2.1, 24.4.6, 24.4.8.5, A.18.8.1.2, A.24.4.2.2.2, A.24.4.6.1, F.1; *see also* High power loudspeaker array (HPLA)

Amplifiers, monitoring of, 10.19.1, A.10.19.1

In-building mass notification systems, 21.6.2.6.4, 24.5.4, A.21.6.2.6.4, A.24.5.4.1

Intelligibility requirements, 24.3.1.2, A.24.3.1.1, A.24.3.1.2

Tone signals, transmission of, 23.10.4

Low-power radio transmitters/transceivers, Table 14.4.3.2, 23.16, 29.9.3(5), 29.10.8, A.23.16, A.29.10.8.2.4, Fig. F.3.14(b)

Definition, 3.3.165

-M-

Maintenance, 10.3.2, 14.1, 14.2.2, 14.2.3, 14.5, A.14.2.2.1.2, A.14.2.3.1, A.14.2.3.6

Carbon monoxide detection systems, 26.2.4.1.3, 26.2.4.2.2, A.26.2.4.1.3

Central station service alarm systems, 26.3.9.2, 26.3.10, Table A.26.1

Definition, 3.3.166

Documentation and records, 7.2.1(16), 7.6, 14.2.5, 14.6.2

Emergency communications systems, 24.11.7

Engine-driven generators, 10.6.11.4

Household signaling systems, 14.4.6.2, 29.6.3, 29.13, A.29.6.3

In-building mass notification systems, 24.5.1.4, 24.5.6

Personnel, 10.5.3, 14.2.3.6, A.10.5.3, A.14.2.3.6

Proprietary supervising station alarm systems, 26.4.1.2, 26.4.7.2, 26.4.8, Table A.26.1

Protected premises fire alarm systems, Table A.26.1

Public emergency alarm reporting systems, 27.2.1, 27.3, A.27.2.1, A.27.2.3

Smoke alarms, 14.4.5, A.14.4.5.3, A.14.4.5.4

Supervising station alarm systems, 26.3.2(5), 26.3.3, 26.5.1.2, 26.5.2, 26.5.8.2, 26.5.9, 26.6.7, Table A.26.1, A.26.5.2.2(1)

Tagging, color-coded, I.1.2

Malicious alarms, 10.22(1)

Definition, 3.3.326.1

Managed facilities-based voice network (MFVN), 26.6.4.2.1, 26.6.4.2.5(3), A.26.6.4.2.1

Definition, 3.3.168, A.3.3.168

Manual alarm boxes, *see* Alarm boxes

Manual controls, status indicators for, 10.16.1

Manual operation, mass notification system, 21.6.2.1, 21.6.2.3, 21.6.2.4, 24.5.1.5, 24.5.2.7, 24.5.2.9, 24.5.9.4 to 24.5.9.6, 24.5.12.8, 24.5.13.2, A.21.6.2.1.2, A.21.6.2.3.1 to A.21.6.2.3.6, A.21.6.2.4

Manufacturer's published instructions, 7.2.1(6), 7.5.3(1), 10.3.2, 14.4.5.1, 14.4.5.6, 14.4.5.8, 14.4.5.9, 14.4.6.5, 14.4.6.6, 17.7.1.9, 17.7.7.3.3.3, 17.11.5.1.1, 29.3.2, 29.11.2.1(1), A.7.5.3(1), A.17.7.1.9

Definition, 3.3.170, A.3.3.170

Markings

Air sampling type smoke detector piping, 17.7.4.6.2.5

Carbon monoxide alarms and detectors, 29.14.1.2

Elevators, fire service access, 21.5, A.21.5

Heat detectors, 17.6.2.2

Household signaling systems, 29.14, A.29.14.2.2(2)

Notification appliances, 18.3.3.2, 18.3.3.3, A.18.3.3.2

Tagging program, color-coded, Annex I

Inspection tagging, I.1.3

Installation tagging, I.1.1

Red tags, I.1.5

Service tagging, I.1.2

Testing tagging, I.1.3

Yellow tags, I.1.4

Masked threshold, *see* Effective masked threshold

Mass notification priority mode, 10.7.3, 10.7.4, 24.5.1.7, A.10.7.3

Definition, 3.3.171, A.3.3.171

Mass notification systems, *see also* In-building mass notification systems

Control units, listing of, 24.3.10, A.24.3.10

Definition, A.3.3.172

Distributed recipient mass notification system (DRMNS), 24.7, A.24.7

Definition, 3.3.97.1.1

Emergency response plan, 24.3.12.10, 24.3.13, A.24.3.13

Inspection, Table 14.3.1

Performance-based design of, 24.12, A.24.12.6.3, A.24.12.6.6

Priority of signals, 10.7.3, 10.7.4, A.10.7.3

Record of inspection and testing, Figs. 7.8.2(j)

Risk analysis for, *see* Risk analysis

Speakers, use of, 24.4.6.2

Testing, Table 14.4.3.2

Wide area mass notification systems, *see* One-way emergency communications systems

Master boxes, *see* Alarm boxes

Master fire alarm control units, *see* Fire alarm control units (FACU)

McCulloh systems

Inspection, Table 14.3.1

Testing, Table 14.4.3.2, F.3.6

Measurement, units of, 1.6, A.1.6.5

Mechanically powered, single-station heat alarms, 29.5.3, A.29.8.2.1.1

Definition, 3.3.136.1

Metallic conductors, testing of, Table 14.4.3.2

Metallic systems and interconnections, 27.7, A.27.7.1.6.2, A.27.7.3

Microwave radio systems, private, Table 14.4.3.2

Minimum hearing distance

Definition, 3.3.176, A.3.3.176

Monitoring, Table A.26.1

Area of refuge, stairway, and elevator communication systems, 24.10.6, 24.10.7, A.24.10.6, A.24.10.7

Carbon monoxide detection systems, 10.6.7.2.17

Central station service alarm systems, 26.3.3.2

Circuits, 12.6, 24.5.4.1, 24.5.25.2(3), A.12.6, A.24.5.4.1

Combination fire alarm systems, 23.8.4.10, A.23.8.4.10

Control units, 23.8.2.7, 23.8.2.8, A.23.8.2.7.4

Emergency command center, 24.11.1.2(7), 24.11.1.7

- Emergency voice/alarm communication systems, 24.3.5.2(2), 24.4.1.1
 - Fire extinguisher electronic monitoring devices, 3.3.120, 17.16, 23.8.4.10, A.23.8.4.10
 - Fire pumps, 23.8.5.9.1, 23.8.5.9.2
 - Fire service access elevators, 21.5, A.21.5
 - Household signaling systems, 29.10.6.7, 29.10.8.1.1, 29.10.9.10.6, 29.12
 - For integrity, *see* Integrity
 - Protected premises fire alarm systems, 27.2.4
 - Supervising station fire alarm system transmission technology, Table A.26.6.1
 - Termination of, 10.21.3
 - Two-way telephone communications service, 24.8.3
 - Waterflow alarm-initiating devices, 23.8.5.5.1
 - Wireless reporting systems, 27.5.5.3
 - Motor generators**, 27.5.2.5.3, 27.5.2.5.4, 27.5.2.6; *see also* Engine-driven generators
 - Multi-criteria detectors**, 17.9.1, 17.9.3
 - Definition, 3.3.77.13, A.3.3.77.13
 - Testing, Table 14.4.3.2
 - Multiple buildings, supervising station systems**, 26.2.6
 - Multiple dwelling unit (definition)**, *see* Apartment buildings
 - Multiple emergency communications control units**, 24.11.2.6
 - Multiple-station alarm**, 17.1.5, Chap. 29
 - Carbon monoxide, 29.7, A.29.7
 - Combination systems, 29.10.7.8, A.29.10.7.8
 - Definition, 3.3.178
 - Inspection, testing, and maintenance, Figs. 7.8.2(m), Table 14.4.3.2, 14.4.5, 29.10.5, A.14.4.5.3, A.14.4.5.4
 - Interconnection, 29.11.2
 - One- and two-family dwelling units, 29.8.1.1, A.29.8.1.1(1) to A.29.8.1.1(5)
 - Visual notification appliance with, 29.9.6
 - Waterflow alarm connected to, 29.10.7.8.4
 - Multiple-station alarm devices**
 - Definition, 3.3.178
 - Listed, 29.3.1
 - Multiplexing (definition)**, 3.3.179; *see also* Active multiplex systems; Two-way emergency communications systems
 - Multi-sensor detectors**, 17.7.7.1.1, 17.9.1, 17.9.4
 - Definition, 3.3.77.14, A.3.3.77.14
 - Testing, Table 14.4.3.2
 - Municipal fire alarm (street) boxes**, *see* Alarm boxes
 - Municipal fire alarm systems**, *see* Fire alarm systems; Public emergency alarm reporting systems
- N-
- Nameplates, fire alarm systems**, 18.3.2
 - National Telecommunications and Information Administration (NTIA)**, 27.4.3.2
 - Net-centric alerting system (NCAS)**, 24.7.4, A.24.7, A.24.7.6
 - Definition, 3.3.183
 - Network architecture**, 24.7.4
 - Definition, 3.3.185
 - Networks**, *see* Wired networking; Wireless network
 - 911 public safety answering point**, 26.3.6.6.1
 - Noncontiguous property**, 26.4.2.2
 - Definition, 3.3.221.2
 - Nonrequired**
 - Definition, 3.3.187, A.3.3.187
 - Detectors, 17.5.3.3, A.17.5.3.3
 - Protected premises fire alarm systems and components, 23.3.2, A.23.3.2
 - Nonrestorable initiating device (definition)**, 3.3.148.3
 - Normal condition**, 10.3.4, 10.8.2.4, Table 14.3.1, 14.4.4.5.5, 26.2.5.2, 27.6.5.1.2, 29.9.1, 29.9.3, 29.13.2, A.29.10.9.1
 - Definition, 3.3.65.2
 - Notification appliance circuits**, 10.4.5, 10.17, 23.4.2, 23.7, 23.8.6.4, A.10.4.5, A.23.4.2.2
 - Definition, 3.3.190
 - Pathway survivability, 24.3.14, A.24.3.14.3, A.24.3.14.9
 - Supervised control circuit, 10.17
 - Definition, 3.3.300
 - Testing, Table 14.4.3.2, A.14.4.3.2, F.2.5, F.2.6, F.2.9 to F.2.13
 - Notification appliances**, Chap. 18, C.2.2.2.3, F.1; *see also* Exit marking audible notification appliances; Mass notification systems
 - Activation of, 23.3.3.1(6)
 - Positive alarm sequence, use of, 23.8.1.2.1.1, A.23.8.1.2.1.1(6)
 - Turning off activated system, 29.10.6.6
 - Audible signals, *see* Audible notification appliances
 - Carbon monoxide detection systems, 18.4.3
 - Connections, 18.3.6, A.18.3.6
 - Definition, 3.3.189
 - Documentation
 - Design documentation, 7.3.4, A.7.3.4.1
 - Minimum required, 7.2.1(10), 7.2.1(11)
 - Record of inspection and testing, Figs. 7.8.2(h)
 - In elevator cars, 23.8.6.2, A.23.8.6.2
 - In exit stair enclosures and exit passageways, 23.8.6.2, A.23.8.6.2
 - Hearing loss, for persons with, 29.5.9, 29.5.10, A.29.5.8, A.29.5.10.1 to A.29.5.10.2(1)
 - Household signaling systems, 29.5, 29.8, A.29.5.1 to A.29.5.10.2(1), A.29.8.1 to A.29.8.2.2
 - Integrity, monitoring for, 29.10.6.7
 - Optional functions, 29.12
 - Power supplies, 29.9.6
 - Testing, 29.11.2.4
 - In-building mass notification systems, 24.5.1.2(4)
 - Inspection, Table 14.3.1
 - Interconnection of appliances, 18.1.7
 - Mounting, 18.3.5
 - Nameplates, 18.3.2
 - Physical construction, 18.3.3, A.18.3.3.2
 - Power panel record of completion, Fig. 7.8.2(d)
 - Protection, 18.3.4, A.18.3.4
 - Requirements, 18.1, A.18.1
 - Secondary power supply, 10.6.7.2.1, A.10.6.7.2
 - Supervisory, 10.15.10.4, F.2.11, F.2.12
 - Supplementary visible signaling method, 18.7
 - Testing, 14.4.2.1, 14.4.2.2, Table 14.4.3.2, A.14.4.3.2, F.2.9
 - Textual appliances
 - Audible, 18.8, A.18.8.1.2
 - Visual, 18.9, A.18.9
 - Trouble, 10.15.10, A.10.15.10.7

Visual signals, *see* Visual notification appliances
Notification before testing, 14.2.4, A.14.2.4
Notification zones, *see* Zones
Nuisance alarms, 10.22(2), 14.4.4.3.3.1, 14.4.4.3.3.2,
 23.8.5.4.1(1); *see also* Alarm verification features;
 Unwanted alarms
 Definition, 3.3.326.2, A.3.3.326.2

-O-

Observation
 Definition, 3.3.193, A.3.3.193
Occupant evacuation elevators, *see* Elevators
Occupant notification, 23.8.6.1; *see also* Emergency voice/alarm
 communications; Evacuation; Mass notification systems;
 Relocation; Voice/alarm signaling service
 Documentation, 7.2.1(10)
Occupiable area (definition), 3.3.195
Occupiable (definition), 3.3.194, A.3.3.194
Octave band
 Definition, 3.3.196, A.3.3.196
 One-third octave band (definition), 3.3.196.1
Off-hook, Table 14.4.3.2, 24.8.7 to 24.8.10, 26.6.4.2.3.1, 26.6.4.2.3.2,
 Table A.26.6.1, A.26.6.4.2.3
 Definition, 3.3.197
One- and two-family dwellings, 29.8.1, A.29.8.1, A.29.8.1.1; *see also*
 Household signaling systems
One-third octave band (definition), 3.3.196.1
One-way emergency communications systems, *see also* In-building
 fire emergency voice/alarm communications systems
 (EVACS); In-building mass notification systems
 Classification as, 1.3.2(1), 24.3.7, A.24.3.7
 Definition, 3.3.97.1
 Distributed recipient mass notification system (DRMNS), 24.7,
 A.24.7.1
 Definition, 3.3.97.1.1
 Messages for, 24.3.6
 Public emergency alarm reporting systems, 27.4.3.5(1)
 Wide-area mass notification systems, 10.6.7.2.6, 10.6.7.2.8, 24.6,
 A.24.6
 Definition, 3.3.97.1.4
 External connections, 24.6.3, A.24.6.3
 Layers, 24.3.8, A.24.3.8
 Password protection, 24.6.2, A.24.6.2
 Pathway survivability, 24.3.14.6
 Risk analysis for, *see* Risk analysis
One-way private radio alarm systems, 26.6.5.2, Table A.26.6.1,
 A.26.6.5.2.2, Fig. F.3.14(d), Fig. F.3.14(e)
 Independent receivers, 26.6.5.2.1
 Maximum operating time, 26.6.5.2.2, A.26.6.5.2.2
 Supervision, 26.6.5.2.3
 System categories, 26.6.5.2.5
 Transmission channels, 26.6.5.2.4
On-hook, Table A.26.6.1
 Definition, 3.3.200
On-premises communication equipment, 26.6.3.12, A.26.6.3.12
Operating mode
 Private, 18.4.4.3, 18.4.4.4, 18.4.5, 18.6, 18.9.2.1, 23.8.6.1.1,
 A.18.4.5.1, A.18.4.5.2, A.18.6
 Definition, 3.3.201.1

Public, 18.4.4, 18.5, 18.9.2.2, 23.8.5.4.5, 23.8.6.1.1, A.18.4.4,
 A.18.5

Definition, 3.3.201.2

Operating system software, 23.2.2, A.23.2.2.1.1 to A.23.2.2.2

Operators, *see* Personnel

Other fire detectors, 17.11, A.17.11.2

Definition, 3.3.77.15

Overcurrent protection, 10.6.5.2.4, 10.6.5.5, 10.6.10.4

Ownership

Definition, 3.3.203, A.3.3.203

Inspection, testing, and maintenance, responsibility for, 14.2.3.1
 to 14.2.3.4, A.14.2.3.1

Proprietary supervising station systems, protected
 property, 26.4.2.1, 26.4.2.2

Remote supervising station alarm systems, 26.5.6.3.1 to 26.5.3.3,
 A.26.5.3.1.4, A.26.5.3.2

Owner's manuals, 7.5.3(1), 7.5.4, A.7.5.3(1)

-P-

Paging systems, 24.4.8.5, 24.11.6, A.24.11.6

Definition, 3.3.204

Partial coverage, heat/smoke detectors, 17.5.3.2, A.17.5.3.2

Paths (pathways), Chap. 12, 24.10.5, F.1; *see also* Interconnections;
 Signaling paths

Classification, 12.3, 23.4.3, A.12.3

Class N, 23.6.3, 24.3.5.4, A.23.6.3.3 to A.23.6.3.8

Combination systems (non-fire alarm equipment), 23.8.4.4.1,
 23.8.4.4.2

Definition, 3.3.205

Documentation, 7.2.1(12), A.7.2.1(12)

Shared pathway designations, 12.5, A.12.5

Pathway survivability, 12.4, 12.7, 24.3.14, A.12.4, A.12.7, A.24.3.14.3,
 A.24.3.14.9

Definition, 3.3.206

Peaked ceiling types, *see* Sloping peaked-type ceiling

Performance-based design

Documentation, 7.3.7, A.7.3.7

Fire detector spacing, Annex B

Initiating devices, 17.3, A.17.3

Mass notification systems, 24.12, A.24.12.6.3, A.24.12.6.6

Supervising station alarm systems, 26.6.3, A.26.6.3

Visual notification appliances, 18.5.5.9, A.18.5.5.7

Performance-based inspection and testing, 14.2.9, A.14.2.9

Permanent records

System information, 14.6.1, A.14.6.1

Visual record (recording), 27.5.2.2.2, 27.5.2.2.3, 27.5.2.2.5.1,
 27.5.4.4.1

Definition, 3.3.207

Personnel, 10.5, A.10.5.3 to A.10.5.6.4.2(4); *see also* Certification of
 personnel

Authorized, 7.7.2.7, 10.6.5.2.5, 18.4.2.2, 21.6.2.4.2, 23.6.3.3.3.4,
 24.4.5.2, A.14.6.1.2, A.24.4.8.3.2, A.24.5.2.1 to
 A.24.5.2.5

Definition, 3.3.24

Central station, 26.3.3, 26.3.7, Table A.26.1

Design professional (definition), 3.3.76, A.3.3.76

Emergency command center, 24.11.1.4, 24.11.1.5, A.24.11.1.4,
 A.24.11.1.5

Emergency personnel, 24.12.6.5.2

- Definition, 3.3.102
- Inspection personnel, 10.5.3, 14.2.3.6, A.10.5.3, A.14.2.3.6
 - Definition, 3.3.208.1
- One-way private radio alarm system, power failure
 - in, 26.6.5.2.3(C)
- Plans examiners and inspectors, 10.5.4
- Proprietary supervising station, 26.4.1.2, 26.4.2.1, 26.4.5, Table A.26.1
- Public emergency alarm reporting systems, 10.5.6, 27.3.7, A.10.5.6.4.2(2), A.10.5.6.4.2(4)
- Remote supervising station systems, 26.5.1.3, 26.5.5, 26.5.6.3.3.2, 26.5.6.3.3.3, Table A.26.1
- Service personnel, 10.5.3, 10.5.6.3, 14.2.3.6, A.10.5.3, A.14.2.3.6
 - Definition, 3.3.208.2
- Supervising station operators, 26.2.4.1.4, 26.2.5.2, 26.2.9, 26.3.7, 26.4.3.4.3, 26.4.4.2.1, 26.4.4.3, 26.4.4.5.1, 26.4.5, 26.4.6.1.3.2, 26.4.6.1.4, 26.4.6.1.6.1, 26.4.6.1.6.3, 26.4.6.1.6.4, 26.5.5, 26.5.7, 26.6.5.1.6.2, 26.6.6.1, 26.6.6.5, A.26.2.5.2.2, A.26.4.4.3, A.26.4.6.1.6.3(5), A.26.6.6.1, A.26.6.6.5
- System designers, 7.2.2, 10.5.1, 10.5.6.1, 24.12.2, 24.12.6.3, A.24.12.6.3
 - Definition, 3.3.208.3
- System installers, 10.5.2, 10.5.6.2
 - Definition, 3.3.208.4
- System operators
 - Definition, 3.3.310
 - Supervising station, *see* subhead: Supervising station operators
- Testing personnel, 10.5.3, 14.2.3.6, 14.2.6.1, A.10.5.3, A.14.2.3.6
 - Definition, 3.3.208.5
- Photoelectric light obscuration smoke detection (definition)**, 3.3.285.3, A.3.3.285.3; *see also* Projected beam-type detectors
- Photoelectric light-scattering smoke detection (definition)**, 3.3.285.4, A.3.3.285.4; *see also* Spot-type detectors
- Plans examiners and inspectors**, 10.5.4
- Plant (definition)**, 3.3.211
- Plenums, detectors in**, 17.7.5.2, 17.7.5.4, 17.7.5.5, 17.7.7.3.4, A.17.7.5.4
- Pneumatic rate-of-rise tubing heat detectors**, Table 14.4.3.2, 17.6.3.5.2
 - Definition, 3.3.77.16
- Poles, leads down**, 27.7.1.5
- Positive alarm sequence**, 23.8.1.2, 24.4.3, A.23.8.1.2.1.1(6), A.23.8.1.2.1.2
 - Definition, 3.3.213
- Power supplies**, 10.6, A.10.6.1 to A.10.6.10.3.4; *see also* Batteries; Loss of power
 - Central station alarm systems, 26.3.6.4
 - Common-current systems, grounded, 27.5.4.3
 - Constant-current systems, 27.5.4.2
 - Continuity, 10.6.6, A.10.6.6
 - Definition, 3.3.214
 - Emergency communications systems, 24.11.4
 - Engine-driven generators, *see* Engine-driven generators
 - Household signaling systems, 29.9, A.29.9.4(3)
 - Inspection, Table 14.3.1
 - Low-power radio (wireless) systems, 23.16.2, A.23.16.2
 - Monitoring, 10.6.3.4, 10.6.9, A.10.6.9.2, A.10.6.9.3
 - Public emergency alarm reporting systems, *see* Public emergency alarm reporting systems
 - Record of completion, Fig. 7.8.2(c)
 - Remotely located
 - Control equipment, 10.6.8, A.10.6.8.1
 - Supervising station systems, 26.5.4.2
 - Secondary (standby), *see* Secondary (standby) power supply
 - Smoke alarms, 29.9, A.29.9.4(3)
 - Testing, Table 14.4.3.2
 - Visual notification appliances, 29.9.6
- Pre-alarm condition**, 10.8.2.1
 - Definition, 3.3.65.1.2, A.3.3.65.1.2
- Pre-alarm responses**, 10.9.2
 - Definition, 3.3.261.2, A.3.3.261.2
- Pre-alarm signals**, 10.7.6
 - Definition, 3.3.272.7, A.3.3.272.7
 - Distinctive signals, 10.10.1, 10.10.8
 - Response to, 10.9.2
- Prerecorded (digital) voice and tone fire alarm systems**, 14.4.11, 23.10, 24.3.1.1, 24.5.1.7 to 24.5.1.9, 24.5.2.2, A.14.4.11, A.23.10.2, A.24.3.1.1, A.24.5.2.2
 - Localized messaging, 24.5.3.1, A.24.5.3.1
- Presignal feature**, 23.8.1.1, A.23.8.1.1
- Pressure supervisory signal-initiating devices**, 17.17.2, 21.4.3, A.17.17.2.2.2, A.21.4.3
- Pressure tanks supervisory signal-initiating devices**, 17.17.2.2.1, 17.17.3.2
- Primary batteries (dry cell)**, 23.16.2, 29.9.1, A.23.16.2
 - Definition, 3.3.215
- Primary trunk facility (definition)**, 3.3.216
- Prime contractor**, 26.3.4, A.26.3.4
 - Definition, 3.3.216
- Private operating mode**, *see* Operating mode
- Private radio systems**, Table 14.4.3.2, 26.5.4.4(3); *see also* One-way private radio alarm systems
- Profound hearing loss**, *see* Hearing loss
- Projected beam-type detectors**
 - Definition, 3.3.77.17
 - Spacing, 17.7.4.7, 17.7.6.3.3.3, A.17.7.4.7
 - Test methods, Table 14.4.3.2
- Property**
 - Contiguous property, 26.4.2.2
 - Definition, 3.3.221.1
 - Noncontiguous, 26.4.2.2
 - Definition, 3.3.221.2
- Proprietary supervising station**
 - Definition, 3.3.301.2
 - Emergency lighting, 26.4.3.4
 - Equipment, 26.4.4, A.26.4.4.1.3, A.26.4.4.3
 - Facilities, 26.4.3, A.26.4.3.1, A.26.4.3.6
 - Protected premises fire alarm systems, 23.12.1
 - Testing and maintenance, 26.4.1.2
- Proprietary supervising station alarm systems**, 26.4, A.26.4.3.1 to A.26.4.6.1.6.3(5)
 - Communications and transmission channels, 26.4.6.1.3, A.26.4.6.1.3.3
 - Definition, 3.3.302.2

- Disposition of signals, 26.4.6.1.6, A.26.4.6.1.6.3(5)
- Operations, 26.4.6, A.26.4.6.1.3.3, A.26.4.6.1.6.3(5)
- Performance criteria, Table A.26.1
- Personnel, 26.4.2.1, 26.4.5
- Record keeping and reporting, 26.4.7
- Supervisory signals, 26.4.6.1.6.3, A.26.4.6.1.6.3(5)
- Testing and maintenance, 26.4.7.2, 26.4.8
- Trouble signals, 26.4.6.1.6.4
- Proprietary supervising station service**, 26.4, A.26.4.3.1 to A.26.4.6.1.6.3(5)
 - Definition, 3.3.303.2
- Protected premises (definition)**, 3.3.225
- Protected premises (local) alarm and signaling systems**, Chap. 23
 - Alarm signal verification, *see* Alarm verification features
 - Annunciation, signal, 23.8.1.2.1.1(1)
 - Building scale, C.2
 - Combination systems, 23.3.3.1(13), 23.8.2.1 to 23.8.2.8, 23.8.4, A.23.8.2.7.4, A.23.8.4.1 to A.23.8.4.10
 - Deactivation of alarms, 10.11.8
 - Dedicated function systems, 23.3.3.2, A.23.3.3.2
 - Definition, 3.3.118.4.2
 - Definition, 3.3.118.4, A.3.3.118.4
 - Dwelling unit fire and carbon monoxide warning equipment interconnected, 23.8.3
 - Emergency control functions, *see* Emergency control functions
 - Emergency voice/alarm communications, 23.9
 - End-to-end communication time, 26.6.3.8, A.12.3.3
 - Fire service response locations, C.2.1
 - High-profile or other unusual characteristics, buildings with, Annex C
 - In-building mass notification systems, 24.5.1.1
 - Initiating device circuits, 23.5
 - Inputs, 23.8.5, A.23.8.5.1.2 to A.23.8.5.8
 - Installation and design, 23.4.1
 - Integrity, 23.4, A.23.4.2.2
 - Low-power radio system requirements, 23.16, A.23.16
 - Nonrequired systems, 23.3.2, A.23.3.2
 - Notification appliance circuits, 23.7
 - One-way private radio alarm systems, supervision of, 26.6.5.2.3(B)
 - Performance, 23.4 to 23.7, A.23.4.2.2 to A.23.6.3.8, Table A.26.1
 - Positive alarm sequence, 23.8.1.2, A.23.8.1.2.1.1(6), A.23.8.1.2.1.2
 - Power supplies, 10.6, A.10.6.1 to A.10.6.10.3.4
 - Continuity of, 10.6.6.1
 - Engine-driven generators, secondary power provided by, 10.6.11.3.1
 - Presignal feature, 23.8.1.1, A.23.8.1.1
 - Releasing system, 23.3.3.1(4)
 - Definition, 3.3.118.4.3
 - Requirements, 23.3.1, 23.3.3, 23.8, A.23.3.1, A.23.3.3.1, A.23.3.3.2, A.23.8.1.1 to A.23.8.6.3.3
 - Signaling line circuits, 23.6, 27.2.4, A.23.6.1 to A.23.6.3.8
 - Supervising station, communications with, *see* Supervising station alarm systems
 - Suppression system signal initiation, 23.8.5.7, 23.8.5.8, 23.8.5.10, A.23.8.5.8
 - System performance and design guide, Annex C
 - Trouble notification appliances, 10.15.10.7, A.10.15.10.7
 - Two-way radio frequency (RF) systems, supervision of, 26.6.5.1.6.1
- Protected premises (local) control unit**, *see* Fire alarm control units (FACU)
- Public address systems**, 24.5.24, 24.5.25, A.24.5.24.2; *see also* Loudspeakers
 - Definition, 3.3.228
- Public emergency alarm reporting systems**, 1.3.1(4), Chap. 27; *see also* Alarm boxes
 - Alarm processing equipment, 27.5, A.27.5.2.5.1(1) to A.27.5.5.3.3
 - Auxiliary systems, 27.6.3, A.27.6.3.1.2 to A.27.6.3.2.2.1
 - Cable plant, public, *see* Wired network, public fire alarm reporting system
 - Coded systems, *see* Coded
 - Definition, 3.3.229
 - Household signaling systems, 29.10.9, A.29.10.9.1 to A.29.10.9.7
 - Management/maintenance, 27.2.1, 27.3, A.27.2.1, A.27.2.3
 - Metallic systems and interconnections, 27.7, A.27.7.1.6.2, A.27.7.3
 - Personnel qualifications, 10.5.6, 27.3.7, A.10.5.6.4.2(2), A.10.5.6.4.2(4)
 - Power supplies, 10.6, 27.5.2.5, 27.5.3.7, 27.5.5.2, 27.6.6.9 to 27.6.6.13, A.10.6.1 to A.10.6.10.3.4, A.27.5.2.5.1(1), A.27.5.2.5.1(2)
 - Supervisory signals, 27.5.2.2.2
 - System integrity, 27.5.2.3
 - Telephone reporting systems
 - Series, 27.5.4.4
 - Street boxes, 27.6.5.1
 - Testing, Table 14.4.3.2, 14.4.9
 - Transmission means, 27.4.2.1.1, 27.7.2; *see also* Alarm boxes
 - Trouble signals, 27.5.2.2.2, 27.5.2.4
 - Type A, 27.5.2.1, 27.5.4.1.6.1
 - Definition, 3.3.229.2
 - Type B, 27.5.2.1, 27.5.4.1.1, 27.5.4.1.6.2, 27.5.5.1.2
 - Definition, 3.3.229.3
 - Wired network, *see* Wired network, public fire alarm reporting system
 - Wireless network, *see* Wireless network
- Public fire service communications center**, *see* Communications center
- Publicly accessible alarm boxes**, *see* Alarm boxes
- Public operating mode**, *see* Operating mode
- Public safety agency (definition)**, 3.3.231
- Public safety radio enhancement system**
 - Definition, 3.3.232
 - Two-way system, 24.9
- Public safety radio system (definition)**, 3.3.233 *see also* Low-power radio transmitters/transceivers; Radio alarm system (RAS); Two-way emergency communications systems
- Public switched telephone network**
 - Definition, 3.3.309.2 *see also* Managed facilities-based voice network (MFVN)
 - Loop start telephone circuit, 26.6.4.2.1.2
 - Definition, 3.3.309.1
- Purpose of code**, 1.2, A.1.2

Q

Qualified, 10.5, A.10.5.3 to A.10.5.6.4.2(4)

- Definition, 3.3.236, A.3.3.236
 - Inspection, testing, and maintenance personnel, *see* subhead:
 - Service personnel
 - Plans examiners and inspectors, 10.5.4
 - Public emergency alarm reporting system personnel, 10.5.6, 27.3.7, A.10.5.6.4.2(2), A.10.5.6.4.2(4)
 - Service personnel, 10.5.3, 10.5.6.3, 14.2.3.6, A.10.5.3, A.14.2.3.6
 - Supervising station operators, 10.5.5, 26.2.9, A.10.5.5.1(2)
 - System designer, 10.5.1, 10.5.6.1, 24.12.2
 - System installer, 10.5.2, 10.5.6.2
- R-**
- Radiant energy-sensing fire detectors**, 17.8, A.17.8.1 to A.17.8.5.4, B.5
- Definition, 3.3.77.18
 - Design documentation, 7.3.5.3
 - Inspection, Table 14.3.1
 - Testing, Table 14.4.3.2
- Radio alarm repeater station receiver (RARSR)**, 26.6.5.2, 27.5.5.3.5, A.26.6.5.2.2
- Definition, 3.3.238
 - Testing, Table 14.4.3.2
- Radio alarm supervising station receiver (RASSR)**, 26.6.5.2.1, 26.6.5.2.2(5), 26.6.5.2.4, 26.6.5.2.5
- Definition, 3.3.239
 - Testing, Table 14.4.3.2
- Radio alarm system (RAS)**, 26.6.2.4.3, 26.6.4.2.4; *see also* Digital alarm radio system (DARS); One-way private radio alarm systems; Two-way emergency communications systems
- Definition, 3.3.240
 - Low-power radio system requirements, *see* Low-power radio transmitters/transceivers
 - Microwave radio systems, Table 14.4.3.2
 - Proprietary supervising station, use by, 26.4.6.1.6.2(1)
 - Remote supervising station system, 26.5.4.4(3)
 - Two-way radio communications enhancement system, 24.9
- Radio alarm transmitter (RAT)**, 26.6.2.4.3, 26.6.5.2.1, 26.6.5.2.2(5), 26.6.5.2.4, 26.6.5.2.5, 26.6.5.2.7
- Definition, 3.3.241
 - Inspection, Table 14.3.1
 - Testing, Table 14.4.3.2
- Radio channels (definition)**, 3.3.50.2, A.3.3.50.2; *see also* Radio frequency
- Radio communications**
- One-way, 27.4.3.5
 - Definition, 3.3.64.1
 - Two-way, 27.4.3.5
 - Definition, 3.3.64.2
- Radio frequency**, 27.4.3.3, 27.4.3.4, A.27.4.3.3
- Definition, 3.3.244, A.3.3.244
- Raised floors**, 17.7.4.2.2, 17.7.4.5, A.17.7.4.2.2
- RARSR**, *see* Radio alarm repeater station receiver (RARSR)
- RAS**, *see* Radio alarm system (RAS)
- RASSR**, *see* Radio alarm supervising station receiver (RASSR)
- RAT**, *see* Radio alarm transmitter (RAT)
- Rate compensation detectors**, 17.6.2.1, 17.6.2.2.1.1, 17.6.2.3.1, B.3.3.10
- Definition, 3.3.77.19, A.3.3.77.19
- Testing, Table 14.4.3.2
- Rate-of-rise detectors**
- Definition, 3.3.77.20, A.3.3.77.20
 - Spacing, B.3.2.4.3, B.3.3.9
 - Testing, Table 14.4.3.2
- Rate-of-rise tubing heat detectors, pneumatic**, 12.6.11, 17.6.3.5.2
- Definition, 3.3.77.16
- Rate-of-temperature detectors**, 29.10.4.1
- Receiver/control output signals**, 23.16.5
- Record drawings**, 7.2.1(15), 7.5.3(2), 7.5.5, A.7.5.5.2, A.7.5.5.5
- Definition, 3.3.247
- Records**, 7.2.1(16), 7.7, A.7.7.1.2 to A.7.7.3.2; *see also* Documentation; Records of completion
- Guard's tour, 23.13.3
 - Household signaling systems, 29.11.6
 - Impairments, 10.21.2
 - Of inspection, testing, and maintenance, 7.2.1(17), 7.6.6, 7.8.2, Figs. 7.8.2(g) to (m), 29.11.6, A.7.8.2(1), A.7.8.2(2)
 - Maintenance of, 7.2.1(16), 7.7, A.7.7.1.2 to A.7.7.3.2
 - Nuisance alarms, 14.4.4.3.3.1
 - Permanent, 14.6.1, A.14.6.1
 - Proprietary supervising stations, 26.4.4.2.2, 26.4.4.4, 26.4.4.5, 26.4.7, Table A.26.1
 - Protected premises fire alarm systems, Table A.26.1
 - Public emergency alarm reporting system circuits, 27.3.3, 27.3.5
 - Remote supervising station systems, 26.5.1.3, 26.5.7, 26.5.8, Table A.26.1
 - Retention, 7.2.1(16), 7.7, A.7.7.1.2 to A.7.7.3.2
 - Simulated operation note, 14.6.4
 - Supervising stations, 14.6.3, 26.6.6, A.26.6.6.1 to A.26.6.6.5
 - Signals, 26.3.8.3.5.1, 26.3.9, Table A.26.1, Table A.26.6.1
 - Telephone reporting system, 27.5.4.4.1 to 27.5.4.4.6
 - Test signals, 26.3.8.3.5.1
 - Visual recording devices, *see* Visual recording devices
 - Voice recordings, 27.5.4.4.5, 27.5.4.4.6
 - Wireless reporting system, 27.5.5.1.2.3, 27.5.5.1.3
- Records of completion**, 7.2.1(13), 7.5.3(3), 7.5.6, 7.8.2, 14.2.5, 23.8.5.4.1(4), 29.11.6, A.7.5.6.1 to A.7.5.6.6.3, A.7.8.2(1), A.7.8.2(2), Table A.26.1, A.26.3.4.2(2)
- Definition, 3.3.248
- Rectifiers**, 27.5.2.5.1 to 27.5.2.5.4, 27.5.2.6, A.27.5.2.5.1(1), A.27.5.2.5.1(2)
- Redundant communication paths**, Table A.26.6.1
- References**, Chap. 2, Annex K
- Refuge, area of, emergency communications systems**, 24.3.7.2(3), 24.3.14.9, 24.10, A.24.3.14.9, A.24.10
- Release devices and service, suppression system**, *see* Extinguishing systems
- Release service, door**, *see* Door release service
- Releasing fire alarm systems**, *see* Protected premises (local) alarm and signaling systems
- Releasing service fire alarm control units**, *see* Fire alarm control units (FACU)
- Relocation**, 23.8.6.1.1, 23.10.2, A.23.10.2, C.2.2.1.3
- Alarm audible signal pattern for, 18.4.2.1, A.18.4.2.1
 - Definition, 3.3.251
 - In-building emergency voice/alarm communication systems, 24.4.8, A.24.4.8
 - Positive alarm sequence, use of, 23.8.1.2.1.1, A.23.8.1.2.1.1(6)

Remote access, 23.8.2.11, 29.10.6.9, A.23.8.2.11.1 to A.23.8.2.11.5(2)
 Definition, 3.3.252, A.3.3.252

Remote alarm or supervisory indicators, smoke alarms, 17.4.7, A.17.4.7.1

Remote annunciators, 29.4, 29.8.2.3
 Inspection, Table 14.3.1
 Testing, Table 14.4.3.2

Remote communications stations, 24.10.3 to 24.10.5, 24.10.8 to 24.10.10, A.24.10.3, A.24.10.9

Remote receiving equipment, 27.5.3, A.27.5.3

Remote supervising station alarm systems, 23.12.1, 26.5, A.26.5.2.2(1) to A.26.5.3.2
 Definition, 3.3.302.3
 Operations, 26.5.7
 Performance criteria, Table A.26.1
 Power supply, 10.6.8, A.10.6.8.1
 Presignal feature, 23.8.1.1.2(2)

Remote supervising stations, 29.10.9.10.6
 Definition, 3.3.301.3

Remote supervising station service, 26.5, A.26.5.2.2(1) to A.26.5.3.2
 Definition, 3.3.303.3
 Documentation, 7.5.10

Repeater station, Table 14.4.3.2, 29.10.8.1.1(4)
 Definition, 3.3.257

Reporting, *see* Records

Reset, 10.3.4, 10.11.6, 23.8.2.9, 23.8.2.10, 23.8.3.3, 26.6.4.2.3.3, 29.10.6.4, A.10.11.6, A.26.6.4.2.3.3
 Definition, 3.3.258

Residential board and care occupancies, 29.8.1.1(4), 29.8.1.1(6), A.29.1.2, A.29.8.1.1; *see also* Household signaling systems
 Definition, 3.3.259

Residential occupancies, A.29.8.1.1; *see also* Household signaling systems
 Definition, 3.3.260

Responses
 Alarm, 10.9.1
 Definition, 3.3.261.1, A.3.3.261.1
 Definition, 3.3.261, A.3.3.261
 Pre-alarm, 10.9.2
 Definition, 3.3.261.2, A.3.3.261.2
 Supervisory, 10.9.3
 Definition, 3.3.261.3, A.3.3.261.3
 Trouble, 10.9.4
 Definition, 3.3.261.4, A.3.3.261.4

Response time index (RTI), 17.6.1.5, 17.6.2.2.3, 21.4.1, A.17.6.1.5, A.21.4.1
 Definition, 3.3.262

Restorable initiating device (definition), 3.3.148.4

Restoration signals, 10.14.1, 10.15.1, 26.2.5, A.26.2.5.2.2
 Definition, 3.3.272.8

Retransmission, *see* Transmission means

Retroactivity of code, 1.4

Return air system, 17.7.6.4.2.2, 17.7.6.5.8, A.17.7.6.4.2.2

Risk analysis
 Definition, 3.3.264
 Documentation, 7.3.6, A.7.3.6

Emergency command center, 24.11.1.1, 24.11.2.1, 24.11.3, A.24.11.1.1, A.24.11.3

Mass notification systems, 7.3.6.4, 24.3.12, 24.12.1, 24.12.6.4, A.24.3.12
 In-building, 24.5.3.3, 24.5.4.2, 24.5.7, 24.5.10, A.24.5.7, A.24.5.10, A.24.5.22.3.1
 Wide area, 24.6.5, 24.6.9, A.24.6.5, A.24.6.9

Rooming house, *see* Lodging or rooming houses

Room temperature supervisory signal-initiating devices, 17.17.5

Runner, 26.3.8.3.1(2), 26.3.8.3.2.1(2), 26.3.8.3.3(2), 26.4.5.3 to 26.4.5.5, 26.4.6.1.6.1(2), 26.4.6.1.6.2(2)
 Definition, 3.3.265

Runner service, 26.3.2(6), Table A.26.1
 Definition, 3.3.266

-S-

Scope of code, 1.1

Secondary power source, A.21.3.2, A.21.10.3, A.23.6.3.6.2, A.23.8.5.4.6.3, A.23.10.2, A.24.5.24.2

Secondary (standby) power supply, 10.6.7, A.10.6.7.2 to A.10.6.7.3
 Amplifiers, power load of, 10.19.1.2
 Area of refuge, stairway, and elevator communication systems, 24.10.2.1, A.24.10
 Continuity of power supply, 10.6.6, A.10.6.6
 Control units, 23.8.2.6.1(2)
 Electrically locked doors, 21.10.3, A.21.10.3
 Engine driven generators, 10.6.11.3
 Failure of, 23.12.3
 Household signaling systems, 29.9.1, 29.9.3, 29.9.4(7), 29.9.9, 29.10.9.10.4
 Integrity, 10.6.9, A.10.6.9.2, A.10.6.9.3
 Supervising station alarm systems, 26.6.3.13, A.26.6.3.13.1
 Testing, Table 14.4.3.2
 Wide area mass notification system, 24.6.5.2, 24.6.10.1

Secondary trunk facility (definition), 3.3.267

Selective coverage, heat/smoke detectors, 17.5.3.2, A.17.5.3.2

Selective talk mode (definition), 3.3.313.2

Self-rescue, 29.6.1.1, A.29.1.1

Sensitivity, 14.4.4.3, 17.7.3, A.14.4.4.3, A.17.7.3

Service personnel, *see* Personnel

Servicing, *see* Maintenance

Shall (definition), 3.2.6

Shapes of ceilings (definition), 3.3.270; *see also* Sloping ceilings;
 Sloping peaked-type ceiling; Sloping shed-type ceiling;
 Smooth ceilings

Shed ceiling types, *see* Sloping shed-type ceiling

Shop drawings, 7.4, 7.5.5.1, A.7.4.1 to A.7.4.9; *see also* Record drawings
 Definition, 3.3.271, A.3.3.271

Should (definition), 3.2.7

Shutter release, *see* Door release service

Signal (definition), 3.3.272, A.3.3.272; *see also* Alarm signals

Signaling line circuit interface, *see* Interface

Signaling line circuits, 7.3.7.5, 10.3.3, 10.12.5.2, Table 14.4.3.2, 21.2.10(2), 23.4.2, 23.4.3.2, 23.8.2.6, 24.5.1.3, 27.2.4, 27.7.2, A.23.4.2.2, F.1, F.3.1
 Combined coded signals, 10.14.4
 Definition, 3.3.274
 Faults, 10.11.7

- Performance/capabilities of, 23.6, A.23.6.1 to A.23.6.3.8
- Signaling paths**, 23.8.2.6.1, 26.6.3.3 to 26.6.3.5, 27.2.4, 27.5.3.5, 27.5.3.6, 29.10.9.10.3, 29.10.9.10.5, A.23.8.2.7.4, A.26.6.3.5
- Signaling systems**, *see also* Fire alarm systems; Protected premises (local) alarm and signaling systems
 - Definition, 3.3.276
- Signaling zones**, *see* Zones
- Signal priority**, 10.7, 10.10.1, 24.4.7, 24.5.1.7, 24.5.2.8, 24.5.7, 24.5.13, 24.5.25.2(1), A.10.7.3, A.10.7.9, A.24.4.7.1, A.24.5.7, A.24.5.13.1, A.24.5.13.6(2)
 - Carbon monoxide alarm signals, 26.2.4.1.1
 - Priority supervising station alarm systems, 26.4.4.3.2
- Signal transmission sequence**, 26.6.4.2.5, A.26.6.4.2.5(4), A.26.6.4.2.5(8)
 - Definition, 3.3.273
- Single dwelling unit (definition)**, *see* One- and two-family dwellings
- Single-station alarm**, 17.1.5, Chap. 29
 - Carbon monoxide, 29.7, A.29.7
 - Combination systems, 29.10.7.8, A.29.10.7.8
 - Definition, 3.3.278
 - Inspection, testing, and maintenance, Figs. 7.8.2(m), Table 14.4.3.2, 14.4.5, 29.10.5, A.14.4.5.3, A.14.4.5.4
 - Mechanically powered heat alarms, 29.5.3, A.29.8.2.1.1
 - Definition, 3.3.136.1
 - One- and two-family dwelling units, 29.8.1.1, A.29.8.1.1(1) to A.29.8.1.1(5)
 - Visual notification appliance with, 29.9.6
- Single-station alarm devices**
 - Definition, 3.3.278
 - Listed, 29.3.1
- Site-specific software**, *see* Software
- Sleeping areas/rooms**, 29.8.1.1, 29.8.1.2, A.29.1.2, A.29.8.1.1(1) to A.29.8.1.1(5)
 - Audible appliances in, 18.4.6, A.18.4.6.1 to A.18.4.6.3(2)
 - Definition, 3.3.280, A.3.3.280
 - One- and two-family dwelling units, 29.8.1.1, A.29.8.1.1(1) to A.29.8.1.1(5)
 - Visual notification appliances located in, 18.5.5.10, A.18.5.5.10.3, A.18.5.5.10.4
 - Voice/alarm communications systems, 24.4.4.2, 24.4.4.3, A.24.4.4.2, A.24.4.4.3
- Sloping ceilings**, 29.11.3.1, 29.11.3.2, 29.11.4.2, A.29.11.3.1, A.29.11.3.2, A.29.11.4.2
 - Definition, 3.3.40.2
 - Detector location, 17.6.3.4.2
 - Detector spacing, 17.6.3.4.1, 17.7.4.2.4.3 to 17.7.4.2.4.6, 17.7.4.7.5, 29.8.1.3.2, A.17.6.3.4, A.17.7.4.2.4.3 to A.17.7.4.2.4.5
- Sloping peaked-type ceiling**, 17.6.3.4, 17.7.4.3, 29.11.3.1, 29.11.4.2, A.17.6.3.4, A.17.7.4.3, A.29.11.3.1, A.29.11.4.2
 - Definition, 3.3.40.3, A.3.3.40.3
- Sloping shed-type ceiling**, 17.6.3.4, 17.7.4.4, A.17.6.3.4, A.17.7.4.4
 - Definition, 3.3.40.4, A.3.3.40.4
- Smoke alarms**, 29.8, A.29.1.1, A.29.8.1 to A.29.8.2.2; *see also* Multiple-station alarm; Single-station alarm
 - Definition, 3.3.284
 - Inspection, 14.4.5.1 to 14.4.5.4, A.14.4.5.3, A.14.4.5.4
 - Installation, 29.1.2, 29.3.3, 29.8.1, 29.11.3, A.29.1.2, A.29.3.3, A.29.8.1, A.29.11.3
 - Interconnection of, 29.8.2.1.1, 29.11.2, A.29.8.2.1.1, A.29.11.2.1
 - Maintenance, 14.4.5, A.14.4.5.3, A.14.4.5.4
 - One- and two-family dwelling units, 29.8.1, A.29.8.1
 - Performance of, 29.10.2, 29.10.6 to 29.10.8, A.29.10.2, A.29.10.6.2 to A.29.10.8.2.4
 - Power supplies, household fire alarm systems, 29.9, A.29.9.4(3)
 - Testing, 14.4.5.1 to 14.4.5.4, 29.10.5, A.14.4.5.3, A.14.4.5.4
 - Wireless interconnections, 29.10.8.2.4, A.29.10.8.2.4
- Smoke control systems**, 17.7.5.4.1, 17.7.6, 17.12.9.2, A.17.7.6; *see also* Firefighter's Smoke Control Station (FCFS)
- Smoke detectors**, 10.4.5, 14.4.5, 17.5, 17.7, A.10.4.5, A.14.4.5.3, A.14.4.5.4, A.17.5.2 to A.17.5.3.3, A.17.7.1.1 to A.17.7.8.4, F.1
 - Air duct systems, 17.7.4.6.4.1, 17.7.5.4, 17.7.5.5, 17.7.6.2.1, 17.7.6.3.1, 17.7.6.3.4, 17.7.6.4.2, 17.7.6.5, 21.7.4, 23.8.5.4.6, A.17.7.5.4, A.17.7.6.2, A.17.7.6.4.2, A.23.8.5.4.6.3
 - Alarm verification features, *see* Alarm verification features
 - Area, 17.7.6.4.1
 - Characteristics, B.4.7
 - Cloud chamber smoke detection (definition), 3.3.285.1
 - Coverage, 17.5.3, A.17.5.3
 - Definition, 3.3.77.21
 - Design, 7.3.5.2, 17.7.1.1 to 17.7.1.3, A.17.7.1.1 to A.17.7.1.3, A.17.7.1.8
 - Door release service, 17.7.6.3.3, 17.7.6.6
 - Ducts, detectors in, *see* Ducts, detectors in
 - Elevators, 21.3, A.21.3
 - Heating, ventilating, and air conditioning (HVAC), 17.7.5, A.17.7.5.4
 - Inspection, Table 14.3.1
 - Installation, 17.4.3 to 17.4.8, 17.7.1.4 to 17.7.1.9, 17.7.4.6.3, 17.7.6.5, 21.3.6, 21.3.9, 21.3.10, 29.3.3, 29.8.1, 29.11.3, A.17.4.6 to A.17.4.8, A.17.7.1.8 to A.17.7.1.11, A.17.7.4.6.3.1, A.17.7.4.6.3.3, A.17.7.6.2, A.21.3.9, A.21.3.10, A.29.3.3, A.29.8.1
 - Integrity, monitoring for, 29.10.6.7
 - Location, 17.7.1.4, 17.7.1.9, 17.7.1.10, 17.7.4, 17.7.5.3, 17.7.6.5, 17.7.7.3.1, 17.7.7.3.2, 21.3.5, 29.3.3, 29.11.3.1 to 29.11.3.4, A.17.7.1.9, A.17.7.4.1 to A.17.7.4.7.8, A.17.7.6.2, A.21.3.5, A.29.3.3, A.29.11.3.1 to A.29.11.3.4(11)
 - Performance of, 29.10.1, 29.10.2, 29.10.6 to 29.10.8, A.29.2, A.29.10.6.2 to A.29.10.8.2.4
 - Protected premises alarm systems, 23.8.5.4, A.23.8.5.4.1, A.23.8.5.4.6.3
 - Response characteristics, B.4.2
 - Response prediction methods, B.4.8
 - Self-diagnostic, 29.10.1
 - Sensitivity, 14.4.4.3, 17.7.3, A.14.4.4.3, A.17.7.3
 - Smoke spread control, 17.7.5.4.1, 17.7.6, A.17.7.6
 - Spacing, *see* Spacing
 - Special considerations, 17.7.7, A.17.7.7.1.2 to A.17.7.7.3.3
 - Testing, Table 14.4.3.2, F.2.3 to F.2.8
 - Video image smoke detection, *see* Video image smoke detection (VISD)
- Smoke doors**, 21.7.2, A.21.7.2
- Smooth ceilings**
 - Definition, 3.3.42.3, A.3.3.42.3
 - Detector spacing, 17.7.4.2.3, 29.11.4.1, A.17.7.4.2.3.1, A.29.11.4.1

Software

- Building system information units, 23.8.4.2.2.4
- Cybersecurity, 11.1, 29.10.10.3, A.11.1, J.6.2, J.6.3
- Definition, 3.3.288
- Executive, 14.4.2.5
 - Definition, 3.3.288.1
- Protected premises fire alarm systems, 23.2.2, 23.11.5.3, A.23.2.2.1.1 to A.23.2.2.2
- Site-specific, 7.2.1(14), 7.5.3(4), 7.5.7, 14.2.5.1, 14.2.5.2, 14.6.1.2, A.14.6.1.2
 - Definition, 3.3.288.2

Solid joist construction (ceiling)

- Definition, 3.3.42.4
- Detector location, 17.6.3.2.2
- Detector spacing, 17.6.3.2.1, 17.7.4.2.4, 29.11.4.6, 29.11.4.7, A.17.7.4.2.4, A.29.11.4.7

Spacing, Annex B

- Definition, 3.3.290
- Ember/spark detectors, 17.8.3.3, A.17.8.3.3.1 to A.17.8.3.3.6
- Flame detectors, 17.8.3.2, A.17.8.3.2.1 to A.17.8.3.2.6
- Gas detectors, 17.11.5
- Heat detectors, 17.6.3, A.17.6.3.1.1 to A.17.6.3.6, B.1.3.2, B.3.3
- Smoke detectors, 17.7.4, 17.7.5.3, 17.7.7.3.3, Table 17.7.7.3.3.2, 23.8.5.4.4, A.17.7.7.3.3, B.4
- Visual notification appliances, 18.5.5.7, 18.5.5.8, A.18.5.5.5, A.18.5.5.6

Spark detectors, 17.8, A.17.8.1 to A.17.8.5.4

- Definition, 3.3.77.22, A.3.3.77.22
- Spacing, 17.8.3.3, A.17.8.3.3.1 to A.17.8.3.3.6
- System design, B.5.3

Spark detector sensitivity, B.5.3.3, B.5.3.4.1

- Definition, 3.3.293

Sparks, B.5.1.4.2, B.5.3.1.3

- Definition, 3.3.291, A.3.3.291

Special hazard equipment, testing of, Table 14.4.3.2**Spot-type detectors, 14.6.2.2, 17.7.4.2.4, 17.7.7.1, A.17.7.4.2.4.2(3), A.17.7.4.2.4.2(4)**

- Definition, 3.3.77.23, A.3.3.77.23
- Heat-sensing, 14.4.4.5, A.21.4.2
 - Location, 17.6.3.1.3.1, A.17.6.3.1.3.1
 - Marking of, 17.6.2.2.1.1, 17.6.2.2.2.3
 - Operating temperature/RTI information, 17.6.1.5, A.17.6.1.5
- Smoke, 17.7.4.2, 17.7.7.1, 17.7.7.3.3.2, A.17.7.4.2, A.17.7.7.1.2
- Testing, Table 14.4.3.2

Sprinkler systems, *see also* Extinguishing systems; Waterflow alarms

- Dry pipe, 17.17.2.2.2, A.17.17.2.2.2
- Elevators, use in, 21.3.8, 21.3.14.1(3), 21.4.1, 21.4.3, A.21.3.8, A.21.4.1 to A.21.4.3

Stair enclosures, notification appliances in, 23.8.6.2, A.23.8.6.2**Stairway communication systems, 24.3.7.2(4), 24.10, A.24.10****Stairways, door unlocking controls for, 24.11.1.2(7)****Stakeholder (definition), 3.3.295****Steam pressure supervisory signal-initiating devices, 17.17.2.2.3****Storage batteries, *see* Batteries****Stored-energy emergency power supply systems (SEPS), 10.6.4**

- Definition, 3.3.296

Stratification, 17.7.1.11, 17.7.4.7.2, A.17.7.1.11, B.4.6

- Definition, 3.3.297

Street boxes

- Alarm, *see* Alarm boxes
- Telephone, Table 26.6.3.2.2.2, 27.6.5.1

Subscriber (definition), 3.3.298**Subsequent alarms, recording and display of, 26.6.3.10****Subsidiary station, 26.4.3.5**

- Definition, 3.3.299

Supervising station, 10.14.1(4), Table A.26.1

- Alarm signal disposition, 26.2.1, A.26.2.1.2, A.26.2.1.3(3)
- Carbon monoxide signal disposition, 26.2.4, A.26.2.4.1.3
- Change of service, 26.2.7, A.26.2.7
- Definition, 3.3.301
- Documentation, 7.5.8.3(3), 7.5.8.3(4)
- End-to-end communication time, 26.6.3.8, A.12.3.3
- Household signaling systems, 29.10.9, A.29.10.9.1 to A.29.10.9.7
- Impairments, 10.21.3
- One-way private radio alarm systems, 26.6.5.2, A.26.6.5.2.2
- Power supplies
 - Continuity of, 10.6.6.2
 - Engine-driven generators, secondary power provided by, 10.6.11.3.2
- Recording and display of subsequent alarms, 26.6.3.10
- Records, 14.6.3
- Secondary power system, 10.6.7.2.5
- Signal processing equipment, 26.2.8
- Trouble signals transmitted to, 23.12.2, 23.12.3
- Two-way radio frequency multiplex systems, 26.6.5.1.2

Supervising station alarm systems, 1.3.1(3), Chap. 26; *see also*

- Remote supervising station alarm systems
- Alarm signal content, 26.2.3
- Alarm signal verification, *see* Alarm verification features
- Central station service alarm systems, *see* Central station service alarm systems
- Communications with protected premises, 26.6, Table A.26.1, Table A.26.6.1
- Digital communicator systems, *see* Digital alarm communicator system (DACS)
- Display, 26.6.6, A.26.6.6.1 to A.26.6.6.5
- Inspection, testing, and maintenance, Table 14.3.1, Table 14.4.3.2, 26.3.3, 26.5.1.2, 26.5.1.3, 26.5.2, 26.5.8.2, 26.5.9, 26.6.7, A.26.5.2.2(1)
- Performance criteria, 26.1, A.26.1
- Power failure signals, 10.6.9.3, A.10.6.9.3
- Power supplies, 10.6, A.10.6.1 to A.10.6.10.3.4
- Presignal feature, 23.8.1.1.2(2)
- Process monitoring, 23.3.3.1(11)
- Proprietary, *see* Proprietary supervising station alarm systems
- Public alarm reporting systems, *see* Public emergency alarm reporting systems
- Receivers, Table 14.3.1, Table 14.4.3.2
- Recording, 26.6.6, A.26.6.6.1 to A.26.6.6.5
- Remote programming of, 26.6.2.3
- Restoral signals, 10.14.1, 26.2.5, A.26.2.5.2.2
- Spare equipment, 26.6.3.6
- Transmitters, *see* Transmitters
- Trouble notification appliances, 10.15.10.7, A.10.15.10.7

- Supervising station service.** *see* Central station service; Proprietary supervising station service; Remote supervising station service
- Supervising system operators.** 10.5.5, A.10.5.5.1(2)
- Supervisory condition.** 10.8.2.2, 10.14.3.2, 10.15.10.4, 23.8.2.7, A.23.8.2.7.4, A.24.7
 Definition, 3.3.65.1.3, A.3.3.65.1.3
- Supervisory responses.** 10.9.3
 Definition, 3.3.261.3, A.3.3.261.3
- Supervisory service**
 Definition, 3.3.304
 Guard's tour, 23.3.3.1(10), 23.13
 One-way private radio alarm systems, 26.6.5.2.3
- Supervisory signal initiating devices.** 17.17, 23.8.5.6, 23.8.5.8 to 23.5.10, A.17.17.2.2.2, A.23.8.5.6, A.23.8.5.8, F.1, F.2.14
 Definition, 3.3.148.5
 Extinguishing systems, *see* Extinguishing systems
 Inspection, Table 14.3.1
 Testing, F.1, F.2.1.1, F.2.2
- Supervisory signals.** 10.14; *see also* Alarm signals; Guard's tour supervisory signal
 Annunciation, 10.18.2
 Central station response, 26.3.8.3.3, A.26.3.8.3.3
 Coded, 10.14.3, 10.14.4
 Combination systems, 23.8.4.10, A.23.8.4.10
 Control units, interconnected, 23.8.2.7.2
 Deactivation, 10.14.6, 10.14.7
 Definition, 3.3.272.9, A.3.3.272.9
 Distinctive signals, 10.10.1, 10.10.5, A.10.10.5
 Ducts, detectors in, 21.7.4
 Elevator recall operation initiation, 21.3.13
 Elevator shutdown, control circuits for, 21.4.5
 Household signaling systems, 29.10.9.1.3, 29.10.9.6
 Identification of, 26.6.6.2, A.26.6.6.2(4)
 Initiation, 23.8.5.8 to 23.5.10, A.23.8.5.8
 Inspections, Table 14.3.1
 Latching indication, 10.14.2
 Low-power radio (wireless) systems, A.23.16.3.1.5
 Power supervisory devices, operation of, 10.6.9.4
 Priority of, 10.7.7, 26.2.4.1.1
 Proprietary supervising station systems, 26.4.4.2.1.3, 26.4.4.2.2.3, 26.4.6.1.6.3, A.26.4.6.1.6.3(5)
 Protected premises alarm systems, 23.8.3.2
 Public emergency alarm reporting systems, 27.5.2.2.2
 Remote supervising station systems, 26.5.1.4, 26.5.3.1, 26.5.4.1.2, 26.5.6.3.2, 26.5.7, A.26.5.3.1.4, A.26.5.3.2
 Response to, 10.9.3
 Secondary power, operation on, 10.6.7.1.1, 26.6.3.13, A.26.6.3.13.1
 Supervising station alarm systems, 26.6.1.2, 26.6.3.11
 Suppression system actuation, 23.11.5.1
 Wireless, 27.5.5.1.3
- Supplementary (definition).** 3.3.307
- Supply air system.** 17.7.6.4.2.1
- Suppressed (exception reporting) signal system.** 23.14
- Suppression systems.** *see* Extinguishing systems
- Surge protection device (SPD).** Table 14.3.1
 Definition, 3.3.308
- Survivability.** 23.10.3, 24.5.4.2, C.2.2.1.4
- Suspended ceilings.** 17.7.4.5
- Switched telephone network.** 26.5.4.4(1); *see also* Public switched telephone network
- System designer.** *see* Personnel
- System installer.** *see* Personnel
- System interfaces.** *see* Interface equipment
- System operators**
 Definition, 3.3.310
 Supervising station, *see* Personnel, Supervising station operators
- System riser diagrams.** 7.2.1(2), 7.4.6
- System unit.** 26.6.5.1.1(3)
 Definition, 3.3.311
 Loading capacity, 26.6.3.7
 Spare equipment, 26.6.3.6
- T-**
- Tactile notification appliance.** 18.10, A.18.10.2
 Definition, 3.3.189.2
 In-building mass notification systems, 24.5.19
- Talk mode**
 Common talk mode, 24.8.6, 24.8.11, A.24.8.6
 Definition, 3.3.313.1
 Definition, 3.3.313
 Selective talk mode (definition), 3.3.313.2
- Telephones.** *see also* Digital alarm communicator receiver (DACR)
 Call forwarding equipment, 26.6.4.2.5(8), A.26.6.4.2.5(8)
 Digital alarm communicator systems, use of, 26.6.4.2.4, 26.6.4.2.5, 26.6.4.3.2, Table A.26.6.1, A.26.6.4.2.5(4), A.26.6.4.2.5(8), A.26.6.4.3.2.1, A.26.6.4.3.2.4
 Distributed recipient mass notification system (DRMNS), A.24.7.5
 Emergency command center, 24.11.1.2(7), 24.11.1.6
 One-way (outgoing only), 26.5.4.4(2)
 Proprietary supervising station, 26.4.6.1.6.2(1)
 Remote supervising station, 26.5.4.4
 Series reporting systems, 27.5.4.4
 Switched telephone network, 26.5.4.4(1); *see also* Public switched telephone network
 Testing, Table 14.4.3.2
 Textual appliances, 18.8.2
 Two-way telephone communications service, 10.19.2, 24.8, A.24.8
- Telephone street boxes.** Table 26.6.3.2.2.2, 27.6.5.1
- Terrorism.** A.24.7
- Testing.** 10.3.2, Chap. 14, Table A.26.1
 Automated, 14.2.8
 Central station service, 26.3.8.3.5.1, 26.3.9.2, 26.3.10
 Circuits, *see* Circuits
 Documentation and records, 7.2.1(17), 7.6, 7.8.2, 14.2.5, 14.6.2, A.7.8.2(1), A.7.8.2(2)
 Emergency communications systems, 24.3.5.3, 24.3.6.4, 24.11.7
 Engine-driven generators, 10.6.11.4
 Extinguishing system release, *see* Extinguishing systems
 Frequency, 14.4.4
 Heat alarms, 29.10.5
 Household carbon monoxide detection systems, 14.4.8, 29.10.6.11, A.14.4.8.1.3

- Household signaling systems, 14.4.6, 29.6.3, 29.10.5, 29.10.9.8, A.14.4.6.3, A.29.6.3
- In-building mass notification systems, 24.5.1.4, 24.5.6
- Methods, 14.4.3, Table 14.4.3.2, A.14.4.3, A.14.4.3.2
- Personnel, *see* Personnel
- Plan, 14.2.10, A.14.2.10
- Proprietary supervising station alarm systems, 26.4.1.2, 26.4.7.2, 26.4.8
- Protected premises alarm systems, 23.2.2.3
- Public emergency alarm reporting systems, 27.3.3, 27.3.6, 27.5.5.1.1.5, 27.5.5.1.1.7, 27.5.5.1.3, 27.5.5.3.3, 27.5.5.3.4, 27.6.3.2.3.15(B), A.27.5.5.3.3
- Remote supervising station systems, 26.5.1.2, 26.5.1.3, 26.5.2, 26.5.8.2, 26.5.9, A.26.5.2.2(1)
- Smoke alarms/detectors, 14.4.5.1 to 14.4.5.4, 29.10.5, 29.13, A.14.4.5.3, A.14.4.5.4
- Supervising station fire alarm systems, 26.2.7.2, 26.2.7.3, 26.3.2(5), Table A.26.6.1
- System acceptance, 14.4.1
 - Reacceptance testing, 14.4.2, A.14.4.2
- Tagging, color-coded, I.1.3
- Voice systems, intelligibility of, Annex D
- Testing personnel**, *see* Personnel
- Test signals**, 26.3.8.3.5, 26.6.4.2.4.2(2), 26.6.4.2.5(6), 26.6.4.3.2.8, 26.6.5.2.7.3, 27.5.2.2.2, 27.5.5.1.1.7, 27.5.5.1.3, A.26.3.8.3.5.3
- Textual audible notification appliances**, *see* Audible notification appliances
- Textual visual notification appliances**, *see* Visual notification appliances
- Throughput probability**, Table A.26.6.1
- Time Constant and Response Time Index (RTI)**, B.3.2.5
- Tone generator**, *see* Fire alarm/evacuation signal tone generator
- Total coverage, detectors**, 17.5.3.1, A.17.5.3.1
- Transmission channels**, 26.6.1.1(2), A.26.6.1
 - Definition, 3.3.50.3
 - Digital alarm communicator receiver (DACR), 26.6.4.3.2, A.26.6.4.3.2.1, A.26.6.4.3.2.4
 - Digital alarm communicator transmitter (DACT), 26.6.4.2.4, A.26.6.4.2.4.2(6)
 - One-way private radio alarm systems, 26.6.5.2.4
 - Proprietary supervising station fire alarm systems, A.26.4.6.1.3.3
 - Two-way radio frequency (RF) multiplex systems, 26.6.5.1.3
- Transmission means**, 26.2.1, A.26.2.1.2, A.26.2.1.3(3); *see also* Active multiplex systems
 - Central station alarm systems, 26.3.2(3), 26.3.3.2, 26.3.6.5, 26.3.6.6, 26.3.8.3.1(1), Table A.26.1, A.26.3.6.6, A.26.3.8.3.1(1)
 - Digital alarm communicator transmitter (DACT), 26.6.4.2.4, 26.6.4.2.5, A.26.6.4.2.4.2(6), A.26.6.4.2.5(4), A.26.6.4.2.5(8)
 - Emergency communications systems, 24.11.5
 - Household signaling systems, 29.10.9.1.1, 29.10.9.1.3, 29.10.9.8, 29.10.9.10
 - Proprietary supervising station, 26.4.6.1.3, Table A.26.1, A.26.4.6.1.3.3, A.26.4.6.1.6.3(5)
 - Public emergency alarm reporting system, Table 14.4.3.2, 27.5.5.4
 - Remote supervising station systems, 26.5.1.3, 26.5.1.6, 26.5.4.3, 26.5.4.4, 26.5.6.3.1(1), Table A.26.1
 - Supervising station alarms systems, 26.6, Table A.26.6.1, A.26.6.1 to A.26.6.6.5
 - Testing, Table 14.4.3.2, 29.10.9.8
 - Wired network, 27.4.2.1.1
- Transmitters**, 10.4.5, 26.6.1.1, A.10.4.5; *see also* Digital alarm communicator transmitter (DACT); Digital alarm radio transmitter (DART); Radio alarm transmitter (RAT)
 - Auxiliary, 27.6.3.2.3.1 to 27.6.3.2.3.3, 27.6.3.2.3.6, 27.6.3.2.3.10, 27.6.3.2.3.14
 - Definition, 3.3.318
 - Low-power radio, 23.16.2 to 23.16.4, A.23.16.2 to A.23.16.3.1.5
 - McCulloh systems, Table 14.3.1
 - Testing, Table 14.4.3.2
 - Unique identifier, 26.6.3.9, Table A.26.6.1
- Transponders (definition)**, 3.3.319
- Trouble condition**, 10.8.2.3, 23.8.2.7, A.23.8.2.7.4, A.24.7
 - Definition, 3.3.65.1.4, A.3.3.65.1.4
 - Supervising station, transmission to, 26.6.6.1, 29.10.9.10.4, A.26.6.6.1
- Trouble responses**, 10.9.4
 - Definition, 3.3.261.4, A.3.3.261.4
- Trouble signals**, 10.15, 10.19.1, 21.2.11(3), A.10.15.9, A.10.15.10.7, A.10.19.1
 - Annunciation, 10.18.2
 - Auxiliary systems, public fire alarm reporting systems, 27.6.3.2.2.1(3)
 - Carbon monoxide, 26.2.4.2
 - Central station response, 26.3.8.3.4, A.26.3.8.3.4(1)
 - Combination systems, 23.8.4.7(3)
 - Control units, interconnected, 23.8.2.7.3, 29.10.6.7
 - Deactivation of, 10.15.9, 10.15.10, A.10.15.9, A.10.15.10.7
 - Definition, 3.3.272.10, A.3.3.272.10
 - Digital alarm communicator systems, 26.6.4.2.4.2(3), 26.6.4.3.2.8, A.26.6.4.2.4.2(6)
 - Distinctive signals, 10.10.1, 10.10.6
 - Energy storage systems (ESS), failure of, 10.6.4.5
 - Household signaling systems, 29.9.5(1), 29.9.7, 29.10.1, 29.10.6.5, 29.10.7.6, 29.10.9.1.3, 29.10.9.6
 - Initiation, 23.8.5.11
 - Inspection, Table 14.3.1
 - Integral, initiating devices with, 23.8.5.3.1
 - Loss of power, 10.6.9.1.1, 10.15.2
 - Low-power radio (wireless) systems, 23.16.4.5 to 23.16.4.7, A.23.16.3.1.5
 - Priority of, 26.2.4.1.1
 - Proprietary supervising station, 26.4.4.2.1.2 to 26.4.4.2.1.4, 26.4.4.2.2.3, 26.4.4.5, 26.4.6.1.6.4
 - Public emergency alarm reporting systems, 27.5.2.2.2, 27.5.2.4
 - Remote supervising station systems, 26.5.1.4, 26.5.3.1.1 to 26.5.3.1.4, 26.5.3.2, 26.5.4.1.2, 26.5.4.1.3, 26.5.6.3.3, 26.5.7, A.26.5.3.1.4, A.26.5.3.2
 - Response to, 10.9.4
 - Secondary power; operation on, 10.6.7.1.1, 26.6.3.13, A.26.6.3.13.1
 - Signaling line circuits and pathways, 12.3.1 to 12.3.3, 12.3.6, 12.3.7, 12.6.7, 12.6.15, 23.4.2.1, A.12.3.1, A.12.3.3, A.12.3.6(1) to A.12.3.6(5)
 - Supervising station, transmission to, 23.12.2, 23.12.3, 26.6.1.2, 26.6.3.11, 26.6.6.2, A.26.6.6.2(4)
 - Supervisory signal deactivation, signal for, 10.14.7.5

- Testing, Table 14.4.3.2, F.2.1 to F.2.3
 - Wireless, 27.5.5.1.3
 - Wireless box systems, 27.5.5.3.6, 27.5.5.3.7
 - Wireless network boxes, 27.6.3.2.3.15(B), 27.6.6.11.4.2
 - Trunk facility, primary (definition)**, 3.3.216
 - Two-way emergency communications systems**, 1.3.2(2), 23.9.4
 - Area of refuge, stairway, and elevator emergency communications systems, 24.10, A.24.10
 - Classification as, 24.3.7, A.24.3.7
 - Coded retransmission, confirmation of, 26.4.6.1.3.3, A.26.4.6.1.3.3
 - Definition, 3.3.97.2
 - In-building
 - Area of refuge (area of rescue assistance) emergency communications systems, Table 14.3.1
 - Elevator emergency communications systems, 24.10, A.24.10
 - Wired systems, 24.3.7.2(1), 24.3.14.7, 24.3.14.8, 24.8, A.24.8
 - Master control station
 - Definition, 3.3.174
 - Public emergency alarm reporting systems, 27.4.3.5
 - Radio communications enhancement system, 24.3.7.2(2), 24.9
 - Radio frequency (RF) multiplex systems, 26.6.4.2.4, 26.6.5.1, Table A.26.6.1, A.26.6.4.2.4.2(6), A.26.6.5.1.4, Fig. F.3.14(c)
 - Classifications, adverse conditions, 26.6.5.1.4, A.26.6.5.1.4
 - Loading capacities, 26.6.5.1.5, Table 26.6.5.1.5.2
 - Testing, Table 14.4.3.2
 - Transmission channel, 26.6.5.1.3
 - Remote call station, 24.10.2.1 to 24.10.12, A.24.10.3, A.24.10.9
 - Definition, 3.3.253
 - Stairway communication systems, 24.10, A.24.10
 - Telephone communications service, 10.19.2
 - Two-way radio communications enhancement system**, 24.9
 - Type A public emergency alarm reporting system**, *see* Public emergency alarm reporting systems
 - Type B public emergency alarm reporting system**, *see* Public emergency alarm reporting systems
- U-**
- Underground cables**, 27.7.1.2.2, 27.7.1.3
 - Unintentional alarms**, 10.22(3)
 - Definition, 3.3.326.3
 - Unique transmitter identifier**, 26.6.3.9, Table A.26.6.1
 - Units of measurement**, 1.6, A.1.6.5
 - Unknown alarms**, 10.22(4)
 - Definition, 3.3.326.4
 - Unwanted alarms**, 10.22, A.10.22, A.29.1.1, A.29.10.6.2, B.3.2.4.2; *see also* Nuisance alarms
 - Definition, 3.3.326, A.3.3.326
 - Uplink (definition)**, 3.3.327
- V-**
- Valves, supervision of**, 17.17.1, F.2.15
 - Video alerting**, 24.5.20, A.24.5.20
 - Video image flame detection (VIFD)**, Table 14.3.1, 17.8.5, A.17.8.5.3, A.17.8.5.4
 - Definition, 3.3.328, A.3.3.328
 - Video image smoke detection (VISD)**, Table 14.3.1, 17.7.8, A.17.7.8.3, A.17.7.8.4
 - Definition, 3.3.285.5, A.3.3.285.5
 - Visible zone indication**
 - Alarm, 10.18.1
 - Supervisory and trouble annunciation, 10.18.2
 - Visual notification appliances**, 18.4.1.1, A.18.4.1.1
 - Alarm receiving equipment, public fire service communications equipment, 27.5.2.2.5, 27.5.2.4.2, 27.5.2.4.4, 27.5.2.5.7, 27.5.4.2.3, 27.5.4.3.2, 27.5.5.3.7
 - Alarm signal deactivation (silencing), 10.11.8.2, 10.12.2, 24.5.13.5, 24.5.25.1, 29.10.6.6(2), A.10.12.2
 - Appliance photometrics, 18.5.4, A.18.5.4
 - Area of coverage, 18.5.2, A.18.5.2.2
 - Area of refuge, stairway, and elevator communication systems, 24.10.12
 - Definition, 3.3.189.3
 - Distributed recipient mass notification systems, A.24.7.5
 - Documentation, 7.2.1(11)
 - Elevator cars, 23.8.6.2.2
 - Emergency voice/alarm communications, 24.4.8.6, A.24.4.8.6.1, A.24.4.8.6.3, G.2.2.1(5)
 - Exit stair enclosures and exit passageways, 23.8.6.2.1
 - Graphical, 18.9, 24.5.18, A.18.9, A.24.5.18
 - Household signaling systems, 29.5.8, 29.5.10.2, A.29.5.8, A.29.5.10.2
 - Alarm silence indication, 29.10.6.6(2)
 - Power supplies, 29.9.6
 - Trouble signals, 29.9.5(1)
 - In-building mass notification systems, 24.5.16 to 24.5.18, 24.5.20, A.24.5.18, A.24.5.20
 - Inspections, Table 14.3.1
 - Light, color, and pulse characteristics, 18.5.3, A.18.5.3.3 to A.18.5.3.7
 - Location, 18.5.5, 18.5.6, 18.9.2, A.18.5.5.1 to A.18.5.5.8.5
 - Mass notification systems, 24.5.2.10, 24.5.25.2(4), A.24.5.2.10
 - Mounting
 - Ceiling-mounted, 18.5.5.4, 18.5.5.5, Table 18.5.5.7.1(b), 18.5.5.7.6 to 18.5.5.7.8, A.18.5.5.4, A.18.5.5.5.6
 - Desktop and surface-mounted, 18.9.2.3
 - Wall-mounted appliances, 18.5.5.1, 18.5.5.2, Table 18.5.5.7.1(a), 18.5.5.7.3, 18.5.5.7.4, A.18.5.5.1
 - Nameplates, 18.3.2.1, 18.3.2.3
 - Occupant evacuation elevators, 21.6.2.6.5
 - Performance-based alternative, 18.5.5.9, A.18.5.5.7
 - Private mode, 18.6, 18.9.2.1, A.18.6
 - Public mode, 18.4.4.2, 18.5, 18.9.2.2, A.18.5
 - Remote supervising station systems, 26.5.1.4, 26.5.1.5, 26.5.4.1
 - Spacing, 18.5.5.7, 18.5.5.8, A.18.5.5.5, A.18.5.5.6
 - Supervisory signals, 10.14.1, 10.14.2.1, 10.14.6.1, 10.14.6.2
 - Supplementary visual signaling method, 18.7
 - Testing, Table 14.4.3.2, F.2.11, F.2.12
 - Textual appliances, 10.6.7.2, 18.9, 24.11.6, A.18.9, A.24.11.6
 - Definition, 3.3.189.3.1, A.3.3.189.3.1
 - In-building mass notification systems, 24.5.18, A.24.5.18
 - Wide area mass notification system, 24.6.10
 - Trouble signals, 10.15.7 to 10.15.9, Table 14.4.3.2, A.10.15.9
 - Wide-area signaling, 18.5.6
 - Zone indication**
 - Alarm, 10.18.1
 - Supervisory and trouble, 10.18.2

Visual recording devices, 27.5.2.2, 27.5.4.4.3

Permanent record (recording), 27.5.2.2.2, 27.5.2.2.3, 27.5.2.2.5, 27.5.4.4.1, 27.5.5.1.3

Definition, 3.3.207

Voice/alarm signaling service, 18.4.1.6, 24.4.4, 29.5.6, A.18.4.1.6, A.24.3.5.2, A.24.4.4.2, A.24.4.4.3, A.29.5.6; *see also* In-building fire emergency voice/alarm communications systems (EVACS)**Voice communications systems**, *see* Emergency voice/alarm communications; In-building fire emergency voice/alarm communications systems (EVACS); Voice/alarm signaling service**Voice intelligibility**, *see* Intelligibility**Voice message priority**, 24.4.7, 24.5.1.7, 24.5.2.8, 24.5.13, A.24.4.7.1, A.24.5.13.1, A.24.5.13.6(2)

Definition, 3.3.331

Voice recordings, 27.5.4.4.5, 27.5.4.4.6**-W-****Warning messages**, G.2.2**Waterflow alarms**, 17.13, A.17.13.1, A.17.13.2

Auxiliary fire alarm systems, application of, Table 27.6.3.2.2.3

Combination systems, 29.10.7.8.4

Elevator shutdown, 21.3.3.2, 21.4.3, 21.8, A.21.4.3

Inspection, Table 14.3.1

Manual fire box, available, 23.8.5.1.2, A.23.8.5.1.2

Signal initiation, 23.8.5.5, 26.2.1.1, A.23.8.5.5

Testing, Table 14.4.3.2, F.2.15

Water level supervisory signal-initiating devices, 17.17.3**Water temperature supervision**, 17.17.4**WATS (Wide Area Telephone Service) (definition)**, 3.3.332**Wavelength**, B.5.1.2**Wide area mass notification system**, *see* One-way emergency communications systems**Wide-area signaling**, 18.4.10, 18.5.6

Definition, 3.3.334

Wired IP transmissions, A.26.6.3**Wired network**, 27.5.4

Definition, 3.3.184.1

Public fire alarm reporting system, 27.4.1.1, 27.4.2, Table 26.6.3.2.2.2, 27.6.5, 27.7, A.27.7.1.6.2, A.27.7.3

Wireless control units (definition), 3.3.69.4; *see also* Radio alarm system (RAS)**Wireless devices**

Cybersecurity, 29.10.10.2

Household signaling systems, 29.10.8, A.29.10.8.2.4

Low-power radio transmitters, *see* Low-power radio transmitters/transceivers

Nonsupervised wireless interconnected alarms, 29.10.8.2, A.29.10.8.2.4

Wireless mesh networks (WMN), 26.6.5.2.8

Definition, 3.3.336, A.3.3.336

Wireless network, 27.4.1.1, 27.4.3, A.27.4.3.3

Alarm processing equipment, 27.5.5, A.27.5.5.1.1 to A.27.5.5.3.3

Alarm receiving equipment, public fire service communications center, 27.5.5, A.27.5.5.1.1 to A.27.5.5.3.3

Definition, 3.3.184.2

Publicly accessible alarm boxes, 27.6.6, A.27.6.6.2, A.27.6.6.7

Auxiliary systems, public fire alarm reporting systems, Table 27.6.3.2.2.2

Receiving networks, 27.5.5.1.1.1 to 27.5.5.1.1.5

Wireless protection system (definition), 3.3.337**Wireless repeater**, A.27.5.5.1.4

Definition, 3.3.338

Wireless signals, mass notification system, Table 14.4.3.2**Wiring**, *see also* Circuits

Diagrams, 7.4.8, Annex F

Fire alarm control unit to emergency control function relay or other appliance, 21.2.6

Household signaling systems, 29.11.5

-Z-**Zones**

Definition, 3.3.339

Notification, 18.4.2.5, 18.4.3.3, 23.8.6.1.1, 23.8.6.1.3, 23.8.6.3, 23.8.6.4.1, 23.8.6.4.2, 23.10.2, 24.4.8.2, 24.4.8.5, 24.5.2.8, 24.5.3.3, 24.5.12.10, A.18.4.2.5, A.23.8.6.3.3, A.24.3.5.2

Definition, 3.3.339.1

High power loudspeaker array, 24.6.5.1, 24.6.8, A.24.6.5.1(B)

Occupant evacuation elevator, 21.6.2.6.4, A.21.6.2.6.4

Signaling, 23.8.2.8, 23.10.2, 24.4.1.2, 24.4.5.6, 24.4.5.7, 24.4.8.6.1, 24.4.9, A.23.10.2, A.24.4.8.6.1, A.24.4.9.1

Definition, 3.3.339.2, A.3.3.339.2

Visible zone indication, 10.18.1, 10.18.2

Sequence of Events for the Standards Development Process

Once the current edition is published, a Standard is opened for Public Input.

Step 1 – Input Stage

- Input accepted from the public or other committees for consideration to develop the First Draft
- Technical Committee holds First Draft Meeting to revise Standard (23 weeks); Technical Committee(s) with Correlating Committee (10 weeks)
- Technical Committee ballots on First Draft (12 weeks); Technical Committee(s) with Correlating Committee (11 weeks)
- Correlating Committee First Draft Meeting (9 weeks)
- Correlating Committee ballots on First Draft (5 weeks)
- First Draft Report posted on the document information page

Step 2 – Comment Stage

- Public Comments accepted on First Draft (10 weeks) following posting of First Draft Report
- If Standard does not receive Public Comments and the Technical Committee chooses not to hold a Second Draft meeting, the Standard becomes a Consent Standard and is sent directly to the Standards Council for issuance (see Step 4) or
- Technical Committee holds Second Draft Meeting (21 weeks); Technical Committee(s) with Correlating Committee (7 weeks)
- Technical Committee ballots on Second Draft (11 weeks); Technical Committee(s) with Correlating Committee (10 weeks)
- Correlating Committee Second Draft Meeting (9 weeks)
- Correlating Committee ballots on Second Draft (8 weeks)
- Second Draft Report posted on the document information page

Step 3 – NFPA Technical Meeting

- Notice of Intent to Make a Motion (NITMAM) accepted (5 weeks) following the posting of Second Draft Report
- NITMAMs are reviewed and valid motions are certified by the Motions Committee for presentation at the NFPA Technical Meeting
- NFPA membership meets each June at the NFPA Technical Meeting to act on Standards with “Certified Amending Motions” (certified NITMAMs)
- Committee(s) vote on any successful amendments to the Technical Committee Reports made by the NFPA membership at the NFPA Technical Meeting

Step 4 – Council Appeals and Issuance of Standard

- Notification of intent to file an appeal to the Standards Council on Technical Meeting action must be filed within 20 days of the NFPA Technical Meeting
- Standards Council decides, based on all evidence, whether to issue the standard or to take other action

Notes:

1. Time periods are approximate; refer to published schedules for actual dates.
2. Annual revision cycle documents with certified amending motions take approximately 101 weeks to complete.
3. Fall revision cycle documents receiving certified amending motions take approximately 141 weeks to complete.

Committee Membership Classifications^{1,2,3,4}

The following classifications apply to Committee members and represent their principal interest in the activity of the Committee.

1. M *Manufacturer*: A representative of a maker or marketer of a product, assembly, or system, or portion thereof, that is affected by the standard.
2. U *User*: A representative of an entity that is subject to the provisions of the standard or that voluntarily uses the standard.
3. IM *Installer/Maintainer*: A representative of an entity that is in the business of installing or maintaining a product, assembly, or system affected by the standard.
4. L *Labor*: A labor representative or employee concerned with safety in the workplace.
5. RT *Applied Research/Testing Laboratory*: A representative of an independent testing laboratory or independent applied research organization that promulgates and/or enforces standards.
6. E *Enforcing Authority*: A representative of an agency or an organization that promulgates and/or enforces standards.
7. I *Insurance*: A representative of an insurance company, broker, agent, bureau, or inspection agency.
8. C *Consumer*: A person who is or represents the ultimate purchaser of a product, system, or service affected by the standard, but who is not included in (2).
9. SE *Special Expert*: A person not representing (1) through (8) and who has special expertise in the scope of the standard or portion thereof.

NOTE 1: “Standard” connotes code, standard, recommended practice, or guide.

NOTE 2: A representative includes an employee.

NOTE 3: While these classifications will be used by the Standards Council to achieve a balance for Technical Committees, the Standards Council may determine that new classifications of member or unique interests need representation in order to foster the best possible Committee deliberations on any project. In this connection, the Standards Council may make such appointments as it deems appropriate in the public interest, such as the classification of “Utilities” in the National Electrical Code Committee.

NOTE 4: Representatives of subsidiaries of any group are generally considered to have the same classification as the parent organization.

Submitting Public Input / Public Comment Through the Online Submission System

Following publication of the current edition of an NFPA standard, the development of the next edition begins and the standard is open for Public Input.

Submit a Public Input

NFPA accepts Public Input on documents through our online submission system at www.nfpa.org. To use the online submission system:

- Choose a document from the List of NFPA codes & standards or filter by Development Stage for “codes accepting public input.”
- Once you are on the document page, select the “Next Edition” tab.
- Choose the link “The next edition of this standard is now open for Public Input.” You will be asked to sign in or create a free online account with NFPA before using this system.
- Follow the online instructions to submit your Public Input (see www.nfpa.org/publicinput for detailed instructions).
- Once a Public Input is saved or submitted in the system, it can be located on the “My Profile” page by selecting the “My Public Inputs/Comments/NITMAMs” section.

Submit a Public Comment

Once the First Draft Report becomes available there is a Public Comment period. Any objections or further related changes to the content of the First Draft must be submitted at the Comment Stage. To submit a Public Comment follow the same steps as previously explained for the submission of Public Input.

Other Resources Available on the Document Information Pages

Header: View document title and scope, access to our codes and standards or NFCSS subscription, and sign up to receive email alerts.

 Current & Prior Editions	Research current and previous edition information.
 Next Edition	Follow the committee’s progress in the processing of a standard in its next revision cycle.
 Technical Committee	View current committee rosters or apply to a committee.
 Ask a Technical Question	For members, officials, and AHJs to submit standards questions to NFPA staff. Our Technical Questions Service provides a convenient way to receive timely and consistent technical assistance when you need to know more about NFPA standards relevant to your work.
 News	Provides links to available articles and research and statistical reports related to our standards.
 Purchase Products & Training	Discover and purchase the latest products and training.
 Related Products	View related publications, training, and other resources available for purchase.

Information on the NFPA Standards Development Process

I. Applicable Regulations. The primary rules governing the processing of NFPA standards (codes, standards, recommended practices, and guides) are the NFPA *Regulations Governing the Development of NFPA Standards (Regs)*. Other applicable rules include NFPA *Bylaws*, NFPA *Technical Meeting Convention Rules*, NFPA *Guide for the Conduct of Participants in the NFPA Standards Development Process*, and the NFPA *Regulations Governing Petitions to the Board of Directors from Decisions of the Standards Council*. Most of these rules and regulations are contained in the *NFPA Standards Directory*. For copies of the *Directory*, contact Codes and Standards Administration at NFPA headquarters; all these documents are also available on the NFPA website at “www.nfpa.org/regs.”

The following is general information on the NFPA process. All participants, however, should refer to the actual rules and regulations for a full understanding of this process and for the criteria that govern participation.

II. Technical Committee Report. The Technical Committee Report is defined as “the Report of the responsible Committee(s), in accordance with the Regulations, in preparation of a new or revised NFPA Standard.” The Technical Committee Report is in two parts and consists of the First Draft Report and the Second Draft Report. (See *Regs* at Section 1.4.)

III. Step 1: First Draft Report. The First Draft Report is defined as “Part one of the Technical Committee Report, which documents the Input Stage.” The First Draft Report consists of the First Draft, Public Input, Committee Input, Committee and Correlating Committee Statements, Correlating Notes, and Ballot Statements. (See *Regs* at 4.2.5.2 and Section 4.3.) Any objection to an action in the First Draft Report must be raised through the filing of an appropriate Comment for consideration in the Second Draft Report or the objection will be considered resolved. [See *Regs* at 4.3.1(b).]

IV. Step 2: Second Draft Report. The Second Draft Report is defined as “Part two of the Technical Committee Report, which documents the Comment Stage.” The Second Draft Report consists of the Second Draft, Public Comments with corresponding Committee Actions and Committee Statements, Correlating Notes and their respective Committee Statements, Committee Comments, Correlating Revisions, and Ballot Statements. (See *Regs* at 4.2.5.2 and Section 4.4.) The First Draft Report and the Second Draft Report together constitute the Technical Committee Report. Any outstanding objection following the Second Draft Report must be raised through an appropriate Amending Motion at the NFPA Technical Meeting or the objection will be considered resolved. [See *Regs* at 4.4.1(b).]

V. Step 3a: Action at NFPA Technical Meeting. Following the publication of the Second Draft Report, there is a period during which those wishing to make proper Amending Motions on the Technical Committee Reports must signal their intention by submitting a Notice of Intent to Make a Motion (NITMAM). (See *Regs* at 4.5.2.) Standards that receive notice of proper Amending Motions (Certified Amending Motions) will be presented for action at the annual June NFPA Technical Meeting. At the meeting, the NFPA membership can consider and act on these Certified Amending Motions as well as Follow-up Amending Motions, that is, motions that become necessary as a result of a previous successful Amending Motion. (See 4.5.3.2 through 4.5.3.6 and Table 1, Columns 1-3 of *Regs* for a summary of the available Amending Motions and who may make them.) Any outstanding objection following action at an NFPA Technical Meeting (and any further Technical Committee consideration following successful Amending Motions, see *Regs* at 4.5.3.7 through 4.6.5) must be raised through an appeal to the Standards Council or it will be considered to be resolved.

VI. Step 3b: Documents Forwarded Directly to the Council. Where no NITMAM is received and certified in accordance with the *Technical Meeting Convention Rules*, the standard is forwarded directly to the Standards Council for action on issuance. Objections are deemed to be resolved for these documents. (See *Regs* at 4.5.2.5.)

VII. Step 4a: Council Appeals. Anyone can appeal to the Standards Council concerning procedural or substantive matters related to the development, content, or issuance of any document of the NFPA or on matters within the purview of the authority of the Council, as established by the *Bylaws* and as determined by the Board of Directors. Such appeals must be in written form and filed with the Secretary of the Standards Council (see *Regs* at Section 1.6). Time constraints for filing an appeal must be in accordance with 1.6.2 of the *Regs*. Objections are deemed to be resolved if not pursued at this level.

VIII. Step 4b: Document Issuance. The Standards Council is the issuer of all documents (see Article 8 of *Bylaws*). The Council acts on the issuance of a document presented for action at an NFPA Technical Meeting within 75 days from the date of the recommendation from the NFPA Technical Meeting, unless this period is extended by the Council (see *Regs* at 4.7.2). For documents forwarded directly to the Standards Council, the Council acts on the issuance of the document at its next scheduled meeting, or at such other meeting as the Council may determine (see *Regs* at 4.5.2.5 and 4.7.4).

IX. Petitions to the Board of Directors. The Standards Council has been delegated the responsibility for the administration of the codes and standards development process and the issuance of documents. However, where extraordinary circumstances requiring the intervention of the Board of Directors exist, the Board of Directors may take any action necessary to fulfill its obligations to preserve the integrity of the codes and standards development process and to protect the interests of the NFPA. The rules for petitioning the Board of Directors can be found in the *Regulations Governing Petitions to the Board of Directors from Decisions of the Standards Council* and in Section 1.7 of the *Regs*.

X. For More Information. The program for the NFPA Technical Meeting (as well as the NFPA website as information becomes available) should be consulted for the date on which each report scheduled for consideration at the meeting will be presented. To view the First Draft Report and Second Draft Report as well as information on NFPA rules and for up-to-date information on schedules and deadlines for processing NFPA documents, check the NFPA website (www.nfpa.org/docinfo) or contact NFPA Codes & Standards Administration at (617) 984-7246.

**DIGITAL ACCESS TO
NFPA CODES AND
STANDARDS.**
AT WORK. AND AT
YOUR FINGERTIPS.

**SUBSCRIPTIONS STARTING
AS LOW AS \$9.99/MONTH.**

Presenting NFPA LiNK™: NFPA LiNK™ provides digital access to codes and standards. Find, bookmark, organize, and share knowledge anytime and anywhere. Transform the speed, accuracy, and efficiency of your work.

Learn more at [NFPA.org/LiNK](https://www.nfpa.org/LiNK)

