

C:\Users\Anthony\McNEIL - CROUPE\Documents\Server\Current Projects\18448\18448_STRUCT [09-06-18].dwg Anthony Oct 19, 2018 - 9:55am

STRUCTURAL STEEL (IBC 1705.2.1, 1705.11.1 & 1705.12.2)

Item

Detailed Instructions and Frequencies

PRIOR TO WELDING (TABLE N5.4-1, AISC 360-10):			
Verify welding procedures (WPS) and consumable certificates	☒ Continuous	☐ Periodic	
Material identification	☐ Continuous	☒ Periodic	Verify type and grade of material.
Welder identification	☐ Continuous	☒ Periodic	A system shall be maintained by which a welder who has welded a joint or member can be identified.
Fit-up groove welds	☐ Continuous	☒ Periodic	Verify joint preparation, dimensions, cleanliness, tacking, and backing.
Access holes	☐ Continuous	☒ Periodic	Verify configuration and finish.
Fit-up fillet welds	☐ Continuous	☒ Periodic	Verify alignment, gaps at root, cleanliness of steel surfaces, and tack weld quality and location.
DURING WELDING (TABLE N5.4-2, AISC 360-10):			
Use of qualified welders	☐ Continuous	☒ Periodic	Verify that welders are appropriately qualified.
Control and handling of welding consumables	☐ Continuous	☒ Periodic	Verify packaging and exposure control.
Cracked tack welds	☐ Continuous	☒ Periodic	Verify that welding does not occur over cracked tack welds.
Environmental conditions	☐ Continuous	☒ Periodic	Verify win speed is within limits as well as precipitation and temperature.
WPS followed	☐ Continuous	☒ Periodic	Verify items such as settings on welding equipment, travel speed, welding materials, shielding gas type/flow rate, preheat applied, interpass temperature maintained, and proper position.
Welding techniques	☐ Continuous	☒ Periodic	Verify interpass and final cleaning, each pass is within profile limitations, and quality of each pass.
AFTER WELDING (TABLE N5.4-3, AISC 360-10):			
Welds cleaned	☐ Continuous	☒ Periodic	Verify that welds have been properly cleaned.
Size, length, and location of welds	☒ Continuous	☐ Periodic	
Welds meet visual acceptance criteria	☒ Continuous	☐ Periodic	
Arc strikes	☒ Continuous	☐ Periodic	
Reinforcement	☒ Continuous	☐ Periodic	
Backing & weld tabs removed	☒ Continuous	☐ Periodic	
Repair activities	☒ Continuous	☐ Periodic	
Document acceptance or rejection of welded joint/member	☒ Continuous	☐ Periodic	
NONDESTRUCTIVE TESTING (TABLE N5.5, AISC 360-10):			
CJP welds (Risk Cat. II)	☐ Continuous	☒ Periodic	Ultrasonic testing shall be performed on 10% of CJP groove welds in butt, T- and corner joints subject to transversely applied tension loading in materials 5/16-inch thick or greater. Testing rate must be increased if >5% of welds tested have unacceptable defects. A reduction in the rate of ultrasonic testing is allowed per Section N5.5e.
Size, length, and location of welds	☒ Continuous	☐ Periodic	
Welds meet visual acceptance criteria	☒ Continuous	☐ Periodic	
Arc strikes	☒ Continuous	☐ Periodic	
PRIOR TO BOLTING (TABLE N5.6-1, AISC 360-10):			
> Not required if only snug-tight joints are specified [per Section N5.6(1) of AISC 360-10]			
Certifications of fasteners	☒ Continuous	☐ Periodic	
Fasteners marked	☐ Continuous	☒ Periodic	Verify that fasteners have been marked in accordance with ASTM requirements.
Proper fasteners for joint	☐ Continuous	☒ Periodic	Verify grade, type, and bolt length if threads are excluded from the shear plane.
Proper bolting procedure	☐ Continuous	☒ Periodic	Verify proper procedure is used for the joint detail.
Connecting elements	☐ Continuous	☒ Periodic	Verify appropriate laying surface condition and hole preparation, if specified, meet requirements.
Pre-installation verification testing	☐ Continuous	☒ Periodic	Observe and document verification testing by installation personnel for fastener assemblies and methods used.
Proper storage	☐ Continuous	☒ Periodic	Verify proper storage of bolts, nuts, washers, and other fastener components.
DURING BOLTING (TABLE N5.6-2, AISC 360-10):			
> Not required if only snug-tight joints are specified [per Section N5.6(1) of AISC 360-10]			
> Not required for pretensioned joints using turn-of-th-nut method with match-marking, direct-tension-indicators, or twist-off type tension control method [per Section N5.6(2) of AISC 360-10]			
Fastener assemblies	☐ Continuous	☒ Periodic	Verify that fastener assemblies are of suitable condition, placed in all holes, and washers are positioned as required.
Snug-tight prior to pretensioning	☐ Continuous	☒ Periodic	Verify that joints are brought to snug-tight condition prior to pretensioning operation.
Fastener component	☐ Continuous	☒ Periodic	Verify that fastener component is not turned by wrench prevented from rotating.
Pretensioned fasteners	☐ Continuous	☒ Periodic	Verify that fasteners are Pretensioned in accordance with RCSC Specification, progressing systematically from the most rigid point toward the free edges.
AFTER BOLTING (TABLE N5.6-3, AISC 360-10):			
Document acceptance or rejection of bolted connections	☒ Continuous	☐ Periodic	
OTHER STEEL INSPECTIONS (SECTION N5.7, AISC 360-10; TABLES J8-1 & J10-1, AISC 341-10):			
Structural steel details	☐ Continuous	☒ Periodic	All fabricated steel or steel frames shall be inspected to verify compliance with the details shown in the construction documents, such as braces, stiffeners, member locations, and proper application of joint details at each connection.
Anchor rods and other embedments supporting structural steel	☐ Continuous	☒ Periodic	Shall be on the premises during the placement of anchor rods and other embedments supporting structural steel for compliance with construction documents. Verify the diameter, grade, type, and length of the anchor rod or embedded item, and the extent or depth of embedment prior to placement of concrete.
Reduced beam sections (RBS)	☐ Continuous	☒ Periodic	Verify contour and finish as well as dimensional tolerances (see Table J8-1 of AISC 341-10)
Protected zones	☐ Continuous	☒ Periodic	Verify that no holes or unapproved attachments are made within the protected zone (see Table J8-1 or AISC 341-10)
H-piles	☐ Continuous	☒ Periodic	Verify that no holes or unapproved attachments occur within the protected zones of piling (see Table J10-1 of AISC 341-10)
STEEL ELEMENTS OF COMPOSITE CONSTRUCTION (TABLES N6.1, AISC 360-10; TABLES J9-1 THRU J9-3, AISC 341-11)			
Placement and installation of steel deck	☒ Continuous	☐ Periodic	
Placement and installation of steel headed stud anchors	☒ Continuous	☐ Periodic	
Document acceptance or rejection of steel elements	☒ Continuous	☐ Periodic	
Reinforcing steel	☐ Continuous	☒ Periodic	Verify appropriate reinforcement size, spacing, and orientation; that it has not been re-bent in field; that it is correctly tied and supported; and that required steel clearances have been provided.
Composite member size	☐ Continuous	☒ Periodic	Verify that composite member is the required size.

CONCRETE CONSTRUCTION (IBC 1705.3 & 1705.12.1)

Item

Detailed Instructions and Frequencies

Reinforcing steel, including prestressing tendons	☐ Continuous	☒ Periodic	Verify prior to placing concrete that reinforcing is of specified type, grade and size; that it is free of oil, dirt and rust; that it is located and spaced properly; that hooks, bends, ties, stirrups and supplemental reinforcement are placed correctly; that lap lengths, stagger and offsets are provided; and that all mechanical connections are installed per the manufacturer's instructions and/or evaluation report.
Cast-in bolts & embeds	☐ Continuous	☒ Periodic	Inspection of anchors or embeds cast in concrete is required when allowable loads have been increased or where strength design is used.
Post-installed anchors or dowels	☐ Continuous	☒ Periodic	All post-installed anchors/dowels shall be specially inspected as required by the approved ICC-ES report.
Use of required mix design	☐ Continuous	☒ Periodic	Verify that all mixes used comply with the approved construction documents; ACI 318: Ch. 4, 5.2-5.4; and IBC 1904.3, 1913.2, 1913.3.
Concrete sampling for strength tests, slump, air content, and temperature	☒ Continuous	☐ Periodic	
Concrete & shotcrete placement	☒ Continuous	☐ Periodic	
Curing temperature and techniques	☐ Continuous	☒ Periodic	Verify that the ambient temperature for concrete is kept at >50°F for at least 7 days after placement. High-early-strength concrete shall be kept at >50°F for at least 3 days. Accelerated curing methods may be used (see ACI 318.5.11.3). The ambient temperature for shotcrete shall be >40°F for the same period of time as noted for concrete. Shotcrete shall be kept continuously moist for at least 24 hours after shotcreting. All concrete materials, reinforcement, forms, fillers, and ground shall be free from frost. In hot weather conditions ensure that appropriate measures are taken to avoid plastic shrinkage cracking and that the specified water/cement ratio is not exceeded.
Pre-stressed concrete	☒ Continuous	☐ Periodic	
Erection of precast concrete	☐ Continuous	☒ Periodic	Verify that all precast elements are lifted, assembled and braced in accordance with the approved construction documents.
Strength verification	☐ Continuous	☒ Periodic	Verify that adequate strength has been achieved prior to the removal of shores and forms or the stressing of post-tensioned tendons.
Formwork	☐ Continuous	☒ Periodic	Verify that the forms are placed plumb and conform to the shapes, lines, and dimensions of the members as required by the approved construction documents.
Reinforcement complying with ASTM A 615 in special moment frames, special structural walls and coupling beams	☐ Continuous	☒ Periodic	Verify that ASTM A 615 reinforcing steel used in these areas complies with ACI 318: 21.1.5.2 by means of certified mill test reports. If this reinforcing steel is to be welded chemical tests shall be performed in accordance with ACI 318: 3.5.2.

SOILS CONSTRUCTION (IBC 1705.6)

Item

Detailed Instructions and Frequencies

Verify subgrade is adequate to achieve design bearing capacity	☐ Continuous	☒ Periodic	Prior to placement of concrete.
Verify excavations extend to proper depth and material	☐ Continuous	☒ Periodic	Prior to placement of compacted fill or concrete.
Verify that subgrade has been appropriately prepared prior to placing compacted fill	☐ Continuous	☒ Periodic	Prior to placement of compacted fill.
Perform classification and testing of compacted fill materials	☐ Continuous	☒ Periodic	All materials shall be checked at each lift for proper classifications and gradations not less than once for each 10,000 ft² of surface area.
Verify proper materials, densities and lift thicknesses during placement and compaction.	☒ Continuous	☐ Periodic	

McNEIL ENGINEERING

Economic and Sustainable Designs, Professionals You Know and Trust

8410 South Sandy Parkway, Suite 200 Sandy, Utah 84070 801.255.7700 mcnileengineering.com

Civil Engineering • Consulting & Landscape Architecture
Structural Engineering • Land Surveying & HDS



NEW JAPANESE STEAKHOUSE & SUSHI

251 W. HILTON DR #202 P.O. BOX 2775
ST. GEORGE UTAH 84770

REVISIONS

REV	DATE	DESCRIPTION
<<	<<	<<
<<	<<	<<
<<	<<	<<
<<	<<	<<
<<	<<	<<
<<	<<	<<

PROJECT NO:

18448

DRAWN BY:

GLO

CHECKED BY:

ABS

DATE:

10/19/18


SHEET:

02 OF 14

GENERAL NOTES


S0.01

C:\Users\Anthony\McNEIL - CROUPE\Documents\Current Projects\18448\18448_STRUCT [09-06-18].dwg Anthony Oct 19, 2018 - 9:55am




1-C
S0.02 N.T.S


BAR SIZE		D		180°				90°		D		90°		135°			
				A O R G		J		A O R G				A O R G		A O R G		H	
U.S.	SI	U.S.	SI	U.S.	SI	U.S.	SI	U.S.	SI	U.S.	SI	U.S.	SI	U.S.	SI	U.S.	SI
#3	#10	2 1/2"	60	5	125	3	80	6	150	1 1/2"	40	4"	105	4	105	2 1/2"	65
#4	#13	3	80	6	160	4	105	8	200	2"	50	4 1/2"	115	4 1/2"	115	3"	80
#5	#16	3 1/2"	96	7	175	5	130	10	250	2 1/2"	65	6"	155	5 1/2"	140	3 1/2"	95
#6	#19	4 1/2"	115	8	200	6	155	1'-0"	300	4 1/2"	115	1'-0"	305	8"	205	4 1/2"	115
#7	#22	5 1/2"	135	10	250	7	180	1'-2"	375	5 1/2"	135	1'-2"	355	9"	230	5 1/2"	135
#8	#25	6"	155	1'-1"	275	8	206	1'-4"	425	6"	155	1'-4"	410	10 1/2"	270	6	155
#9	#29	9"	240	1'-3"	375	11 1/2"	300	1'-7"	475	U.S. CUSTOMARY UNITS: in. or ft-in. SI UNITS: MM							
#10	#32	10 1/2"	275	1'-7 1/2"	425	1'-1 1/2"	335	1'-10"	550								
#11	#36	11 1/2"	305	1'-9 1/2"	475	1'-2 1/2"	375	2'-0"	600								
#14	#43	16 1/8"	465	2'-3"	675	1'-9 1/2"	550	2'-7"	775								
#18	#57	22 1/2"	610	3'-0"	925	2'-4 1/2"	725	3'-5"	1050								



1-A
S0.02 N.T.S




2-B
S0.02 N.T.S




2-A
S0.02 N.T.S


NOTE:
SPACE CONTROL AND/OR CONSTRUCTIONS JOINTS @
16'-0" MAX. EACH WAY U.N.O. ON PLANS




3-D
S0.02 N.T.S




3-C
S0.02 N.T.S




3-B
S0.02 N.T.S




3-A
S0.02 N.T.S



4-D
S0.02 N.T.S



4-C
S0.02 N.T.S




4-B
S0.02 N.T.S

4-A
S0.02 N.T.S

REVISIONS		DESCRIPTION	
REV	DATE	DESCRIPTION	
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			

PROJECT NO: 18448
DRAWN BY: GLO
CHECKED BY: ABS
DATE: 10/19/18
SHEET: 03 OF 14

C:\Users\Anthony\McNEIL - 090101\Documents\Current Projects\18448\18448_STRUCT (09-06-18).dwg Anthony Oct. 19, 2018 - 9:35am



NOTES:

- ALL FOOTINGS ADJACENT TO AREAS EXPOSED TO FREEZING TEMPT SHALL BE BELOW FINISH GRADE
- FOR LOCATION OF CONCRETE-ENCASED GROUNDING ELECTRODE (UFER) - PER E3508.12, NEC 250.50, REFERENCE ELECTRICAL PLANS
- PROVIDE 1/2" A.B. FOR 2X OR 3X SILL PLATE WITH 7" MIN EMBEDMENT @ 32" O.C. @ ALL SHEARWALL OR EXTERIOR LOCATIONS (UNLESS NOTED OTHERWISE) INTERIOR BEARING WALLS TO BE AT 32" ON CENTER WITH APPROVED 3x3/4" SQUARE PLATE WASHERS.
- HOLD-DOWN CONNECTOR BOLTS INTO WOOD FRAMING REQUIRE APPROVED PLATE WASHERS; AND HOLD-DOWNS SHALL BE TIGHTENED JUST PRIOR TO COVERING THE WALL FRAMING.
- ALL BOLT HOLES SHALL BE DRILLED 1/8" TO 1/4" OVERSIZED
- ALL WASHERS TO BE APPROVED PLATE WASHERS
- DIMENSIONS ARE FOR REFERENCE ONLY. VERIFY ALL DIMENSIONS WITH ARCH PLANS.
- DO NOT SCALE PLANS. REFERENCE ARCH PLANS FOR ALL DIMENSIONS
- SEE ARCH PLANS FOR SLOPE OF SLABS.
- CCX= INDICATES CONCRETE COLUMN SEE SHEET S4.00 FOR SCHEDULE AND DETAIL 2-D/S5.00 FOR CONCRETE COLUMN AT FOOTINGS
- CWX= INDICATES CONCRETE FOUNDATION WALL SEE SHEET S4.00 FOR SCHEDULE
- F-XX= INDICATES CONTINUOUS FOOTING SEE SHEET S4.00 FOR SCHEDULE
- FS-XX=INDICATES SPOT FOOTING SEE SHEET S4.00 FOR SCHEDULE
- SEE S0.0 FOR FROST DEPTH, VERIFY W/ LOCAL CITY REQUIREMENTS.

LEGENDS

SW

- INDICATES WOOD STRUCTURAL PANEL SHEAR WALL WITH LENGTH SEE SHEAR PLAN FOR SHEAR WALL CALLOUTS, HOLD-DOWNS & SHEATHING INFORMATION

STHD

-STHD SHEAR WALL HOLD DOWN SEE 2-B/S5.00

S

-INDICATES APPROXIMATE FOOTING STEP LOCATION, MIN 24" FROM OUTSIDE FACE OF FND

A.B. @ 1/2"

-INDICATES ANCHOR BOLT SPACING FOR WALL LINE IN INCHES OTHER THAN SPACING INDICATED IN NOTES FOR SW

FOOTING AND FOUNDATION PLAN

SCALE: 3/16"=1'-0"

NOTE: DO NOT SCALE PLAN. USE AS REFERENCE ONLY
VERIFY ALL DIMENSIONS ON ARCHITECTURAL PLANS

McNEIL ENGINEERING

Economic and Sustainable Designs, Professionals You Know and Trust

8410 South Sandy Parkway, Suite 200 Sandy, Utah 84070 801.255.7700 mcnileengineering.com

Civil Engineering • Consulting & Landscape Architecture

Structural Engineering • Land Surveying & HDS

PROFESSIONAL SEAL

#5253654-2203

ANTHONY B. SCHMID

10-19-18

NEW JAPANESE STEAKHOUSE & SUSHI

251 W. HILTON DR #202 P.O. BOX 2775

ST. GEORGE UTAH 84770

REVISIONS

REV	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		

PROJECT NO: 18448

DRAWN BY: GLO


CHECKED BY: ABS

DATE: 10/19/18

SHEET: 04 OF 14

FOOTING & FOUNDATION PLAN

S1.00




KEYED NOTES:	
①	12" 1/4" THICK PREMIER SP5S PANEL WITH DOUBLE 2x6 SPLINE AT 48" OC. SEE DETAIL A4-B55 FOR SPLINE
②	APPROXIMATE LOCATIONS OF MECHANICAL UTILITY TRUSS MANUFACTURER TO COORDINATE WITH MECHANICAL PLANT LOCATIONS AND WEIGHTS.
③	APPROXIMATE LOCATION OF ROOF ACCESS HATCH COORDINATE WITH ARCHITECTURAL DRAWINGS.
④	2x10 DF-L #2 ROOF RAFTERS AT 12" OC.
⑤	FLOOR DECK: USE VULCAFAST 1/50L2 METAL DECK WITH 2 1/2" OF CONCRETE WITH 666-1W-41W-4 SPAN MIN. WEAVE FABRIC PLAND MIDLAB OVERALLOVER THICKNESS 4" (5) SPAN MIN. WEAVE SHEETS TO SUPPORT W 53" DIA. RUSON WELLS W/ PATTERN AND AT 18" OC. WHEN FLUTES ARE PARALLEL TO SUPPORT, WEAVE SIDE SIPS WITH 1/2" LONG TOP SEAM WEALS AT 24" OC. (ALTERNATE EQUIVALENT FASTENERS MAY BE USED WITH PERMISSION FROM STRUCTURAL ENGINEER)
⑥	PROVIDE STEP IN DECK PER ARCHITECTURAL PLANS

FRAMING NOTES

- SEE S0.0 FOR LOADING INFORMATION
- INDICATES BEAM
- ALL EXTERIOR WALL FRAMING TO BE 2x6 DF-L STUD GRADE FRAMING AT 16" O.C. UNLESS NOTED OTHERWISE.
- PROVIDE FULL BEARING FOR ALL BEAMS ENDS, WIDTH OF COLUMN TO EQUAL WIDTH OF BEAM, U.N.O.. PROVIDE SQUASH BLOCKING AT FLOOR LEVEL
- PROVIDE (2) 2x6 TRIM STUDS AND (2) 2x6 KING STUDS FOR OPENINGS OVER 8'-0".
- STRAP & TIE ALL BEAMS TO POSTS, TO BE KING POST, COIL STRAP OR POST CAPS
- SOLID BLOCK JOISTS @ SUPPORTS & LAP SPLICES
- ALL BOLT HOLES SHALL BE DRILLED $\frac{1}{2}$ " TO $\frac{1}{4}$ " OVERSIZED
- HOLD-DOWN CONNECTOR BOLTS INTO WOOD FRAMING REQUIRE APPROVED PLATE WASHERS; AND HOLD-DOWNS SHALL BE TIGHTENED JUST PRIOR TO COVERING THE WALL FRAMING.
- ALL WASHERS TO BE APPROVED PLATE WASHERS
- SEE S0.00 FOR FASTENERS IN PRESERVATIVE-TREATED AND FIRE-RETARDANT-TREATED WOOD
- SEE S0.02 FOR ADDITIONAL TYPICAL STRUCTURAL DETAILS
- INDICATES CONCRETE COLUMN SEE SHEET \$4.00 FOR SCHEDULE AND DETAILS
- INDICATES LOCATION OF CONCRETE LINTEL SEE SHEET \$4.00 FOR SCHEDULE AND DETAILS
- INDICATES CAMBER ON STEEL BEAMS

CCX

CLX

 $(C=X)$ 

MAIN FLOOR FRAMING PLAN

SCALE: 3/16"=1'-0"



NOTE: DO NOT SCALE PLAN. USE AS REFERENCE ONLY
VERIFY ALL DIMENSIONS ON ARCHITECTURAL PLANS

NEW JAPANESE STEAKHOUSE & SUSHI

251 W. HILTON DR #202 P.O. BOX 2775
ST. GEORGE UTAH 84770

CHICAGO

[illegible]

PROJECT NO: 18448

DRAWN BY: C

CHECKED BY: A


DATE: 10/19/18

SHEET: 05 OF 14

MAIN FLOOR FRAMING PLAN

S1.01

C:\Users\Anthony.McNEIL\Documents\Current Projects\18448\18448_STRUCT_102-04-19.dwg Anthony Feb. 13, 2019 - 11:21am



KEYED NOTES:	
①	12-1/4" THICK PREMIER SIPS PANEL WITH DOUBLE 2x SPLINE AT 48" O.C. SEE DETAIL 4-B/S5.03 FOR SPLINE.
②	APPROXIMATE LOCATIONS OF MECHANICAL UNITS TRUSS MANUFACTURER TO COORDINATE WITH MECHANICAL PLAN LOCATIONS AND WEIGHTS.
③	APPROXIMATE LOCATION OF ROOF ACCESS HATCH COORDINATE WITH ARCHITECTURAL DRAWINGS.
④	2x10 DF-L #2 ROOF RAFTERS AT 12" O.C.
⑤	FLOOR DECK USE "VULCRAFT" 15/122 METAL DECK WITH 2-1/2" OF CONCRETE WITH 666- W14x14 WELDED WIRE FABRIC PLACED MID SLAB OVERALL THICKNESS 4". (3) SPAN MIN. WELD SHEETS TO SUPPORT W/ 5/8" DIA. FUSION WELDS W/ 3/4" PATTERN AND AT 18" O.C. WHEN FLUTES ARE PARALLEL TO SUPPORTS. WELD SIDE LAPS WITH 1-1/2" LONG TOP SEAM WELDS AT 24" O.C. (ALTERNATE EQUIVALENT FASTENERS MAY BE USED WITH PERMISSION FROM STRUCTURAL ENGINEER)
⑥	PROVIDE STEP IN DECK PER ARCHITECTURAL PLANS

FRAMING NOTES	
- SEE S0.0 FOR LOADING INFORMATION	
- INDICATES BEAM	
- ALL EXTERIOR WALL FRAMING TO BE 2x6 DF-L STUD GRADE FRAMING AT 16" O.C. UNLESS NOTED OTHERWISE.	
- ROOF SHEATHING TO BE 3/4" OSB SHEATHING WITH A MIN. SPAN RATING OF 40/20 W/ 8d NAILS AT 6" O.C. PERIMETER AND EDGE NAILING AND 12" O.C. FIELD NAILING	
- PROVIDE FULL BEARING FOR ALL BEAMS ENDS. WIDTH OF COLUMN TO EQUAL WIDTH OF BEAM, U.N.O.. PROVIDE SQUASH BLOCKING AT FLOOR LEVEL	
- PROVIDE (2) 2x6 TRIM STUDS AND (2) 2x6 KING STUDS FOR OPENINGS OVER 8'-0".	
- STRAP & TIE ALL BEAMS TO POSTS, TO BE KING POST, COIL STRAP OR POST CAPS	
- SOLID BLOCK JOISTS @ SUPPORTS & LAP SPLICES	
- ALL BOLT HOLES SHALL BE DRILLED 1/2" TO 3/4" OVERSIZED	
- HOLD-DOWN CONNECTOR BOLTS INTO WOOD FRAMING REQUIRE APPROVED PLATE WASHERS, AND HOLD-DOWNS SHALL BE TIGHTENED JUST PRIOR TO COVERING THE WALL FRAMING.	
- ALL WASHERS TO BE APPROVED PLATE WASHERS	
- SEE S0.00 FOR FASTENERS IN PRESERVATIVE-TREATED AND FIRE-RETARDANT-TREATED WOOD	
- SEE S0.02 FOR ADDITIONAL TYPICAL STRUCTURAL DETAILS	
- INDICATES CONCRETE COLUMN SEE SHEET S4.00 FOR SCHEDULE AND DETAILS	
- INDICATES LOCATION OF CONCRETE LINTEL SEE SHEET S4.00 FOR SCHEDULE AND DETAILS	
- INDICATES CAMBER ON STEEL BEAMS	

CCX
CLX
(C=X)

ROOF FRAMING PLAN
SCALE: 3/16"=1'-0"
NOTE: DO NOT SCALE PLAN. USE AS REFERENCE ONLY
VERIFY ALL DIMENSIONS ON ARCHITECTURAL PLANS

McNEIL ENGINEERING

Economic and Sustainable Designs, Professionals You Know and Trust

8410 South Sandy Parkway, Suite 200 Sandy, Utah 84070 801.255.7700 mcnileengineering.com

Civil Engineering • Consulting & Landscape Architecture

Structural Engineering • Land Surveying & HDS

PROFESSIONAL SEAL

#5253654-2203

ANTHONY B. SCHMID

STATE OF UTAH

02-13-19

NEW JAPANESE STEAKHOUSE & SUSHI

251 W. HILTON DR #202 P.O. BOX 2775

ST. GEORGE UTAH 84770

REVISIONS		
REV	DATE	DESCRIPTION
1	02-13-19	REVIEW COMMENTS

PROJECT NO: 18448

DRAWN BY: GLO

CHECKED BY: ABS


DATE: 02/13/19

SHEET: 06 OF 14

ROOF FRAMING PLAN


S1.02

C:\Users\Anthony.McNEIL - 0901P\Documents\Current Projects\18448\18448_STRUCT (02-04-19).dwg Anthony Feb 13, 2019 - 11:21am



ROOF LAYOUT

SCALE 1/16" = 1'-0"



UPPER ROOF FRAMING PLAN

SCALE: 3/16"=1'-0"
0' 5' 10' 15' 30'
NOTE: DO NOT SCALE PLAN. USE AS REFERENCE ONLY
VERIFY ALL DIMENSIONS ON ARCHITECTURAL PLANS

KEYED NOTES:

1	12-1/4" THICK PREMIER SIPS PANEL WITH DOUBLE 2x SPLINE AT 48" O.C. SEE DETAIL 4-B/S5.03 FOR SPLINE.
2	APPROXIMATE LOCATIONS OF MECHANICAL UNITS TRUSS MANUFACTURER TO COORDINATE WITH MECHANICAL PLAN LOCATIONS AND WEIGHTS.
3	APPROXIMATE LOCATION OF ROOF ACCESS HATCH COORDINATE WITH ARCHITECTURAL DRAWINGS.
4	2x10 DF-L #2 ROOF RAFTERS AT 12" O.C.
5	FLOOR DECK: USE "VULCRAFT" 1.5VL22 METAL DECK WITH 2-1/2" OF CONCRETE WITH 666 - W1.4xW1.4 WELDED WIRE FABRIC PLACED MID-SLAB OVERALL THICKNESS 4" (3) SPAN MIN. WELD SHEETS TO SUPPORT W/ 5/8" DIA. FUSION WELDS W/ 3/4" PATTERN AND AT 18" O.C. WHEN FLUTES ARE PARALLEL TO SUPPORTS. WELD SIDE LAPS WITH 1-1/2" LONG TOP SEAM WELDS AT 24" O.C. (ALTERNATE EQUIVALENT FASTENERS MAY BE USED WITH PERMISSION FROM STRUCTURAL ENGINEER)
6	PROVIDE STEP IN DECK PER ARCHITECTURAL PLANS

FRAMING NOTES

- SEE S0.0 FOR LOADING INFORMATION
- INDICATES BEAM
- ALL EXTERIOR WALL FRAMING TO BE 2x6 DF-L STUD GRADE FRAMING AT 16" O.C. UNLESS NOTED OTHERWISE.
- ROOF SHEATHING TO BE 3/4" OSB SHEATHING WITH A MIN. SPAN RATING OF 40/20 W/ 8d NAILS AT 6" O.C. PERIMETER AND EDGE NAILING AND 12" O.C. FIELD NAILING.
- PROVIDE FULL BEARING FOR ALL BEAMS ENDS, WIDTH OF COLUMN TO EQUAL WIDTH OF BEAM, U.N.O.. PROVIDE SQUASH BLOCKING AT FLOOR LEVEL.
- PROVIDE (2) 2x6 TRIM STUDS AND (2) 2x6 KING STUDS FOR OPENINGS OVER 8'-0".
- STRAP & TIE ALL BEAMS TO POSTS, TO BE KING POST, COIL STRAP OR POST CAPS
- SOLID BLOCK JOISTS @ SUPPORTS & LAP SPLICES
- ALL BOLT HOLES SHALL BE DRILLED 1/2" TO 3/8" OVERSIZED
- HOLD-DOWN CONNECTOR BOLTS INTO WOOD FRAMING REQUIRE APPROVED PLATE WASHERS, AND HOLD-DOWNS SHALL BE TIGHTENED JUST PRIOR TO COVERING THE WALL FRAMING.
- ALL WASHERS TO BE APPROVED PLATE WASHERS
- SEE S0.00 FOR FASTENERS IN PRESERVATIVE-TREATED AND FIRE-RETARDANT-TREATED WOOD
- SEE S0.02 FOR ADDITIONAL TYPICAL STRUCTURAL DETAILS
- INDICATES CONCRETE COLUMN SEE SHEET S4.00 FOR SCHEDULE AND DETAILS
- INDICATES LOCATION OF CONCRETE LINTEL SEE SHEET S4.00 FOR SCHEDULE AND DETAILS
- INDICATES CAMBER ON STEEL BEAMS

CCX

CLX

(C=X)

McNEIL ENGINEERING
Economic and Sustainable Designs, Professionals You Know and Trust

8610 South Sandy Parkway, Suite 200 Sandy, Utah 84070 801.255.7700 mcnaiengineering.com
Civil Engineering • Consulting & Landscape Architecture
Structural Engineering • Land Surveying & HDS



NEW JAPANESE STEAKHOUSE & SUSHI

251 W. HILTON DR #202 P.O. BOX 2775
ST. GEORGE UTAH 84770

REVISIONS

REV	DATE	DESCRIPTION	REVIEW COMMENTS
1	02-13-19		
2			
3			
4			
5			
6			

PROJECT NO:	18448
DRAWN BY:	GLO
CHECKED BY:	ABS
DATE:	02/13/19
SHEET:	07 OF 14

UPPER ROOF FRAMING PLAN

S1.03



Diagram illustrating the cross-section of a wall with reinforcement details:

- CONCRETE WALL (INSIDE FACE)
- CONCRETE WALL (OUTSIDE FACE SOIL SIDE WHERE OCCURS)
- VERTICAL BAR
- HORIZONTAL BAR

Diagram illustrating the Reinforcement Placement for a Concrete Lintel. The diagram shows a cross-section of the lintel with the following components labeled:

- WALL REINFORCEMENT EXTEND TO BOTTOM OF LINTEL
- TOP BARS PER PLAN
- TIES PER PLAN
- BOTTOM BARS PER PLAN, 3 BARS MAX PER LAYER, IF MORE THAN 2 BAR PLACE OTHER BARS IN ANOTHER LEVEL
- CONCRETE LINTEL
- WALL THICKNESS
- LINTEL DEPTH
- ELEV. PER ARCH

NOTE: EXTEND HORIZONTAL WALL REINFORCEMENT THROUGH LINTEL



WHERE DISTANCE IS LESS THAN 2'-0" START TRIM BARS AT FLR LINE

TRIM BARS

FLR LINE

DOWEL SAME SIZE AS TRIM BAR(S)

USE STD HOOKS WHERE FULL EMBED IS NOT POSSIBLE

TRIM BAR(S): FOR 8" TO 12" WALLS (2) #5

BARS TO EXTEND PAST EDGE OF OPNG A MIN OF EMBED LENGTH, SEE SCHED


WHERE THIS DIM IS LESS THAN 2'-6" USE #3 TIES AT 8" O.C. MAX

SECTION B-B

USE DOWELS - SAME AS TRIM BARS - WHERE JAMBS DO NOT ALIGN VERTLY AND WHERE THERE ARE NO OPNGS BLW. PROVIDE STD HOOK WHERE FULL EMBED "a" IS NOT POSSIBLE

WHERE JAMBS ALIGN VERTLY USE SPLIT 2" TIE (a) (b) (c) (d) (e) (f) (g) (h) (i) (j) (k) (l) (m) (n) (o) (p) (q) (r) (s) (t) (u) (v) (w) (x) (y) (z)

CONCRETE COLUMN SCHEDULE			
MARK	SIZE	VERT. REINF.	TIE CONFIG.
CC1	18" x WALL THICKNESS	(8) #5	#3 TIES @ 8" O.C.



REBAR SIZE		CONCRETE REINFORCING BAR LAP SPlice SCHEDULE																							
		f _c = 3000 psi						f _c = 4000 psi						f _c = 5000 psi						f _c = 6000 psi					
		REGULAR			TOP			REGULAR			TOP			REGULAR			TOP			REGULAR			TOP		
		CLASS			CLASS			CLASS			CLASS			CLASS			CLASS			CLASS			CLASS		
		A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B
#4	17"	22"	22"	28"	15"	19"	19"	24"	13"	17"	17"	22"	12"	16"	16"	20"									
	22"	29"	29"	38"	19"	25"	25"	33"	17"	22"	29"	29"	38"	21"	21"	21"	27"								
#5	28"	36"	36"	47"	24"	31"	31"	41"	22"	28"	36"	36"	47"	26"	26"	26"	33"								
#6	33"	43"	43"	56"	29"	37"	37"	49"	26"	34"	34"	43"	24"	31"	31"	40"									
#7	49"	63"	63"	81"	42"	54"	54"	70"	37"	48"	48"	63"	35"	45"	45"	58"									
#8	55"	72"	72"	93"	47"	62"	62"	80"	42"	55"	71"	71"	93"	51"	51"	51"	66"								
#9	62"	81"	81"	105"	53"	69"	69"	90"	48"	62"	62"	81"	44"	58"	58"	75"									
#10	70"	91"	91"	118"	60"	78"	78"	101"	54"	70"	70"	91"	50"	65"	65"	84"									
#11	78"	101"	101"	131"	67"	87"	87"	112"	60"	77"	77"	100"	55"	72"	72"	93"									

CONCRETE REINFORCING BAR LAP SPlice NOTES:

1. THIS SCHEDULE SHALL BE USED FOR ALL SPlices, UNLESS NOTED OTHERWISE.

2. HORIZONTAL BARS ARE CLASSIFIED AS TOP BARS WHERE 12" OR MORE, OF FRESH CONCRETE IS CAST BELOW THE REINFORCING BARS.

3. CLASS 'B' SPlices SHALL BE USED FOR ALL SPlices, UNLESS NOTED OTHERWISE.


4. TIES AND STRIPPUS SHALL NOT BE SPliced.

5. FOR ALL LIGHTWEIGHT CONCRETE, LAP LENGTHS SHALL BE MULTIPLIED BY 1.3.

6. FOR ALL EPOXY COATED BARS, LAP LENGTHS SHALL BE MULTIPLIED BY 1.3 FOR TOP BARS AND 1.5 FOR REGULAR BARS.



7. LAP LENGTHS SHALL BE MULTIPLIED BY 1.25 AT SHEARWALL BOUNDARY ELEMENTS AT FOOTINGS AND AT MOMENT FRAME BEAMS TO COLLUMNS.

FOOTING SCHEDULE													
MARK	WIDTH	LENGTH	DEPTH	REINFORCING CROSSWISE				REINFORCING LENGTHWISE				REMARKS	DEPTH OF STRUCTURAL FILL
				NO	SIZE	LENGTH	SPACING	NO	SIZE	LENGTH	SPACING		
F-24	24"	CONT	12"	-	-	-	-	2	#5	CONT	EQ	CONTINUOUS FOOTING	2'-0"
F-36	36"	CONT	14"	-	-	-	-	3	#5	CONT	EQ	CONTINUOUS FOOTING	2'-0"
F-48	48"	CONT	14"	-	#5	3'-6"	18" O.C.	4	#5	CONT	EQ	CONTINUOUS FOOTING	3'-0"
FS-3	3'-0"	3'-0"	12"	3	#5	2'-6"	EQ	3	#5	2'-6"	EQ	SPOT FOOTING	2'-0"
FS-4	4'-0"	4'-0"	12"	4	#5	3'-6"	EQ	4	#5	3'-6"	EQ	SPOT FOOTING	2'-0"
FS-4.5	4'-6"	7'-6"	12"	7	#5	4'-0"	EQ	4	#5	7'-0"	EQ	SPOT FOOTING	2'-0"
FS-6.5	6'-6"	6'-6"	14"	7	#5	6'-0"	EQ	7	#5	6'-0"	EQ	SPOT FOOTING	3'-0"
FS-7	7'-0"	7'-0"	14"	8	#5	6'-6"	EQ	8	#5	6'-6"	EQ	SPOT FOOTING	3'-0"
FS-8	8'-0"	8'-0"	16"	10	#5	7'-6"	EQ	10	#5	7'-6"	EQ	SPOT FOOTING	3'-0"
FS-9	9'-0"	9'-0"	24"	16	#5	8'-6"	EQ	18	#5	8'-6"	EQ	SPOT FOOTING PROVIDE (2) MATS OF REINFORCING PLACE HALF THE REQUIRED REINFORCING 2" FROM TOP OF FOOTING AND HALF 3" FROM BOTTOM OF FOOTING	4'-0"
FS-10	10'-0"	10'-0"	24"	22	#5	9'-6"	EQ	22	#5	9'-6"	EQ	SPOT FOOTING PROVIDE (2) MATS OF REINFORCING PLACE HALF THE REQUIRED REINFORCING 2" FROM TOP OF FOOTING AND HALF 3" FROM BOTTOM OF FOOTING	4'-0"
NOTES:													
*STRUCTURAL FILL PER SOILS REPORT													
SEE STEPPED FOUNDATION DETAIL WHERE FOOTING STEP IS REQUIRED													






RETAINING WALL SCHEDULE							
WALL DIMENSIONS					REINFORCING BARS		
h	a	b	c	d	STEM		
					" π "	" σ "	" γ "
3'-0"	10"	1'-0"	2'-6"	14"	#5 @ 16" O.C.	#5 @ 16" O.C.	-
5'-0"	10"	1'-0"	4'-6"	14"	#5 @ 14" O.C.	#5 @ 14" O.C.	-
7'-0"	10"	1'-0"	6'-0"	14"	#5 @ 10" O.C.	#5 @ 10" O.C.	#5 @ 10" O.C.
9'-0"	AT 9'-0" RAMP WALL AT CORNER USE FOOTING AND WALL REQUIREMENTS FOR 7'-0" WALL						


[illegible]




WALK OUT
BASEMENT FOUNDATION

SLABE ON GRADE FOOTING


3-C STL. COLUMN BASEMENT WALL
\$5.00 N.T.S




STEM WALL FOUNDATION PERIMETER



FOUNDATION WALL




1-B BASEMENT FOUNDATION
S5.00 N.T.S




FOOTING DETAIL

2-B STRAP TIE HOLDOWN STEM
S5.00 N.T.S




CONCRETE COLUMN
BASEMENT FOUNDATION




3-A STL. COLUMN FOOTING DETAIL
\$5.00 N.T.S.


4-D STAIR STRINGER TO SLAB
S5.06 N.T.S



STEM WALL
PRIVACY FENCE



WF TO CONCRETE COLUMN
N.T.S.



SECTION
N.T.S



REVISIONS	REV	DATE	DESCRIPTION
	<		
	<		
	<		
	<		
	<		
PROJECT NO:		18448	
DRAWN BY:		GLO	
CHECKED BY:		ABS	
DATE:		10/19/18	
SHEET:		10 OF 14	

C.L. OF COL. & TAB U.N.O.

SHEAR TAB

STEEL BEAM

STEEL COLUMN

BEAM TO STL. COL. SHEAR TAB CONN.

$\frac{1}{2}"$ TYP.

$2" @ 1" \text{ } \phi$ BOLTS

CENTER LINE OF BEAM EQUALS
CENTER LINE OF COL. I.N.O.

SEE SCHED.

$\frac{1}{2}"$ TYP.

$2" @ 1" \text{ } \phi$ BOLTS

BOLTS PER TABLE

STEEL BEAM

FACE OF COLUMN/
BEAM WEB

SHEAR PL. - SEE SCHEDULE

SHORT-SLOTTED HOLES IN
SHEAR PLATE W/ WASHER
PER THE STRUCTURAL NOTES


W BEAM-SEE PLAN

USE FULL DEPTH WEB STIFF. WHERE NO
ADJACENT BEAM LOCATED WITH IN $36"$
OF EACH OTHER. ALIGN STIFFENER WITH
BEAM @ LEFT. MATCH SHEAR TAB PLAT
THICKNESS


SHEAR TAB CONNECTIONS

WF BEAM CONN.


1-C
\$5.01
N.T.S.




C:\Users\Anthony\McNeil - 09010\Documents\Server\Current Projects\18448\18448_STRUCT (09-06-18).dwg Anthony Oct 19, 2018 - 9:36am




SECTION
1-D
S5.02 N.T.S.




SECTION
1-C
S5.02 N.T.S.




SECTION
2-A
S5.02 N.T.S.




SECTION
1-A
S5.02 N.T.S.




SECTION
2-D
S5.02 N.T.S.




SECTION
2-C
S5.02 N.T.S.




SECTION
2-B
S5.02 N.T.S.




SECTION
2-A
S5.02 N.T.S.




SECTION
3-C
S5.02 N.T.S.





SECTION
3-B
S5.02 N.T.S.



SECTION
4-D
S5.02 N.T.S.



SECTION
4-C
S5.02 N.T.S.



















SECTION
4-A
S5.02 N.T.S.

REVISIONS		DESCRIPTION
REV	DATE	

PROJECT NO:	18448
DRAWN BY:	GLO
CHECKED BY:	ABS
DATE:	10/19/18
SHEET:	12 OF 14

C:\Users\Anthony.McNeil\Documents\Current Projects\18448\18448_STRUCT (02-04-19).dwg Anthony Feb 13, 2019 - 11:21am



REVISIONS			
REV	DATE	DESCRIPTION	REVIEW COMMENTS
1	02-13-19		
2			
3			
4			
5			
6			
7			
8			
9			
10			

PROJECT NO: 18448
DRAWN BY: GLO
CHECKED BY: ABS
DATE: 02/13/19
SHEET: 13 OF 14


STRUCTURAL DETAILS

S5.03


C:\Users\Anthony\McNeil-0901P\Documents\Server\Current Projects\18448\18448_STRUCT (02-04-19).dwg Anthony Feb 13, 2019 - 11:22am

SHEATHING SCHEDULE						
MARK	OSB OR PLYWOOD	COMMON NAILS			16 GA. STAPLE ALT.	LAYERS OF SHEATHING
		SIZE	PERIMETER	FIELD		
SW1	7/16"	8d	6"	12"	3"	1
SW2	7/16"	8d	4"	12"	2"	1
SW3	7/16"	8d	3"	12"	NOT ALLOWED	1
SW4	7/16"	8d	4"	12"	2"	1
SW5	7/16"	8d	3"	12"	NOT ALLOWED	1
SW6	7/16"	8d	2"	12"	NOT ALLOWED	1
ROOF	5/8"	8d	6"	12"	NOT ALLOWED	1


- NOTES FOR SHEAR WALLS 3-4:
- FRAMING AT ADJOINING PANEL EDGES SHALL BE 3" NOMINAL OR SHALL BE (2) 2" NOMINAL MEMBERS. STITCH NAIL THE (2) 2X MEMBER WITH A DOUBLE ROW OF 16d COMMON NAILS AT 4" O.C.. AT 3" NOMINAL MEMBER IS NOT REQUIRED FOR SILL PLATE U.N.O.
 - ALL SHEATHED WALLS TO BE TYPE "1" U.N.O.
 - 8" FIELD SPACING FOR STAPLE ALT.




3-D
S5.04
TYP. TOP PLATE SPLICE
N.T.S.




3-C
S5.04
SHEAR WALLS WITH INTERSECTING WALLS
N.T.S.



3-B
S5.04
TYP. SHEAR WALL DETAIL
& ROOF/FLOOR SHEATHING DETAIL
N.T.S.



1-A
S5.04
BUILT UP CORNER
N.T.S.



4-D
S5.04
SECTION
N.T.S.



REVISIONS		
REV	DATE	DESCRIPTION
1	02-13-19	REVIEW COMMENTS

PROJECT NO: 18448
DRAWN BY: GLO
CHECKED BY: ABS
DATE: 02/13/19
SHEET: 14 OF 14

**STRUCTURAL
DETAILS**

S5.04