Attachment #5 Geotechnical Report



# 309th SWEG Office Building

HAFB, Utah April 11, 2022 Terracon Project No. 61225006

### **Prepared for:**

CRSA Salt Lake City, Utah

### Prepared by:

Terracon Consultants, Inc. Midvale, Utah

🧧 Geotechnical

April 11, 2022

CRSA 649 E. South Temple Salt Lake City, Utah 84102



Attn: Mr. David Triplett – Senior Principal P: (801) 746 6805 E: davet@crsa-us.com

Re: Geotechnical Engineering Report 309th SWEG Office Building Hill Air Force Base HAFB, Utah Terracon Project No. 61225006

Dear Mr. Triplett:

We have completed the Geotechnical Engineering services for the above referenced project. This study was performed in general accordance with Terracon Proposal No. P61225006 dated February 2, 2022. This report presents the findings of the subsurface exploration and provides geotechnical recommendations concerning earthwork and the design and construction of foundations and floor slabs for the proposed project.

We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report or if we may be of further service, please contact us.

Sincerely, Terracon Consultants, Inc.

Joshua D. White, P.E. Project Engineer John B. Mancini, P.E. Principal

Terracon Consultants, Inc. 6949 S High Tech Drive, Suite 100 Midvale, Utah 84047 P (801) 545 8500 F (801) 545 8600 terracon.com

### **REPORT TOPICS**

| INTRODUCTION                  | 1  |
|-------------------------------|----|
| SITE CONDITIONS               | 1  |
| PROJECT DESCRIPTION           | 2  |
| GEOTECHNICAL CHARACTERIZATION | 3  |
| GEOTECHNICAL OVERVIEW         | 5  |
| EARTHWORK                     | 6  |
| SHALLOW FOUNDATIONS           | 10 |
| SEISMIC CONSIDERATIONS        | 13 |
| LIQUEFACTION                  | 13 |
| FLOOR SLABS                   | 14 |
| PAVEMENTS                     | 15 |
| FROST CONSIDERATIONS          | 18 |
| CORROSIVITY                   | 18 |
| GENERAL COMMENTS              | 19 |
| FIGURES                       | 20 |

**Note:** This report was originally delivered in a web-based format. **Orange Bold** text in the report indicates a referenced section heading. The PDF version also includes hyperlinks which direct the reader to that section and clicking on the *GeoReport* logo will bring you back to this page. For more interactive features, please view your project online at <u>client.terracon.com</u>.

### ATTACHMENTS

EXPLORATION AND TESTING PROCEDURES SITE LOCATION AND EXPLORATION PLANS EXPLORATION RESULTS SUPPORTING INFORMATION

Note: Refer to each individual Attachment for a listing of contents.



### **REPORT SUMMARY**

| Topic <sup>1</sup>  | Overview Statement <sup>2</sup>   |
|---|---|
| Project   | 10,000 square foot reinforced CMU structure<br>Max. Column loads: 100 kips, Max. Wall loads: 4 kips per lineal foot                       |
| Description   | Little excavation other than foundation construction  |
| Geotechnical  | Some areas contain existing fill up to 4½ feet deep   |
| Characterization  | Groundwater not encountered   |
|   | Remove existing fill where encountered.   |
| Earthwork   | Existing lean clays can be used for engineered fill   |
|   | Clays are sensitive to moisture variation   |
|   | Shallow foundations will be sufficient  |
| Shallow Allowable bearing pressure = 1,800 psf  |   |
| <b>Foundations</b> Expected settlements: < 1-inch total, < <sup>1</sup> / <sub>2</sub> -inch differential |   |
|   | Detect and remove zones of fill as noted in Earthwork.  |
| General   | This section contains important information about the limitations of this geotechnical  |
| Comments  | engineering report.   |
| 1. If the reader<br>of the report   | is reviewing this report as a pdf, the topics above can be used to access the appropriate section to simply clicking on the topic itself. |
| 2. This summa   | ary is for convenience only. It should be used in conjunction with the entire report for design   |

purposes.

309th SWEG Office Building Hill Air Force Base HAFB, Utah Terracon Project No. 61225006 April 11, 2022

### **INTRODUCTION**

This report presents the results of our subsurface exploration and geotechnical engineering services performed for the proposed 309<sup>th</sup> SWEG to be located at Hill Air Force Base in HAFB, Utah. The purpose of these services is to provide information and geotechnical engineering recommendations relative to:

- Subsurface soil conditions
- Groundwater conditions
- Site preparation and earthwork
- Demolition considerations
- Excavation considerations
- Stormwater pond considerations

- Foundation design and construction
- Floor slab design and construction
- Seismic site classification per IBC
- Lateral earth pressures
- Frost considerations
- Other

The geotechnical engineering Scope of Services for this project included the advancement of 2 exploratory borings and 3 hand augured test holes to depths ranging from approximately 6 to  $26\frac{1}{2}$  feet below existing site grades.

Maps showing the site and boring locations are shown in the **Site Location** and **Exploration Plan** sections, respectively. The results of the laboratory testing performed on soil samples obtained from the site during the field exploration are included on the boring logs and/or as separate graphs in the **Exploration Results** section.

### SITE CONDITIONS

The following description of site conditions is derived from our site visit in association with the field exploration and our review of publicly available geologic and topographic maps.

| ltem               | Description  |  |
|--------------------|--|--|
| Parcel Information | The project is located at Hill Air Force Base in HAFB, Utah. Site coordinates are Latitude: 41.134357°, Longitude: -112.014949° (approximate). See Site Location |  |

309th SWEG Office Building = HAFB, Utah April 11, 2022 = Terracon Project No. 61225006



| ltem                     | Description  |  |
|--------------------------|--|--|
| Existing<br>Improvements | Vacant area with existing detention pond.  |  |
| Current Ground<br>Cover  | Bare soil  |  |
| Existing Topography      | Relatively flat elevations   |  |
| Geology                  | Available geologic map indicates subsurface conditions consist of<br>Quaternary Lake Bonneville deposits consisting of clay soils with occasional<br>sand. |  |

### **PROJECT DESCRIPTION**

Our initial understanding of the project was provided in our proposal and was discussed during project planning. A period of collaboration has transpired since the project was initiated, and our final understanding of the project conditions is as follows:

| Item                               | Description   |  |
|------------------------------------|---|--|
| Information Provided               | Information was provided by Mr. David Triplett via email dated 12/21/2021 with occasional updates from design team members.                   |  |
| Project Description                | Project consists of construction of a new office facility for the 309 <sup>th</sup> Software Engineering Group                                |  |
| Proposed Structure                 | The project includes a single-story building with a footprint of about 10,000 square feet. The building will be slab-on-grade (non-basement). |  |
| <b>Building Construction</b>       | Reinforced Concrete Masonry Unit (CMU)  |  |
| Finished Floor Elevation           | Finished floor elevation is expected to be within 1 to 2 feet above existin site grade.   |  |
| Maximum Loads                      | <ul> <li>Columns: 100 kips (spaced at approximately 22 feet x 22 feet)</li> <li>Walls: 3 to 4 klf</li> <li>Floor: 150 psf typical</li> </ul>  |  |
| Grading/Slopes                     | None  |  |
| <b>Below-Grade Structures</b>      | None  |  |
| Free-Standing Retaining Walls      | None  |  |
| Below-Grade Areas                  | Stormtech Below Ground Storm Water Retention System in the existing pond area to east of proposed building                                    |  |
| Pavements                          | Asphalt Parking lot with light truck and passenger vehicles of 500 per day.   |  |
| Estimated Start of<br>Construction | 2022  |  |

April 11, 2022 
Terracon Project No. 61225006



### **GEOTECHNICAL CHARACTERIZATION**

We have developed a general characterization of the subsurface conditions based upon our review of the subsurface exploration, laboratory data, geologic setting and our understanding of the project. This characterization, termed GeoModel, forms the basis of our geotechnical calculations and evaluation of site preparation and foundation options. Conditions encountered at each exploration point are indicated on the individual logs. The individual logs can be found in the **Exploration Results** section and the GeoModel can be found in the **Figures** section of this report.

As part of our analyses, we identified the following model layers within the subsurface profile. For a more detailed view of the model layer depths at each boring location, refer to the GeoModel.

| Model Layer | Layer Name | General Description                                |  |
|-------------|------------|--|--|
| 1           | Fill       | Existing fill consisting of silty sand with gravel |  |
| 2           | Clay       | Lean clay with varying amounts of sand and silt    |  |
| 3           | Silt       | Silt with vary amounts of sand and clay            |  |

Groundwater was not encountered during the subsurface exploration or for the short duration the borings were open. These observations represent groundwater conditions at the time of the field exploration and may not be indicative of other times or at other locations.

Groundwater level fluctuations occur due to seasonal variations in the amount of rainfall, runoff, and other factors not evident at the time the borings were performed. Groundwater levels during construction or at other times in the life of the structure may be higher or lower than the levels indicated on the boring logs. The possibility of groundwater level fluctuations should be considered when developing the design and construction plans for the project.

### Site Geology

The project site is located in central Davis County, Utah north of the town of Layton, Utah. Soil profile and geologic information from various sources follows.

### Near Surface Soils

The Natural Resources Conservation Service Web Soil Survey (WSS) indicates the primary natural surficial soil unit present in portions of the project site is Kidman Fine Sandy Loam and Preston Fine Sand. The following table summarizes the general characteristics of these soils as described in the Web Soil Survey:

309th SWEG Office Building = HAFB, Utah April 11, 2022 = Terracon Project No. 61225006



| Soil<br>Name                    | Parent<br>Material | Landform<br>Location      | Drainage<br>Class      | Maximum<br>Salinity                        | Shrink/Swell<br>Potential | Depth to<br>Seasonal<br>High Water<br>Table (feet) |
|---------------------------------|--------------------|---------------------------|------------------------|--|---------------------------|--|
| Kidman<br>Fine<br>Sandy<br>Loam | Lake sediment      | Lake<br>terraces<br>tread | Well<br>drained        | Nonsaline<br>to very<br>slightly<br>saline | None                      | More than 80<br>inches                             |
| Preston<br>Fine<br>Sand         | Eolian deposits    | Hills side<br>slope       | Excessively<br>drained | Nonsaline<br>to very<br>slightly<br>saline | None                      | More than 80<br>inches                             |

### **Quaternary Geology**

The site is located west of the Wasatch Mountains along the eastern margin of the Basin and Range physiographic province. The northwest portion of the Basin and Range province is situated north of the Colorado Plateau and is bounded by the Wasatch Mountains to the east. Formed during middle and late Tertiary time (1 million years (m.y.) to 23 m.y. ago), the Basin and Range province is dominated by fault-controlled topography. The topography consists of mountain ranges and relatively flat, broad alluvial valleys. These mountain ranges and valleys have evolved from generally complex movements and associated erosional and depositional processes. Structurally, the site lies within the Great Salt Lake Valley. Drainage flows along local streams and rivers and slope wash during late Tertiary time, coupled with structural activity and Lake Bonneville deposition, are generally responsible for the present-day topography within the basin. The site is located in an area mapped as having very low liquefaction potential <sup>1</sup>.

- The geologic unit mapped <sup>2</sup> at the surface of the site is deltaic sand deposits of Provo shoreline age of Lake Bonneville. Deltaic materials generally consist of sand soils.
- The nearest known Quaternary fault is 5.7 miles east of the Weber Section of the greater Wasatch fault zone.<sup>3</sup>

<sup>&</sup>lt;sup>1</sup> Christenson, G.E., Shaw, L.M., 2008, Liquefaction Special Study Areas, Wasatch Front and Nearby Areas, Utah, Supplement Map to Utah Geological Survey Circular 106.

<sup>&</sup>lt;sup>2</sup> U.S. Geological Survey, mapView, Geologic Map Portal, April 2022, <u>https://ngmdbs.usgs.gov/mapview/</u>

<sup>&</sup>lt;sup>3</sup> U.S. Geological Survey, April 4, 2022, Interactive Fault Map, <u>https://earthquake.usgs.gov/hazards/qfaults/</u>



Faults are mapped along the nearby mountain foothills, at the base of the Wasatch Mountains to the east, and within the Great Salt Lake. The activity of segments of the Wasatch Fault is believed to be infrequent, but studies indicate large (magnitude 7.0) earthquakes every 900 to 1,300 years.

### **Bedrock Geology**

Bedrock was not encountered in the borings performed during this exploration, and due to the Basin and Range geologic province area, bedrock may not be present within 1,000 to 2,000 feet of ground surface in the locale.<sup>5</sup>

### **GEOTECHNICAL OVERVIEW**

Based on the conditions encountered, the site is suitable for the proposed building.

Existing silty sand and gravel fill was encountered at borings B-01 and B-02 to depths of about 4½ feet. The fill appears to have been placed in a loose manner and we have no records to indicate the degree of control. We recommend removal and replacement of existing fills below all foundations. The **Shallow Foundations** section addresses support of the building bearing on a minimum of 12 inches of engineered fill extending to the native fine-grained soils or extending the footings to the native fine-grained soils.

In floor slab areas, existing granular fills may remain provided Owner accepts additional risk. Support of floor slabs and pavements on or above existing fill soils is discussed in this report. However, even with the recommended construction procedures, there is inherent risk for the owner that compressible fill or unsuitable material, within or buried by the fill will, not be discovered. This risk of unforeseen conditions cannot be eliminated without completely removing the existing fill, but can be reduced by following the recommendations contained in this report. To take advantage of the cost benefit of not removing the entire amount of undocumented fills following the recommended reworking of the material. Should this be the case, development can be supported on a shallow foundation system. The Floor Slabs section addresses slab-on-grade support of the building.

The near surface, loose sandy existing fill and the native fine-grained soils could become unstable with typical earthwork and construction traffic, especially after precipitation events. The effective drainage should be completed early in the construction sequence and maintained after construction to avoid potential issues. If possible, the grading should be performed during the warmer and drier times of the year. If grading is performed during the winter months, an increased risk for possible undercutting and replacement of unstable subgrade will persist. Additional site preparation recommendations, including subgrade improvement and fill placement, are provided in the **Earthwork** section.



The **Pavements** section addresses the design of asphalt pavement systems.

The General Comments section provides an understanding of the report limitations.

### EARTHWORK

Earthwork is anticipated to include clearing and grubbing, excavations, and fill placement. The following sections provide recommendations for use in the preparation of specifications for the work. Recommendations include critical quality criteria, as necessary, to render the site in the state considered in our geotechnical engineering evaluation for foundations, floor slabs, and pavements.

#### Site Preparation

Prior to placing fill, existing vegetation and root mat should be removed. Complete stripping of the topsoil should be performed in the proposed building areas and parking/driveway areas.

Following stripping and removal of existing fill materials, building foundation areas should be undercut to native soils in order remove the existing granular fill. Exposed foundation subgrade should be scarified to a depth of 8 inches, moisture conditioned, and recompacted prior to constructing new foundations.

In floor slab and pavement areas, the exposed subgrade should be proof rolled to identify soft or deflecting areas and further evaluate the effectiveness of the subgrade compaction. Proofrolling should be performed with a heavily loaded tandem axle dump truck or with similar approved construction equipment under the observation of the Terracon geotechnical engineer. If conditions are found to be unstable, these areas should be removed and replaced with properly placed and compacted Structural fill or stabilized using a combination of Stabilization Fill, geogrids and geotextiles. Soft spot stabilization, if needed, may be accomplished by placement of a bi-axial geogrid product such as those provided by Tensar® (TX grid) or Mirafi® on top of the subgrade and covered with a minimum 8-inch thick layer of the Stabilization Fill. A separation fabric, such as Mirafi® N-series, should be placed between the native soil and the geogrid to minimize migration of clayey soils into the Stabilization Fill.

### **Existing Fill**

As noted in **Geotechnical Characterization**, borings B-01 and B-02 encountered existing fill to depths of about 4½ feet. The fill appears to have been placed in a loose manner and we have no records to indicate the degree of control. Support of footings on existing fill is not recommended.



Floor slabs and pavements constructed on or above existing fill soils is discussed in this report. However, even with the recommended construction procedures, there is inherent risk for the owner that compressible fill or unsuitable material, within or buried by the fill will, not be discovered. This risk of unforeseen conditions cannot be eliminated without completely removing the existing fill, but can be reduced by following the recommendations contained in this report.

If the owner elects to construct the floor slabs and pavements on the existing fill, the following protocol should be followed. Once the planned grading has been completed, the area should be undercut 1 foot within the footing area and 2 feet within the building slab area and 5 feet beyond the lateral limits of the building area. Once materials have been removed, the entire area should be proofrolled with heavy, rubber tire construction equipment, to aid in delineating areas of soft or otherwise unsuitable soil. Once unsuitable materials have been remediated, and the subgrade has passed the proofroll test, the existing and undocumented fill that was removed can be evaluated for reuse as structural fill.

### Fill Material Types

Fill required to achieve design grade should be classified as structural fill and general fill. Structural fill is material used below, or within 5 feet of structures, pavements or constructed slopes. General fill is material used to achieve grade outside of these areas. Earthen materials used for structural and general fill should meet the following material property requirements:

| Fill Type <sup>1</sup>             |   |  | Gradation  |  |  |
|------------------------------------|---|--|--|--|--|
| гш туре                            | Аррисанон   | Size   | Percent finer by<br>weight   | Plasticity   |  |
| Structural Fill <sup>2</sup>       | Below foundations,<br>concrete slabs or other<br>structural areas, and<br>within 5 feet of the<br>building perimeter            | 4 inch<br>No. 4 Sieve<br>No. 200 Sieve   | 100<br>25 - 60<br>< 15 max   | Liquid Limit 20<br>max<br>Plasticity Index 5<br>max  |  |
| Stabilization<br>Fill <sup>2</sup> | Fill used to stabilize soft,<br>potentially pumping<br>subgrade   | 4 inch<br>No. 200 Sieve  | 100<br>5 max   | -  |  |
| Onsite Fill                        | General Fill unless it<br>can meet Structural Fill<br>requirements  | 4 inch<br>No. 200 Sieve  | 100<br>< 35  | Liquid Limit 35<br>max<br>Plasticity Index 15<br>max |  |
| Drainage Fill                      | Gradation No. 1 from<br>UFC 3-250-01<br>recommended for<br>material used below<br>pavements needed for<br>drainage <sup>3</sup> | <sup>3</sup> ∕₄ inch<br>1∕₂ inch<br>3/8 inch<br>No. 4 Sieve<br>No. 8 Sieve<br>No. 16 Sieve | 100 (-5 tolerance)<br>78 (±8 tolerance)<br>63 (±8 tolerance)<br>38 (±8 tolerance)<br>19 (±6 tolerance)<br>4 (±4 tolerance) | -  |  |

309th SWEG Office Building = HAFB, Utah April 11, 2022 = Terracon Project No. 61225006



|   |   |   | Requirements               |                             |
|---|---|---|----------------------------|-----------------------------|
| Fill Type <sup>1</sup>  | Application   | Gra   | adation                    |                             |
| гш туре Аррисацон   |   | Size  | Percent finer by<br>weight | Plasticity                  |
| On-Grade Slab<br>Base Course  | Immediately below on-<br>grade slabs  | In accordance with American Concrete Institute (ACI)<br>302.1R-15 and 360R-10 |                            | rete Institute (ACI)<br>-10 |
| <ol> <li>All fill should consist of approved materials that are free of organic matter and debris. Frozen material should<br/>not be used, and fill should not be placed on a frozen subgrade. A sample of each material type should be<br/>submitted to the geotechnical engineer for evaluation.</li> </ol> |   |   |                            |                             |
| Cruched and   | Cruched angular reak with more than 50 percent with two frequence forces on per ASTM D 5921 |   |                            |                             |

- 2. Crushed angular rock with more than 50 percent with two fractured faces as per ASTM D 5821.
- 3. Gradation 2 or 3 could also be used as found in Table 20-5 of UFC 3-250-01.

Materials proposed for use as Structural Fill should be tested to verify conformance with the materials requirements presented above.

#### **Fill Compaction Requirements**

| Item   | Structural Fill   | General Fill   |
|--|---|--|
| Maximum Lift<br>Thickness                                | 8 inches or less in loose thickness when heavy,<br>self-propelled compaction equipment is used<br>4 to 6 inches in loose thickness when hand-<br>guided equipment (i.e. jumping jack or plate<br>compactor) is used                   | Same as Structural fill                                |
| Minimum<br>Compaction<br>Requirements <sup>1, 2, 3</sup> | <ul> <li>100% of maximum dry density for Structural Fill<br/>(cohesionless) soils per HAFB Design Standard<br/>Section 3.7.8</li> <li>95% of max. below foundations, below floor<br/>slabs and pavements for native soils.</li> </ul> |  |
| Water Content<br>Range <sup>1</sup>                      | Low plasticity cohesive: -2% to +3% of optimum<br>Granular: -3% to +3% of optimum   | As required to achieve min.<br>compaction requirements |

Structural and general fill should meet the following compaction requirements.

 Maximum density and optimum water content for cohesive soils determined by Method 106 of MIL-STD-621 using CE55 compaction effort or granular soils determined by Modified Proctor (ASTM D1557).

### **Utility Trench Backfill**

For low permeability subgrades, utility trenches are a common source of water infiltration and migration. Utility trenches penetrating beneath the building should be effectively sealed to restrict water intrusion and flow through the trenches, which could migrate below the building. The trench



should provide an effective trench plug that extends at least 5 feet from the face of the building exterior. The plug material should consist of cementitious flowable fill or low permeability clay. The trench plug material should be placed to surround the utility line. If used, the clay trench plug material should be placed and compacted to comply with the water content and compaction recommendations for structural fill stated previously in this report.

### Grading and Drainage

All grades must provide effective drainage away from the building during and after construction and should be maintained throughout the life of the structure. Water retained next to the building can result in soil movements greater than those discussed in this report. Greater movements can result in unacceptable differential floor slab and/or foundation movements, cracked slabs and walls, and roof leaks. The roof should have gutters/drains with downspouts that discharge onto splash blocks at a distance of at least 10 feet from the building.

Exposed ground should be sloped and maintained at a minimum 5% away from the building for at least 10 feet beyond the perimeter of the building. Locally, flatter grades may be necessary to transition ADA access requirements for flatwork. After building construction and landscaping have been completed, final grades should be verified to document effective drainage has been achieved. Grades around the structure should also be periodically inspected and adjusted, as necessary, as part of the structure's maintenance program. Where paving or flatwork abuts the structure, a maintenance program should be established to effectively seal and maintain joints and prevent surface water infiltration.

### **Earthwork Construction Considerations**

Shallow excavations for the proposed structure are anticipated to be accomplished with conventional construction equipment. Upon completion of filling and grading, care should be taken to maintain the subgrade water content prior to construction of floor slabs. Construction traffic over the completed subgrades should be avoided. The site should also be graded to prevent ponding of surface water on the prepared subgrades or in excavations. Water collecting over or adjacent to construction areas should be removed. If the subgrade freezes, desiccates, saturates, or is disturbed, the affected material should be removed, or the materials should be scarified, moisture conditioned, and recompacted prior to floor slab construction.

As a minimum, excavations should be performed in accordance with OSHA 29 CFR, Part 1926, Subpart P, "Excavations" and its appendices, and in accordance with any applicable local, and/or state regulations.

Construction site safety is the sole responsibility of the contractor who controls the means, methods, and sequencing of construction operations. Under no circumstances shall the information provided herein be interpreted to mean Terracon is assuming responsibility for



construction site safety, or the contractor's activities; such responsibility shall neither be implied nor inferred.

#### **Construction Observation and Testing**

The earthwork efforts should be monitored under the direction of the Geotechnical Engineer. Monitoring should include documentation of adequate removal of vegetation and topsoil, proofrolling, and mitigation of areas delineated by the proofroll to require mitigation.

Each lift of compacted fill should be tested, evaluated, and reworked, as necessary, until approved by the Geotechnical Engineer prior to placement of additional lifts. Each lift of fill should be tested for density and water content at a frequency of at least one test for every 2,500 square feet of compacted fill in the building areas and 5,000 square feet in pavement areas. One density and water content test should be performed for every 50 linear feet of compacted utility trench backfill.

In areas of foundation excavations, the bearing subgrade should be evaluated under the direction of the Geotechnical Engineer. If unanticipated conditions are encountered, the Geotechnical Engineer should prescribe mitigation options.

In addition to the documentation of the essential parameters necessary for construction, the continuation of the Geotechnical Engineer into the construction phase of the project provides the continuity to maintain the Geotechnical Engineer's evaluation of subsurface conditions, including assessing variations and associated design changes.

### SHALLOW FOUNDATIONS

If the site has been prepared in accordance with the requirements noted in **Earthwork**, the following design parameters are applicable for shallow foundations.

#### **Design Parameters – Compressive Loads**

| Item   | Description  |  |  |
|--|--|--|--|
| Maximum Net Allowable Bearing pressure <sup>1, 2</sup> | 1,800 psf (foundation bearing on native fine-grained<br>soils or a minimum of 12 inches of Structural Fill over<br>the native soils) |  |  |
| Required Bearing Stratum <sup>3</sup>                  | Undisturbed native soils or structural fill overlying the<br>native fine-grained soils   |  |  |
| Minimum Foundation Dimensions                          | Columns: 30 inches<br>Continuous: 18 inches  |  |  |
| Maximum Foundation Dimensions                          | Columns:120 inchesContinuous:60 inches   |  |  |
| Ultimate Coefficient of Sliding Friction <sup>5</sup>  | 0.35 (Native Soil)<br>0.45 (Structural Fill)   |  |  |

309th SWEG Office Building = HAFB, Utah April 11, 2022 = Terracon Project No. 61225006



| ltem  | Description                   |  |
|---|-------------------------------|--|
| Minimum Embedment below                           |                               |  |
| Finished Grade <sup>6</sup>                       | Exterior footings: 36 inches  |  |
| Estimated Total Settlement from                   | Loss then shout 4 inch        |  |
| Structural Loads <sup>2</sup>                     |                               |  |
| Estimated Differential Settlement <sup>2, 7</sup> | About 1/2 of total settlement |  |

- 1. The maximum net allowable bearing pressure is the pressure in excess of the minimum surrounding overburden pressure at the footing base elevation. An appropriate factor of safety has been applied. Values assume that exterior grades are no steeper than 20% within 10 feet of structure.
- 2. Values provided are for maximum loads noted in Project Description.
- 3. Unsuitable or soft soils should be over-excavated and replaced per the recommendations presented in the **Earthwork**.
- 4. Use of passive earth pressures require the sides of the excavation for the spread footing foundation to be nearly vertical and the concrete placed neat against these vertical faces or that the footing forms be removed and compacted structural fill be placed against the vertical footing face.
- 5. Can be used to compute sliding resistance where foundations are placed on suitable soil/materials. Should be neglected for foundations subject to net uplift conditions.
- 6. Embedment necessary to minimize the effects of frost and/or seasonal water content variations. For sloping ground, maintain depth below the lowest adjacent exterior grade within 5 horizontal feet of the structure.
- 7. Differential settlements are as measured over a span of 50 feet.

#### **Design Parameters - Uplift Loads**

Uplift resistance of spread footings can be developed from the effective weight of the footing and the overlying soils. As illustrated on the subsequent figure, the effective weight of the soil prism defined by diagonal planes extending up from the top of the perimeter of the foundation to the ground surface at an angle,  $\theta$ , of 32 degrees from the vertical can be included in uplift resistance. The maximum allowable uplift capacity should be taken as a sum of the effective weight of soil plus the dead weight of the foundation, divided by an appropriate factor of safety. A maximum total unit weight of 110 pcf should be used for the backfill.

Terracon GeoReport

309th SWEG Office Building HAFB, Utah April 11, 2022 Terracon Project No. 61225006



### **Foundation Construction Considerations**

As noted in **Earthwork**, the footing excavations should be evaluated under the direction of the Geotechnical Engineer. The base of all foundation excavations should be free of water and loose soil, prior to placing concrete. Concrete should be placed soon after excavating to reduce bearing soil disturbance. Care should be taken to prevent wetting or drying of the bearing materials during construction. Excessively wet or dry material or any loose/disturbed material in the bottom of the footing excavations should be removed/reconditioned before foundation concrete is placed.

If unsuitable bearing soils are encountered at the base of the planned footing excavation, the excavation should be extended deeper to suitable soils, and the footings could bear directly on these soils at the lower level or on lean concrete backfill placed in the excavations. This is illustrated on the sketch below.





Over-excavation for structural fill placement below footings should be conducted as shown below. The over-excavation should be backfilled up to the footing base elevation, with structural fill material placed, as recommended in the **Earthwork** section.



### SEISMIC CONSIDERATIONS

The seismic design requirements for buildings and other structures are based on Seismic Design Category. Site Classification is required to determine the Seismic Design Category for a structure. The Site Classification is based on the upper 100 feet of the site profile defined by a weighted average value of either shear wave velocity, standard penetration resistance, or undrained shear strength in accordance with Section 20.4 of ASCE 7 and the International Building Code (IBC). Based on the soil properties encountered at the site and as described on the exploration logs and results, it is our professional opinion that the **Seismic Site Classification is D**. Subsurface explorations at this site were extended to a maximum depth of 26½ feet. The site properties below the boring depth to 100 feet were estimated based on our experience and knowledge of geologic conditions of the general area<sup>3</sup>. Additional deeper borings or geophysical testing may be performed to confirm the conditions below the current boring depth.

### LIQUEFACTION

Based on the type of subsurface soils explored and published Liquefaction maps seen in **Supporting Information**, the site is mapped to have a very low liquefaction potential.

<sup>&</sup>lt;sup>3</sup> McDonald, Greg N., Ashland, Francis X., Earthquake Site-Conditions Map for the Wasatch Front Urban Corridor, Utah, Plate 1, Utah Geological Survey Special Study 125, 2008.



## FLOOR SLABS

Design parameters for floor slabs assume the requirements for **Earthwork** have been followed. Specific attention should be given to positive drainage away from the structure and positive drainage of the aggregate base beneath the floor slab.

### Floor Slab Design Parameters

| Item   | Description  |  |  |  |  |
|--|--|--|--|--|--|
| Floor Slab Support <sup>1</sup>  | Minimum 6 inches of crushed gravel (Slab Base Course) underlain by properly prepared native soil, or Structural Fill extending to suitable native soils.             |  |  |  |  |
| Estimated Modulus of Subgrade Reaction <sup>2</sup>  | <ul> <li>Native Subgrade: 125 pounds per square inch per inch (psi/in)</li> <li>Structural Fill: 175 psi/in for point loads<sup>3</sup> (Structural Fill)</li> </ul> |  |  |  |  |
| 1. Floor slabs should be structurally independent of building footings or walls to reduce the possibility of floor slab cracking caused by differential movements between the slab and foundation. |  |  |  |  |  |

2. Modulus of subgrade reaction is an estimated value based upon our experience with the subgrade condition, the requirements noted in **Earthwork**, and the floor slab support as noted in this table. It is provided for point loads. For large area loads the modulus of subgrade reaction would be lower.

The use of a vapor retarder should be considered beneath concrete slabs on grade covered with wood, tile, carpet, or other moisture sensitive or impervious coverings, or when the slab will support equipment sensitive to moisture. When conditions warrant the use of a vapor retarder, the slab designer should refer to ACI 302 and/or ACI 360 for procedures and cautions regarding the use and placement of a vapor retarder.

Saw-cut control joints should be placed in the slab to help control the location and extent of cracking. For additional recommendations refer to the ACI Design Manual. Joints or cracks should be sealed with a water-proof, non-extruding compressible compound specifically recommended for heavy duty concrete pavement and wet environments.

Where floor slabs are tied to perimeter walls or turn-down slabs to meet structural or other construction objectives, our experience indicates differential movement between the walls and slabs will likely be observed in adjacent slab expansion joints or floor slab cracks beyond the length of the structural dowels. The Structural Engineer should account for potential differential settlement through use of sufficient control joints, appropriate reinforcing or other means.

Settlement of floor slabs supported on existing fill materials cannot be accurately predicted, but could be larger than normal and result in some cracking. Mitigation measures, as noted in **Existing Fill** within **Earthwork**, are critical to the performance of floor slabs. In addition to the mitigation measures, the floor slab can be stiffened by adding steel reinforcement, grade beams and/or post-tensioned elements.



### **Floor Slab Construction Considerations**

Finished subgrade, within and for at least 10 feet beyond the floor slab, should be protected from traffic, rutting, or other disturbance and maintained in a relatively moist condition until floor slabs are constructed. If the subgrade should become damaged or desiccated prior to construction of floor slabs, the affected material should be removed and structural fill should be added to replace the resulting excavation. Final conditioning of the finished subgrade should be performed immediately prior to placement of the floor slab support course.

The Geotechnical Engineer should approve the condition of the floor slab subgrades immediately prior to placement of the floor slab support course, reinforcing steel, and concrete. Attention should be paid to high traffic areas that were rutted and disturbed earlier, and to areas where backfilled trenches are located.

### **PAVEMENTS**

### **General Pavement Comments**

Pavement designs are provided for the traffic conditions and pavement life conditions as noted in **Project Description** and in the following sections of this report. A critical aspect of pavement performance is site preparation. Pavement designs noted in this section must be applied to the site which has been prepared as recommended in the **Earthwork** section.

All paved areas should have adequate crown and slope to provide positive drainage and prevent ponding of surface water and infiltration below the pavement section. Water collection devices such as gutters and ditches should be incorporated into the parking lot design to prevent percolation of surface water below the pavement section.

### **Pavement Design Parameters**

Pavement sections were developed using PCASE design methodology and traffic volumes summarized in the **Project Description** section. Pavement sections were developed for vehicular parking lot only. Pavement sections for truck traffic areas are not part of this scope of work. If actual truck traffic is determined for the site, we should be notified so the pavement sections can be modified for the truck traffic. The life span used during pavement calculations was 25 years according to UFC 3-201-01 Section 4-1. Design traffic and estimated 18-kip Equivalent Single Axle Loads (ESAL) are summarized in the following table:

| Section                         | Design ESALs <sup>1</sup> | Equivalent Passes<br>per day of<br>passenger cars <sup>2</sup> |  |  |
|---------------------------------|---------------------------|--|--|--|
| Automobile Parking (Light Duty) | 52,000                    | 500  |  |  |



- 1. Based on traffic conditions describe in the Project Description section.
- 2. See Pavement Calculations for more details on estimated traffic in Supporting Information.

We anticipate that the pavement subgrades will consist of existing native fine-grained silt and clayey soils, properly placed and compacted grading or Structural Fill prepared as discussed previously. Based on this understanding and the field blow counts and lab tests, a design California Bearing Ratio (CBR) value of 3.0 percent was conservatively chosen, which is equivalent to a subgrade resilient modulus of 5161 psi and a subgrade modulus k-value of 110 pound per cubic inch (pci). This CBR value represents the native soils or fill soils being prepared according to the recommendations presented in the **Earthwork** section.

#### **Pavement Section Thicknesses**

Long-term, the native fine-grained soils will provide generally poor support for pavements. With this in consideration we recommend the following minimum pavement sections, or approved equivalent, constructed on the properly prepared subgrade soils:

|                                    | Pavement Section Thickness<br>(Inches) |                   |                   |                     |                    |  |  |
|------------------------------------|--|-------------------|-------------------|---------------------|--------------------|--|--|
| I raffic Area                      | Asphalt<br>Cement                      | Aggregate<br>Base | Drainage<br>Layer | Separation<br>Layer | Total<br>Thickness |  |  |
| Automobile Parking<br>(Light Duty) | 4.0                                    | 8.0               | 4.0               | 4.0                 | 20.0               |  |  |

### **Pavement Construction Considerations**

As noted previously, native fine-grained soils generally provide relatively poor pavement support and are susceptible to rutting and pumping under repeated heavy vehicle traffic. Construction scheduling often involves grading and paving by separate contractors and can involve a time lapse between the end of grading operations and the commencement of paving. Disturbance, desiccation, or wetting of the subgrade soils between grading and paving can result in deterioration of the previously completed subgrade. A non-uniform subgrade can result in poor pavement performance and local failures relatively soon after pavements are constructed.

Prior to placing fill for pavement sections, native clay soils should be scarified, moisture conditioned and compacted according to the recommendations presented in the **Earthwork** section. If a significant precipitation event occurs after the evaluation or if the surface becomes disturbed, the subgrade should be reviewed by a Terracon representative immediately prior to paving. The subgrade should be in its finished form at the time of the final review.



We recommend a program of observation and testing during construction to assist the owner managing the quality assurance of the construction. Pavement materials should be inspected and tested during construction and proper placement and compaction is essential to achieve the intended design life. A Terracon representative should observe proofrolling of the pavement subgrade prior to paving operations to help delineate soft or disturbed areas, and the pavement subgrade should be prepared in accordance with the recommendations presented in the **Earthwork** section.

Pavement sections have not been designed to support construction equipment. As such, the contractor should protect pavement areas from damage that may result from construction traffic.

#### **Pavement Maintenance**

The pavement sections represent minimum recommended thicknesses and, as such, periodic maintenance should be anticipated. Therefore, preventive maintenance should be planned and provided for through an on-going pavement management program. Maintenance activities are intended to slow the rate of pavement deterioration and to preserve the pavement investment. Maintenance consists of both localized maintenance (e.g., crack and joint sealing and patching) and global maintenance (e.g., surface sealing). Preventive maintenance is usually the priority when implementing a pavement maintenance program. Additional engineering observation is recommended to determine the type and extent of a cost-effective program. Even with periodic maintenance, some movements and related cracking may still occur, and repairs may be required.

Pavement performance is affected by its surroundings. In addition to providing preventive maintenance, the civil engineer should consider the following recommendations in the design and layout of pavements:

- Final grade adjacent to paved areas should slope down from the edges at a minimum 2%.
- Subgrade and pavement surfaces should have a minimum 2% slope to promote proper surface drainage.
- Install below pavement drainage systems surrounding areas anticipated for frequent wetting.
- Install joint sealant and seal cracks immediately.
- Seal all landscaped areas in or adjacent to pavements to reduce moisture migration to subgrade soils.
- Place compacted, low permeability backfill against the exterior side of curb and gutter.
- Place curb, gutter and/or sidewalk directly on clay subgrade soils rather than on unbound granular base course materials.

309th SWEG Office Building HAFB, Utah April 11, 2022 = Terracon Project No. 61225006



### **FROST CONSIDERATIONS**

The soils on this site are frost susceptible, and small amounts of water can affect the performance of the slabs on-grade, and sidewalks. Exterior slabs should be anticipated to heave during winter months. If frost action needs to be eliminated in critical areas, we recommend the use of non-frost susceptible (NFS) fill or structural slabs (for instance, structural stoops in front of building doors). Placement of NFS material in large areas may not be feasible; however, the following recommendations are provided to help reduce potential frost heave:

- Provide surface drainage away from the building and slabs, and toward the site storm drainage system.
- Install drains around the perimeter of the building, stoops, below exterior slabs and connect them to the storm drainage system.
- Grade clayey subgrades, so groundwater potentially perched in overlying more permeable subgrades, such as sand or aggregate base, slope toward a site drainage system.
- Place NFS fill as backfill beneath slabs critical to the project.
- Place a 3 horizontal to 1 vertical (3H:1V) transition zone between NFS fill and other soils.
- Place NFS materials in critical sidewalk areas.

### CORROSIVITY

The table below lists the results of laboratory soluble sulfate, soluble chloride, electrical resistivity, and pH testing. The values may be used to estimate potential corrosive characteristics of the onsite soils with respect to contact with the various underground materials which will be used for project construction.

| Corrosivity Test Results Summary |                           |                  |                           |                            |                                     |     |  |  |
|----------------------------------|---------------------------|------------------|---------------------------|----------------------------|-------------------------------------|-----|--|--|
| Boring                           | Sample<br>Depth<br>(feet) | Soil Description | Soluble<br>Sulfate<br>(%) | Soluble<br>Chloride<br>(%) | Electrical<br>Resistivity<br>(Ω-cm) | рН  |  |  |
| B-1                              | 5 <b>-</b> 6½             | Lean Clay        | 293                       | 69                         | 5,472                               | 7.7 |  |  |

Results of water-soluble sulfate testing indicate that samples of the on-site soils have an exposure class of S1 when classified in accordance with Table 19.3.1.1 of the American Concrete Institute (ACI) Design Manual. Concrete should be designed in accordance with the provisions of the ACI Design Manual, Section 318, Chapter 19. To improve sulfate resistance of concrete in severe sulfate exposure when Type V cement is not available, the following should be considered:

- Use of Type I-II modified cement for sulfate resistance
- Cement should have a tricalcium aluminate content of not more than 8%.

309th SWEG Office Building HAFB, Utah April 11, 2022 Terracon Project No. 61225006



- Concrete mixture should contain at least 20% Class F fly ash.
- Provide air-entrainment of 4% to 7% by volume.
- Lower the water to cement ratio to 0.4 to 0.45.

### **GENERAL COMMENTS**

Our analysis and opinions are based upon our understanding of the project, the geotechnical conditions in the area, and the data obtained from our site exploration. Natural variations will occur between exploration point locations or due to the modifying effects of construction or weather. The nature and extent of such variations may not become evident until during or after construction. Terracon should be retained as the Geotechnical Engineer, where noted in this report, to provide observation and testing services during pertinent construction phases. If variations appear, we can provide further evaluation and supplemental recommendations. If variations are noted in the absence of our observation and testing services on-site, we should be immediately notified so that we can provide evaluation and supplemental recommendations.

Our Scope of Services does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be undertaken.

Our services and any correspondence or collaboration through this system are intended for the sole benefit and exclusive use of our client for specific application to the project discussed and are accomplished in accordance with generally accepted geotechnical engineering practices with no third-party beneficiaries intended. Any third-party access to services or correspondence is solely for information purposes to support the services provided by Terracon to our client. Reliance upon the services and any work product is limited to our client, and is not intended for third parties. Any use or reliance of the provided information by third parties is done solely at their own risk. No warranties, either express or implied, are intended or made.

Site characteristics as provided are for design purposes and not to estimate excavation cost. Any use of our report in that regard is done at the sole risk of the excavating cost estimator as there may be variations on the site that are not apparent in the data that could significantly impact excavation cost. Any parties charged with estimating excavation costs should seek their own site characterization for specific purposes to obtain the specific level of detail necessary for costing. Site safety, and cost estimating including, excavation support, and dewatering requirements/design are the responsibility of others. If changes in the nature, design, or location of the project are planned, our conclusions and recommendations shall not be considered valid unless we review the changes and either verify or modify our conclusions in writing.

# **FIGURES**

### **Contents:**

GeoModel

#### **GEOMODEL** CRSA - HAFB SWEG Office 📕 Hill Air Force Base, UT Terracon Project No. 61225006



This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.

| Model Layer | Layer Name General Description |   |  |  |  |  |
|-------------|--------------------------------|---|--|--|--|--|
| 1           | Fill                           | Clay/Sand disturbed                             |  |  |  |  |
| 2           | CL                             | Lean Clay with varying amounts of sand and silt |  |  |  |  |
| 3           | ML                             | Silt with varying amounts of sand and clay      |  |  |  |  |



Silty Sand with Gravel

Silty Clay

Lean Clay with Sand

Lean Clay

Silt with Sand

Sandy Silt

Sandy Lean Clay

NOTES:

Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground

<u>llerracon</u>

surface.

# ATTACHMENTS

Responsive Resourceful Reliable



### **EXPLORATION AND TESTING PROCEDURES**

#### **Field Exploration**

| Number of Explorations    | Boring Depth (feet) | Planned Location      |  |  |  |  |
|---------------------------|---------------------|-----------------------|--|--|--|--|
| 2 borings                 | 25 or auger refusal | utilities / buildings |  |  |  |  |
| 3 hand augured test holes | 6 or auger refusal  | Retention pond areas  |  |  |  |  |

**Boring Layout and Elevations:** Unless otherwise noted, Terracon personnel provided the boring layout. Coordinates were obtained with a handheld GPS unit (estimated horizontal accuracy of about ±10 feet) and approximate elevations were obtained by interpolation from the provided topographic map. If elevations and a more precise boring layout are desired, we recommend borings be surveyed following completion of fieldwork.

Subsurface Exploration Procedures: We advanced the borings with a truck-mounted rotary drill rig using continuous flight augers (solid stem and/or hollow stem, as necessary, depending on soil conditions). Four samples were obtained in the upper 10 feet of each boring and at intervals of 5 feet thereafter. In the thin-walled tube sampling procedure, a thin-walled, seamless steel tube with a sharp cutting edge was pushed hydraulically into the soil to obtain a relatively undisturbed sample. In the split-barrel sampling procedure, a standard 2-inch outer diameter split-barrel sampling spoon was driven into the ground by a 140-pound automatic hammer falling a distance of 30 inches. The number of blows required to advance the sampling spoon the last 12 inches of a normal 18-inch penetration is recorded as the Standard Penetration Test (SPT) resistance value. The SPT resistance values, also referred to as N-values, are indicated on the boring logs at the test depths. A 3-inch O.D. split-barrel sampling spoon with 2.5-inch I.D. ring lined sampler was used for sampling in the upper 10 feet. Ring-lined, split-barrel sampling procedures are similar to standard split spoon sampling procedure; however, blow counts are typically recorded for 6-inch intervals for a total of 12 inches of penetration. We observed and recorded groundwater levels during drilling and sampling. For safety purposes, all borings were backfilled with auger cuttings after their completion. Pavements were patched with cold-mix asphalt and/or pre-mixed concrete, as appropriate.

The sampling depths, penetration distances, and other sampling information was recorded on the field boring logs. The samples were placed in appropriate containers and taken to our soil laboratory for testing and classification by a Geotechnical Engineer. Our exploration team prepared field boring logs as part of the drilling operations. These field logs included visual classifications of the materials encountered during drilling and our interpretation of the subsurface conditions between samples. Final boring logs were prepared from the field logs. The final boring logs represent the Geotechnical Engineer's interpretation of the field logs and include modifications based on observations and tests of the samples in our laboratory.



**Percolation Tests:** Three percolation tests were completed at the boring locations P-3, P-4 and P-5 as shown on the Exploration Plan. An approximately four-inch diameter test hole was hand augered to approximately six feet below the existing site grade inside the existing detention ponds. A four-inch diameter, solid pvc, pipe was inserted, and the annular space between the soil and the exterior of the pipe was backfilled with bentonite chips and soil cuttings. The pipe was then filled with water and the soil allowed to saturate. After saturation, the pipe was refilled with water and the time required for the water level to drop incrementally was measured until a stabilized rate was achieved. Rates were considered to be stable when the rate of percolation appeared to be relatively constant.

### Laboratory Testing

The project engineer reviewed the field data and assigned laboratory tests to understand the engineering properties of the various soil strata, as necessary, for this project. Procedural standards noted below are for reference to methodology in general. In some cases, variations to methods were applied because of local practice or professional judgment. Standards noted below include reference to other, related standards. Such references are not necessarily applicable to describe the specific test performed.

- ASTM D2216 Standard Test Methods for Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass
- ASTM D4318 Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
- ASTM D422 Standard Test Method for Particle-Size Analysis of Soils
- ASTM D2435/D2435M Standard Test Methods for One-Dimensional Consolidation Properties of Soils Using Incremental Loading
- Soil corrosivity tests including pH (ASTM G51), water soluble sulfate (ASTM C1580), sulfide ion (ASTM D4658), total salts (ASTM D1125), red-ox potential (ASTM D1498), chloride ion (ASTM D512) and Miller box resistivity (ASTM G187) on one sample (results summarized in the Soil Corrosivity section and test reports included in the Exploration Results section)

The laboratory testing program often included examination of soil samples by an engineer. Based on the material's texture and plasticity, we described and classified the soil samples in accordance with the Unified Soil Classification System.

### SITE LOCATION AND EXPLORATION PLANS

#### **Contents:**

Site Location Plan Exploration Plan (2) Site Geologic Map

Note: All attachments are one page unless noted above.

#### SITE LOCATION

309th SWEG Office Building = HAFB, Utah April 11, 2022 = Terracon Project No. 61225006





DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

#### **EXPLORATION PLAN**

309th SWEG Office Building = HAFB, Utah April 11, 2022 = Terracon Project No. 61225006





DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

#### **EXPLORATION PLAN**

309th SWEG Office Building = HAFB, Utah April 11, 2022 = Terracon Project No. 61225006





DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

#### **GEOLOGIC MAP OVERLAY**

309th SWEG Office Building = HAFB, Utah April 11, 2022 = Terracon Project No. 61225006





DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

### **EXPLORATION RESULTS**

#### **Contents:**

Boring Logs (B-1 through P-5) Percolation Results (3) Laboratory Summary Atterberg Limits Consolidation/Swell (16) Corrosivity Results

Note: All attachments are one page unless noted above.

|                 | BORING LOG NO. B-1 Page 1 of 1   |  |                                    |                             |             |                        |                     |                      |                          |                     |               |  |
|-----------------|--|--|------------------------------------|-----------------------------|-------------|------------------------|---------------------|----------------------|--------------------------|---------------------|---------------|--|
| F               | PROJECT: CRSA - HAFB SWEG Office   |  |                                    | T: C                        | RS/         |                        |                     |                      |                          |                     |               |  |
| Ş               | SITE:  | Indigo Street<br>Hill Air Force Base, UT   |                                    | 3                           | ait I       | Lake City, UT          |                     |                      |                          |                     |               |  |
| MODEL LAYER     | GRAPHIC LOG  | LOCATION See Exploration Plan<br>Latitude: 41.1345° Longitude: -112.0150°<br>Approximate Surface Elev.: 4664 (Ft.) | DEPTH (Ft.)                        | WATER LEVEL<br>OBSERVATIONS | SAMPLE TYPE | FIELD TEST<br>RESULTS  | N160                | WATER<br>CONTENT (%) | DRY UNIT<br>WEIGHT (pcf) | ATTERBERG<br>LIMITS | PERCENT FINES |  |
|                 | 0.00   | FILL - SILTY SAND WITH GRAVEL (SM), dark brown,<br>loose   | -                                  |                             |             |                        |                     |                      |                          |                     |               |  |
| 1               |  | 4 5 4659   | 5+/-                               |                             | $\times$    | 2-2-3<br>N=5           | 14                  |                      |                          |                     |               |  |
| E.GDT 4/6       |  | LEAN CLAY WITH SAND (CL), brown, medium stiff<br>6.5 4657.   | 5+/- 5                             | -                           |             | 1-2-3<br>N=5           | 14                  | 15.5                 |                          | 26-18-8             | 71            |  |
| TATEMPLA        |  | SILTY CLAY (CL-ML), trace sand, brown, stiff   | 5+/                                |                             |             | 3-6-7<br>N=13          | 35                  | 22.2                 |                          | 27-21-6             | 87            |  |
| ACON_DA         |  | LEAN CLAY (CL), trace sand, brown, soft to stiff   | <u></u><br>10-                     |                             |             | 3-4-8                  | 22                  | 24.2                 |                          | 21 10 10            | 00            |  |
| GPJ TERK        |  |  | -                                  | -                           | $\square$   | N=12                   |                     | 24.3                 |                          | 31-19-12            | 90            |  |
| VFB SWEG .      |  |  | 15-                                |                             |             |                        |                     |                      |                          |                     |               |  |
| 2 CRSA - H      |  |  |                                    | _                           | X           | 0-1-2<br>N=3           | 6                   | 26.2                 |                          | 27-18-9             | 87            |  |
| L 61225006      |  |  | -                                  |                             |             |                        |                     |                      |                          |                     |               |  |
| OG-NO WEI       |  |  | 20-                                | -                           | X           | 0-3-2<br>N=5           | 7                   | 25.5                 |                          |                     |               |  |
| GEO SMART L     |  |  | -                                  |                             |             |                        |                     |                      |                          |                     |               |  |
| . REPORT.       |  | 26.5 4637.   | 25-<br>5+/-                        |                             |             | 2-3-3<br>N=6           | 7                   | 24.5                 |                          |                     |               |  |
| M ORIGINAL      |  | Boring Terminated at 26.5 Feet   |                                    |                             |             |                        |                     |                      |                          |                     |               |  |
| ATED FROI       | Str  | atification lines are approximate. In-situ, the transition may be gradual.   |                                    |                             |             | Hammer Type: Aut       | omatic              |                      |                          |                     |               |  |
| SEPA            | anceme   | nt Method  |                                    | -                           |             | Notes:                 |                     |                      |                          |                     |               |  |
|                 | Auvancement (Method:         See Exploration and           Hollow Stem Auger         description of field a<br>and additional data |  | ng Procedur<br>poratory proc<br>). | es for a cedures            | used        | INOLES:                |                     |                      |                          |                     |               |  |
| Ab:<br>00 SI DO | andonme<br>Boring ba   | nt Method:<br>ckfilled with auger cuttings upon completion.<br>Elevations were interpolat<br>plan                  | ed from a to                       | pograpi                     | nic site    | •                      |                     |                      |                          |                     |               |  |
| DNG             | WATER LEVEL OBSERVATIONS   |  |                                    |                             |             | Boring Started: 03-04- | -2022               | Borin                | ng Comp                  | bleted: 03-04-20    | )22           |  |
| BOR             | 91   |  | IJCON                              |                             |             | Drill Rig: Geoprobe    | Drill Rig: Geoprobe |                      |                          | Driller: Terracon   |               |  |
| THIS            | 2<br>6949 S H  |  |                                    | 00                          |             | Project No.: 61225006  |                     |                      |                          |                     |               |  |
|                |                     | BORING LO   | OG N  | О.                             | <b>B-</b> : | 2                     |         |                      | F                        | Page 1 of           | 1             |
|----------------|---------------------|---|---|--------------------------------|-------------|-----------------------|---------|----------------------|--------------------------|---------------------|---------------|
| F              | PROJ                | ECT: CRSA - HAFB SWEG Office  | CLIEN   | T: C                           | RS/         | A<br>ako City IIT     |         |                      |                          |                     |               |
| \$             | SITE:               | Indigo Street<br>Hill Air Force Base, UT  |   | 0                              |             | Lake Oity, OT         |         |                      |                          |                     |               |
| MODEL LAYER    | GRAPHIC LOG         | LOCATION See Exploration Plan<br>Latitude: 41.1342° Longitude: -112.0150°<br>Approximate Surface Elev.: 4664 (Ft.)<br>DEPTH ELEVATION (F        | .++<br>DEPTH (Ft.)                                  | WATER LEVEL<br>OBSERVATIONS    | SAMPLE TYPE | FIELD TEST<br>RESULTS | N160    | WATER<br>CONTENT (%) | DRY UNIT<br>WEIGHT (pcf) | Atterberg<br>Limits | PERCENT FINES |
| 1              | 000                 | FILL - SILTY SAND WITH GRAVEL (SM), dark brown,<br>loose  | -   | -                              |             |                       |         |                      |                          |                     |               |
| /22            | 0.00                | 4659  | 5+/-  | -                              | Д           | 1-2-2<br>N=4          | 11      |                      |                          |                     |               |
| TE.GDI 4/6     |                     | SILT WITH SAND (ML), brown, stiff   | 5-  | -                              | X           | 2-5-13                |         | 17.4                 |                          | NP                  | 71            |
| ATAI EMPLA     |                     | SILTY CLAY (CL-ML), brown, medium stiff   | -   | -                              |             |                       |         | 22.8                 |                          | 26-21-5             | 94            |
|                |                     |   | 10-   | -                              |             |                       |         | 21.7                 |                          |                     |               |
| veg .gpj tei   |                     |   | -   | _                              |             |                       |         |                      |                          |                     |               |
| SA - HAFB SV   |                     |   | 15-   | -                              |             | 1-2-4<br>N=6          | 11      | 25.3                 |                          | 25-19-6             | 91            |
| 61225006 CR    |                     | 18.0 464<br>LEAN CLAY (CL), brown, medium stiff   | -<br>6+/-   | -                              |             |                       |         |                      |                          |                     |               |
| LOG-NO WELL    |                     |   | 20-   | _                              | X           | 0-2-3<br>N=5          | 7       |                      |                          |                     |               |
| . GEO SMARI    |                     |   | -   | _                              |             |                       |         |                      |                          |                     |               |
|                |                     | 26.5 4637.  |   |                                | X           | 0-3-3<br>N=6          | 7       | 27.1                 |                          |                     |               |
| D FROM ORIGINA |                     | Bonng reminated at 20.5 Feet  |   |                                |             |                       |         |                      |                          |                     |               |
| PARATE(        | St                  | I ratification lines are approximate. In-situ, the transition may be gradual.   |   | <u> </u>                       |             | Hammer Type: Au       | tomatic |                      |                          |                     |               |
| DT VALID IF SE | vanceme<br>Hollow S | ent Method:<br>tem Auger See Exploration and Testi<br>description of field and lat<br>and additional data (If any<br>See Supporting Information | ng Procedur<br>poratory proc<br>).<br>on for explan | es for a<br>edures<br>ation of | used        | Notes:                |         |                      |                          |                     |               |
|                | andonmo<br>Boring b | ent Method:<br>ackfilled with auger cuttings upon completion.<br>Elevations were interpolat   | s.<br>ed from a to                                  | pograpł                        | nic site    | à                     |         |                      |                          |                     |               |
|                | G                   | WATER LEVEL OBSERVATIONS  |   |                                |             | Boring Started: 03-04 | -2022   | Borin                | ig Comp                  | leted: 03-04-20     | )22           |
| S BOR          | 0                   |   |   |                                | l.          | Drill Rig: Geoprobe   |         | Drille               | er: Terrao               | con                 |               |
| Ĩ              |                     | Midval  | le, UT  | UU                             |             | Project No.: 6122500  | 6       |                      |                          |                     |               |

|  |             |                    | TEST PI  | T LC   | DG N        | 10.                         | P           | -3                      |                |                      | F                        | Page 1 of           | 1             |
|--|-------------|--------------------|--|--|-------------|-----------------------------|-------------|-------------------------|----------------|----------------------|--------------------------|---------------------|---------------|
|  | Ρ           | ROJ                | ECT: CRSA - HAFB SWEG Office   | C  | LIEN        | T: C                        | RS/         | A<br>ako City IIT       |                |                      |                          |                     |               |
|  | S           | ITE:               | Indigo Street<br>Hill Air Force Base, UT   |  |             | 0                           |             | Lake oky, or            |                |                      |                          |                     |               |
|  | MODEL LAYER | <b>GRAPHIC LOG</b> | LOCATION See Exploration Plan<br>Latitude: 41.1345° Longitude: -112.0148°<br>Approximate Surface Elev.: 466<br>DEPTH ELEVA | 62 (Ft.) +/-   | DEPTH (Ft.) | WATER LEVEL<br>OBSERVATIONS | SAMPLE TYPE | FIELD TEST<br>RESULTS   | N160           | WATER<br>CONTENT (%) | DRY UNIT<br>WEIGHT (pcf) | Atterberg<br>Limits | PERCENT FINES |
|  | 3           |                    | 3.5  | 4658.5+/   |             | -                           | E.          |                         |                |                      |                          |                     |               |
| 4/6/22   | 2           |                    | 5.0  | 4657+/   | - 5-        |                             | m           |                         |                | 23.8                 |                          |                     | 93            |
| E.GDT  |             |                    | 6.0 LEAN CLAY (CL), orangish brown   | 4656+/   | <u> </u>    |                             | m           |                         |                | 24.8                 |                          | 28-20-8             | 90            |
| VATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL 61225006 CRSA - HAFB SWEG .GPJ TERRACON_DATATEMP |             | Str                | atification lines are approximate. In-situ, the transition may be gradual.   |  |             |                             |             | Hammer Type: Aut        | tomatic        |                      |                          |                     |               |
| F SEPAF  | Adva        |                    | nt Method: See Exploration ar  | nd Testing   | Procedure   | es for a                    | 1           | Notes:                  |                |                      |                          |                     |               |
| S NOT VALID I  | Abar        | ndonme             | description of field and additional date see Supporting Inf symbols and abbre symbols and abbre                            | and labora<br>(If any).<br>formation f<br>eviations. | atory proc  | edures<br>ation of          | used        | Percolation test at th  | ne bottom of l | hole                 |                          |                     |               |
| SI DOJ   |             |                    | WATER LEVEL OBSERVATIONS   | terpolated   | from a top  | ograpł                      | nic site    |                         |                |                      |                          |                     |               |
| JRING  |             | Gr                 | roundwater not encountered   |  |             | זר                          |             | Test Pit Started: 03-04 | 4-2022         | Test                 | Pit Com                  | pleted: 03-04-2     | 2022          |
| THIS BC  |             |                    | 6949 S   | High Tech<br>Midvale,                                | Dr Ste 10   | 00                          |             | Project No.: 61225006   | 6              | Oper                 | ator: le                 | TACON               |               |

|   |   | TE  | ST PIT L   | .OG N  | 10.                                       | P  | -4                              |              |                      | I                        | Page 1 of           | 1             |
|---|---|---|--|--|---|--|---------------------------------|--------------|----------------------|--------------------------|---------------------|---------------|
|   | PROJ  | ECT: CRSA - HAFB SWEG Office  |  | CLIEN  | T: C<br>S                                 | RS/<br>alt I   | A<br>.ake City, UT              |              |                      |                          |                     |               |
|   | SITE:                                       | Indigo Street<br>Hill Air Force Base, UT  |  |  | •   |  | <b>,</b> ,                      |              |                      |                          |                     |               |
| MODEL LAYER   | GRAPHIC LOG                                 | LOCATION See Exploration Plan<br>Latitude: 41.1343° Longitude: -112.0148°<br>Approximate Surf           | ace Elev.: 4662 (Ft.)<br>ELEVATION (f  | DEPTH (Ft.)  | WATER LEVEL<br>OBSERVATIONS               | SAMPLE TYPE  | FIELD TEST<br>RESULTS           | N160         | WATER<br>CONTENT (%) | DRY UNIT<br>WEIGHT (pcf) | Atterberg<br>Limits | PERCENT FINES |
| 23  |   | LEAN CLAY (CL), trace sand, orangish brown,   | stiff  | -  | -   | E Constantino de la constant |                                 |              |                      |                          |                     |               |
| T 4/6/:   |   |   |  | 5 -  | -   |  |                                 |              | 23.8                 |                          |                     | 89            |
| Ц<br>Ш<br>Ш   |   | 6.0<br>Test Pit Terminated at 6 Feet  | 465  | 6+/-   |   | 35   |                                 |              | 26.1                 |                          |                     | 92            |
| ED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL 61225006 CRSA - HAFB SWEG. GPJ. TERRACON_DATATEM |   |   |  |  |   |  |                                 |              |                      |                          |                     |               |
| PARATI  | St  | ratification lines are approximate. In-situ, the transition may be grade                                | ual.   |  | 4   | . 1  | Hammer Type: Au                 | tomatic      | •                    |                          |                     |               |
| OG IS NOT VALID IF SEF  | vanceme<br>Hollow S<br>andonme<br>Boring ba | ent Method:<br>tem Auger desc<br>and a<br>set Method:<br>ackfilled with auger cuttings upon completion. | Exploration and Testi<br>ription of field and lat<br>additional data (If any<br>Supporting Informatic<br>iols and abbreviation<br>ations were interpolat | ng Procedure<br>poratory proc<br>).<br>on for explana<br>s.<br>ed from a top | es for a<br>edures<br>ation of<br>pograph | used<br>nic site   | Notes:<br>Percolation test at t | ne bottom of | hole                 |                          |                     |               |
|   | G   | WATER LEVEL OBSERVATIONS  | Gee  | 200  |   |  | Test Pit Started: 03-0          | 4-2022       | Test                 | Pit Com                  | pleted: 03-04-2     | 2022          |
| HIS BOF   | 5.  |   | 6949 S High T  | ech Dr Ste 10  |   | ł.   | Excavator: Geoprobe             |              | Oper                 | rator: Te                | rracon              |               |
| É 📔   |   |   | Midva  | le, UT   |   |  | Project No.: 6122500            | 6            |                      |                          |                     |               |

|  |               |                 | TEST   |  | .OG                               | NO                          | . P              | -5  |              |                      | I                        | Page 1 of           | 1             |
|--|---------------|-----------------|--|--|-----------------------------------|-----------------------------|------------------|---|--------------|----------------------|--------------------------|---------------------|---------------|
| Γ  | PR            | OJI             | ECT: CRSA - HAFB SWEG Office   |  | CLIEN                             | IT: C                       | RS/              | A<br>ake City UT                            |              |                      |                          |                     |               |
|  | SIT           | E:              | Indigo Street<br>Hill Air Force Base, UT   |  |                                   | -                           |                  |   |              |                      |                          |                     |               |
| MODEL LAVER  |               | GRAPHIC LOG     | LOCATION See Exploration Plan<br>Latitude: 41.1366° Longitude: -112.0147°<br>Approximate Surface E | iev.: 4660 (Ft.)   | DEPTH (Ft.)                       | WATER LEVEL<br>OBSERVATIONS | SAMPLE TYPE      | FIELD TEST<br>RESULTS                       | N160         | WATER<br>CONTENT (%) | DRY UNIT<br>WEIGHT (pcf) | Atterberg<br>Limits | PERCENT FINES |
|  |               |                 | SANDY LEAN CLAY (CL), orangish brown   |  |                                   |                             | m                |   |              |                      |                          |                     |               |
| 2  |               |                 |  |  |                                   |                             | m                |   |              | 24.2                 | -                        |                     | 84            |
| .GDT 4/6   |               |                 | 6.0  | 465  | 5 -                               |                             |                  |   |              |                      |                          |                     |               |
| EPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL 61225006 CRSA - HAFB SWEG .GPJ TERRACON_DATATEMPLA'<br> |               | Stra            | atification lines are approximate. In-situ, the transition may be gradual.                         |  |                                   |                             |                  | Hammer Type: Au                             | tomatic      |                      |                          |                     |               |
| ALID IF 5  | Vanc<br>Hollo | emer<br>ow Ste  | em Auger See Explor<br>and addition  | ration and Testi<br>of field and lak<br>onal data (If any<br>orting Informatic | ng Procedu<br>poratory pro<br>/). | res for a<br>cedures        | a<br>s used<br>f | Notes:<br>Percolation test at t             | he bottom of | hole                 |                          |                     |               |
| OG IS NOT  | ando<br>Borir | onmer<br>ng bao | nt Method:<br>ckfilled with auger cuttings upon completion.<br>Elevations<br>plan.                 | nd abbreviation:<br>were interpolat  | s.<br>ted from a to               | pograp                      | hic site         | •   |              |                      |                          |                     |               |
| SING   |               | Gro             | WATER LEVEL OBSERVATIONS       pundwater not encountered   | Brr  | 20                                |                             |                  | Test Pit Started: 03-0                      | 4-2022       | Test                 | Pit Com                  | pleted: 03-04-2     | 2022          |
| THIS BOI   |               |                 |  | 6949 S High To<br>Midva  | ech Dr Ste 1<br>Ile, UT           | 00                          |                  | Excavator: Geoprobe<br>Project No.: 6122500 | 6            | Oper                 | rator: Te                | rracon              |               |

| Fiel       | d Perco               | olation F       | Rate Te                                   | est                                    | llerra              | acon                                |
|------------|-----------------------|-----------------|---|--|---------------------|-------------------------------------|
| 1 101      |                       | Jacon           |   |  | Test Hole           | P3                                  |
| Project Na | ame: HAFE             | 3 SWEG          |   |  | Date: 03/4/202      | 2                                   |
| Terracon   | Project No            | o.: 6122500     | )6  |  | Hole Diameter       | (inches): 4                         |
| Eng./Tech  | ι.: Kris Po           | well            |   |  | Hole Depth (inc     | ches): 72                           |
| Time       | Length of<br>Interval | Total<br>Time   | Beginning<br>Depth to<br>Water<br>Surface | Ending<br>Depth to<br>Water<br>Surface | Water Level<br>Drop | Percolation Rate<br>During Interval |
|            | (min)                 | (min)           | (in)                                      | (in)                                   | (in)                | (min/in)                            |
| 11:00      | 30                    | 0               | 0.00                                      | 0.00                                   | 0.00                |                                     |
| 11:05      | 30                    | 30              | 0.00                                      | 1.75                                   | 1.75                | 17.14                               |
| 11:10      | 30                    | 60              | 1.75                                      | 3.50                                   | 1.75                | 17.14                               |
| 11:15      | 30                    | 90              | 3.50                                      | 5.25                                   | 1.75                | 17.14                               |
| 11:20      | 30                    | 120             | 5.25                                      | 7.00                                   | 1.75                | 17.14                               |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
| Lithology: |                       |                 |   | <u> </u>                               | !                   |                                     |
|            | 0 to 3.5 ft           | Sandy Silt      | (ML)                                      |  |                     |                                     |
| <b> </b>   | 3.5 to 5 ft           | Silty Clay      | (CL-ML)                                   | (01)                                   | ļ!                  |                                     |
|            | 5 to 6 tt             | Sandy Lear      | n Clay                                    | (CL)                                   | <sup>1</sup>        |                                     |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
| ┣───       | <sup> </sup>          | <b> </b>        | <sup>!</sup>                              | [                                      | <u> </u> !          |                                     |
|            |                       |                 |   |  | <u> </u> ′          |                                     |
|            | <u> </u>              |                 |   |  | <u> </u>            |                                     |
|            |                       |                 |   |  |                     |                                     |
| REMARKS    | 3: Bottom o           | f test pit is a | approximate                               | ly 6 feet be                           | low site grade.     |                                     |

| Fiel       | d Perco               | plation I       | Rate Te                                   | est                                    | Test Hole           | <b>əcon</b><br>P4                   |
|------------|-----------------------|-----------------|---|--|---------------------|-------------------------------------|
| Proiect Na | ame: HAFE             | 3 SWEG          |   |  | Date: 03/04/20      | 22                                  |
| Terracon   | Proiect No            | .: 6122500      | )6  |  | Hole Diameter       | <br>(inches): 4                     |
| Eng./Tech  | n.: Kris Pov          | well            |   |  | Hole Depth (inc     | (incince): 1                        |
| Time       | Length of<br>Interval | Total<br>Time   | Beginning<br>Depth to<br>Water<br>Surface | Ending<br>Depth to<br>Water<br>Surface | Water Level<br>Drop | Percolation Rate<br>During Interval |
| 40.00      | (min)                 | (min)           | (in)                                      | (in)                                   | (in)                | (min/in)                            |
| 13:22      | 30                    | 0               | 0.00                                      | 0.00                                   | 0.00                |                                     |
| 13:27      | 30                    | 30              | 0.00                                      | 0.38                                   | 0.38                | 80.00                               |
| 13:32      | 30                    | 60              | 0.38                                      | 0.63                                   | 0.25                | 120.00                              |
| 13:37      | 30                    | 90              | 0.63                                      | 0.88                                   | 0.25                | 120.00                              |
| 13:42      | 30                    | 120             | 0.88                                      | 1.13                                   | 0.25                | 120.00                              |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
| Lithology: |                       |                 |   |  |                     |                                     |
|            | 0 to 6 ft             | Sandy Lea       | n Clay                                    | (CL)                                   |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
|            |                       |                 |   |  |                     |                                     |
| REMARKS    | : Bottom o            | of test hole is | s approxima                               | itely 6 feet l                         | below site grade.   |                                     |

| Fiel        | d Perco               | plation F       | Rate Te                                   | est                                    | llerra              | acon                                |
|-------------|-----------------------|-----------------|---|--|---------------------|-------------------------------------|
|             |                       |                 |   |  | lest Hole           | P5                                  |
| Project Na  | ame: HAFE             | 3 SWEG          |   |  | Date: 03/04/202     | 22                                  |
| Terracon    | Project No            | .: 6122500      | )6  |  | Hole Diameter       | (inches): 4                         |
| Eng./Tech   | n.: Kris Po∖          | well            |   |  | Hole Depth (inc     | :hes): 72                           |
| Time        | Length of<br>Interval | Total<br>Time   | Beginning<br>Depth to<br>Water<br>Surface | Ending<br>Depth to<br>Water<br>Surface | Water Level<br>Drop | Percolation Rate<br>During Interval |
|             | (min)                 | (min)           | (in)                                      | (in)                                   | (in)                | (min/in)                            |
| 13:22       | 30                    | 0               | 0.00                                      | 0.00                                   | 0.00                |                                     |
| 13:27       | 30                    | 30              | 0.00                                      | 0.00                                   | 0.00                | #DIV/0!                             |
| 13:32       | 30                    | 60              | 0.00                                      | 0.00                                   | 0.00                | #DIV/0!                             |
| 13:37       | 30                    | 90              | 0.00                                      | 0.00                                   | 0.00                | #DIV/0!                             |
| 13:42       | 30                    | 120             | 0.00                                      | 0.00                                   | 0.00                | #DIV/0!                             |
| 13:47       | 30                    | 180             | 0.00                                      | 0.00                                   | 0.00                | #DIV/0!                             |
|             |                       |                 |   |  |                     |                                     |
|             |                       |                 |   |  |                     |                                     |
|             |                       |                 |   |  |                     |                                     |
|             |                       |                 |   |  |                     |                                     |
| Lithology   |                       |                 |   |  |                     |                                     |
| Litilology. | 0 to 6 ft             | Sandy Lea       | n Clay                                    | (CL)                                   |                     |                                     |
|             |                       |                 |   |  |                     |                                     |
|             |                       |                 |   |  |                     |                                     |
|             |                       |                 |   |  |                     |                                     |
|             |                       |                 |   |  |                     |                                     |
|             |                       |                 |   |  |                     |                                     |
|             |                       |                 |   |  |                     |                                     |
| REMARKS     | Bottom o              | it test hole is | s approxima                               | itely 6 feet l                         | below site grade.   |                                     |

Water Elevation never moved and northern pond contained existing water.

|                            |                         | SI                          | AMMU                 | RY OF                               | LAB              | ORAT                       | ORY                 | RESU     | LTS    |           |   |             |  | PAGE 1                                  | OF 1                               |
|----------------------------|-------------------------|-----------------------------|----------------------|-------------------------------------|------------------|----------------------------|---------------------|----------|--------|-----------|---|-------------|--|---|------------------------------------|
| BORING<br>ID               | Depth (Ft.)             | Soil Classification<br>USCS | Water<br>Content (%) | Unit Weight<br>Dry<br>Density (pcf) | Liquid<br>Limit  | Plastic<br>Limit           | Plasticity<br>Index | % Gravel | % Sand | % Fines   | Unconfined<br>Compressive<br>Strength (tsf) | pH Analysis | Water<br>Soluble<br>Sulfate<br>(mg/kg) | Water<br>Soluble<br>Chloride<br>(mg/kg) | Water<br>Soluble<br>Salts<br>(ppm) |
| B-1                        | 5-6.5                   | LEAN CLAY with SAND(CL)     | 15.5                 |                                     | 26               | 18                         | ø                   |          |        | 71.2      |   |             |  |   |                                    |
| B-1                        | 7.5-9                   | SILTY CLAY(CL-ML)           | 22.2                 |                                     | 27               | 21                         | 9                   |          |        | 86.8      |   |             |  |   |                                    |
| <del>В</del> 1             | 10-11.5                 | LEAN CLAY(CL)               | 24.3                 |                                     | 31               | 19                         | 12                  |          |        | 89.7      |   |             |  |   |                                    |
| B-1                        | 15-16.5                 | LEAN CLAY(CL)               | 26.2                 |                                     | 27               | 18                         | თ                   |          |        | 86.9      |   |             |  |   |                                    |
| В-1                        | 20-21.5                 | LEAN CLAY (CL)              | 25.5                 |                                     |                  |                            |                     |          |        |           |   |             |  |   |                                    |
| B-1                        | 25-26.5                 | LEAN CLAY (CL)              | 24.5                 |                                     |                  |                            |                     |          |        |           |   |             |  |   |                                    |
| B-2                        | 5-6.5                   | SILT with SAND(ML)          | 17.4                 |                                     | ď                | £                          | ₽                   |          |        | 71.3      |   |             |  |   |                                    |
| B-2                        | 7.5-9.5                 | SILTY CLAY(CL-ML)           | 22.8                 |                                     | 26               | 21                         | ى<br>ك              |          |        | 93.6      |   |             |  |   |                                    |
| B-2                        | 10-11.5                 | SILTY CLAY (CL-ML)          | 21.7                 |                                     |                  |                            |                     |          |        |           |   |             |  |   |                                    |
| B-2                        | 15-16.5                 | SILTY CLAY(CL-ML)           | 25.3                 |                                     | 25               | 19                         | Q                   |          |        | 90.7      |   |             |  |   |                                    |
| B-2                        | 25-26.5                 | LEAN CLAY (CL)              | 27.1                 |                                     |                  |                            |                     |          |        |           |   |             |  |   |                                    |
| P-3                        | 4-5                     | SILTY CLAY (CL-ML)          | 23.8                 |                                     |                  |                            |                     |          |        | 92.5      |   |             |  |   |                                    |
| P-3                        | 5-6                     | LEAN CLAY(CL)               | 24.8                 |                                     | 28               | 20                         | ω                   |          |        | 89.8      |   |             |  |   |                                    |
| P-4                        | 4-5                     | LEAN CLAY (CL)              | 23.8                 |                                     |                  |                            |                     |          |        | 89.4      |   |             |  |   |                                    |
| P-4                        | 5-6                     | LEAN CLAY (CL)              | 26.1                 |                                     |                  |                            |                     |          |        | 91.8      |   |             |  |   |                                    |
| P-5                        | 34                      | SANDY LEAN CLAY (CL)        | 24.2                 |                                     |                  |                            |                     |          |        | 83.7      |   |             |  |   |                                    |
|                            |                         |                             |                      |                                     |                  |                            |                     |          |        |           |   |             |  |   |                                    |
| PROJECT: CI                | RSA - HAFB S            | SWEG Office                 |                      |                                     |                  | ľ                          |                     |          | Ϋ́     | ROJECT    | IUMBER: (                                   | 31225006    |  |   |                                    |
| SITE: Indigo (<br>Hill Air | Street<br>Force Base, L | Т                           |                      |                                     | 6949 S Hig<br>Mi | h Tech Dr Ste<br>dvale, UT | 90                  |          | ŭ      | -IENT: CF | SSA<br>alt Lake Cit <u>i</u>                | , UT        |  |   |                                    |
|                            |                         |                             |                      | PH. 801-5                           | 15-8500          | FAX. 8                     | 01-545-8600         |          |        |           |   |             |  |   |                                    |



ATTERBERG LIMITS 61225006 CRSA - HAFB SWEG .GPJ TERRACON\_DATATEMPLATE.GDT 4/1/22 -ABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. One-Dimensional Swell/Collapse of Soils ASTM D2435 or D4546 - Method C

## Terracon

| Project:HAFENo:6122Location:HAFEDate:3/16/  | 3 SWEG Offi<br>5006<br>3<br>2022   | ce  | Test by: CM/AW<br>Reduced by: CO<br>Checked by: JDW<br>Comments: Sat At 1000   |
|---|--|---|--|
| Sample: B-2<br>Depth (ft): 7.5<br>Lab description: Brow<br>Preparation procedur   | n Clay<br>e∶Cutting Rin  | ıg  | Sample type: Elevation:<br>Inundation stress (psf): 1000<br>Swell pressure (psf): 1000<br>Test Method: C   |
| Liquid Limit: 26<br>Plastic Limit: 21<br>Plastic Index: 5   |  |   | Percent Fines: 93.6<br>Large Particles:<br>USCS Classification: Silty Cly (CL-ML)  |
| Phase Relationships   |  |   | Deformation Results - Vertical Stress  |
|   | Initial I  | Final   | Change in Vertical<br>Vert. stress Height, ΔH Height, D strain Void  |
| Height, H (irr<br>Height, H (cm<br>Diameter, D (irr<br>Diameter, D (cm<br>Wt, wet soil + ring (g<br>Weight of ring (g<br>Wet soil + tare (g<br>Dry soil + tare (g<br>Tare (g<br>foisture Content, w (%<br>Specific Gravity, G<br>Mass of Soli total (g<br>Mass of Soli total (g<br>Volume of voids (cm^3<br>/olume of solids (cm^3) | 1.000     2.540     2.540     2.540     2.540     2.540     2.540     2.540     2.540     2.540     1.000     6.350     10.52     10.52     10.52     10.52     10.52     10.52     10.52     10.52     10.52     10.52     10.52     10.52     10.52     10.52     10.52     10.52     10.51     10.518     10.518     10.518 | 0.878<br>2.230<br>2.500<br>6.350<br>255.39<br>106.52<br>44.26<br>36.62<br>1.78<br>21.9%<br>2.65<br>148.9<br>122.1<br>70.6<br>26.8<br>46.1<br>24.5<br>-2.2<br>31.7<br>1.455<br>0.533<br>109<br>1.729 | Seating     0     1.000     0.00     0.746       0.15     0.0043     0.996     0.43     0.738       0.25     0.0053     0.995     0.53     0.737       0.5     0.0091     0.991     0.91     0.730       0.75     0.0128     0.987     1.28     0.724       1     0.0129     0.977     2.29     0.706       2     0.0302     0.970     3.02     0.693       4     0.0392     0.961     3.92     0.678       8     0.0492     0.951     4.92     0.660       16     0.0603     0.940     6.03     0.641       32     0.0890     0.911     8.90     0.590       64     0.1313     0.869     13.13     0.517       16     0.1288     0.871     12.88     0.521       4     0.1221     0.878     12.21     0.533 |
| Dry Unit Weight (pc   | 94.8   | 107.9   | Collapse Strain -0.36 %<br>Collapse Load: 1000 psf   |

Comments:

Page 1 of 2

One-Dimensional Swell/Collapse of Soils ASTM D2435 or D4546 - Method C







Terracon

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 150 psf



**][erracon** 

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 250 psf



**][erracon** 

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 500 psf



## TIMED CONSOLIDATION TEST RESULTS **Terracon**

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 750 psf



lerracon

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 1000 psf



lerracon

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 1000 psf



lerracon

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 2000 psf





Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 4000 psf



lerracon

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 8000 psf



lerracon

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 16000 psf



**Terracon** 

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 32000 psf



lerracon

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 64000 psf



**Terracon** 

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 16000 psf



**Terracon** 

Project Name: HAFB SWEG Office Project No.: 61225006 Location: HAFB Sample: B-2 at 7.5'

Applied Stress: 4000 psf

## CHEMICAL LABORATORY TEST REPORT

Project Number: 61225006 Service Date: 03/22/22 **Report Date:** 03/24/22



## Client

CRSA

175 South Main Street Suite 300 Salt Lake City, UT 84111

Project

CRSA - HAFB SWEG Office Indigo Street Hill Air Force Base, UT

| Sample Location                                     | B-1   |
|---|-------|
| Sample Depth (ft.)                                  | 5-6.5 |
| pH Analysis, ASTM - G51-18                          | 7.7   |
| Water Soluble Sulfate (SO4), ASTM C 1580<br>(mg/kg) | 293   |
| Sulfides, ASTM - D4658-15, (mg/kg)                  | nil   |
| Chlorides, ASTM D 512, (mg/kg)                      | 69    |
| RedOx, ASTM D-1498, (mV)                            | +436  |
| Total Salts, ASTM D1125-14, (mg/kg)                 | 371   |
| Resistivity, ASTM G187, (ohm-cm)                    | 5,472 |

Analyzed By: <u>Jack Robertson</u> Zach Robertson

Engineering Technician III

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

## SUPPORTING INFORMATION

## **Contents:**

Calculations (18) Hammer Energy Evaluation (20) General Notes Unified Soil Classification System

Note: All attachments are one page unless noted above.



## **1.0** CALCULATION PACKAGE – 309<sup>TH</sup> SWEG BUILDING, HAFB, UTAH

Designed: JDW Checked: JBM

Complete geotechnical analyses for:

- 2. Blow Count Correction
- 3 Shallow Foundations
  - a. Settlement
- 4. Seismic Considerations
- 5. Liquefaction Analysis
- 6. Pavements

309<sup>th</sup> SWEG Building, Hill Air Force Base, Utah Terracon Project No.: 61225006 Calculation Package



## 2.0 BLOW COUNT CORRECTION

- Rig: Terracon GeoProbe 3100GT
- See following pages for most recent Hammer Calibration (20).

See the following calculation pages for B-01 and B-02 (2).

N-Value Corrections & Correlations

## **PROJECT INFORMATION**

Project Name: 309th SWEG Project Number: 61225006 Notes: B-01 Date: 3/4/2022

# N-Values, Hammer Energy, and Correction Information

|                       |                             | V Plot (N1)60                 |  |
|-----------------------|-----------------------------|-------------------------------|--|
| Hammer Efficiency 96% | Overburden Exponent (n) 1.0 | Max Overburden Correction 1.7 |  |

| (N <sub>1</sub> ) <sub>60</sub> | 14     | 14   | 35     | 33   | 6    | 7    | 7    |
|---------------------------------|--------|------|--------|------|------|------|------|
| N <sub>60</sub>                 | 8      | 8    | 21     | 19   | 2    | 8    | 10   |
| a'                              | 300    | 600  | 006    | 1200 | 1800 | 2400 | 3000 |
| Raw N-Value                     | 5      | 5    | 13     | 12   | 3    | 5    | 9    |
| Depth (ft)                      | 2.5    | 5    | 7.5    | 10   | 15   | 20   | 25   |
| Elevation (ft)                  | 4661.5 | 4659 | 4656.5 | 4654 | 4649 | 4644 | 4639 |

Plot of N<sub>60</sub> and (N<sub>1</sub>)<sub>60</sub>



# N-Value Corrections & Correlations

## -

## PROJECT INFORMATION

Project Name: 309th SWEG Project Number: 61225006 Notes: B-02 Date: 4/4/2022

# N-Values, Hammer Energy, and Correction Information

| 96%               | 1.0                     | 1.7                       |  |
|-------------------|-------------------------|---------------------------|--|
| Hammer Efficiency | Overburden Exponent (n) | Max Overburden Correction |  |

| / Plot N60 | / Plot (N1)60 |
|------------|---------------|

Г

| (N <sub>1</sub> ) <sub>60</sub> | 11     |      | 11   | 7    | 2    |
|---------------------------------|--------|------|------|------|------|
| N <sub>60</sub>                 | 9      |      | 10   | 8    | 10   |
| <b>-</b> b                      | 300    | 600  | 1800 | 2400 | 3000 |
| Raw N-Value                     | 4      |      | 9    | 5    | 9    |
| Depth (ft)                      | 2.5    | 5    | 15   | 20   | 25   |
| Elevation (ft)                  | 4661.5 | 4659 | 4649 | 4644 | 4639 |

Г





309<sup>th</sup> SWEG Building, Hill Air Force Base, Utah Terracon Project No.: 61225006 Calculation Package



## 3.0 SHALLOW FOUNDATIONS

Estimated Loads:

- See Report Section Project Description
  - o Columns: 100 kips
  - Walls: 3 to 4 kips per linear foot (klf)
  - Slabs: 150 pounds per square foot (psf)

**Building Construction:** 

- See Report Section Project Description
  - o Load- bearing masonry walls
  - Steel frame with slab on grade

## **Bearing Soils**

Native fine-grained soils:

B-01 – Fills to 4.5 feet below existing site grade over Lean Clays B-02 – Fills to 4.5 feet below existing site grade over Silt with Sand P-03, P-04 and P-05 – Clays to 6 feet below existing site grade Based on the 1.0 feet of compacted sand soils over the native clays and silts Estimated Cohesion = 1,100 psf Unit Weight = 120 pcf Factor of Safety used for Bearing Analysis = 3.0

## 12" Structural fill or recompacted fill soils:

Based on our boreholes, loose sandy fills exist to approximately 4.5 feet below site grade. If these sandy soils can be re-used or replaced with structural fill, compacted according to Earthwork section in report in approximately 12 inches depth on the native fine-grained soils. Based on the expected soils at the base of the foundations will be non-consistent soils. We recommend that soils are all based on either fine-grained soils or coarse-grained soils but not both.

## Maximum Settlement: 1 inch

See following 2 pages for Bearing calculation sheets. See the following 5 pages for Settlement calculation sheets.

## **Gross Bearing Capacity**



| Project Name:   | 309th SWEG Building       |
|-----------------|---------------------------|
| Project Number: | 61225006                  |
| Notes:          | Horizontal ground surface |
| Date:           | April 4, 2022             |

## Soil Properties, Footing Dimensions, and Groundwater

| Symbol             | Value | Units   | Definition                               |
|--------------------|-------|---------|--|
| С                  | 1100  | psf     | Cohesion                                 |
| φ                  |       | degrees | Drained Friction Angle                   |
| γabove             | 120   | pcf     | Unit Weight of Soil above Footing        |
| γ <sub>below</sub> | 120   | pcf     | Unit Weight of Soil below Footing        |
| D <sub>f</sub>     | 3     | feet    | Depth of Footing from Ground Surface     |
| $D_w$              | 50    | feet    | Depth to Groundwater from Ground Surface |
| $B_{min}$          | 1.5   | feet    | Minimum Footing Width                    |
| B <sub>max</sub>   | 10    | feet    | Maximum Footing Width                    |
| L                  | 80    | feet    | Footing Length                           |
| FOS                | 3.0   | none    | Factor of Safety                         |

Check if the soils above the footing are as competent as those below the footing.

Check if local or punching shear is possible. See Figure C10.6.3.1.2b-1 on the Instructions sheet.



## Notes

- 1. Calculations are based on Section 10.6.3.1.2 of AASHTO 2010 (Vesic factors).
- 2. User can differentiate between soil unit weight above and below footing.
- 3. Inclination factors are assumed to be 1.0. User must manually input overides.
- 4. Values for d<sub>q</sub> are linearly interpolated based on D<sub>f</sub>/B and  $\phi$  (see Table 10.6.3.1.2a-4).
- 5. See Calculation Sheet for a summary of all other variables.



## Shallow Foundation Bearing Capacity (Gross)

### **PROJECT INFORMATION**

Project Name: 309th SWEG Building Project Number: 61225006 Notes: Horizontal ground surface Date: April 4, 2022

## Governing Equations

 $q_{n} = cN_{cm} + \gamma D_{f}N_{gm}C_{wq} + 0.5\gamma \quad BN_{\gamma m}C_{w\gamma}$ 

 $N_{cm} = N_c s_c i_c$ 

 $N_{qm} = N_q s_q d_q i_q$ 

 $N_{\gamma}m = N_{\gamma}s_{\gamma}i_{\gamma}$ 

See the instructions sheet for a definition of variables.

## Parameter Values and Results of Equations for GROSS Capacity

| Design phi = 0  | Width = 1.5' | Width = 3.63' | Width = 5.76' | Width = 7.89' | Width = 10' |
|---|--------------|---------------|---------------|---------------|-------------|
| С   | 1100         | 1100          | 1100          | 1100          | 1100        |
| N <sub>c</sub>  | 5.14         | 5.14          | 5.14          | 5.14          | 5.14        |
| s <sub>c</sub>  | 1.00         | 1.01          | 1.01          | 1.02          | 1.03        |
| i <sub>c</sub>  | 1.00         | 1.00          | 1.00          | 1.00          | 1.00        |
| cN <sub>c</sub> s <sub>c</sub> i <sub>c</sub>                 | 5,654        | 5,711         | 5,711         | 5,767         | 5,824       |
|   | T            | I             | I             | I             | I           |
| γ <sub>above</sub>  | 120          | 120           | 120           | 120           | 120         |
| D <sub>f</sub>  | 3.00         | 3.00          | 3.00          | 3.00          | 3.00        |
| N <sub>q</sub>  | 1.00         | 1.00          | 1.00          | 1.00          | 1.00        |
| Sq  | 1.00         | 1.00          | 1.00          | 1.00          | 1.00        |
| d <sub>q</sub>  | 1.00         | 1.00          | 1.00          | 1.00          | 1.00        |
| i <sub>q</sub>  | 1.00         | 1.00          | 1.00          | 1.00          | 1.00        |
| C <sub>wq</sub>   | 1.00         | 1.00          | 1.00          | 1.00          | 1.00        |
| $\gamma_{above} D_f N_q s_q d_q i_q C_{wq}$                   | 360          | 360           | 360           | 360           | 360         |
|   |              |               |               |               |             |
| Ybelow  | 120          | 120           | 120           | 120           | 120         |
| В   | 1.50         | 3.63          | 5.76          | 7.89          | 10.00       |
| Νγ  | 0.00         | 0.00          | 0.00          | 0.00          | 0.00        |
| Sγ  | 1.00         | 1.00          | 1.00          | 1.00          | 1.00        |
| iγ  | 1.00         | 1.00          | 1.00          | 1.00          | 1.00        |
| C <sub>wγ</sub>   | 1.00         | 1.00          | 1.00          | 1.00          | 1.00        |
| $0.5\gamma_{below}BN_{\gamma}s_{\gamma}i_{\gamma}C_{w\gamma}$ | 0            | 0             | 0             | 0             | 0           |
|   |              |               |               |               | -           |
| Gross Bearing Capacity  | Width = 1.5' | Width = 3.63' | Width = 5.76' | Width = 7.89' | Width = 10' |

| Gross Bearing Capacity         | Width = 1.5' | Width = 3.63' | Width = 5.76' | Width = 7.89' | Width = 10' |
|--------------------------------|--------------|---------------|---------------|---------------|-------------|
| Ultimate (psf)                 | 6,014        | 6,071         | 6,071         | 6,127         | 6,184       |
| Gross Allowable (psf), FOS = 3 | 2,005        | 2,024         | 2,024         | 2,042         | 2,061       |

## **Shallow Foundation Settlement**

## **PROJECT INFORMATION**

ProjectCRSA 309th SWEGProject No.61225006Notes/LocationHAFB, UtahDate4/1/2022

## Definition of Footing Variables



| Footing Input Parameters       |               |                |  |  |  |  |
|--------------------------------|---------------|----------------|--|--|--|--|
| Symbol                         | Value         | Units          | Description                                |  |  |  |
| B <sub>min</sub>               | 1.50          | ft             | Minimum Footing Width                      |  |  |  |
| B <sub>max</sub>               | 10.00         | ft             | Maximum Footing Width                      |  |  |  |
| Footing length                 | Fixed I       | ooting Length  |  |  |  |  |
| defined by:                    | C Fixed I     | ength to Width | (L/B) Ratio                                |  |  |  |
| Length                         | 80.00         | ft             | Fixed Footing Length                       |  |  |  |
| D <sub>f</sub>                 | 3.00          | ft             | Depth of Footing (from ground surface)     |  |  |  |
| G <sub>w</sub>                 | 50.00         | ft             | Depth to Groundwater (from ground surface) |  |  |  |
| Selected Analysis<br>Method:   | Fixed Settlem | ent 🔻          |  |  |  |  |
| Settlement                     | 1.00          | in             | Design settlement                          |  |  |  |
| Stress Distribution<br>Method: | Boussinesq    | ¥              |  |  |  |  |
| Perform Analysis               | Cli           | ck to Perfor   | m Analysis                                 |  |  |  |

## Shallow Foundation Settlement

## **PROJECT INFORMATION**

Project CRSA 309th SWEG Project No. 61225006 Notes/Location HAFB, Utah Date 4/1/2022

| De | pth of | Footing | and De | pth to | Groundwater |
|----|--------|---------|--------|--------|-------------|
|    |        |         |        |        |             |

Click to Analyze

Footing is 3 feet below the ground surface. Groundwater is 50 feet below the ground surface.

| Soil Input Parameters |                |                             |        |                        |                                       |      |       |     |  |  |
|-----------------------|----------------|-----------------------------|--------|------------------------|---------------------------------------|------|-------|-----|--|--|
| Top<br>(ft)           | Bottom<br>(ft) | γ <sub>moist</sub><br>(pcf) | Method | N-Value<br>(corrected) | Hough Type                            | Cεc  | Cεr   | OCR |  |  |
| 0.0                   | 4.5            | 125                         | Hough  | 14                     | Clean well graded fine to coarse SAND |      |       |     |  |  |
| 4.5                   | 7.0            | 110                         | Direct | 8                      | Sandy CLAY                            | 0.01 | 0.008 | 10  |  |  |
| 7.0                   | 9.0            | 110                         | Direct | 21                     | Sandy CLAY                            | 0.01 | 0.008 | 9.8 |  |  |
| 9.0                   | 13.0           | 120                         | Direct | 19                     | Sandy CLAY                            | 0.01 | 0.008 | 7.2 |  |  |
| 13.0                  | 18.0           | 120                         | Direct | 5                      | Sandy CLAY                            | 0.01 | 0.008 | 5.2 |  |  |
| 18.0                  | 23.0           | 120                         | Direct | 8                      | Sandy CLAY                            | 0.01 | 0.008 | 3.9 |  |  |
| 23.0                  | 30.0           | 110                         | Direct | 10                     | Sandy CLAY                            | 0.01 | 0.008 | 3.2 |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |
|                       |                |                             |        |                        |                                       |      |       |     |  |  |


# Settlement Results

#### **PROJECT INFORMATION**

ProjectCRSA 309th SWEGProject No.61225006Notes/LocationHAFB, UtahDate4/1/2022



**Boussinesq Stress Distribution Method** 

| Dimensions, Pressure, and Settlement |             |                |                 |  |  |  |  |  |  |  |  |  |
|--------------------------------------|-------------|----------------|-----------------|--|--|--|--|--|--|--|--|--|
| Width (ft)                           | Length (ft) | Pressure (psf) | Settlement (in) |  |  |  |  |  |  |  |  |  |
| 1.5                                  | 80          | 11300          | 1.0             |  |  |  |  |  |  |  |  |  |
| 2.5                                  | 80          | 7600           | 1.0             |  |  |  |  |  |  |  |  |  |
| 3.5                                  | 80          | 6000           | 1.0             |  |  |  |  |  |  |  |  |  |
| 4.5                                  | 80          | 5000           | 1.0             |  |  |  |  |  |  |  |  |  |
| 5.5                                  | 80          | 4400           | 1.0             |  |  |  |  |  |  |  |  |  |
| 6.5                                  | 80          | 4000           | 1.0             |  |  |  |  |  |  |  |  |  |
| 7.5                                  | 80          | 3700           | 1.0             |  |  |  |  |  |  |  |  |  |
| 8.5                                  | 80          | 3400           | 1.0             |  |  |  |  |  |  |  |  |  |
| 9.5                                  | 80          | 3200           | 1.0             |  |  |  |  |  |  |  |  |  |
| 10.5                                 | 80          | 3100           | 1.0             |  |  |  |  |  |  |  |  |  |

# Stress and Settlement Calculation Output



Project: CRSA 309th SWEG Number: 61225006 Notes HAFB, Utah Date: 4/1/2022

| Width (ft) | Length (ft) | Mid Point Depth (ft) | $\sigma_{o}'$ (psf) | $\sigma_{p}'$ (psf) | $\Delta\sigma'$ (psf) | σ <sub>f</sub> ' (psf) | Settlement (in) |
|------------|-------------|----------------------|---------------------|---------------------|-----------------------|------------------------|-----------------|
| 1.5        | 80.0        | 3.75                 | 469                 | 469                 | 9247                  | 9716                   | 0.4             |
| 1.5        | 80.0        | 5.75                 | 700                 | 7000                | 3741                  | 4441                   | 0.2             |
| 1.5        | 80.0        | 8.00                 | 948                 | 9286                | 2126                  | 3074                   | 0.1             |
| 1.5        | 80.0        | 11.00                | 1298                | 9342                | 1340                  | 2638                   | 0.1             |
| 1.5        | 80.0        | 15.50                | 1838                | 9555                | 859                   | 2696                   | 0.1             |
| 1.5        | 80.0        | 20.50                | 2438                | 9506                | 610                   | 3047                   | 0.0             |
| 1.5        | 80.0        | 26.50                | 3123                | 9992                | 446                   | 3569                   | 0.0             |
|            |             |                      |                     | Summary:            | 11300                 | Boussinesq             | 1.0             |
|            |             |                      |                     |                     |                       | · · ·                  |                 |
| 2.5        | 80.0        | 3.75                 | 469                 | 469                 | 7120                  | 7589                   | 0.4             |
| 2.5        | 80.0        | 5.75                 | 700                 | 7000                | 3887                  | 4587                   | 0.2             |
| 2.5        | 80.0        | 8.00                 | 948                 | 9286                | 2323                  | 3271                   | 0.1             |
| 2.5        | 80.0        | 11.00                | 1298                | 9342                | 1487                  | 2785                   | 0.1             |
| 2.5        | 80.0        | 15.50                | 1838                | 9555                | 958                   | 2796                   | 0.1             |
| 2.5        | 80.0        | 20.50                | 2438                | 9506                | 682                   | 3119                   | 0.1             |
| 2.5        | 80.0        | 26.50                | 3123                | 9992                | 500                   | 3622                   | 0.0             |
|            |             |                      |                     | Summary:            | 7600                  | Boussinesq             | 1.0             |
|            |             |                      |                     |                     |                       |                        |                 |
| 3.5        | 80.0        | 3.75                 | 469                 | 469                 | 5836                  | 6305                   | 0.4             |
| 3.5        | 80.0        | 5.75                 | 700                 | 7000                | 3895                  | 4595                   | 0.2             |
| 3.5        | 80.0        | 8.00                 | 948                 | 9286                | 2477                  | 3424                   | 0.1             |
| 3.5        | 80.0        | 11.00                | 1298                | 9342                | 1619                  | 2917                   | 0.1             |
| 3.5        | 80.0        | 15.50                | 1838                | 9555                | 1053                  | 2890                   | 0.1             |
| 3.5        | 80.0        | 20.50                | 2438                | 9506                | 751                   | 3189                   | 0.1             |
| 3.5        | 80.0        | 26.50                | 3123                | 9992                | 551                   | 3674                   | 0.0             |
|            |             |                      |                     | Summary:            | 6000                  | Boussinesa             | 1.0             |
|            |             |                      |                     |                     |                       |                        |                 |
| 4.5        | 80.0        | 3.75                 | 469                 | 469                 | 4931                  | 5400                   | 0.3             |
| 4.5        | 80.0        | 5.75                 | 700                 | 7000                | 3743                  | 4443                   | 0.2             |
| 4.5        | 80.0        | 8.00                 | 948                 | 9286                | 2537                  | 3484                   | 0.1             |
| 4.5        | 80.0        | 11.00                | 1298                | 9342                | 1701                  | 2999                   | 0.1             |
| 4.5        | 80.0        | 15.50                | 1838                | 9555                | 1118                  | 2956                   | 0.1             |
| 4.5        | 80.0        | 20.50                | 2438                | 9506                | 801                   | 3239                   | 0.1             |
| 4.5        | 80.0        | 26.50                | 3123                | 9992                | 589                   | 3712                   | 0.1             |
|            |             |                      |                     | Summarv:            | 5000                  | Boussinesa             | 1.0             |
|            |             |                      |                     |                     |                       |                        |                 |
| 5.5        | 80.0        | 3.75                 | 469                 | 469                 | 4365                  | 4834                   | 0.3             |
| 5.5        | 80.0        | 5.75                 | 700                 | 7000                | 3601                  | 4301                   | 0.2             |
| 5.5        | 80.0        | 8.00                 | 948                 | 9286                | 2591                  | 3539                   | 0.1             |
| 5.5        | 80.0        | 11.00                | 1298                | 9342                | 1787                  | 3085                   | 0.1             |
| 5.5        | 80          | 15,50                | 1838                | 9555                | 1191                  | 3028                   | 0,1             |
| 5.5        | 80          | 20,50                | 2438                | 9506                | 857                   | 3295                   | 0.1             |
| 5.5        | 80          | 26,50                | 3123                | 9992                | 632                   | 3754                   | 0,1             |
| 0.0        |             | _0.00                | 0.20                | Summary.            | 4400                  | Boussinesa             | 1.0             |
|            |             |                      |                     | 2 annuar y r        |                       | 20000000               |                 |
| 6.5        | 80          | 3.75                 | 469                 | 469                 | 3980                  | 4449                   | 0.3             |
| 6.5        | 80          | 5.75                 | 700                 | 7000                | 3467                  | 4167                   | 0.2             |
|            |             |                      |                     |                     | • .                   |                        |                 |

| 6.5  | 80 | 3.75  | 469  | 469      | 3980 | 4449       | 0.3 |
|------|----|-------|------|----------|------|------------|-----|
| 6.5  | 80 | 5.75  | 700  | 7000     | 3467 | 4167       | 0.2 |
| 6.5  | 80 | 8.00  | 948  | 9286     | 2631 | 3579       | 0.1 |
| 6.5  | 80 | 11.00 | 1298 | 9342     | 1869 | 3167       | 0.1 |
| 6.5  | 80 | 15.50 | 1838 | 9555     | 1264 | 3101       | 0.1 |
| 6.5  | 80 | 20.50 | 2438 | 9506     | 915  | 3353       | 0.1 |
| 6.5  | 80 | 26.50 | 3123 | 9992     | 676  | 3799       | 0.1 |
|      |    |       |      | Summary: | 4000 | Boussinesq | 1.0 |
|      |    |       |      |          |      |            |     |
| 7.5  | 80 | 3.75  | 469  | 469      | 3688 | 4157       | 0.3 |
| 7.5  | 80 | 5.75  | 700  | 7000     | 3333 | 4033       | 0.2 |
| 7.5  | 80 | 8     | 948  | 9286     | 2646 | 3594       | 0.1 |
| 7.5  | 80 | 11    | 1298 | 9342     | 1936 | 3234       | 0.2 |
| 7.5  | 80 | 15.5  | 1838 | 9555     | 1331 | 3168       | 0.1 |
| 7.5  | 80 | 20.5  | 2438 | 9506     | 970  | 3407       | 0.1 |
| 7.5  | 80 | 26.5  | 3123 | 9992     | 719  | 3841       | 0.1 |
|      |    |       |      | Summary: | 3700 | Boussinesq | 1.0 |
|      |    |       |      |          |      | · · · ·    |     |
| 8.5  | 80 | 3.75  | 469  | 469      | 3392 | 3861       | 0.3 |
| 8.5  | 80 | 5.75  | 700  | 7000     | 3144 | 3844       | 0.2 |
| 8.5  | 80 | 8     | 948  | 9286     | 2593 | 3540       | 0.1 |
| 8.5  | 80 | 11    | 1298 | 9342     | 1953 | 3250       | 0.2 |
| 8.5  | 80 | 15.5  | 1838 | 9555     | 1365 | 3202       | 0.1 |
| 8.5  | 80 | 20.5  | 2438 | 9506     | 1001 | 3439       | 0.1 |
| 8.5  | 80 | 26.5  | 3123 | 9992     | 745  | 3868       | 0.1 |
|      |    |       |      | Summary: | 3400 | Boussinesq | 1.0 |
|      |    |       |      |          |      |            |     |
| 9.5  | 80 | 3.75  | 469  | 469      | 3195 | 3664       | 0.3 |
| 9.5  | 80 | 5.75  | 700  | 7000     | 3014 | 3714       | 0.2 |
| 9.5  | 80 | 8     | 948  | 9286     | 2565 | 3512       | 0.1 |
| 9.5  | 80 | 11    | 1298 | 9342     | 1984 | 3282       | 0.2 |
| 9.5  | 80 | 15.5  | 1838 | 9555     | 1412 | 3249       | 0.1 |
| 9.5  | 80 | 20.5  | 2438 | 9506     | 1044 | 3481       | 0.1 |
| 9.5  | 80 | 26.5  | 3123 | 9992     | 780  | 3902       | 0.1 |
|      |    |       |      | Summary: | 3200 | Boussinesq | 1.0 |
|      |    |       |      |          |      |            |     |
| 10.5 | 80 | 3.75  | 469  | 469      | 3096 | 3565       | 0.3 |
| 10.5 | 80 | 5.75  | 700  | 7000     | 2959 | 3659       | 0.2 |
| 10.5 | 80 | 8     | 948  | 9286     | 2583 | 3531       | 0.1 |
| 10.5 | 80 | 11    | 1298 | 9342     | 2050 | 3347       | 0.2 |
| 10.5 | 80 | 15.5  | 1838 | 9555     | 1484 | 3322       | 0.1 |
| 10.5 | 80 | 20.5  | 2438 | 9506     | 1106 | 3544       | 0.1 |
| 10.5 | 80 | 26.5  | 3123 | 9992     | 830  | 3952       | 0.1 |
|      |    |       |      | Summary: | 3100 | Boussinesq | 1.0 |

309<sup>th</sup> SWEG Building, Hill Air Force Base, Utah Terracon Project No.: 61225006 Calculation Package



### 4.0 SEISMIC CONSIDERATIONS

Based on the map created by McDonald, Greg N., Ashland, Francis X., *Earthquake Site-Conditions Map for the Wasatch Front Urban Corridor*, Utah, Plate 1, Utah Geological Survey Special Study 125, 2008 seen in the following page with the project site located.

#### SITE CLASS – USGS MAP OVERLAY

309th SWEG Office Building = HAFB, Utah April 11, 2022 = Terracon Project No. 61225006





309<sup>th</sup> SWEG Building, Hill Air Force Base, Utah Terracon Project No.: 61225006 Calculation Package



### 5.0 LIQUEFACTION POTENTIAL ANALYSIS

- 1. The following image is based on the published map by Christenson, G.E., Shaw, L.M., 2008, Liquefaction Special Study Areas, Wasatch Front and Nearby Areas, Utah, Supplement Map to Utah Geological Survey Circular 106.
- 2. The Project site is located on a Very Low Potential (VLP) area for liquefaction potential according to the published map.





## 6.0 PAVEMENT CALCULATIONS

Using local Utah Department Of Transportation method based on AASHTO methods for the parking lot area.

Design Life: 25 years

|         |           | ESAL's              |          | 1,274         | 4,368                | 0                    | 0          | 0        | 0                   | 31,031                 | 0                       | 14,638                 | 0                     | 0                 | 0                         | 0                            | 0                    | 0            | 0            | 0                | 0                | 0                | 0              | 0                 | 0                 | 0                | 51,311                         | <b>ESAL</b> Class 1       | avement                   |             |          |   |
|---------|-----------|---------------------|----------|---------------|----------------------|----------------------|------------|----------|---------------------|------------------------|-------------------------|------------------------|-----------------------|-------------------|---------------------------|------------------------------|----------------------|--------------|--------------|------------------|------------------|------------------|----------------|-------------------|-------------------|------------------|--------------------------------|---------------------------|---------------------------|-------------|----------|---|
| Ē       | ÿ         |                     | Axle 3   | 0             | 0                    | 0                    | 0          | 0        | 0.012               | 0                      | 0.177                   | 0                      | 0                     | 0                 | 0                         | 0.001                        | 1.07                 | 0.117        | 0            | 0                | 0                | 0                | 0              | 3.62              | 13.5              | 0.723            |                                | Iperpave                  | ht Duty F                 |             |          | י |
|         | quivalenc | Factors             | Axle 2   | 0.0002        | 0.003                | 0.003                | 0.338      | 0.338    | 1.118               | 0.338                  | 0.177                   | 1.225                  | 0.992                 | 0.992             | 0                         | 0.003                        | 1.07                 | 8.655        | 0.003        | 0.598            | 3.62             | 13.5             | 1.07           | 3.62              | 13.5              | 0.723            | AL's                           | SL                        | Lig                       |             | Ì.       | J |
|         | ш         |                     | Axle 1   | 0.0002        | 0.0002               | 0.003                | 0.012      | 0.035    | 0.2897              | 0.003                  | 0.012                   | 1.59                   | 1.59                  | 1.59              | 0.035                     | 0.035                        | 0.177                | 0.012        | 0.035        | 0.003            | 0.012            | 0.035            | 0.598          | 0.012             | 0.035             | 0.085            | HTO ES                         |                           | tegory                    |             |          |   |
| ents    | Gross     | Weight              | (pounds) | 4,000         | 6,000                | 8,000                | 20,000     | 22,000   | 37,800              | 18,000                 | 30,000                  | 55,000                 | 68,000                | 68,000            | 10,000                    | 22,000                       | 80,000               | 55,000       | 16,000       | 20,000           | 30,000           | 40,000           | 50,000         | 54,000            | 72,000            | 72,000           | <b>Fotal AAS</b>               |                           | Traffic Ca                |             |          |   |
| /em     |           | ო                   | _        |               |                      |                      |            |          | S                   |                        | S                       |                        |                       |                   |                           | ⊢                            | ⊢                    | ⊢            | ⊢            |                  |                  |                  |                | S                 | S                 | ⊢                |                                |                           | -                         | ر<br>س      |          |   |
| ole Pav | Type      | Axle                | (kips    |               |                      |                      |            |          | 9                   |                        | 12                      |                        |                       |                   |                           | 9                            | 34                   | 20           |              |                  |                  |                  |                | 24                | 32                | 31               |                                | mary:                     |                           | achusett    |          |   |
| exik    | and .     | 5                   | s)       | S             | S                    | S                    | S          | S        | S                   | S                      | S                       | ⊢                      | Я                     | R                 | ⊢                         | ⊢                            | ⊢                    | S            | ⊢            | S                | S                | S                | ⊢              | S                 | S                 | ⊢                |                                | Sumi                      |                           | assa        | 4        |   |
| for Fl  | e Load    | Axle                | (kip     | 2             | 4                    | 4                    | 14         | 14       | 18.4                | 14                     | 12                      | 35                     | 48                    | 48                | 2                         | 8                            | 34                   | 29           | 8            | 16               | 24               | 32               | 34             | 24                | 32                | 31               |                                |                           |                           | ham, M      | 4/7/20   |   |
| ator    | Axle      | e 1                 | (sc      | S             | S                    | S                    | S          | S        | t S                 | S                      | S                       | S                      | S                     | S                 | S                         | S                            | S                    | S            | S            | S                | S                | S                | S              | S                 | S                 | S                |                                |                           |                           | Vare        |          |   |
| cula    |           | AxI                 | (kij     | 2             | 2                    | 4                    | 9          | ω        | 13.4                | 4                      | 9                       | 20                     | 20                    | 20                | 8                         | 8                            | 12                   | 9            | 8            | 4                | 9                | 8                | 16             | 9                 | 8                 | 10               |                                |                           |                           | ast V       |          |   |
| SAL Cal | Analysis  | Period              | (years)  | 25            | 25                   |                      |            |          |                     | 25                     |                         | 25                     |                       |                   |                           |                              |                      |              |              |                  |                  |                  |                |                   |                   |                  |                                |                           |                           | Location: E | Date:    |   |
| 1993 E  |           | Weeks               | per Year | 52            | 52                   |                      |            |          |                     | 52                     |                         | 52                     |                       |                   |                           |                              |                      |              |              |                  |                  |                  |                |                   |                   |                  |                                |                           |                           |             |          |   |
| ASHTO   | Volume    | Days                | per Week | 7             | 2                    |                      |            |          |                     | 7                      |                         | 2                      |                       |                   |                           |                              |                      |              |              |                  |                  |                  |                |                   |                   |                  |                                |                           |                           | neral Stor  |          |   |
|         | Traffic   | ty in the           | n Lane   | 50            | 50                   |                      |            |          |                     | 10                     |                         | 2                      |                       |                   |                           |                              |                      |              |              |                  |                  |                  |                |                   |                   |                  | 2.0                            | 2                         | 0                         | Dollar Ge   | J3135123 |   |
|         |           | Quanti              | Desig    | e             | L                    |                      |            |          |                     |                        |                         |                        |                       |                   |                           |                              |                      |              |              |                  |                  |                  |                |                   |                   |                  |                                | , SN                      |                           | roposed     |          |   |
|         |           | Vehicle Description |          | Passenger car | Pick-up truck or van | Recreational vehicle | School bus | TARC bus | Greyhound MC-12 bus | Package delivery truck | Beverage delivery truck | Garbage/dumpster truck | Concrete truck (full) | Dump truck (full) | Semi-tractor (no trailer) | Semi-tractor trailer (empty) | Semi-tractor trailer | User Defined | User Defined | Vehicle type H10 | Vehicle type H15 | Vehicle type H20 | Vehicle type 3 | Vehicle type HS15 | Vehicle type HS20 | Vehicle type 3S2 | Terminal Serviceability, $r_t$ | Assumed Structural Number | Traffic Growth Rate, %/yr | Project:    | Job No.: |   |

Version 01142002

## Pavement Design (AASHTO 1993 Method)

| Design Inputs<br>CBR, Calculated Mr<br>Sugrade Support Used<br>Reliability (%) =<br>Standard Deviation<br>Initial Serviceability =<br>Terminal Serviceability =<br>Design Serviceability Loss, = | 3.0 Mr =<br>Mr =<br>So =<br>Po =<br>Pt =<br>∆PSI =                           | <u>Asphalt</u><br>5161 psi<br>5161 psi<br>90<br>0.42<br>4.2<br>2.0<br>2.2 | $K = \frac{110}{110}$ $K = \frac{110}{90}$ $0.35$ $4.5$ $2.5$ $2.0$ | pci<br>pci<br>WM = 4.2<br>WM = 2.0              |  |  |  |  |  |  |
|--|--|---|---|---|--|--|--|--|--|--|
| Asphalt Layer Coefficients   | a <sub>1</sub> =<br>a <sub>2</sub> =<br>a <sub>2</sub> =<br>a <sub>3</sub> = | 0.40<br>0.40<br>0.10<br>0.08  | AC Surface and Bi<br>AC Base<br>Aggregate Base<br>Subbase           | nder  |  |  |  |  |  |  |
| Concrete Compressive Strength<br>Modulus of Elasticity of Concrete =<br>Modulus of Rupture of Concrete: =<br>Load Transfer ("J" Factor)<br>Drainage Coefficient                                  |  |   | 4000<br>3,605<br>580<br>4.2<br>1.0                                  | psi<br>ksi<br>psi<br>See Table 1<br>See Table 2 |  |  |  |  |  |  |
| Pavement Thickness Designs   |  |   |   |   |  |  |  |  |  |  |
| Traffic Category - Flexible Paveme<br>Asphalt Section Traffic (18 kip ESA  | nt Ligh<br>AL) =   | t Duty Pavement<br>52,000   | Calculated ESALs =  | 51,311  |  |  |  |  |  |  |
| Flexible Pavement Section<br>AC Surface + Binder<br>Asphalt Base<br>Aggregate Base<br>Subbase  | Drainage, m  | D <sub>i</sub><br>2.0 in<br>2.0 in<br>8.0 in<br>0.0 in                    | Solve for SN  | re quire d                                      |  |  |  |  |  |  |
|  | Structural Number  | 2.40  | <u>OK</u>   |   |  |  |  |  |  |  |
|  | Required   | 2.38  |   |   |  |  |  |  |  |  |
| Rigid Pavement Section         Traffic Category - Rigid Pavement       Rigid - Heavy Duty Pavement   |  |   |   |   |  |  |  |  |  |  |
| Concrete Section Traffic (18 kip ES  | SAL) =   |   | Calculated ESALs =  | 30,787  |  |  |  |  |  |  |
| Concrete Thickr<br>Calcul  | ness, D <sub>PCC</sub><br>ated to less than                                  | 5.00<br>minimum!!   | Solve for DI  | 20°   |  |  |  |  |  |  |

Click button to solve for slab Thicknes